



THE CITY OF  
SAN DIEGO

- ▶ Airports
- ▶ Bikeways
- ▶ Bridges
- ▶ Drainage Control & Flood Control Facilities
- ▶ Libraries
- ▶ Park & Recreation Centers
- ▶ Police, Fire & Lifeguard Stations
- ▶ Street Improvements
- ▶ Street Lights & Traffic Signals
- ▶ Utilities Undergrounding
- ▶ Water & Sewer Facilities
- ▶ Water & Sewer Pipelines



# Harbor Drive Trunk Sewer



## Background

The City of San Diego has established an ongoing program that mandates the replacement of all aging and below-capacity concrete sewer mains. The Harbor Drive Trunk Sewer was originally installed in 1981 and has nearly reached its full capacity, especially after the construction of the Convention Center and the new developments in the Barrio Logan area. This replacement project will eliminate future sewer main stoppages and sewer spills, while bringing the existing sewer mains up to current City standards.

## Project Overview

The Harbor Drive Trunk Sewer is located on Harbor Drive between Beardsley Street and just south of 28<sup>th</sup> Street as shown on the location map. The project will replace approximately 4,700 linear feet (0.9 miles) of existing 39-inch concrete sewer main, with a 48-inch plastic lined concrete pipe. Curb ramps will also be installed within the project area.

The majority of the construction work will occur within the public right of way, with the exception of a few segments that run in private easements. Multiple methods of construction will be used to replace the existing pipes including open trench, tunneling and pipe rehabilitation.

## Construction Schedule

Construction began on April 30, 2012 and is anticipated to be complete in 180 working days. Working hours are from 7:30 A.M. to Midnight including weekends.

Precautions will be taken to minimize noise, debris, traffic and parking disruptions. A traffic control plan will be prepared to help minimize traffic impacts and ensure public and property safety. Construction noise will not exceed limits established by the applicable laws and regulations.

## Cost

The total cost of the project is approximately \$9 million.

## Additional Information

Additional information about sewer main replacements and other important infrastructure improvement projects can be found online at [www.sandiego.gov/engineering-cip](http://www.sandiego.gov/engineering-cip), or by calling the public information line at (619) 533-4207.

***“Working together to engineer a better tomorrow.”***

*If you have any questions about this project, please call Engineering and Capital Projects Public Information Line at (619) 533-4207 or visit us online at [www.sandiego.gov/engineering-cip](http://www.sandiego.gov/engineering-cip).*