



THE CITY OF  
SAN DIEGO

# Normal Street Median Improvement Project

## Project Background

Normal Street between University Avenue and Blaine Avenue is a four-lane 110-foot wide street with angle parking zones on both sides of the street and an existing raised center median. The existing parking of this block primarily supports the businesses along University Avenue. While these businesses rely on a high percentage of walking customers, they are benefited by the presence and visibility of increased parking.

## Project Overview

The project will demolish the existing raised median with asphalt concrete and install a new raised median with landscaping and irrigation, 15 2-hour metered angled parking spaces at east side of median, upgrade 2 existing pedestrian ramps, install 3 new ramps, and install 2 new disabled parking spaces on the east curb of Normal Street. There should be minimal to no impacts to residents and businesses in the area. Construction activity will take place at the median but it is not anticipated that Normal Street will be closed or vehicular access impeded.

## Construction Schedule

Construction Start:	September 2009
Scheduled date for completion:	December 2009
Plant Maintenance Period:	Six months

## Contractor

Tri Group Construction

## Cost

The construction contract is for \$134,119.

Project Funding from Proposition 1B, Uptown Parking District, Uptown Urban Community Funds



***"Working together to engineer a better tomorrow."***

*If you have any questions about this project or the Engineering & Capital Projects Department, please call our Public Information Line at (619) 533-4207 or visit us online at [www.sandiego.gov/engineering-cip](http://www.sandiego.gov/engineering-cip).*

- Airports
- Bikeways
- Bridges
- Drainage Control & Flood Control Facilities
- Libraries
- Park & Recreation Centers
- Police, Fire & Lifeguard Stations
- Street Improvements
- Street Lights & Traffic Signals
- Utilities Undergrounding
- Water & Sewer Facilities
- Water & Sewer Pipelines

