#### SPECIAL NOTES

THE FOLLOWING NOTES ARE PROVIDED TO GIVE DIRECTIONS TO THE CONTRACTOR BY THE ENGINEER OF WORK. THE CITY ENGINEER'S SIGNATURE ON THESE PLANS DOES NOT CONSTITUTE APPROVAL OF ANY OF THESE NOTES AND THE CITY WILL NOT BE HELD RESPONSIBLE FOR THEIR ENFORCEMENT.

- 1. THE CONTRACTOR SHALL ENFORCE ALL SAFETY MEASURES. THE CONTRACTOR SHALL DESIGN, CONSTRUCT, AND MAINTAIN ALL SAFETY DEVICES, INCLUDING SHORING AND SHALL BE SOLELY RESPONSIBLE FOR CONFORMING TO ALL LOCAL, STATE, AND FEDERAL SAFETY AND HEALTH STANDARDS, LAWS, AND REGULATIONS.
- 2. CONTRACTOR SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS OURING THE COURSE OF CONSTRUCTION, INCLUDING THE SAFETY OF ALL PERSONS AND PROPERTY. THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY MONUMENTATION AND/OR BENCHMARKS WHICH WILL BE DISTURBED OR DESTROYED BY CONSTRUCTION, SUCH POINTS SHALL BE REFERENCED AND REPLACED WITH APPROPRIATE MONUMENTATION BY A LICENSED LAND SURVEYOR OR A REGISTERED CIVIL ENGINEER AUTHORIZED TO PRACTICE LAND SURVEYING. A CORNER RECORD OR RECORD OF SURVEY, AS APPROPRIATE, SHALL BE FILED BY THE LICENSED LAND SURVEYOR OR REGISTERED CIVIL ENGINEER AS REQUIRED BY THE LAND SURVEYOR'S ACT.
- 4. IF THERE IS ANY QUESTION REGARDING THESE PLANS OR FIELD STAKES, THE CONTRACTOR SHALL REQUEST AN INTERPRETATION BEFORE DDING ANY WORK BY CALLING THE RESIDENT ENGINEER. THE CONTRACTOR SHALL ALSO TAKE THE NECESSARY STEPS TO PROTECT THE PROJECT AND ADJACENT PROPERTY FROM ANY EROSION AND SILTATION THAT RESULT FROM HIS OPERATIONS BY APPROPRIATE MEANS (SAND BAGS, HAY BALES, TEMPORARY DESILTING BASINS, DIKES, SHORING, ETC.) UNTIL SUCH TIME THAT THE PROJECT IS COMPLETED.
- LOCATION AND ELEVATION OF IMPROVEMENTS TO BE MET BY WORK TO BE DDNE SHALL BE CONFIRMED BY FIELD MEASUREMENTS PRIOR TO CONSTRUCTION OF NEW WORK.
- 6. THE CONTRACTOR SHALL MAINTAIN A LEVEL DF SECURITY TO PRIVATE PROPERTIES COMPARABLE TO EXISTING CONDITIONS WHEN THE WORK HAS REMOVED EXISTING SECURITY MEASURES (E.G., FENCING).
- 7. UPON COMPLETION OF EACH DAYS WORK, THE CONTRACTOR SHALL BE RESPONSIBLE FOR LEAVING THE WORK AREA FREE OF HAZARDS, AND SHALL PROVIDE NECESSARY TEMPORARY SIGNS, WARNING DEVICES, AND RARRICADES
- 8. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER OF ANY BID ITEM QUANTITIES THAT EXCEEDS 5% OF THE CONTRACT QUANTITY BEFORE PERFORMING THE WORK.
- THE WORKING HOURS FOR INSPECTION IS 7:00 AM TO 3:30 PM, MONDAY-FRIDAY. IF INSPECTION IS REQUIRED BEYOND THIS TIME FRAME, A REQUEST SHALL BE SUBMITTED 48 HOURS IN ADVANCE.


#### WATER POLLUTION CONTROL NOTES

- 1. THE CONTRACTOR SHALL TAKE THE NECESSARY STEPS TO PROTECT ADJACENT PROPERTY FROM ANY EROSIDN AND SILTATION THAT RESULTS FROM HIS OPERATIONS BY APPROPRIATE MEANS (GRAVEL BAGS, DIKES, ETC) UNTIL SUCH TIME THAT THE PROJECT IS COMPLETE AND ACCEPTED FOR MAINTENANCE BY THE CITY.
- 2. THE CONTRACTOR IS TO PROVIDE PILE PROTECTION, STREET SWEEPING, STORAGE/STAGING AREA PROTECTION, POLLUTION CONTROL MEASURES FOR EQUIPMENT MAINTENANCE, FUELING, CLEANING AND STORAGE AND TEMPORARY CONCRETE WASH OUT AREA.
- 3. FOR DETAILS ON WATER POLLUTION CONTROL SITE MANAGEMENT, SEE CALTRANS MANUALS: "THE CONSTRUCTION SITE BEST MANAGEMENT PRACTICES (BMP) MANUAL AND "STORM WATER POLLUTION PREVENTION PLAN (SWPPP) AND WATER POLLUTION CONTROL PROGRAM (WPCP) PREPARATION MANUAL".


## CITY OF SAN DIEGO PROJECT PLANS FOR THE CONSTRUCTION OF

#### OTAY TRUCK ROUTE WIDENING PHASE 3


#### FEDERAL AID PROJECT NO. DEMO5L 5004(170)








#### PROPOSED TYPICAL CROSS SECTION STA 0+00.00 TO 12+06 NO SCALE



#### PROPOSED TYPICAL CROSS SECTION



#### SPECIFICATION NO. 4104 CITY CONTRACT, CIP NO. 52-682.0

### PLANS FOR THE CONSTRUCTION OF:

CONTRACTOR MUST NOTIFY THE
BELOW LISTED AGENCY AT
LEAST TWO (2) WORKING DAYS
PRIOR TO COMMENCEMENT OF
EXCAVATION:

CITY O

CITY O

WORK TO BE DONE

PCC PAVEMENT & CLASS 2 BASE

PIPE PROTECTION SLAB & MIO BLOCK CROSSING

DEMO PAVEMENT

BORDER FENCE

K - RAIL

(6") CURE

TREE/SHRUB

STORM DRAIN

RELOCATED SECON BORDER FENCE ENVIRONMENTAL AREA

RETAINING WALL (TYPE-A)

ADJEM CRASH CUSHION

DIRECTION OF SURFACE FLOW

EXISTING IMPROVEMENTS

RETAINING WALL (ENVIRO-BLDCK)

**IMPROVEMENT** 

THE IMPROVEMENTS CONSIST OF THE FOLLOWING WORK TO BE

STANDARD DRAWINGS OF THE CITY OF SAN DIEGO.

DONE ACCORDING TO THESE PLANS AND THE SPECIFICATIONS AND

**LEGEND** 

STANDARD DRAWING

CALTRANS PI

CALTRANS P17 CALTRANS P18

CALTRANS P2Ø CALTRANS P3Ø CALTRANS P33

RELOCATED

C-9

G-1

CALTRANS SE-

SYMBOL

UNDERGROUND SERVICE ALERT

# OTAY TRUCK ROUTE WIDENING FROM DRUCKER LANE TO THE POINT OF ENTRY CITY OF SAN DISCO CAUSODNIA

	CITY OF SA ENGI SHE	No. 52682I				
Ε	FOR CITY ENGINEE	R	DATE			BRAD JOHNSON SECTION HEAD
	DESCRIPTION	BY	APPROYED	DATE	FILMED	MIKE ARNOLO
	FILE NAME: DATE: Phase3.dgn 8-X-8	Мнс				PROJECT MANAGER
						LOUIS SCHULTZ
						PROJECT ENGINEER
						138-1785
	AS-BUILT					LAMBERT COORDINATES
	CONTRACTOR		STARTEO COMPLETEO_			32555-I-D

# A JOLA WETA

VICINITY MAP

SHEET INDEX	<u>(</u>
SHEET #	DESCRIPTION
1 2 3 4 5 6 7 8 9 10 11 - 12	TITLE SHEET STATION 0+00 TO STATION 6+00 STATION 6+00 TO STATION 12+00 STATION 12+00 TO STATION 12+00 STATION 12+00 TO STATION 18+00 STATION 18+00 TO STATION 24+00 STATION 24+00 TO STATION 27+24 TYPICAL SECTIONS AND PROFILES SECURITY SWING GATE DETAILS PIPE BRIOGE & SECURITY GATE DETAILS SECURITY FENCE RELOCATION DETAILS SIGNING AND STRIPING
1 - 4	TRAFFIC CONTROL AND CONSTRUCTION PHASING

#### ABBREVIATIONS

	, BBI (EV) (TO)	<u> </u>		
ABAN	ABANDON	EVC	END OF VERTICAL CURVE	
ABANO	ABANDONED	VIF	VERIFY IN FIELD	
AC, ASPH	ASPHALT CONCRETE	EX, EXIST	EXISTING	
BC	BEGINNING DF CURVE	G	GRADE	
BVC	BEGINNING OF VERTICAL	LT	LEFT	
	CURVE	P <b>V</b> C	POLYVINYL CHLORIDE	
CIP	CAST IRON PIPE	PVI	POINT OF VERTICAL	F
CIPCP	CAST IN PLACE		I NTERSECTI ON	Ė
	CONCRETE PIPE	PVMT	PAVEMENT	2
Œ.	CENTERLINE	RT	RI GHT	2
СТВ	CEMENT TREATED	STA	STATION	3
	BASE	TOF	TOP OF FODTING	
EC	END OF CURVE	TOW	TOP OF WALL	
EOP	EDGE OF PAVEMENT	TYP	TYPI CAL	

#### REFERENCE DRAWINGS

23630-D, 'CUSTOMHOUSE COURT & 150' BORDER CORRIDOR' 27316-D, 'DTAY MESA TRUCK ROUTE'

30262-D. SOUTHBOUND TRUCK ROUTE


# PROPOSED TYPICAL CROSS SECTION STA 15-52 TO 25-60 NO SCALE SURVEY REFERENCES


#### MAP 11163, 11612, 12488, 12659, P.M. 15289 RoS. 8920, 13376, 16826, 17171 DWG. 18253-B, 27284-D


\*22 SBP CUSTOM HOUSE COURT & CUSTOM HOUSE PLAZA ELEV. 508.920 \*23 NWBP OTAY CENTER ROAD & CUSTOM HOUSE PLAZA, ELEV 514.191


ELEV. 514.191 DATUM: NVGO29 FEET


**BENCHMARK** 












SECONDARY FENCE SECTION




SPECIFICATION NO. 2002 CITY CONTRACT, CIP NO. 52-682.0


PLANS FOR THE CONSTRUCTION OF:


OTAY TRUCK ROUTE WIDENING SECONDARY FENCE RELOCATION DETAILS


OF CALIFORNIA	CITY OF SA ENGI SHE	w.o. 52682I				
CONTRACTOR MUST NOTIFY THE BELOW LISTED AGENCY AT	FOR CITY ENGINEER	BRAD JOHNSON SECTION HEAD				
LEAST TWO (2) WORKING DAYS	DESCRIPTION	BY	APPROVED	DATE	FILMED	MIKE ARNOLD
PRIDR TO COMMENCEMENT OF	FILE NAME: DATE: Phase3.dqn Ø-X-Ø	MHC				PROJECT MANAGER
EXCAVATION:						LOUIS SCHULTZ
						PROJECT ENGINEER
						138-1785
	AS-BUILT					LAMBERT COORDINATES
UNDERGROUND SERVICE ALERT (USA) 1-800-422-4133	CONTRACTOR DATE STARTED INSPECTOR DATE COMPLETED					32555-IO-D

lo. <u>C-45836</u> Exp. 12-31-10









DRAINAGE OPENING (SEE DETAIL 1 SHEET 11)



LEAST TWO (2) WORKING D PRIOR TO COMMENCEMENT EXCAVATION:

STRIPING AND SIGNING.

RESIDENT ENGINEER.

C-45836

D. 12-31-10

SPECIFICATION NO. 2002 CITY CONTRACT, CIP NO. 52-682.0

8. ALL LIMIT LINES/STOP LINES, CROSSWALK LINES, PAVEMENT LEGENDS, AND ARROWS (EXCEPT WITHIN BIKE LANES) SHALL BE THERMOPLASTIC.

A MINIMUM OF FIVE (5) WORKING DAYS PRIOR TO AND UPON COMPLETION OF

9. CONTRACTOR SHALL NOTIFY CITY TRAFFIC ENGINEER AT (619) 533-4443

10.SIGNS INDICATED FOR RELOCATION SHALL BE SALVAGED AND STORED UNTIL READY FOR REINSTALLATION.

11.NEW LOCATIONS OF RELOCATED SIGNS SHALL BE DETERMINED BY THE

#### PLANS FOR THE CONSTRUCTION OF:

OTAY TRUCK ROUTE WIDENING FROM DRUCKER LANE TO THE POINT OF ENTRY SIGNING STRIPING AND BARRIER PLAN

OF CALIFORNIA	CITY OF SA ENGI SHE	w.a. 52682I				
CONTRACTOR MUST NOTIFY THE BELOW LISTED AGENCY AT	FOR CITY ENGINEE	R		DATE	_	BRAD JOHNSON SECTION HEAD
LEAST TWO (2) WORKING DAYS	DESCRIPTION	BY	APPROVED	DATE	FILMED	MIKE ARNOLD
PRIOR TO COMMENCEMENT OF	FILE NAME: DATE: Phose3.dgn 8-X-8	MHC				PROJECT MANAGER
EXCAVATION:						LOUIS SCHULTZ
						PROJECT ENGINEER
						138-1785
	AS-BUILT					LAMBERT COORDINATES
UNDERGROUND SERVICE ALERT (USA) 1-800-422-4133	CONTRACTORINSPECTOR		STARTED COMPLETED_			32555-I2-D

### TRAFFIC CONTROL

#### TRAFFIC CONTROL NOTES

- THIS TRAFFIC CONTROL PLAN IS NOT VALID UNTIL WORK DATES ARE APPROVED. THE CONTRACTOR SHALL, PER SECTION 7-18.1.3 OF THE CONTROL PROVISIONS, CALL THE ENGINEERING TRAFFIC CONTROL SECTION AT 0858) 495-4741 TO OBTAIN A PERMIT THE CONTRACTOR MUST CALL A MINIMUM DE TWO (2) WORKING DAYS PRIOR TO STARTING WORK, OR FIVE (5) WORKING DAYS WHEN THE WORK WILL AFFECT A TRAFFIC SIGNAL.
- 2. STANDARDS. THIS TRAFFIC CONTROL PLAN SHALL CONFORM TO THE MOST RECENTLY ADOPTED EDITION OF EACH OF THE FOLLOWING MANUALS:
  - a. CITY OF SAN DIEGO STANDARO DRAWINGS, APPENDIX "A";
  - CALIFORNIA MANUAL ON UNIFORM TRAFFIC CONTROL GEVICES FOR STREETS AND HIGHWAYS, AND
     STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION ("GREENBOOK"), INCLUDING REGIONAL AND CITY OF SAN DIEGO SUPPLEMENT AMENDMENTS.
- 3. NOTIFICATIONS. THE CONTRACTOR SHALL NOTIFY THE FOLLOWING AFFECTED AGENCIES A MINIMUM OF FIVE (5) WORKING DAYS PRIOR TO ANY EXCAVATION, CONSTRUCTION OR TRAFFIC CONTROL:

FIRE OEPARTMENT DISPATCH (STREET OR ALLEY CLOSURE) (858) 573-1300 FINE UEPARTMENT DISPATCH
POLICE OEPARTMENT TRAFFIC
WASTE MANAGEMENT DEPT.
STREET DIVISION/ELECTRICAL
SAN DIEGO TRANSIT
MTOB (STREET OR ALLEY CLOSURE)
(REFUSE COLLECTION)
(TRAFFIC SIGNALS) (BUS STOPS) UNDERGROUND SERVICE ALERT (ANY EXCAVATION)

THE CONTRACTOR SHALL NOTIFY PROPERTY OWNERS AND TENANTS A MINIMUM OF FIVE (5) WORKING DAYS PRIOR TO CLOSURE OF ORIVEWAYS. THE CONTRACTOR SHALL POST SIGNS NOTIFYING THE PUBLIC A MINIMUM OF FIVE (5) WORKING DAYS PRIOR TO CLOSURE OF STREETS.

- 4. POSTING NO PARKING SIGNS. THE CONTRACTOR SHALL POST 'TOW-AWAY/NO PARKING' SIGNS TWENTY-FOUR (24) HOURS IN ADVANCE FOR TEMPORARY PARKING REMOVAL. SIGNS SHALL INDICATE SPECIFIC DAYS, DATES, AND TIMES OF RESTRICTIONS.
- 5. EXCAPATIONS. EXCEPT AS SHOWN ON THE PLANS, TRENCHES SHALL BE BACKFILLED OR TRENCH-PLATED AT THE END OF EACH WORK DAY. AN ASPHALT RAMP SHALL BE PLACED AROUND EACH TRENCH PLATE TO PREVENT THE PLATE FROM BEING DISLODGED, UPON COMPLETION OF EXCAVATION BACKFILL, THE CONTRACTOR SHALL PROVIDE A SATISFACTORY SURFACE FOR TRAFFIC, WHEN CONSTRUCTION DERATIONS ARE NOT ACTIVELY IN PROGRESS, THE CONTRACTOR SHALL MAINTAIN ALL TRAVEL LANES OPEN TO TRAFFIC,
- 6. RESTURATION OF TRAFFIC CONTROL DEVICES. HE CONTRACTOR SHALL REPAIR OR REPLACE TRAFFIC CONTROL DEVICES (INCLUDING TRAFFIC SIGNS, STRIPING, PAVEMENT MARKERS, PAVEMENT MARKINGS, LEGENDS, CURB MARKINGS, LOOP DETECTORS, TRAFFIC SIGNAL EQUIPMENT, ETC.) DAMAGED OR REMOVED AS A RESULT OF OPERATIONS AND NOT DESIGNATED FOR REMOVAL, REPAIRS AND REPLACEMENTS SHALL BE EQUAL TO EXISTING IMPROVEMENTS, LOOP DETECTORS SHALL BE REPLACED WITHIN THREE (3) WORKING DAYS OF COMPLETION OF UNDERGROUND WORK.
- 7. CHANGES DE MORE, THE RESIDENT ENGINEER WILL OBSERVE THESE TRAFFIC CONTROL PLANS IN OPERATION AND RESERVES THE RIGHT TO MAKE CHANGES AS THE FIELD CONDITIONS WARRANT, SUCH CHANGES SHALL SUPERSEOE THESE PLANS.

#### LECEND

DELINEATOR

SIGN

TYPE K GUARDRAIL

#### Typical work zone



PHASE 3

KEY MAP

PHASE 1,2

#### TRAFFIC CONTROL SIGNS

ROAD CLOSED

ROAD WORK

G20-2



W20-1



NOTE: ALL SIGNS ARE STANDARD SIZE

#### TABLE I

#### RECOMMENDED SIGN SPACING FOR ADVANCE WARNING SIGN SERIES

APPROACH SPEED	MINIMUM DISTANCE IN FEET BETWEEN SIGNS AND	MAXIMUM DEVICE SPACING	TAPE	MINIMUM ER LENI LANE W	STHS
(MPH)	FROM LAST SIGN TO TAPER	IN FEET	IO FT	HFT	I2 FT
25	150-200	25	105	II5	125
30	200-300	30	150	165	180
35	250-400	35	205	225	245
40	350-500	40	265	295	320
45	500-750	45	450	495	540
50	500-1000	50	500	550	600
55+	500-1500	50	550	605	660

• L=WS /60 FOR SPEED OF 40 MPH OR LESS; L=WS FOR SPEED GREATER THAN 40 MPH. TAPER LENGTHS SHOWN ARE ROUNDED TO NEAREST 5 FEET.

#### TABLE 2

#### RECOMMENDED TAPER LENGTH AND DEVICE SPACING FOR CHANNELIZING TAPERS

APPROACH	TADED	SPACING OF CONES	NOTE:
SPEED (MPH)	TAPER LENGTH (L) •	ALONG TAPER (FEET) ±	TAPER FORMULA
25	125	25	L = S x W for speeds greater than 40 mph
30	180	30	_ · · ·
35	245	35	$L = \frac{W \times S^{2}}{60}$ for speeds of 40 mph or less
40	320	40	$L = \frac{W \times S}{60}$ for speeds of 40 mph or less
45	540	45	10
50	600	50	
50+	1000	50	Where:
			L = minimum length of taper

BASED ON 12-FOOT WIDE LANE. THIS COLUMN IS ALSO APPROPRIATE FOR LANE WIDTHS LESS THAN 12 FEET

S = numerical value of APPROACH speed prior to work (mph)

MINIMALINA

W = width of offset (feet)

#### TRAFFIC CONTROL DESIGN SPEED

OTAY TRUCK ROUTE (DRUCKER LANE TO THE OTAY MESA POINT OF ENTRY)

40 MPH

SPECIFICATION NO. 2002 CITY CONTRACT, CIP NO. 52-682.0

### C-45836 <sub>KD.</sub> 12-31-10

IPLANS FOR THE CONSTRUCTION OF:

OTAY TRUCK ROUTE WIDENING FROM DRUCKER LANE TO THE POINT OF ENTRY TRAFFIC CONTROL PLAN

	CITY OF S ENGI SH	w.o. 52682I				
ŧΕ	FOR CITY ENGINEE	R		DATE		BRAD JOHNSON SECTION HEAD
	DESCRIPTION	BY	APPRDYED	DATE	FILMED	MIKE ARNOLD
	FILE NAME: DATE: Phose3.dqn 0-X-0	MHC				PROJECT MANAGER
						LOUIS SCHULTZ
						PROJECT ENGINEER
						138-1785
	AS-BUILT					LAMBERT COORDINATES
	CONTRACTOR		STARTED			32555-TI-D


# CONTRACTOR MUST NOTIFY TH

BELOW LISTED AGENCY AT LEAST TWO (2) WORKING DAYS PRIOR TO COMMENCEMENT OF EXCAVATION:


> INDERGRALINA SERVICE ALERT (USA) 1-800-422-4133

CITY OF SAN DIEGO WORK HOURS CONTINUOUS SETUP TRAFFIC ENGINEER FOR CITY ENGINEER OATE:


OTAY MESA POINT OF ENTRY



# CONSTRUCTION AND TRAFFIC CONTROL



# CONSTRUCTION AND TRAFFIC CONTROL



\*NOTE: TYPE K BARRIER SHALL BE USED FOR TEMPORARY TRAFFIC CONTROL DURING CONSTRUCTION AND AS PERMANENT LANE DIVIDER PER THESE PLANS

CONTINUOUS SETUP

DATE:

SPECIFICATION NO. 2002 CITY CONTRACT, CIP NO. 52-682.0

#### PLANS FOR THE CONSTRUCTION OF:

OTAY TRUCK ROUTE WIDENING FROM DRUCKER LANE TO THE POINT OF ENTRY TRAFFIC CONTROL PLAN

-SECONDARY BORDER FENCE

VARIES 1.5'- 2'

-2' WIGE CONC STRIP

OF CAUTON	CITY OF S	y.o. 52682I				
CONTRACTOR MUST NOTIFY THE BELOW LISTED AGENCY AT	FOR CITY ENGINEE	R		DATE	_	BRAD JOHNSON SECTION HEAD
LEAST TWO (2) WORKING DAYS	DESCRIPTION	BY	APPROVED	DATE	FILMED	MIKE ARNOLD
PRIOR TO COMMENCEMENT OF	FILE NAME: DATE: Phase3.dqn 8-X-8	HHC				PROJECT MANAGER
EXCAVATION :						LOUIS SCHULTZ
						PROJECT ENGINEER
						138-1785
	AS-BUILT					LAMBERT COORDINATES
UNDERGROUND SERVICE ALERT (USA) 1-800-422-4133	CONTRACTORINSPECTOR		STARTEO COMPLETEO_			32555-T4-D