

City of San Diego

CONTRACTOR'S NAME: Pavement Coatings Co.

ADDRESS: 10240 San Sevaine Way, Jurupa Valley, CA 91752

TELEPHONE NO.: 714-826-3011 ext. 2258 **FAX NO.:**

CITY CONTACT: Abel Martinez, Contract Specialist, Email: MartinezAbel@sandiego.gov

Phone No. (619) 533-5270

C. Hudson / L. Arikat / K.E. Ranshaw

BIDDING DOCUMENTS



FOR

SLURRY SEAL GROUP 2524



BID NO.: **K-25-2345-DBB-3**

SAP NO. (WBS/IO/CC): **21005580**

CLIENT DEPARTMENT: **2116**

COUNCIL DISTRICT: **1, 2**

PROJECT TYPE: **ID**

THIS CONTRACT WILL BE SUBJECT TO THE FOLLOWING:

- THE CITY'S SUBCONTRACTING PARTICIPATION REQUIREMENTS FOR SLBE PROGRAM
- PREVAILING WAGE RATES: STATE ☒ FEDERAL ☐
- APPRENTICESHIP
- THIS IS A GAS TAX FUNDED CONTRACT THROUGH THE DEPARTMENT OF CALIFORNIA TRANSPORTATION COMMISSION (CTC)

BID DUE DATE:

2:00 PM

JANUARY 28, 2025

CITY OF SAN DIEGO'S ELECTRONIC BIDDING SITE, PLANETBIDS

<http://www.sandiego.gov/cip/bidopps/>

ENGINEER OF WORK

The engineering Specifications and Special Provisions contained herein have been prepared by or under the direction of the following Registered Engineer:



For City Engineer

12/11/2024
Date

Seal:



TABLE OF CONTENTS

SECTION	PAGE
1. REQUIRED DOCUMENTS SCHEDULE.....	4
2. NOTICE INVITING BIDS.....	6
3. INSTRUCTIONS TO BIDDERS	9
4. PERFORMANCE AND PAYMENT BONDS	19
5. ATTACHMENTS:	
A. SCOPE OF WORK.....	22
B. RESERVED.....	25
C. EQUAL OPPORTUNITY CONTRACTING PROGRAM	26
D. PREVAILING WAGE.....	46
E. SUPPLEMENTARY SPECIAL PROVISIONS.....	51
1. Appendix A - Notice of Exemption	98
2. Appendix B - Fire Hydrant Meter Program	108
3. Appendix C - Materials Typically Accepted by Certificate of Compliance	122
4. Appendix D - Sample City Invoice	124
5. Appendix E - Overall Location Map.....	126
6. Appendix F - Resurfacing Limits Maps	128
7. Appendix G - Contractor's Daily Quality Control Inspection Report	175
8. Appendix H - Sample of Public Notice (SB1 Funded Only)	182
9. Appendix I - Advanced Metering Infrastructure (AMI) Device Protection.....	184
10. Appendix J - Advanced Construction Notice.....	191
11. Appendix K - Estimated Construction Quantities.....	194
12. Appendix L - Scrub Broom Diagram	198
13. Appendix M - Street List.....	200
14. Appendix N - Cape Seal Flyer.....	204
15. Appendix O - Red Curb Quantities.....	206
F. IN-USE OFF-ROAD DIESEL FUELED FLEET REGULATION (OFF-ROAD REGULATION) COMPLIANCE (CARB).....	210
G. CONTRACT AGREEMENT	214
6. CERTIFICATIONS AND FORMS.....	217

REQUIRED DOCUMENTS SCHEDULE DURING BIDDING AND AWARDING

The Bidder's attention is directed to the City's Municipal Code §22.0807(d)(2) for important information regarding grounds for debarment for failure to submit required documentation.

The specified Equal Opportunity Contracting Program (EOCP) forms are available for download from the City's web site at:

<http://www.sandiego.gov/eoc/forms/index.shtml>

ITEM	DOCUMENT TO BE SUBMITTED	WHEN DUE	FROM
1.	Bid Bond (PDF via PlanetBids)	At Time of Bid	ALL BIDDERS
2.	Contractor's Certification of Pending Actions	At Time of Bid	ALL BIDDERS
3.	Mandatory Disclosure of Business Interests	At Time of Bid	ALL BIDDERS
4.	Debarment and Suspension Certification for Prime Contractors	At Time of Bid	ALL BIDDERS
5.	Debarment and Suspension Certification for Subcontractors, Suppliers & Mfgs	At Time of Bid	ALL BIDDERS
6.	Bid Bond (Original)	At Time of Bid	ALL BIDDERS
7.	SLBE Good Faith Effort Documentation	By 5PM 3 working days after bid opening	ALL BIDDERS
8.	Form AA60 – List of Work Made Available	By 5PM 3 working days after bid opening with Good Faith Effort (GFE) documentation	ALL BIDDERS
9.	If the Contractor is a Joint Venture: <ul style="list-style-type: none"> Joint Venture Agreement Joint Venture License 	Within 10 working days of receipt by bidder of contract forms	AWARDED BIDDER
10.	Payment & Performance Bond; Certificates of Insurance & Endorsements; and Signed Contract Agreement Page	Within 10 working days of receipt by bidder of contract forms and NOI	AWARDED BIDDER
11.	In-Use Off-Road Diesel Fueled Fleet Regulation (OFF-ROAD REGULATION) Compliance	Within 10 working days of receipt by bidder of contract forms and NOI	AWARDED BIDDER

ITEM	DOCUMENT TO BE SUBMITTED	WHEN DUE	FROM
12.	Listing of "Other Than First Tier" Subcontractors	Within 10 working days of receipt by bidder of contract forms	AWARDED BIDDER

NOTICE INVITING BIDS

1. **SUMMARY OF WORK:** This is the City of San Diego's (City) solicitation process to acquire Construction services for **SLURRY SEAL GROUP 2524**. For additional information refer to Attachment A.
2. **FULL AND OPEN COMPETITION:** This solicitation is subject to full and open competition and may be bid by Contractors on the City's approved Prequalified Contractors List. For information regarding the Contractors Prequalified list visit the City's web site: <http://www.sandiego.gov>.
3. **ESTIMATED CONSTRUCTION COST:** The City's estimated construction cost for this project is **\$5,300,000.00**
4. **BID DUE DATE AND TIME ARE: JANUARY 28, 2025 at 2:00 PM.**
5. **PREVAILING WAGE RATES APPLY TO THIS CONTRACT:** Refer to Attachment D.
6. **LICENSE REQUIREMENT:** To be eligible for award of this contract, Prime contractor must possess the following licensing classifications: **A or C-12 or C-32**
7. **SUBCONTRACTING PARTICIPATION PERCENTAGES:** Subcontracting participation percentages apply to this contract.
 - 7.1. The City has incorporated **mandatory** SLBE-ELBE subcontractor participation percentages to enhance competition and maximize subcontracting opportunities. For the purpose of achieving the mandatory subcontractor participation percentages, a recommended breakdown of the SLBE and ELBE subcontractor participation percentages based upon certified SLBE and ELBE firms has also been provided to achieve the mandatory subcontractor participation percentages:

1. SLBE participation	8.1%
2. ELBE participation	7.0%
3. Total mandatory participation	15.1%
 - 7.2. The current list of Certified SLBE/ELBE Firms to be used for outreach for this project is posted to the Documents tab on PlanetBids.
 - 7.3. The Bid may be declared non-responsive if the Bidder fails to meet the following requirements:
 - 7.3.1. Include SLBE-ELBE certified subcontractors at the overall mandatory participation percentage identified in this document; OR
 - 7.3.2. Submit Good Faith Effort (GFE) documentation, saved in searchable Portable Document Format (PDF), demonstrating the Bidder made a good faith effort to conduct outreach to and include SLBE-ELBE Subcontractors as required in this solicitation by 5PM 3 Working Days after the Bid opening if the overall mandatory participation percentage is not met.

All submittals in searchable PDF shall be submitted electronically within the prescribed time identified in the contract documents via PlanetBids by invitation to the point of contact named in the bid provided by the Contract Specialist to all bidders.

8. NON-MANDATORY PRE-BID MEETING:

8.1. ONLINE PRE-BID MEETING:

Prospective Bidders are **Encouraged** to attend the Pre-Bid Meeting.

The Pre-Bid Meeting will be held on **Thursday, January 9, 2025**, at **10:00 AM (PDT)** at:

Microsoft Teams [Need help?](#)

[Join the meeting now](#)

Meeting ID: 272 231 179 233

Passcode: x6ra6Se9

Dial in by phone

[+1 945-468-5511,,182752869#](#) United States, Los Angeles

[Find a local number](#)

Phone Conference ID: # 182 752 869

For organizers: [Meeting options](#) | [Reset dial-in PIN](#)

Please Note: You will need to join the meeting with a computer, tablet or smartphone with the **Microsoft Teams** in order to sign in via the Chat feature as attendance at the meeting will be evidenced by the Chat sign-in. The Chat feature will also be used for attendees to ask any questions.

The purpose of the meeting is to discuss the scope of the Project, submittal requirements, and any Equal Opportunity Contracting Program requirements and reporting procedures.

Upon entering the meeting, all attendees must use the chat feature to sign in with the following information: Name of firm, Attendee's name, Phone number and Email address.

9. AWARD PROCESS:

- 9.1.** The Award of this contract is contingent upon the Contractor's compliance with all conditions of Award as stated within these documents and within the Notice of Intent to Award.
- 9.2.** Upon acceptance of bids and determination of the apparent low bidder, the City will prepare the contract documents for execution within approximately 21 days of the date of the bid opening. The City will then award the contract upon receipt of properly signed Contract, bonds, and insurance documents.
- 9.3.** This contract will be deemed executed and effective only upon the signing of the Contract by the Mayor or his designee and approval as to form by the City Attorney's Office.

- 9.4.** The low Bid will be determined by the Base Bid.
- 9.5.** Once the low Bid has been determined, the City may, at its sole discretion, award the contract for the Base Bid alone.

10. SUBMISSION OF QUESTIONS:

- 10.1.** The Director (or Designee) of the Purchasing & Contracting Department is the officer responsible for opening, examining, and evaluating the competitive Bids submitted to the City for the acquisition, construction and completion of any public improvement except when otherwise set forth in these documents. Any questions related to this solicitation shall be submitted to:

Abel Martinez, Contract Specialist at MartinezAbel@sandiego.gov

- 10.2.** Questions received less than 14 days prior to the date for opening of Bids may not be considered.
- 10.3.** Questions or clarifications deemed by the City to be material shall be answered via issuance of an addendum and posted to the City's online bidding service.
- 10.4.** Only questions answered by formal written addenda shall be binding. Oral and other interpretations or clarifications shall be without legal effect. It is the Bidder's responsibility to be informed of any addenda that have been issued and to include all such information in its Bid.

INSTRUCTIONS TO BIDDERS

1. PREQUALIFICATION OF CONTRACTORS:

- 1.1. Contractors submitting a Bid must be pre-qualified for the total amount proposed, including all alternate items, prior to the date of submittal. Bids from contractors who have not been pre-qualified as applicable and Bids that exceed the maximum dollar amount at which contractors are pre-qualified may be deemed **non-responsive** and ineligible for award.
- 1.2. The completed application must be submitted online no later than 2 weeks prior to the bid opening.
- 1.3. **Joint Venture Bidders Cumulative Maximum Bidding Capacity:** For projects with an engineer's estimate of \$30,000,000 or greater, Joint Ventures submitting bids may be deemed responsive and eligible for award if the cumulative maximum bidding capacity of the individual Joint Venture entities is equal to or greater than the total amount proposed.
 - 1.3.1. Each of the entities of the Joint Venture must have been previously prequalified at a minimum of \$15,000,000.
 - 1.3.2. Bids submitted with a total amount proposed of less than \$30,000,000 are not eligible for Cumulative Maximum Bidding Capacity prequalification. To be eligible for award in this scenario, the Joint Venture itself or at least one of the Joint Venture entities must have been prequalified for the total amount proposed.
 - 1.3.3. Bids submitted by Joint Ventures with a total amount proposed of \$30,000,000 or greater on a project with an engineer's estimate of less than \$30,000,000 are not eligible for Cumulative Maximum Bidding Capacity prequalification.
 - 1.3.4. The Joint Venture designated as the Apparent Low Bidder shall provide evidence of its corporate existence and furnish good and approved bonds in the name of the Joint Venture within 14 Calendar Days of receipt by the Bidder of a form of contract for execution.
- 1.4. Complete information and links to the on-line prequalification application are available at:

<http://www.sandiego.gov/cip/bidopps/prequalification>
- 1.5. Due to the City's responsibility to protect the confidentiality of the contractors' information, City staff will not be able to provide information regarding contractors' prequalification status over the telephone. Contractors may access real-time information about their prequalification status via their vendor profile on [PlanetBids.™](#)

2. **ELECTRONIC FORMAT RECEIPT AND OPENING OF BIDS:** Bids will be received in electronic format (eBids) EXCLUSIVELY at the City of San Diego's electronic bidding (eBidding) site, at: <http://www.sandiego.gov/cip/bidopps/> and are due by the date, and time shown on the cover of this solicitation.
- 2.1. **BIDDERS MUST BE PRE-REGISTERED** with the City's bidding system and possess a system-assigned Digital ID in order to submit an electronic bid.
- 2.2. The City's bidding system will automatically track information submitted to the site including IP addresses, browsers being used and the URLs from which information was submitted. In addition, the City's bidding system will keep a history of every login instance including the time of login, and other information about the user's computer configuration such as the operating system, browser type, version, and more. Because of these security features, Contractors who disable their browsers' cookies will not be able to log in and use the City's bidding system.
- 2.3. The City's electronic bidding system is responsible for bid tabulations. Upon the bidder's or proposer's entry of their bid, the system will ensure that all required fields are entered. **The system will not accept a bid for which any required information is missing.** This includes all necessary pricing, subcontractor listing(s) and any other essential documentation and supporting materials and forms requested or contained in these solicitation documents.
- 2.4. **BIDS REMAIN SEALED UNTIL BID DEADLINE.** eBids are transmitted into the City's bidding system via hypertext transfer protocol secure (https) mechanism using SSL 128-256 bit security certificates issued from Verisign/Thawte which encrypts data being transferred from client to server. Bids submitted prior to the "Bid Due Date and Time" are not available for review by anyone other than the submitter who has until the "Bid Due Date and Time" to change, rescind or retrieve its proposal should it desire to do so.
- 2.5. **BIDS MUST BE SUBMITTED BY BID DUE DATE AND TIME.** Once the bid deadline is reached, no further submissions are accepted into the system. Once the Bid Due Date and Time has lapsed, bidders, proposers, the general public, and City staff are able to immediately see the results on line. City staff may then begin reviewing the submissions for responsiveness, EOCB compliance and other issues. The City may require any Bidder to furnish statement of experience, financial responsibility, technical ability, equipment, and references.
- 2.6. **RECAPITULATION OF THE WORK.** Bids shall not contain any recapitulation of the Work. Conditional Bids may be rejected as being non-responsive. Alternative proposals will not be considered unless called for.
- 2.7. **BIDS MAY BE WITHDRAWN** by the Bidder only up to the bid due date and time.
- 2.7.1. **Important Note:** Submission of the electronic bid into the system may not be instantaneous. Due to the speed and capabilities of the user's internet service provider (ISP), bandwidth, computer hardware and other variables, it may take time for the bidder's submission to upload and be received by the City's eBidding system. It is the bidder's sole responsibility to ensure their bids are received on time by the City's eBidding system. The City of San Diego is not responsible for bids that do not arrive by the required date and time.

- 2.8. ACCESSIBILITY AND AMERICANS WITH DISABILITIES ACT (ADA) COMPLIANCE:** To request a copy of this solicitation in an alternative format, contact the Purchasing & Contracting Department, Public Works Division Contract Specialist listed on the cover of this solicitation at least five (5) working days prior to the Bid/Proposal due date to ensure availability.
- 3. ELECTRONIC BID SUBMISSIONS CARRY FULL FORCE AND EFFECT:**
- 3.1.** The bidder, by submitting its electronic bid, acknowledges that doing so carries the same force and full legal effect as a paper submission with a longhand (wet) signature.
- 3.2.** By submitting an electronic bid, the bidder certifies that the bidder has thoroughly examined and understands the entire Contract Documents (which consist of the plans and specifications, drawings, forms, affidavits and the solicitation documents), and that by submitting the eBid as its bid proposal, the bidder acknowledges, agrees to and is bound by the entire Contract Documents, including any addenda issued thereto, and incorporated by reference in the Contract Documents.
- 3.3.** The Bidder, by submitting its electronic bid, agrees to and certifies under penalty of perjury under the laws of the State of California, that the certification, forms and affidavits submitted as part of this bid are true and correct.
- 3.4.** The Bidder agrees to the construction of the project as described in Attachment "A-Scope of Work" for the City of San Diego, in accordance with the requirements set forth herein for the electronically submitted prices. The Bidder guarantees the Contract Price for a period of 120 days from the date of Bid opening. The duration of the Contract Price guarantee shall be extended by the number of days required for the City to obtain all items necessary to fulfill all conditions precedent.
- 4. BIDS ARE PUBLIC RECORDS:** Upon receipt by the City, Bids shall become public records subject to public disclosure. It is the responsibility of the respondent to clearly identify any confidential, proprietary, trade secret or otherwise legally privileged information contained within the Bid. General references to sections of the California Public Records Act (PRA) will not suffice. If the Contractor does not provide applicable case law that clearly establishes that the requested information is exempt from the disclosure requirements of the PRA, the City shall be free to release the information when required in accordance with the PRA, pursuant to any other applicable law, or by order of any court or government agency, and the Contractor will hold the City harmless for release of this information.
- 5. CONTRACTOR REGISTRATION AND ELECTRONIC REPORTING SYSTEM:**
- 5.1.** **Prior** to the Award of the Contract or Task Order, you and your Subcontractors and Suppliers must register with the City's web-based vendor registration and bid management system. For additional information go to:
<http://www.sandiego.gov/purchasing/bids-contracts/vendorreg>
- 5.2.** The City may not award the contract until registration of all subcontractors and suppliers is complete. In the event this requirement is not met within the time frame specified in the Notice of Intent to Award letter, the City reserves the right to rescind the Notice of Award / Intent to Award and to make the award to the next responsive and responsible bidder / proposer

6. **JOINT VENTURE CONTRACTORS:** Provide a copy of the Joint Venture agreement and the Joint Venture license to the City within 14 Calendar Days after receiving the Contract forms.
7. **INSURANCE REQUIREMENTS:**
- 7.1. All certificates of insurance and endorsements required by the contract are to be provided upon issuance of the City's Notice of Intent to Award letter.
- 7.2. Refer to sections 5-4, "INSURANCE" of the Supplementary Special Provisions (SSP) for the insurance requirements which must be met.
8. **REFERENCE STANDARDS:** Except as otherwise noted or specified, the Work shall be completed in accordance with the following standards:

Title	Edition	Document Number
Standard Specifications for Public Works Construction ("The GREENBOOK") http://www.greenbookspecs.org/	2021	ECPI010122-01
City of San Diego Standard Specifications for Public Works Construction ("The WHITEBOOK")* https://www.sandiego.gov/ecp/edocref/greenbook	2021	ECPI010122-02
City of San Diego Standard Drawings* https://www.sandiego.gov/ecp/edocref/standarddraw	2021	ECPI010122-03
Citywide Computer Aided Design and Drafting (CADD) Standards https://www.sandiego.gov/ecp/edocref/drawings	2018	PWPI010119-04
California Department of Transportation (CALTRANS) Standard Specifications https://dot.ca.gov/programs/design/july-2023-ccs-standard-plans-and-standard-specifications	2023	ECPD092023-05
CALTRANS Standard Plans https://dot.ca.gov/programs/design/july-2023-ccs-standard-plans-and-standard-specifications	2023	ECPD092023-06
California Manual on Uniform Traffic Control Devices Revision 8 (CA MUTCD Rev 8) https://dot.ca.gov/programs/safety-programs/camutcd	2014	ECPD032324-07
NOTE: *Available online under Engineering Documents and References at: https://www.sandiego.gov/ecp/edocref/ *Electronic updates to the Standard Drawings may also be found in the link above		

9. **CITY'S RESPONSES AND ADDENDA:** The City, at its discretion, may respond to any or all questions submitted in writing via the City's eBidding web site in the **form of an addendum**. No other responses to questions, oral or written shall be of any force or effect with respect to this solicitation. The changes to the Contract Documents through addenda are made effective as though originally issued with the Bid. The Bidders shall acknowledge the receipt of Addenda at the time of bid submission.

10. **CITY'S RIGHTS RESERVED:** The City reserves the right to cancel the Notice Inviting Bids at any time, and further reserves the right to reject submitted Bids, without giving any reason for such action, at its sole discretion and without liability. Costs incurred by the Bidder(s) as a result of preparing Bids under the Notice Inviting Bids shall be the sole responsibility of each bidder. The Notice Inviting Bids creates or imposes no obligation upon the City to enter a contract.
11. **CONTRACT PRICING:** This solicitation is for a Lump Sum contract with Unit Price provisions as set forth herein. The Bidder agrees to perform construction services for the City of San Diego in accordance with these contract documents for the prices listed below. The Bidder further agrees to guarantee the Contract Price for a period of 120 days from the date of Bid opening. The duration of the Contract Price guarantee may be extended, by mutual consent of the parties, by the number of days required for the City to obtain all items necessary to fulfill all contractual conditions.

12. **SUBCONTRACTOR INFORMATION:**

- 12.1. **LISTING OF SUBCONTRACTORS.** In accordance with the requirements provided in the "Subletting and Subcontracting Fair Practices Act" of the California Public Contract Code, the Bidder shall provide the **NAME** and **ADDRESS** of each Subcontractor who will perform work, labor, render services or who specially fabricates and installs a portion [type] of the work or improvement, in an amount in excess of 0.5% of the Contractor's total Bid. The Bidder shall also state within the description, whether the subcontractor is a **CONSTRUCTOR**, **CONSULTANT** or **SUPPLIER**. The Bidder shall state the **DIR REGISTRATION NUMBER** for all subcontractors and shall further state within the description, the **PORTION** of the work which will be performed by each subcontractor under this Contract. The Contractor shall list only one Subcontractor for each portion of the Work. The **DOLLAR VALUE** of the total Bid to be performed shall be stated for all subcontractors listed. Failure to comply with this requirement may result in the Bid being rejected as **non-responsive** and ineligible for award. The Bidder's attention is directed to the Special Provisions – Section 3-2, "Self-Performance", which stipulates the percent of the Work to be performed with the Bidders' own forces. The Bidder shall list all SLBE, ELBE, DBE, DVBE, MBE, WBE, OBE, SDB, WoSB, HUBZone, and SDVOSB Subcontractors for which Bidders are seeking recognition towards achieving any mandatory, voluntary (or both) subcontracting participation goals.

Additionally, pursuant to California Senate Bill 96 and in accordance with the requirements of Labor Code sections 1771.1 and 1725.5, by submitting a bid or proposal to the City, Contractor is certifying that he or she has verified that all subcontractors used on this public work project are registered with the California Department of Industrial Relations (DIR). **The Bidder shall provide the name, address, license number, DIR registration number of any Subcontractor – regardless of tier** - who will perform work, labor, render services or specially fabricate and install a portion [type] of the work or improvement pursuant to the contract.

- 12.2. LISTING OF SUPPLIERS.** Any Bidder seeking the recognition of Suppliers of equipment, materials, or supplies obtained from third party Suppliers towards achieving any mandatory or voluntary (or both) subcontracting participation goals shall provide, at a minimum, the **NAME, LOCATION (CITY), DIR REGISTRATION NUMBER** and the **DOLLAR VALUE** of each supplier. The Bidder will be credited up to 60% of the amount to be paid to the Suppliers for materials and supplies unless vendor manufactures or substantially alters materials and supplies, in which case, 100% will be credited. The Bidder is to indicate within the description whether the listed firm is a supplier or manufacturer. If no indication is provided, the listed firm will be credited at 60% of the listed dollar value for purposes of calculating the Subcontractor Participation Percentage.
- 12.3. LISTING OF SUBCONTRACTORS OR SUPPLIERS FOR ALTERNATES.** For subcontractors or suppliers to be used on alternate items, bidder shall use the provided **"Subcontractors For Alternates"** form and shall indicate for each alternate subcontract whether it is an additive or deductive alternate; the subcontractor's name, location, phone number, email address, CA license number, and DIR registration number; whether the subcontractor is a designer, constructor or supplier; the type of work the subcontractor will be performing; and the dollar value of the subcontract for that alternate item. Failure to comply with this requirement may result in the bid being rejected as nonresponsive and ineligible for award.
- 13. SUBMITTAL OF "OR EQUAL" ITEMS:** See Section 4-6, "Trade Names" in The WHITEBOOK and as amended in the SSP.
- 14. AWARD:**
- 14.1.** The Award of this contract is contingent upon the Contractor's compliance with all conditions precedent to Award.
- 14.2.** Upon acceptance of a Bid, the City will prepare contract documents for execution within approximately 21 days of the date of the Bid opening and award the Contract approximately within 7 days of receipt of properly executed Contract, bonds, and insurance documents.
- 14.3.** This contract will be deemed executed and effective only upon the signing of the Contract by the Mayor or his designee and approval as to form the City Attorney's Office.
- 15. SUBCONTRACT LIMITATIONS:** The Bidder's attention is directed to Standard Specifications for Public Works Construction, Section 3-2, "SELF-PERFORMANCE" in The GREENBOOK and as amended in the SSP which requires the Contractor to self-perform not less than the specified amount. Failure to comply with this requirement shall render the bid **non-responsive** and ineligible for award.
- 16. AVAILABILITY OF PLANS AND SPECIFICATIONS:** Contract Documents may be obtained by visiting the City's website: <http://www.sandiego.gov/cip/>. Plans and Specifications for this contract are also available for review in the office of the City Clerk or Purchasing & Contracting Department, Public Works Division.

- 17. ONLY ONE BID PER CONTRACTOR SHALL BE ACCEPTED:** No person, firm, or corporation shall be allowed to make, file, or be interested in more than one (1) Bid for the same work unless alternate Bids are called for. A person, firm or corporation who has submitted a sub-proposal to a Bidder, or who has quoted prices on materials to a Bidder, is not hereby disqualified from submitting a sub-proposal or quoting prices to other Bidders or from submitting a Bid in its own behalf. Any Bidder who submits more than one bid will result in the rejection of all bids submitted.
- 18. SAN DIEGO BUSINESS TAX CERTIFICATE:** The Contractor and Subcontractors, not already having a City of San Diego Business Tax Certificate for the work contemplated shall secure the appropriate certificate from the City Treasurer, Civic Center Plaza, First floor and submit to the Contract Specialist upon request or as specified in the Contract Documents. Tax Identification numbers for both the Bidder and the listed Subcontractors must be submitted on the City provided forms within these documents.
- 19. BIDDER'S GUARANTEE OF GOOD FAITH (BID SECURITY) FOR DESIGN-BID-BUILD CONTRACTS:**
- 19.1.** For bids \$250,000 and above, bidders shall submit Bid Security at bid time. Bid Security shall be in one of the following forms: a cashier's check, or a properly certified check upon some responsible bank; or an approved corporate surety bond payable to the City of San Diego for an amount of not less than 10% of the total bid amount.
- 19.2.** This check or bond, and the monies represented thereby, will be held by the City as a guarantee that the Bidder, if awarded the contract, will in good faith enter into the contract and furnish the required final performance and payment bonds.
- 19.3.** The Bidder agrees that in the event of the Bidder's failure to execute this contract and provide the required final bonds, the money represented by the cashier's or certified check will remain the property of the City; and the Surety agrees that it will pay to the City the damages, not exceeding the sum of 10% of the amount of the Bid, that the City may suffer as a result of such failure.
- 19.4.** At the time of bid submission, bidders must upload and submit an electronic PDF copy of the aforementioned bid security. Whether in the form of a cashier's check, a properly certified check or an approved corporate surety bond payable to the City of San Diego, the bid security must be uploaded to the City's eBidding system. By 5PM, 1 working day after the bid opening date, all bidders must provide the City with the original bid security.
- 19.5.** Failure to submit the electronic version of the bid security at the time of bid submission AND failure to provide the original by 5PM, 1 working day after the bid opening date shall cause the bid to be rejected and deemed **non-responsive**.

Original Bid Bond shall be submitted to:
Purchasing & Contracting Department, Public Works Division
1200 3rd Ave., Suite 200, MS 56P
San Diego, California, 92101
To the Attention of the Contract Specialist on the Front Page of this solicitation.

20. AWARD OF CONTRACT OR REJECTION OF BIDS:

- 20.1.** This contract may be awarded to the lowest responsible and reliable Bidder.
- 20.2.** Bidders shall complete ALL eBid forms as required by this solicitation. Incomplete eBids will not be accepted.
- 20.3.** The City reserves the right to reject any or all Bids, to waive any informality or technicality in Bids received, and to waive any requirements of these specifications as to bidding procedure.
- 20.4.** Bidders will not be released on account of their errors of judgment. Bidders may be released only upon receipt by the City within 3 Working Days of the bid opening, written notice from the Bidder which shows proof of honest, credible, clerical error of a material nature, free from fraud or fraudulent intent; and of evidence that reasonable care was observed in the preparation of the Bid.
- 20.5.** A bidder who is not selected for contract award may protest the award of a contract to another bidder by submitting a written protest in accordance with the San Diego Municipal Code.
- 20.6.** The City of San Diego will not discriminate in the award of contracts with regard to race, religion creed, color, national origin, ancestry, physical handicap, marital status, sex or age.
- 20.7.** Each Bid package properly signed as required by these specifications shall constitute a firm offer which may be accepted by the City within the time specified herein.
- 20.8.** The City reserves the right to evaluate all Bids and determine the lowest Bidder on the basis of the base bid and any proposed alternates or options as detailed herein.

21. BID RESULTS:

- 21.1.** The availability of the bids on the City's eBidding system shall constitute the public announcement of the apparent low bidder. In the event that the apparent low bidder is subsequently deemed non-responsive or non-responsible, a notation of such will be made on the eBidding system. The new ranking and apparent low bidder will be adjusted accordingly.
- 21.2.** To obtain the bid results, view the results on the City's web site, or request the results by U.S. mail and provide a self-addressed, stamped envelope. If requesting by mail, be sure to reference the bid name and number. The bid tabulations will be mailed to you upon their completion. The results will not be given over the telephone.

22. THE CONTRACT:

- 22.1.** The Bidder to whom award is made shall execute a written contract with the City of San Diego and furnish good and approved bonds and insurance certificates specified by the City within 14 days after receipt by Bidder of a form of contract for execution unless an extension of time is granted to the Bidder in writing.

- 22.2.** If the Bidder takes longer than 14 days to fulfill these requirements, then the additional time taken shall be added to the Bid guarantee. The Contract shall be made in the form adopted by the City, which includes the provision that no claim or suit whatsoever shall be made or brought by Contractor against any officer, agent, or employee of the City for or on account of anything done or omitted to be done in connection with this contract, nor shall any such officer, agent, or employee be liable hereunder.
- 22.3.** If the Bidder to whom the award is made fails to enter into the contract as herein provided, the award may be annulled and the Bidder's Guarantee of Good Faith will be subject to forfeiture. An award may be made to the next lowest responsible and reliable Bidder who shall fulfill every stipulation embraced herein as if it were the party to whom the first award was made.
- 22.4.** Pursuant to the San Diego City Charter section 94, the City may only award a public works contract to the lowest responsible and reliable Bidder. The City will require the Apparent Low Bidder to (i) submit information to determine the Bidder's responsibility and reliability, (ii) execute the Contract in form provided by the City, and (iii) furnish good and approved bonds and insurance certificates specified by the City within 14 Days, unless otherwise approved by the City, in writing after the Bidder receives notification from the City, designating the Bidder as the Apparent Low Bidder and formally requesting the above mentioned items.
- 22.5.** The award of the Contract is contingent upon the satisfactory completion of the above-mentioned items and becomes effective upon the signing of the Contract by the Mayor or designee and approval as to form by the City Attorney's Office. If the Apparent Low Bidder does not execute the Contract or submit required documents and information, the City may award the Contract to the next lowest responsible and reliable Bidder who shall fulfill every condition precedent to award. A corporation designated as the Apparent Low Bidder shall furnish evidence of its corporate existence and evidence that the officer signing the Contract and bond for the corporation is duly authorized to do so.
- 23. EXAMINATION OF PLANS, SPECIFICATIONS, AND SITE OF WORK:** The Bidder shall examine carefully the Project Site, the Plans and Specifications, other materials as described in the Special Provisions, Section 3-9, "TECHNICAL STUDIES AND SUBSURFACE DATA", and the proposal forms (e.g., Bidding Documents). The submission of a Bid shall be conclusive evidence that the Bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and scope of work, the quantities of materials to be furnished, and as to the requirements of the Bidding Documents Proposal, Plans, and Specifications.
- 24. CITY STANDARD PROVISIONS:** This contract is subject to the following standard provisions. See The WHITEBOOK for details.
- 24.1.** The City of San Diego Resolution No. R-277952 adopted on May 20, 1991 for a Drug-Free Workplace.
- 24.2.** The City of San Diego Resolution No. R-282153 adopted on June 14, 1993 related to the Americans with Disabilities Act.
- 24.3.** The City of San Diego Municipal Code §22.3004 for Contractor Standards.

- 24.4.** The City of San Diego's Labor Compliance Program and the State of California Labor Code §§1771.5(b) and 1776.
- 24.5.** Sections 1777.5, 1777.6, and 1777.7 of the State of California Labor Code concerning the employment of apprentices by contractors and subcontractors performing public works contracts.
- 24.6.** The City's Equal Benefits Ordinance (EBO), Chapter 2, Article 2, Division 43 of The San Diego Municipal Code (SDMC).
- 24.7.** The City's Information Security Policy (ISP) as defined in the City's Administrative Regulation 90.63.

25. PRE-AWARD ACTIVITIES:

- 25.1.** The contractor selected by the City to execute a contract for this Work shall submit the required documentation as specified herein and in the Notice of Intent to Award. Failure to provide the information as specified may result in the Bid being rejected as **non-responsive**.
- 25.2.** The decision that bid is non-responsive for failure to provide the information required within the time specified shall be at the sole discretion of the City.

PERFORMANCE BOND, LABOR AND MATERIALMEN'S BOND
FAITHFUL PERFORMANCE BOND AND LABOR AND MATERIALMEN'S BOND:

Pavement Coatings Co., a corporation, as principal, and
The Ohio Casualty Insurance Company, a corporation authorized to do
business in the State of California, as Surety, hereby obligate themselves, their successors and assigns,
jointly and severally, to The City of San Diego a municipal corporation in the sum of
Five Million Six Hundred Fourty One Thousand Three Hundred Eighty Eight Dollars and Fifty
Cents (\$5,641,388.50) for the faithful performance of the annexed contract, and in the sum of **Five**
Million Six Hundred Fourty One Thousand Three Hundred Eighty Eight Dollars and Fifty Cents
(\$5,641,388.50) for the benefit of laborers and materialmen designated below.

Conditions:

If the Principal shall faithfully perform the annexed contract with the City of San Diego, California, then the obligation herein with respect to a faithful performance shall be void; otherwise it shall remain in full force.

If the Principal shall promptly pay all persons, firms and corporations furnishing materials for or performing labor in the execution of this contract, and shall pay all amounts due under the California Unemployment Insurance Act then the obligation herein with respect to laborers and materialmen shall be void; otherwise it shall remain in full force.

The obligation herein with respect to laborers and materialmen shall inure to the benefit of all persons, firms and corporations entitled to file claims under the provisions of Article 2. Claimants, (iii) public works of improvement commencing with Civil Code Section 9100 of the Civil Code of the State of California.

Changes in the terms of the annexed contract or specifications accompanying same or referred to therein shall not affect the Surety's obligation on this bond, and the Surety hereby waives notice of same.

The Surety shall pay reasonable attorney's fees should suit be brought to enforce the provisions of this bond.

The Surety expressly agrees that the City of San Diego may reject any contractor or subcontractor which may be proposed by Surety in fulfillment of its obligations in the event of default by the Principal.

The Surety shall not utilize the Principal in completing the improvements and work specified in the Agreement in the event the City terminates the Principal for default.


PERFORMANCE BOND, LABOR AND MATERIALMEN'S BOND

CONTRACTOR

By: [Signature]
Pavement Coatings Co.

Print Name: Tom Mucenski
Tom Mucenski, Secretary

Date: 2-19-2025



THE CITY OF SAN DIEGO

By: [Signature]

Print Name: Berric Doringo
Deputy Director
Purchasing & Contracting Department


Date: 2/26/2025

SURETY

By: [Signature]
The Ohio Casualty Insurance Company

Print Name: Marisella Rivera
Attorney-In-Fact

Date: February 18, 2025



APPROVED AS TO FORM
Heather Ferbert, City Attorney

By: [Signature]

Print Name: Dominic Guglielmo
Deputy City Attorney

Date: 2/26/25

790 The City Drive South, Suite 200, Orange, CA 92868

Local Address of Surety

(714) 634-5717

Local Phone Number of Surety

\$21,668.00

Premium

024280535

Bond Number

CALIFORNIA ALL-PURPOSE ACKNOWLEDGMENT

CIVIL CODE § 1189

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

State of California }

County of Riverside }


On February 19th, 2025 before me, Ottly J Gettle, Notary Public
Date Here Insert Name and Title of the Officer

personally appeared Tom Mucenski
Name(s) of Signer(s)

who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.



Place Notary Seal and/or Stamp Above

Signature *Ottly J. Gettle*
Signature of Notary Public

OPTIONAL

Completing this information can deter alteration of the document or fraudulent reattachment of this form to an unintended document.

Description of Attached Document

Title or Type of Document: _____

Document Date: _____ Number of Pages: _____

Signer(s) Other Than Named Above: _____

Capacity(ies) Claimed by Signer(s)

Signer's Name: _____ Signer's Name: _____

☐ Corporate Officer – Title(s): _____ ☐ Corporate Officer – Title(s): _____

☐ Partner – ☐ Limited ☐ General ☐ Partner – ☐ Limited ☐ General

☐ Individual ☐ Attorney in Fact ☐ Individual ☐ Attorney in Fact

☐ Trustee ☐ Guardian of Conservator ☐ Trustee ☐ Guardian of Conservator

☐ Other: _____ ☐ Other: _____

Signer is Representing: _____ Signer is Representing: _____


CALIFORNIA ALL-PURPOSE ACKNOWLEDGMENT**CIVIL CODE § 1189**

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

State of California)

County of Orange)On February 18, 2025 before me, Evet Lam, Notary Public,
*Date Here Insert Name and Title of the Officer*personally appeared Marisella Rivera
Name(s) of Signer(s)

who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.



I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature _____
Signature of Notary Public

Place Notary Seal Above

OPTIONAL

Though this section is optional, completing this information can deter alteration of the document or fraudulent reattachment of this form to an unintended document.

Description of Attached Document

Title or Type of Document: _____ Document Date: _____

Number of Pages: _____ Signer(s) Other Than Named Above: _____

Capacity(ies) Claimed by Signer(s)

Signer's Name: _____

☐ Corporate Officer — Title(s): _____☐ Partner — ☐ Limited ☐ General☐ Individual ☐ Attorney in Fact☐ Trustee ☐ Guardian or Conservator☐ Other: _____

Signer Is Representing: _____

Signer's Name: _____

☐ Corporate Officer — Title(s): _____☐ Partner — ☐ Limited ☐ General☐ Individual ☐ Attorney in Fact☐ Trustee ☐ Guardian or Conservator☐ Other: _____

Signer Is Representing: _____



This Power of Attorney limits the acts of those named herein, and they have no authority to bind the Company except in the manner and to the extent herein stated.

Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

Certificate No: 8208193-971991

POWER OF ATTORNEY

KNOWN ALL PERSONS BY THESE PRESENTS: That The Ohio Casualty Insurance Company is a corporation duly organized under the laws of the State of New Hampshire, that Liberty Mutual Insurance Company is a corporation duly organized under the laws of the State of Massachusetts, and West American Insurance Company is a corporation duly organized under the laws of the State of Indiana (herein collectively called the "Companies"), pursuant to and by authority herein set forth, does hereby name, constitute and appoint, Brian A. McGoldrick, Brigid Lopez, Evett Lam, Marisella Rivera

all of the city of Placentia state of CA each individually if there be more than one named, its true and lawful attorney-in-fact to make, execute, seal, acknowledge and deliver, for and on its behalf as surety and as its act and deed, any and all undertakings, bonds, recognizances and other surety obligations, in pursuance of these presents and shall be as binding upon the Companies as if they have been duly signed by the president and attested by the secretary of the Companies in their own proper persons.

IN WITNESS WHEREOF, this Power of Attorney has been subscribed by an authorized officer or official of the Companies and the corporate seals of the Companies have been affixed thereto this 21st day of June, 2022.



Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

By: David M. Carey
David M. Carey, Assistant Secretary

State of PENNSYLVANIA ss
County of MONTGOMERY

On this 21st day of June, 2022 before me personally appeared David M. Carey, who acknowledged himself to be the Assistant Secretary of Liberty Mutual Insurance Company, The Ohio Casualty Company, and West American Insurance Company, and that he, as such, being authorized so to do, execute the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my notarial seal at King of Prussia, Pennsylvania, on the day and year first above written.



Commonwealth of Pennsylvania - Notary Seal
Teresa Pastella, Notary Public
Montgomery County
My commission expires March 28, 2025
Commission number 1126044
Member, Pennsylvania Association of Notaries

By: Teresa Pastella
Teresa Pastella, Notary Public

This Power of Attorney is made and executed pursuant to and by authority of the following By-laws and Authorizations of The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company which resolutions are now in full force and effect reading as follows:

ARTICLE IV - OFFICERS: Section 12. Power of Attorney.

Any officer or other official of the Corporation authorized for that purpose in writing by the Chairman or the President, and subject to such limitation as the Chairman or the President may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Corporation to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact, subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Corporation by their signature and execution of any such instruments and to attach thereto the seal of the Corporation. When so executed, such instruments shall be as binding as if signed by the President and attested to by the Secretary. Any power or authority granted to any representative or attorney-in-fact under the provisions of this article may be revoked at any time by the Board, the Chairman, the President or by the officer or officers granting such power or authority.

ARTICLE XIII - Execution of Contracts: Section 5. Surety Bonds and Undertakings.

Any officer of the Company authorized for that purpose in writing by the chairman or the president, and subject to such limitations as the chairman or the president may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Company by their signature and execution of any such instruments and to attach thereto the seal of the Company. When so executed such instruments shall be as binding as if signed by the president and attested by the secretary.

Certificate of Designation - The President of the Company, acting pursuant to the Bylaws of the Company, authorizes David M. Carey, Assistant Secretary to appoint such attorneys-in-fact as may be necessary to act on behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations.

Authorization - By unanimous consent of the Company's Board of Directors, the Company consents that facsimile or mechanically reproduced signature of any assistant secretary of the Company, wherever appearing upon a certified copy of any power of attorney issued by the Company in connection with surety bonds, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

I, Renee C. Llewellyn, the undersigned, Assistant Secretary, The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company do hereby certify that the original power of attorney of which the foregoing is a full, true and correct copy of the Power of Attorney executed by said Companies, is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this 18 day of February, 2025.



By: Renee C. Llewellyn
Renee C. Llewellyn, Assistant Secretary

Not valid for mortgage, note, loan, letter of credit, currency rate, interest rate or residual value guarantees.

For bond and/or Power of Attorney (POA) verification inquiries, please call 610-832-8240 or email HOSUR@libertymutual.com.

ATTACHMENTS

ATTACHMENT A
SCOPE OF WORK

SCOPE OF WORK

1. **SCOPE OF WORK:** Slurry Seal Group 2524 involves furnishing all labor, materials, equipment, services, and construction related to slurry seal, scrub seal, and cape seal work on existing paved roadways in various areas throughout the City of San Diego. The work includes: placement of rubber polymer modified slurry seal (RPMS) or placement of polymer modified rejuvenating emulsion (PMRE) scrub seal and/or cape seal on 40.02 lane miles, crack sealing, asphalt mill and pave, and digouts, pavement base repairs, milling and disposal of pavement fabric, development of a QA/QC plan that includes inspection and testing for asphalt and surface seal work, replacing traffic signal detection loops and stub outs, adjusting existing City manhole frames and covers to grade, raising appurtenances to grade (water, sewer), raising survey monuments to grade, reconstructing survey monument boxes, street and sidewalk sweeping, removal and replacement of existing thermoplastic striping and markings/legends, implementation of new striping plans, traffic control drawings & permits, weed abatement, storm drain inlet protection, installation of inlet markings, sediment control, and possible night and weekend work. All work would occur within the public right-of-way (paved streets) or previously disturbed non-sensitive areas only, and outside of the City's Multiple Habitat Planning Area (MHPA). No sensitive vegetation would be impacted or removed. Storm Water Best Management Practices (BMPs) for erosion control preventing discharge, as well as Traffic Control Plan (TCP) would be implemented throughout construction.

1.1. The Work shall be performed in accordance with:

- 1.1.1. The Notice Inviting Bids and Striping, Signage & Electrical Improvement plans, Appendix K, Appendix M and Appendix O included below, inclusive. The PDFs of the plans can be found in the link below:

https://drive.google.com/drive/folders/1IUtjVMMZeE40P2GXy64UNN_eG9M-s3j-

- 1) **Canon St Striping, Signage & Electrical Improvement**
(0101854-1-D through 0101854-11-D).
- 2) **Cardeno Dr Striping & Signage Improvement**
(0101856-01-D through 0101856-07-D).
- 3) **Carmel Country Rd Striping, Signage & Electrical Improvement**
(0101855-01-D through 0101855-10-D).
- 4) **Rosecrans St Striping, Signage & Electrical Improvement**
(0101858-1-D through 0101858-09-D).
- 5) **Soledad Mountain Rd Striping & Signage Improvement**
(0101859-01-D through 0101859-07-D).
- 6) **Sunset Cliffs Blvd Striping & Signage Improvement**
(0101861-01-D through 0101861-03-D).
- 7) **Vista Sorrento Pkwy Striping, Signage & Electrical Improvement**
(0101860-01-D through 0101860-12-D).

1.1.1.1. Appendix M – Street List

1.1.1.2. Appendix K – Estimated Construction Quantities

1.1.1.3. Appendix O – Red Curb Quantities

2. LOCATION OF WORK: The location of the Work is as follows:

See **Appendix E – Overall Location Map** and **Appendix F – Resurfacing Limits Maps**

3. CONTRACT TIME: The Contract Time for completion of the Work shall be **90 Working Days**.

ATTACHMENT B

RESERVED

ATTACHMENT C

EQUAL OPPORTUNITY CONTRACTING PROGRAM

EQUAL OPPORTUNITY CONTRACTING PROGRAM (EOCP)

SECTION A - GENERAL REQUIREMENTS

A. INTRODUCTION.

1. This document sets forth the following specifications:
 - a) The City's general EOCP requirements for all Construction Contracts.
 - b) Special Provisions for Contracts subject to SLBE and ELBE requirements only.
2. Additional requirements may apply for state or federally funded projects.
3. These requirements shall be included as Contract provisions for all Subcontracts.
4. The City specified forms, instructions, and guides are available for download from the EOCP's web site at: <http://www.sandiego.gov/eoc/forms/index.shtml>

B. GENERAL.

1. The City of San Diego promotes equal employment and subcontracting opportunities.
2. The City is committed to ensuring that taxpayer dollars spent on public Contracts are not paid to businesses that practice discrimination in employment or subcontracting.
3. The City encourages all companies seeking to do business with the City to share this commitment.

C. DEFINITIONS.

1. For the purpose of these requirements: Terms "Bid" and "Proposal", "Bidder" and "Proposer", "Subcontractor" and "Subconsultant", "Contractor" and "Consultant", "Contractor" and "Prime Contractor", "Consultant" and "Professional Service Provider", "Suppliers" and "Vendors", "Suppliers" and "Dealers", and "Suppliers" and "Manufacturers" may have been used interchangeably.
2. The following definitions apply:
 - a) **Emerging Business Enterprise (EBE)** - A for-profit business that is independently owned and operated; that is not a subsidiary or franchise of another business and whose gross annual receipts do not exceed the amount set by the City Manager and that meets all other criteria set forth in regulations implementing Municipal Code Chapter 2, Article 2, Division 36. The City Manager shall review the threshold amount for EBEs on an annual basis and adjust as necessary to reflect changes in the marketplace.
 - b) **Emerging Local Business Enterprise (ELBE)** - A Local Business Enterprise that is also an Emerging Business Enterprise.

- c) **Minority Business Enterprise (MBE)** - A certified business that is at least fifty-one percent (51%) owned by one or more minority individuals, or, in the case of a publicly owned business at least fifty-one percent (51%) of the stock is owned by one or more minority individuals; and (2) whose daily business operations are managed and directed by one or more minorities owners. Minorities include the groups with the following ethnic origins: African, Asian Pacific, Asian Subcontinent, Hispanic, Native Alaskan, Native American, and Native Hawaiian.
- d) **Women Business Enterprise (WBE)** - A certified business that is at least fifty-one percent (51%) owned by a woman or women, or, in the case of a publicly owned business at least fifty-one percent (51%) of the stock is owned by one or more women; and (2) whose daily business operations are managed and directed by one or more women owners.
- e) **Disadvantaged Business Enterprise (DBE)** - a certified business that is at least fifty-one percent (51%) owned by socially and economically disadvantaged individuals, or, in the case of a publicly owned business at least fifty-one percent (51%) of the stock is owned by one or more socially and economically disadvantaged individuals; and (2) whose daily business operations are managed and directed by one or more socially and economically disadvantaged owners.
- f) **Disabled Veteran Business Enterprise (DVBE)** - A certified business that is at least fifty-one percent (51%) owned by one or more disabled veterans; and (2) business operations must be managed and controlled by one or more disabled veterans. Disabled Veteran is a veteran of the U.S. military, naval, or air service; the veteran must have a service-connected disability of at least 10% or more; and the veteran must reside in California.
- g) **Other Business Enterprise (OBE)** - Any business which does not otherwise qualify as a Minority, Woman, Disadvantaged, or Disabled Veteran Business Enterprise.
- h) **Small Business Enterprise (SBE)** - A for-profit business that is independently owned and operated; that is not a subsidiary or franchise of another business and whose gross annual receipts do not exceed the amount set by the City Manager and that meets all other criteria set forth in regulations implementing Municipal Code Chapter 2, Article 2, Division 36. The City Manager shall review the threshold amount for SBEs on an annual basis and adjust as necessary to reflect changes in the marketplace. A business certified as a Micro Business (MB) or a Disabled Veteran Business Enterprise (DVBE) by the State of California and that has provided proof of such certification to the City Manager shall be deemed to be an SBE.

- i) **Small Local Business Enterprise (SLBE)** - A Local Business Enterprise that is also a Small Business Enterprise.

D. CITY'S EQUAL OPPORTUNITY COMMITMENT.

1. Nondiscrimination in Contracting Ordinance.

- a) You, your Subcontractors, and Suppliers shall comply with the requirements of the City's Nondiscrimination in Contracting Ordinance, San Diego Municipal Code §§22.3501 through 22.3517.

You shall not discriminate on the basis of race, gender, gender expression, gender identity, religion, national origin, ethnicity, sexual orientation, age, or disability in the solicitation, selection, hiring, or treatment of subcontractors, vendors, or suppliers. You shall provide equal opportunity for Subcontractors to participate in subcontracting opportunities. You understand and agree that the violation of this clause shall be considered a material breach of the Contract and may result in Contract termination, debarment, or other sanctions.

You shall include the foregoing clause in all Contracts between you and your Subcontractors and Suppliers.

- b) **Disclosure of Discrimination Complaints.** As part of its Bid or Proposal, you shall provide to the City a list of all instances within the past 10 years where a complaint was filed or pending against you in a legal or administrative proceeding alleging that you discriminated against your employees, Subcontractors, vendors, or suppliers, and a description of the status or resolution of that complaint, including any remedial action taken.
- c) Upon the City's request, You agree to provide to the City, within 60 Calendar Days, a truthful and complete list of the names of all Subcontractors and Suppliers that you have used in the past 5 years on any of your Contracts that were undertaken within the San Diego County, including the total dollar amount paid by you for each Subcontract or supply Contract.
- d) You further agree to fully cooperate in any investigation conducted by the City pursuant to the City's Nondiscrimination in Contracting Ordinance, Municipal Code §§22.3501 through 22.3517. You understand and agree that violation of this clause shall be considered a material breach of the Contract and may result in remedies being ordered against you up to and including contract termination, debarment, and other sanctions for the violation of the provisions of the Nondiscrimination in Contracting Ordinance. You further understand and agree that the procedures, remedies, and sanctions provided for in the Nondiscrimination in Contracting Ordinance apply only to violations of the Ordinance.

E.

EQUAL EMPLOYMENT OPPORTUNITY OUTREACH PROGRAM.

1. You, your Subcontractors, and Suppliers shall comply with the City's Equal Employment Opportunity Outreach Program, San Diego Municipal Code §§22.2701 through 22.2707.

You shall not discriminate against any employee or applicant for employment on any basis prohibited by law. You shall provide equal opportunity in all employment practices. You shall ensure that your Subcontractors comply with this program. Nothing in this section shall be interpreted to hold you liable for any discriminatory practices of your Subcontractors.

You shall include the foregoing clause in all Contracts between you and your Subcontractors and Suppliers.

2. If the Contract is competitively solicited, the selected Bidder shall submit a Work Force Report (Form BB05) within 10 Working Days after receipt by the Bidder to the City for approval as specified in the Notice of Intent to Award letter.
3. The selected Bidder shall submit an Equal Employment Opportunity Plan if a Work Force Report is submitted and if the City determines that there are under-representations when compared to County Labor Force Availability data.
4. If the selected Bidder submits an Equal Employment Opportunity Plan, it shall include the following assurances:
 - a) You shall maintain a working environment free of discrimination, harassment, intimidation, and coercion at all Sites and in all facilities at which your employees are assigned to Work.
 - b) You shall review your EEO Policy annually with all on-Site supervisors involved in employment decisions.
 - c) You shall disseminate and review your EEO Policy with all employees at least once a year, post the policy statement and EEO posters on all company bulletin boards and job sites, and document every dissemination, review, and posting with a written record to identify the time, place, employees present, subject matter, and disposition of meetings.
 - d) You shall review, at least annually, all supervisors' adherence to and performance under the EEO Policy and maintain written documentation of these reviews.
 - e) You shall discuss your EEO Policy Statement with Subcontractors with whom you anticipate doing business, including the EEO Policy Statement in your Subcontracts, and provide such documentation to the City upon request.

- f) You shall document and maintain a record of all Bid solicitations and outreach efforts to and from Subcontractors, contractor associations, and other business associations.
- g) You shall disseminate your EEO Policy externally through various media, including the media of people of color and women, in advertisements to recruit. Maintain files documenting these efforts and provide copies of these advertisements to the City upon request.
- h) You shall disseminate your EEO Policy to union and community organizations.
- i) You shall provide immediate written notification to the City when any union referral process has impeded your efforts to maintain your EEO Policy.
- j) You shall maintain a current list of recruitment sources, including those outreaching to people of color and women, and provide written notification of employment opportunities to these recruitment sources with a record of the organizations' responses.
- k) You shall maintain a current file of names, addresses and phone numbers of each walk-in applicant, including people of color and women, and referrals from unions, recruitment sources, or community organizations with a description of the employment action taken.
- l) You shall encourage all present employees, including people of color and women employees, to recruit others.
- m) You shall maintain all employment selection process information with records of all tests and other selection criteria.
- n) You shall develop and maintain documentation for on-the-job training opportunities, participate in training programs, or both for all of your employees, including people of color and women, and establish apprenticeship, trainee, and upgrade programs relevant to your employment needs.
- o) You shall conduct, at least annually, an inventory and evaluation of all employees for promotional opportunities and encourage all employees to seek and prepare appropriately for such opportunities.
- p) You shall ensure that the company's working environment and activities are non-segregated except for providing separate or single-user toilets and necessary changing facilities to assure privacy between the sexes.

F. SUBCONTRACTING.

1. The City encourages all eligible business enterprises to participate in City contracts as a Contractor, Subcontractor, and joint venture partner with you, your Subcontractors, or your Suppliers. You are encouraged to take positive steps to diversify and expand your Subcontractor solicitation base and to offer

subcontracting opportunities to all eligible business firms including SLBEs, ELBEs, MBEs, WBEs, DBEs, DVBES, and OBEs.

2. For Subcontractor participation level requirements, see the Contract Documents where applicable.
3. For the purposes of achieving the mandatory Subcontractor participation percentages, City percentage calculations will not account for the following:
 - a) "Field Orders" and "City Contingency" Bid items.
 - b) Alternate Bid items.
 - c) Allowance Bid items designated as "EOC Type II".
4. Allowance Bid items designated as "EOC Type I" will be considered as part of the Base Bid and will be included in the percentage calculation.
5. Each joint venture partner shall be responsible for a clearly defined Scope of Work. In addition, an agreement shall be submitted and signed by all parties identifying the extent to which each joint venture partner shares in ownership, control, management, risk, and profits of the joint venture.

G. LISTS OF SUBCONTRACTORS AND SUPPLIERS.

1. You shall comply with the Subletting and Subcontracting Fair Practices Act, Public Contract Code §§4100 through 4113, inclusive.
2. You shall list all Subcontractors who will receive more than 0.5% of the total Bid amount or \$10,000, whichever is greater on the form provided in the Contract Documents (Subcontractors list).
3. The Subcontractors list shall include the Subcontractor's name, telephone number including area code, physical address, Scope of Work, the dollar amount of the proposed Subcontract, the California contractor license number, the Public Works contractor registration number issued pursuant to Section 1725.5 of the Labor Code, and the Subcontractor's certification status with the name of the certifying agency.
4. The listed Subcontractor shall be appropriately licensed pursuant to Contractor License Laws.
5. For Design-Build Contracts, refer to the RFQ and RFP for each Project or Task Order.

H. SUBCONTRACTOR AND SUPPLIER SUBSTITUTIONS.

1. Listed Subcontractors and Suppliers shall not be substituted without the Express authorization of the City or its duly authorized agent.
2. Request for Subcontractor or Supplier substitution shall be made in writing to Purchasing & Contracting Department, Public Works Division, Attention Contract Specialist, 1200 3rd Ave., Suite 200, MS 56P, San Diego, CA 92101 with a copy to the Engineer.

3. The request shall include a thorough explanation of the reason(s) for the substitution, including dollar amounts and a letter from each substituted Subcontractor or Supplier stating that they (the Subcontractors or Suppliers) release all interest in working on the Project and written confirmation from the new Subcontractor or Supplier stating that they agree to work on the Project along with the dollar value of the Work to be performed.
4. Written approval of the substitution request shall be received by you or from the City or its authorized officer prior to any unlisted Subcontractor or Supplier performing Work on the Project.
5. Substitution of Subcontractors and Suppliers without authorization shall subject you to those penalties set forth in Public Contract Code §4110.
6. Requests for Supplier substitution shall be made in writing at least 10 Days prior to the provision of materials, supplies, or services by the proposed Supplier and shall include proof of written notice to the originally listed Supplier of the proposed substitution.
7. A Contractor whose Bid is accepted shall not:
 - a) Substitute a person as Subcontractor or Supplier in place of the Subcontractor or Supplier listed in the original bid, except that the City, or its duly authorized officer, may consent to the substitution of another person as a Subcontractor or Supplier in any of the following situations:
 - i. When the Subcontractor or Supplier listed in the Bid, after having a reasonable opportunity to do so, fails or refuses to execute a written Contract for the scope of work specified in the subcontractor's bid and at the price specified in the subcontractor's bid, when that written contract, based upon the general terms, conditions, plans, and specifications for the project involved or the terms of the subcontractor's written bid, is presented to the subcontractor by the prime contractor.
 - ii. When the listed Subcontractor or Supplier becomes insolvent or the subject of an order for relief in bankruptcy.
 - iii. When the listed Subcontractor or Supplier fails or refuses to perform his or her subcontract.
 - iv. When the listed Subcontractor fails or refuses to meet bond requirements as set forth in Public Contract Code §4108.
 - v. When you demonstrate to the City or its duly authorized officer, subject to the provisions set forth in Public Contract Code §4107.5, that the name of the Subcontractor was listed as the result of an inadvertent clerical error.
 - vi. When the listed Subcontractor is not licensed pursuant to Contractor License Law.

- vii. When the City, or its duly authorized officer, determines that the Work performed by the listed Subcontractor or that the materials or supplies provided by the listed Supplier are substantially unsatisfactory and not in substantial accordance with the Plans and specifications or that the Subcontractor or Supplier is substantially delaying or disrupting the progress of the Work.
 - viii. When the listed Subcontractor is ineligible to work on a public works project pursuant to §§1777.1 or 1777.7 of the Labor Code.
 - ix. When the City or its duly authorized agent determines that the listed Subcontractor is not a responsible contractor.
 - b) Permit a Contract to be voluntarily assigned or transferred or allow it to be performed by anyone other than the original Subcontractor, Supplier listed in the original Bid without the consent of the City, or its duly authorized officer.
 - c) Other than in the performance of "Change Orders" causing changes or deviations from the Contract, sublet or subcontract any portion of the Work, or contract for materials or supplies in excess of 0.5% of your total bid or \$10,000, whichever is greater, as to which his or her original Bid did not designate a Subcontractor or Supplier.
8. Following receipt of notice from you of the proposed substitution of a Subcontractor or Supplier, the listed Subcontractor or Supplier who has been so notified shall have 5 Working Days within which to submit written objections to the substitution to the Contract Specialist with a copy to the Engineer. Failure to file these written objections shall constitute the listed Subcontractor or Supplier's consent to the substitution. If written objections are filed, the City shall give notice in writing of at least 5 Working Days to the listed Subcontractor or Supplier of a hearing by the City on your request for substitution.

I. PROMPT PAYMENT.

- 1. You or your Subcontractors shall pay to any subcontractor, not later than 7 Calendar Days of receipt of each progress payment, unless otherwise agreed to in writing, the respective amounts allowed you on account of the Work performed by the Subcontractors, to the extent of each Subcontractor's interest therein. In cases of Subcontractor performance deficiencies, you shall make written notice of any withholding to the Subcontractor with a copy to the Contracts Specialist. Upon correction of the deficiency, you shall pay the Subcontractor the amount previously withheld within 14 Calendar Days after payment by the City.
- 2. Any violation of California Business and Professions Code, §7108.5 concerning prompt payment to Subcontractors shall subject the violating Contractor or

Subcontractor to the penalties, sanctions, and other remedies of that section. This requirement shall not be construed to limit or impair any contractual, administrative, or judicial remedies otherwise available to you or your Subcontractor in the event of a dispute involving late payment or nonpayment by the Prime Contractor, deficient subcontract performance, or noncompliance by a Subcontractor.

J. PROMPT PAYMENT OF FUNDS WITHHELD TO SUBCONTRACTORS.

1. The City will hold retention from you and will make prompt and regular incremental acceptances of portions, as determined by the Engineer, of the Work and pay retention to you based on these acceptances.
2. You or your Subcontractors shall return all monies withheld in retention from a Subcontractor within 30 Calendar Days after receiving payment for Work satisfactorily completed and accepted including incremental acceptances of portions of the Work by the City.
3. Federal law (49CFR26.29) requires that any delay or postponement of payment over 30 Calendar Days may take place only for good cause and with the City's prior written approval. Any violation of this provision by you or your Subcontractor shall subject you or your Subcontractor to the penalties, sanctions, and other remedies specified in §7108.5 of the Business and Professions Code.
4. These requirements shall not be construed to limit or impair any contractual, administrative, or judicial remedies otherwise available to you or your Subcontractor in the event of a dispute involving late payment or nonpayment by you, deficient subcontract performance, or noncompliance by a Subcontractor.

K. CERTIFICATION.

1. The City accepts certifications of DBE, DVBE, MBE, SDBE, SWBE, or WBE by any of the following certifying agencies:
 - a) Current certification by the State of California Department of Transportation (CALTRANS) as DBE, SDBE, or SWBE.
 - b) Current MBE, WBE, or DVBE certification from the California Public Utilities Commission.
 - c) DVBE certification is received from the State of California's Department of General Services, Office of Small and Minority Business.
 - d) Current certification by the City of Los Angeles as DBE, WBE, or MBE.
 - e) Subcontractors' valid proof of certification status (copies of MBE, WBE, DBE, or DVBE certifications) shall be submitted as required.

L. CONTRACT RECORDS AND REPORTS.

1. You shall maintain records of all subcontracts and invoices from your Subcontractors and Suppliers for work on this project. Records shall show

name, telephone number including area code, and business address of each Subcontractor, Supplier, and joint venture partner, and the total amount actually paid to each firm. Project relevant records, regardless of tier, may be periodically reviewed by the City.

2. You shall retain all records, books, papers, and documents pertinent to the Contract for a period of not less than 5 years after Notice of Completion and allow access to said records by the City's authorized representatives.
3. You shall submit the following reports using the City's web-based contract compliance (Prism® portal):
 - a. **Monthly Payment.** You shall submit Monthly Payment Reporting by the 10th day of the subsequent month. Incomplete and/or delinquent reporting may cause payment delays, non-payment of invoices, or both.
3. You shall submit the following reports using the web-based contract compliance software, LCP Tracker Online Payroll Reporting:
 - a. **Monthly Payment.** You and your Subcontractors and Suppliers shall submit Monthly Payment Reporting by the 5th day of the subsequent month. Incomplete and/or delinquent reporting may cause payment delays, non-payment of invoices, or both.
4. The records maintained under item 1, described above, shall be consolidated into a Final Summary Report, certified as correct by an authorized representative of the Contractor. The Final Summary Report shall include all subcontracting activities and be sent to the EOCP Program Manager and Office of Labor Standards & Enforcement (OLSE) Prevailing Wage Unit prior to Acceptance. Failure to comply may result in assessment of liquidated damages or withholding of retention. The City will review and verify 100% of subcontract participation reported in the Final Summary Report prior to approval and release of final retention to you. In the event your Subcontractors are owed money for completed Work, the City may authorize payment to subcontractor via a joint check from the withheld retention.

EQUAL OPPORTUNITY CONTRACTING PROGRAM (EOCP)

SECTION B - SLBE-ELBE SUBCONTRACTING REQUIREMENTS

THESE SPECIAL PROVISIONS SUPPLEMENT THE POLICIES AND REQUIREMENTS ESTABLISHED BY THE CITY OF SAN DIEGO EQUAL OPPORTUNITY CONTRACTING PROGRAM SPECIFIED IN THE CITY'S GENERAL EOCP REQUIREMENTS.

A. GENERAL.

1. It is the City's policy to encourage greater availability, capacity development, and contract participation by SLBE and ELBE firms in City contracts. This policy is, in part, intended to further the City's compelling interest to stimulate economic development through the support and empowerment of the local community, ensure that it is neither an active nor passive participant in marketplace discrimination, and promote equal opportunity for all segments of the contracting community.
2. The City is committed to maximizing subcontracting opportunities for all qualified and available firms.
3. This policy applies to City-funded construction contracts. Bidders shall be fully informed of this policy as set forth in these specifications. Mandatory or voluntary subcontracting percentages, Bid Discounts, and restricted competitions are specified in the Contract Documents.
4. You shall make subcontracting opportunities available to a broad base of qualified Subcontractors and shall achieve the minimum SLBE-ELBE Subcontractor participation identified for your project.
5. Failure to subcontract the specified minimum (mandatory) percentages of the Bid to qualified available SLBE-ELBE Subcontractors will cause a Bid to be rejected as non-responsive unless the Bidder has demonstrated compliance with the affirmative steps as specified in the City's document titled "Small Local Business (SLBE) Program, INSTRUCTIONS FOR BIDDERS COMPLETING THE GOOD FAITH EFFORT SUBMITTAL" and has submitted documentation showing that all required positive efforts were made prior to the Bid submittal due date. The required Good Faith Effort (GFE) documentation shall be submitted to the Contract Specialist. The instructions for completing the good faith effort submittal can be found on the City's website:
<https://www.sandiego.gov/sites/default/files/legacy/eoc/pdf/slbegeinst.pdf>
6. The current list of certified SLBE-ELBE firms and information for completing the GFE submittal can be found on the City's EOC Department website:
<http://www.sandiego.gov/eoc/programs/slbe>
7. These requirements may be waived, at the City's sole discretion, on projects deemed inappropriate for subcontracting participation.

B.

DEFINITIONS.

1. The following definitions shall be used in conjunction with these specifications:

- a) **Bid Discount** – Additional inducements or enhancements in the bidding process that are designed to increase the chances for the selection of SLBE firms in competition with other firms.
- b) **Commercially Useful Function** – An SLBE-ELBE performs a commercially useful function when it is responsible for the execution of the Work and is carrying out its responsibilities by actually performing, managing, and supervising the Work involved. To perform a commercially useful function, the SLBE-ELBE shall also be responsible, with respect to materials and supplies used on the Contract, for negotiating price, determining quantity and quality, ordering the material, and installing (where applicable) and paying for the material itself.

To determine whether an SLBE-ELBE is performing a commercially useful function, an evaluation will be performed of the amount of Work subcontracted, normal industry practices, whether the amount the SLBE-ELBE firm is to be paid under the contract is commensurate with the Work it is actually performing and the SLBE-ELBE credit claimed for its performance of the Work, and other relevant factors. Specifically, an SLBE-ELBE does not perform a commercially useful function if its role is limited to that of an extra participant in a transaction, contract, or project through which funds are passed in order to obtain the appearance of meaningful and useful SLBE-ELBE participation, when in similar transactions in which SLBE-ELBE firms do not participate, there is no such role performed.

- c) **Good Faith Efforts (GFE)** – Documentation of the Bidder's intent to comply with SLBE Program goals and procedures included in the City's SLBE Program, Instructions for Completing Good Faith Effort Submittal available from the City's EOCP website or the Contract Specialist.
- d) **Independently Owned, Managed, and Operated** – Ownership of a SLBE-ELBE firm shall be direct, independent, and by individuals only. Business firms that are owned by other businesses or by the principals or owners of other businesses that cannot themselves qualify under the SLBE-ELBE eligibility requirements shall not be eligible to participate in the Program. Moreover, the day-to-day management of the SLBE-ELBE firm shall be direct and independent of the influence of any other businesses that cannot themselves qualify under the SLBE-ELBE eligibility requirements.
- e) **Joint Venture** – An association of two or more persons or business entities that is formed for the single purpose of carrying out a single defined business enterprise for which purpose they combine their

capital, efforts, skills, knowledge, or property. Joint ventures shall be established by written agreement to qualify for this program.

- f) **Local Business Enterprise (“LBE”)** – A firm having a Principal Place of Business and a Significant Employment Presence in San Diego County, California that has been in operation for 12 consecutive months and a valid business tax certificate. This definition is subsumed within the definition of Small Local Business Enterprise.
- g) **Minor Construction Program** – A program developed for bidding exclusively among SLBE-ELBE Construction firms.
- h) **Principal Place of Business** – A location wherein a firm maintains a physical office and through which it obtains no less than 50% of its overall customers or sales dollars.
- i) **Protégé** – A firm that has been approved and is an active participant in the City’s Mentor-Protégé Program and that has signed the required program participation agreement and has been assigned a mentor.
- j) **Significant Employee Presence** – No less than 25% of a firm’s total number of employees are domiciled in San Diego County.

C. SUBCONTRACTOR PARTICIPATION.

1. For the purpose of satisfying subcontracting participation requirements, only 1st tier SLBE–ELBE Subcontractors will be recognized as participants in the Contract according to the following criteria:
 - a) For credit to be allowed toward a respective participation level, all listed SLBE-ELBE firms shall have been certified by the Bid due date.
 - b) The Subcontractor shall perform a commercially useful function for credit to be allowed toward subcontractor participation levels. The Subcontractor shall be required by you to be responsible for the execution of a distinct element of the Work and shall carry out its responsibility by actually performing and supervising its own workforce.
 - c) If the Bidder is seeking the recognition of materials, supplies, or both towards achieving any mandatory subcontracting participation level, the Bidder shall indicate on Form AA40 – Named Equipment/Material Supplier List with the Bid the following:
 - i. If the materials or supplies are obtained from a SLBE-ELBE manufacturer, the Bidder will receive 100% of the cost of the materials or supplies toward SLBE participation. For the purposes of counting SLBE-ELBE participation, a manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the Contract and of the general character described by the specifications.

- ii. If the materials or supplies are obtained from a SLBE-ELBE supplier, the Bidder will receive 60% of the cost of the materials or supplies toward SLBE participation. For the purposes of counting SLBE-ELBE participation a Supplier is a firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the Contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business. To be a supplier, the firm shall be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question. A person may be a supplier in such bulk items as petroleum products, steel, cement, gravel, stone, or asphalt without owning, operating, or maintaining a place of business if the person both owns and operates distribution equipment for the products. Any supplementing of the suppliers' own distribution equipment shall be by a long-term lease agreement and shall not be on an ad hoc or contract-by-contract basis.
 - iii. If the materials or supplies are obtained from a SLBE-ELBE, which is neither a manufacturer nor a supplier, the entire amount of fees or commissions charged for assistance in the procurement of the materials and supplies, fees or transportation charges for the delivery of materials or supplies required on a job site will be counted toward SLBE-ELBE participation, provided the fees are reasonable and not excessive as compared with fees customarily allowed for similar services. No portion of the cost of the materials and supplies themselves will be counted toward SLBE-ELBE participation.
- d) If the Bidder is seeking the recognition of SLBE-ELBE Trucking towards achieving any mandatory subcontracting participation level, the Bidder shall indicate it on Form AA35 – List of Subcontractors with the Bid. The following factors will be evaluated in determining the credit to be allowed toward the respective participation level:
- i. The SLBE-ELBE shall be responsible for the management and supervision of the entire trucking operation for which it is getting credit on a particular Contract and there shall not be a contrived arrangement for the purpose of counting SLBE-ELBE participation.
 - ii. The SLBE-ELBE shall itself own and operate at least 1 fully licensed, insured, and operational truck used on the Contract.

- iii. The SLBE-ELBE receives credit for the total value of the transportation services it provides on the Contract using trucks it owns, insures, and operates using drivers it employs.
- iv. The SLBE-ELBE may lease trucks from another SLBE-ELBE firm including an owner-operator who is certified as a SLBE-ELBE. The SLBE-ELBE who leases trucks from another SLBE-ELBE receives credit for the total value of the transportation services the lessee SLBE-ELBE provides on the contract.
- v. The SLBE-ELBE may also lease trucks from a non-SLBE-ELBE firm, including an owner-operator. The SLBE-ELBE who leases trucks from a non-SLBE-ELBE is entitled to credit for the total value of transportation services provided by non-SLBE-ELBE lessees not to exceed the value of transportation services provided by SLBE-ELBE owned trucks on the contract. Additional participation by non-SLBE-ELBE lessees receive credit only for the fee or commission it receives as a result of the lease arrangement.
- vi. A lease shall indicate that the SLBE-ELBE has exclusive use of and control over the truck. This does not preclude the leased truck from working for others during the term of the lease with the consent of the SLBE-ELBE so long as the lease gives the SLBE-ELBE absolute priority for use of the leased truck.

D. SLBE-ELBE SUBCONTRACTOR PARTICIPATION PERCENTAGES.

- 1. Contracts valued at \$1,500,000 and above will be considered Major Public Works Contracts and will include a mandatory Subcontractor participation requirement for SLBE-ELBE firms.
 - a) The Bidder shall achieve the mandatory Subcontractor participation requirement or demonstrate GFE.
 - b) The Bidders shall indicate the participation on Forms AA35 - List of Subcontractors and AA40 - Named Equipment/Material Supplier List as applicable regardless of the dollar value.
 - c) An SLBE-ELBE Bidder may count its own participation toward achieving the mandatory goal as long as the SLBE-ELBE Bidder performs 51% of the Contract Price.
- 2. Contracts Valued over \$1,000,000 and under \$1,500,000 will also be considered Major Public Works Contracts and will include the mandatory subcontractor participation requirements described above and the following:
 - a) 5% bid discount for SLBE-ELBE firms.
 - b) Non-certified Contractor will receive 5% bid discount if they achieve the specified mandatory Subcontracting participations.
 - c) Bid discounts shall not apply if the award will result in a total contract cost of \$50,000 in excess of the apparent lowest Bid.

- d) In the event of a tie bid between a SLBE-ELBE Bidder and a non-SLBE-ELBE Bidder, the SLBE-ELBE Bidder will be awarded the Contract.
 - e) In the event of a tie bid between a discounted Bid and a non-discounted Bid, the discounted Bid will be awarded the Contract.
- 3. Contracts valued over \$500,000 up to \$1,000,000 will be considered Minor Public Works Contracts and will be awarded through a competitive Bid process open only to City certified SLBE-ELBE firms. If there are no bidders or no responsible bidders, the Contract will be made available to all Bidders and will be subject to requirements listed in items 1 and 2 for Major Public Works Contracts above.
 - 4. Contracts valued at \$500,000 and below will also be considered Minor Public Works Contracts and will be awarded through a competitive bid process open only to City certified ELBEs unless there are less than 2 firms available at which it will be awarded through a competitive process open only to the City certified SLBE-ELBE firms. If there are no bidders or no responsible bidders, the Contract will be made available to all Bidders and subject to requirements listed in items 1 and 2 for Major Public Works Contracts above.

E. JOINT VENTURES.

- 1. The City may allow for Joint Venture bid discounts on some Contracts. Contracts that allow for Joint Venture bid discounts will be designated in Bid documents. A firm that is bidding or competing for City Contracts may partner with a certified SLBE or ELBE to compete for Contracts as a Joint Venture.
- 2. A Joint Venture shall be between two entities with the same discipline or license as required by the City. Joint ventures will receive bid discounts depending on the SLBE or ELBE percentage of participation. To be eligible for a discount, a Joint Venture Agreement shall be approved by the City at the time of Bid submittal. The maximum allowable discount shall be 5%. The parties shall agree to enter in the relationship for the life of the projects.
- 3. Joint Venture shall submit a Joint Venture Management Plan, a Joint Venture Agreement, or both at least 2 weeks prior to the Bid due date. Copies of the Joint Venture applications are available upon request to the Contract Specialist. Each agreement or management plan shall include the following:
 - a) Detailed explanation of the financial contribution for each partner.
 - b) List of personnel and equipment used by each partner.
 - c) Detailed breakdown of the responsibilities of each partner.
 - d) Explanation of how the profits and losses will be distributed.
 - e) Description of the bonding capacity of each partner.
 - f) Management or incentive fees available for any one of the partners (if any).

4. Each Joint Venture partner shall perform a Commercially Useful Function. An SLBE or ELBE that relies on the resources and personnel of a non-SLBE or ELBE firm will not be deemed to perform a Commercially Useful Function.
5. Each Joint Venture partner shall possess licenses appropriate for the discipline for which a proposal is being submitted. If a Joint Venture is bidding on a single trade project, at the time of bid submittal, each Joint Venture partner shall possess the requisite specialty license for that trade bid.
6. The SLBE or ELBE partner shall clearly define the portion of the Work to be performed. This Work shall be of the similar type of Work the SLBE or ELBE partner performs in the normal course of its business. The Joint Venture Participation Form shall specify the Bid items to be performed by each individual Joint Venture partner. Lump sum Joint Venture participation shall not be acceptable.
7. Responsibilities of the SLBE or ELBE Joint Venture Partner:
 - a) The SLBE or ELBE partner shall share in the control, management responsibilities, risks and profits of the Joint Venture in proportion with the level of participation in the project.
 - b) The SLBE or ELBE partner shall perform Work that is commensurate with its experience.
 - c) The SLBE or ELBE partner shall use its own employees and equipment to perform its portion of the Work.
 - d) The Joint Venture as a whole shall perform Bid items that equal or exceed 50% of the Contract Price, excluding the cost of manufactured items, in order to be eligible for a Joint Venture discount.

F. MAINTAINING PARTICIPATION LEVELS.

1. Credit and preference points are earned based on the level of participation proposed prior to the award of the Contract. Once the Project begins you shall achieve and maintain the SLBE-ELBE participation levels for which credit and preference points were earned. You shall maintain the SLBE-ELBE percentages indicated at the Award of Contract and throughout the Contract Time.
2. If the City modifies the original Scope of Work, you shall make reasonable efforts to maintain the SLBE-ELBE participation for which creditor preference points were earned. If participation levels will be reduced, approval shall be received from the City prior to making changes.
3. You shall notify and obtain written approval from the City in advance of any reduction in subcontract scope, termination, or substitution for a designated SLBE-ELBE Subcontractor. Failure to do so shall constitute a material breach of the Contract.
4. If you fail to maintain the SLBE-ELBE participation listed at the time the Contract is awarded and have not received prior approval from the City, the

City may declare you in default and will be considered grounds for debarment under Chapter 2, Article 2, Division 8, of the San Diego Municipal Code.

G. SUBCONTRACTING EFFORTS REVIEW AND EVALUATION.

1. Documentation of your subcontracting efforts will be reviewed by EOCP to verify that you made subcontracting opportunities available to a broad base of qualified Subcontractors, negotiated in good faith with interested Subcontractors, and did not reject any bid for unlawful discriminatory reasons. The EOCP review is based on the federal "Six Good Faith Efforts" model.
2. The GFEs are required methods to ensure that all ELBE and SLBE firms have had the opportunity to compete for the City's Public Works procurements. The Six Good Faith Efforts, also known as affirmative steps, attract and utilize ELBE and SLBE firms:
 - a) Ensure ELBE firms are made aware of contracting opportunities to the fullest extent practicable through outreach and recruitment activities.
 - b) Make information of forthcoming opportunities available to SLBE-ELBE firms and arrange time for Contracts and establish delivery schedules, where requirements permit, in a way that encourages and facilitates participation by SLBE-ELBE firms in the competitive process. This includes posting solicitations for Bids or proposals to SLBE-ELBE firms for a minimum of 10 Working Days before the Bid or Proposal due date.
 - c) Consider in the contracting process whether firms competing for large Contracts could subcontract with SLBE-ELBE firms.
 - d) Encourage contracting with a consortium of ELBE-SLBE firms when a Contract is too large for one of these firms to handle individually.
 - e) Use the services and assistance of the City's EOC Office and the SLBE-ELBE Directory.
 - f) If you award subcontracts, require your Subcontractors to take the steps listed above.

H. GOOD FAITH EFFORT DOCUMENTATION.

1. If the specified SLBE-ELBE Subcontractor participation percentages are not met, you shall submit information necessary to establish that adequate GFEs were taken to meet the Contract Subcontractor participation percentages. See the City's document titled "Small Local Business (SLBE) Program, INSTRUCTIONS FOR BIDDERS COMPLETING THE GOOD FAITH EFFORT SUBMITTAL." The instructions for completing the good faith effort submittal can be found on the City's website:

<https://www.sandiego.gov/sites/default/files/legacy/eoc/pdf/slbegfeinst.pdf>

I. SUBCONTRACTOR SUBSTITUTION.

1. Evidence of fraud or discrimination in the substitution of Subcontractors will result in sanctions including assessment of penalty fines, termination of Contract, or debarment. This section does not replace applicable California Public Contract Code.

J. FALSIFICATION OF SUB-AGREEMENT AND FRAUD.

1. Falsification or misrepresentation of a sub-agreement as to company name, Contract amount or actual Work performed by Subcontractors, or any falsification or fraud on the part your submission of documentation and forms pursuant to this program, will result in sanctions against you including assessment of penalty fines, termination of the Contract, or debarment. Instances of falsification or fraud which are indicative of an attempt by you to avoid subcontracting with certain categories of Subcontractors on the basis of race, gender, gender expression, gender identity, religion, national origin, ethnicity, sexual orientation, age, or disability shall be referred to the Equal Opportunity Contracting Program's Investigative Unit for possible violations of Article 2, Division 35 of the City Administrative Code, §§22.3501 et seq. (Nondiscrimination in Contracting).

K. RESOURCES.

1. The current list of certified SLBE-ELBE firms and information for completing the GFE submittal can be found on the City's EOC Department website:
<http://www.sandiego.gov/eoc/programs/slbe>
-

ATTACHMENT D
PREVAILING WAGE

PREVAILING WAGE

1. **PREVAILING WAGE RATES:** Pursuant to San Diego Municipal Code section 22.3019, construction, alteration, demolition, repair and maintenance work performed under this Contract is subject to State prevailing wage laws. For construction work performed under this Contract cumulatively exceeding \$25,000 and for alteration, demolition, repair and maintenance work performed under this Contract cumulatively exceeding \$15,000, the Contractor and its subcontractors shall comply with State prevailing wage laws including, but not limited to, the requirements listed below.
 - 1.1. **Compliance with Prevailing Wage Requirements.** Pursuant to sections 1720 through 1861 of the California Labor Code, the Contractor and its subcontractors shall ensure that all workers who perform work under this Contract are paid not less than the prevailing rate of per diem wages as determined by the Director of the California Department of Industrial Relations (DIR). This includes work performed during the design and preconstruction phases of construction including, but not limited to, inspection and land surveying work.
 - 1.1.1. Copies of such prevailing rate of per diem wages are on file at the City and are available for inspection to any interested party on request. Copies of the prevailing rate of per diem wages also may be found at <http://www.dir.ca.gov/OPRL/DPreWageDetermination.htm>. Contractor and its subcontractors shall post a copy of the prevailing rate of per diem wages determination at each job site and shall make them available to any interested party upon request.
 - 1.1.2. The wage rates determined by the DIR refer to expiration dates. If the published wage rate does not refer to a predetermined wage rate to be paid after the expiration date, then the published rate of wage shall be in effect for the life of this Contract. If the published wage rate refers to a predetermined wage rate to become effective upon expiration of the published wage rate and the predetermined wage rate is on file with the DIR, such predetermined wage rate shall become effective on the date following the expiration date and shall apply to this Contract in the same manner as if it had been published in said publication. If the predetermined wage rate refers to one or more additional expiration dates with additional predetermined wage rates, which expiration dates occur during the life of this Contract, each successive predetermined wage rate shall apply to this Contract on the date following the expiration date of the previous wage rate. If the last of such predetermined wage rates expires during the life of this Contract, such wage rate shall apply to the balance of the Contract.
 - 1.2. **Penalties for Violations.** Contractor and its subcontractors shall comply with California Labor Code section 1775 in the event a worker is paid less than the prevailing wage rate for the work or craft in which the worker is employed. This shall be in addition to any other applicable penalties allowed under Labor Code sections 1720 – 1861.

- 1.3. Payroll Records.** Contractor and its subcontractors shall comply with California Labor Code section 1776, which generally requires keeping accurate payroll records, verifying and certifying payroll records, and making them available for inspection. Contractor shall require its subcontractors to also comply with section 1776. Contractor and its subcontractors shall submit weekly certified payroll records online via the City's web-based Labor Compliance Program. Contractor is responsible for ensuring its subcontractors submit certified payroll records to the City.
- 1.3.1.** Contractor and their subcontractors shall also furnish records specified in Labor Code section 1776 directly to the Labor Commissioner in the manner required by Labor Code section 1771.4.
- 1.4. Apprentices.** Contractor and its subcontractors shall comply with California Labor Code sections 1777.5, 1777.6 and 1777.7 concerning the employment and wages of apprentices. Contractor is held responsible for the compliance of their subcontractors with sections 1777.5, 1777.6 and 1777.7.
- 1.5. Working Hours.** Contractor and their subcontractors shall comply with California Labor Code sections 1810 through 1815, including but not limited to: (i) restrict working hours on public works contracts to eight hours a day and forty hours a week, unless all hours worked in excess of 8 hours per day are compensated at not less than 1½ times the basic rate of pay; and (ii) specify penalties to be imposed on contractors and subcontractors of \$25 per worker per day for each day the worker works more than 8 hours per day and 40 hours per week in violation of California Labor Code sections 1810 through 1815.
- 1.6. Required Provisions for Subcontracts.** Contractor shall include at a minimum a copy of the following provisions in any contract they enter into with a subcontractor: California Labor Code sections 1771, 1771.1, 1775, 1776, 1777.5, 1810, 1813, 1815, 1860 and 1861.
- 1.7. Labor Code Section 1861 Certification.** Contractor in accordance with California Labor Code section 3700 is required to secure the payment of compensation of its employees and by signing this Contract, Contractor certifies that "I am aware of the provisions of Section 3700 of the California Labor Code which require every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the work of this Contract."
- 1.8. Labor Compliance Program.** The City has its own Labor Compliance Program authorized in August 2011 by the DIR. The City will withhold contract payments when payroll records are delinquent or deemed inadequate by the City or other governmental entity, or it has been established after an investigation by the City or other governmental entity that underpayment(s) have occurred. For questions or assistance, please contact the City of San Diego's Prevailing Wage Unit at PWDPprevailingWage@sandiego.gov.

- 1.9. Contractor and Subcontractor Registration Requirements.** This project is subject to compliance monitoring and enforcement by the DIR. A contractor or subcontractor shall not be qualified to bid on, be listed in a bid or proposal, subject to the requirements of section 4104 of the Public Contract Code, or engage in the performance of any contract for public work, unless currently registered and qualified to perform public work pursuant to Labor Code section 1725.5. It is not a violation of this section for an unregistered contractor to submit a bid that is authorized by Section 7029.1 of the Business and Professions code or by Section 10164 or 20103.5 of the Public Contract Code, provided the contractor is registered to perform public work pursuant to Section 1725.5 at the time the contract is awarded.
- 1.9.1.** A Contractor's inadvertent error in listing a subcontractor who is not registered pursuant to Labor Code section 1725.5 in response to a solicitation shall not be grounds for filing a bid protest or grounds for considering the bid non-responsive provided that any of the following apply: (1) the subcontractor is registered prior to bid opening; (2) within twenty-four hours after the bid opening, the subcontractor is registered and has paid the penalty registration fee specified in Labor Code section 1725.5; or (3) the subcontractor is replaced by another registered subcontractor pursuant to Public Contract Code section 4107.
- 1.9.2.** By submitting a bid or proposal to the City, Contractor is certifying that he or she has verified that all subcontractors used on this public work project are registered with the DIR in compliance with Labor Code sections 1771.1 and 1725.5, and Contractor shall provide proof of registration for themselves and all listed subcontractors to the City at the time of bid or proposal due date or upon request.
- 1.10. Stop Order.** For Contractor or its subcontractors engaging in the performance of any public work contract without having been registered in violation of Labor Code sections 1725.5 or 1771.1, the Labor Commissioner shall issue and serve a stop order prohibiting the use of the unregistered contractors or unregistered subcontractor(s) on ALL public works until the unregistered contractor or unregistered subcontractor(s) is registered. Failure to observe a stop order is a misdemeanor.
- 1.11. List of all Subcontractors.** The Contractor shall provide the list of subcontractors (regardless of tier), along with their DIR registration numbers, utilized on this Contract prior to any work being performed; and the Contractor shall provide a complete list of all subcontractors with each invoice. Additionally, Contractor shall provide the City with a complete list of all subcontractors (regardless of tier) utilized on this contract within ten working days of the completion of the contract, along with their DIR registration numbers. The City shall withhold final payment to Construction Management Professional until at least thirty (30) days after this information is provided to the City.

1.12. Exemptions for Small Projects. There are limited exemptions for installation, alteration, demolition, or repair work done on projects of \$25,000 or less. The Contractor shall still comply with Labor Code sections 1720 et. seq. The only recognized exemptions are listed below:

1.12.1. Registration. The Contractor will not be required to register with the DIR for small projects. (Labor Code section 1771.1).

1.12.2. Certified Payroll Records. The records required in Labor Code section 1776 shall be required to be kept and submitted to the City of San Diego, but will not be required to be submitted online with the DIR directly. The Contractor will need to keep those records for at least three years following the completion of the Contract. (Labor Code section 1771.4).

1.12.3. List of all Subcontractors. The Contractor shall not be required to hire only registered subcontractors and is exempt from submitting the list of all subcontractors that is required in section 1.11. above. (Labor code section 1773.3).

ATTACHMENT E
SUPPLEMENTARY SPECIAL PROVISIONS

SUPPLEMENTARY SPECIAL PROVISIONS

The following Supplementary Special Provisions (SSP) modifies the following documents:

1. The **2021 Edition** of the Standard Specifications for Public Works Construction (The "GREENBOOK").
2. The **2021 Edition** of the City of San Diego Standard Specifications for Public Works Construction (The "WHITEBOOK"), including the following:
 - a) General Provisions (A) for all Construction Contracts.

SECTION 1 – GENERAL, TERMS, DEFINITIONS, ABBREVIATIONS, UNITS OF MEASURE, AND SYMBOLS

1-2 TERMS AND DEFINITIONS. To the "WHITEBOOK":

To item 47, "Holiday", ADD the following:

Holiday	Observed On
Juneteenth	June 19

To item 55, "Normal Working Hours", DELETE in its entirety and SUBSTITUTE with the following:

Normal Working Hours: Normal Working Hours shall be **8:30 AM to 3:30 PM, Monday through Friday**, inclusive. Saturdays, Sundays, and City Holidays are excluded. Unless otherwise specified on the Traffic Control Permits.

Night Working Hours: Night Working Hours shall be **9:00 PM to 5:00 AM, Sunday through Thursday inclusive** Saturdays, Sundays, and City Holidays are excluded on the Traffic Control Permits. Night Work shall be included in the contract price.

ADD the following:

111. **Surface Seal** - a preventative maintenance application which may include one or more of the following: fog seal, slurry seal, microsurfacing, chip seal, scrub seal, or cape seal.

SECTION 2 – SCOPE OF THE WORK

2-7 CHANGES INITIATED BY THE AGENCY.

2-7.1 **General.** To the "WHITEBOOK", DELETE in its entirety and SUBSTITUTE with the following:

1. The Engineer may substitute specific sites for asphalt overlay or surface seal due to utility or construction conflicts or urgent community needs. The Engineer will adjust the location provided in the Contract Documents as needed.

2. The location list provided in the Contract Documents will be adjusted by the City as needed to match the Bid Quantities at no additional cost to the City.
3. The Bid quantities are for estimating purposes only and will vary due to continued deterioration of the streets, such as streets quantified as having no tons of AC required, may in fact need AC repair (see 301-1.6).

SECTION 3 – CONTROL OF THE WORK

3-2 SELF-PERFORMANCE. To the “GREENBOOK”, DELETE in its entirety and SUBSTITUTE with the following:

1. You shall perform, with your own organization, Contract Work amounting to at least **30%** of the Base Bid.

3-7.6.1 Use of Computer Aided Drafting and Design. To the “WHITEBOOK”, Item 1, DELETE in its entirety and SUBSTITUTE with the following:

1. Use Bentley Connect ORD Version 10.12 format with the ability to convert to AutoCAD for the preparation of Plans and As-Built drawings in accordance with the City’s CADD Standards.

3-8.7 Contractor’s Quality Control Plan (QCP). To the “WHITEBOOK”, item 1, DELETE in its entirety and SUBSTITUTE with the following:

1. You shall establish, implement, and maintain an effective Quality Control Plan (QCP) to perform quality control inspection and testing for all items of paving, slurry seal, scrub seal, and/or cape seal work required by the Contract Documents, including those performed by subcontractors and material suppliers.

To the “WHITEBOOK”, ADD the following:

7. The establishment and implementation of a Quality Control Plan (QCP), as defined in the standard specifications, shall be required for this Contract. See example in **Appendix G - Contractor’s Daily Quality Control Inspection Report.**
8. The Contractor’s Quality Control Plan shall be subject to approval by the Engineer.
9. Additions and Alterations to the Contractor’s Quality Control Plan may be requested at the direction of the Engineer. The request for Additions and Alterations to the Contractor’s Quality Control Plan will be made to the Contractor in writing by the Engineer. Submission of Additions and Alterations to the Contractor’s Quality Control Plan Shall be submitted within 5 business days from the date the requests for Additions and Alterations is made by the Engineer.
10. Additions and Alterations to the Contractor’s Quality Control Plan shall be subject to approval by the Engineer.

11. The Contractor shall ensure that all items of Work, regardless of their inclusion in or omission from the Contractor's Quality Control Plan, conform to the Contract Document.
12. Payments for the Contractor's Quality Control Plan and all testing associated with it shall be included in the Contract Price.
13. No additional Payment shall be made for additions and Alterations to the Contractor's Quality Control Plan.

3-12.1 General. To the "WHITEBOOK", item 2, DELETE in its entirety and SUBSTITUTE with the following:

2. You shall provide a PM-10 certified self-loading motorized street sweeper equipped with a functional water spray system for this project.

To the "WHITEBOOK", ADD the following:

3. You shall sweep all paved areas within the Work site and all paved haul routes as specified below:
 - a) Prior to Surface Seal Application
 - b) As directed by the Engineer

If these requirements would require you to sweep on a Holiday or Weekend, then you shall sweep the next available Working Day prior to that Holiday or Weekend.

3-13.1.2 Walk-through and Punchlist Procedure. To the "WHITEBOOK", ADD the following:

10. When a comment from the Punchlist is disputed, you shall submit in writing justification for the dispute within 15 days of receiving Punchlist.

3-13.3 Warranty. To the "WHITEBOOK", ADD the following:

9. Should any area of the Surface Seal prove defective or fail to perform properly as defined herein, within one (1) year after the date on which all construction operations are completed, the Contractor will be required to perform repair work at its own expense to the satisfaction of the Engineer.

The following performance and repair criteria will apply:

Any single area of surface seal greater than four (4) square feet that fails to meet the performance criteria due to raveling, bleeding or flushing, or delaminating as defined herein will be considered defective and shall be repaired at the Contractor's expense to the satisfaction of the Engineer.

- a) Raveling – the wearing away (loss of aggregate) of the surface seal surface, including areas affected by longitudinal and transverse streaking.
- b) Bleeding or Flushing – the upward movement of asphalt that creates a film of asphaltic emulsion on the surface of the finished road surface.
- c) Delaminating – the loss of the bond between the surface seal and the existing asphalt concrete pavement surface.

SECTION 4 - CONTROL OF MATERIALS

4-6 TRADE NAMES. To the "WHITEBOOK", ADD the following:

11. You shall submit your list of proposed substitutions for an "equal" item **no later than 5 Working Days after the issuance of the Notice of Intent to Award** and on the City's Product Submittal Form available at:

<https://www.sandiego.gov/ecp/edocref/>

SECTION 5 - LEGAL RELATIONS AND RESPONSIBILITIES

5-4 INSURANCE. To the "GREENBOOK", DELETE in its entirety and SUBSTITUTE with the following:

1. The insurance provisions herein shall not be construed to limit your indemnity and defense duties set forth in the Contract.

5-4.1 Policies and Procedures.

1. You shall procure the insurance described below, at your sole cost and expense, to provide coverage against claims for loss including injuries to persons or damage to property, which may arise out of or in connection with the performance of the Work by you, your agents, representatives, officers, employees or Subcontractors.
2. Insurance coverage for property damage resulting from your operations is on a replacement cost valuation. The market value will not be accepted.
3. You shall maintain this insurance as required by this Contract and at all times thereafter when you are correcting, removing, or replacing Work in accordance with this Contract. Your duties under the Contract, including your indemnity obligations, are not limited to the insurance coverage required by this Contract.
4. If you maintain broader coverage or higher limits than the minimums shown below, City requires and shall be entitled to the broader coverage or the higher limits maintained by you. Any available insurance proceeds in excess of the specified minimum limits of insurance and coverage shall be available to City.
5. Your payment for insurance shall be included in the Contract Price you bid. You are not entitled to any additional payment from the City to cover your insurance, unless the City specifically agrees to payment in writing. Do not begin any Work under this Contract or allow any Subcontractors to begin work, until you have provided, and the City has approved, all required insurance.
6. Policies of insurance shall provide that the City is entitled to 30 days advance written notice of cancellation or non-renewal of the policy or 10 days advance written notice for cancellation due to non-payment of premium. Maintenance of specified insurance coverage is a material element of the Contract. Your failure to maintain or renew coverage and to provide evidence of renewal during the term of the Contract may be treated by the City as a material breach of the Contract.

5-4.2 Types of Insurance.

5-4.2.1 General Liability Insurance.

1. Commercial General Liability Insurance shall be written on the current version of the ISO Occurrence form CG 00 01 07 98 or an equivalent form providing coverage at least as broad.
2. The policy shall cover liability arising from premises and operations, XCU (explosions, underground, and collapse), independent contractors, products/completed operations, personal injury and advertising injury, bodily injury, property damage, and liability assumed under an insured's contract (including the tort liability of another assumed in a business contract).
3. There shall be no endorsement or modification limiting the scope of coverage for either "insured vs. insured" claims or contractual liability. You shall maintain the same or equivalent insurance for at least 10 years following completion of the Work.
4. All costs of defense shall be outside the policy limits. Policy coverage shall be in liability limits of not less than the following:

<u>General Annual Aggregate Limit</u>	<u>Limits of Liability</u>
Other than Products/Completed Operations	\$10,000,000
Products/Completed Operations Aggregate Limit	\$10,000,000
Personal Injury Limit	\$5,000,000
Each Occurrence	\$5,000,000

5-4.2.2 Commercial Automobile Liability Insurance.

1. You shall provide a policy or policies of Commercial Automobile Liability Insurance written on the current version of the ISO form CA 00 01 12 90 or later version or equivalent form providing coverage at least as broad in the amount of \$1,000,000 combined single limit per accident, covering bodily injury and property damage for owned, non-owned, and hired automobiles ("Any Auto").
2. All costs of defense shall be outside the limits of the policy.

5-4.2.3 Workers' Compensation Insurance and Employers Liability Insurance.

1. In accordance with the provisions of California Labor Code section 3700, you shall provide, at your expense, Workers' Compensation Insurance and Employers Liability Insurance to protect you against all claims under applicable state workers' compensation laws. The City, its elected officials, and employees will not be responsible for any claims in law or equity occasioned by your failure to comply with this requirement.
2. Statutory Limits shall be provided for Workers' Compensation Insurance as required by the state of California, and Employer's Liability Insurance with limits of no less than \$1,000,000 per accident for bodily injury or disease.

3. By signing and returning the Contract, you certify that you are aware of the provisions of California's Workers' Compensation laws, including Labor Code section 3700, which requires every employer to be insured against liability for workers' compensation or to undertake self-insurance, and that you will comply with these provisions before commencing the Work.

5-4.3 Rating Requirements. Except for the State Compensation Insurance Fund, all insurance required by this Contract shall be carried only by responsible insurance companies with a rating of, or equivalent to, at least "A-, VI" by A.M. Best Company, that are authorized by the California Insurance Commissioner to do business in the state of California, and that have been approved by the City.

5-4.3.1 Non-Admitted Carriers. The City will accept insurance provided by non-admitted, "surplus lines" carriers only if the carrier is authorized to do business in the state of California and is included on the List of Approved Surplus Lines Insurers (LASLI list).

All policies of insurance carried by non-admitted carriers shall be subject to all of the requirements for policies of insurance provided by admitted carriers described in this Contract.

5-4.4 Evidence of Insurance. You shall furnish the City with original Certificates of Insurance, including all required amendatory endorsements (or copies of the applicable policy language effecting coverage required by this clause), prior to your commencement of Work under this Contract. In addition, The City reserves the right to require complete, certified copies of all required insurance policies, including endorsements, required by these specifications, at any time.

5-4.5 Policy Endorsements.

5-4.5.1 Commercial General Liability Insurance.

5-4.5.1.1 Additional Insured. To the fullest extent permitted by law and consistent with the limiting provisions set forth at California Civil Code section 2782, California Insurance Code section 11580.04, and any applicable successor statutes limiting indemnification of public agencies that bind the City, the policy or policies shall be endorsed to include as an Additional Insured the City and its respective elected officials, officers, employees, agents, and representatives, with respect to liability arising out of:

1. Ongoing operations performed by you or on your behalf,
2. your products,
3. your work, e.g., your completed operations performed by you on your behalf, or
4. premises owned, leased, controlled, or used by you.

5-4.5.1.2 Primary and Non-Contributory Coverage. The policy shall be endorsed to provide that the coverage with respect to operations, including the completed operations, if appropriate, of the Named Insured is primary to any insurance or self-insurance of the City and its elected officials, officers, employees, agents and representatives. Further, it shall provide that any insurance maintained by the City and its elected officials, officers, employees, agents and representatives shall be in excess of your insurance and shall not contribute to it.

- 5-4.5.1.3 Project General Aggregate Limit.** The policy or policies shall be endorsed to provide a Designated Construction Project General Aggregate Limit that will apply only to the Work. Only claims payments which arise from the Work shall reduce the Designated Construction Project General Aggregate Limit. The Designated Construction Project General Aggregate Limit shall be in addition to the aggregate limit provided for the products-completed operations hazard.
- 5-4.5.2 Workers' Compensation Insurance and Employers Liability Insurance.**
- 5-4.5.2.1 Waiver of Subrogation.** The policy or policies shall be endorsed to provide that the insurer will waive all rights of subrogation against the City and its respective elected officials, officers, employees, agents, and representatives for losses paid under the terms of the policy or policies and which arise from Work performed by the Named Insured for the City.
- 5-4.6 Deductibles and Self-Insured Retentions.** You shall disclose deductibles and self-insured retentions to the City at the time the evidence of insurance is provided. The City may require you to purchase coverage with a lower retention or provide proof of ability to pay losses and related investigations, claim administration, and defense expenses within the retention. The policy language shall provide, or be endorsed to provide, that the self-insured retention may be satisfied by either the named insured or City.
- 5-4.7 Reservation of Rights.** The City reserves the right, from time to time, to review your insurance coverage, limits, deductibles, and self-insured retentions to determine if they are acceptable to the City. The City will reimburse you, without overhead, profit, or any other markup, for the cost of additional premium for any coverage requested by the Engineer, but not required by this Contract.
- 5-4.8 Notice of Changes to Insurance.** You shall notify the City, in writing, 30 days prior to any material change to the policies of insurance provided under this Contract. This written notice is in addition to the requirements of paragraph 6 of Section 5-4.1.
- 5-4.9 Excess Insurance.** Policies providing excess coverage shall follow the form of the primary policy or policies, including all endorsements.
- 5-10 COMMUNITY OUTREACH.**
- 5-10.2.1 Public Notice by Contractor.** To the "WHITEBOOK", items 2 and 3, DELETE in their entirety and SUBSTITUTE the following:
1. No less than 5 Working Days in advance of Project construction activities, you shall notify all critical facilities, businesses, institutions, property owners, residents, or other impacted stakeholders with a minimum 300-foot radius of the project. Verbal and written notifications shall be sent to critical facilities (including but not limited to police stations, fire stations, hospitals, and schools). A copy of written notifications sent to any critical facility shall be sent to the Resident Engineer. You shall keep records of the people contacted along with the dates of notifications and shall provide the record to the Engineer upon request.

2. Furnish and distribute public notices in the form of door hangers using the City's format to all occupants and/or property owners along streets:
 - a) You shall distribute an Advanced Construction Notice as shown in **Appendix J – Advanced Construction Notice** and **Appendix N - Cape Seal Flyer** where where work is to be performed at least 5 Working Days before starting construction or survey activities or impacting the community as approved by the Resident Engineer.
 - b) You shall distribute notices in the form of door hangers, which outlines the anticipated dates of slurry seal as shown in **Appendix H – Sample of Public Notice (SB1 FUNDED ONLY)**, at least 72 hours in advance of the Scheduled resurfacing as approved by the Engineer.

To the "WHITEBOOK", ADD the following:

9. Door hangers shall include the funding source if project is funded in part by State Gas Tax Revenue (SB1). See **Appendix H – Sample of Public Notice (SB1 FUNDED ONLY)**.
10. You shall coordinate with schools within a minimum 300-foot radius of the Project construction activities. You shall notify school staff of any planned street closures and/or detours that may impact regular school operations (pick-ups, drops offs, events, etc.)

No work shall be scheduled in the vicinity of a school during the first week of school or graduation days.
11. You shall coordinate with apartment complexes and/or condominiums within a minimum 300-foot radius of the project construction activities. You shall notify property management of any planned street closure and/or detours that may impact residents.

SECTION 6 – PROSECUTION AND PROGRESS OF THE WORK

6-1.1 Construction Schedule. To the "WHITEBOOK", ADD the following:

3. Refer to the Sample City Invoice in **Appendix D – Sample City Invoice** and use the format shown.

6-1.3 Work Outside Normal Working Hours. To the "WHITEBOOK", ADD the following:

4. The following locations may require Night Work:
 - a) Voltaire St.
 - b) Vista Sorrento Pkwy.
 - c) Sunset Cliffs Blvd.

- d) Soledad Mountain Rd.
- e) Scott St.
- f) Rosecrans St.
- g) Olivetas Ave.
- h) Mango Dr.
- i) La Jolla Mesa Dr.
- j) La Jolla Blvd.
- k) Girard Ave.
- l) Garrison St.
- m) Garnet Ave.
- n) Chatsworth Blvd.
- o) Carmel Knolls Dr.
- p) Carmel Country Rd.
- q) Canon St.
- r) Cable St.

6-1.3.1 Payment. To the "WHITEBOOK", ADD the following:

- 2. The payment for any work outside normal working hours, including weekend work and night work, shall be done at no additional cost to the City.
- 3. Payment for any work outside normal working hours, including weekend work and night work, shall be included in the Contract Price.

6-1.6 Pre-construction Meeting. To the "WHITEBOOK", DELETE in its entirety and SUBSTITUTE with the following:

- 1. Within 10 Working Days from the LNTP the Engineer shall schedule a mandatory Pre-construction meeting with you. The agenda shall include items such as NTP, design services and submittal and review process, critical elements of the Work schedule, submittal schedule, cost breakdown of major lump sum items, payment requests and processing, environmental and community concerns, coordination with the involved utility firms, the level of record project documents required, and emergency telephone numbers for all representatives involved in the course of construction.

6-6.1.1 Environmental Document.

1. The City of San Diego has prepared a **Notice of Exemption** for **Fiscal Year 2025 Road Maintenance and Rehabilitation Account (RMRA) Funds Proposed Project List and Approval of Six Slurry Seal Groups 2521, 2522, 2523, 2524, 2525, and 2526 to be Funded by RMRA Funds** for **Slurry Seal Group 2524** Project No. 21005580, as referenced in the Contract Appendix. You shall comply with all requirements of the **Notice of Exemption** as set forth in **Appendix A**.
2. Compliance with the City's environmental document shall be included in the Contract Price unless separate bid items have been provided.

6-9 LIQUIDATED DAMAGES. To the "WHITEBOOK", item 2, DELETE in its entirety and SUBSTITUTE with the following:

2. The execution of the Contract shall constitute agreement between you and the City that the liquidated damage amount described in the table below is the value of the damage caused by your failure to complete the Work within the allotted time. Such sum shall not be construed as a penalty and may be deducted from your payments if such delay occurs.

Contract Value	Liquidated Damages Daily Amount
Less than \$200,001	\$1,000
\$200,001 to \$500,000	\$1,500
\$500,001 to \$1,000,000	\$2,000
\$1,000,001 to \$2,000,000	\$2,500
\$2,000,001 to \$5,000,000	\$3,000
\$5,000,001 to \$10,000,000	\$5,500
\$10,000,001 to \$20,000,000	\$6,500
Greater Than \$20,000,000	\$7,000

SECTION 7 – MEASUREMENT AND PAYMENT

7-2.1 **Schedule of Values (SOV).** To the "WHITEBOOK", item 1, DELETE in its entirety and SUBSTITUTE with the following:

1. You shall submit an SOV for the lump sum Bid Items below to the Engineer for review and approval at the Pre-construction meeting:
 - a) **Remove, Replace & Install Traffic Striping, Markers, Markings & Devices.**
 - b) **Traffic Control and Working Drawings.**

7-3.5.1 **General.** To the "WHITEBOOK", DELETE in its entirety and SUBSTITUTE with the following:

1. Unit Bid Prices shall not be subject to adjustment regardless of quantity used for the following Bid Items:
 - a) **"Asphalt Pavement Repair"**
 - b) **"Crack Seal"**
 - c) **"Crushed Miscellaneous Base"**
 - d) **"Asphalt Concrete with Pavement Fabric Material"**
 - e) **"Raise Appurtenance to Grade (Water, Sewer)"**
 - f) **"Adjust Existing Manhole Frame and Cover to Grade"**
 - g) **"Adjust Existing Survey Monument to Grade"**
 - h) **"Reconstruct Survey Monument Box"**
 - i) **"Traffic Detector Loop Replacement or Conduit Stub Installed"**
 - j) **"Removal of Humps, Lumps, and Pavement Irregularities"**
 - k) **"Edge Grind AC Pavement (<2-inch)"**

7-3.8 **Eliminated Items.** To the "GREENBOOK", DELETE in its entirety and SUBSTITUTE with the following:

1. Should any Bid items, except Bid Items listed in item 2 of this section, be eliminated in its entirety, payment will be made to the Contractor for its actual costs incurred in connection with the eliminated item prior to notification in writing from the Engineer so stating its elimination.
2. If eliminated in their entirety, no payment will be made for actual costs incurred in connection with the following eliminated items:
 - a) **"Raise Appurtenance to Grade (Water, Sewer)"**
 - b) **"Adjust Existing Manhole Frame and Cover to Grade"**
 - c) **"Survey Monument Lids"**
 - d) **"Reconstruct Survey Monument Box"**
 - e) **"Adjust Existing Survey Monument to Grade"**

- f) **“Crushed Miscellaneous Base”**
- g) **“Traffic Detector Loop Replacement or Conduit Stub Installed”**
- h) **“Detector Lead In Cable”**
- i) **“Removal of Humps, Lumps, and Pavement Irregularities”**
- j) **“Asphalt Concrete with Pavement Fabric Material”**
- k) **“Edge Grind AC Pavement (<2-inch)”**
- l) **“Crack Seal”**

3. If material conforming to the Plans and Specifications is ordered for use in the eliminated items prior to the date of notification of elimination by the Engineer, and if the order for that material cannot be canceled, payment will be made to you for the actual cost of the material. In this case, the material shall become the property of the City and payment will be made to you for actual costs for any further handling. If the material is returnable, the material shall be returned, and payment will be made to you for actual cost of charges made by the supplier for handling and returning the material.

7-3.9

Field Orders. To the “WHITEBOOK”, DELETE in its entirety and SUBSTITUTE with the following:

1. If the cumulative total of Field Order items of Work does not exceed the **“Field Orders”** Bid Item, the City shall pay those Field Orders as shown below:

**TABLE 7-3.9
FIELD ORDER LIMITS**

Contract Price	Maximum Each Field Order Work Amount
Less than \$1,000,001	\$10,000
\$1,000,001 to \$5,000,000	\$20,000
\$5,000,001 to \$10,000,000	\$25,000
\$10,000,001 to \$30,000,000	\$40,000
Greater than \$30,000,000	\$70,000

7-3.11 Compensation Adjustments for Price Index Fluctuations. To the "WHITEBOOK", item 2, DELETE in its entirety and SUBSTITUTE with the following:

2. The compensation for paving asphalt shall be increased or decreased for paving asphalt price fluctuations in accordance with 9-1.07 "Payment Adjustments for Price Index Fluctuations" in the Caltrans Standard Specifications.

To the "WHITEBOOK", ADD the following:

5. This Contract **is** subject to the provisions of the "WHITEBOOK" for Compensation Adjustments for Price Index Fluctuations for paving asphalt.

SECTION 200 - ROCK MATERIALS

ADD:

200-1.2.2.4 Screenings for Polymer Modified Rejuvenating Emulsion (PMRE). Screenings for use as cover aggregate over polymer modified rejuvenating emulsion for scrub seal applications shall conform to the gradation requirements shown in Table 200-1.2.2.4.

Table 200-1.2.2.4

Sieve Size	Percentage Passing Sieve		
	Medium 3/8" x No. 6	Medium Fine 5/16" x No.8	Fine 1/4" x No.10
3/4"	-	-	-
1/2"	100	-	-
3/8"	85-100	100	100
No. 4	0-15	0-50	60-85
No. 8	0-5	0-15	0-25
No. 16	-	0-5	0-5
No. 30	-	0-3	0-3
No. 200	0-2	0-2	0-2

The ratio of length to width of screenings shall not be greater than 2:1

SECTION 203 - BITUMINOUS MATERIALS

ADD:

203-3.4.7 Polymer Modified Rejuvenating Emulsion (PMRE).

203-3.4.7.1 General. PMRE shall be cationic and shall consist of asphalt, latex polymer modifier and a rejuvenating agent.

PMRE shall conform to the requirements shown in Table 203-3.4.7.

Table 203-3.4.7

Test on Emulsion	Test Method	Specification
Viscosity @ 122°F (SFS)	AASHTO T59	50-350
pH	ASTM E70	2.5-5.0
Sieve, w%, max.	AASHTO D244	0.1
Residue, w%, min.	AASHTO T59	65
Oil distillate, w% (177°C)	ASTM D244	0.5
Storage Stability, 24 Hr, 25°C, max	AASHTO T59	1.0
Test on Residue Recovered by Evaporation (AASHTO T59)		
Viscosity @ 140°F, (P), max.	ASTM D2171 (c,d)	5000
Penetration @ 39.2°F, min.	ASTM D5	40 to 70
Elastic Recovery %, min.	AASHTO T59, T301(a,b)	60

203-3.4.7.2 Rejuvenating Agent. The rejuvenating agent shall conform to Table 203-3.4.7.2.

Table 203-3.4.7.2

Test on Rejuvenating Agent	Test Method	Requirements
Viscosity, 140°F, CST	ASTM D2170	50-175
Flash Point, °F, COC	ASTM D92	380 Min
Test on Rejuvenating Agent	Test Method	Requirements
Saturate, % by weight	ASTM D2007	30 Max
Asphaltenes, % by weight	ASTM D2007	1.0 Max

Test on Rejuvenating Agent RTFOT Residue		
Weight Change, %	ASTM D2872	6.5
Viscosity Ratio	ASTM D2170	3.0

- a. Exception to AASHTO T59: Bring the temperature on the lower thermometer slowly to 350° F plus or minus 10°F. Maintain at this temperature for 20 minutes. Complete total distillation in 60 plus or minus 5 minutes from the first application of heat.
- b. Elastic Recovery @ 10°C (50° F): Hourglass sides, pull 20 cm, hold 5 minutes then cut, let sit for 1 hour.
- c. If it is suspected that a sample may contain solid material, strain the melted sample into the container through a No. 500 (300-µm) sieve conforming to Specification E 11."
- d. Use an AI-200 glass capillary tube to run the test. If the viscosity is 4000 or above, use an AI 400 instead.

203-3.4.7.3 Certificate of Compliance. A Certificate of Compliance conforming to SECTION 4-5 CERTIFICATE OF COMPLIANCE of the GREENBOOK shall accompany each shipment of PMRE to the Work site and be submitted to the Engineer prior to application. In addition to the requirements of SECTION 4-5 CERTIFICATE OF COMPLIANCE of the GREENBOOK, the certificate shall show the shipment number, type of material, density, refinery, consignee, destination, quantity, Project title, purchase order number, and date of shipment.

PMRE shipped without a Certificate of Compliance will not be allowed to be used.

203-6.1 General. To the "WHITEBOOK" and "GREENBOOK", DELETE in its entirety and SUBSTITUTE with the following:

203-6.1 General. Asphalt concrete shall be the product of mixing mineral aggregate and reclaimed asphalt pavement (RAP) with asphalt binder at a central mixing plant.

When specified in the Special Provisions, asphalt concrete may be produced using a warm mix asphalt (WMA) technology.

Unless otherwise specified in the Special Provisions or shown on the Plans, asphalt concrete mixtures shall conform to 203-6.4.

If the asphalt concrete mixture contains more than 15% RAP, refer to Caltrans Standard Specifications Section 39, "Asphalt Concrete" for "Materials" and "Construction" requirements only unless specified otherwise in these (1) Supplementary Special Provisions, (2) The WHITEBOOK, and (3) The GREENBOOK in that order of precedence. Replace all references to actions by the "Department" with actions by the "City."

203-6.2.1 Asphalt Binder. To the "GREENBOOK", ADD the following:

Unless otherwise specified, for mixtures containing 15 percent or less RAP, the performance grade of the virgin asphalt binder shall be the grade specified in the Special Provisions with the upper and lower temperature classification of Performance Grade (PG) 64-10.

For mixtures containing greater than 15 percent and not exceeding 25 percent RAP, the performance grade of the virgin binder shall be the grade specified in the Special Provisions with the upper and lower temperature classification of PG 58-16.

For mixtures containing greater than 25 percent RAP, the performance grade of the asphalt binder shall be determined based on viscosity and blending charts developed in accordance with AASHTO M323.

203-6.2.2 Rock Products for Asphalt Concrete Mixtures. To the "GREENBOOK", ADD the following:

Aggregates must be clean and free from deleterious substances. The aggregates for a leveling course must comply with the gradation specifications for Type A HMA in Caltrans Standard Specification Section 39-2.02B.

203-6.2.3 Rock Products for Type III Asphalt Concrete Mixtures. To the "GREENBOOK", ADD the following:

Aggregate gradation must be determined before the addition of asphalt binder and must include supplemental fine aggregates. Test for aggregate gradation under AASHTO T 27. Do not wash the coarse aggregate. Wash the fine aggregate only. Use a mechanical sieve shaker. Aggregate shaking time must not exceed 10 minutes for each coarse and fine aggregate portion. Choose a TV within the TV limits shown in the tables titled "Aggregate Gradations." Gradations are based on nominal maximum aggregate size.

203-6.2.5.1 General. To the "GREENBOOK", ADD the following:

RAP shall be defined as asphalt concrete pavement that has been processed to a maximum of 1 inch (25 mm) in size and is free of contaminants. RAP may be substituted for part of the virgin aggregate in a quantity up to the lowest level allowed in the Caltrans Standard Specifications by dry weight of the combined aggregates.

Unless otherwise specified, RAP may be substituted for part of the virgin aggregate at or above the level allowed in the Caltrans Standard Specifications; currently, 25 percent by dry weight of the combined aggregates.

203-6.2.5.2 RAP Stockpiles. To the "GREENBOOK", ADD the following:

Fractionated RAP stockpiles shall be isolated from other materials. Fractionated RAP shall be stored in conical or longitudinal stockpiles. Fractionated RAP shall not be agglomerated or be allowed to congeal.

203-6.2.5.3 Fractionation. To the "GREENBOOK", DELETE in its entirety and SUBSTITUTE with the following:

203-6.2.5.3 Fractionation. Fractionation is the processing of RAP into 2 or more sizes. For RAP substitution of 15 percent or less, fractionation is not required. For RAP substitution greater than 15 percent, RAP shall be fractionated into 2 sizes conforming to the requirements shown in Table 203-6.2.5.3. The RAP stockpile fractionation gradation shall conform to the requirements shown in Table 203-6.2.5.3.

Table 203-6.2.5.3

Size	Test Method	Requirement
Coarse (% passing the 1-inch sieve)	California Test 202 ^a	100
Fine (% passing the 3/8-inch sieve)	California Test 202 ^a	98-100

^a Maximum mechanical shaking time is 10 minutes.

If RAP is from multiple sources, the RAP shall be thoroughly and completely blended before fractionating.

The coarse fractionated stockpile, the fine fractionated stockpile, or a combination of the coarse and fine fractionated stockpile may be used.

203-6.2.5.4 Testing. To the "GREENBOOK", ADD the following:

The mix design RAP stockpile shall be sampled and tested in accordance with California Test 384. The average shall be reported on the mix design submittal. When the mix design RAP stockpile is augmented, RAP used to augment the stockpile shall be sampled at a minimum frequency of 1 sample per 500 tons in accordance with California Test 384 before augmenting. Each sample shall be tested to determine the uncorrected binder content in accordance with AASHTO T 308. The same ignition oven shall determine the uncorrected asphalt binder content reported on the mix design submittal.

The augmented RAP sample, when tested under AASHTO T 209, shall be within ± 0.06 of the average maximum specific gravity reported on the mix design submittal.

For startup of a project:

1. Less than 5,000 tons of a QC test from another City approved submittal from the same plant within the last 90 days may be submitted for review.
2. For greater than 5,000 tons the following QC test must be completed and submitted to the Engineer:

Quality Characteristic	Test Method
Asphalt binder content	AASHTO T 308, Method A
HMA moisture content	AASHTO T 329
Combined Aggregate Gradation	California Test 384
Combined Aggregate Sand equivalent	California Test 217 or ASTM D2419
Combined Aggregate Moisture content	AASHTO T 255

Quality Characteristic	Test Method
Air voids content	AASHTO T 269
Voids in mineral aggregate	MS-2 Asphalt mixture volumetrics
Dust proportion	MS-2 Asphalt mixture volumetrics
Hveem Stability	MS-2 and OBC CT 367
Hamburg wheel track	AASHTO T 324 (modified)
Gyrations Compaction	AASHTO T 312

During production, RAP QC testing shall be sampled twice daily and the following additional tests shall be performed with the minimum frequency:

Quality Characteristic	Test Method	Minimum Frequency
Asphalt binder content	AASHTO T 308, Method A	1 per day with a minimum of 500 tons
Aggregate Gradation – combined with RAP	California Test 384	1 per day with a minimum of 100 tons
Aggregate Sand equivalency	California Test 217 or ASTM D2419	1 per day with a minimum of 100 tons
Aggregate Moisture content	AASHTO T 255	1 per day with a minimum of 100 tons
Hveem Stability	MS-2 and OBC CT 367	1 per day with a minimum of 100 tons
Hamburg wheel track	AASHTO T 324 (modified)	1 per 5,000 tons or 1 per project, whichever is greater
Nuclear gauge density	California Test 375	1 per 50 tons

203-6.2.5.5 Quality. To the "GREENBOOK", ADD the following:

For RAP content higher than 15% in HMA, refer to Sections 39-2.01, "General"; 39-2.02, "Type A Hot Mix Asphalt," and 39-2.03, "Rubberized Hot Mix Asphalt-Gap Graded," of the Caltrans Standard Specifications in effect at the time of Bid for the quality assurance requirements. Under this process, the contractor performs quality control testing, and the City performs acceptance testing and inspection. The acceptance decision is based on the City's test results only.

RAP shall conform to the requirements shown in Table 203-6.2.5.5:

Table 203-6.2.5.5

Quality Characteristic	Test method	Requirement
Uncorrected Binder Content (% within the average value reported) ^a	AASHTO T 308	±2.00
Specific gravity (within the average value reported) ^b	AASHTO T 209	±0.06
Combined Aggregates Sand Equivalent (min)	California Test 217 or ASTM D2419	50

^a Average uncorrected binder content of 3 ignition oven tests performed.

^b Average maximum specific gravity reported on the JMF.

203-6.3.1 General. To the "GREENBOOK" and "WHITEBOOK", DELETE in its entirety and SUBSTITUTE with the following:

203-6.3.1 General.

1. The Contractor shall submit in accordance with 3-8.4 a JMF that summarizes each asphalt concrete mix design for each class and grade of asphalt concrete required to construct the Work. Supporting information for the warm mix asphalt (WMA) technology and/or recycling agent, if included in a mixture, shall also be submitted e.g., C2 PG 58-16 (½ inch) (12.5 mm) and B3 PG 58-16 (¾ inch) (19 mm) asphalt concrete.
2. Asphalt concrete for JMF and Mix Designs shall be Type III and shall not exceed the allowable RAP level.
3. The JMF shall identify the source and the individual grading of each material used to produce the mix design (including the percentage and individual gradation of any manufactured or natural sands), the combined gradation, the optimum binder content (OBC), void content, reclaimed asphalt pavement (RAP) percentage, RAP gradation, RAP binder content, stability value, plant identification, mix number, WMA technology, and the source and performance grade of the paving asphalt. Upon request, the mix design test data represented by the JMF shall be immediately made available to the Engineer.
4. When greater than 25 percent RAP is to be included in a mixture, a mix design shall be submitted on Caltrans Forms CEM-3511 and CEM-3512 or another format as approved by the Engineer. The submittal shall include supporting information showing the viscosity of the individual binders (both the virgin paving asphalt grade and that of the binder recovered from the RAP); and the amount of recycling agent, if any, and the blended final viscosity in accordance with AASHTO M323.

5. For all mixtures, the asphalt binder content shall be defined as the total bituminous material present in the mix consisting of the blend of virgin paving asphalt, residual paving asphalt from RAP, and recycling agent.
6. Refer to Caltrans Standard Specifications, 39-2.01A(3)(b), "Job Mix Formula" for additional requirements for modifications, renewal, authorization, and quality control plan.
7. A new mix design shall be prepared and a new JMF submitted if:
 - a) the combined aggregate gradation is not within ± 3 percentage points of the gradation shown on the referenced mix design on any sieve,
 - b) the source of any aggregate is changed,
 - c) the performance grade of paving asphalt is changed,
 - d) the average binder content in a new fractionated RAP stockpile varies by more than ± 2.00 percent from the average RAP binder content reported on the JMF,
 - e) the average maximum specific gravity in a new fractionated RAP stockpile varies by more than ± 0.060 from the average maximum specific gravity value reported on the JMF.
8. AASHTO T 324 (Modified) is AASHTO T 324 (Standard Method of Test for Hamburg Wheel-Track Testing of Compacted Asphalt Mixtures) with the following parameters:
 - a) Target air voids must equal 7.0 ± 1.0 percent.
 - b) Specimen height must be 60 ± 1 mm.
 - c) Number of test specimens must be 4 to run 2 tests.
 - d) Do not average the 2 test results.
 - e) Test specimen must be a 150 mm gyratory compacted specimen.
 - f) Test temperature must be set at:
 1. 113 ± 2 degrees F for PG 58 for use of 25% RAP
 2. 122 ± 2 degrees F for PG 64 for use of 15% RAP
 3. Measurements for impression must be taken at every 100 passes along the total length of the sample.
 - g) Inflection point is the number of wheel passes at the intersection of the creep slope and the stripping slope at maximum rut depth.
 - h) Testing shut off must be set at 25,000 passes.
 - i) Submersion time for samples must not exceed 4 hours.
9. Take samples under California Test 125.

ADD:

203-6.3.3

Asphalt Binder Replacement. Asphalt binder replacement shall be defined as the asphalt binder from RAP expressed as a percent of the total asphalt binder in the mixture. The asphalt binder replacement shall be calculated as a percentage of the approved JMF target asphalt binder content. The maximum asphalt binder replacement for mixtures containing RAP shall be 25 percent of the optimum binder content (OBC) for surface courses and 40 percent for leveling and base courses.

For Type A HMA with a binder replacement percent less than or equal to 25 percent of your specified OBC, you may request that the performance-graded asphalt binder grade with upper and lower temperature classifications be reduced by 6 degrees C from the specified grade.

Once the City has approved a mix design, the asphalt binder content shall be within 0.5% of the identified target binder contents for each mix design submitted.

Each approved asphalt plant and location shall perform an annual verification process with the City.

ADD:

203-6.4.5

Miscellaneous Areas and Dikes. For miscellaneous areas and dikes:

1. Choose the aggregate gradation from:
 - a) 1/2-inch Type A HMA aggregate gradation.
 - b) Dike mix aggregate gradation.
2. Choose asphalt binder Grade PG 58-16 or 64-10.
3. Minimum asphalt binder content must be:
 - a) 5.70 percent for 1/2-inch Type A HMA aggregate gradation.
 - b) 6.00 percent for dike mix aggregate gradation.

If you request and the Engineer authorizes, you may reduce the minimum asphalt binder content. Aggregate gradation for dike mix must be within the TV limits for the specified sieve size as shown below:

Sieve size	Target value limit	Allowable tolerance
1/2"	100	--
3/8"	---	95 - 100
No. 4	73-77	TV \pm 10
No. 8	58-63	TV \pm 10
No. 30	29-34	TV \pm 10
No. 200		0 - 14

For HMA used in miscellaneous areas and dikes, sections 203-6.3.1 do not apply.

203-6.7 Production. To the "GREENBOOK", ADD the following:

1. Before production, the HMA plant must have a current qualification under the City's Material Plant Quality Program for each mix design.

203-6.7.1 General. To the "GREENBOOK", ADD the following:

During production, the hot- or cold-feed proportion controls for virgin aggregate and RAP may be adjusted. For RAP substitution of 15 percent or less, RAP must be within ± 5 of the RAP percentage shown in the approved JMF form without exceeding 15 percent. For RAP substitution of greater than 15 percent, RAP must be within ± 5 of the RAP percentage shown in the approved JMF form without exceeding 25 percent.

Do not start HMA production before verification and authorization of JMF. The HMA plant must have a current qualification under the City's Material Plant Quality Program. Weighing and metering devices used to produce HMA modified with additives must comply with the City's MPQP. If a loss-in-weight meter is used for dry HMA additive, the meter must have an automatic and integral material delivery control system for the refill cycle.

Calibrate the loss-in-weight meter by:

1. Including at least 1 complete system refill cycle during each calibration test run
2. Operating the device in a normal run mode for 10 minutes immediately before starting the calibration process
3. Isolating the scale system within the loss-in-weight feeder from surrounding vibration
4. Checking the scale system within the loss-in-weight feeder for accuracy before and after the calibration process and daily during mix production
5. Using a minimum 15 minute or minimum 250 lb. test run size for a dry ingredient delivery rate of less than 1 ton per hour
6. Complying with the limits of City's Conveyor Scale Testing

Proportion aggregate by hot or cold-feed control. The aggregate temperature must not be more than 375 degrees F when mixed with the asphalt binder. Asphalt binder temperature must be from 275 to 375 degrees F when mixed with aggregate. Mix HMA ingredients into a homogeneous mixture of coated aggregates.

HMA must be produced at the temperatures shown in the following table:

HMA compaction	Temperature (°F)
Density based Method	Not to exceed 325

If you stop production for longer than 30 days, a production start-up evaluation is required.

SECTION 301 – SUBGRADE PREPARATION, TREATED MATERIALS, AND PLACEMENT OF BASE MATERIALS

301-1.6 Preparatory Repair Work. To the “WHITEBOOK”, DELETE in its entirety and SUBSTITUTE with the following:

1. Prior to the application of slurry seal or scrub seal, the Contractor shall complete all necessary preparation and repair work to the road segment as specified in the Special Provisions and Contract Documents or as directed by the engineer.
2. No preparatory asphalt work shall be done when the atmospheric temperature is below 50 °F or during unsuitable weather.
3. Prior to the application of the surface seal, the Contractor shall reference all utility and manhole covers and survey monuments with sufficient number of points to locate each facility after sealing the street. The reference marks shall be removed to the satisfaction of the Engineer when no longer needed.
4. Manhole covers, utility vaults and the surfaces of other utility facilities, survey monuments and benchmarks, shall be covered using a material approved by the Engineer. The cover material and application procedure shall not result in adherence of the surface seal nor in stripping of the surface seal from the adjacent roadway pavement. All utility, manhole, and survey monument covers will need to be removed prior to leaving the work site at the end of the day. Temporary covers shall be re-applied prior to each subsequent surface seal application.
5. Preparatory Work shall include tree trimming, weed abatement, weed spraying, crack sealing, asphalt repair, base repair, edge grind, removal of humps and pavement irregularities, removal of raised pavement markers, removal of pavement markings, identifying location of public and private utilities and appurtenances, all concrete work, and any other work and as specified in the Special Provisions and Contract Documents or as directed by the Engineer.
6. Preparatory crack sealing for slurry seal shall occur after the completion of asphalt pavement repair, base repair, edge grind. At the end of each day the Contractor shall submit to the Engineer an itemized list of crack seal work completed. The list shall include the location of the work and the exact quantity of pounds of crack seal placed. Crack seal shall not be required for streets scheduled to be scrub sealed and/or cape seal as specified in the Contract Documents.
7. Existing City manhole frames and covers, appurtenances (water and sewer), and survey monuments to be raised or reconstructed shall be adjusted after the placement of the surface seal or as directed by the Engineer. Relocation or adjustment to grade by other agencies/companies shall be identified by marking the face of the curb closest to the utility appurtenance as follows:
 1. Offset distance of the appurtenance from the curb face
 2. The limits of the appurtenance or corners of the vault/box

8. Most areas of damaged asphalt requiring Asphalt Pavement Repair have been marked out in the field as "MP" or "DO" or "MM" (mill & pave or dig-out). Mill & Paves shall have a minimum depth of 2", and dig-outs, also called base repairs, shall have a minimum depth of 10". Some areas (ie. those uplifted by tree roots) may be marked out in the field as "MP4" and shall have a minimum mill & pave depth of 4".
9. The minimum repair area shall be 4 feet by 4 feet regardless of mark out.
10. Edges of milled areas shall be cut cleanly.
11. Material removed, regardless of removal method, shall be disposed of at a legal site.
12. You shall repair marked out areas of distressed asphalt concrete pavement by, milling, grinding, or saw cutting to remove damaged areas of pavement in accordance with 404-1, "General", to expose firm and unyielding pavement, base or native. Unyielding pavement will have no visible cracks and unyielding base or native will be properly compacted, as determined by the Engineer. If cracks are visible, then pavement is not unyielding and shall require additional depth be removed. The Contractor shall prepare subgrade as needed and install a maximum of 5" compacted asphalt concrete pavement over compacted base material to be level with adjacent roadway surface.
13. If, in order to achieve the minimum specified depth, the base material is exposed, then the existing base material, as well as additional base material shall be compacted to 95% relative compaction to a depth 5" below the finished grade (dig-out).
14. The QCP shall establish location and timing of compaction testing and shall be subject to approval by the Engineer. You shall reimburse the City for the cost of retesting failing compaction tests conducted as part of the City of San Diego Quality Assurance testing.
15. Base repairs shall have a minimum depth of 10".
16. Compaction tests shall be made to ensure compliance with the specifications. The Engineer will determine when and where the test will occur. If additional base material is required, the Contractor shall use Crushed Miscellaneous Base in accordance with 200-2.4, "Crushed Miscellaneous Base". If the base material is exposed, to achieve the required minimum removal thickness, the base material shall be prepared conforming to 301-1, "SUBGRADE PREPARATION."
17. Recycled base material shall conform to Crushed Miscellaneous Base Material in accordance with 200-2.4, "Crushed Miscellaneous Base."
18. Base repairs shall comply with 203-6, "Asphalt Concrete."

19. You may use grinding as a method for removal of deteriorated pavement when the areas indicated for removal are large enough (a minimum of the machine drum width) and when approved by the Engineer.
20. For both scheduled and unscheduled base repairs, failed areas may be removed by milling or by excavation provided that the edges are cut cleanly with a saw. The areas shall be cleaned, and tack coated in accordance with 302-5.4, "Tack Coat" before replacing the asphalt pavement. Please refer to the Contract Documents .
21. Base repair areas where failed pavement is removed either by cold milling or by excavation shall be restored to existing pavement grade with "Crushed Miscellaneous Base" at 5 inches, and 5 inches of Asphalt Concrete shall be placed atop the layer of "Crushed Miscellaneous Base" unless otherwise directed by the Engineer. These areas have been identified in the Contract Documents field as "DO". The Crushed Miscellaneous Base shall be in accordance with 200-2.4, "Crushed Miscellaneous Base."
22. Preliminary quantities are identified in the Contract Documents but may need to be increased and approved by the Engineer at the time of construction. Base Repairs shall not exceed 25% RAP in content.
23. When applicable, the areas and quantities shown in the Contract Documents are given only for the Contractor's aid in planning the Work and preparing Bids. You shall identify any new areas that require repair prior to paving in order to construct a smooth and stable pavement surface. Upon approval by the engineer, the repair locations shall be incorporated into scope of work and shall not be considered extra work. You shall mark the pavement area as "DO" or as directed by the Engineer.
24. Prior to replacing asphalt, the area shall be cleaned by removing all loose and damaged material, moisture, dirt, and other foreign matter and shall be tack coated in accordance with 302-5.4, "Tack Coat."
25. When milling and/or grinding asphalt pavement and the Contractor encounters solid, level unyielding PCC trench caps or appurtenance collars before reaching a minimum depth of 2", then the Contractor shall place enough asphalt concrete pavement to bring the surface to be level with the adjacent roadway.
26. The Contractor shall install new asphalt within the repair area or for patches in accordance with 302-5, "ASPHALT CONCRETE PAVEMENT." Asphalt concrete shall be III-B3-PG 64-10 (3/4") and III-C2-PG 64-10 (1/2") in compliance with 203-6, "ASPHALT CONCRETE."
27. Following the asphalt placement, the Contractor shall roll the entire area of new asphalt in both directions at least twice. The finished patch shall be level and smooth in compliance with the 302-5.6.2, "Density and Smoothness." After placement and compaction of the asphalt patch, you shall seal all finished edges with a 4 inch (101.6 mm) wide continuous band of SS-1H.

28. At the end of each day the Contractor shall submit to the Engineer an itemized list of asphalt pavement and base repair work completed. The list shall include the location of the work, the exact square footage of the repair, tons of asphalt placed, and tons of base material placed.
29. When micro-mill is specified in the Contract Documents, streets shall be micro-milled after the asphalt pavement repairs, base repairs, and edge-grinding have been completed.
30. The quantities shown in the appendices are based on a street assessment survey and may vary. The Engineer will designate the limits to be removed and prepared and these designated areas shall be considered to take precedence over the areas shown in an Appendix to the Contract Documents.

301-1.6.1 Asphalt Patching. To the "WHITEBOOK", items 1, 2, and 5, DELETE in their entirety and SUBSTITUTE with the following:

1. Miscellaneous asphalt patching shall consist of patching potholes and skin patching other low spots in the pavement that are deeper than ¼" per 302-5.6.2, "Density and Smoothness." These areas are generally smaller and more isolated than those areas in need of mill and pave.
2. The areas requiring patching have not been identified in the Contract Documents, nor in the field. The Contractor and/or Engineer shall identify areas that may require patching prior to slurry work to ensure the smoothness and quality of the finished product.
5. You shall remove distressed asphalt pavement either by saw cutting or milling to expose firm and unyielding pavement, prepare subgrade (as needed), and install compacted asphalt concrete pavement over prepared subgrade per 301-1, "Subgrade Preparation."

301-1.7 Payment. To the "WHITEBOOK", DELETE in its entirety and SUBSTITUTE with the following:

1. The payment for the preparatory works shall be included in the Contract Unit Bid Item for which preparation works are performed unless it is specified as a separate Bid Item.
2. The areas and quantities shown on the road segments and in the appendices are given only for the Contractor's aid in planning the Work and preparing Bids. The Engineer will designate the limits to be removed and prepared and these designated areas shall be considered to take precedent over the areas shown in an Appendix to the Contract Documents. The quantities shown in the appendices are based on a street assessment survey and may vary. No payment shall be made for areas of over excavation as determined by the Engineer.

3. Asphalt pavement repair, including both mill & paves and base repair dig-outs, required for both mill & paves and base repair dig-outs, shall be paid at the Contract unit price per ton for **"Asphalt Pavement Repair"**. No Payment shall be made for areas of over excavation as determined by the Engineer.
4. The payment for preparatory repair asphalt works shall be paid at the Contract Unit Price for **"Asphalt Pavement Repair"** for each ton placed and includes milling, grinding, hauling, disposal or saw cutting of existing pavement, tree trimming, tack coating, compaction, and all other necessary work related to asphalt pavement installation.

No additional payment shall be made for milling, grinding, or saw cutting concrete, pavement fabric, rubberized material, steel reinforcement, or any other material.
5. Miscellaneous asphalt patching and tack coat shall be included in the unit price for Bid Item **"Asphalt Pavement Repair"** and no additional payment shall be made therefore regardless of number and location of patches.

301-2.4 Measurement and Payment. To the "GREENBOOK", ADD the following:

- i. The payment for base repair dig-outs shall be paid at the Contract Unit Price for **"Crushed Miscellaneous Base"**, for each ton placed and includes milling, grinding, excavating, hauling, disposal, or saw cutting of existing pavement, and all other necessary work related to asphalt base repair.

SECTION 302 – ROADWAY RESURFACING

302-2 CHIP SEAL.

302-2.2.1 Emulsified Asphalt. To the "GREENBOOK", ADD the following:

Emulsified asphalt for scrub seal applications shall be a polymer modified rejuvenating emulsion (PMRE) conforming to 203-3.4.7.

302-2.2.3 Screenings. To the "GREENBOOK", DELETE in its entirety and SUBSTITUTE with the following:

The size of screenings used shall be medium fine 5/16" x No. 8 and conform to the requirements shown in Table 200-1.2.2.2 unless otherwise specified.

The contractor shall ensure that the selected bituminous material is compatible with the aggregate to be used. This may require conducting electrostatic testing of aggregate source before chip design to ensure that the binder selected is compatible with the potential sources of aggregate.

302-2.2.4 Sand. To the "GREENBOOK", ADD the following:

Sand shall not be applied for Scrub Seals or Cape Seals.

302-2.3.6 Sweepers. To the "GREENBOOK", ADD the following:

Brooms shall not be steel-tined brooms on emulsion chip seals. Sweepers shall be capable of removing loose screenings adjacent to barriers that prevent aggregate from being swept off the roadway, including curbs, gutters, dikes, berms, and railings.

302-2.4 Roadway Surface Preparation. To the "GREENBOOK", ADD the following:

Remove any extraneous material affecting adhesion of the chip seal with the existing surface and drying.

ADD:

302-2.4.1 Testing. Testing shall conform to the requirements of 203-3.4.5.

302-2.6 Application and Spreading.

302-2.6.1 General. To the "GREENBOOK", ADD the following:

Schedule the operations so that chip seals are placed on both lanes of the travel way each work shift. At the end of the work shift, the end of the chip seals on both lanes must generally match.

302-2.6.2 Polymer Modified Emulsified Asphalt. To the "GREENBOOK", ADD the following:

The initial application rate for each road shall be 0.30 gal/sq yd and any adjustments to this rate shall be determined by the Contractor.

Do not apply polymer modified asphaltic emulsions when weather forecasts predict the ambient air temperature will fall below 39 degrees F within 24 hours after application.

Emulsion shall not be applied a greater distance than can be immediately covered by screenings, and, in no case, shall the distributor truck advance more than 200' ahead of the screening spreader.

302-2.6.4.1 General. To the "GREENBOOK", ADD the following:

Do not allow vehicles to drive on asphaltic emulsion or asphalt binder before spreading aggregate. Operate the spreader at speeds slow enough to prevent aggregate from rolling over after dropping.

If the spreader is not moving, aggregate must not drop. If you stop spreading and aggregate drops, remove the excess aggregate before resuming activities.

302-2.6.4.2 Spreading on Polymer Modified Emulsified Asphalt. To the "GREENBOOK", ADD the following:

You may stockpile aggregate for the polymer modified emulsified asphalt chip seals if you prevent contamination. Aggregate must have a damp surface at spreading. If water visibly separates from the aggregate, do not spread. You may re-dampen aggregate in the delivery vehicle. Operating the chip spreader at speeds which cause the chips to roll over after striking the bituminous covered surface will not be permitted.

Spread aggregate before the polymer modified emulsified asphalt sets or breaks.

Do not spread aggregate more than 500 feet ahead of the completed initial rolling.

302-2.7 Finishing.

302-2.7.1 General. To the "GREENBOOK", ADD the following:

- d) Remove temporary covers from appurtenances and utility covers prior to leaving the worksite at the end of the day.

302-2.8 Flush Coat.

302-2.8.1 General. To the "GREENBOOK", paragraph 1, DELETE in its entirety and SUBSTITUTE with the following:

Flush coat shall consist of the application of an emulsified asphalt fog seal to the surface of the chip seal. Flush coat application shall begin immediately after initial sweeping and removal of excess screenings and prior to opening the lane to uncontrolled (not controlled with pilot cars) traffic.

Flush coat shall not be applied when a chip seal is applied as part of a cape seal treatment.

302-2.8.3 Sand Cover. To the "GREENBOOK", DELETE in its entirety.

302-2.11 Payment. To the "GREENBOOK", DELETE in its entirety and SUBSTITUTE with the following:

The payment for chip seals will be made at the Contract Unit Price for "PME Chip Seal" per square foot for each combination of size of screenings and grade of emulsified asphalt or modified paving asphalt used in the Work. The basis of the payment shall be as specified in the Bid.

Unless otherwise specified, the Contract Unit Price shall include:

- a) public notification,
- b) surface preparation,
- c) materials,
- d) application and spreading,
- e) finishing,
- f) sweeping,
- g) disposal, and
- h) maintenance of the completed chip seal

302-4.12.2 Application. To the "WHITEBOOK", item 1, subsection c, DELETE in its entirety and SUBSTITUTE with the following:

- c) RPMS shall only be placed when the ambient temperature is at least 50° F and rising. Do not place slurry seal if rain is imminent or the ambient temperature is expected to be below 32° within 24 hours after placement.
- d) The weather and temperature requirements listed in subsection c shall supersede those listed in section 37-3.01 C(5)(b) of the Caltrans Standard Specifications.

To the "WHITEBOOK", item 2, subsection b, ADD the following:

- iii. Where multiple layers of RPMS are specified, the first layer, regardless of Type, shall be placed 1' from concrete gutters.

302-4.12.4 Measurement and Payment. To the "WHITEBOOK", DELETE in its entirety and SUBSTITUTE with the following:

- 1. RPMS shall be paid on the square footage of RPMS applied. The measurement of RPMS applied shall be calculated by dividing the weight obtained from Certified Weighmaster Certificates by the spread rate for the type specified. You shall present Weighmaster Certificates for unused material remaining at the completion of the Work at no cost to the City. The payment shall be determined by deducting the amount of unused material from the total amount of material delivered.
- 2. The payment for RPMS shall be the total square footage used on the project calculated using the method described and shall be paid under the following:

BID DESCRIPTION	UNIT
Rubber Polymer Modified Slurry (RPMS) Type I	SF
Rubber Polymer Modified Slurry (RPMS) Type II	SF
Rubber Polymer Modified Slurry (RPMS) Type III	SF

- 3. The Bid items for RPMS shall include full compensation for the specified surface preparation not included in other Bid items and shall include the work necessary to construct the RPMS as specified on the Plans. Sweeping, removals, and furnishing the aggregate required for the mix design shall also be included in this Bid item.
- 4. The payment for sampling and testing of RPMS shall be included in the bid items of the Rubber Polymer Modified Slurry listed in the table of item 2.

ADD:**302-4.12.5 Field Sampling and Testing.**

1. The contractor shall be responsible for sampling and testing of the RPMS mix.
2. During the performance of the work, the Contractor shall provide at least 2 field samples, from separate loads, of mixed slurry seal per mixer per day.
3. WTAT specimens shall be cast and struck off within 60 seconds of obtaining the sample. WTAT specimens shall not be transported until the slurry seal has set as defined by ASTM D3910.
4. RPMS field samples shall be tested to conform to the requirements below and Table 302-4.9.1 of the "GREENBOOK".

TEST	FREQUENCY OF TESTING
Wet Track Abrasion Test	Minimum 2 per day per type per mixer
Consistency Test	Minimum 1 per day per type per mixer
Extraction Test	Minimum 1 per day per type per mixer
Water Content	Minimum 1 per day per type per mixer

302-5.4 Tack Coat. To the "WHITEBOOK", ADD the following:

3. Prior to applying the tack coat, submit calculations for the minimum spray rate required to achieve the minimum residual rate.

302-15.1 General. To the "WHITEBOOK", item 1, DELETE in its entirety and SUBSTITUTE with the following:

1. All cracks in asphalt 1/8 inch or wider but no greater than 1 inch wide shall be sealed prior to the application of slurry. You shall seal only transverse, longitudinal, block, or reflective cracks. You shall not seal alligator (fatigue) cracked areas or cracks in PCC.

ADD:**302-16 SCRUB SEAL.****302-16.1 General.** Scrub seal shall consist of furnishing all labor, materials, tools, equipment, transportation, and incidentals necessary for scrub seal resurfacing.

A scrub seal consists of applying a seal coat using a polymer modified rejuvenating asphaltic emulsion (PMRE), scrubbing the emulsion to fill cracks and voids in the pavement, applying and rolling screenings, and applying a flush coat.

The contractor shall prepare a submittal detailing the scrub seal order of operations including but not limited to the following: weed abatement, asphalt pavement repairs and/or base repairs, edge grinding, application of the PMRE and scrubbing the applied emulsion with a scrub broom as specified, application of screenings, brooming the screenings with a secondary broom when specified, rolling the screenings, and application of a flush coat.

Flush coat shall not be applied when a scrub seal is applied as part of a cape seal treatment.

302-16.2 Materials.

302-16.2.1 Chip Seal. Chip seal shall conform to 302-2.

302-16.2.1.1 Emulsified Asphalt. Emulsified asphalt for the flush coat shall conform to 302-2.2.1.

302-16.2.1.2 Modified Paving Asphalt. Modified paving asphalt shall conform to 302-2.2.2.

302-16.2.1.3 Screenings. The size of screenings used shall be medium fine 5/16" x No. 8 and conform to 200-1.2.2.2 unless otherwise specified.

The screening gradation for a PMRE scrub seal must comply with the requirements of 200-1.2.2.2.

The contractor shall ensure that the selected bituminous material is compatible with the aggregate to be used. This may require conducting electrostatic testing of aggregate source before chip design to ensure that the binder selected is compatible with the potential sources of aggregate.

302-16.3 Equipment. Equipment shall conform to 302-2.3 with the addition of a scrub broom (See **Appendix L - Scrub Broom Diagram**). The scrub broom shall be a broom sled of angled nylon-bristled street brooms. The broom sled shall be attached to and pulled by the distributor truck. The broom sled must be equipped with the means to mechanically raise and lower the scrub broom off and onto the road surface at designated points of completion and start up. It shall be towable in an elevated position to the next area of construction. The weight of the broom assembly shall be such that it does not squeegee the emulsion sealer off the roadway surface. Sandbags may be used to ensure contact is maintained.

302-16.4 Roadway Surface Preparation. Roadway surface preparation shall conform to 302-2.4.

Prior to the Scrub Seal operation on city streets, the Contractor shall remove any and all vegetation within the limits of the scrub seal by applying an approved herbicide.

The herbicide shall be applied at least 10 days prior to the chip seal operation, or as directed by the manufacturer of the approved herbicide. Herbicides shall be submitted by the contractor for approval by the Agency and shall be certified for use in the State of California for the specific use intended. The application of the herbicide shall be performed in accordance with all applicable regulations. Any and all fines or clean-up costs for unlawful misuse or discarding of herbicides shall be the sole responsibility of the Contractor. Mixtures and spread rates for the herbicides shall be determined by the manufacturer's specifications. Washing down of equipment or discarding of herbicides shall not enter the catch basins or positive drainage facilities.

Prior to the Scrub Seal operation, the Contractor shall remove all existing thermoplastic striping, thermoplastic legends and raised pavement markers within the scrub seal limits. When removing the raised pavement markers, the Contractor shall remove excessive adhesive left on pavement caused from the removal of raised pavement markers. Removal shall be done to the satisfaction of the Engineer.

Prior to the Scrub Seal operation, all personnel covers, drain inlet covers, monument covers, and all other utility covers shall be protected from the Contractor's scrub seal operations by applying a sheet of plastic, cut to fit, or placing a plastic bag over the exposed facilities or other methods approved by the Engineer. All traces of plastic, residual emulsion and chips shall be removed from all personnel covers, drain inlet covers, monument covers, and all other utility covers as quickly as possible, after the application of the scrub seal and/or prior to the final acceptance of the project.

Immediately prior to the Scrub Seal operations, the Contractor shall thoroughly clean the surface to receive scrub seal. The Contractor shall sweep the entire surface with power brooms to the satisfaction of the Engineer.

All cracks 1" in width or less shall be blown out with compressed air immediately prior to applying the PMRE so that it is allowed to penetrate and fill these cracks.

Contractor shall identify locations where cracks are found to be in excess of 1" and shall bring them to the attention of the Engineer.

The Contractor shall furnish a computer generated schedule for the work, listing the dates on which individual streets or locations are to be closed to traffic for surfacing. The schedule shall detail the dates each street is to be scrub sealed, and when the final flush coat layer shall be applied. The Contractor shall adhere diligently to the work schedule in the prosecution of the work.

302-16.5 Temporary Traffic Control. Temporary traffic control to conform to 302-2.5.

302-16.6 Application and Spreading. Chip seal and flush coat shall be applied to the specified roadways where Scrub Seal is identified. Application and spreading shall conform to 302-2.6 and the following:

PMRE shall not be applied:

- a) when the atmospheric temperature is below 50°F or above 105°F
- b) until sufficient screenings are on hand to immediately cover the PMRE,
- c) more than 500 feet ahead of the completed initial rolling

In no case, shall the distributor truck advance more than 200 feet ahead of the screening spreader.

The contractor shall schedule PMRE application such that the PMRE breaks (turns from brown to black) before

- a) the atmospheric temperature falls below 50°F,
- b) the pavement temperature falls below 50°F, and
- c) the time the lane is to be opened to traffic

PMRE must be heated to a temperature above 130°F but not exceed 180°F at the time of application.

The initial application rate shall be 0.32 gallon per square yard. The contractor may propose a different initial rate. If so requested by the Engineer, the Contractor shall apply PMRE to 100-foot test strips to assist in determination. The initial rate of application, and any adjustments thereto during application, shall be subject to approval by the Engineer.

Immediately following application, PMRE shall be scrubbed into the existing pavement surface with a scrub broom. Scrubbing shall fill cracks and voids, force the PMRE into the existing pavement surface, and distribute the PMRE uniformly over the roadway cross section.

Screenings shall be spread immediately after application and brooming of PMRE. Spreading of screenings shall conform to 302-2.6.4. The spread rate for screenings shall be between 16 to 25 lbs per square yard. The exact rate will be determined by the contractor. The rate shall be adjusted up or down as necessary to provide complete and uniform coverage over the PMRE and ensure that no bleeding occurs during rolling. The initial rate, and any adjustments thereto during spreading, shall be subject to approval by the Engineer.

Finishing including initial and final rolling, sweeping, and application of a flush coat shall conform to 302-2.7.

Allow at least three calendar days for cure time on the chip seal prior to applying flush coat.

The Contractor shall exercise care to prevent spillage of resurfacing material on concrete surfaces. All surfaces not designated to be resurfaced shall be cleaned immediately before resurfacing any more streets. All streets are to be resurfaced from edge of pavement to edge of pavement and no overlap on concrete shall be permitted.

302-16.7 **Finishing.** Finishing shall conform to 302-2.7. The Contractor shall assume full liability and pay all costs associated with any claims made for cracked/broken windshields, damage to paint, etc. on roads scheduled for scrub seal at no cost to the City.

302-16.8 **Flush Coat.** Flush coat shall conform to 302-2.8.

Flush coat shall not be applied on roads receiving a cape seal.

302-16.9 **Maintenance.** Maintenance shall conform to 302-2.9.

302-16.10 **Measurement.** Scrub seal will be measured by the square foot. The quantity of Scrub Seal to be paid will be determined by measuring the total area where Scrub Seal was placed. No payment will be made for materials not used or material placed outside of the limits specified in these contract documents unless directed by the Engineer.

Application rates of PMRE and screening will be verified utilizing calibration information from the distributor and spreader trucks used.

302-16.11 Payment. The payment for scrub seal will be made at the Contract Unit Price for “Polymer Modified Rejuvenating Emulsion (PMRE) Scrub Seal” per square foot and shall include full compensation for furnishing all labor, materials, equipment and incidentals for the following items:

- a) public notification
- b) surface preparation,
- c) materials, including the rejuvenating emulsion, screenings, and flush coat
- d) application and spreading,
- e) finishing
- f) sweeping,
- g) disposal, and
- h) maintenance of the completed scrub seal

ADD:

302-17 CAPE SEAL.

302-17.1 General. Cape seal shall consist of furnishing all labor, materials, tools, equipment, transportation, and incidentals necessary for constructing cape seal resurfacing.

Cape seal resurfacing includes an initial scrub seal conforming to 302-16 followed by Type II slurry seal surfacing conforming to 302-4.

When specified, an additional Type I slurry seal shall be applied over bike lanes conforming to 302-4.

302-17.2 Materials.

302-17.2.1 Scrub Seal. Scrub seal shall conform to 302-16.

302-17.2.1.1 Emulsified Asphalt. Emulsified Asphalt shall conform to 203-3.4.7.

302-17.2.1.2 Modified Paving Asphalt. Modified paving asphalt shall conform to 302-2.2.2.

302-17.2.1.3 Screenings. Screenings shall be medium fine 5/16” x No. 8 and conform to 200-1.2.2.2.

302-17.2.2 Slurry Seal Surfacing. Slurry seal surfacing methods shall be Type II and conform to 302-4.12 and 203-5.6.

- 302-17.3 Equipment.** Equipment shall conform to 302-16.3 and 302-4.5.
- 302-17.4 Roadway Surface Preparation.** Roadway surface preparation shall conform to 302-16.4.
- 302-17.5 Temporary Traffic Control.** Temporary traffic control shall conform to 302-2.5 and 302-4.7.
- 302-17.6 Application and Spreading.** Scrub seal and Type II RPMS slurry seal shall be applied to the specified roadways where Cape Seal is identified. An additional Type I RPMS slurry seal layer shall be applied within bike lane limits as specified in the Contract Documents.
- Allow at least three calendar days but no more than seven calendar days for cure time on the scrub seal prior to applying slurry seal surfacing.
- The Contractor shall exercise care to prevent spillage of resurfacing material on concrete surfaces. All surfaces not designated to be resurfaced shall be cleaned immediately before resurfacing any more streets. All streets are to be resurfaced from edge of pavement to edge of pavement and no overlap on concrete shall be permitted.
- 302-17.7 Finishing.** Finishing shall conform to the Standard Specifications and these Special Provisions.
- The Contractor shall assume full liability and pay all costs associated with any claims made for cracked/broken windshields, damage to paint, etc. on roads scheduled for cape seal at no cost to the City.
- 302-17.8 NOT USED.**
- 302-17.9 Maintenance.** Maintenance shall conform to the Standard Specifications and these Special Provisions.
- 302-17.10 Measurement.** Cape Seal will be measured by the square foot. The quantity of Cape Seal to be paid will be determined by measuring the total area where Cape Seal was placed. No payment will be made for materials not used or material placed outside of the limits specified in these contract documents unless directed by the Engineer.
- Application rates of PRME and screening we be verified utilizing calibration information from the distributor and spreader trucks used.
- 302-17.11 Payment.** The payment for cape seal will be made at the Contract Unit Price for **“Cape Seal (PMRE Scrub Seal with Type II Slurry Seal)”** per square foot and shall include full compensation for furnishing all labor, materials, equipment, and incidentals for the following items:
- a) public notification
 - b) surface preparation
 - c) materials, including the rejuvenating emulsion, screenings, and Type II RPMS Slurry Seal

- d) application and spreading
- e) finishing
- f) sweeping
- g) disposal and
- h) maintenance of the completed scrub seal

The payment for Type I slurry to be placed in bike lanes shall be made at the Contract Unit Price for **"Rubber Polymer Modified Slurry (RPMS) Type I"** per square foot.

SECTION 314 – TRAFFIC STRIPING, CURB AND PAVEMENT MARKINGS, AND PAVEMENT MARKERS

314-1 GENERAL. To the "GREENBOOK", ADD the following:

All crosswalks required for this contract shall be in conformance with Standard Drawing SDM-116 for Continental Crosswalks.

The Contractor shall install all traffic striping, pavement markings, pavement markers and devices within 15 calendar days, and no less than 7 calendar days after the last coat of slurry has been applied in accordance with current standards regardless of the existing conditions and installation will include the proposed striping modifications as identified in the Contract Document. All striping modifications shall be coordinated by the Engineer.

Any traffic signage installation as required by the striping plans shall be installed concurrently or prior to the striping installation.

If any striping is removed in the vicinity of a school, the contractor shall re-install all striping prior to the first day of school.

Pedestrian crosswalks, limit lines, pavement arrows, pavement legends, diagonal markings, chevron markings and all bikeway markings shall be installed utilizing 125 mil thickness thermoplastic marking material. All markings noted as green should be skid/slip resistant and comply with the Federal Highway Administration's Interim Approval for Optional Use of Green Colored Pavement for Bike Lanes (IA-14). Unless specified in the Striping Plans, locations and quantities of red curb installation are identified in **Appendix O – Red Curb Quantities**.

314-2.3 Payment. To the "GREENBOOK", DELETE in its entirety

314-3.3 Payment. To the "GREENBOOK", DELETE in its entirety

314-4.3.7 Payment. To the "WHITEBOOK", DELETE in its entirety and SUBSTITUTE with the following:

1. All work, materials, labor, costs, and time associated with installing painted red curb as specified in Appendix O – Red Curb Quantities shall be made at the contract unit price for **"Red Curb"** per LF. This shall also include payment for removal of existing red curb.

2. Payment for red curb specified as part of the striping plans shall be included in the lump sum bid items for each striping modification. See 314-5.7.

314-4.4.6 Payment. To the "WHITEBOOK", DELETE in its entirety.

314-5.7 Payment. To the "GREENBOOK", DELETE in its entirety and SUBSTITUTE with the following:

1. All work, materials, labor, costs, and time associated with removing traffic striping, pavement markings and thermoplastics, removal of pavement markers and devices, installing painted traffic striping and markings, installing thermoplastics, installing continental crosswalks, installing curb markings, replacement of existing channelizers replacement and installation of new pavement markers and devices shall be included in the lump sum bid item for **"Remove, Replace & Install Traffic Striping, Markers, Markings and Devices"** regardless of amount installed.

This Bid Item also includes payment for the removal of existing traffic striping, pavement markings, curb markings and pavement markers for streets requiring striping modifications as indicated below:

- a) **Canon St Striping, Signage & Electrical Improvement**
(0101854-1-D through 0101854-11-D).
- b) **Cardeno Dr Striping & Signage Improvement**
(0101856-01-D through 0101856-07-D).
- c) **Carmel Country Rd Striping, Signage & Electrical Improvement**
(0101855-01-D through 0101855-10-D).
- d) **Rosecrans St Striping, Signage & Electrical Improvement**
(0101858-1-D through 0101858-09-D).
- e) **Soledad Mountain Rd Striping & Signage Improvement**
(0101859-01-D through 0101859-07-D).
- f) **Sunset Cliffs Blvd Striping & Signage Improvement**
(0101861-01-D through 0101861-03-D).
- g) **Vista Sorrento Pkwy Striping, Signage & Electrical Improvement**
(0101860-01-D through 0101860-12-D).

2. All work, material, labor, costs, and time associated with installing painted traffic striping and markings, installing thermoplastics, installing continental crosswalks, installing curb markings, removing and installing traffic signage, installing pavement markers and devices, installing channelizers, and installing other markings in accordance with the Striping Plans in the following link:

https://drive.google.com/drive/folders/1IUtjVMMZeE40P2GXy64UNN_eG9M-s3j-

Payment shall be included in the lump sum Bid items for each striping modification.

- a) **Canon St Striping, Signage & Electrical Improvement**
(0101854-1-D through 0101854-11-D).
- b) **Cardeno Dr Striping & Signage Improvement**
(0101856-01-D through 0101856-07-D).
- c) **Carmel Country Rd Striping, Signage & Electrical Improvement**
(0101855-01-D through 0101855-10-D).
- d) **Rosecrans St Striping, Signage & Electrical Improvement**
(0101858-1-D through 0101858-09-D).
- e) **Soledad Mountain Rd Striping & Signage Improvement**
(0101859-01-D through 0101859-07-D).
- f) **Sunset Cliffs Blvd Striping & Signage Improvement**
(0101861-01-D through 0101861-03-D).
- g) **Vista Sorrento Pkwy Striping, Signage & Electrical Improvement**
(0101860-01-D through 0101860-12-D).

SECTION 403 – MANHOLE, SURVEY MONUMENT, AND GATE VALVE FRAMES AND COVERS ADJUSTMENT AND RECONSTRUCTION

403-3 MANHOLES AND GATE VALVES IN ASPHALT CONCRETE PAVEMENT. To the "WHITEBOOK", item 1, DELETE in its entirety and SUBSTITUTE with the following:

1. Manhole, sewer, and water valve covers shall be raised to be level with the surrounding pavement surface when such appurtenance are a minimum of one inch (1") below the final surface elevation after the slurry seal has been placed. Engineer to approve location prior to raising.

Appurtenance extending more than one inch (1") above the road surface shall be marked out as mill & pave and asphalt ramped to smooth transition.

To the "WHITEBOOK", ADD the following:

9. Manhole, sewer, and water valve covers shall be raised after the placement of the surface seal.

403-4 SURVEY MONUMENTS. To the "WHITEBOOK", DELETE in its entirety and SUBSTITUTE with the following:

1. The casing and cover for survey monuments shall be adjusted to the new grade using riser rings, when such appurtenances are 1.5" to 3.75" below the final surface elevation, in accordance with Standard Drawing M-10B, "Street Survey Monument Overlay Adjustment" and Standard Drawing M-10C, "Street Survey Monument Notes".

2. The Survey Monument Precast Concrete Pipe Box must be reconstructed in accordance with Standard Drawing M-10B for survey monuments that are greater than 0.5" and less than 1.5" below the final surface elevation or if the lid has been damaged.
3. The Survey Monument Precast Concrete Pipe Box must be reconstructed in accordance with Standard Drawings M-10A and Standard Drawings M-10B for survey monuments that are greater than 3.75" below the final surface elevation.
4. Survey monuments shall be adjusted or reconstructed after the placement of the surface seal.

403-5 MEASUREMENT AND PAYMENT. To the "WHITEBOOK", DELETE in its entirety and SUBSTITUTE with the following:

1. The payment for Raising Appurtenances to Grade, including sewer and water valve covers, all casings, extensions, concrete collars, and any necessary items to complete the work shall be made at the Bid unit **"Raise Appurtenance to Grade (Water, Sewer)"** for each appurtenance raised.
2. The payment for adjusting existing survey monument, including casing, frame, ring, covers, extensions, grout, brick support, sand base and any other material to grade shall be included in the Contract Bid Unit Price for **"Adjust Existing Survey Monument to Grade"** for each survey monument raised.
3. The payment for reconstructing the Survey Monument Precast Concrete Pipe Box, monument casing, frame, ring, covers, extensions, grout, brick support, sand base, and any other material required to reconstruct the survey monument precast concrete pipe box shall be included in the Contract Bid Unit Price for **"Reconstruct Survey Monument Box"** for each the Survey Monument Precast Concrete Pipe box reconstructed.
4. The payment for raising sewer and storm drain Manholes to grade, including casings, rings, extensions, concrete collars, asphalt, and any other materials, shall be made at the Bid unit price for **"Adjust Existing Manhole Frame and Cover to Grade"** for each manhole adjusted.
5. The payment for replacing Survey Monument Lids shall be made at the Bid unit price **"Survey Monument Lids"** for each lid replacement.

SECTION 404 – COLD MILLING

404-1 GENERAL. To the "WHITEBOOK", ADD the following:

8. Edges of milled areas shall be cut cleanly. The outside edges of the milled pavement may have a radius transition on the sides parallel to the cutting drum.

9. The presence of roots, pavement fabric, concrete, rubberized material or steel reinforcement within the depth to be cold milled have not been noted, marked out in the field, or quantified.
10. All milling shall be performed in such manner as to improve drainage, eliminate ponding, and re-establish gravity flow across intersections.
11. Material removed, regardless of removal method, shall be disposed of at a legal site.
12. Areas where excess asphalt resulting from successive overlay and or surface treatment, should be milled 6 foot wide, tapering from the lower edge at the edge of gutter to existing pavement surface.

Where specified in the contract documents and as specified by the Engineer, edge grind shall be tapered, 6 feet wide, along the edge of the street and along raised medians with gutters.

The edge grind shall remove variable depth from 0" to 2" of asphalt concrete. Additional edge cold milling may be required at various locations as determined by the Engineer.

404-6 COLD MILLING OF COMPOSITE PAVEMENTS. To the "WHITEBOOK", DELETE in its entirety and SUBSTITUTE with the following:

1. The areas and depths of composite pavement to be cold milled, sawn, or cut have not been identified in the field nor the Contract Documents.
2. Any pavement fabric encountered within the depth to be cold milled shall be disposed of at an approved facility within the jurisdiction of work.

404-6.1 Cold Milling Of Asphalt Concrete With Pavement Fabric Material. To the "WHITEBOOK", DELETE in its entirety and SUBSTITUTE with the following:

1. The area of pavement containing pavement fabric has not been measured out in the field, quantified, or identified in the Contract Documents.
2. Any pavement fabric encountered within the depth to be cold milled shall be disposed of at an approved facility within the jurisdiction of work.

404-9 TRAFFIC SIGNAL LOOP DETECTORS. To the "WHITEBOOK", ADD the following:

6. All damaged traffic detector loop and/or other detection systems located within or adjacent to the limits of work shall be replaced after resurfacing and striping. "Q" loops may be required at bike lanes. "E Modified" loops are required at stop bars. You shall install as many loops as necessary to meet current standards.

Loops may be installed in asphalt, concrete or any other material that may be encountered during installation.
7. The contractor shall provide the City with 3 Working Day written notice for evaluation of the loop layout.

404-12

PAYMENT. To the "WHITEBOOK", item 1 and item 4, DELETE in their entirety and SUBSTITUTE with the following:

1. The payment for installation of traffic detector loops and conduits shall be included in the bid item **"Traffic Detector Loop Replacement or Conduit Stub Installed"** for each loop or conduit installed. No additional payment shall be made for loop, detector, or conduit type.

No additional payment shall be made for milling, grinding, or saw cutting concrete, asphalt pavement fabric, and any other material that may be encountered during the installation.

4. The payment for cold milling of the existing pavement shall be included in the contract bid unit price for which the milling is required **"Asphalt Pavement Repair"**, and/or **"Crushed Miscellaneous Base"**, including hauling and disposal of milled material.

No additional payment shall be made for root pruning, milling, grinding, hauling, disposal or saw cutting concrete, and any other material that may be encountered during the installation.

No additional payment shall be made for the milling and grinding of pavement fabric.

To the "WHITEBOOK", ADD the following:

5. The payment for the hauling and disposal of asphalt pavement and fabric shall be included in the bid item **"Asphalt Concrete with Pavement Fabric Material"** per ton.

Payment for milling, grinding, or saw cutting asphalt pavement fabric shall be made included in the contract bid unit price for which the milling is required **"Asphalt Pavement Repair"**, and/or **"Crushed Miscellaneous Base"**.

6. The payment for edge grinding asphalt concrete, including hauling and disposal of milled material, shall be included in the Contract Price for **"Edge Grind AC Pavement (<2-inch)"** per LF.

SECTION 405 – MICRO-MILLING

405-1

GENERAL. To the "GREENBOOK", ADD the following:

Areas identified in the contract documents shall be micro-milled after the asphalt pavement repairs, base repairs, and/or edge grinding are completed.

405-4

WORK SITE MAINTENANCE. To the "GREENBOOK", ADD the following:

A self-loading motorized street sweeper equipped with both brooms and a vacuum system, and a functional water spray system shall immediately follow the milling machine. Sweeping shall continue until loose millings have been completely removed and as requested by the Engineer. The Contractor shall maintain the micro-milled surface until the surface treatment is applied.

405-7 **PAYMENT.** To the "GREENBOOK", DELETE in its entirety and SUBSTITUTE with the following:

Payment for micro-milling will be made at the unit price per square foot for "Micro-Mill AC Pavement (<1-inch)".

SECTION 601 – TEMPORARY TRAFFIC CONTROL FOR CONSTRUCTION AND MAINTENANCE WORK ZONES

601-3.5.1 **General.** To the "WHITEBOOK", item 3, DELETE in its entirety and SUBSTITUTE with the following:

3. Temporary "No Parking" and "No Stopping" signs shall be installed **72 hours** before enforcement. Temporary "No Parking" and "No Stopping" signs shall be installed and removed as specified in the WHITEBOOK. Signs shall indicate specific days, dates, and times of restriction. If violations occur, call Police Dispatch 619-531-2000 to enforce the Tow-Away notice.

601-7 **PAYMENT.** To the "WHITEBOOK", item 1 and item 4, DELETE in their entirety and SUBSTITUTE with the following:

1. The payment for traffic control Working Drawings, permits, traffic control Work including any traffic control devices that may be required by the City, shall be included in Lump Sum Bid Item for **"Traffic Control and Working Drawings."**
4. No separate or additional payment shall be made for the following: operation maintenance, repair, or replacement of Temporary Traffic (TTC) zone devices; all traffic control devices, required signs, notices, and detours; Working Drawings, Traffic Control Plans; Labor; and Traffic Control for asphalt pavement repair, surface seal, striping, loop installation, raising appurtenances (manholes, monuments, valves), or any other material relating to traffic control work.

SECTION 700 – DETECTORS

700-5.1 **Vehicle Detectors.** To the "WHITEBOOK", ADD the following:

7. Detector lead-in cables shall be installed where new Type 'Q' Detector loops are specified per the provided striping plans.

SECTION 701 – CONSTRUCTION

701-2 **PAYMENT.** To the "WHITEBOOK", item 5, ADD the following:

- u) The payment for furnishing and installing detector lead-in cable connecting new or existing traffic signal loops to controller shall be included in the Bid item **"Detector Lead-In Cable"** per LF installed.

SECTION 801 – INSTALLATION

801-7.1 Tree Trimming. To the “WHITEBOOK”, item 1, DELETE in its entirety and SUBSTITUTE with the following:

1. Trees shall be trimmed per ANSI A300 Standards for Tree Care Operations so as to provide adequate clearance for construction equipment during asphalt preparatory work and/or surface seal operations. Tree trimming shall include:

Removal of low branches overhanging residential, collector, or major streets to a height above street grade of 14 feet (4.3 m) unless directed otherwise.
 - a) The Contractor shall complete all tree trimming work prior any asphalt preparatory work and/or surface seal operation.
 - b) A tree trimming schedule shall be provided to the Engineer for approval.

801-9 PAYMENT. To the “WHITEBOOK”, item 2, DELETE in its entirety and SUBSTITUTE with the following:

2. The payment for tree trimming shall be included in the Contract Price.

SECTION 1001 – CONSTRUCTION BEST MANAGEMENT PRACTICES (BMPs)

1001-1 GENERAL. To the “WHITEBOOK”, ADD the following:

8. Based on a preliminary assessment by the City, this Contract is subject to **WPCP**.

1001-1.11 Post-Construction Requirements. To the “WHITEBOOK”, item 2, DELETE in its entirety and SUBSTITUTE with the following:

2. You shall mark every storm drain inlet within the project boundaries with stenciled inlet markings or imbedded concrete stamps. You shall use stenciled inlet markings on existing inlets and concrete stamps on new inlets. On curb inlets, the concrete stamp or stenciled inlet markings shall be placed on the top of the curb at the inlet roof. On catch basins, the concrete stamp shall be imprinted next to the inlet grate.

To the “WHITEBOOK”, ADD the following:

5. You shall remove any damaged decal-disk inlet markers.
6. You shall comply with the following post-construction requirements: Storm Drain Inlet Markings.
7. The stencil shall be approximately 3' x 7-1/4" in size.
8. White and blue waterborne traffic paint shall be used for the inlet markings.

9. You shall apply a white base with stenciled blue lettering.
10. You shall allow sufficient time for the base to dry prior to applying the lettering.
11. A copy of the stencil shall be provided at the pre-construction meeting.

1001-4.2 Payment. To the "WHITEBOOK", ADD the following:

4. All work, materials, labor, costs, and time associated with installing stenciled inlet marking shall be paid at the unit bid price **"Post-construction Requirements - Inlet Markings"** for each stenciled marking installed.
 5. The unit bid price for **"Post-construction Requirements - Inlet Markings"** shall include the cost of removal of any decal-disk inlet markers.
-

SUPPLEMENTARY SPECIAL PROVISIONS

APPENDICES

APPENDIX A

NOTICE OF EXEMPTION



**SAN DIEGO COUNTY CLERK
CEQA FILING COVER SHEET**

FILED
Jul 19, 2024 02:15 PM
JORDAN Z. MARKS
SAN DIEGO COUNTY CLERK
File # 2024-000627
State Receipt # 37071920240583

THIS SPACE FOR CLERK'S USE ONLY

Complete and attach this form to each CEQA Notice filed with the County Clerk

TYPE OR PRINT CLEARLY

Project Title

FISCAL YEAR 2025 ROAD MAINTENANCE AND REHABILITATION ACCOUNT (RMRA) FUND PROPOSED PROJECT
LIST AND APPROVAL OF SIX SLURRY SEAL GROUPS 2521, 2522, 2523, 2524, 2525, AND 2526 TO BE FUNDED BY BY
RMRA FUNDS

Check Document being Filed:

- ☐ Environmental Impact Report (EIR)
☐ Mitigated Negative Declaration (MND) or Negative Declaration (ND)
☒ Notice of Exemption (NOE)
☐ Other (Please fill in type):

**FILED IN THE OFFICE OF THE SAN DIEGO
COUNTY CLERK ON** July 19, 2024
Posted July 19, 2024 **Removed** _____
Returned to agency on _____
DEPUTY _____

Filing fees are due at the time a Notice of Determination/Exemption is filed with our office. For more information
on filing fees and No Effect Determinations, please refer to California Code of Regulations, Title 14, section 753.5.

NOTICE OF EXEMPTION

TO: X Recorder County Clerk
P.O. Box 1750, MS-A-33
1600 Pacific Hwy, Room 260
San Diego, CA 92101-2422

FROM: City of San Diego
City Planning Department
202 C Street
San Diego, CA 92101

X Office of Planning and Research
1400 Tenth Street, Room 121
Sacramento, CA 95814

PROJECT TITLE: Fiscal Year 2025 Road Maintenance and Rehabilitation Account (RMRA) Funds Proposed Project List and Approval of Six Slurry Seal Contracts for Slurry Seal Groups 2521, 2522, 2523, 2524, 2525, and 2526 to be Funded by RMRA Funds

PROJECT LOCATION-SPECIFIC: The projects are located in the following Community Planning areas: City Heights, College Area, Eastern Area, Kensington-Talmadge, Navajo, Normal Heights, Southeastern San Diego, Encanto, Otay Mesa, Otay Mesa-Nestor, San Ysidro, Skyline-Paradise Hills, Barrio Logan, Downtown, Greater Golden Hill, Greater North Park, Mission Valley, Uptown, Carmel Valley, Clairemont Mesa, La Jolla, Midway-Pacific Highway, Mission Beach, Ocean Beach, Pacific Beach, Peninsula, Torrey Hills, Torrey Pines, Kearny Mesa, Linda Vista, Mira Mesa, Serra Mesa, Tierrasanta, University, Black Mountain Ranch, Carmel Mountain Ranch, Miramar Ranch North, Rancho Bernardo, Rancho Encantada, Rancho Penasquitos, and Scripps Miramar Ranch in Council Districts 1, 2, 3, 4, 5, 6, 7, 8, and 9. See Exhibit A for specific locations.

PROJECT LOCATION-CITY/COUNTY: San Diego/San Diego

DESCRIPTION OF NATURE AND PURPOSE OF THE PROJECT:

The Road Repair and Accountability Act of 2017, which established the Road Maintenance and Rehabilitation Account (RMRA), was signed into law by the Governor on April 28, 2017 as a means to address basic road maintenance, rehabilitation, and critical safety needs on both the state highway and local streets and road systems. Per State and Highway Code (SHC) Section 2030(a), RMRA funds shall be prioritized for expenditure on basic road maintenance and rehabilitation projects, and on critical safety projects.

SHC Section 2030(b)(1) provides a number of example projects and uses for RMRA funding that include, but are not limited to, the following:

- Road maintenance and rehabilitation
- Safety projects
- Railroad Grade Separations
- Complete Street components (including active transportation elements, pedestrian and safety projects, transit facilities, and drainage and stormwater capture projects in conjunction with any other allowable project)
- Traffic control devices

SHC Section 2030(b)(2) states that funds made available by the program may also be used to satisfy a match requirement to obtain state or federal funds for projects authorized by this subdivision.

Pursuant to SHC Section 2037, a City or County may spend an apportionment of RMRA funds on transportation priorities other than those outlined in SHC Section 2030 if the City's or County's average Pavement Condition Index (PCI) meets or exceeds 80. The City of San Diego does not qualify

to spend RMRA funds on other transportation priorities as the average PCI on the last pavement condition assessment completed in 2023 was a 63.

RMRA has become a critical funding source for the City's Street Maintenance Program over the past few years and will help ensure that the City continues to maintain pavement conditions. This consistent funding stream has supported regular preventative maintenance that keeps treated roads from becoming more dangerous and expensive to repair.

A requirement of the program is the approval of a project list by the governing body via Resolution, which is due to the California Transportation Commission by July 1, 2024.

The proposed project includes City Council approval of the Fiscal Year 2025 project list and the approval of six slurry seal contracts for Slurry Seal Groups 2521, 2522, 2523, 2524, 2525, and 2526 to be funded by RMRA funds (Exhibit A). The project list includes streets planned for maintenance and repair in all nine (9) Council Districts and will include approximately 238 lane miles (approximately 128 repair miles) of streets that will have slurry seal or cape seal treatments.

A cape seal project combines the application of a chip seal or scrub seal followed by a slurry seal. A cape seal begins with the application of a chip seal or scrub seal. A chip seal involves the placement of a layer of asphalt emulsion followed by the application of aggregate chips (usually small-sized gravel) over the asphalt emulsion. This is then rolled and compacted to create a durable and skid-resistant surface. Scrub seals are very similar to chip seals described above with the addition of a series of brooms that follow the application of the asphalt emulsion. These brooms, referred to as "scrub brooms", work the emulsion into the surface cracks which helps ensure the surface is completely sealed. After the chip or scrub seal is complete, the surface is overlaid with a slurry seal.

Slurry Seal is an asphalt street surface treatment which consists of sand, emulsion, and water applied as a thin layer up to 3/8-inch thick. Minor surface repairs are completed by the pavement specialists prior to the application of the slurry seal.

These slurry seal and cape seal treatments will also include the installation of high-visibility crosswalk striping after the application of cape seal, scrub seal, or slurry seal to improve pedestrian crossings. Slurry seal and cape seal projects may also include the implementation of bicycle network improvements including bicycle facilities, bicycle striping, and safety improvements.

Slurry Seal Group 2521 involves the application of a slurry seal or cape seal on approximately 38.4 lane miles (approximately 20.9 repair miles) of streets in Council Districts 7 and 9. The proposed slurry seal activities will occur in the Mid-City: City Heights, College Area, Mid-City: Eastern Area, Mid-City: Kensington-Talmadge, Navajo, Mid-City: Normal Heights, and Southeastern San Diego Community Planning areas.

Slurry Seal Group 2522 involves the application of a slurry seal or cape on approximately 36.3 lane miles (19.2 repair miles) of streets in Council Districts 4 and 8. The proposed slurry seal activities will occur in the Eastern Area, Encanto, Otay Mesa, Otay Mesa-Nestor, San Ysidro, and Skyline-Paradise Hills Community Planning Areas.

Slurry Seal Group 2523 involves the application of a slurry seal or cape seal on approximately 34.2 lane miles (22.1 repair miles) of streets in Council Districts 3, 4, and 8. The proposed slurry seal activities will occur in the Barrio Logan, Downtown, Encanto, Greater Golden Hill, Greater North Park, Mission Valley, Skyline-Paradise Hills, Southeastern San Diego, and Uptown Community Planning Areas.

Slurry Seal Group 2524 involves the application of a slurry seal or cape seal on approximately 41.2 lane miles (22.7 repair miles) of streets in Council Districts 1 and 2. The proposed slurry seal

activities will occur in the Carmel Valley, Clairemont Mesa, La Jolla, Midway-Pacific Highway, Mission Beach, Ocean Beach, Pacific Beach, Peninsula, Torrey Hills, and Torrey Pines Community Planning Areas.

Slurry Seal Group 2525 involves the application of a slurry seal or cape seal on approximately 47.9 lane miles (24.1 repair miles) of streets in Council Districts 2, 6, and 7. The proposed slurry seal activities will occur in the Clairemont Mesa, Kearny Mesa, Linda Vista, Mira Mesa, Serra Mesa, Tierrasanta, and University Community Planning Areas.

Slurry Seal Group 2526 involves the application of a slurry seal or cape seal on approximately 39.8 lane miles (19.5 repair miles) of streets in Council Districts 5 and 6. The proposed slurry seal activities will occur in the Black Mountain Ranch, Carmel Mountain Ranch, Mira Mesa, Miramar Ranch North, Rancho Bernardo, Rancho Encantada, Rancho Penasquitos, and Scripps Miramar Ranch Community Planning Areas.

All work would occur within the public right of-way (paved streets) or previously disturbed non-sensitive areas only. Stormwater Best Management Practices (BMPs) to prevent non-stormwater discharges from entering the City's stormwater conveyance system, as well as Traffic Control Plans (TCPs), will be implemented throughout construction.

NAME OF PUBLIC AGENCY APPROVING PROJECT: City of San Diego

NAME OF PERSON OR AGENCY CARRYING OUT PROJECT: City of San Diego Transportation Department, 2781 Caminito Chollas, San Diego, CA 92105. Contact: Joshua Lahmann, Senior Civil Engineer. E-mail: jlahmann@sandiego.gov. Phone Number: (619) 527-7509.

EXEMPT STATUS:

☐ MINISTERIAL

☐ DECLARED EMERGENCY

☐ EMERGENCY PROJECT

☒ CATEGORICAL EXEMPTION: CEQA Guidelines Sections 15301(c)(Existing Facilities), 15302 (Replacement or Reconstruction), and 15304 (Minor Alterations to Land)

☐ STATUTORY EXEMPTION

☐ COMMON SENSE EXEMPTION

REASONS WHY PROJECT IS EXEMPT:

The City of San Diego conducted an environmental review that determined the project would not have the potential for causing a significant effect on the environment pursuant to State CEQA Guidelines Section 15301(c) (Existing Facilities) which exempts the operation, repair, maintenance, permitting, leasing, licensing, or minor alteration of existing public or private structures, facilities, mechanical equipment, or topographical features, involving negligible or no expansion of existing or former use, including existing highways and streets, sidewalks, gutters, bicycle and pedestrian trails, and similar facilities (this includes road grading for the purpose of public safety), and other alterations such as the addition of bicycle facilities, including but not limited to bicycle parking, bicycle-share facilities and bicycle lanes, transit improvements such as bus lanes, pedestrian crossings, street trees, and other similar alterations that do not create additional automobile lanes; Section 15302 (Replacement or Reconstruction) which exempts the replacement or reconstruction of existing structures and facilities where the new structure will be located on the same site as the structure replaced and will have substantially the same purpose and capacity as the structure replaced; and Section 15304 (Minor Alterations to Land) which exempts minor public or private alterations in the condition of land, water, and/or vegetation which do not involve removal of healthy, mature, scenic trees except for forestry or agricultural purposes. The exceptions to the

exemptions listed in CEQA Guidelines Section 15300.2 would not apply in that no cumulative impacts were identified; no significant effects on the environment were identified; the projects would not result in damages to an officially designated state scenic highway; and no historical resources would be affected by the action. As to the exception for hazardous materials, the proposed projects would only involve the repair, maintenance, and/or rehabilitation of existing City streets and would not involve any excavation into previously undisturbed soils which would expose potentially hazardous materials. Therefore, the proposed project would not preclude the use of a CEQA exemption pursuant to Section 65962.5 of the Government Code. R-315598

CONTACT PERSON: Edgar Ramirez Manriquez, Associate Planner
City of San Diego, City Planning Department
202 C Street
San Diego, CA 92101

IF FILED BY APPLICANT:

1. ATTACH CERTIFIED DOCUMENT OF EXEMPTION FINDING

2. HAS A NOTICE OF EXEMPTION BEEN FILED BY THE PUBLIC AGENCY APPROVING THE PROJECT?

(X) YES () NO

IT IS HEREBY CERTIFIED THAT THE CITY OF SAN DIEGO HAS DETERMINED THE ABOVE ACTIVITY TO BE EXEMPT FROM CEQA.

Elena Pascual

Elena Pascual, Senior Planner

City of San Diego City Planning Department

Filed by: *Kristell Gordon* 5/9/2024

Signature

Date

Legislative Recorder

Title

CHECK ONE:

(X) SIGNED BY LEAD AGENCY

DATE RECEIVED FOR FILING WITH COUNTY CLERK OR OPR:

() SIGNED BY APPLICANT

Heinold, June 11, 2024

CITY OF SAN DIEGO - TRANSPORTATION DEPARTMENT

FY2025 Road Maintenance and Rehabilitation Account Project List

Exhibit A

Project Title	Segment ID	Street Name	Cross Street 1	Cross Street 2	Council District	Project Location (Community Planning Area)	Activity	Project Description	Estimated Construction Dates		Estimated Useful Life (# of years)		Functional Classification
									Begin	End	Min	Max	
S2520	SS-029541-PV1	S 46TH ST	BEGIN	OCEAN VIEW BL	4	SOUTHEASTERN SAN DIEGO	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2520	SS-029542-PV1	Q1ST AV	UPAS ST	W WALNUT AV	8	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Collector
S2523	SS-030006-PV2	03RD AV	WASHINGTON ST	LEWIS ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Local
S2523	SS-030007-PV2	03RD AV	UPAS ST	WALNUT AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030007-PV2	03RD AV	THORN ST	UPAS ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030015-PV1	05TH AV	REDFORD ST	SPURGE ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Collector
S2528	SS-030006-PV1	ALBATROSS ST	W OLIVE ST	W PALM ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2528	SS-030010-PV1	ALBATROSS ST	W KALAMIA ST	W LAUREL ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030011-PV1	ALBATROSS ST	W JUNIPER ST	W KALAMIA ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030012-PV1	ALBATROSS ST	W IVY ST	W JUNIPER ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030038-PV2	ALBERTA PL	HAWK ST	END	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030224-PV1	ALTAMIRA PL	SIERRA VISTA	VALLE VISTA	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030227-PV1	ALTAMIRA PL	HERMOSA WY	SIERRA VISTA	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030238-PV1	ALTURA PL	HERMOSA WY	SIERRA VISTA	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030399-PV1	BARNSON PL	BRANT ST	W OLIVE ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030478-PV1	BRANT ST	UNIVERSITY PL	W UNIVERSITY AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030478-PV1	BRANT ST	UNIVERSITY PL	UNIVERSITY PL	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030493-PV1	BRANT ST	BARNSON PL	W OLIVE ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030493-PV1	BRANT ST	W NUTMEG ST	BARNSON PL	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030589-PV1	BUSH ST	HAWK ST	HAWK ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030589-PV1	BUSH ST	GOLDFRICH ST	HAWK ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030589-PV1	CAMPUS AV	MORROW AV	MADISON AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030589-PV1	CAMPUS AV	TYLER AV	VAN BUREN AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Collector
S2523	SS-030589-PV1	CAMPUS AV	MEADE AV	MORROW AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030589-PV1	CAMPUS AV	VAN BUREN AV	MEADE AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030642-PV1	CURLEW ST	W BROOKES AV	OTSEGO DR	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Collector
S2523	SS-030642-PV1	CURLEW ST	REYNARD WY	W BROOKES AV	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Residential
S2523	SS-031349-PV1	FORT STOCKTON DR	GOLDFRICH ST	HAWK ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Collector
S2523	SS-031350-PV1	FORT STOCKTON DR	GOLDFRICH ST	GOLDFRICH ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Collector
S2523	SS-031354-PV1	FORT STOCKTON DR	W LEWIS ST	SIERRA VISTA	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Collector
S2523	SS-031564-PV1	FRONT ST	W UPAS ST	W WALNUT AV	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032366-PV1	GOLDFRICH ST	W UNIVERSITY AV	W WASHINGTON ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Collector
S2523	SS-032366-PV1	HAWK ST	W WASHINGTON ST	FORT STOCKTON DR	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Collector
S2523	SS-032366-PV1	HERMOSA WY	TERALTA PL	VALLE VISTA	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032366-PV1	HERMOSA WY	ALTAMIRA PL	TERALTA PL	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032366-PV1	HERMOSA WY	ALTURA PL	ALTAMIRA PL	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032366-PV1	HERMOSA WY	W MONTECITO WY	ALTURA PL	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032366-PV1	MARYLAND ST	TYLER AV	MARYLAND PL	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Collector
S2523	SS-032366-PV1	MARYLAND ST	MORROW WY	TYLER AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Collector
S2523	SS-030685-PV1	ORZABA AV	MILLER ST	BANDINI ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030685-PV1	ORZABA AV	BANDINI ST	COJITS ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Residential
S2523	SS-030685-PV1	ORZABA AV	ARDEN WY	MILLER ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Residential
S2523	SS-031078-PV1	PALMETTO WY	W MONTECITO WY	W ARBOR DR	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032306-PV1	05TH AV	06TH AV	06TH AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Collector
S2523	SS-032312-PV1	RHODE ISLAND ST	HOFFMAN ST	MADISON AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032312-PV1	RHODE ISLAND ST	BEGIN	HOFFMAN ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032643-PV1	THORN ST	03RD AV	04TH AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032702-PV1	TYLER AV	CLEVELAND AV	CAMPUS AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032702-PV1	TYLER AV	MARYLAND ST	CLEVELAND AV	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032702-PV1	UNION ST	W THORN ST	W UPAS ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032702-PV1	UNIVERSITY PL	BRANT ST	END	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032702-PV1	WALNUT VISTA	Q1ST AV	ALTAMIRA PL	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032856-PV1	W JUNIPER ST	Q1ST AV	FRONT ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032856-PV1	W LEWIS ST	STEPHENS ST	FORT STOCKTON DR	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Collector
S2523	SS-032944-PV1	W MONTECITO WY	BIS ST	JACKDAW ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032951-PV1	W OLIVE ST	ALBATROSS ST	BARNSON PL	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032954-PV1	W OLIVE ST	BRANT ST	BRANT ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-032955-PV1	W PALM ST	FRONT ST	ALBATROSS ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Residential
S2523	SS-033046-PV1	W UNIVERSITY AV	DOVE ST	EAGLE ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Collector
S2523	SS-033047-PV1	W UNIVERSITY AV	EAGLE ST	FALCON ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Collector
S2523	SS-033048-PV1	W UNIVERSITY AV	FALCON ST	GOLDFRICH ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Collector
S2523	SS-033051-PV1	W UNIVERSITY AV	FRONT ST	ALBATROSS ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Collector
S2523	SS-033053-PV1	W UNIVERSITY AV	ALBATROSS ST	BRANT ST	3	UPTOWN	AC - Cape Seal	Cape Seal	11/2024	04/2025	5	8	Collector
S2523	SS-033059-PV1	W UPAS ST	Q1ST AV	FRONT ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Collector
S2523	SS-033078-PV1	W WALNUT AV	ALBATROSS ST	ALBATROSS ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Collector
S2523	SS-033078-PV1	W WALNUT AV	FRONT ST	ALBATROSS ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Collector
S2523	SS-033078-PV1	W WALNUT AV	Q1ST AV	FRONT ST	3	UPTOWN	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	04/2025	5	8	Collector
S2524	SS-033370-PV1	CARMEL COUNTRY RD	DEL MAR MESA RD	SHAW VALLEY RD	1	CARMEL VALLEY	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-033370-PV1	CARMEL COUNTRY RD	SAGAMORE WY	DEL MAR MESA RD	1	CARMEL VALLEY	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-033370-PV1	OCEAN VALLEY LN	BEIGH	CARMEL CENTER RD	1	CARMEL VALLEY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-033370-PV1	TIMBER RIDGE RD	CORRETT CT	CHAPARRAL RIDGE RD	1	CARMEL VALLEY	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-033370-PV1	DENVER ST	KANE ST	JELLY ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-033370-PV1	ERIE ST	KANE ST	JELLY ST	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-033370-PV1	ERIE ST	LISTER ST	KANE ST	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-033370-PV1	ERIE ST	LITTLEFIELD ST	ASHTON ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-033370-PV1	FRANKFORT ST	KANE ST	JELLY ST	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential

Project Title	Segment ID	Street Name	Cross Street 1	Cross Street 2	Council District	Project Location (Community Planning Area)	Activity	Project Description	Estimated Construction Dates	Estimated Useful Life (# of years)	Functional Classification		
									Begin	End	Min	Max	
52524	SS-011299-PV1	GILVESTON ST	GARDENA AV	ASHTON ST	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-012052-PV1	GEORGETOWN AV	GOLDBORO ST	GASCONADE AV	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-012053-PV1	GEORGETOWN AV	GOLDBORO ST	CROSS ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-012091-PV1	GENESER ST	BAY CANYON CT	EDISON ST	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-012098-PV1	GENESER ST	BAY CANYON CT	GENESER PL	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-012380-PV1	GOLDBORO ST	GEORGETOWN AV	GENESER PL	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-012385-PV1	GOLDFIELD ST	GALILEA AV	ASHTON ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-013122-PV1	HARTFORD ST	HUXLEY ST	CLAIREMONT DR	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-014902-PV1	KANE ST	ERIE ST	FRANKFORT ST	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-002228-PV1	ALTA LA JOLLA DR	CALLE MIRAMAR	CALLE DELCADA	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-002666-PV1	ARENAS ST	LA JOLLA BL	DRAPER AV	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-003103-PV1	AVNDA CHAMINEZ	VIA ESPANA	END	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-003861-PV1	BAHIA LN	BAHIA WY	CORAL REEF AV	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-003862-PV1	BAHIA LN	PARKVIEW TR	BAHIA WY	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-003864-PV1	BAHIA WY	THUNDERBIRD LN	LA JOLLA	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-003930-PV1	BELLEVUE AV	COLUMA ST	MIDWAY ST	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-004074-PV1	BRODIAEA WY	ROMERO DR	ENCINIA DR	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-005263-PV1	CARDENO DR	VIA CABRERA	LA JOLLA SCENIC S DR	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-005263-PV1	CARDENO DR	VIA NINA	VIA CABRERA	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-009443-PV1	DRAPER AV	FAIRWAY RD	LA JOLLA KNOLL	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-009443-PV1	DRAPER AV	SILVER ST	KLING ST	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-010885-PV1	CARDENO DR	KAMALINO LN	SILVER ST	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-011385-PV1	FOURWARD ST	LA JOLLA BL	CALLE VAQUERO	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-012160-PV1	GIRARD AV	PEARL ST	LA JOLLA HERMOSA AV	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-015518-PV1	LA JOLLA BL	WIRETON DR	TURKOWNS ST	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-015521-PV1	LA JOLLA BL	PROSPECT ST	COAST SOLITE BL	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-015549-PV1	LA JOLLA HERMOSA AV	COLUMA ST	MIDWAY ST	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-015560-PV1	LA JOLLA MESA DR	VAN NUYS ST	COLUMA ST	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-015577-PV1	LA JOLLA RANCHO RD	RAVENSWOOD RD	BOX CANYON RD	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-015682-PV1	LA PIUTURA DR	AVILA CT	OLITE CT	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-016846-PV1	LOOKOUT DR	BOULEVARD PL	SOLEDAO AV	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-020509-PV1	OLIVETAS AV	MARINE ST	PEARL ST	1	LA JOLLA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-023457-PV1	ROMERO DR	BEGIN	BACDIAEA WY	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-023815-PV1	RUSHVILLE ST	DRAPER AV	EADS AV	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-025171-PV1	SOLEDAO MTH RD	AL BAHAR DR	LUDINGTON PL	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-025175-PV1	SOLEDAO MTH RD	FALOMINO CR	SOLEDAO RD	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-025175-PV1	SOLEDAO MTH RD	SOLEDAO MTH RD	PALM CANYON DR	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-025185-PV1	SOLEDAO MTH RD	SOLEDAO MTH RD	PALM CANYON DR	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-027680-PV1	VIA CORONA	GOLF DE ORO DR	FALOMINO CR	1	LA JOLLA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-012880-PV1	HANDCOCK ST	CHANNEL WY	BUTTERS RD	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-023528-PV1	ROSECRANS PL	ROSECRANS ST	SPORTS ARENA BL	2	MIDWAY-PACIFIC HIGHWAY	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-023530-PV1	ROSECRANS ST	ROSECRANS ST	CAGE ST	2	MIDWAY-PACIFIC HIGHWAY	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-023541-PV1	ROSECRANS PL	MADRID ST	NORTH EVERGREEN ST	2	MIDWAY-PACIFIC HIGHWAY	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-031742-PV1	ST CHARLES ST	MALAGA ST	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Major	
52524	SS-031742-PV1	HERMITAGE VIEW PL	DURHAM RIDGE DR	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Major	
52524	SS-031746-PV1	DURHAM RIDGE DR	ST CHARLES ST	ROSECRANS PL	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-031749-PV1	MENDONCA DR	BARNETT AV	MANITOWOC WY	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-031750-PV1	MENDONCA DR	MANITOWOC WY	TUSCALOOSA ST	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-031753-PV1	MENDONCA DR	TUSCALOOSA ST	ST CHARLES ST	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-019159-PV1	SHOP DR	BEGIN	TUSCALOOSA ST	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-019159-PV1	SHOP DR	TUSCALOOSA ST	MENDONCA DR	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-019159-PV1	PELLU WY	BARNETT AV	TUSCALOOSA ST	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-019159-PV1	TUSCALOOSA ST	BARNETT AV	MCDR GATE 2	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-019159-PV1	TUSCALOOSA ST	GUAM WY	PELLU WY	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-019159-PV1	TUSCALOOSA ST	PELLU WY	SHOP DR	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-019159-PV1	TUSCALOOSA ST	SHOP DR	MENDONCA DR	2	MIDWAY-PACIFIC HIGHWAY	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-018484-PV1	MISSION BL	SANTA RITA PL	WAVECREST CT	2	MISSION BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-018523-PV1	MISSION BL	REDONCT CT	ROCKAWAY CT	2	MISSION BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-003870-PV1	BACON ST	NARRAGANSETT AV	NIAGARA AV	2	OCEAN BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-003289-PV1	CABLE ST	VOLTAIRE ST	LOTUS ST	2	OCEAN BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-005284-PV1	CABLE ST	SANTA CRUZ AV	DEL MONTE AV	2	OCEAN BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-003939-PV1	DEL MONTE AV	SUNSET CLIFFS BL	CABLE ST	2	OCEAN BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-009464-PV1	EBERS ST	BRIGHTON AV	LONG BRANCH AV	2	OCEAN BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-018993-PV1	NIAGARA AV	BACON ST	END	2	OCEAN BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-024285-PV1	SANTA CRUZ AV	FROUDE ST	EBERS ST	2	OCEAN BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-024364-PV1	SARATOGA AV	AIRKITT ST	END	2	OCEAN BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-023904-PV1	SUNSET CLIFFS BL	PESCADERO AV	ORCHARD AV	2	OCEAN BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-023905-PV1	SUNSET CLIFFS BL	BERMUDA AV	PESCADERO AV	2	OCEAN BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-023906-PV1	SUNSET CLIFFS BL	POINT LOMA AV	BERMUDA AV	2	OCEAN BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-023827-PV1	VOLTAIRE ST	SUNSET CLIFFS BL	CABLE ST	2	OCEAN BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-023789-PV1	COLLINGWOOD DR	BEGIN	JEWELL ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-006798-PV1	DAWES ST	REED AV	THOMAS AV	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-006799-PV1	DAWES ST	OLIVER AV	REED AV	1	PACIFIC BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-006800-PV1	DAWES ST	PACIFIC BEACH DR	OLIVER AV	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-005862-PV1	BEATL ST	CRYSTAL DR	EVERTS ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-003018-PV1	EMERALD ST	DAWES ST	EVERTS ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential

CITY OF SAN DIEGO - TRANSPORTATION DEPARTMENT
FY2025 Road Maintenance and Rehabilitation Account Project List

Exhibit A

Project Title	Segment ID	Street Name	Cross Street 1	Cross Street 2	Council District	Project Location (Community Planning Area)	Activity	Project Description	Estimated Construction Dates		Estimated Useful Life (# of years)		Functional Classification
									Begin	End	Min	Max	
S2524	SS-010895-PV1	PANUEL ST	GARNET AV	FELSPAR ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-010870-PV2	GARNET AV	PENDELTON ST	BALBOA AV	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-010870-PV2	GARNET AV	PENDELTON ST	PENDELTON ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-011879-PV1	GARNET AV	NOYES ST	OLNEY ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-011879-PV2	GARNET AV	PANUEL ST	GRESHAM ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-011880-PV1	GARNET AV	EVERTS ST	PANUEL ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-011881-PV2	GARNET AV	MORRELL ST	NOYES ST	1	PACIFIC BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
S2524	SS-013752-PV1	HORNBLOND ST	CASS ST	DAWES ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-013568-PV1	LA JOLLA MESA DR	AGATE ST	ARCHER ST	1	PACIFIC BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
S2524	SS-015991-PV1	LA PLAYA AV	RIVIERA DR	HAINES ST	1	PACIFIC BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
S2524	SS-020179-PV1	NOYES ST	HORNBLOND ST	GARNET AV	1	PACIFIC BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
S2524	SS-020486-PV1	OLIVER AV	GRESHAM ST	HAINES ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-020489-PV1	OLIVER AV	DAWES ST	EVERTS ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-020521-PV1	CINIFY ST	EMERALD ST	DIAMOND ST	1	PACIFIC BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
S2524	SS-020522-PV1	CINIFY ST	FELSPAR ST	EMERALD ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-023459-PV1	RODNEY RD	SAN AQUILARIO DR	PACHICA DR	1	PACIFIC BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-023460-PV1	RODNEY RD	PENDELTON ST	SAN AQUILARIO DR	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-025384-PV1	THOMAS AV	LAMONT ST	MORRELL ST	1	PACIFIC BEACH	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-025389-PV1	THOMAS AV	DAWES ST	EVERTS ST	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-026940-PV1	TURQUOISE ST	WRELTION DR	LA JOLLA MESA DR	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-026945-PV1	TURQUOISE ST	LA JOLLA BL	END	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-028366-PV1	WESTKNOLL DR	WESTKNOLL LN	WRELTION DR	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-030034-PV1	HILL ST	ALBION ST	CALLE VAQUERO	1	PACIFIC BEACH	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030068-PV1	ALCOTT ST	ALCOTT CT	ULLMAN ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030069-PV1	ALCOTT ST	CHATSWORTH BL	POINSETTIA DR	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030232-PV1	ALGECRAS ST	CORNISH DR	CORVOYA ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030247-PV1	ARMADA TR	BESSEMER ST	TALBOT ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030317-PV1	AVENIDA DE PORTUGAL	EVERGREEN ST	WILLOW ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030318-PV1	AVENIDA DE PORTUGAL	LOCUST ST	EVERGREEN ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030319-PV1	AVENIDA DE PORTUGAL	ROSCREANS ST	LOCUST ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030319-PV1	BANGOR ST	BANGOR FL	CONCORD ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030319-PV1	BANGOR ST	VALEMONT ST	BANGOR FL	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030325-PV1	BANGOR ST	ULLMAN ST	VALEMONT ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030326-PV1	BANGOR ST	TRUMBULL ST	ULLMAN ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030482-PV1	BRINSON ST	CORNISH DR	CORVOYA ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030510-PV1	CANON ST	LOCUST ST	EVERGREEN ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-030511-PV1	CANON ST	ROSCREANS ST	LOCUST ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-030515-PV1	CANON ST	SHAFER ST	SCOTT ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-030517-PV1	CANON ST	AKORH ST	DEL MAR AV	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030628-PV1	CAPSTRANO ST	POE ST	QUIMBY ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
S2524	SS-030647-PV1	CARMELO ST	CORNISH DR	CORVOYA ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030649-PV1	CARMELO ST	CORVOYA ST	SUNSET CLIFFS BL	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030650-PV1	CASITAS ST	AMFORD DR	CORNISH DR	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030704-PV1	CHATSWORTH BL	ALCOTT ST	BROWNING ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-030743-PV1	CLOVE ST	FENELON ST	GARRISON ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030768-PV1	CONCORD ST	VALEMONT ST	BANGOR ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030768-PV1	CONCORD ST	ULLMAN ST	VALEMONT ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030768-PV1	CONCORD ST	CONCORD ST	TRUMBULL ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030768-PV1	CONCORD ST	HILL ST	TRUMBULL ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030794-PV1	CORVOYA ST	LADERA ST	CASITAS ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
S2524	SS-030795-PV1	CORNISH DR	ALGE CIRAS ST	ALGECRAS ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030795-PV1	CORNISH DR	CARMELO ST	ALGE CIRAS ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030797-PV1	CORNISH DR	LADERA ST	CASITAS ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030848-PV1	CURTIS ST	POINSETTIA DR	END	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030903-PV1	DEL MONTE AV	BEGIN	FROUDE ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030922-PV1	DICKENS ST	ROSCREANS ST	LOCUST ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-030952-PV1	DUMAS ST	LOCUST ST	EVERGREEN ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-031001-PV1	ELLIOTT ST	CLOVE ST	CHATSWORTH BL	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-031002-PV1	ELLIOTT ST	WILLOW ST	CLOVE ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-031003-PV1	ELLIOTT ST	EVERGREEN ST	WILLOW ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-0310630-PV1	EVERGREEN ST	IBSEN ST	JAMES ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-031021-PV1	FENELON ST	PULM ST	CLOVE ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-031148-PV1	FREEMAN ST	LOCUST ST	EVERGREEN ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
S2524	SS-0311624-PV1	FROUDE ST	SANTA CRUZ AV	DEL MONTE AV	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-0311896-PV1	GARRISON ST	PULM ST	CLOVE ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Collector
S2524	SS-0312383-PV1	GOLDSMITH ST	ROSCREANS ST	LOCUST ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-0313054-PV1	HARBOR VIEW DR	HARBOR VIEW PL	BESSEMER ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-0313056-PV1	HARBOR VIEW PL	ARMADA TR	LUCINDA ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-031423-PV1	INGELWOW ST	ROSCREANS ST	LOCUST ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-0314676-PV1	IONGUA DR	ELLIOTT ST	LOTUS DR	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-0315249-PV1	KINGSLEY ST	EVERGREEN ST	LOCUST ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-0315678-PV1	LA PALOMA ST	SAVOY ST	LOCUST ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
S2524	SS-0315724-PV1	LADERA ST	CORNISH DR	CORVOYA ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential
S2524	SS-0316210-PV1	LAWRENCE ST	SAN ELIO ST	SAN FERNANDO ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type VII Slurry Seal	11/2024	05/2025	5	8	Residential

CITY OF SAN DIEGO - TRANSPORTATION DEPARTMENT
FY2025 Road Maintenance and Rehabilitation Account Project List

Exhibit A

Project Title	Segment ID	Street Name	Cross Street 1	Cross Street 2	Council District	Project Location (Community Planning Area)	Activity	Project Description	Estimated Construction Dates		Estimated Useful Life (in years)		Functional Classification
									Begin	End	Min	Max	
52524	SS-016211-PV1	LAWRENCE ST	ROSECRANS ST	SAN ELIO ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-016213-PV2	LAWRENCE ST	SAN ANTONIO AV	ROSECRANS ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-016219-PV2	LEON ST	NOVARA ST	GUZOT ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-016572-PV1	LOCUST ST	NIMTZ BL	MACAULAY ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-016573-PV2	LOCUST ST	KENTS ST	NIMTZ BL	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-016584-PV1	LOCUST ST	CANON ST	AVINDA DE PORTUGAL	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-016589-PV1	LUCERNE DR	POINSETTIA DR	LA PALOMA ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-018572-PV1	MODANA DR	LA PALOMA ST	POE ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-019334-PV1	NIMTZ BL	CAPISTRANO ST	POE ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-020164-PV1	NOVARA ST	CORNISH DR	LEON ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-020168-PV1	NOVARA ST	PIEDMONT DR	CORNISH DR	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-021786-PV1	PIEDMONT DR	NOVARA ST	CORNISH DR	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-021787-PV1	PIEDMONT DR	ALEXANDRIA DR	CORNISH DR	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-022043-PV1	POE ST	CAPISTRANO ST	NIMTZ BL	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-022066-PV1	POINSETTIA DR	PALERMO DR	LUCERNE DR	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-022067-PV1	POINSETTIA DR	PALERMO DR	PALERMO DR	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-023540-PV1	ROSECRANS ST	MALAGA ST	MADRID ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Major
52524	SS-023566-PV1	ROSECRANS ST	JARVIS ST	KEATS ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-023577-PV1	ROSECRANS ST	UPSHUR ST	CANON ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-023578-PV1	ROSECRANS ST	TALBOT ST	UPSHUR ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-024045-PV1	SAN ELIO ST	KELLOGG ST	LAWRENCE ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-024047-PV1	SAN ELIO ST	WIDOLIS ST	OWEN ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-024237-PV1	SANTA BARBARA ST	NEWPORT AV	SANTA MONICA AV	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-024239-PV1	SANTA BARBARA ST	NARRAGANSETT AV	NAGARA AV	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-024241-PV1	SAVOY CR	PISCADERO AV	VENIZ ST	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-024247-PV1	SAVOY CR	BERMUDA CR	VENIZ ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-024249-PV1	SCOTT ST	AVINDA DE PORTUGAL	SHELTER ISLAND DR	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-024249-PV1	SCOTT ST	CANON ST	AVINDA DE PORTUGAL	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-027048-PV1	UDALL ST	WILLOW ST	PLUM ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-027336-PV1	VALEMONT ST	BANGOR ST	CONCORD ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-027337-PV1	VALEMONT ST	CANON ST	END	2	PENINSULA	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Residential
52524	SS-028223-PV1	WILLOW ST	WESTCLIFFE PL	VOLTAIRE ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-028242-PV1	WILLOW ST	AVINDA DE PORTUGAL	BYRON ST	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-028243-PV1	WILLOW ST	CANON ST	AVINDA DE PORTUGAL	2	PENINSULA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-028281-PV1	VISTA SORRENTO PY	OCEAN BLUFF AV	CARMEL MTN RD	1	TORREY HILLS	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-028283-PV1	VISTA SORRENTO PY	CALLE MAR DE MARIPOS	OCEAN BLUFF AV	1	TORREY HILLS	AC - Cape Seal	Cape Seal	11/2024	05/2025	5	8	Collector
52524	SS-028524-PV1	CARCUSEL LN	MARIPOSA DR	MARIPOSA DR	1	TORREY PINES	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52524	SS-011227-PV1	MARIPOSA DR	PORCUPHINO DR	CARCUSEL LN	1	TORREY PINES	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Collector
52524	SS-011860-PV1	MONTGEO CV	BERGEN	PORCUPHINO DR	1	TORREY PINES	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	11/2024	05/2025	5	8	Residential
52525	SS-001622-PV1	ABERNATHY CV	BERGEN	MT ABERNATHY AV	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-001657-PV1	AVILET PL	BERGEN	BIRKWAY DR	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-001388-PV1	BAKEWELL ST	BERGEN	MT ABERNATHY AV	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-004735-PV1	BOYD AV	EARNSCUPP PL	END	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-004736-PV1	BOYD AV	EARNSCUPP PL	EARNSCUPP PL	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-004893-PV1	BRILLO ST	GENESE AV	ABERDEEN ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-004894-PV1	BRILLO ST	BERGEN	END	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-004895-PV1	BRILLO ST	CONRAD AV	END	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-005947-PV1	CAMBER CT	CAMBER DR	END	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-005948-PV1	CAMBER DR	CAMBER CT	MT ABERNATHY AV	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-005949-PV1	CAMBER DR	CAMBER CT	CAMBER CT	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-005950-PV1	CAMBER DR	CHATEAU DR	CAMBER PL	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-005952-PV1	CAMBER PL	CAMBER DR	END	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-007242-PV1	CAYWOOD ST	DUBOIS DR	PROVIDENCE RD	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-006024-PV1	CAYWOOD ST	CAYWOOD ST	DUBOIS DR	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-006074-PV1	CAYWOOD ST	APPLETON ST	OVID PL	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-006912-PV1	CHAMPLAIN WY	NEW HAVEN RD	OVID PL	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-007092-PV1	CHESHIRE ST	CANOSA AV	TELAVA ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-007812-PV1	CONRAD AV	BAKTER ST	CADET ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-007828-PV1	CONRAD AV	BRILLO ST	BAKTER ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-007830-PV1	CONRAD AV	FRANK AV	BRILLO ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-007831-PV1	CONRAD AV	CADET ST	DIANE AV	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-008285-PV1	DOLIVA DR	DANTE ST	KESLING ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Prime
52525	SS-009301-PV1	DOLIVA DR	KESLING ST	CLAIREMONT MESA BL	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Prime
52525	SS-009487-PV1	DUBOIS DR	LODI ST	COLE ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-009488-PV1	DUBOIS DR	CAYWOOD ST	LODI ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-009489-PV1	DUBOIS DR	APPLETON ST	CAYWOOD ST	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential
52525	SS-009722-PV1	EARNSCUPP PL	BERGEN	BOYD AV	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-011179-PV1	INNUIT AV	MELISA WY	KAMLOOP AV	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-014637-PV1	JICARILLO AV	LA JUNTA AV	KAROK AV	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-014638-PV1	JICARILLO AV	HOPF PL	LA JUNTA AV	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-014639-PV1	JICARILLO AV	KEOKUK CT	HOPF PL	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-014626-PV1	JICARILLO AV	KAROK AV	IDLEWILD WY	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-014628-PV1	KAROK AV	KEOKUK CT	KEOKUK CT	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-015145-PV1	KEOKUK CT	MELISA WY	JICARILLO AV	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-015150-PV1	KEOKUK CT	MELISA WY	JICARILLO AV	2	CLAIREMONT MESA	AC - Surface Treatment (RPMS)	Type 1/8 Slurry Seal	01/2025	06/2025	5	8	Residential
52525	SS-015169-PV1	KESLING ST	DOLIVA DR	CANNINGTON DR	2	CLAIREMONT MESA	AC - Cape Seal	Cape Seal	01/2025	06/2025	5	8	Residential

APPENDIX B

FIRE HYDRANT METER PROGRAM

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 1 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

1. **PURPOSE**

- 1.1 To establish a Departmental policy and procedure for issuance, proper usage and charges for fire hydrant meters.

2. **AUTHORITY**

- 2.1 All authorities and references shall be current versions and revisions.
- 2.2 San Diego Municipal Code (NC) Chapter VI, Article 7, Sections 67.14 and 67.15
- 2.3 Code of Federal Regulations, Safe Drinking Water Act of 1986
- 2.4 California Code of Regulations, Titles 17 and 22
- 2.5 California State Penal Code, Section 498B.0
- 2.6 State of California Water Code, Section 110, 500-6, and 520-23
- 2.7 Water Department Director

Reference

- 2.8 State of California Guidance Manual for Cross Connection Programs
- 2.9 American Water Works Association Manual M-14, Recommended Practice for Backflow Prevention
- 2.10 American Water Works Association Standards for Water Meters
- 2.11 U.S.C. Foundation for Cross Connection Control and Hydraulic Research Manual

3. **DEFINITIONS**

- 3.1 **Fire Hydrant Meter:** A portable water meter which is connected to a fire hydrant for the purpose of temporary use. (These meters are sometimes referred to as Construction Meters.)

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 2 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

3.2 **Temporary Water Use:** Water provided to the customer for no longer than twelve (12) months.

3.3 **Backflow Preventor:** A Reduced Pressure Principal Assembly connected to the outlet side of a Fire Hydrant Meter.

4. **POLICY**

4.1 The Water Department shall collect a deposit from every customer requiring a fire hydrant meter and appurtenances prior to providing the meter and appurtenances (see Section 7.1 regarding the Fees and Deposit Schedule). The deposit is refundable upon the termination of use and return of equipment and appurtenances in good working condition.

4.2 Fire hydrant meters will have a 2 ½" swivel connection between the meter and fire hydrant. The meter shall not be connected to the 4" port on the hydrant. All Fire Hydrant Meters issued shall have a Reduced Pressure Principle Assembly (RP) as part of the installation. Spanner wrenches are the only tool allowed to turn on water at the fire hydrant.

4.3 The use of private hydrant meters on City hydrants is prohibited, with exceptions as noted below. All private fire hydrant meters are to be phased out of the City of San Diego. All customers who wish to continue to use their own fire hydrant meters must adhere to the following conditions:

a. Meters shall meet all City specifications and American Water Works Association (AWWA) standards.

b. Customers currently using private fire hydrant meters in the City of San Diego water system will be allowed to continue using the meter under the following conditions:

1. The customer must submit a current certificate of accuracy and calibration results for private meters and private backflows annually to the City of San Diego, Water Department, Meter Shop.

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 3 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

2. The meter must be properly identifiable with a clearly labeled serial number on the body of the fire hydrant meter. The serial number shall be plainly stamped on the register lid and the main casing. Serial numbers shall be visible from the top of the meter casing and the numbers shall be stamped on the top of the inlet casing flange.
3. All meters shall be locked to the fire hydrant by the Water Department, Meter Section (see Section 4.7).
4. All meters shall be read by the Water Department, Meter Section (see Section 4.7).
5. All meters shall be relocated by the Water Department, Meter Section (see Section 4.7).
6. These meters shall be tested on the anniversary of the original test date and proof of testing will be submitted to the Water Department, Meter Shop, on a yearly basis. If not tested, the meter will not be allowed for use in the City of San Diego.
7. All private fire hydrant meters shall have backflow devices attached when installed.
8. The customer must maintain and repair their own private meters and private backflows.
9. The customer must provide current test and calibration results to the Water Department, Meter Shop after any repairs.
10. When private meters are damaged beyond repair, these private meters will be replaced by City owned fire hydrant meters.

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 4 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

11. When a private meter malfunctions, the customer will be notified and the meter will be removed by the City and returned to the customer for repairs. Testing and calibration results shall be given to the City prior to any re-installation.
 12. The register shall be hermetically sealed straight reading and shall be readable from the inlet side. Registration shall be in hundred cubic feet.
 13. The outlet shall have a 2 ½ "National Standards Tested (NST) fire hydrant male coupling.
 14. Private fire hydrant meters shall not be transferable from one contracting company to another (i.e. if a company goes out of business or is bought out by another company).
- 4.4 All fire hydrant meters and appurtenances shall be installed, relocated and removed by the City of San Diego, Water Department. All City owned fire hydrant meters and appurtenances shall be maintained by the City of San Diego, Water Department, Meter Services.
- 4.5 If any fire hydrant meter is used in violation of this Department Instruction, the violation will be reported to the Code Compliance Section for investigation and appropriate action. Any customer using a fire hydrant meter in violation of the requirements set forth above is subject to fines or penalties pursuant to the Municipal Code, Section 67.15 and Section 67.37.

4.6 **Conditions and Processes for Issuance of a Fire Hydrant Meter**

Process for Issuance

- a. Fire hydrant meters shall only be used for the following purposes:
 1. Temporary irrigation purposes not to exceed one year.

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 5 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

2. Construction and maintenance related activities (see Tab 2).

- b. No customer inside or outside the boundaries of the City of San Diego Water Department shall resell any portion of the water delivered through a fire hydrant by the City of San Diego Water Department.
- c. The City of San Diego allows for the issuance of a temporary fire hydrant meter for a period not to exceed 12 months (365 days). An extension can only be granted in writing from the Water Department Director for up to 90 additional days. A written request for an extension by the consumer must be submitted at least 30 days prior to the 12 month period ending. No extension shall be granted to any customer with a delinquent account with the Water Department. No further extensions shall be granted.
- d. Any customer requesting the issuance of a fire hydrant meter shall file an application with the Meter Section. The customer must complete a "Fire Hydrant Meter Application" (Tab 1) which includes the name of the company, the party responsible for payment, Social Security number and/or California ID, requested location of the meter (a detailed map signifying an exact location), local contact person, local phone number, a contractor's license (or a business license), description of specific water use, duration of use at the site and full name and address of the person responsible for payment.
- e. At the time of the application the customer will pay their fees according to the schedule set forth in the Rate Book of Fees and Charges, located in the City Clerk's Office. All fees must be paid by check, money order or cashiers check, made payable to the City Treasurer. Cash will not be accepted.
- f. No fire hydrant meters shall be furnished or relocated for any customer with a delinquent account with the Water Department.
- g. After the fees have been paid and an account has been created, the

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 6 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

meter shall be installed within 48 hours (by the second business day). For an additional fee, at overtime rates, meters can be installed within 24 hours (within one business day).

4.7 Relocation of Existing Fire Hydrant Meters

- a. The customer shall call the Fire Hydrant Meter Hotline (herein referred to as "Hotline"), a minimum of 24 hours in advance, to request the relocation of a meter. A fee will be charged to the existing account, which must be current before a work order is generated for the meter's relocation.
- b. The customer will supply in writing the address where the meter is to be relocated (map page, cross street, etc). The customer must update the original Fire Hydrant Meter Application with any changes as it applies to the new location.
- c. Fire hydrant meters shall be read on a monthly basis. While fire hydrant meters and backflow devices are in service, commodity, base fee and damage charges, if applicable, will be billed to the customer on a monthly basis. If the account becomes delinquent, the meter will be removed.

4.8 Disconnection of Fire Hydrant Meter

- a. After ten (10) months a "Notice of Discontinuation of Service" (Tab 3) will be issued to the site and the address of record to notify the customer of the date of discontinuance of service. An extension can only be granted in writing from the Water Department Director for up to 90 additional days (as stated in Section 4.6C) and a copy of the extension shall be forwarded to the Meter Shop Supervisor. If an extension has not been approved, the meter will be removed after twelve (12) months of use.
- b. Upon completion of the project the customer will notify the Meter Services office via the Hotline to request the removal of the fire hydrant meter and appurtenances. A work order will be generated

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 7 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

for removal of the meter.

- c. Meter Section staff will remove the meter and backflow prevention assembly and return it to the Meter Shop. Once returned to the Meter Shop the meter and backflow will be tested for accuracy and functionality.
- d. Meter Section Staff will contact and notify Customer Services of the final read and any charges resulting from damages to the meter and backflow or its appurtenance. These charges will be added on the customer's final bill and will be sent to the address of record. Any customer who has an outstanding balance will not receive additional meters.
- e. Outstanding balances due may be deducted from deposits and any balances refunded to the customer. Any outstanding balances will be turned over to the City Treasurer for collection. Outstanding balances may also be transferred to any other existing accounts.

5. **EXCEPTIONS**

- 5.1 Any request for exceptions to this policy shall be presented, in writing, to the Customer Support Deputy Director, or his/her designee for consideration.

6. **MOBILE METER**

- 6.1 Mobile meters will be allowed on a case by case basis. All mobile meters will be protected by an approved backflow assembly and the minimum requirement will be a Reduced Pressure Principal Assembly. The two types of Mobile Meters are vehicle mounted and floating meters. Each style of meters has separate guidelines that shall be followed for the customer to retain service and are described below:
 - a) **Vehicle Mounted Meters:** Customer applies for and receives a City owned Fire Hydrant Meter from the Meter Shop. The customer mounts the meter on the vehicle and brings it to the Meter Shop for

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 8 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

inspection. After installation is approved by the Meter Shop the vehicle and meter shall be brought to the Meter Shop on a monthly basis for meter reading and on a quarterly basis for testing of the backflow assembly. Meters mounted at the owner's expense shall have the one year contract expiration waived and shall have meter or backflow changed if either fails.

- b) **Floating Meters:** Floating Meters are meters that are not mounted to a vehicle. **(Note: All floating meters shall have an approved backflow assembly attached.)** The customer shall submit an application and a letter explaining the need for a floating meter to the Meter Shop. The Fire Hydrant Meter Administrator, after a thorough review of the needs of the customer, (i.e. number of jobsites per day, City contract work, lack of mounting area on work vehicle, etc.), may issue a floating meter. At the time of issue, it will be necessary for the customer to complete and sign the "Floating Fire Hydrant Meter Agreement" which states the following:

- 1) The meter will be brought to the Meter Shop at 2797 Caminito Chollas, San Diego on the third week of each month for the monthly read by Meter Shop personnel.
- 2) Every other month the meter will be read and the backflow will be tested. This date will be determined by the start date of the agreement.

If any of the conditions stated above are not met the Meter Shop has the right to cancel the contract for floating meter use and close the account associated with the meter. The Meter Shop will also exercise the right to refuse the issuance of another floating meter to the company in question.

Any Fire Hydrant Meter using reclaimed water shall not be allowed use again with any potable water supply. The customer shall incur the cost of replacing the meter and backflow device in this instance.

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 9 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

7. **FEE AND DEPOSIT SCHEDULES**

- 7.1 **Fees and Deposit Schedules:** The fees and deposits, as listed in the Rate Book of Fees and Charges, on file with the Office of the City Clerk, are based on actual reimbursement of costs of services performed, equipment and materials. These deposits and fees will be amended, as needed, based on actual costs. Deposits, will be refunded at the end of the use of the fire hydrant meter, upon return of equipment in good working condition and all outstanding balances on account are paid. Deposits can also be used to cover outstanding balances.

All fees for equipment, installation, testing, relocation and other costs related to this program are subject to change without prior notification. The Mayor and Council will be notified of any future changes.

8. **UNAUTHORIZED USE OF WATER FROM A HYDRANT**

- 8.1 Use of water from any fire hydrant without a properly issued and installed fire hydrant meter is theft of City property. Customers who use water for unauthorized purposes or without a City of San Diego issued meter will be prosecuted.
- 8.2 If any unauthorized connection, disconnection or relocation of a fire hydrant meter, or other connection device is made by anyone other than authorized Water Department personnel, the person making the connection will be prosecuted for a violation of San Diego Municipal Code, Section 67.15. In the case of a second offense, the customer's fire hydrant meter shall be confiscated and/or the deposit will be forfeited.
- 8.3 Unauthorized water use shall be billed to the responsible party. Water use charges shall be based on meter readings, or estimates when meter readings are not available.
- 8.4 In case of unauthorized water use, the customer shall be billed for all applicable charges as if proper authorization for the water use had been obtained, including but not limited to bi-monthly service charges, installation charges and removal charges.

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 10 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

- 8.5 If damage occurs to Water Department property (i.e. fire hydrant meter, backflow, various appurtenances), the cost of repairs or replacements will be charged to the customer of record (applicant).

Water Department Director

- Tabs: 1. Fire Hydrant Meter Application
2. Construction & Maintenance Related Activities With No Return To Sewer
3. Notice of Discontinuation of Service

APPENDIX

Administering Division: Customer Support Division

Subject Index: Construction Meters
Fire Hydrant
Fire Hydrant Meter Program
Meters, Floating or Vehicle Mounted
Mobile Meter
Program, Fire Hydrant Meter

Distribution: DI Manual Holders



Application for Fire (EXHIBIT A) Hydrant Meter

(For Office Use Only)

NS REQ	FAC#
DATE	BY

METER SHOP (619) 527-7449

Meter Information

Application Date	Requested Install Date:
------------------	-------------------------

Fire Hydrant Location: (Attach Detailed Map//Thomas Bros. Map Location or Construction drawing.) <u>Zip:</u>	<u>T.B.</u>	<u>G.B. (CITY USE)</u>
Specific Use of Water:		
Any Return to Sewer or Storm Drain, If so, explain:		
Estimated Duration of Meter Use: <input type="text"/>	<input type="checkbox"/>	Check Box if Reclaimed Water

Company Information

Company Name:			
Mailing Address:			
City:	State:	Zip:	Phone: ()
*Business license#		*Contractor license#	
A Copy of the Contractor's license OR Business License is required at the time of meter issuance.			
Name and Title of Billing Agent: <small>(PERSON IN ACCOUNTS PAYABLE)</small>		Phone: ()	
Site Contact Name and Title:		Phone: ()	
Responsible Party Name:		Title:	
Cal ID#		Phone: ()	
Signature:		Date:	
Guarantees Payment of all Charges Resulting from the use of this Meter. Insures that employees of this Organization understand the proper use of Fire Hydrant Meter			

Fire Hydrant Meter Removal Request		Requested Removal Date:
<input type="text"/>		
Provide Current Meter Location if Different from Above:		
Signature:		Title: Date:
Phone: ()	Pager: ()	

<input type="checkbox"/> City Meter	<input type="checkbox"/> Private Meter	
Contract Acct #:	Deposit Amount: \$ 936.00	Fees Amount: \$ 62.00
Meter Serial #	Meter Size: 05	Meter Make and Style: 6-7
Backflow #	Backflow Size:	Backflow Make and Style:
Name:	Signature:	Date:

WATER USES WITHOUT ANTICIPATED CHARGES FOR RETURN TO SEWER

Auto Detailing
Backfilling
Combination Cleaners (Vactors)
Compaction
Concrete Cutters
Construction Trailers
Cross Connection Testing
Dust Control
Flushing Water Mains
Hydro Blasting
Hydro Seeing
Irrigation (for establishing irrigation only; not continuing irrigation)
Mixing Concrete
Mobile Car Washing
Special Events
Street Sweeping
Water Tanks
Water Trucks
Window Washing

Note:

1. If there is any return to sewer or storm drain, then sewer and/or storm drain fees will be charges.

Date

Name of Responsible Party

Company Name and Address

Account Number: _____

Subject: Discontinuation of Fire Hydrant Meter Service

Dear Water Department Customer:

The authorization for use of Fire Hydrant Meter # _____, located at *(Meter Location Address)* ends in 60 days and will be removed on or after *(Date Authorization Expires)*. Extension requests for an additional 90 days must be submitted in writing for consideration 30 days prior to the discontinuation date. If you require an extension, please contact the Water Department, or mail your request for an extension to:

City of San Diego
Water Department
Attention: Meter Services
2797 Caminito Chollas
San Diego, CA 92105-5097

Should you have any questions regarding this matter, please call the Fire Hydrant Hotline at (619) _____ - _____.

Sincerely,

Water Department

APPENDIX C

MATERIALS TYPICALLY ACCEPTED BY CERTIFICATE OF COMPLIANCE

MATERIALS TYPICALLY ACCEPTED BY CERTIFICATE OF COMPLIANCE

1. Soil amendment
2. Fiber mulch
3. PVC or PE pipe up to 16 inch diameter
4. Stabilizing emulsion
5. Lime
6. Preformed elastomeric joint seal
7. Plain and fabric reinforced elastomeric bearing pads
8. Steel reinforced elastomeric bearing pads
9. Waterstops (Special Condition)
10. Epoxy coated bar reinforcement
11. Plain and reinforcing steel
12. Structural steel
13. Structural timber and lumber
14. Treated timber and lumber
15. Lumber and timber
16. Aluminum pipe and aluminum pipe arch
17. Corrugated steel pipe and corrugated steel pipe arch
18. Structural metal plate pipe arches and pipe arches
19. Perforated steel pipe
20. Aluminum underdrain pipe
21. Aluminum or steel entrance tapers, pipe downdrains, reducers, coupling bands and slip joints
22. Metal target plates
23. Paint (traffic striping)
24. Conductors
25. Painting of electrical equipment
26. Electrical components
27. Engineering fabric
28. Portland Cement
29. PCC admixtures
30. Minor concrete, asphalt
31. Asphalt (oil)
32. Liquid asphalt emulsion
33. Epoxy

APPENDIX D

SAMPLE CITY INVOICE

City of San Diego, CM&FE Div., 9573 Chesapeake Drive, SD CA 92123

Project Name:

Work Order No or Job Order No.

City Purchase Order No.

Resident Engineer (RE):

RE Phone#: Fax#:

Contractor's Name:

Contractor's Address:

Contractor's Phone #:

Contractor's fax #:

Contact Name:

Invoice No.

Invoice Date:

Billing Period: (To)

Trigger Asset	Item #	Item Description	Contract Authorization				Previous Totals To Date		This Estimate		Totals to Date		Amount Remaining
			Unit	Price	Qty	Extension	%/QTY	Amount	% / QTY	Amount	% / QTY	Amount	
	1				1.00	\$ -		\$0.00		\$0.00	0.00	\$0.00	\$ -
	2				1.00	\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	3				1.00	\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	4				1.00	\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	5				1.00	\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	6				1.00	\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	7				1.00	\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	8				1.00	\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	5				1.00	\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	6					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	7					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	8					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	9					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	10					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	11					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	12					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	13					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	14					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	15					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	16					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
	17					\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
						\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
		CHANGE ORDER No.				\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
						\$ -		\$0.00		\$0.00	0.00%	\$0.00	\$ -
		Total Auhtorized Amount (Original)				\$ -		\$0.00		\$0.00		\$0.00	\$ -
		Total Authorized Amount (including approved Change Order)				\$ -		\$0.00		\$0.00	Total Billed	\$0.00	Total Amount Remaining
								\$0.00		\$0.00		\$ -	

SUMMARY

A. Original Contract Amount	\$0.00
B. Approved Change Order #00 Thru #00	\$0.00
C. Total Authorized Amount (A+B)	\$0.00
D. Total Billed to Date	\$0.00
E. Less Total Retention (5% of D)	\$0.00
F. Less Total Previous Payments	\$0.00
G. Payment Due Less Retention	\$0.00
H. Remaining Authorized Amount	\$0.00

I certify that the materials have been received by me, or services have been rendered, in the quality and quantity specified per the approved contracted amounts, and is approved for payment

Resident Engineer

Construction Engineer

Date

Date

Retention and/or Escrow Payment Schedule

Total Retention Required as of this billing (Item E)	\$0.00
Previous Retention Withheld in PO or in Escrow	\$0.00
Add'l Amt to Withhold in PO/Transfer in Escrow:	\$0.00
Amt to Release to Contractor from PO/Escrow:	\$0.00

Contractor Signature and Date: _____

1/10/2024 Rev

Slurry Seal Group 2524

K-25-2345-DBB-3

125 | Page


APPENDIX E

OVERALL LOCATION MAP



CONSTRUCTION PROJECT
INFORMATION LINE
(619) 527-7500

Slurry Seal Group 2524



APPENDIX F

RESURFACING LIMITS MAPS



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: TORREY PINES

CD: 1



 S2524 Slurry Seal

 Caltrans_ROW

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed





TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: CARMEL VALLEY DEL MAR MESA

CD: 1



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: TORREY HILLS TORREY PINES

CD: 1



 S2524 Slurry Seal

 Schools

 Fire Station

 Caltrans_ROW

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: TORREY HILLS

CD: 1



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM

NOT TO SCALE



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed





TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



 S2524 Slurry Seal

 S2524 Cape Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed





TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



 S2524 Slurry Seal

 Schools

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034

RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



S2524 Slurry Seal

S2524 Cape Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



 S2524 Slurry Seal

 S2524 Cape Seal



Schools

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed





TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



S2524 Slurry Seal

Caltrans_ROW

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed





TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



NOT TO SCALE

 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



 S2524 Slurry Seal

 S2524 Cape Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



 S2524 Slurry Seal

 S2524 Cape Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034

RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: PACIFIC BEACH

CD: 1



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE.
Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA

CD: 1



 S2524 Slurry Seal

 S2524 Cape Seal

 Schools

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: LA JOLLA PACIFIC BEACH

CD: 1



S2524 Slurry Seal

S2524 Cape Seal



Schools

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034

RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PACIFIC BEACH

CD: 1



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PACIFIC BEACH

CD: 1



 S2524 Cape Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PACIFIC BEACH

CD: 1



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034

RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: PACIFIC BEACH

CD: 1



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034

RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: PACIFIC BEACH

CD: 1



 S2524 Slurry Seal

 S2524 Cape Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: CLAIREMONT MESA

CD: 2



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: CLAIREMONT MESA

CD: 2



 S2524 Slurry Seal

 S2524 Cape Seal

 Schools

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed





TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034

RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: CLAIREMONT MESA

CD: 2



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed





TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: CLAIREMONT MESA

CD: 2



/// S2524 Slurry Seal

/// S2524 Cape Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: MIDWAY-PACIFIC HIGHWAY

CD: 2



 S2524 Slurry Seal

 Caltrans_ROW

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034

RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: MIDWAY-PACIFIC HIGHWAY PENINSULA

CD: 2



 S2524 Slurry Seal

 Schools

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed





TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA

CD: 2



S2524 Slurry Seal

Schools

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



NOT TO SCALE

Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA

CD: 2



Date Exported: 11/19/2024 5:38 PM

 S2524 Slurry Seal

 Schools

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



NOT TO SCALE

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: OCEAN BEACH

CD: 2



 S2524 Slurry Seal

 Fire Station

 Schools

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE.
Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: OCEAN BEACH

CD: 2



S2524 Slurry Seal

S2524 Cape Seal

Schools

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: OCEAN BEACH

CD: 2



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA OCEAN BEACH

CD: 2



 S2524 Slurry Seal

 S2524 Cape Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA

CD: 2

 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA

CD: 2



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA

CD: 2



 S2524 Slurry Seal

 Fire Station

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034

RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA

CD: 2



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA

CD: 2



 S2524 Slurry Seal

 Schools

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright 2015 - All Rights Reserved. Full text of this legal notice can be found at: <http://www.sandis.org/legal/Notice.htm>



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076


Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA

CD: 2



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA

CD: 2



S2524 Slurry Seal

Fire Station

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed





TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA

CD: 2



 S2524 Slurry Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Copyright SanGIS 2015 - All Rights Reserved. Full text of this legal notice can be found at: http://www.sandis.org/legal_notice.htm



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034

RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: PENINSULA

CD: 2



S2524 Slurry Seal

S2524 Cape Seal

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



Date Exported: 11/19/2024 5:38 PM



TRANSPORTATION

SENIOR ENGINEER
Joshua Lahmann
619-527-7509

PROJECT MANAGER
Chris Hudson
619-527-8081

PROJECT ENGINEER
Kevin Yacoub
619-527-8034


RESIDENT ENGINEER
Nahome Mekonnen
619-527-8076

Slurry Seal Group 2524

IO: 21005580

Community: CARMEL VALLEY

CD: 1



S2524 Slurry Seal

Caltrans_ROW

The required curb ramps by the ADA title II as a result of the cape seal installation work included in this contract will be installed under a separate contract (2025 City Wide Curb Ramps) after the necessary design work and compilation with other accessibility improvements are completed



APPENDIX G

CONTRACTOR'S DAILY QUALITY CONTROL INSPECTION REPORT

Appendix G

City of San Diego
Asphalt Concrete Overlay
Contractor's Daily Quality Control Inspection Report

Project Title: _____ Date: _____

Locations: 1. _____
2. _____
3. _____

Asphalt Mix Specification: Attached Supplier: _____

Dig out Locations: 1. _____
2. _____
3. _____

Tack Coat Application Rate @ Locations:
1. _____
2. _____
3. _____

Asphalt Temperature at Placement @ Locations:
1. _____
2. _____
3. _____

Asphalt Depth @Locations:
1. _____
2. _____
3. _____

Compaction Test Result @Locations:
1. _____
2. _____
3. _____

Location and nature of defects:

1. _____
2. _____
3. _____

Remedial and Corrective Actions taken or proposed for Engineer's approval:

1. _____
2. _____
3. _____

Date's City Laboratory representative was present:

1. _____
2. _____
3. _____

Verified the following:

1. Proper Storage of Materials & Equipment
2. Proper Operation of Equipment
3. Adherence to Plans and Specs
4. Review of QC Tests
5. Safety Inspection

Initials:

Deviations from QCP _____ (see attached)

Quality Control Plan Administrator's Signature:

Date Signed:

City of San Diego
Rubber Polymer Modified Slurry
Contractor's Daily Quality Control Inspection Report

Project Title: _____ Date: _____

Ambient Temperature (Start of Work): _____ Time: _____

Environmental Considerations: _____

Locations (Address Range/Cross Streets):

1. _____
2. _____
3. _____

Approved Mix Design: _____

Material Suppliers: _____

RPMS Type(s): _____

Slurry Machine #'s: _____

Estimated Cure Time (Break) of Slurry: _____

Pre-Mix (Per 100 Counts)

Gate Setting/Emulsion %: _____

Aggregate Weight: _____

Cement % (by weight of aggregate): _____

Crumb Rubber % (by volume of cement): _____

Machine Inspection

Leaks: _____

Sprayers: _____

Emulsion Filter: _____

Carbon Black: _____

Spreader Box Inspection

Cleanliness: _____

Augers: _____

Rubbers: _____

Fabric: _____

Runners: _____

City of San Diego
Rubber Polymer Modified Slurry
Contractor's Daily Quality Control Inspection Report

Project Conditions

Crack Fill: _____

Asphalt Deficiencies: _____

Cleanliness: _____

Impediments/Other: _____

Communication to Client/ Resident Engineer

Crack Fill: _____

Asphalt Deficiencies: _____

Cleanliness: _____

Impediments/Other: _____

Test Lab

Tech: _____ Time on Site: _____

Wet Track Abrasion: _____

Consistency Test: _____

Extraction Test: _____

Water Content: _____

Spread Rate: _____

Notes

QCP Administrator Signature:

Date Signed:

City of San Diego
PMRE Scrub Seal
Contractor's Daily Quality Control Inspection Report

Project Title: _____ Date: _____

Ambient Temperature (Start of Work): _____ Time: _____

Pavement Temperature (Start of Work): _____ Time: _____

Locations (Address Range/Cross Streets):

1. _____

2. _____

Approved Mix Design: _____

Surface Preparation:

1. Weed Spray: _____

2. Cracks Blown Out: _____

3. Asphalt Deficiencies: _____

Scrub Broom Inspection:

Hydraulic Lift (yes/no): _____ Nylon Bristles (yes/no): _____

Asphalt Distributor Inspection:

Emulsion: Spread Rate _____ Temperature _____

Sprayers: _____

Aggregate/Chip Spreader Inspection:

Spread Rate _____ Coverage _____

Rollers inspection:

of pneumatic rollers on site _____ # of passes _____

Pads (yes/no): _____ water application system (yes/no): _____

Cleanliness: _____

Sweeper Inspection:

of sweepers on site _____ # of passes _____

City of San Diego
PMRE Scrub Seal
Contractor's Daily Quality Control Inspection Report

Test Lab:

Tech: _____ Time on Site: _____

Rock Sieve Analysis: _____

Location and nature of any defects:

1. _____
2. _____
3. _____

Remedial and Corrective Actions taken for Engineer's approval:

1. _____
2. _____
3. _____

Notes:

QCP Administrator Signature:

Date Signed:

APPENDIX H

SAMPLE OF PUBLIC NOTICE (SB1 FUNDED ONLY)



This project is funded
in part by state gas
tax revenue (SB1)



CONSTRUCTION NOTICE

PROJECT TITLE

Street Resurfacing

As part of the Capital Improvements Program (CIP) project, **funded in part by State Gas Tax revenue (SB1)**, in your community, street resurfacing has been scheduled for the following date and locations:

**Thursday, Aug. 31 at 7 p.m.
to Friday, Sept. 1 at 5 a.m.**

The work will take place:

- Sassafras Street/India Street
- Sassafras Street/Kettner Boulevard

How your neighborhood may be impacted:

- No parking signs will be posted at least 72 hours before work begins. Vehicles in violation of signs **will be towed**.
- Temporary road closures, traffic rerouting, parking and access restrictions will be in effect during the work hours.
- Access to driveways will not be available when resurfacing is taking place at your driveway. Please allot extra time for ingress/egress from driveways and direct all questions about driveway access to the foreman on site.
- Trash service schedule will not be impacted. Please place trash cans in normal pickup area.

City of San Diego contractor contact information:

To contact the City of San Diego:  **Public Works**
619-533-4207 | engineering@sandiego.gov | sandiego.gov/CIP

 This information is available in alternative formats upon request.



This project is funded
in part by state gas
tax revenue (SB1)



CONSTRUCTION NOTICE

PROJECT TITLE

Street Resurfacing

As part of the Capital Improvements Program (CIP) project, **funded in part by State Gas Tax revenue (SB1)**, in your community, street resurfacing has been scheduled for the following date and locations:

**Thursday, Aug. 31 at 7 p.m.
to Friday, Sept. 1 at 5 a.m.**

The work will take place:


- Sassafras Street/India Street
- Sassafras Street/Kettner Boulevard

How your neighborhood may be impacted:

- No parking signs will be posted at least 72 hours before work begins. Vehicles in violation of signs **will be towed**.
- Temporary road closures, traffic rerouting, parking and access restrictions will be in effect during the work hours.
- Access to driveways will not be available when resurfacing is taking place at your driveway. Please allot extra time for ingress/egress from driveways and direct all questions about driveway access to the foreman on site.
- Trash service schedule will not be impacted. Please place trash cans in normal pickup area.

City of San Diego contractor contact information:

To contact the City of San Diego:  **Public Works**
619-533-4207 | engineering@sandiego.gov | sandiego.gov/CIP

 This information is available in alternative formats upon request.

APPENDIX I

ADVANCED METERING INFRASTRUCTURE (AMI) DEVICE PROTECTION

Protecting AMI Devices in Meter Boxes and on Street Lights

The Public Utilities Department (PUD) has begun the installation of the Advanced Metering Infrastructure (AMI) technology as a new tool to enhance water meter reading accuracy and efficiency, customer service and billing, and to be used by individual accounts to better manage the efficient use of water. **All AMI devices shall be protected per Section 402-2, "Protection", of the 2021 Whitebook.**

AMI technology allows water meters to be read electronically rather than through direct visual inspection by PUD field staff. This will assist PUD staff and customers in managing unusual consumption patterns which could indicate leaks or meter tampering on a customer's property.

Three of the main components of an AMI system are the:

- A. Endpoints, see Photo 1:


Photo 1



- B. AMI Antenna attached to Endpoint (antenna not always required), see Photo 2:



Network Devices, see Photo 3:



AMI endpoints transmit meter information to the AMI system and will soon be on the vast majority of meters in San Diego. These AMI devices provide interval consumption data to the PUD's Customer Support Division. If these devices are damaged or communication is interrupted, this Division will be alerted of the situation. The endpoints are installed in water meter boxes, coffins, and vaults adjacent to the meter. A separate flat round antenna may also be installed through the meter box lid. This antenna is connected to the endpoint via cable. The following proper installation shall be implemented when removing the lid to avoid damaging the antenna, cable, and/or endpoint. Photo 4 below demonstrates a diagram of the connection:

Photo 4



The AMI device ERT/Endpoint/Transmitter shall be positioned and installed as discussed in this Appendix. If the ERT/Endpoint/Transmitter is disturbed, it shall be re-installed and returned to its original installation with the end points pointed upwards as shown below in Photo 5.

The PUD's code compliance staff will issue citations and invoices to you for any damaged AMI devices that are not re-installed as discussed in the Contract Document

Photo 5 below shows a typical installation of an AMI endpoint on a water meter.

Photo 5




Photo 6 below is an example of disturbance that shall be avoided:

Photo 6



You are responsible when working in and around meter boxes. If you encounter these endpoints, use proper care and do not disconnect them from the registers on top of the water meter. If the lid has an antenna drilled through, do not change or tamper with the lid and inform the Resident Engineer immediately about the location of that lid. Refer to Photo 7 below:

Photo 7



Another component of the AMI system are the Network Devices. The Network Devices are strategically placed units (mainly on street light poles) that collect interval meter reading data from multiple meters for transmission to the Department Control Computer. **If you come across any of these devices on street lights that will be removed or replaced (refer to Photos 8 and 9 below), notify Elvira Santiesteban, Compliance & Metering Manager 619-380-3804 and Kevin Wilson, Senior Water Utility Supervisor 619-857-8257 immediately.**

Photo 8 shows an installed network device on a street light. On the back of each Network Device is a sticker with contact information. See Photo 9. **Call PUD Water Emergency Repairs at 619-515-3525 if your work will impact these street lights.** These are assets that belong to the City of San Diego and you shall be responsible for any costs of disruption of this network.

Photo 8



Network Device

Photo 9



If you encounter any bad installations, disconnected/broken/buried endpoints, or inadvertently damage any AMI devices or cables, notify the Resident Engineer immediately. The Resident Engineer will then immediately contact Elvira Santiesteban, Compliance & Metering Manager 619-380-3804 and Kevin Wilson, Senior Water Utility Supervisor 619-857-8257.

Rev. 9.11.2023

APPENDIX J
ADVANCED CONSTRUCTION NOTICE

ASPHALT REPAIR, CRACK SEAL, AND SURFACE SEAL



Construction Notice

The City of San Diego has contracted with **[INSERT CONTRACTOR NAME]** to perform maintenance on certain streets in your neighborhood. **Over the next two to three months, [INSERT CONTRACTOR NAME]** will complete preventive maintenance to fill pavement cracks and add a surface seal coating to help preserve asphalt streets near your address. Please accept our apology for any inconveniences this work may cause. Your patience and cooperation will help to get this work completed safely and with minimal interruption of your daily activities.

Work will be performed between the hours of **8:30 AM and 3:30 PM**. The general order of work will include:

1. "No Parking" signs set out 72 hours in advance of the work.
2. Asphalt repairs, crack seal, weed abatement, and street sweeping
3. Placement of surface seal; typically 7-14 days following the asphalt repairs. Occasionally, multiple coats of surface seal are applied on different days.

How will I be affected?

Before 7 a.m. on the day of the surface seal work, residential streets may be completely closed to all vehicles. That makes it important to plan ahead for parking on a street nearby or for leaving home before 7 a.m. that day. It is also important to help keep the street dry before the work begins. Please turn off any sprinklers or other irrigation systems the night before.

When possible, some streets will be surface sealed in stages to allow for limited access while the work is underway. It is important to obey the traffic control and "No Parking" warnings and to stay off the surface seal until the street is reopened for traffic – normally by 5 p.m. the same day.

What can I expect once the work is completed?

Surface seals have a light brown color when they are first applied to the street. They change color to black after a few hours of exposure to sunlight and heat. That change is important and helps confirm that the newly sealed street is ready for vehicle traffic. *Again, it is important to protect new surface seal work by staying off the street until traffic control and parking restrictions are removed by work crews.*

Surface seals can appear rough-at-the-edges when first applied and may even show some tire tracks or minor gouges once vehicles are allowed back on to the recently sealed streets. These marks will disappear as more traffic travels across the street and as the sealant continues to dry over time.

Please note: Surface seals are used to protect streets in generally good condition from further deterioration and do not return streets to “as new” condition. Surface seals help to extend a street’s life by three to seven years. Complete replacements are limited to those streets that are in fair to poor condition.

What about trash pickup on the day of the work?

If the day of the planned surface seal work falls on the same day as your trash collection, please bring your trash bins out early. Work crews will coordinate with the trash hauler to ensure your trash is collected prior to street closure for that day.

What about regular street sweeping?

Regular street sweeping will be suspended during the surface seal work to allow the new coating to properly set. The entire street sweeping route will be suspended allowing you to park on nearby streets normally affected by “no-parking” restrictions associated with those routes.

When will street striping and markings be restored?

Any striping or markings covered over by the surface seal effort will be restored within a few weeks following the work. Some temporary markers or signs may be installed to help with traffic control until the striping is restored.

Contact Information:

For any questions related to the surface seal work planned in your neighborhood, please contact the Project Manager at **[INSERT CONTRACTOR NAME]** - **[INSERT CONTRACTOR PHONE NUMBER]**. You may also submit questions or requests for additional services via the City's *Get It Done* system at <https://www.sandiego.gov/get-it-done>.

APPENDIX K
ESTIMATED CONSTRUCTION QUANTITIES

SLURRY SEAL GROUP 2524
IO: 21005580
ESTIMATED CONSTRUCTION QUANTITIES

Pavement ID	Street Name	Cross Street 1	Cross Street 2	Council District	Trash Day	Community Planning Area	Functional Classification	Lane Count	Survey Length (LF)	Survey Width (LF)	Survey Area (SF)	Crack Seal (LB)	Cape Seal (SF)	Slurry Seal Type I (SF)	Slurry Seal Type II (SF)	Slurry Seal Type III (SF)	6" Edge Grind (LF)	Base Repair (TONS)	Mill & Pave (TONS)	Inlet Marking (EA)	Inlet Protection (EA)	Adjust Survey Monument (EA)	Reconstruct Survey Monument (EA)	Water Valve (EA)	Sewer Manhole (EA)	Traffic Loops (EA)	Traffic Loops Location	ADT	Treatment Type	Task Comments
SS-029245-PV1	ZOLA ST	LUCERNE DR	PALERMO DR	2	Monday	PENINSULA	Residential	2	250	35	8,750	78.75	0	8,750	8,750	0	0	0.00	6.45	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-029246-PV1	ZOLA ST	POINSETTIA DR	LUCERNE DR	2	Monday	PENINSULA	Residential	2	297	28	8,316	74.84	0	8,316	8,316	0	0	0.00	0.00	0	0	0	0	4	2	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-029247-PV1	ZOLA ST	CHATSWORTH BL	POINSETTIA DR	2	Monday	PENINSULA	Residential	2	406	34	13,804	124.24	0	13,804	13,804	0	0	0.00	5.00	0	0	0	0	3	3	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-028823-PV1	WILLOW ST	WESTCLIFFE PL	VOLTAIRE ST	2	Monday	PENINSULA	Prime	2	174	34	5,917	53.25	0	5,917	5,917	0	0	0.00	7.26	0	0	0	0	7	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-028824-PV1	WILLOW ST	UDALL ST	WESTCLIFFE PL	2	Monday	PENINSULA	Prime	2	132	38	5,016	45.14	0	5,016	5,016	0	0	0.00	1.00	0	0	0	0	4	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-028841-PV1	WILLOW ST	BYRON ST	CARLETON ST	2	Monday	PENINSULA	Residential	2	258	41	10,578	95.20	0	10,578	10,578	0	0	2.55	3.43	0	0	0	0	1	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-028842-PV1	WILLOW ST	AVNDA DE PORTUGAL	BYRON ST	2	Monday	PENINSULA	Residential	2	270	39	10,530	94.77	0	10,530	10,530	0	0	1.13	1.32	0	0	0	0	3	1	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-028843-PV1	WILLOW ST	CANON ST	AVNDA DE PORTUGAL	2	Monday	PENINSULA	Residential	2	132	38	5,016	45.14	0	5,016	5,016	0	0	0.00	1.40	0	0	0	0	3	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-028566-PV1	WESTKNOLL DR	WESTKNOLL LN	CALLE VAQUERO	1	Monday	PACIFIC BEACH	Residential	2	818	38	31,084	0.00	31,084	0	0	0	0	0.00	12.72	0	0	0	0	1	0	0	2500	CAPE SEAL	CAPE SEAL	
SS-028127-PV1	VOLTAIRE ST	SUNSET CLIFFS BL	CABLE ST	2	Monday	OCEAN BEACH	Collector	2	643	51	32,793	295.14	0	0	32,793	32,793	0	0.00	9.19	0	0	0	0	1	0	9	EB @ Sunset Cliffs Blvd 8 VEH 1 ADV	6870	SLURRY SEAL	SLURRY SEAL TYPE II/III. Diagonal/Parallel Parking.
SS-028128-PV1	VOLTAIRE ST	EBERS ST	SUNSET CLIFFS BL	2	Monday	OCEAN BEACH	Collector	2	640	52	33,280	299.52	0	0	33,280	33,280	0	1.89	9.32	0	0	0	0	0	0	9	EB @ Ebers St 8 VEH 1 ADV	15000	SLURRY SEAL	SLURRY SEAL TYPE II/III.
SS-028081-PV1	VISTA SORRENTO PY	OCEAN BLUFF AV	CARMEL MTN RD	1		TORREY HILLS	Major	4	1,146	76	87,096	783.86	0	27,504	87,096	87,096	0	0.00	26.65	5	5	0	0	4	2	35	NB @ Carmel Mnt Rd 14 VEH 2 ADV 1 BIKE SB @ Ocean Bluff Ave 14 VEH 2 ADV 1 BIKE	17000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-028083-PV1	VISTA SORRENTO PY	CALLE MAR DE MARIPOS	OCEAN BLUFF AV	1		TORREY HILLS	Major	4	1,720	72	123,840	1,114.56	0	41,280	123,840	123,840	0	1.10	71.52	3	4	0	1	5	1	50	NB @ Ocean Bluff Ave 10 VEH 2 ADV 1 BIKE SB @ Pacific Plaza Dr 12 VEH 2 ADV 1 BIKE NB @ Pacific Plaza Dr 4 VEH 2 ADV 1 BIKE SB @ Calle Mar De Mariposa 12 VEH 2 ADV 1 BIKE	17000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-027660-PV1	VIA CORONA	COPA DE ORO DR	RUTGERS RD	1	Monday	LA JOLLA	Residential	2	600	28	16,800	151.20	0	16,800	16,800	0	0	0.00	14.89	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-027661-PV1	VIA CORONA	COPA DE ORO DR	END	1	Monday	LA JOLLA	Residential	2	242	36	8,712	78.41	0	8,712	8,712	0	0	0.00	34.64	0	0	0	0	3	1	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-027337-PV1	VALEMONT ST	CANON ST	END	2	Monday	PENINSULA	Residential	2	234	17	3,978	35.80	0	3,978	3,978	0	0	0.00	0.00	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-027049-PV1	UDALL ST	WILLOW ST	PLUM ST	2	Monday	PENINSULA	Residential	2	370	35	12,950	116.55	0	12,950	12,950	0	0	0.00	8.14	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-026940-PV1	TURQUOISE ST	WRELTON DR	LA JOLLA MESA DR	1	Monday	PACIFIC BEACH	Residential	4	324	64	20,736	186.62	0	0	20,736	20,736	0	5.70	48.46	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE II/III.	
SS-026943-PV1	TURQUOISE ST	LA JOLLA BL	END	1	Monday	PACIFIC BEACH	Residential	2	104	26	2,704	24.34	0	0	2,704	2,704	0	0.00	10.43	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE II/III.	
SS-026945-PV1	TURQUOISE ST	BEGIN	WRELTON DR	1	Monday	PACIFIC BEACH	Residential	4	330	62	20,460	184.14	0	0	20,460	20,460	0	9.61	23.51	0	0	0	0	1	0	0	9250	SLURRY SEAL	SLURRY SEAL TYPE II/III.	
SS-030909-PV1	TRZA MAR MARVELOSA	EAST OCEAN AIR DR	END	1	Monday	TORREY HILLS	Residential	2	430	36	15,480	139.32		15,480				0.00	0.00	0	0	0	0	1	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I. This segment is to receive slurry seal type I only, since it was slurried with Type II already.	
SS-026392-PV1	THOMAS AV	DAWES ST	EVERTS ST	1	Monday	PACIFIC BEACH	Residential	2	582	40	23,280	209.52	0	23,280	23,280	0	0	32.76	51.03	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-025904-PV1	SUNSET CLIFFS BL	PESCADERO AV	ORCHARD AV	2	Monday	OCEAN BEACH	Prime	2	365	36	13,140	118.26	0	13,140	13,140	0	0	5.39	7.68	0	2	0	0	0	1	0	14900	SLURRY SEAL	SLURRY SEAL TYPE I/II. STRIPING MOD.	
SS-025905-PV1	SUNSET CLIFFS BL	BERMUDA AV	PESCADERO AV	2	Monday	OCEAN BEACH	Prime	2	378	37	13,986	125.87	0	13,986	13,986	0	0	0.00	5.04	0	1	0	0	4	2	0	16000	SLURRY SEAL	SLURRY SEAL TYPE I/II. STRIPING MOD.	
SS-025906-PV1	SUNSET CLIFFS BL	POINT LOMA AV	BERMUDA AV	2	Monday	OCEAN BEACH	Prime	2	392	36	14,112	127.01	0	14,112	14,112	0	0	0.00	7.93	1	3	0	0	0	1	0	16000	SLURRY SEAL	SLURRY SEAL TYPE I/II. STRIPING MOD.	
SS-025175-PV1	SOLEDAD MTN RD	PALOMINO CR	SOLEDAD RD	1	Monday	LA JOLLA	Major	3	986	69	68,034	612.31	0	23,664	68,034	68,034	0	20.51	64.26	0	0	0	0	5	1	0	8450	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.	
SS-025176-PV1	SOLEDAD MTN RD	DESERT VIEW DR	PALM CANYON DR	1	Monday	LA JOLLA	Major	3	394	65	25,610	230.49	0	9,456	25,610	25,610	0	0.00	35.57	0	0	0	0	5	1	0	17000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.	
SS-025189-PV1	SOLEDAD MTN RD	PALM CANYON DR	PALOMINO CR	1	Monday	LA JOLLA	Major	3	1,074	65	69,794	628.15	0	25,770	69,794	69,794	0	0.00	82.54	1	1	0	0	1	1	0	2500	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.	
SS-025171-PV1	SOLEDAD AV	AL BAHR DR	LUDINGTON PL	1	Monday	LA JOLLA	Prime	2	610	24	14,640	131.76	0	14,640	14,640	0	0	0.00	27.11	2	2	0	0	0	1	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-024497-PV1	SCOTT ST	AVNDA DE PORTUGAL	SHELTER ISLAND DR	2	Monday	PENINSULA	Collector	2	246	46	11,316	101.84	0	11,316	11,316	0	0	0.00	2.96	1	1	0	0	0	0	0	15000	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-024498-PV1	SCOTT ST	CANON ST	AVNDA DE PORTUGAL	2	Monday	PENINSULA	Collector	2	253	36	9,108	81.97	0	9,108	9,108	0	0	0.00	11.38	0	0	0	0	0	0	0	4900	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-024265-PV1	SANTA CRUZ AV	FROUDE ST	OCEAN BEACH	2	Monday	OCEAN BEACH	Residential	2	622	40	24,880	0.00	24,880	0	0	0	0	7.02	85.62	0	0	0	0	0	0	0	2500	CAPE SEAL	CAPE SEAL	
SS-024236-PV1	SANTA BARBARA ST	SANTA MONICA AV	SARATOGA AV	2	Monday	PENINSULA	Prime	2	322	36	11,592	104.33	0	11,592	11,592	0	0	2.52	0.26	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-024239-PV1	SANTA BARBARA ST	NARRAGANSETT AV	NIAGARA AV	2	Monday	PENINSULA	Prime	2	322	40	12,880	115.92	0	12,880	12,880	0	0	4.10	5.12	0	0	0	0	1	0	0	1160	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-024240-PV1	SANTA BARBARA ST	DEL MONTE AV	NARRAGANSETT AV	2	Monday	PENINSULA	Prime	2	382	40	15,280	137.52	0	15,280	15,280	0	0	0.00	1.19	0	0	0	0	0	1	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-023815-PV1	RUSHVILLE ST	DRAPER AV	EADS AV	1	Monday	LA JOLLA	Residential	2	512	25	12,800	115.20	0	12,800	12,800	0	0	0.00	6.61	0	0	0	0	0	2	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-023539-PV1	ROSECRANS ST	MADRID ST	NORTH EVERGREEN ST	2	Monday	MIDWAY-PACIFIC HIGHWAY	Major	6	294	90	26,460	238.14	0	7,056	26,460	26,460	0	0.00	15.05	0	2	0	0	0	0	14	NB at N Evergreen St 10 VEH 3 ADV 1 BIKE	17000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-023540-PV1	ROSECRANS ST	MALAGA ST	MADRID ST	2	Monday	PENINSULA	Major	6	420	60	25,200	226.80	0	10,080	25,200	25,200	0	0.00	17.31	0	2	0	0	0	0	0	39900	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.	
SS-023541-PV1	ROSECRANS ST	ROSECRANS PL	MALAGA ST	2	Monday	MIDWAY-PACIFIC HIGHWAY	Major	6	539	85	45,815	412.34	0	12,936	45,815	45,815	0	0.00	10.16	0	0	0	0	0	1	0	17000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.	
SS-023594-PV1	ROSECRANS ST	LYTTON ST	ROSECRANS PL	2	Monday	MIDWAY-PACIFIC HIGHWAY	Major	6	238	90	21,420	192.78	0	5,712	21,420	21,420	0	0.00	0.32	0	1	0	0	0	0	0	17000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.	
SS-023576-PV1	ROSECRANS ST	CANON ST	AVNDA DE PORTUGAL	2	Monday	PENINSULA	Major	4	233	68	15,844	142.60	0	5,592	15,844	15,844	0	3.81	10.39	0	0	0	0	0	0	0	17000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.	
SS-023577-PV1	ROSECRANS ST	UPSHUR ST	CANON ST	2	Monday	PENINSULA	Major	2	289	56	16,184	145.66	0	6,936	16,184	16,184	0	7.69	22.04	1	1	0	0	0	0	0	17000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.	
SS-023578-PV1	ROSECRANS ST	TALBOT ST	UPSHUR ST	2	Monday	PENINSULA	Major	2	204	48	9,792	88.13	0	4,896	9,792	9,792	0	0.00	19.54	1	1	0	0	0	0	18	SB at Lytton St 14 VEH 2 ADV 2 BIKE	17110	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-023523-PV1	ROSECRANS PL	ROSECRANS ST	CADIZ ST	2		MIDWAY-PACIFIC HIGHWAY	Residential	2	142	61	8,662	77.96	0	61	8,662	0	0	0.00	11.06	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-023459-PV1	ROMNEY RD	SAN AQUARIO DR	PACIFICA DR	1	Monday	PACIFIC BEACH	Residential	2	238	39	9,282	83.54	0	9,282	9,282	0	476	0.00	4.12	0	0	0	0	0	1	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II. Edge grind both sides.	
SS-023460-PV1	ROMNEY RD	PENDELETEON ST	SAN AQUARIO DR	1	Monday	PACIFIC BEACH	Residential	2	1,166	37	43,142	388.28	0	43,142	43,142	0	2,332	14.43	18.53	0	2	2	0	2	1	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II. Edge grind both sides.	
SS-023457-PV1	ROMERO DR	BEGIN	BRODIAEA WY	1	Monday	LA JOLLA	Residential	2	772	20	15,440	138.96																		


SLURRY SEAL GROUP 2524
IO: 21005580
ESTIMATED CONSTRUCTION QUANTITIES

Pavement ID	Street Name	Cross Street 1	Cross Street 2	Council District	Trash Day	Community Planning Area	Functional Classification	Lane Count	Survey Length (LF)	Survey Width (LF)	Survey Area (SF)	Crack Seal (LB)	Cape Seal (SF)	Slurry Seal Type I (SF)	Slurry Seal Type II (SF)	Slurry Seal Type III (SF)	6" Edge Grind (LF)	Base Repair [TONS]	Mill & Pave [TONS]	Inlet Marking (EA)	Inlet Protection (EA)	Adjust Survey Monument (EA)	Reconstruct Survey Monument (EA)	Water Valve (EA)	Sewer Manhole (EA)	Traffic Loops (EA)	Traffic Loops Location	ADT	Treatment Type	Task Comments
SS-019893-PV1	NIAGARA AV	BACON ST	END	2	Monday	OCEAN BEACH	Local	2	552	38	20,976	0.00	20,976	0	0	0	0	0.00	44.88	0	0	0	0	0	0	0	2500	CAPE SEAL	CAPE SEAL	
SS-018672-PV1	MOANA DR	LA PALOMA ST	LA PALOMA ST	2	Monday	PENINSULA	Residential	2	343	36	12,348	111.13	0	12,348	0	0	0	0.00	0.95	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-018677-PV1	MOANA DR	VARONA ST	LA PALOMA ST	2	Monday	PENINSULA	Residential	2	648	37	23,976	215.78	0	23,976	23,976	0	0	0.00	0.21	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-017327-PV1	MANGO DR	PORTOFINO DR	CAROUSEL LN	1	Monday	TORREY PINES	Major	2	394	38	14,972	134.75	0	14,972	14,972	0	0	7.56	21.41	0	1	0	0	0	1	0	17000	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-016969-PV1	LUCERNE DR	POINSETTIA DR	ZOLA ST	2	Monday	PENINSULA	Residential	2	652	31	20,212	181.91	0	20,212	20,212	0	0	0.00	2.69	0	0	0	0	0	1	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-016672-PV1	LOCUST ST	NIMITZ BL	MACAULAY ST	2	Monday	PENINSULA	Residential	2	216	34	7,344	66.10	0	7,344	7,344	0	0	0.00	15.51	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-016673-PV1	LOCUST ST	KEATS ST	NIMITZ BL	2	Monday	PENINSULA	Prime	2	199	32	6,368	57.31	0	6,368	6,368	0	0	0.00	18.28	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-016684-PV1	LOCUST ST	CANON ST	AVNDA DE PORTUGAL	2	Monday	PENINSULA	Prime	2	160	38	6,080	54.72	0	6,080	6,080	0	0	0.00	9.21	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-015681-PV1	LA PINTURA DR	OLITE CT	LA JOLLA SCENIC S DR	1	Monday	LA JOLLA	Residential	2	276	36	9,936	0.00	9,936	0	0	0	0	0.00	21.70	0	0	0	0	0	0	0	2500	CAPE SEAL	CAPE SEAL	
SS-015682-PV1	LA PINTURA DR	AVILA CT	OLITE CT	1	Monday	LA JOLLA	Residential	2	1,362	33	44,946	10.80	43,746	0	1,200	0	0	96.11	68.39	2	2	1	1	2	0	0	2500	CAPE SEAL	CAPE SEAL to stop at PCR (refer to the resurfacing limit map).	
SS-015683-PV1	LA PINTURA DR	BEGIN	AVILA CT	1	Monday	LA JOLLA	Residential	2	449	37	16,613	59.58	9,993	0	6,620	0	0	3.15	9.27	0	1	2	0	2	0	0	2500	CAPE SEAL	CAPE SEAL to stop 35 ft from PCR (40 ft S/O Fire Hydrant) and at the Cul-De-Sac PCR, (refer to the resurfacing limit map).	
SS-015678-PV1	LA PALOMA ST	SAVOY ST	MOANA DR	2	Monday	PENINSULA	Residential	2	294	38	11,172	100.55	0	11,172	11,172	0	0	0.00	2.53	0	0	0	0	2	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-015577-PV1	LA JOLLA RANCHO RD	RAVENSWOOD RD	BOX CANYON RD	1	Monday	LA JOLLA	Prime	2	644	37	23,828	214.45	0	23,828	23,828	0	0	10.49	22.16	0	0	0	0	7	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-015566-PV1	LA JOLLA MESA DR	VAN NUYS ST	COLIMA ST	1	Monday	LA JOLLA	Prime	2	400	40	16,000	144.00	0	0	16,000	16,000	0	4.16	16.92	0	0	0	0	2	1	0	16000	SLURRY SEAL	SLURRY SEAL TYPE II/III.	
SS-015568-PV1	LA JOLLA MESA DR	AGATE ST	ARCHER ST	1	Monday	PACIFIC BEACH	Prime	2	324	45	14,580	131.22	0	0	14,580	14,580	0	0.00	21.48	0	0	0	0	3	0	0	16000	SLURRY SEAL	SLURRY SEAL TYPE II/III.	
SS-015518-PV1	LA JOLLA BL	WRELTON DR	TURQUOISE ST	1	Monday	LA JOLLA	Major	2	190	70	13,300	119.70	0	4,560	13,300	13,300	0	0.00	0.53	0	0	0	0	1	0	0	17000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE.	
SS-015249-PV1	KINGSLEY ST	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Residential	2	386	37	14,282	128.54	0	14,282	14,282	0	0	0.00	1.27	0	2	0	0	0	1	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-015250-PV1	KINGSLEY ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Residential	2	350	37	12,950	116.55	0	12,950	12,950	0	0	1.51	2.14	0	1	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-014902-PV1	KANE ST	ERIE ST	FRANKFORT ST	2	Wednesday	CLAIREMONT MESA	Residential	2	349	36	12,564	113.08	0	12,564	12,564	0	0	0.00	17.45	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-014675-PV1	JONQUIL DR	ELLIOTT ST	LOTUS DR	2	Monday	PENINSULA	Residential	2	680	37	25,160	226.44	0	25,160	25,160	0	0	0.00	27.76	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-014121-PV1	INGELOW ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Residential	2	338	36	12,168	109.51	0	12,168	12,168	0	0	6.52	4.99	0	1	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-013762-PV1	HORNBLEND ST	CASS ST	DAWES ST	1	Monday	PACIFIC BEACH	Prime	2	579	52	30,117	0.00	30,117	0	0	0	0	0.00	10.47	0	0	0	0	0	0	0	2500	CAPE SEAL	CAPE SEAL	
SS-013122-PV1	HARTFORD ST	HUXLEY ST	CLAIREMONT DR	2	Wednesday	CLAIREMONT MESA	Residential	2	313	34	10,642	95.78	0	10,642	10,642	0	0	0.00	5.17	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-012980-PV1	HANCOCK ST	CHANNEL WY	SPORTS ARENA BL	2	Monday	MIDWAY-PACIFIC HIGHWAY	Major	2	896	61	54,656	491.90	0	0	54,656	54,656	0	6.24	27.64	0	0	0	0	3	1	0	5460	SLURRY SEAL	SLURRY SEAL TYPE II/III. Diagonal/Parallel Parking.	
SS-012382-PV1	GOLDSMITH ST	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Residential	2	350	39	13,650	122.85	0	13,650	13,650	0	0	0.00	3.30	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-012383-PV1	GOLDSMITH ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Residential	2	354	40	14,160	127.44	0	14,160	14,160	0	0	0.00	1.64	0	4	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-012355-PV1	GOLDFIELD ST	LITTLEFIELD ST	ASHTON ST	2	Wednesday	CLAIREMONT MESA	Residential	2	530	38	20,140	181.26	0	20,140	20,140	0	0	0.00	3.17	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-012330-PV1	GOLDBORO ST	GEORGETOWN AV	GALENA AV	2	Wednesday	CLAIREMONT MESA	Residential	2	226	34	7,684	69.16	0	7,684	7,684	0	0	2.27	22.28	0	0	0	0	1	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-012160-PV1	GIRARD AV	PEARL ST	TORREY PINES RD	1	Monday	LA JOLLA	Major	3	512	66	33,792	52.50	27,959	0	5,833	0	0	5.86	48.84	0	1	0	0	0	0	0	28970	CAPE SEAL SLURRY SEAL	PARTIAL CAPE SEAL & SLURRY SEAL SLURRY SEAL TYPE II for final 50 FT. Stop Cape Seal limits 50ft off the resurfacing limits @ Torrey Pines Rd. Stop Cape Seal limits 50ft off the resurfacing limits @ Pearl St.	
SS-012091-PV1	GESNER ST	GESNER PL	EDISON ST	2	Wednesday	CLAIREMONT MESA	Residential	2	260	26	6,760	60.84	0	6,760	6,760	0	0	0.00	0.00	0	0	0	0	0	1	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-012093-PV1	GESNER ST	BAY CANYON CT	GESNER PL	2	Wednesday	CLAIREMONT MESA	Residential	2	534	25	13,350	120.15	0	13,350	13,350	0	0	0.00	2.22	1	2	2	0	0	2	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-012052-PV1	GEORGETOWN AV	GOLDBORO ST	GASCONADE AV	2	Wednesday	CLAIREMONT MESA	Residential	2	686	33	22,638	0.00	22,638	0	0	0	0	0.00	7.29	0	0	0	0	0	0	0	2500	CAPE SEAL	CAPE SEAL	
SS-012053-PV1	GEORGETOWN AV	GASCONADE AV	CROSS ST	2	Wednesday	CLAIREMONT MESA	Residential	2	400	33	13,200	0.00	13,200	0	0	0	0	0.00	8.13	0	0	0	0	0	0	0	2500	CAPE SEAL	CAPE SEAL	
SS-011896-PV1	GARRISON ST	PLUM ST	CLOVE ST	2	Monday	PENINSULA	Prime	2	400	34	13,600	122.40	0	13,600	13,600	0	0	0.00	0.53	0	0	0	0	0	1	0	16000	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-011872-PV1	GARNET AV	NOYES ST	OLNEY ST	1	Monday	PACIFIC BEACH	Collector	3	520	54	28,080	0.00	28,080	0	0	0	0	10.24	14.06	0	1	0	0	1	0	0	15000	CAPE SEAL	CAPE SEAL	
SS-011799-PV1	GALVESTON ST	GARDENA AV	ASHTON ST	2	Wednesday	CLAIREMONT MESA	Residential	2	550	34	18,700	168.30	0	18,700	18,700	0	0	0.00	0.00	0	0	1	0	2	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-011623-PV1	FROUDE ST	DEL MONTE AV	NARRAGANSETT AV	2	Monday	PENINSULA	Residential	2	341	36	12,276	110.48	0	12,276	12,276	0	0	1.51	24.05	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-011624-PV1	FROUDE ST	SANTA CRUZ AV	NAR MONTE AV	2	Monday	PENINSULA	Residential	2	398	36	14,328	128.95	0	14,328	14,328	0	0	0.00	3.01	0	0	0	0	10	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-011469-PV1	FREEMAN ST	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Local	2	348	40	13,920	125.28	0	13,920	13,920	0	0	1.26	7.60	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-011470-PV1	FREEMAN ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Prime	2	346	37	12,802	115.22	0	12,802	12,802	0	0	0.00	3.75	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-011424-PV1	FRANKFORT ST	KANE ST	JELLETT ST	2	Wednesday	CLAIREMONT MESA	Residential	2	441	20	8,812	79.31	0	8,812	8,812	0	0	0.00	14.94	0	0	0	0	1	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-011385-PV1	FORWARD ST	LA JOLLA BL	LA JOLLA HERMOSA AV	1	Monday	LA JOLLA	Local	2	267	29	7,743	69.69	0	7,743	7,743	0	0	0.00	6.20	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-011021-PV1	FENELOM ST	PLUM ST	CLOVE ST	2	Monday	PENINSULA	Residential	2	370	35	12,950	116.55	0	12,950	12,950	0	0	0.00	30.84	0	0	0	0	1	2	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-010629-PV1	EVERGREEN ST	JAMES ST	KINGSLEY ST	2	Monday	PENINSULA	Residential	2	257	35	8,995	80.96	0	8,995	8,995	0	0	0.00	0.21	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-010630-PV1	EVERGREEN ST	IBSEN ST	JAMES ST	2	Monday	PENINSULA	Residential	2	270	34	9,180	82.62	0	9,180	9,180	0	0	0.00	0.00	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-010631-PV1	EVERGREEN ST	HOMER ST	IBSEN ST	2	Monday	PENINSULA	Residential	2	270	34	9,194	82.75	0	9,194	9,194	0	0	0.00	1.23	0	0	0	0	0	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-010632-PV1	EVERGREEN ST	GOLDSMITH ST	HOMER ST	2	Monday	PENINSULA	Residential	2	269	34	9,154	82.39	0	9,154	9,154	0	0	0.00	0.00	0	0	0	0	1	1	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-010633-PV1	EVERGREEN ST	FREEMAN ST	GOLDSMITH ST	2	Monday	PENINSULA	Residential	2	304	34	10,336	93.02	0	10,336	10,336	0	0	0.00	0.90	0	0	0	0	1	0	0	2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.	
SS-010418-PV1	ERIE ST	KANE ST	JELLETT ST	2	Wednesday	CLAIREMONT MESA	Residential	2	436	38	16,56																			

SLURRY SEAL GROUP 2524
IO: 21005580
ESTIMATED CONSTRUCTION QUANTITIES

Pavement ID	Street Name	Cross Street 1	Cross Street 2	Council District	Trash Day	Community Planning Area	Functional Classification	Lane Count	Survey Length (LF)	Survey Width (LF)	Survey Area (SF)	Crack Seal (LB)	Cape Seal (SF)	Slurry Seal Type I (SF)	Slurry Seal Type II (SF)	Slurry Seal Type III (SF)	6" Edge Grind (LF)	Base Repair [TONS]	Mill & Pave [TONS]	Inlet Marking (EA)	Inlet Protection (EA)	Adjust Survey Monument (EA)	Reconstruct Survey Monument (EA)	Water Valve (EA)	Sewer Manhole (EA)	Traffic Loops (EA)	Traffic Loops Location	ADT	Treatment Type	Task Comments
SS-007431-PV1	CLOVE ST	FENELON ST	GARRISON ST	2	Monday	PENINSULA	Residential	2	312	33	10,296	92.66	0	10,296	10,296	0	0	0.00	10.39	0	0	0	0	0	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-007014-PV1	CHATSWORTH BL	ALCOTT ST	BROWNING ST	2	Monday	PENINSULA	Major	2	103	42	4,336	39.02	0	0	4,336	4,336	0	0.00	12.32	1	1	0	0	6	1	0		17000	SLURRY SEAL	SLURRY SEAL TYPE II/III.
SS-006524-PV1	CAROUSEL LN	BEGIN	MANGO DR	1	Monday	TORREY PINES	Residential	2	657	28	18,396	165.56	0	18,396	18,396	0	0	20.54	20.64	0	0	0	0	0	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006497-PV1	CARMELO ST	CORNISH DR	CORDOVA ST	2	Monday	PENINSULA	Local	2	550	36	19,800	178.20	0	19,800	19,800	0	0	0.00	11.60	0	0	0	0	0	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006498-PV1	CARMELO ST	CORDOVA ST	SUNSET CLIFFS BL	2	Monday	PENINSULA	Local	2	332	37	12,284	110.56	0	12,284	12,284	0	0	0.00	26.40	0	0	0	0	0	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006395-PV1	CARMEL KNOLLS DR	BEACHCOMBER CT	PEARLMAN WY	1	Monday	CARMEL VALLEY	Major	2	294	38	11,172	100.55	0	11,172	11,172	0	0	2.27	0.63	0	1	0	0	5	0	0		17000	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006396-PV1	CARMEL KNOLLS DR	SANDHILL TR	BEACHCOMBER CT	1	Monday	CARMEL VALLEY	Major	2	288	38	10,952	98.57	0	10,952	10,952	0	0	0.00	4.33	1	2	0	0	1	1	0		17000	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006397-PV1	CARMEL KNOLLS DR	SANDDOLLAR CT	SANDHILL TR	1	Monday	CARMEL VALLEY	Major	2	498	37	18,426	165.83	0	18,426	18,426	0	0	0.00	1.86	0	1	0	0	0	2	0		17000	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006398-PV1	CARMEL KNOLLS DR	PACIFIC GROVE PL	SANDDOLLAR CT	1	Monday	CARMEL VALLEY	Major	2	248	38	9,424	84.82	0	9,424	9,424	0	0	0.00	1.11	0	1	0	0	2	1	0		17000	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006399-PV1	CARMEL KNOLLS DR	SOUTHAMPTON CV	PACIFIC GROVE PL	1	Monday	CARMEL VALLEY	Major	2	238	37	8,804	79.24	0	8,804	8,804	0	0	0.00	1.16	2	2	0	0	3	1	0		17000	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006400-PV1	CARMEL KNOLLS DR	CARMEL CANYON RD	ASHLEY FALLS DR	1		CARMEL VALLEY	Major	2	442	46	20,332	182.99	0	20,332	20,332	0	0	0.00	1.06	0	0	0	0	0	2	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006405-PV1	CARMEL KNOLLS DR	ASHLEY FALLS DR	WINDY HEIGHTS WY	1		CARMEL VALLEY	Major	2	532	42	22,344	201.10	0	22,344	22,344	0	0	0.00	0.84	0	0	1	0	6	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006406-PV1	CARMEL KNOLLS DR	SEABREEZE FARMS DR	SOUTHAMPTON CV	1	Monday	CARMEL VALLEY	Major	2	182	37	6,734	60.61	0	6,734	6,734	0	0	0.00	0.86	0	0	0	0	2	1	0		17000	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006407-PV1	CARMEL KNOLLS DR	SANDY CREST CT	CHANDON CT	1	Monday	CARMEL VALLEY	Major	2	265	38	10,076	90.68	0	10,076	10,076	0	0	0.00	3.96	0	1	0	0	5	3	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006408-PV1	CARMEL KNOLLS DR	WINDY HEIGHTS WY	ALMONDWOOD WY	1		CARMEL VALLEY	Major	2	550	38	20,900	188.10	0	20,900	20,900	0	0	0.00	3.81	0	2	1	0	4	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006409-PV1	CARMEL KNOLLS DR	ALMONDWOOD WY	SANDY CREST CT	1		CARMEL VALLEY	Major	2	444	38	16,872	151.85	0	16,872	16,872	0	0	0.00	26.19	0	2	0	0	1	1	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-031338-PV1	CARMEL KNOLLS DR	CHANDON CT	SEABREEZE FARMS DR	1		CARMEL VALLEY	Major	2	800	38	30,386	273.48	0	30,386	30,386	0	0	0.00	8.34	0	1	1	0	1	4	0		17000	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006370-PV1	CARMEL COUNTRY RD	DEL MAR MESA RD	SHAW VALLEY RD	1		CARMEL VALLEY	Major	3	794	64	50,816	457.34	0	19,056	50,816	50,816	0	2.14	50.12	0	0	0	0	3	2	0		17000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-006379-PV1	CARMEL COUNTRY RD	SAGAMORE WY	DEL MAR MESA RD	1		CARMEL VALLEY	Collector	2	1,820	66	120,120	1,081.08	0	43,680	120,120	120,120	0	0.00	44.26	4	4	0	0	10	10	16	SB at Grand Del Mar Way 6 VEH 1 ADV 1 BIKE NB at Grand Del Mar Way 6 VEH 1 ADV 1 BIKE	15000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-006252-PV1	CARDENO DR	VIA CABRERA	LA JOLLA SCENIC S DR	1	Monday	LA JOLLA	Residential	2	448	72	32,256	290.30	0	0	32,256	32,256	896	11.34	15.26	0	0	0	0	1	0	0		6150	SLURRY SEAL	SLURRY SEAL TYPE II/III. Edge grind both sides.
SS-006262-PV1	CARDENO DR	CALLE VAQUERO	CAMTO ACENTO	1	Monday	LA JOLLA	Residential	2	880	38	33,440	300.96	0	21,120	33,440	33,440	0	0.00	14.94	2	2	0	0	2	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-006263-PV1	CARDENO DR	VIA NINA	VIA CABRERA	1	Monday	LA JOLLA	Residential	2	1,444	38	54,872	493.85	0	0	54,872	54,872	2,888	19.53	22.27	0	0	0	0	1	2	0		2500	SLURRY SEAL	SLURRY SEAL TYPE II/III. Edge grind both sides.
SS-006265-PV1	CARDENO DR	CAMTO ACENTO	ALTA LA JOLLA DR	1	Monday	LA JOLLA	Residential	2	762	38	28,956	260.60	0	18,288	28,956	28,956	0	14.65	5.07	0	0	0	0	2	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-010885-PV1	CARDENO DR	KAIMALINO LN	CALLE VAQUERO	1		LA JOLLA	Residential	2	1,104	37	40,848	367.63	0	26,496	40,848	40,848	0	0.00	5.86	0	0	0	0	4	1	0		2500	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-006225-PV1	CAPISTRANO ST	POE ST	QUIMBY ST	2	Monday	PENINSULA	Prime	2	375	38	14,250	128.25	0	14,250	14,250	0	0	0.00	6.18	0	0	0	0	0	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-006140-PV1	CANON ST	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Major	2	352	50	17,600	158.40	0	8,448	17,600	17,600	0	0.00	17.45	0	1	0	0	0	0	0		15600	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-006141-PV1	CANON ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Prime	2	358	50	17,900	161.10	0	8,592	17,900	17,900	0	2.52	15.22	0	1	0	0	0	0	7	SB at Rosecrans St 6 VEH 1 BIKE	16000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-006145-PV1	CANON ST	SHAFTER ST	SCOTT ST	2	Monday	PENINSULA	Residential	2	326	50	16,300	146.70	0	16,300	16,300	0	0	0.00	3.96	0	0	0	0	0	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II. Diagonal/Parallel Parking.
SS-006147-PV1	CANON ST	AKRON ST	DEL MAR AV	2	Monday	PENINSULA	Major	2	1,670	40	66,800	601.20	0	40,080	66,800	66,800	0	12.10	108.86	2	2	0	0	2	2	0		17000	SLURRY SEAL	SLURRY SEAL TYPE II/III. TYPE I OVER BIKE LANE. STRIPING MOD.
SS-005639-PV1	CALLE VAQUERO	CARDENO DR	CASTLE HILLS DR	1	Monday	LA JOLLA	Residential	2	172	39	6,708	0.00	6,708	0	0	0	0	0.00	28.46	0	0	0	0	0	0	0		2500	CAPE SEAL	CAPE SEAL
SS-005640-PV1	CALLE VAQUERO	CALLE MIRAMAR	WESTKNOLL DR	1	Monday	LA JOLLA	Residential	2	496	38	18,848	0.00	18,848	0	0	0	0	0.00	15.81	0	2	1	0	1	0	0		2500	CAPE SEAL	CAPE SEAL
SS-005641-PV1	CALLE VAQUERO	CASTLE HILLS DR	CALLE MIRAMAR	1	Monday	LA JOLLA	Residential	2	219	37	8,103	0.00	8,103	0	0	0	0	13.73	4.20	0	0	0	0	0	0	0		2500	CAPE SEAL	CAPE SEAL
SS-005283-PV1	CABLE ST	VOLTAIRE ST	LOTUS ST	2	Monday	OCEAN BEACH	Major	2	299	41	12,259	110.33	0	12,259	12,259	0	0	0.00	13.83	0	0	1	0	0	0	0		6620	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-005292-PV1	CABLE ST	NARRAGANSETT AV	NIAGARA AV	2	Monday	OCEAN BEACH	Collector	2	400	37	14,800	133.20	0	14,800	14,800	0	0	0.00	19.91	2	2	0	0	0	0	0		4870	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-005293-PV1	CABLE ST	DEL MONTE AV	NARRAGANSETT AV	2	Monday	OCEAN BEACH	Collector	2	387	37	14,319	128.87	0	14,319	14,319	0	0	10.46	9.61	0	0	0	0	0	0	0		15000	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-005294-PV1	CABLE ST	SANTA CRUZ AV	DEL MONTE AV	2	Monday	OCEAN BEACH	Major	2	395	38	15,010	135.09	0	15,010	15,010	0	0	0.79	5.60	0	0	0	0	0	0	0		17000	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-004974-PV1	BRODIAEA WY	ROMERO DR	ENCELIA DR	1	Monday	LA JOLLA	Prime	4	770	22	16,940	152.46	0	16,940	16,940	0	0	8.44	27.98	1	1	0	0	1	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-003939-PV1	BELLEVUE AV	COLUMA ST	MIDWAY ST	1	Monday	LA JOLLA	Residential	2	560	32	17,920	0.00	17,920	0	0	0	0	12.41	37.54	0	0	0	0	0	0	0		2500	CAPE SEAL	CAPE SEAL
SS-003364-PV1	BAHIA WY	BAHIA DR	THUNDERBIRD LN	1	Monday	LA JOLLA	Residential	2	270	34	9,180	82.62	0	9,180	9,180	0	0	0.00	2.43	0	0	1	0	0	1	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-003361-PV1	BAHIA LN	BAHIA WY	CORAL REEF AV	1	Monday	LA JOLLA	Residential	2	441	37	16,317	146.85	0	16,317	16,317	0	0	7.62	18.48	0	0	0	0	0	3	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-003362-PV1	BAHIA LN	PARKVIEW TR	BAHIA WY	1	Monday	LA JOLLA	Residential	2	764	34	25,976	233.78	0	25,976	25,976	0	0	19.09	46.61	0	0	0	0	1	2	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-003347-PV1	BACON ST	NARRAGANSETT AV	NIAGARA AV	2	Monday	OCEAN BEACH	Prime	2	379	34	12,879	115.91	0	12,879	12,879	0	0	12.54	20.84	0	0	0	0	0	0	0		4270	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-003167-PV1	AVNDA DE PORTUGAL	EVERGREEN ST	WILLOW ST	2	Monday	PENINSULA	Residential	2	333	38	12,654	113.89	0	12,654	12,654	0	0	6.17	0.59	0	0	0	0	0	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-003168-PV1	AVNDA DE PORTUGAL	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Residential	2	362	36	13,032	117.29	0	13,032	13,032	0	0	5.32	1.80	0	0	0	0	0	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-003169-PV1	AVNDA DE PORTUGAL	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Residential	2	349	34	11,866	106.79	0	11,866	11,866	0	0	12.16	0.48	0	0	0	0	0	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-003102-PV1	AVNDA CHAMNEZ	BEGIN	VIA ESPANA	1	Monday	LA JOLLA	Residential	2	732	34	24,888	223.99	0	24,888	24,888	0	0	0.00	45.63	1	1	0	0	0	0	0		2500	SLURRY SEAL	SLURRY SEAL TYPE I/II.
SS-003103-PV1	AVNDA CHAMNEZ	VIA ESPANA	END	1	Monday	LA JOLLA	Residential	2	874	35	30,590	275.31	0	30,590	30,590	0	0	14.49</												

APPENDIX L
SCRUB BROOM DIAGRAM



APPENDIX M

STREET LIST

SLURRY SEAL GROUP 2524

IO: 21005580

STREET LIST

Work Order	Pavement ID	Street Name	Cross Street 1	Cross Street 2	Council District	Trash Day	Community Planning Area	Functional Classification
S2524	SS-029245-PV1	ZOLA ST	LUCERNE DR	PALERMO DR	2	Monday	PENINSULA	Residential
S2524	SS-029246-PV1	ZOLA ST	POINSETTIA DR	LUCERNE DR	2	Monday	PENINSULA	Residential
S2524	SS-029247-PV1	ZOLA ST	CHATSWORTH BL	POINSETTIA DR	2	Monday	PENINSULA	Residential
S2524	SS-028823-PV1	WILLOW ST	WESTCLIFFE PL	VOLTAIRE ST	2	Monday	PENINSULA	Prime
S2524	SS-028824-PV1	WILLOW ST	UDALL ST	WESTCLIFFE PL	2	Monday	PENINSULA	Prime
S2524	SS-028841-PV1	WILLOW ST	BYRON ST	CARLETON ST	2	Monday	PENINSULA	Residential
S2524	SS-028842-PV1	WILLOW ST	AVNDA DE PORTUGAL	BYRON ST	2	Monday	PENINSULA	Residential
S2524	SS-028843-PV1	WILLOW ST	CANON ST	AVNDA DE PORTUGAL	2	Monday	PENINSULA	Residential
S2524	SS-028566-PV1	WESTKNOLL DR	WESTKNOLL LN	CALLE VAQUERO	1	Monday	PACIFIC BEACH	Residential
S2524	SS-028127-PV1	VOLTAIRE ST	SUNSET CLIFFS BL	CABLE ST	2	Monday	OCEAN BEACH	Collector
S2524	SS-028128-PV1	VOLTAIRE ST	EBERS ST	SUNSET CLIFFS BL	2	Monday	OCEAN BEACH	Collector
S2524	SS-028081-PV1	VISTA SORRENTO PY	OCEAN BLUFF AV	CARMEL MTN RD	1		TORREY HILLS	Major
S2524	SS-028083-PV1	VISTA SORRENTO PY	CALLE MAR DE MARIPOS	OCEAN BLUFF AV	1		TORREY HILLS	Major
S2524	SS-027660-PV1	VIA CORONA	COPA DE ORO DR	RUTGERS DR	1	Monday	LA JOLLA	Residential
S2524	SS-027661-PV1	VIA CORONA	COPA DE ORO DR	END	1	Monday	LA JOLLA	Residential
S2524	SS-027337-PV1	VALEMONT ST	CANON ST	END	2	Monday	PENINSULA	Residential
S2524	SS-027049-PV1	UDALL ST	WILLOW ST	PLUM ST	2	Monday	PENINSULA	Residential
S2524	SS-026940-PV1	TURQUOISE ST	WRELTON DR	LA JOLLA MESA DR	1	Monday	PACIFIC BEACH	Residential
S2524	SS-026943-PV1	TURQUOISE ST	LA JOLLA BL	END	1	Monday	PACIFIC BEACH	Residential
S2524	SS-026945-PV1	TURQUOISE ST	BEGIN	WRELTON DR	1	Monday	PACIFIC BEACH	Residential
S2524	SS-030909-PV1	TRZA MAR MARVELOSA	EAST OCEAN AIR DR	END	1	Monday	TORREY HILLS	Residential
S2524	SS-026392-PV1	THOMAS AV	DAWES ST	EVERTS ST	1	Monday	PACIFIC BEACH	Residential
S2524	SS-025904-PV1	SUNSET CLIFFS BL	PESCADERO AV	ORCHARD AV	2	Monday	OCEAN BEACH	Prime
S2524	SS-025905-PV1	SUNSET CLIFFS BL	BERMUDA AV	PESCADERO AV	2	Monday	OCEAN BEACH	Prime
S2524	SS-025906-PV1	SUNSET CLIFFS BL	POINT LOMA AV	BERMUDA AV	2	Monday	OCEAN BEACH	Prime
S2524	SS-025175-PV1	SOLEDAD MTN RD	PALOMINO CR	SOLEDAD RD	1	Monday	LA JOLLA	Major
S2524	SS-025176-PV1	SOLEDAD MTN RD	DESERT VIEW DR	PALM CANYON DR	1	Monday	LA JOLLA	Major
S2524	SS-025189-PV1	SOLEDAD MTN RD	PALM CANYON DR	PALOMINO CR	1	Monday	LA JOLLA	Major
S2524	SS-025171-PV1	SOLEDAD AV	AL BAHR DR	LUDINGTON PL	1	Monday	LA JOLLA	Prime
S2524	SS-024497-PV1	SCOTT ST	AVNDA DE PORTUGAL	SHELTER ISLAND DR	2	Monday	PENINSULA	Collector
S2524	SS-024498-PV1	SCOTT ST	CANON ST	AVNDA DE PORTUGAL	2	Monday	PENINSULA	Collector
S2524	SS-024265-PV1	SANTA CRUZ AV	FROUDE ST	EBERS ST	2	Monday	OCEAN BEACH	Residential
S2524	SS-024236-PV1	SANTA BARBARA ST	SANTA MONICA AV	SARATOGA AV	2	Monday	PENINSULA	Prime
S2524	SS-024239-PV1	SANTA BARBARA ST	NARRAGANSETT AV	NIAGARA AV	2	Monday	PENINSULA	Prime
S2524	SS-024240-PV1	SANTA BARBARA ST	DEL MONTE AV	NARRAGANSETT AV	2	Monday	PENINSULA	Prime
S2524	SS-023815-PV1	RUSHVILLE ST	DRAPER AV	EADS AV	1	Monday	LA JOLLA	Residential
S2524	SS-023539-PV1	ROSECRANS ST	MADRID ST	NORTH EVERGREEN ST	2	Monday	MIDWAY-PACIFIC HIGHWAY	Major
S2524	SS-023540-PV1	ROSECRANS ST	MALAGA ST	MADRID ST	2	Monday	PENINSULA	Major
S2524	SS-023541-PV1	ROSECRANS ST	ROSECRANS PL	MALAGA ST	2	Monday	MIDWAY-PACIFIC HIGHWAY	Major
S2524	SS-023594-PV1	ROSECRANS ST	LYTTON ST	ROSECRANS PL	2	Monday	MIDWAY-PACIFIC HIGHWAY	Major
S2524	SS-023576-PV1	ROSECRANS ST	CANON ST	AVNDA DE PORTUGAL	2	Monday	PENINSULA	Major
S2524	SS-023577-PV1	ROSECRANS ST	UPSHUR ST	CANON ST	2	Monday	PENINSULA	Major
S2524	SS-023578-PV1	ROSECRANS ST	TALBOT ST	UPSHUR ST	2	Monday	PENINSULA	Major
S2524	SS-023523-PV1	ROSECRANS PL	ROSECRANS ST	CADIZ ST	2		MIDWAY-PACIFIC HIGHWAY	Residential
S2524	SS-023459-PV1	ROMNEY RD	SAN AQUARIO DR	PACIFICA DR	1	Monday	PACIFIC BEACH	Residential
S2524	SS-023460-PV1	ROMNEY RD	PENDLETON ST	SAN AQUARIO DR	1	Monday	PACIFIC BEACH	Residential
S2524	SS-023457-PV1	ROMERO DR	BEGIN	BRODIAEA WY	1	Monday	LA JOLLA	Residential
S2524	SS-022743-PV1	RANLEIGH CT	LOCUST ST	END	2	Monday	PENINSULA	Residential
S2524	SS-022065-PV1	POINSETTIA DR	LUCERNE DR	ZOLA ST	2	Monday	PENINSULA	Residential
S2524	SS-022066-PV1	POINSETTIA DR	PALERMO DR	LUCERNE DR	2	Monday	PENINSULA	Residential
S2524	SS-022067-PV1	POINSETTIA DR	VOLTAIRE ST	PALERMO DR	2	Monday	PENINSULA	Residential
S2524	SS-022043-PV1	POE ST	CAPISTRANO ST	NIMITZ BL	2	Monday	PENINSULA	Residential
S2524	SS-021002-PV1	PALERMO DR	ZOLA ST	ALCOTT ST	2	Monday	PENINSULA	Residential
S2524	SS-021004-PV1	PALERMO DR	YONGE ST	ZOLA ST	2	Monday	PENINSULA	Residential
S2524	SS-021005-PV1	PALERMO DR	POINSETTIA DR	YONGE ST	2	Monday	PENINSULA	Residential
S2524	SS-020503-PV1	OLIVETAS AV	MARINE ST	PEARL ST	1	Monday	LA JOLLA	Prime
S2524	SS-020486-PV1	OLIVER AV	GRESHAM ST	HAINES ST	1	Monday	PACIFIC BEACH	Residential
S2524	SS-020489-PV1	OLIVER AV	DAWES ST	EVERTS ST	1	Monday	PACIFIC BEACH	Residential
S2524	SS-020179-PV1	NOYES ST	HORNBLEND ST	GARNET AV	1	Monday	PACIFIC BEACH	Prime
S2524	SS-019886-PV1	NIAGARA AV	CABLE ST	BACON ST	2	Monday	OCEAN BEACH	Major
S2524	SS-019893-PV1	NIAGARA AV	BACON ST	END	2	Monday	OCEAN BEACH	Local
S2524	SS-018672-PV1	MOANA DR	LA PALOMA ST	LA PALOMA ST	2	Monday	PENINSULA	Residential
S2524	SS-018677-PV1	MOANA DR	VARONA ST	LA PALOMA ST	2	Monday	PENINSULA	Residential
S2524	SS-017327-PV1	MANGO DR	PORTOFINO DR	CAROUSEL LN	1	Monday	TORREY PINES	Major
S2524	SS-016969-PV1	LUCERNE DR	POINSETTIA DR	ZOLA ST	2	Monday	PENINSULA	Residential
S2524	SS-016672-PV1	LOCUST ST	NIMITZ BL	MACAULAY ST	2	Monday	PENINSULA	Residential
S2524	SS-016673-PV1	LOCUST ST	KEATS ST	NIMITZ BL	2	Monday	PENINSULA	Prime
S2524	SS-016684-PV1	LOCUST ST	CANON ST	AVNDA DE PORTUGAL	2	Monday	PENINSULA	Prime
S2524	SS-015681-PV1	LA PINTURA DR	OLITE CT	LA JOLLA SCENIC S DR	1	Monday	LA JOLLA	Residential
S2524	SS-015682-PV1	LA PINTURA DR	AVILA CT	OLITE CT	1	Monday	LA JOLLA	Residential
S2524	SS-015683-PV1	LA PINTURA DR	BEGIN	AVILA CT	1	Monday	LA JOLLA	Residential
S2524	SS-015678-PV1	LA PALOMA ST	SAVOY ST	MOANA DR	2	Monday	PENINSULA	Residential
S2524	SS-015577-PV1	LA JOLLA RANCHO RD	RAVENSWOOD RD	BOX CANYON RD	1	Monday	LA JOLLA	Prime
S2524	SS-015566-PV1	LA JOLLA MESA DR	VAN NUYS ST	COLIMA ST	1	Monday	LA JOLLA	Prime
S2524	SS-015568-PV1	LA JOLLA MESA DR	AGATE ST	ARCHER ST	1	Monday	PACIFIC BEACH	Prime

SLURRY SEAL GROUP 2524

IO: 21005580

STREET LIST

Work Order	Pavement ID	Street Name	Cross Street 1	Cross Street 2	Council District	Trash Day	Community Planning Area	Functional Classification
S2524	SS-015518-PV1	LA JOLLA BL	WRELTON DR	TURQUOISE ST	1	Monday	LA JOLLA	Major
S2524	SS-015249-PV1	KINGSLEY ST	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Residential
S2524	SS-015250-PV1	KINGSLEY ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Residential
S2524	SS-014902-PV1	KANE ST	ERIE ST	FRANKFORT ST	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-014675-PV1	JONQUIL DR	ELLIOTT ST	LOTUS DR	2	Monday	PENINSULA	Residential
S2524	SS-014121-PV1	INGELOW ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Residential
S2524	SS-013762-PV1	HORNBLEND ST	CASS ST	DAWES ST	1	Monday	PACIFIC BEACH	Prime
S2524	SS-013122-PV1	HARTFORD ST	HUXLEY ST	CLAIREMONT DR	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-012980-PV1	HANCOCK ST	CHANNEL WY	SPORTS ARENA BL	2	Monday	MIDWAY-PACIFIC HIGHWAY	Major
S2524	SS-012382-PV1	GOLDSMITH ST	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Residential
S2524	SS-012383-PV1	GOLDSMITH ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Residential
S2524	SS-012355-PV1	GOLDFIELD ST	LITTLEFIELD ST	ASHTON ST	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-012330-PV1	GOLDBORO ST	GEORGETOWN AV	GALENA AV	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-012160-PV1	GIRARD AV	PEARL ST	TORREY PINES RD	1	Monday	LA JOLLA	Major
S2524	SS-012091-PV1	GESNER ST	GESNER PL	EDISON ST	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-012093-PV1	GESNER ST	BAY CANYON CT	GESNER PL	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-012052-PV1	GEORGETOWN AV	GOLDBORO ST	GASCONADE AV	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-012053-PV1	GEORGETOWN AV	GASCONADE AV	CROSS ST	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-011896-PV1	GARRISON ST	PLUM ST	CLOVE ST	2	Monday	PENINSULA	Prime
S2524	SS-011872-PV1	GARNET AV	NOYES ST	OLNEY ST	1	Monday	PACIFIC BEACH	Collector
S2524	SS-011799-PV1	GALVESTON ST	GARDENA AV	ASHTON ST	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-011623-PV1	FROUDE ST	DEL MONTE AV	NARRAGANSETT AV	2	Monday	PENINSULA	Residential
S2524	SS-011624-PV1	FROUDE ST	SANTA CRUZ AV	DEL MONTE AV	2	Monday	PENINSULA	Residential
S2524	SS-011469-PV1	FREEMAN ST	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Local
S2524	SS-011470-PV1	FREEMAN ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Prime
S2524	SS-011424-PV1	FRANKFORT ST	KANE ST	JELLETT ST	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-011385-PV1	FORWARD ST	LA JOLLA BL	LA JOLLA HERMOSA AV	1	Monday	LA JOLLA	Local
S2524	SS-011021-PV1	FENELON ST	PLUM ST	CLOVE ST	2	Monday	PENINSULA	Residential
S2524	SS-010629-PV1	EVERGREEN ST	JAMES ST	KINGSLEY ST	2	Monday	PENINSULA	Residential
S2524	SS-010630-PV1	EVERGREEN ST	IBSEN ST	JAMES ST	2	Monday	PENINSULA	Residential
S2524	SS-010631-PV1	EVERGREEN ST	HOMER ST	IBSEN ST	2	Monday	PENINSULA	Residential
S2524	SS-010632-PV1	EVERGREEN ST	GOLDSMITH ST	HOMER ST	2	Monday	PENINSULA	Residential
S2524	SS-010633-PV1	EVERGREEN ST	FREEMAN ST	GOLDSMITH ST	2	Monday	PENINSULA	Residential
S2524	SS-010418-PV1	ERIE ST	KANE ST	JELLETT ST	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-010419-PV1	ERIE ST	LISTER ST	KANE ST	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-010422-PV1	ERIE ST	LITTLEFIELD ST	ASHTON ST	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-010319-PV1	EMERALD ST	DAWES ST	EVERTS ST	1	Monday	PACIFIC BEACH	Residential
S2524	SS-010201-PV1	ELLIOTT ST	CLOVE ST	CHATSWORTH BL	2	Monday	PENINSULA	Residential
S2524	SS-010202-PV1	ELLIOTT ST	WILLOW ST	CLOVE ST	2	Monday	PENINSULA	Residential
S2524	SS-010203-PV1	ELLIOTT ST	EVERGREEN ST	WILLOW ST	2	Monday	PENINSULA	Residential
S2524	SS-010204-PV1	ELLIOTT ST	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Residential
S2524	SS-010205-PV1	ELLIOTT ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Residential
S2524	SS-009844-PV1	EBERS ST	MUIR AV	VOLTAIRE ST	2	Monday	OCEAN BEACH	Residential
S2524	SS-009845-PV1	EBERS ST	LONG BRANCH AV	MUIR AV	2	Monday	OCEAN BEACH	Residential
S2524	SS-009846-PV1	EBERS ST	BRIGHTON AV	LONG BRANCH AV	2	Monday	OCEAN BEACH	Residential
S2524	SS-009523-PV1	DUMAS ST	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Residential
S2524	SS-009441-PV1	DRAPER AV	SILVER ST	KLINE ST	1	Monday	LA JOLLA	Residential
S2524	SS-009282-PV1	DIXIE DR	BERYL ST	CRYSTAL DR	1	Monday	PACIFIC BEACH	Residential
S2524	SS-009224-PV1	DICKENS ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Residential
S2524	SS-009099-PV1	DENVER ST	KANE ST	JELLETT ST	2	Wednesday	CLAIREMONT MESA	Residential
S2524	SS-008999-PV1	DEL MONTE AV	SUNSET CLIFFS BL	CABLE ST	2	Monday	OCEAN BEACH	Residential
S2524	SS-009002-PV1	DEL MONTE AV	GUIZOT ST	GUIZOT ST	2	Monday	PENINSULA	Residential
S2524	SS-009003-PV1	DEL MONTE AV	SANTA BARBARA ST	GUIZOT ST	2	Monday	PENINSULA	Residential
S2524	SS-009005-PV1	DEL MONTE AV	BEGIN	FROUDE ST	2	Monday	PENINSULA	Residential
S2524	SS-008798-PV1	DAWES ST	REED AV	THOMAS AV	1	Monday	PACIFIC BEACH	Residential
S2524	SS-008799-PV1	DAWES ST	OLIVER AV	REED AV	1	Monday	PACIFIC BEACH	Residential
S2524	SS-008800-PV1	DAWES ST	PACIFIC BEACH DR	OLIVER AV	1	Monday	PACIFIC BEACH	Residential
S2524	SS-008486-PV1	CURTIS ST	POINSETTIA DR	END	2	Monday	PENINSULA	Residential
S2524	SS-008359-PV1	CTE JARDIN DEL MAR	BEGIN	EAST OCEAN AIR DR	1	Monday	TORREY HILLS	Residential
S2524	SS-008091-PV1	COUNTRY CLUB DR	FAIRWAY RD	LA JOLLA KNOLL	1	Monday	LA JOLLA	Prime
S2524	SS-007969-PV1	CORNISH DR	ALGE CIRAS ST	ALGECIRAS ST	2	Monday	PENINSULA	Local
S2524	SS-007970-PV1	CORNISH DR	CARMELO ST	ALGE CIRAS ST	2	Monday	PENINSULA	Local
S2524	SS-007978-PV1	CORNISH DR	LADERA ST	CASITAS ST	2	Monday	PENINSULA	Local
S2524	SS-007954-PV1	CORDOVA ST	LADERA ST	CASITAS ST	2	Monday	PENINSULA	Local
S2524	SS-007891-PV1	COPA DE ORO DR	VIA CORONA	RUTGERS RD	1	Monday	LA JOLLA	Residential
S2524	SS-007892-PV1	COPA DE ORO DR	RUTGERS RD	VIA CORONA	1	Monday	LA JOLLA	Residential
S2524	SS-007431-PV1	CLOVE ST	FENELON ST	GARRISON ST	2	Monday	PENINSULA	Residential
S2524	SS-007014-PV1	CHATSWORTH BL	ALCOTT ST	BROWNING ST	2	Monday	PENINSULA	Major
S2524	SS-006524-PV1	CAROUSEL LN	BEGIN	MANGO DR	1	Monday	TORREY PINES	Residential
S2524	SS-006497-PV1	CARMELO ST	CORNISH DR	CORDOVA ST	2	Monday	PENINSULA	Local
S2524	SS-006498-PV1	CARMELO ST	CORDOVA ST	SUNSET CLIFFS BL	2	Monday	PENINSULA	Local
S2524	SS-006395-PV1	CARMEL KNOLLS DR	BEACHCOMBER CT	PEARLMAN WY	1	Monday	CARMEL VALLEY	Major
S2524	SS-006396-PV1	CARMEL KNOLLS DR	SANDHILL TR	BEACHCOMBER CT	1	Monday	CARMEL VALLEY	Major
S2524	SS-006397-PV1	CARMEL KNOLLS DR	SANDDOLLAR CT	SANDHILL TR	1	Monday	CARMEL VALLEY	Major
S2524	SS-006398-PV1	CARMEL KNOLLS DR	PACIFIC GROVE PL	SANDDOLLAR CT	1	Monday	CARMEL VALLEY	Major

SLURRY SEAL GROUP 2524

IO: 21005580

STREET LIST

Work Order	Pavement ID	Street Name	Cross Street 1	Cross Street 2	Council District	Trash Day	Community Planning Area	Functional Classification
S2524	SS-006399-PV1	CARMEL KNOLLS DR	SOUTHAMPTON CV	PACIFIC GROVE PL	1	Monday	CARMEL VALLEY	Major
S2524	SS-006400-PV1	CARMEL KNOLLS DR	CARMEL CANYON RD	ASHLEY FALLS DR	1		CARMEL VALLEY	Major
S2524	SS-006405-PV1	CARMEL KNOLLS DR	ASHLEY FALLS DR	WINDY HEIGHTS WY	1		CARMEL VALLEY	Major
S2524	SS-006406-PV1	CARMEL KNOLLS DR	SEABREEZE FARMS DR	SOUTHAMPTON CV	1	Monday	CARMEL VALLEY	Major
S2524	SS-006407-PV1	CARMEL KNOLLS DR	SANDY CREST CT	CHANDON CT	1	Monday	CARMEL VALLEY	Major
S2524	SS-006408-PV1	CARMEL KNOLLS DR	WINDY HEIGHTS WY	ALMONDWOOD WY	1		CARMEL VALLEY	Major
S2524	SS-006409-PV1	CARMEL KNOLLS DR	ALMONDWOOD WY	SANDY CREST CT	1		CARMEL VALLEY	Major
S2524	SS-031338-PV1	CARMEL KNOLLS DR	CHANDON CT	SEABREEZE FARMS DR	1		CARMEL VALLEY	Major
S2524	SS-006370-PV1	CARMEL COUNTRY RD	DEL MAR MESA RD	SHAW VALLEY RD	1		CARMEL VALLEY	Major
S2524	SS-006379-PV1	CARMEL COUNTRY RD	SAGAMORE WY	DEL MAR MESA RD	1		CARMEL VALLEY	Collector
S2524	SS-006252-PV1	CARDENO DR	VIA CABRERA	LA JOLLA SCENIC S DR	1	Monday	LA JOLLA	Residential
S2524	SS-006262-PV1	CARDENO DR	CALLE VAQUERO	CAMTO ACENTO	1	Monday	LA JOLLA	Residential
S2524	SS-006263-PV1	CARDENO DR	VIA NINA	VIA CABRERA	1	Monday	LA JOLLA	Residential
S2524	SS-006265-PV1	CARDENO DR	CAMTO ACENTO	ALTA LA JOLLA DR	1	Monday	LA JOLLA	Residential
S2524	SS-010885-PV1	CARDENO DR	KAIMALINO LN	CALLE VAQUERO	1		LA JOLLA	Residential
S2524	SS-006225-PV1	CAPISTRANO ST	POE ST	QUIMBY ST	2	Monday	PENINSULA	Prime
S2524	SS-006140-PV1	CANON ST	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Major
S2524	SS-006141-PV1	CANON ST	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Prime
S2524	SS-006145-PV1	CANON ST	SHAFTER ST	SCOTT ST	2	Monday	PENINSULA	Residential
S2524	SS-006147-PV1	CANON ST	AKRON ST	DEL MAR AV	2	Monday	PENINSULA	Major
S2524	SS-005639-PV1	CALLE VAQUERO	CARDENO DR	CASTLE HILLS DR	1	Monday	LA JOLLA	Residential
S2524	SS-005640-PV1	CALLE VAQUERO	CALLE MIRAMAR	WESTKNOLL DR	1	Monday	LA JOLLA	Residential
S2524	SS-005641-PV1	CALLE VAQUERO	CASTLE HILLS DR	CALLE MIRAMAR	1	Monday	LA JOLLA	Residential
S2524	SS-005283-PV1	CABLE ST	VOLTAIRE ST	LOTUS ST	2	Monday	OCEAN BEACH	Major
S2524	SS-005292-PV1	CABLE ST	NARRAGANSETT AV	NIAGARA AV	2	Monday	OCEAN BEACH	Collector
S2524	SS-005293-PV1	CABLE ST	DEL MONTE AV	NARRAGANSETT AV	2	Monday	OCEAN BEACH	Collector
S2524	SS-005294-PV1	CABLE ST	SANTA CRUZ AV	DEL MONTE AV	2	Monday	OCEAN BEACH	Major
S2524	SS-004974-PV1	BRODIAEA WY	ROMERO DR	ENCELIA DR	1	Monday	LA JOLLA	Prime
S2524	SS-003939-PV1	BELLEVUE AV	COLIMA ST	MIDWAY ST	1	Monday	LA JOLLA	Residential
S2524	SS-003364-PV1	BAHIA WY	BAHIA DR	THUNDERBIRD LN	1	Monday	LA JOLLA	Residential
S2524	SS-003361-PV1	BAHIA LN	BAHIA WY	CORAL REEF AV	1	Monday	LA JOLLA	Residential
S2524	SS-003362-PV1	BAHIA LN	PARKVIEW TR	BAHIA WY	1	Monday	LA JOLLA	Residential
S2524	SS-003347-PV1	BACON ST	NARRAGANSETT AV	NIAGARA AV	2	Monday	OCEAN BEACH	Prime
S2524	SS-003167-PV1	AVNDA DE PORTUGAL	EVERGREEN ST	WILLOW ST	2	Monday	PENINSULA	Residential
S2524	SS-003168-PV1	AVNDA DE PORTUGAL	LOCUST ST	EVERGREEN ST	2	Monday	PENINSULA	Residential
S2524	SS-003169-PV1	AVNDA DE PORTUGAL	ROSECRANS ST	LOCUST ST	2	Monday	PENINSULA	Residential
S2524	SS-003102-PV1	AVNDA CHAMNEZ	BEGIN	VIA ESPANA	1	Monday	LA JOLLA	Residential
S2524	SS-003103-PV1	AVNDA CHAMNEZ	VIA ESPANA	END	1	Monday	LA JOLLA	Residential
S2524	SS-003080-PV1	AVILA CT	LA PINTURA DR	END	1	Monday	LA JOLLA	Local
S2524	SS-002747-PV1	ARMADA TR	BESSEMER ST	TALBOT ST	2	Monday	PENINSULA	Residential
S2524	SS-002748-PV1	ARMADA TR	HARBOR VIEW PL	BESSEMER ST	2	Monday	PENINSULA	Residential
S2524	SS-002666-PV1	ARENAS ST	LA JOLLA BL	DRAPER AV	1	Monday	LA JOLLA	Residential
S2524	SS-002227-PV1	ALTA LA JOLLA DR	CAMTO TURIA	CALLE MIRAMAR	1	Monday	LA JOLLA	Residential
S2524	SS-002228-PV1	ALTA LA JOLLA DR	CALLE MIRAMAR	CALLE DELICADA	1		LA JOLLA	Residential
S2524	SS-002067-PV1	ALCOTT ST	POINSETTIA DR	PALERMO DR	2	Monday	PENINSULA	Residential
S2524	SS-002068-PV1	ALCOTT ST	ALCOTT CT	POINSETTIA DR	2	Monday	PENINSULA	Residential
S2524	SS-002069-PV1	ALCOTT ST	CHATSWORTH BL	ALCOTT CT	2	Monday	PENINSULA	Residential
S2524	SS-002066-PV1	ALCOTT CT	ALCOTT ST	END	2	Monday	PENINSULA	Residential
S2524	SS-002033-PV1	ALBION ST	ULLMAN ST	END	2	Monday	PENINSULA	Residential
S2524	SS-002034-PV1	ALBION ST	HILL ST	ULLMAN ST	2	Monday	PENINSULA	Residential
S2524	SS-002035-PV1	ALBION ST	TALBOT ST	HILL ST	2	Monday	PENINSULA	Residential

APPENDIX N

CAPE SEAL FLYER

PAVEMENT TREATMENT CAPE SEAL



Description:

The City of San Diego will be applying a pavement treatment called cape seal to your street, which you may not have seen in the past. **This treatment type will look different than previous treatments applied to your street.** This cape seal treatment will involve application of asphalt emulsion followed by a layer of crushed rock. The crushed rock and emulsion must cure for 3 days before a slurry seal is applied. During this 3-day period, the street will have loose crushed rock on the pavement until the final slurry seal application is complete. We ask that you drive carefully on the surface during this time.



Completion of crushed rock layer prior to slurry seal application

Benefits:


This treatment type is a cost-effective method of extending the life of your road. It seals moderate cracks, seals against moisture, and extends the life of the road for many years. This treatment will also minimize potholes and repairs needed to your road. Previously, a much more expensive treatment would have been required to obtain this result.



Slurry seal is applied after the crushed rock layer has cured for 3 days

How You Can Help:

The street will be closed to all traffic during the application. No Parking signs will be posted 72 hours in advance of construction. Please remove and park your vehicles on an adjacent street prior to and during construction, otherwise it will be towed with SDPD approval. During the 3-day curing period, drive slowly on the new surface as there may be loose rock.



Please be courteous and respectful of the crews working to improve your street's condition.

APPENDIX O

RED CURB QUANTITIES

**SLURRY SEAL GROUP 2524
RED CURB QUANTITIES**

Intersection ID	Cross Street 1	Cross Street 2	NW (LF)	NE (LF)	SE (LF)	SW (LF)	Total Red Curb (LF)	Community Planning Area	Council District
SX-001830	CARMEL COUNTRY RD	DEL MAR MESA RD	20	20	0	20	60	CARMEL VALLEY	1
SX-001895	CARMEL COUNTRY RD	SAGAMORE WY	0	20	20	20	60	CARMEL VALLEY	1
SX-001411	CARMEL KNOLLS DR	BEACHCOMBER CT	20	0	20	20	60	CARMEL VALLEY	1
SX-001433	CARMEL KNOLLS DR	SANDHILL TER	40	0	20	20	80	CARMEL VALLEY	1
SX-001481	CARMEL KNOLLS DR	SANDDOLLAR CT	45	0	20	20	85	CARMEL VALLEY	1
SX-001502	CARMEL KNOLLS DR	PACIFIC GROVE PL	20	0	20	20	60	CARMEL VALLEY	1
SX-001526	CARMEL KNOLLS DR	SOUTHAMPTON CV	40	0	20	20	80	CARMEL VALLEY	1
SX-017411	CARMEL KNOLLS DR	SEABREEZE FARMS DR	0	20	20	0	40	CARMEL VALLEY	1
SX-001590	CARMEL KNOLLS DR	SANDY CREST CT	20	20	19	20	79	CARMEL VALLEY	1
SX-001793	CARMEL COUNTRY RD	CLEWS RANCH RD	20	0	0	0	20	CARMEL VALLEY	1
SX-001384	CARMEL KNOLLS DR	PEARLMAN WY	20	20	20	38	98	CARMEL VALLEY	1
SX-001539	CARMEL KNOLLS DR	ASHLEY FALLS DR	28	50	7	20	105	CARMEL VALLEY	1
SX-001571	CARMEL KNOLLS DR	WINDY HEIGHTS WY	20	20	20	0	60	CARMEL VALLEY	1
SX-001586	CARMEL KNOLLS DR	CHANDON CT	20	20	0	0	40	CARMEL VALLEY	1
SX-001593	CARMEL KNOLLS DR	ALMONDWOOD WY	0	0	20	20	40	CARMEL VALLEY	1
SX-005292	ALTA LA JOLLA DR	CAMINITO TURIA	0	0	20	20	40	LA JOLLA	1
SX-004388	ARENAS ST	LA JOLLA BLVD	0	20	40	20	80	LA JOLLA	1
SX-004904	AVILA CT	LA PINTURA DR	0	20	33	0	53	LA JOLLA	1
SX-005351	BAHIA LN	BAHIA WY	20	0	20	34	74	LA JOLLA	1
SX-005349	BAHIA WY	BAHIA DR	30	20	40	36	126	LA JOLLA	1
SX-005818	BELLEVUE AV	COLIMA ST	20	20	20	8	68	LA JOLLA	1
SX-005516	CALLE VAQUERO	CARDENO DR	0	22	20	0	42	LA JOLLA	1
SX-005546	CALLE VAQUERO	CALLE MIRAMAR	51	35	0	0	86	LA JOLLA	1
SX-004764	CARDENO DR	VIA NINA	20	0	0	40	60	LA JOLLA	1
SX-005361	COPA DE ORO DR	VIA CORONA	16	22	64	20	122	LA JOLLA	1
SX-004107	COUNTRY CLUB DR	FAIRWAY RD	0	0	28	24	52	LA JOLLA	1
SX-005693	CARDENO DR	KAIMALINO LN	18	0	0	36	54	LA JOLLA	1
SX-006135	LA JOLLA BL	WRELTON DR	0	20	20	0	40	LA JOLLA	1
SX-005764	LA JOLLA HERMOSA AV	MIDWAY ST	10	0	10	4	24	LA JOLLA	1
SX-005861	LA JOLLA MESA DR	VAN NUYS ST	0	20	0	0	20	LA JOLLA	1
SX-005321	LA JOLLA RANCHO RD	RAVENSWOOD RD	25	0	0	22	47	LA JOLLA	1
SX-004696	LA PINTURA DR	OLITE CT	0	21	47	0	68	LA JOLLA	1
SX-003909	LOOKOUT DR	BOULEVARD PL	0	38	0	0	38	LA JOLLA	1
SX-004264	OLIVETAS AV	MARINE ST	10	8	0	2	20	LA JOLLA	1
SX-004395	RUSHVILLE ST	DRAPER AV	0	0	0	6	6	LA JOLLA	1
SX-004043	SOLEDAD AV	AL BAHR DR	20	20	20	0	60	LA JOLLA	1
SX-005010	SOLEDAD MTN RD	PALOMINO CR	84	20	37	57	198	LA JOLLA	1
SX-005161	SOLEDAD MTN RD	DESERT VIEW DR	0	20	37	0	57	LA JOLLA	1
SX-005287	ALTA LA JOLLA DR	CALLE MIRAMAR	0	0	20	0	20	LA JOLLA	1
SX-005188	ALTA LA JOLLA DR	CALLE DELICADA	0	0	22	37	59	LA JOLLA	1
SX-004354	ARENAS ST	DRAPER AV	10	17	19	8	54	LA JOLLA	1
SX-005183	AVNDA CHAMNEZ	VIA ESPANA	0	30	20	0	50	LA JOLLA	1
SX-005364	BAHIA WY	THUNDERBIRD LN	54	20	20	20	114	LA JOLLA	1
SX-005717	BELLEVUE AV	MIDWAY ST	20	20	20	20	80	LA JOLLA	1
SX-005544	CALLE VAQUERO	CASTLE HILLS DR	0	0	35	31	66	LA JOLLA	1
SX-005532	CALLE VAQUERO	WESTKNOLL DR	0	0	0	30	30	LA JOLLA	1
SX-005381	CARDENO DR	CAMINITO ACENTO	20	0	20	0	40	LA JOLLA	1
SX-005292	CARDENO DR	ALTA LA JOLLA DR	0	0	20	0	20	LA JOLLA	1
SX-005355	COPA DE ORO DR	RUTGERS RD	26	20	0	0	46	LA JOLLA	1
SX-004086	COUNTRY CLUB DR	LA JOLLA KNOLL	0	0	13	0	13	LA JOLLA	1
SX-004099	DRAPER AVE	KLINE ST	0	11	20	0	31	LA JOLLA	1
SX-006113	LA JOLLA BLVD	TURQUOISE ST	0	0	4	0	4	LA JOLLA	1
SX-005266	LA JOLLA RANCHO RD	BOX CANYON RD	20	20	20	0	60	LA JOLLA	1
SX-004664	LA PINTURA DR	LA JOLLA SCENIC S DR	0	20	20	0	40	LA JOLLA	1
SX-003951	LOOKOUT DR	SOLEDAD AV	0	0	20	0	20	LA JOLLA	1
SX-004206	OLIVETAS AVE	PEARL ST	34	20	24	20	98	LA JOLLA	1
SX-004368	RUSHVILLE ST	EADS AV	10	0	0	0	10	LA JOLLA	1
SX-004016	SOLEDAD AV	LUDINGTON PL	18	30	0	0	48	LA JOLLA	1
SX-004932	SOLEDAD MTN RD	SOLEDAD RD	0	20	0	23	43	LA JOLLA	1
SX-005116	SOLEDAD MTN RD	PALM CANYON DR	0	0	10	0	10	LA JOLLA	1
SX-007449	DAWES ST	OLIVER AV	0	0	9	0	9	PACIFIC BEACH	1
SX-007527	DAWES ST	PACIFIC BEACH DR	3	0	15	0	18	PACIFIC BEACH	1
SX-006589	DIXIE DR	BERYL ST	20	0	0	0	20	PACIFIC BEACH	1
SX-006846	EMERALD ST	DAWES ST	2	4	0	0	6	PACIFIC BEACH	1
SX-006700	GARNET AV	NOYES ST	20	0	20	0	40	PACIFIC BEACH	1
SX-007112	HORNBLEND ST	CASS ST	0	8	0	0	8	PACIFIC BEACH	1
SX-005976	LA JOLLA MESA DR	AGATE ST	8	0	0	0	8	PACIFIC BEACH	1
SX-006765	NOYES ST	HORNBLEND ST	20	0	20	0	40	PACIFIC BEACH	1

**SLURRY SEAL GROUP 2524
RED CURB QUANTITIES**

Intersection ID	Cross Street 1	Cross Street 2	NW (LF)	NE (LF)	SE (LF)	SW (LF)	Total Red Curb (LF)	Community Planning Area	Council District
SX-007322	OLIVER AV	GRESHAM ST	0	8	0	0	8	PACIFIC BEACH	1
SX-005563	ROMNEY RD	SAN AQUARIO DR	0	0	20	28	48	PACIFIC BEACH	1
SX-005615	ROMNEY RD	PENDLETON ST	22	22	0	0	44	PACIFIC BEACH	1
SX-006079	TURQUOISE ST	WRELTON DR	0	0	0	2	2	PACIFIC BEACH	1
SX-006113	TURQUOISE ST	LA JOLLA BLVD	0	0	4	0	4	PACIFIC BEACH	1
SX-005657	WESTKNOLL DR	WESTKNOLL LN	21	23	0	0	44	PACIFIC BEACH	1
SX-006510	DIXIE DR	CRYSTAL DR	6	0	18	0	24	PACIFIC BEACH	1
SX-006820	EMERALD ST	EVERTS ST	0	0	5	0	5	PACIFIC BEACH	1
SX-006666	GARNET AV	OLNEY ST	0	0	2	0	2	PACIFIC BEACH	1
SX-007073	HORNBLEND ST	DAWES ST	7	4	0	2	13	PACIFIC BEACH	1
SX-005917	LA JOLLA MESA DR	ARCHER ST	0	0	0	2	2	PACIFIC BEACH	1
SX-007291	OLIVER AV	HAINES ST	8	7	10	4	29	PACIFIC BEACH	1
SX-007407	OLIVER AV	EVERTS ST	0	6	3	4	13	PACIFIC BEACH	1
SX-005534	ROMNEY RD	PACIFICA DR	13	20	0	20	53	PACIFIC BEACH	1
SX-007225	THOMAS AV	EVERTS ST	0	4	0	4	8	PACIFIC BEACH	1
SX-005532	WESTKNOLL DR	CALLE VAQUERO	30	0	0	0	30	PACIFIC BEACH	1
SX-017465	TRZA MAR MARVELOSA	EAST OCEAN AIR DRIVE	20	20	0	44	84	TORREY PINES-TORREY HILLS	1
SX-001778	MANGO DR	PORTOFINO DR	0	0	20	20	40	TORREY PINES-TORREY HILLS	1
SX-002764	CTE JARDIN DEL MAR	EAST OCEAN AIR DR	0	0	20	35	55	TORREY PINES-TORREY HILLS	1
SX-02447	VISTA SORRENTO PY	CARMEL MTN RD	22	20	20	20	82	TORREY PINES-TORREY HILLS	1
SX-001774	CAROUSEL LN	MANGO DR	0	0	20	20	40	TORREY PINES-TORREY HILLS	1
SX-007979	DENVER ST	KANE ST	0	0	0	10	10	CLAIREMONT MESA	2
SX-008064	ERIE ST	LISTER ST	0	11	8	7	26	CLAIREMONT MESA	2
SX-008410	ERIE ST	LITTLEFIELD ST	24	20	26	20	90	CLAIREMONT MESA	2
SX-008000	FRANKFORT ST	KANE ST	12	2	0	0	14	CLAIREMONT MESA	2
SX-008415	GALVESTON ST	GARDENA AV	0	15	5	0	20	CLAIREMONT MESA	2
SX-008495	GEORGETOWN AV	GOLDBORO ST	0	25	25	0	50	CLAIREMONT MESA	2
SX-007506	GESNER ST	GESNER PL	0	20	0	0	20	CLAIREMONT MESA	2
SX-007627	GESNER ST	BAY CANYON CT	0	0	27	20	47	CLAIREMONT MESA	2
SX-008375	GOLDFIELD ST	LITTLEFIELD ST	7	7	13	0	27	CLAIREMONT MESA	2
SX-007777	HARTFORD ST	HUXLEY ST	20	0	10	20	50	CLAIREMONT MESA	2
SX-007907	DENVER ST	JELLETT ST	0	0	0	4	4	CLAIREMONT MESA	2
SX-007916	ERIE ST	JELLETT ST	0	0	0	5	5	CLAIREMONT MESA	2
SX-008343	ERIE ST	ASHTON ST	20	0	19	0	39	CLAIREMONT MESA	2
SX-007928	FRANKFORT ST	JELLETT ST	25	26	0	20	71	CLAIREMONT MESA	2
SX-008513	GEORGETOWN AV	GASCONADE AV	20	0	0	23	43	CLAIREMONT MESA	2
SX-008516	GEORGETOWN AV	CROSS ST	0	28	0	0	28	CLAIREMONT MESA	2
SX-008472	GOLDBORO ST	GALENA AV	22	0	0	24	46	CLAIREMONT MESA	2
SX-007667	HARTFORD ST	CLAIREMONT DR	8	0	0	30	38	CLAIREMONT MESA	2
SX-009684	HANCOCK ST	CHANNEL WY	12	4	0	0	16	MIDWAY-PACIFIC HIGHWAY	2
SX-011120	ROSECRANS PL	ROSECRANS ST	20	0	0	0	20	MIDWAY-PACIFIC HIGHWAY	2
SX-010891	ROSECRANS ST	MADRID ST	20	20	0	0	40	MIDWAY-PACIFIC HIGHWAY	2
SX-009919	HANCOCK ST	SPORTS ARENA BLV	0	20	0	0	20	MIDWAY-PACIFIC HIGHWAY	2
SX-011136	ROSECRANS PL	CADIZ ST	0	0	20	20	40	MIDWAY-PACIFIC HIGHWAY	2
SX-010777	ROSECRANS ST	NORTH EVERGREEN ST	0	7	43	0	50	MIDWAY-PACIFIC HIGHWAY	2
SX-010957	ROSECRANS ST	MALAGA ST	50	20	0	0	70	MIDWAY-PACIFIC HIGHWAY	2
SX-011000	BACON ST	NARRAGANSETT AV	10	0	5	1	16	OCEAN BEACH	2
SX-010324	CABLE ST	VOLTAIRE ST	6	0	0	0	6	OCEAN BEACH	2
SX-011186	CABLE ST	NARRAGANSETT AV	20	20	20	11	71	OCEAN BEACH	2
SX-011295	CABLE ST	DEL MONTE AV	0	5	0	0	5	OCEAN BEACH	2
SX-011436	CABLE ST	SANTA CRUZ AV	0	4	0	9	13	OCEAN BEACH	2
SX-011462	DEL MONTE AV	SUNSET CLIFFS BL	0	4	1	0	5	OCEAN BEACH	2
SX-010632	EBERS ST	MUIR AV	20	20	20	20	80	OCEAN BEACH	2
SX-010700	EBERS ST	LONG BRANCH AV	20	20	20	20	80	OCEAN BEACH	2
SX-010759	EBERS ST	BRIGHTON AV	20	20	20	20	80	OCEAN BEACH	2
SX-011822	SANTA CRUZ AV	FROUDE ST	20	45	20	20	105	OCEAN BEACH	2
SX-011946	SUNSET CLIFFS BL	PESCADERO AV	0	20	0	0	20	OCEAN BEACH	2
SX-012008	SUNSET CLIFFS BL	BERMUDA AV	4	0	20	20	44	OCEAN BEACH	2
SX-012087	SUNSET CLIFFS BL	POINT LOMA AV	7	0	0	0	7	OCEAN BEACH	2
SX-010445	VOLTAIRE ST	SUNSET CLIFFS BL	0	0	9	0	9	OCEAN BEACH	2
SX-010905	BACON ST	NIAGARA AV	8	5	10	0	23	OCEAN BEACH	2
SX-010236	CABLE ST	LOTUS ST	0	0	10	20	30	OCEAN BEACH	2
SX-011032	CABLE ST	NIAGARA AV	0	20	13	9	42	OCEAN BEACH	2
SX-010563	EBERS ST	VOLTAIRE ST	11	0	5	0	16	OCEAN BEACH	2
SX-011687	SANTA CRUZ AV	EBERS ST	20	20	47	20	107	OCEAN BEACH	2
SX-011870	SUNSET CLIFFS BL	ORCHARD AV	0	4	0	0	4	OCEAN BEACH	2
SX-013069	ALBION ST	ULLMAN ST	20	20	0	20	60	PENINSULA	2
SX-013207	ALBION ST	HILL ST	0	40	5	0	45	PENINSULA	2

**SLURRY SEAL GROUP 2524
RED CURB QUANTITIES**

Intersection ID	Cross Street 1	Cross Street 2	NW (LF)	NE (LF)	SE (LF)	SW (LF)	Total Red Curb (LF)	Community Planning Area	Council District
SX-013276	ALBION ST	TALBOT ST	20	0	0	27	47	PENINSULA	2
SX-011443	ALCOTT ST	POINSETTIA DR	33	0	0	20	53	PENINSULA	2
SX-013562	ARMADA TR	HARBOR VIEW PL	0	0	37	0	37	PENINSULA	2
SX-012889	BANGOR ST	BANGOR PL	16	20	20	20	76	PENINSULA	2
SX-013048	BANGOR ST	VALEMONT ST	20	0	20	0	40	PENINSULA	2
SX-013126	BANGOR ST	ULLMAN ST	20	0	25	20	65	PENINSULA	2
SX-013194	BANGOR ST	TRUMBULL ST	20	21	44	20	105	PENINSULA	2
SX-013252	BANGOR ST	HILL ST	8	22	50	0	80	PENINSULA	2
SX-013101	CANON ST	AKRON ST	0	0	0	44	44	PENINSULA	2
SX-012135	CAPISTRANO ST	POE ST	20	20	20	20	80	PENINSULA	2
SX-012799	CLOVE ST	FENELON ST	25	74	30	48	177	PENINSULA	2
SX-013024	CONCORD ST	VALEMONT ST	0	20	48	19	87	PENINSULA	2
SX-013105	CONCORD ST	ULLMAN ST	0	20	43	0	63	PENINSULA	2
SX-013160	CONCORD ST	TRUMBULL ST	0	20	47	21	88	PENINSULA	2
SX-013216	CONCORD ST	HILL ST	20	20	20	38	98	PENINSULA	2
SX-013286	CONCORD ST	TALBOT ST	20	10	0	0	30	PENINSULA	2
SX-011195	CURTIS ST	POINSETTIA DR	20	21	20	20	81	PENINSULA	2
SX-011874	DEL MONTE AV	GUIZOT ST	20	39	20	20	99	PENINSULA	2
SX-011956	DEL MONTE AV	SANTA BARBARA ST	20	20	24	20	84	PENINSULA	2
SX-012797	GARRISON ST	PLUM ST	26	36	19	69	150	PENINSULA	2
SX-011662	LUCERNE DR	POINSETTIA DR	0	15	0	9	24	PENINSULA	2
SX-011480	PALERMO DR	YONGE ST	0	0	20	5	25	PENINSULA	2
SX-011564	SANTA BARBARA ST	SANTA MONICA AV	20	20	20	0	60	PENINSULA	2
SX-011877	SANTA BARBARA ST	NARRAGANSETT AV	20	20	44	20	104	PENINSULA	2
SX-012152	UDALL ST	WILLOW ST	0	22	0	23	45	PENINSULA	2
SX-012082	CAPISTRANO ST	QUIMBLY ST	20	9	46	20	95	PENINSULA	2
SX-011495	CHATSWORTH BL	BROWNING ST	0	20	0	0	20	PENINSULA	2
SX-012755	CLOVE ST	GARRISON ST	20	25	21	57	123	PENINSULA	2
SX-011620	FROUDE ST	NARRAGANSETT AV	20	0	20	0	40	PENINSULA	2
SX-011753	FROUDE ST	DEL MONTE AV	20	20	20	27	87	PENINSULA	2
SX-011472	LUCERNE DR	ZOLA ST	0	0	20	20	40	PENINSULA	2
SX-011514	POINSETTIA DR	ZOLA ST	14	0	9	5	28	PENINSULA	2
SX-011470	SANTA BARBARA ST	SARATOGA AV	20	20	47	20	107	PENINSULA	2
SX-011789	SANTA BARBARA ST	NIAGARA AV	20	20	27	20	87	PENINSULA	2
SX-012091	UDALL ST	PLUM ST	20	20	30	20	90	PENINSULA	2

TOTAL: 8,448

ATTACHMENT F

**IN-USE OFF-ROAD DIESEL FUELED FLEET REGULATION (OFF-ROAD REGULATION)
COMPLIANCE (CARB)**

ATTACHMENT F

IN-USE OFF-ROAD DIESEL FUELED FLEET REGULATION (OFF-ROAD REGULATION) COMPLIANCE

The California Air Resources Board (CARB) approved amendments to the Off-Road Regulations which can be found at 13 California Code of Regulations (CCR) sections 2449, 2449.1, and 2449.2. These amendments apply to any person, business, or government agency who owns or operates within California any vehicles with a diesel-fueled or alternative diesel fueled off-road compression-ignition engine with maximum power (max hp) of 25 horsepower (hp) or greater provided that the vehicle cannot be registered and driven safely on-road or was not designed to be driven on-road, even if it has been modified so that it can be driven safely on-road. See 13 CCR section 2449 (b) for the full list of vehicles covered by these Off-Road Regulations.

Beginning **January 1, 2024**, Contractor shall be subject to the requirements below. No Contractor or public works awarding body, as applicable, shall enter into a contract with a fleet for which it does not have a valid Certificate of Reported Compliance for the fleet and its listed subcontractors, if applicable, prior to entering into a new or renewed contract with that fleet. Contractor shall comply with the following requirements:

- (1) For a project involving the use of vehicles subject to the Off-Road Regulation, Contractor must obtain copies of the valid Certificates of Reported Compliance, as described in 13 CCR section 2449(n), for the fleet selected for this Contract and their listed subcontractors, if applicable, prior to entering into a new or renewed contract with that fleet and provide copies of such Certificates of Reported Compliance to the City within 10 days of issuance of the Notice of Intent to Award letter. Contractor shall enter into a contract with a fleet for which it does not have a valid Certificates of Reported Compliance for the fleet and its listed subcontractors. City shall not enter into a contract with Contractor until all current Certificates of Reported Compliance for the fleet to be used on this Project are provided by Contractor.
- (2) The Certificates of Reported Compliance received by Contractor for this Project must be retained by Contractor for three years after the Project's completion. Upon request by CARB, these records must be provided to CARB within five business days of the request. Additionally, upon request by City, these records must be produced to City within five business days of the request.
- (3) For emergency contracts that meet the definition of "emergency operations" as defined in 13 CCR section 2449(c)(18), they are exempt from the requirements in 13 CCR section 2449(i)(1)-(3) and sections (1) and (2) above, but must still retain records verifying vehicles subject to the regulation that are operating on the "emergency operations" project are actually being operated on the project for "emergency operations" only. These records, as described in more detail below in section (B) must be retained by Contractor for three years after completion of the Project and upon request from either CARB or the City, Contractor shall provide those records to the requesting party within five business days. All other emergency contracts that do not meet the definition of "emergency operations" must comply with the requirements above and 13 CCR section 2449(i)(1) – (3).

- A. "Emergency Operations" is defined as:
1. Any activity for a project conducted during emergency, life threatening situations, where a sudden, unexpected occurrence that poses a clear and imminent danger, requiring immediate action to prevent or mitigate the loss or impairment of life, health, property, or an essential public service; or in conjunction with any officially declared disaster or state of emergency, as declared by an authorized health officer, agricultural commissioner, fire protection officer, or other authorized health officer;
 2. Any activity for a project conducted by essential service utilities to provide electricity, natural gas, telephone, water, or sewer during periods of service outages and emergency; or
 3. Operations including repairing or preventing damage to roads, buildings, terrain, and infrastructure as a result of an earthquake, flood, storm, fire, other infrequent act of nature, or terrorism. Routine maintenance or construction to prevent public health risks does not constitute emergency operations under the Off-Road Regulations.
- B. The records retained by Contractor for "emergency operations" projects must include:
1. A description of the emergency;
 2. The address or a description of the specific location of the emergency;
 3. The dates on which the emergency operations were performed; and
 4. An attestation by the fleet that the vehicles are operated on the Project for "emergency operations" only.

Beginning **January 1, 2024**, Contractor is also subject to the requirements described in 13 CCR section 2449(j).

- (1) Between March 1 and June 1 of each year, Contractor must collect new valid Certificates of Reported Compliance for the current compliance year, as defined in 13 CCR section 2449(n), from all fleets that have an ongoing contract with Contractor as of March 1 of that year. Contractors shall not write contracts to evade this requirement.
- (2) Contractor shall only allow fleets with valid Certificates of Reported Compliance on the Contractor's job sites.
- (3) If Contractor discovers that any fleet intending to operate vehicles subject to this regulation for Contractor does not have a valid Certificate of Reported Compliance, as defined in 13 CCR section 2449(n), or if Contractor observes any noncompliant vehicles subject to the regulation on Contractor's job site, then Contractor must report the that to CARB at <https://calepacomplaints.secure.force.com/complaints/Complaint>, or email **dieselcomplaints@arb.ca.gov**, for each fleet without a valid Certificate of Reported Compliance or each noncompliant vehicle,

as applicable, within five business days of such discovery. See 13 CCR 2449(n) for the information required to be disclosed to CARB when reporting non-compliance.

(4) Upon request by CARB, Contractor must immediately disclose to CARB the name and contact information of each responsible party for all vehicles subject to this regulation operating at the job site or for Contractor.

(5) Contractor shall prominently display signage for any project where vehicles subject to this Off-Road Regulation will operate for 8 calendar days or more. The signage must be posted by the eighth calendar day from which the first vehicle operates. The signage will be in lettering larger than size 14-point type and displayed in a conspicuous place where notices to employees are customarily posted at the job site or where there is employee foot traffic. If one of the above locations is also viewable by the public, it should be posted at that location. An exemption to this posting requirement is permitted if the operational time of a project is 7 calendar days or less. The signage must include the following language, verbatim:

(A) Who does the In-Use Off-Road Regulation Apply to?

The In-Use Off-Road Diesel-Fueled Fleets Regulation (Off-Road Regulation) applies to all self-propelled off-road diesel vehicles 25 horsepower or greater and most two-engine vehicles (except on-road two-engine sweepers) owned or operated in California. This includes vehicles that are rented or leased (rental or leased fleets)."

(B) "In-Use Off-Road Regulation Requirements

Idling Limit: Vehicles cannot idle longer than five minutes. There are exceptions for vehicles that need to idle to perform work.

Labeling: Vehicles must be labeled with a CARB assigned equipment identification number (EIN). The EIN shall be white on a red background, unless the vehicle is part of a captive attainment area fleet, in which case the EIN shall be white on a green background.

The EIN shall be located in clear view on both sides of the outside of the vehicle."

ATTACHMENT G
CONTRACT AGREEMENT

ATTACHMENT G
CONTRACT AGREEMENT

CONSTRUCTION CONTRACT

This contract is made and entered into between THE CITY OF SAN DIEGO, a municipal corporation, herein called "City", and Pavement Coatings Co., herein called "Contractor" for construction of **Slurry Seal Group 2524; Bid No. K-25-2345-DBB-3**; in the total amount **Five Million Six Hundred Forty One Thousand Three Hundred Eighty Eight Dollars and Fifty Cents (\$5,641,388.50)**, which is comprised of the Base Bid.

IN CONSIDERATION of the payments to be made hereunder and the mutual undertakings of the parties hereto, City and Contractor agree as follows:

1. The following are incorporated into this contract as though fully set forth herein:
 - (a) The attached Faithful Performance and Payment Bonds.
 - (b) The attached Proposal included in the Bid documents by the Contractor.
 - (c) Reference Standards listed in the Instruction to Bidders and the Supplementary Special Provisions (SSP).
 - (d) That certain documents entitled **Slurry Seal Group 2524**, on file in the office of the Purchasing & Contracting Department as Document No. **21005580**, as well as all matters referenced therein.
2. The Contractor shall perform and be bound by all the terms and conditions of this contract and in strict conformity therewith shall perform and complete in a good and workmanlike manner **Slurry Seal Group 2524**, Bid Number **K-25-2345-DBB-3**, San Diego, California.
3. For such performances, the City shall pay to Contractor the amounts set forth at the times and in the manner and with such additions or deductions as are provided for in this contract, and the Contractor shall accept such payment in full satisfaction of all claims incident to such performances.
4. No claim or suit whatsoever shall be made or brought by Contractor against any officer, agent, or employee of the City for or on account of anything done or omitted to be done in connection with this contract, nor shall any such officer, agent, or employee be liable hereunder.
5. This contract is effective as of the date that the Mayor or designee signs the agreement and is approved by the City Attorney in accordance with San Diego Charter Section 40.

CONTRACT AGREEMENT (continued)

IN WITNESS WHEREOF, this Agreement is signed by the City of San Diego, acting by and through its Mayor or designee, pursuant to Municipal Code 22.3102 authorizing such execution.

CONTRACTOR

By 

Print Name: Tom Mucenski


Title: Secretary

Date: 2-19-2025

City of San Diego License No.: B2011011250

State Contractor's License No.: 303609

DEPARTMENT OF INDUSTRIAL RELATIONS (DIR) REGISTRATION NUMBER: 1000003382




THE CITY OF SAN DIEGO

APPROVED AS TO FORM

Heather Ferbert, City Attorney

By: 

By: 

Print Name: Berric Doringo

Print Name: Dominic Guglielmo

Deputy Director
Purchasing & Contracting Department

Deputy City Attorney

Date: 2/26/2025

Date: 2/26/25

CERTIFICATIONS AND FORMS

The Bidder, by submitting its electronic bid, agrees to and certifies under penalty of perjury under the laws of the State of California, that the certifications, forms and affidavits submitted as part of this bid are true and correct.

BIDDER'S GENERAL INFORMATION

To the City of San Diego:

Pursuant to "Notice Inviting Bids", specifications, and requirements on file with the City Clerk, and subject to all provisions of the Charter and Ordinances of the City of San Diego and applicable laws and regulations of the United States and the State of California, the undersigned hereby proposes to furnish to the City of San Diego, complete at the prices stated herein, the items or services hereinafter mentioned. The undersigned further warrants that this bid is not made in the interest of, or on behalf of, any undisclosed person, partnership, company, association, organization, or corporation; that the bid is genuine and not collusive or sham; that the bidder has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid, and has not directly or indirectly colluded, conspired, connived, or agreed with any bidder or anyone else to put in a sham bid, or that anyone shall refrain from bidding; that the bidder has not in any manner, directly or indirectly, sought by agreement, communication, or conference with anyone to fix the bid price of the bidder or any other bidder, or to fix any overhead, profit, or cost element of the bid price, or of that of any other bidder, or to secure any advantage against the public body awarding the contract of anyone interested in the proposed contract; that all statements contained in the bid are true; and, further, that the bidder has not, directly or indirectly, submitted his or her bid price or any breakdown thereof, or the contents thereof, or divulged information or data relative thereto, or paid, and will not pay, any fee to any corporation, partnership, company, association, organization, bid depository, or to any member or agent thereof to effectuate a collusive or sham bid.

The undersigned bidder(s) further warrants that bidder(s) has thoroughly examined and understands the entire Contract Documents (plans and specifications) and the Bidding Documents therefore, and that by submitting said Bidding Documents as its bid proposal, bidder(s) acknowledges and is bound by the entire Contract Documents, including any addenda issued thereto, as such Contract Documents incorporated by reference in the Bidding Documents.

**NON-COLLUSION AFFIDAVIT TO BE EXECUTED BY BIDDER AND SUBMITTED WITH BID UNDER 23
UNITED STATES CODE 112 AND PUBLIC CONTRACT CODE 7106**

State of California

County of San Diego

The bidder, being first duly sworn, deposes and says that he or she is authorized by the party making the foregoing bid that the bid is not made in the interest of, or on behalf of, any undisclosed person, partnership, company, association, organization, or corporation; that the bid is genuine and not collusive or sham; that the bidder has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid, and has not directly or indirectly colluded, conspired, connived, or agreed with any bidder or anyone else to put in a sham bid, or that anyone shall refrain from bidding; that the bidder has not in any manner, directly or indirectly, sought by agreement, communication, or conference with anyone to fix the bid price of the bidder or any other bidder, or to fix any overhead, profit, or cost element of the bid price, or of that of any other bidder, or to secure any advantage against the public body awarding the contract of anyone interested in the proposed contract; that all statements contained in the bid are true; and further, that the bidder has not, directly or indirectly, submitted his or her bid price or any breakdown thereof, or the contents thereof, or divulged information or data relative thereto, or paid, and will not pay, any fee to any corporation, partnership, company association, organization, bid depository, or to any member or agent thereof to effectuate a collusive or sham bid.

CONTRACTOR CERTIFICATION

DRUG-FREE WORKPLACE

I hereby certify that I am familiar with the requirements of San Diego City Council Policy No. 100-17 regarding Drug-Free Workplace as outlined in the WHITEBOOK, Section 5-1.3, "Drug-Free Workplace", of the project specifications, and that;

This company has in place a drug-free workplace program that complies with said policy. I further certify that each subcontract agreement for this project contains language which indicates the subcontractor's agreement to abide by the provisions of subdivisions a) through c) of the policy as outlined.

CONTRACTOR CERTIFICATION

AMERICANS WITH DISABILITIES ACT (ADA) COMPLIANCE CERTIFICATION

I hereby certify that I am familiar with the requirements of San Diego City Council Policy No. 100-4 regarding the Americans With Disabilities Act (ADA) outlined in the WHITEBOOK, Section 5-1.2, "California Building Code, California Code of Regulations Title 24 and Americans with Disabilities Act". of the project specifications, and that:

This company has in place workplace program that complies with said policy. I further certify that each subcontract agreement for this project contains language which indicates the subcontractor's agreement to abide by the provisions of the policy as outlined.

CONTRACTOR CERTIFICATION

CONTRACTOR STANDARDS – PLEDGE OF COMPLIANCE

I declare under penalty of perjury that I am authorized to make this certification on behalf of the company submitting this bid/proposal, that as Contractor, I am familiar with the requirements of City of San Diego Municipal Code § 22.3004 regarding Contractor Standards as outlined in the WHITEBOOK, Section 5-1.4, ("Contractor Standards and Pledge of Compliance"), of the project specifications, and that Contractor has complied with those requirements.

I further certify that each of the Contractor's subcontractors has completed a Pledge of Compliance attesting under penalty of perjury of having complied with City of San Diego Municipal Code § 22.3004.

CONTRACTOR CERTIFICATION

EQUAL BENEFITS ORDINANCE CERTIFICATION

I declare under penalty of perjury that I am familiar with the requirements of and in compliance with the City of San Diego Municipal Code § 22.4300 regarding Equal Benefits Ordinance.

CONTRACTOR CERTIFICATION

EQUAL PAY ORDINANCE CERTIFICATION

Contractor shall comply with the Equal Pay Ordinance (EPO) codified in the San Diego Municipal Code (SDMC) at section 22.4801 through 22.4809, unless compliance is not required based on an exception listed in SDMC section 22.4804.

Contractor shall require all of its subcontractors to certify compliance with the EPO in their written subcontracts.

Contractor must post a notice informing its employees of their rights under the EPO in the workplace or job site.

By signing this Contract with the City of San Diego, Contractor acknowledges the EPO requirements and pledges ongoing compliance with the requirements of SDMC Division 48, section 22.4801 et seq., throughout the duration of this Contract.

CONTRACTOR CERTIFICATION

IN-USE OFF-ROAD DIESEL FUELED FLEET REGULATION (OFF-ROAD REGULATION) COMPLIANCE

I hereby certify that Contractor is familiar with the requirements 13 CCR 2449, 2449.1, and 2449.2, as well as Attachment F, In-Use Off-Road Diesel Fueled Fleet Regulation (Off-Road Regulation) Compliance (CARB), and that Contractor shall comply with these requirements.

I further certify that each of the Contractor's listed subcontractors is familiar with these requirements and shall also comply.

CONTRACTOR CERTIFICATION

PRODUCT ENDORSEMENT

I declare under penalty of perjury that I acknowledge and agree to comply with the provisions of City of San Diego Administrative Regulation 95.65, concerning product endorsement. Any advertisement identifying or referring to the City as the user of a product or service requires the prior written approval of the City.

AFFIDAVIT OF DISPOSAL

(To be submitted upon completion of Construction pursuant to the contracts Certificate of Completion)

WHEREAS, on the _____ DAY OF _____, 2____ the undersigned entered into and executed a contract with the City of San Diego, a municipal corporation, for:

SLURRY SEAL GROUP 2524

Project Title

as particularly described in said contract and identified as Bid No. **K-25-2345-DBB-3**; SAP No. (IO) **21005580**; and **WHEREAS**, the specification of said contract requires the Contractor to affirm that "all brush, trash, debris, and surplus materials resulting from this project have been disposed of in a legal manner"; and **WHEREAS**, said contract has been completed and all surplus materials disposed of:

NOW, THEREFORE, in consideration of the final payment by the City of San Diego to said Contractor under the terms of said contract, the undersigned Contractor, does hereby affirm that all surplus materials as described in said contract have been disposed of at the following location(s)

and that they have been disposed of according to all applicable laws and regulations.

Dated this _____ DAY OF _____, _____.

By: _____
Contractor

ATTEST:

State of _____ County of _____

On this _____ DAY OF _____, 2____, before the undersigned, a Notary Public in and for said County and State, duly commissioned and sworn, personally appeared _____ known to me to be the _____ Contractor named in the foregoing Release, and whose name is subscribed thereto, and acknowledged to me that said Contractor executed the said Release.

Notary Public in and for said County and State

COMPANY LETTERHEAD

CERTIFICATE OF COMPLIANCE

Materials and Workmanship Compliance

For Contract or Task _____

I certify that the material listed below complies with the materials and workmanship requirements of the Caltrans Contract Plans, Special Provisions, Standard Specifications, and Standard Plans for the contract listed above.

I also certify that I am an official representative for _____ the manufacturer of the material listed above. Furthermore, I certify that where California test methods, physical or chemical test requirements are part of the specifications, that the manufacturer has performed the necessary quality control to substantiate this certification.

Material Description:

Manufacturer: _____
Model: _____
Serial Number (if applicable) _____
Quantity to be supplied: _____
Remarks: _____

Signed by: _____

Printed Name: _____

Title: _____

Company: _____

Date: _____

City of San Diego

Engineering & Capital Projects Department, CMFE Division

NOTICE OF MATERIALS TO BE USED

To: _____
Resident Engineer

Date: _____, 20____

You are hereby notified that the materials required for use under Contract No. _____
for construction of _____

in the City of San Diego, will be obtained from sources herein designated.

CONTRACT ITEM NO. (Bid Item)	KIND OF MATERIAL (Category)	NAME AND ADDRESS WHERE MATERIAL CAN BE INSPECTED (At Source)

It is requested that you arrange for a sampling, testing, and inspection of the materials prior to delivery, in accordance with Section 4 – CONTROL OF MATERIALS of the WHITEBOOK, where it is practicable, and in accordance with your policy. It is understood that source inspection does not relieve the Contractor of full responsibility for incorporating in the work, materials that comply in all respects with the contract plans and specifications, nor does it preclude subsequent rejection of materials found to be undesirable or unsuitable.

Distribution:

Supplier

Signature of Supplier

Address

ELECTRONICALLY SUBMITTED FORMS

FAILURE TO FULLY COMPLETE AND SUBMIT ANY OF THE FOLLOWING FORMS WILL DEEM YOUR BID NON-RESPONSIVE.

PLANETBIDS WILL NOT ALLOW FOR BID SUBMISSIONS WITHOUT THE ATTACHMENT OF THESE FORMS

The following forms are to be completed by the bidder and submitted (uploaded) electronically with the bid in PlanetBids.

- A. BID BOND – See Instructions to Bidders, Bidders Guarantee of Good Faith (Bid Security) for further instructions**
- B. CONTRACTOR’S CERTIFICATION OF PENDING ACTIONS**
- C. MANDATORY DISCLOSURE OF BUSINESS INTERESTS FORM**
- D. DEBARMENT AND SUSPENSION CERTIFICATION FOR PRIME CONTRACTOR**
- E. DEBARMENT AND SUSPENSION CERTIFICATION FOR SUBCONTRACTORS, SUPPLIERS AND MANUFACTURERS**

BID BOND

**See Instructions to Bidders, Bidder Guarantee of Good Faith
(Bid Security)**

KNOW ALL MEN BY THESE PRESENTS,

That Pavement Coatings Co. as Principal,
and The Ohio Casualty Insurance Company as Surety, are held
and firmly bound unto The City of San Diego hereinafter called "OWNER," in the sum
of **10% OF THE TOTAL BID AMOUNT** for the payment of which sum, well and truly to be made, we
bind ourselves, our heirs, executors, administrators, successors, and assigns, jointly and severally,
firmly by these presents.

WHEREAS, said Principal has submitted a Bid to said OWNER to perform the WORK required under
the bidding schedule(s) of the OWNER's Contract Documents entitled

Slurry Seal Group 2524 / K-25-2345-DBB-3

NOW THEREFORE, if said Principal is awarded a contract by said OWNER and, within the time and in
the manner required in the "Notice Inviting Bids" enters into a written Agreement on the form of
agreement bound with said Contract Documents, furnishes the required certificates of insurance, and
furnishes the required Performance Bond and Payment Bond, then this obligation shall be null and
void, otherwise it shall remain in full force and effect. In the event suit is brought upon this bond by
said OWNER and OWNER prevails, said Surety shall pay all costs incurred by said OWNER in such suit,
including a reasonable attorney's fee to be fixed by the court.

SIGNED AND SEALED, this 8 day of January, 2025

Pavement Coatings Co. (SEAL)
(Principal)

By:  (Signature) James Wu - Vice President

(SEAL AND NOTARIAL ACKNOWLEDGEMENT OF SURETY)

The Ohio Casualty Insurance Company (SEAL)
(Surety)

By:  (Signature) Evett Lam, Attorney-in-Fact

CALIFORNIA ALL-PURPOSE ACKNOWLEDGMENT**CIVIL CODE § 1189**

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

State of California)

County of Orange)On January 8, 2025 before me, Brigid Lopez, Notary Public,
Date Here Insert Name and Title of the Officerpersonally appeared Evet Lam
Name(s) of Signer(s)

who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature Brigid Lopez
Signature of Notary Public

Place Notary Seal Above

OPTIONAL

Though this section is optional, completing this information can deter alteration of the document or fraudulent reattachment of this form to an unintended document.

Description of Attached Document

Title or Type of Document: _____ Document Date: _____

Number of Pages: _____ Signer(s) Other Than Named Above: _____

Capacity(ies) Claimed by Signer(s)

Signer's Name: _____

☐ Corporate Officer — Title(s): _____☐ Partner — ☐ Limited ☐ General☐ Individual ☐ Attorney in Fact☐ Trustee ☐ Guardian or Conservator☐ Other: _____

Signer Is Representing: _____

Signer's Name: _____

☐ Corporate Officer — Title(s): _____☐ Partner — ☐ Limited ☐ General☐ Individual ☐ Attorney in Fact☐ Trustee ☐ Guardian or Conservator☐ Other: _____

Signer Is Representing: _____

CALIFORNIA ALL-PURPOSE ACKNOWLEDGMENT

CIVIL CODE § 1189

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

State of California

County of Riverside

On January 15th, 2025

Date

before me, Ottly J Gettle, Notary Public

Here Insert Name and Title of the Officer


personally appeared James Wu

Name(s) of Signer(s)

who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.



Place Notary Seal and/or Stamp Above

Signature

Ottly J. Gettle

Signature of Notary Public

OPTIONAL

Completing this information can deter alteration of the document or fraudulent reattachment of this form to an unintended document.

Description of Attached Document

Title or Type of Document: _____

Document Date: _____ Number of Pages: _____

Signer(s) Other Than Named Above: _____

Capacity(ies) Claimed by Signer(s)

Signer's Name: _____

☐ Corporate Officer – Title(s): _____

☐ Partner – ☐ Limited ☐ General

☐ Individual ☐ Attorney in Fact

☐ Trustee ☐ Guardian of Conservator

☐ Other: _____

Signer is Representing: _____

Signer's Name: _____

☐ Corporate Officer – Title(s): _____

☐ Partner – ☐ Limited ☐ General

☐ Individual ☐ Attorney in Fact

☐ Trustee ☐ Guardian of Conservator

☐ Other: _____

Signer is Representing: _____



This Power of Attorney limits the acts of those named herein, and they have no authority to bind the Company except in the manner and to the extent herein stated.

Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

Certificate No: **8208193-971991**

POWER OF ATTORNEY

KNOWN ALL PERSONS BY THESE PRESENTS: That The Ohio Casualty Insurance Company is a corporation duly organized under the laws of the State of New Hampshire, that Liberty Mutual Insurance Company is a corporation duly organized under the laws of the State of Massachusetts, and West American Insurance Company is a corporation duly organized under the laws of the State of Indiana (herein collectively called the "Companies"), pursuant to and by authority herein set forth, does hereby name, constitute and appoint, Brian A. McGoldrick, Brigid Lopez, Evett Lam, Marisella Rivera

all of the city of Placentia state of CA each individually if there be more than one named, its true and lawful attorney-in-fact to make, execute, seal, acknowledge and deliver, for and on its behalf as surety and as its act and deed, any and all undertakings, bonds, recognizances and other surety obligations, in pursuance of these presents and shall be as binding upon the Companies as if they have been duly signed by the president and attested by the secretary of the Companies in their own proper persons.

IN WITNESS WHEREOF, this Power of Attorney has been subscribed by an authorized officer or official of the Companies and the corporate seals of the Companies have been affixed thereto this 21st day of June, 2022.



Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

By: David M. Carey
David M. Carey, Assistant Secretary

State of PENNSYLVANIA ss
County of MONTGOMERY

On this 21st day of June, 2022 before me personally appeared David M. Carey, who acknowledged himself to be the Assistant Secretary of Liberty Mutual Insurance Company, The Ohio Casualty Company, and West American Insurance Company, and that he, as such, being authorized so to do, execute the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my notarial seal at King of Prussia, Pennsylvania, on the day and year first above written.



Commonwealth of Pennsylvania - Notary Seal
Teresa Pastella, Notary Public
Montgomery County
My commission expires March 28, 2025
Commission number 1126044
Member, Pennsylvania Association of Notaries

By: Teresa Pastella
Teresa Pastella, Notary Public

This Power of Attorney is made and executed pursuant to and by authority of the following By-laws and Authorizations of The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company which resolutions are now in full force and effect reading as follows:

ARTICLE IV – OFFICERS: Section 12. Power of Attorney.

Any officer or other official of the Corporation authorized for that purpose in writing by the Chairman or the President, and subject to such limitation as the Chairman or the President may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Corporation to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact, subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Corporation by their signature and execution of any such instruments and to attach thereto the seal of the Corporation. When so executed, such instruments shall be as binding as if signed by the President and attested to by the Secretary. Any power or authority granted to any representative or attorney-in-fact under the provisions of this article may be revoked at any time by the Board, the Chairman, the President or by the officer or officers granting such power or authority.

ARTICLE XIII – Execution of Contracts: Section 5. Surety Bonds and Undertakings.

Any officer of the Company authorized for that purpose in writing by the chairman or the president, and subject to such limitations as the chairman or the president may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Company by their signature and execution of any such instruments and to attach thereto the seal of the Company. When so executed such instruments shall be as binding as if signed by the president and attested by the secretary.

Certificate of Designation – The President of the Company, acting pursuant to the Bylaws of the Company, authorizes David M. Carey, Assistant Secretary to appoint such attorneys-in-fact as may be necessary to act on behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations.

Authorization – By unanimous consent of the Company's Board of Directors, the Company consents that facsimile or mechanically reproduced signature of any assistant secretary of the Company, wherever appearing upon a certified copy of any power of attorney issued by the Company in connection with surety bonds, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

I, Renee C. Llewellyn, the undersigned, Assistant Secretary, The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company do hereby certify that the original power of attorney of which the foregoing is a full, true and correct copy of the Power of Attorney executed by said Companies, is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this 8 day of January, 2024.



By: Renee C. Llewellyn
Renee C. Llewellyn, Assistant Secretary

Not valid for mortgage, note, loan, letter of credit, currency rate, interest rate or residual value guarantees.

For bond and/or Power of Attorney (POA) verification inquiries, please call 610-832-8240 or email HOSUR@libertymutual.com.

CONTRACTOR'S CERTIFICATION OF PENDING ACTIONS

As part of its bid or proposal (Non-Price Proposal in the case of Design-Build contracts), the Bidder shall provide to the City a list of all instances within the past 10 years where a complaint was filed or pending against the Bidder in a legal or administrative proceeding alleging that Bidder discriminated against its employees, subcontractors, vendors or suppliers, and a description of the status or resolution of that complaint, including any remedial action taken.

CHECK ONE BOX ONLY.



The undersigned certifies that within the past 10 years the Bidder has NOT been the subject of a complaint or pending action in a legal administrative proceeding alleging that Bidder discriminated against its employees, subcontractors, vendors or suppliers.



The undersigned certifies that within the past 10 years the Bidder has been the subject of a complaint or pending action in a legal administrative proceeding alleging that Bidder discriminated against its employees, subcontractors, vendors or suppliers. A description of the status or resolution of that complaint, including any remedial action taken and the applicable dates is as follows:

DATE OF CLAIM	LOCATION	DESCRIPTION OF CLAIM	LITIGATION (Y/N)	STATUS	RESOLUTION/REMEDIAL ACTION TAKEN

Contractor Name: Pavement Coatings Co.

Certified By James Wu

Title Vice President

Name

Signature

Date 1/15/2025

USE ADDITIONAL FORMS AS NECESSARY

Mandatory Disclosure of Business Interests Form

BIDDER/PROPOSER INFORMATION

Legal Name		DBA	
Pavement Coatings Co.		Pavement Coatings Co.	
Street Address	City	State	Zip
10240 San Sevaine Way	Jurupa Valley	California	91752
Contact Person, Title		Phone	Fax
James Wu - Vice President		714-826-3011	714-826-3129

Provide the name, identity, and precise nature of the interest* of all persons who are directly or indirectly involved** in this proposed transaction (SDMC § 21.0103).

* The precise nature of the interest includes:

- the percentage ownership interest in a party to the transaction,
- the percentage ownership interest in any firm, corporation, or partnership that will receive funds from the transaction, the value of any financial interest in the transaction,
- any contingent interest in the transaction and the value of such interest should the contingency be satisfied, and any philanthropic, scientific, artistic, or property interest in the transaction.

** Directly or indirectly involved means pursuing the transaction by:

- communicating or negotiating with City officers or employees,
- submitting or preparing applications, bids, proposals or other documents for purposes of contracting with the City,
- or directing or supervising the actions of persons engaged in the above activity.

Name	Title/Position
Tim Schmid	President
City and State of Residence	Employer (if different than Bidder/Proposer)
Jurupa Valley, CA	Pavement Coatings Co.
Interest in the transaction	
General Contractor - 50% or Greater	

Name	Title/Position
James Wu	Vice President
City and State of Residence	Employer (if different than Bidder/Proposer)
Jurupa Valley, CA	Pavement Coatings Co.
Interest in the transaction	
General Contractor - 50% or Greater	

* Use Additional Pages if Necessary *

Under penalty of perjury under the laws of the State of California, I certify that I am responsible for the completeness and accuracy of the responses contained herein, and that all information provided is true, full and complete to the best of my knowledge and belief. I agree to provide written notice to the Mayor or Designee within five (5) business days if, at any time, I learn that any portion of this Mandatory Disclosure of Business Interests Form requires an updated response. Failure to timely provide the Mayor or Designee with written notice is grounds for Contract termination.

James Wu - Vice President

Print Name, Title

Signature

Date

1/15/2025

Failure to sign and submit this form with the bid/proposal shall make the bid/proposal non-responsive. In the case of an informal solicitation, the contract will not be awarded unless a signed and completed Mandatory Disclosure of Business Interests Form is submitted.

DEBARMENT AND SUSPENSION CERTIFICATION
PRIME CONTRACTOR
FAILURE TO COMPLETE AND SUBMIT AT TIME OF BID SHALL RENDER BID NON-RESPONSIVE

EFFECT OF DEBARMENT OR SUSPENSION
To promote integrity in the City's contracting processes and to protect the public interest, the City shall only enter into contracts with responsible- bidders and contractors. In accordance with San Diego Municipal Code §22.0814 (a): <i>Bidders</i> and <i>contractors</i> who have been <i>debarred</i> or <i>suspended</i> are excluded from submitting bids, submitting responses to requests for proposal or qualifications, receiving <i>contract</i> awards, executing <i>contracts</i> , participating as a <i>subcontractor</i> , employee, agent or representative of another <i>person</i> contracting with the City.

As part of its bid or proposal (Non-Price Proposal in the case of Design-Build contracts), the Bidder shall provide to the City a list of Names of the Principal Individual owner(s).

The names of all persons interested in the foregoing proposal as Principals are as follows:

NAME	TITLE
Tim Schmid	President
James Wu	Vice President
Tom Mucenski	Secretary

IMPORTANT NOTICE: If Bidder or other interested person is a corporation, state secretary, treasurer, and manager thereof; if a co-partnership, state true name of firm, also names of all individual co-partners composing firm; if Bidder or other interested person is an individual, state first and last names in full.

The Bidder, under penalty of perjury, certifies that, except as noted below, he/she or any person associated therewith in the capacity of owner, partner, director, officer, manager:

- Is not currently under suspension, debarment, voluntary exclusion, or determination of ineligibility by any Federal, State or local agency;
- has not been suspended, debarred, voluntarily excluded or determined ineligible by any Federal, State or local agency within the past 3 years;
- does not have a proposed debarment pending; and
- has not been indicted, convicted, or had a civil judgment rendered against it by a court of competent jurisdiction in any matter involving fraud or official misconduct within the past 3 years.


If there are any exceptions to this certification, insert the exceptions in the following space.

N/A

Exceptions will be considered in determining bidder responsibility. For any exception noted above, indicate below to whom it applies, initiating agency, and dates of action.

Contractor Name: Pavement Coatings Co.

Certified By James Wu Title Vice President

Name 

Signature

Date 1/15/2025

NOTE: Providing false information may result in criminal prosecution or administrative sanctions.

DEBARMENT AND SUSPENSION CERTIFICATION
SUBCONTRACTORS, SUPPLIERS AND MANUFACTURERS
TO BE COMPLETED BY BIDDER

FAILURE TO COMPLETE AND SUBMIT AT TIME OF BID SHALL RENDER BID NON-RESPONSIVE

Names of the Principal individual owner(s)

As part of its bid or proposal (Non-Price Proposal in the case of Design-Build contracts), the Bidder shall provide to the City a list of Names of the Principal Individual owner(s) for their subcontractor/supplier/manufacturers.

Please indicate if principal owner is serving in the capacity of **subcontractor**, **supplier**, and/or **manufacturer**:

☒ SUBCONTRACTOR ☐ SUPPLIER ☐ MANUFACTURER

NAME	TITLE
Pavement Rehab Company	Robert Steen - President
Statewide Stripes, Inc	David Brilhante - President

☒ SUBCONTRACTOR ☐ SUPPLIER ☐ MANUFACTURER

NAME	TITLE
Traffic loops Crackfilling, Inc	Mai Lan Nguyen - President
RP General Construction, Inc.	Ramiro Ponce - President

☒ SUBCONTRACTOR ☐ SUPPLIER ☐ MANUFACTURER

NAME	TITLE

☒ SUBCONTRACTOR ☐ SUPPLIER ☐ MANUFACTURER

NAME	TITLE

Contractor Name: Pavement Coatings Co.

Certified By: James Wu

Title: Vice President

Name

Date: 1/15/2025

Signature

****USE ADDITIONAL FORMS AS NECESSARY****

DEBARMENT AND SUSPENSION CERTIFICATION
SUBCONTRACTORS, SUPPLIERS AND MANUFACTURERS
TO BE COMPLETED BY BIDDER

FAILURE TO COMPLETE AND SUBMIT AT TIME OF BID SHALL RENDER BID NON-RESPONSIVE

Names of the Principal individual owner(s)

As part of its bid or proposal (Non-Price Proposal in the case of Design-Build contracts), the Bidder shall provide to the City a list of Names of the Principal Individual owner(s) for their subcontractor/supplier/manufacturers.

Please indicate if principal owner is serving in the capacity of **subcontractor**, **supplier**, and/or **manufacturer**:

☐ SUBCONTRACTOR ☒ SUPPLIER ☐ MANUFACTURER

NAME	TITLE
Sustainable Emulsions, LLC	Stephen Concannon - President
Chandler's Aggregates	Eric Wener - President

☐ SUBCONTRACTOR ☒ SUPPLIER ☐ MANUFACTURER

NAME	TITLE
CDG Materials	Dave Beck - President
Superior Ready Mix Concrete, LP	Chris Brouwer - Vice President of Sales

☐ SUBCONTRACTOR ☒ SUPPLIER ☐ MANUFACTURER

NAME	TITLE
All American Asphalt	Mark Luer - President
Western Emulsion, Inc	Matt Blake - CEO

☐ SUBCONTRACTOR ☒ SUPPLIER ☐ MANUFACTURER

NAME	TITLE

Contractor Name: Pavement Coatings Co.

Certified By: James Wu

Title: Vice President

Name

Date: 4/15/2025
4/15/2021 fw

Signature

****USE ADDITIONAL FORMS AS NECESSARY****

SUBCONTRACTOR LISTING (OTHER THAN FIRST TIER)

Pursuant to California Senate Bill 96 and in accordance with the requirements of Labor Code sections 1771.1 and 1725.5, by submitting a bid or proposal to the City, Contractor is certifying that he or she has verified that all subcontractors used on this public work project are registered with the California Department of Industrial Relations (DIR). **The Bidder is to list below the name, address, license number, DIR registration number of any (known tiered subcontractor)** - who will perform work, labor, render services or specially fabricate and install a portion [type] of the work or improvement pursuant to the contract. **If none are known at this time, mark the table below with non-applicable (N/A).**

Prime Contractor Name: Pavement Coatings Co.

NAME, ADDRESS AND TELEPHONE NUMBER OF SUBCONTRACTOR	CONSTRUCTOR OR DESIGNER	DIR REGISTRATION NUMBER	SUBCONTRACTOR LICENSE NUMBER	TYPE OF WORK
Name: <u>NONE</u> Address: _____ City: _____ State: _____ Zip: _____ Phone: _____ Email: _____				
Name: _____ Address: _____ City: _____ State: _____ Zip: _____ Phone: _____ Email: _____				
Name: _____ Address: _____ City: _____ State: _____ Zip: _____ Phone: _____ Email: _____				
Name: _____ Address: _____ City: _____ State: _____ Zip: _____ Phone: _____ Email: _____				

**** USE ADDITIONAL FORMS AS NECESSARY ****

Bid Results

Bidder Details

Vendor Name	Pavement Coatings Co.
Address	10240 San Sevaine Way Jurupa Valley, California 91752 United States
Respondee	James Wu
Respondee Title	Vice President
Phone	714-826-3011
Email	jwu@pavementrecycling.com
Vendor Type	CADIR
License #	303609
CADIR	1000003382

Bid Detail

Bid Format	Electronic
Submitted	01/28/2025 1:33 PM (PST)
Delivery Method	
Bid Responsive	
Bid Status	Submitted
Confirmation #	410443

Respondee Comment

Buyer Comment

Attachments

File Title	File Name	File Type
Contractors Certification of Pending Actions.pdf	Contractors Certification of Pending Actions.pdf	Contractors Certification of Pending Actions
Mandatory Disclosure of Business Interests.pdf	Mandatory Disclosure of Business Interests.pdf	Mandatory Disclosure of Business Interests
Prime Debarment & Suspension Form.pdf	Prime Debarment & Suspension Form.pdf	Prime Debarment & Suspension Form
Subcontractor Debarment & Suspension Form.pdf	Subcontractor Debarment & Suspension Form.pdf	Subcontractor Debarment & Suspension Form
Bid Bond.pdf	Bid Bond.pdf	Bid Bond

Subcontractors

Showing 4 Subcontractors

Name & Address	Desc	License Num	CADIR	Amount	Type
Pavement Rehab Company 2890 E. La Cresta Ave. Anaheim, California 92806	Constructor: Crack Seal	1051374	1000064823	\$166,919.50	
RP General Construction Inc. 28357 COLE GRADE ROAD VALLEY CENTER, California 92082	Constructor: Adjust Utilities, Asphalt	921361	1000034037	\$1,018,410.00	CADIR, SLBE, MBE, Local
Statewide Stripes Inc. PO Box 600710 San Diego, California 92160	Constructors: Striping removals and Replacement	788286	1000001334	\$1,188,990.00	DBE, CADIR, Local
Traffic Loops Crackfilling, Inc. 946 S. Emerald Street Anaheim, California 92804	Constructors: Traffic Loops	652956	1000003794	\$95,180.00	

Line Items

Discount Terms No Discount

Item #	Item Code	Type	Item Description	UOM	QTY	Unit Price	Line Total	Response	Comment
Main Bid							\$5,641,388.50		
1	237310		Raise Appurtenance to Grade (Water, Sewer)	EA	195	\$393.00	\$76,635.00	Yes	
2	237310		Adjust Existing Manhole Frame and Cover to Grade	EA	109	\$893.00	\$97,337.00	Yes	
3	237310		Survey Monument Lids	EA	2	\$204.00	\$408.00	Yes	
4	237310		Reconstruct Survey Monument Box	EA	3	\$969.00	\$2,907.00	Yes	
5	237310		Adjust Existing Survey Monument to Grade	EA	18	\$1,071.00	\$19,278.00	Yes	
6	237310		Crushed Miscellaneous Base	TON	580	\$5.15	\$2,987.00	Yes	
7	238210		Traffic Detector Loop Replacement or Conduit Stub Installed	EA	162	\$595.00	\$96,390.00	Yes	
8	238210		Detector Lead In Cable	LF	280	\$7.35	\$2,058.00	Yes	
9	237310		Red Curb	LF	8448	\$4.55	\$38,438.40	Yes	
10	237310		Asphalt Pavement Repair	TON	3590	\$265.00	\$951,350.00	Yes	
11	237310		Edge Grind AC Pavement (<2-inch)	LF	8290	\$5.98	\$49,574.20	Yes	
12	237310		Asphalt Concrete with Pavement Fabric Material	TON	500	\$14.70	\$7,350.00	Yes	
13	237310		Rubber Polymer Modified Slurry (RPMS) Type I	SF	2471770	\$0.20	\$494,354.00	Yes	
14	237310		Rubber Polymer Modified Slurry (RPMS) Type II	SF	3318890	\$0.26	\$862,911.40	Yes	
15	237310		Rubber Polymer Modified Slurry (RPMS) Type III	SF	1211550	\$0.44	\$533,082.00	Yes	
16	237310		Cape Seal (PMRE Scrub Seal with Type II Slurry Seal)	SF	424020	\$0.90	\$381,618.00	Yes	
17	237310		Crack Seal	LB	48950	\$3.55	\$173,772.50	Yes	
18	237310		Post-construction Requirements - Inlet Markings	EA	38	\$51.00	\$1,938.00	Yes	
19	524126		Bonds (Payment and Performance)	LS	1	\$22,000.00	\$22,000.00	Yes	
20	541330		WPCP Development	LS	1	\$1,000.00	\$1,000.00	Yes	
21	237310		WPCP Implementation	LS	1	\$15,000.00	\$15,000.00	Yes	
22			Field Orders (EOC Type II)	AL	1	\$100,000.00	\$100,000.00	Yes	
23	237310		Remove, Replace & Install Traffic Striping, Markers, Markings, and Devices	LS	1	\$605,000.00	\$605,000.00	Yes	
24	541330		Traffic Control and Working Drawings	LS	1	\$522,000.00	\$522,000.00	Yes	
25	237310		Carmel Country Rd Striping, Signage & Electrical Improvement	LS	1	\$101,000.00	\$101,000.00	Yes	
26	237310		Vista Sorrento Pkwy Striping, Signage & Electrical Improvement	LS	1	\$152,000.00	\$152,000.00	Yes	
27	237310		Canon St Striping, Signage & Electrical Improvement	LS	1	\$96,000.00	\$96,000.00	Yes	
28	237310		Cardeno Dr Striping & Signage Improvement	LS	1	\$61,000.00	\$61,000.00	Yes	
29	237310		Sunset Cliffs Blvd Striping & Signage Improvement	LS	1	\$42,000.00	\$42,000.00	Yes	
30	237310		Rosecrans St Striping, Signage & Electrical Improvement	LS	1	\$85,000.00	\$85,000.00	Yes	
31	237310		Soledad Mountain Rd Striping & Signage Improvement	LS	1	\$47,000.00	\$47,000.00	Yes	

Line Item Subtotals

Section Title	Line Total
Main Bid	\$5,641,388.50
Grand Total	\$5,641,388.50