

THE CITY OF SAN DIEGO

**FPB POLICY
A-14-9**

**ACCESS ROADWAYS:
MODIFIED ROADWAY SURFACE
CFC SECTION 503**

I. PURPOSE

The purpose of this policy is to establish procedures and standards for all weather access roads for Fire-Rescue Department vehicles when modified access road materials are used.

II. SCOPE

This policy shall govern and include all access roads using modified road surfaces, other than the SDG-113 Standard Portland Cement Concrete or Asphalt Concrete pavements, that may be utilized by Fire-Rescue Department vehicles/apparatus to approach or stage for an emergency response to a structure, hazard, equipment, or process.

III. DEFINITIONS

- A. Standard Road Surface – SDG-113 pavement such as Portland Cement Concrete or Asphalt Concrete within the improved Public Rights-of-Way.
- B. Modified Road Surface – a type of material surface that provides for the structural stability and minimum coefficient of friction needed to traverse the access road over difficult topographic conditions for Fire-Rescue Department vehicle access, such as monolithic stamped concrete, interlocking concrete pavers, etc.
- C. Combined Material Road Surface – the combined use of grass with reinforced concrete pavement, interlocking block systems, or other acceptable reinforced and retained road products.

IV. PROCEDURES

- A. Access roads with other than standard material surfaces shall be approved by the Fire-Rescue Department's Fire Inspector II Liaison for DSD in writing on an individual case-by-case basis only. The Fire-Rescue Department approval letter shall be included with all plan sets and in the record file prior to the commencement of construction.

Fire Prevention Bureau

Fire-Rescue Department • 1010 Second Avenue, Suite 300 • San Diego, CA 92101-4903
Tel (619) 533-4400 Fax 544-6806

- B. The required width of the Fire-Rescue Department vehicle access road shall not be obstructed in any manner, including parked vehicles, landscaping, trees, shrubbery, or decorative objects.
- C. The requirements are applicable except as modified herein:
 - 1. The maximum grade for any Fire-Rescue Department Vehicle Access road is “five percent” (5%) or (2.25 degrees) for combination surfaces (like grass and concrete panels/blocks or pavement).
 - 2. A minimum eight-inch (8”) width concrete border shall be used to define the sides of the Fire-Rescue Department access road. This border may be level with or rise (height not to exceed 8”) above the finished road grade. The “No Parking – Fire Lane” lettering may be stamped into or painted upon the border. Signage shall comply with current Development Services Policy.
 - 3. For combined road surfaces, the support shall be adequately reinforced with structural steel to fully support the dead, live and impact loads necessary for fire apparatus weighing at least 75,000 pounds.
 - 4. Grass within the combined access road surface shall be well maintained with a height not exceeding two-inches (2”). The road surface shall be free of over growth from adjacent areas.
 - 5. Any settlement of the road surface or other damage shall be repaired immediately.
 - 6. The Fire Marshal may require removal of the modified access road surface and the construction of an approved standard all weather road surface (concrete or asphalt) for continued violations of this modified access policy.
- D. In addition to the manufacturer’s required construction standards for the modified road surface, the following minimum base material standards shall be met. Subgrade preparation shall be done in accordance with Section 301-1 of the Standard Specifications for Public Works Construction (also referred to as “The Greenbook”):
 - 1. The latest adopted edition of “The Greenbook” shall be used.
 - 2. The City of San Diego periodically amends “The Greenbook” specific to San Diego needs.

3. The City of San Diego's amendments to "The Greenbook" are referred to as "The Whitebook."

Link: <http://www.sandiego.gov/publicworks/edocref/greenbook.shtml>


4. All items in "The Whitebook" also apply to modified road surfaces as currently adopted by the City of San Diego.
5. The completed road surface shall be capable of supporting the imposed load of fire apparatus weighing at least 75,000 pounds.

- E. Access road engineering plans shall meet or exceed Fire-Rescue Department requirements:

1. In addition to normal Development Services Permit Inspection, Fire-Rescue Department Inspection approval is required.
2. Fire-Rescue Department shall have final approval of the completed road.

- F. A plot plan of the project site showing all access roads, fire hydrants, fire protection systems, and building access locations, suitable for pre-fire planning (8 1/2" x 11"), is required. Fire Companies will maintain up-to-date pre-fire plans of all Fire-Rescue Department vehicle access road installations.

- G. Access road maintenance will be monitored annually by the Fire Company Inspection Program and will include actual operation of Fire-Rescue Department apparatus over the access road surface to verify access road stability.

Promulgated by: 

Date: 2/17/2015

Rev. 2-17-15