

Brown Field Runway 8L/26R Construction Project

April 1, 2016

There will be a major construction project taking place at Brown Field beginning the week of April 4 which will involve rehabilitating runway 8L/26R. The project is phased to reduce the impact to aircraft operations as much as possible; however, operational limitations will exist, including:

- Runway 8L/26R will be temporarily closed for construction preparation at 10:00 PM local on Monday, April 4, and will reopen at 6:00 AM on Thursday, April 7.
- Runway 8R/26L will remain open during the project.
- Runway 26R will utilize a 10 foot blast fence at the approach end and employ a displaced threshold.
- Runway 26R will utilize the following declared distances:
TORA 6049 feet, TODA 6049 feet, ASDA 6049 feet, LDA 5541 feet
- Runway 8L will utilize the following declared distances:
TORA 5541 feet, TODA 5541 feet, ASDA 5141 feet, LDA 5141 feet
- Portions of taxiways Charlie and Alpha will be closed temporarily during construction preparation.
- Taxiway Alpha will be closed east of taxiway Charlie.
- Runway 26R PAPI's and REIL's will be out of service.
- Runway 26R will employ the use of a temporary Pulse Light Approach Slope Indicator (PLASI).
- There will be a significant amount of construction personnel and equipment on and near taxiway Alpha, Charlie and adjacent Runway 26R.

Dates and times are subject to change due to unforeseen delays. Pilots are encouraged to check NOTAM's and listen carefully to ATIS prior to flying during the scheduled construction period, or contact Airport Operations at (619) 424-0455.