

Priority Development Project (PDP) Storm Water Quality Management Plan (SWQMP)

Check if electing for offsite alternative compliance

Engineer of Work:

Provide Wet Signature and Stamp Above Line

Prepared For:

Prepared By:



PROJECT DESIGN CONSULTANTS

Planning | Landscape Architecture | Engineering | Survey

701 B Street, Suite 800
San Diego, CA 92101
619.235.6471 Tel
619.234.0349 Fax

Date:

Approved by: City of San Diego

Date

Written by: Jeff Novoa
Job No. 2357.60



Table of Contents

- Acronyms
- Certification Page
- Submittal Record
- Project Vicinity Map
- FORM DS-560: Storm Water Applicability Checklist
- FORM I-1: Applicability of Permanent, Post-Construction Storm Water BMP Requirements
- HMP Exemption Exhibit (for all hydromodification management exempt projects)
- FORM I-3B: Site Information Checklist for PDPs
- FORM I-4B: Source Control BMP Checklist for PDPs
- FORM I-5B: Site Design BMP Checklist PDPs
- FORM I-6: Summary of PDP Structural BMPs
- Attachment 1: Backup for PDP Pollutant Control BMPs
 - Attachment 1a: DMA Exhibit
 - Attachment 1b: Tabular Summary of DMAs (Worksheet B-1 from Appendix B) and Design Capture Volume Calculations
 - Attachment 1c: FORM I-7 : Worksheet B.3-1 Harvest and Use Feasibility Screening
 - Attachment 1d: Infiltration Feasibility Information(One or more of the following):
 - FORM I-8A: Worksheet C.4-1 Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions
 - Form I-8B: Worksheet C.4-2 Categorization of Infiltration Feasibility Condition based on Groundwater and Water Balance Conditions
 - Infiltration Feasibility Condition Letter
 - Worksheet C.4-3: Infiltration and Groundwater Protection for Full Infiltration BMPs
 - FORM I-9: Worksheet D.5-1 Factor of Safety and Design Infiltration Rate
 - Attachment 1e: Pollutant Control BMP Design Worksheets / Calculations
- Attachment 2: Backup for PDP Hydromodification Control Measures
 - Attachment 2a: Hydromodification Management Exhibit
 - Attachment 2b: Management of Critical Coarse Sediment Yield Areas
 - Attachment 2c: Geomorphic Assessment of Receiving Channels
 - Attachment 2d: Flow Control Facility Design

Project Name:

- Attachment 3: Structural BMP Maintenance Plan
 - Maintenance Agreement (Form DS-3247) (when applicable)
- Attachment 4: Copy of Plan Sheets Showing Permanent Storm Water BMPs
- Attachment 5: Project's Drainage Report
- Attachment 6: Project's Geotechnical and Groundwater Investigation Report

Project Name:

Acronyms

APN	Assessor's Parcel Number
ASBS	Area of Special Biological Significance
BMP	Best Management Practice
CEQA	California Environmental Quality Act
CGP	Construction General Permit
DCV	Design Capture Volume
DMA	Drainage Management Areas
ESA	Environmentally Sensitive Area
GLU	Geomorphic Landscape Unit
GW	Ground Water
HMP	Hydromodification Management Plan
HSG	Hydrologic Soil Group
HU	Harvest and Use
INF	Infiltration
LID	Low Impact Development
LUP	Linear Underground/Overhead Projects
MS4	Municipal Separate Storm Sewer System
N/A	Not Applicable
NPDES	National Pollutant Discharge Elimination System
NRCS	Natural Resources Conservation Service
PDP	Priority Development Project
PE	Professional Engineer
POC	Pollutant of Concern
SC	Source Control
SD	Site Design
SDRWQCB	San Diego Regional Water Quality Control Board
SIC	Standard Industrial Classification
SWPPP	Stormwater Pollutant Protection Plan
SWQMP	Storm Water Quality Management Plan
TMDL	Total Maximum Daily Load
WMAA	Watershed Management Area Analysis
WPCP	Water Pollution Control Program
WQIP	Water Quality Improvement Plan

Project Name:

Certification Page

Project Name: Permit Application

I hereby declare that I am the Engineer in Responsible Charge of design of storm water BMPs for this project, and that I have exercised responsible charge over the design of the project as defined in Section 6703 of the Business and Professions Code, and that the design is consistent with the requirements of the Storm Water Standards, which is based on the requirements of SDRWQCB Order No. R9-2013-0001 as amended by R9-2015-0001 and R9-2015-0100 (MS4 Permit).

I have read and understand that the City Engineer has adopted minimum requirements for managing urban runoff, including storm water, from land development activities, as described in the Storm Water Standards. I certify that this PDP SWQMP has been completed to the best of my ability and accurately reflects the project being proposed and the applicable source control and site design BMPs proposed to minimize the potentially negative impacts of this project's land development activities on water quality. I understand and acknowledge that the plan check review of this PDP SWQMP by the City Engineer is confined to a review and does not relieve me, as the Engineer in Responsible Charge of design of storm water BMPs for this project, of my responsibilities for project design.

Engineer of Work's Signature

PE#

Expiration Date

Print Name

Company

Date



Project Name:

Submittal Record


Use this Table to keep a record of submittals of this PDP SWQMP. Each time the PDP SWQMP is re-submitted, provide the date and status of the project. In last column indicate changes that have been made or indicate if response to plancheck comments is included. When applicable, insert response to plancheck comments.

Submittal Number	Date	Project Status	Changes
1		Preliminary Design/Planning/CEQA Final Design	Initial Submittal
2		Preliminary Design/Planning/CEQA Final Design	
3		Preliminary Design/Planning/CEQA Final Design	
4		Preliminary Design/Planning/CEQA Final Design	

Project Name:

Project Vicinity Map

Project Name:
Permit Application



Project Name:

City of San Diego Form DS-560 Storm Water Requirements Applicability Checklist

Attach DS-560 form.



City of San Diego
Development Services
1222 First Ave., MS-302
San Diego, CA 92101
(619) 446-5000

Storm Water Requirements Applicability Checklist

FORM
DS-560
November 2018

Project Address:

Project Number:

SECTION 1. Construction Storm Water BMP Requirements:

All construction sites are required to implement construction BMPs in accordance with the performance standards in the [Storm Water Standards Manual](#). Some sites are additionally required to obtain coverage under the State Construction General Permit (CGP)¹, which is administered by the State Regional Water Quality Control Board.

For all projects complete PART A: If project is required to submit a SWPPP or WPCP, continue to PART B.

PART A: Determine Construction Phase Storm Water Requirements.

1. Is the project subject to California's statewide General NPDES permit for Storm Water Discharges Associated with Construction Activities, also known as the State Construction General Permit (CGP)? (Typically projects with land disturbance greater than or equal to 1 acre.)

☐ Yes; SWPPP required, skip questions 2-4 ☐ No; next question

2. Does the project propose construction or demolition activity, including but not limited to, clearing, grading, grubbing, excavation, or any other activity resulting in ground disturbance and/or contact with storm water?

☐ Yes; WPCP required, skip questions 3-4 ☐ No; next question

3. Does the project propose routine maintenance to maintain original line and grade, hydraulic capacity, or original purpose of the facility? (Projects such as pipeline/utility replacement)

☐ Yes; WPCP required, skip question 4 ☐ No; next question

4. Does the project only include the following Permit types listed below?

- Electrical Permit, Fire Alarm Permit, Fire Sprinkler Permit, Plumbing Permit, Sign Permit, Mechanical Permit, Spa Permit.
- Individual Right of Way Permits that exclusively include only ONE of the following activities: water service, sewer lateral, or utility service.
- Right of Way Permits with a project footprint less than 150 linear feet that exclusively include only ONE of the following activities: curb ramp, sidewalk and driveway apron replacement, pot holing, curb and gutter replacement, and retaining wall encroachments.

☐ Yes; no document required

Check one of the boxes below, and continue to PART B:

☐ If you checked "Yes" for question 1,
a SWPPP is REQUIRED. Continue to PART B

☐ If you checked "No" for question 1, and checked "Yes" for question 2 or 3,
a WPCP is REQUIRED. If the project proposes less than 5,000 square feet of ground disturbance AND has less than a 5-foot elevation change over the entire project area, a Minor WPCP may be required instead. **Continue to PART B.**

☐ If you checked "No" for all questions 1-3, and checked "Yes" for question 4
PART B does not apply and no document is required. Continue to Section 2.

1. More information on the City's construction BMP requirements as well as CGP requirements can be found at:
www.sandiego.gov/stormwater/regulations/index.shtml

PART B: Determine Construction Site Priority

This prioritization must be completed within this form, noted on the plans, and included in the SWPPP or WPCP. The city reserves the right to adjust the priority of projects both before and after construction. Construction projects are assigned an inspection frequency based on if the project has a "high threat to water quality." The City has aligned the local definition of "high threat to water quality" to the risk determination approach of the State Construction General Permit (CGP). The CGP determines risk level based on project specific sediment risk and receiving water risk. Additional inspection is required for projects within the Areas of Special Biological Significance (ASBS) watershed. **NOTE:** The construction priority does **NOT** change construction BMP requirements that apply to projects; rather, it determines the frequency of inspections that will be conducted by city staff.

Complete PART B and continued to Section 2

1. ☐ **ASBS**
 - a. Projects located in the ASBS watershed.
2. **High Priority**
 - a. Projects that qualify as Risk Level 2 or Risk Level 3 per the Construction General Permit (CGP) and not located in the ASBS watershed.
 - b. Projects that qualify as LUP Type 2 or LUP Type 3 per the CGP and not located in the ASBS watershed.
3. ☐ **Medium Priority**
 - a. Projects that are not located in an ASBS watershed or designated as a High priority site.
 - b. Projects that qualify as Risk Level 1 or LUP Type 1 per the CGP and not located in an ASBS watershed.
 - c. WPCP projects (>5,000sf of ground disturbance) located within the Los Penasquitos watershed management area.
4. ☐ **Low Priority**
 - a. Projects not subject to a Medium or High site priority designation and are not located in an ASBS watershed.

SECTION 2. Permanent Storm Water BMP Requirements.

Additional information for determining the requirements is found in the [Storm Water Standards Manual](#).

PART C: Determine if Not Subject to Permanent Storm Water Requirements.

Projects that are considered maintenance, or otherwise not categorized as "new development projects" or "redevelopment projects" according to the [Storm Water Standards Manual](#) are not subject to Permanent Storm Water BMPs.

If "yes" is checked for any number in Part C, proceed to Part F and check "Not Subject to Permanent Storm Water BMP Requirements".

If "no" is checked for all of the numbers in Part C continue to Part D.

1. Does the project only include interior remodels and/or is the project entirely within an existing enclosed structure and does not have the potential to contact storm water? ☐ Yes ☐ No
2. Does the project only include the construction of overhead or underground utilities without creating new impervious surfaces? ☐ Yes ☐ No
3. Does the project fall under routine maintenance? Examples include, but are not limited to: roof or exterior structure surface replacement, resurfacing or reconfiguring surface parking lots or existing roadways without expanding the impervious footprint, and routine replacement of damaged pavement (grinding, overlay, and pothole repair). ☐ Yes ☐ No

PART D: PDP Exempt Requirements.

PDP Exempt projects are required to implement site design and source control BMPs.

If “yes” was checked for any questions in Part D, continue to Part F and check the box labeled “PDP Exempt.”

If “no” was checked for all questions in Part D, continue to Part E.

1. Does the project ONLY include new or retrofit sidewalks, bicycle lanes, or trails that:

- **Are designed and constructed to direct storm water runoff to adjacent vegetated areas, or other non-erodible permeable areas? Or;**
- **Are designed and constructed to be hydraulically disconnected from paved streets and roads? Or;**
- **Are designed and constructed with permeable pavements or surfaces in accordance with the Green Streets guidance in the City’s Storm Water Standards manual?**

☐ Yes; PDP exempt requirements apply

☐ No; next question

2. Does the project ONLY include retrofitting or redeveloping existing paved alleys, streets or roads designed and constructed in accordance with the Green Streets guidance in the [City’s Storm Water Standards Manual](#)?

☐ Yes; PDP exempt requirements apply

☐ No; project not exempt.

PART E: Determine if Project is a Priority Development Project (PDP).

Projects that match one of the definitions below are subject to additional requirements including preparation of a Storm Water Quality Management Plan (SWQMP).

If “yes” is checked for any number in PART E, continue to PART F and check the box labeled “Priority Development Project”.

If “no” is checked for every number in PART E, continue to PART F and check the box labeled “Standard Development Project”.

1. New Development that creates 10,000 square feet or more of impervious surfaces collectively over the project site. This includes commercial, industrial, residential, mixed-use, and public development projects on public or private land.

☐ Yes ☐ No

2. Redevelopment project that creates and/or replaces 5,000 square feet or more of impervious surfaces on an existing site of 10,000 square feet or more of impervious surfaces. This includes commercial, industrial, residential, mixed-use, and public development projects on public or private land.

☐ Yes ☐ No

3. New development or redevelopment of a restaurant. Facilities that sell prepared foods and drinks for consumption, including stationary lunch counters and refreshment stands selling prepared foods and drinks for immediate consumption (SIC 5812), and where the land development creates and/or replace 5,000 square feet or more of impervious surface.

☐ Yes ☐ No

4. New development or redevelopment on a hillside. The project creates and/or replaces 5,000 square feet or more of impervious surface (collectively over the project site) and where the development will grade on any natural slope that is twenty-five percent or greater.

☐ Yes ☐ No

5. New development or redevelopment of a parking lot that creates and/or replaces 5,000 square feet or more of impervious surface (collectively over the project site).

☐ Yes ☐ No

6. New development or redevelopment of streets, roads, highways, freeways, and driveways. The project creates and/or replaces 5,000 square feet or more of impervious surface (collectively over the project site).

☐ Yes ☐ No

7. **New development or redevelopment discharging directly to an Environmentally Sensitive Area.** The project creates and/or replaces 2,500 square feet of impervious surface (collectively over project site), and discharges directly to an Environmentally Sensitive Area (ESA). "Discharging directly to" includes flow that is conveyed overland a distance of 200 feet or less from the project to the ESA, or conveyed in a pipe or open channel any distance as an isolated flow from the project to the ESA (i.e. not commingled with flows from adjacent lands). ☐ Yes ☐ No
8. **New development or redevelopment projects of a retail gasoline outlet (RGO) that create and/or replaces 5,000 square feet of impervious surface.** The development project meets the following criteria: (a) 5,000 square feet or more or (b) has a projected Average Daily Traffic (ADT) of 100 or more vehicles per day. ☐ Yes ☐ No
9. **New development or redevelopment projects of an automotive repair shops that creates and/or replaces 5,000 square feet or more of impervious surfaces.** Development projects categorized in any one of Standard Industrial Classification (SIC) codes 5013, 5014, 5541, 7532-7534, or 7536-7539. ☐ Yes ☐ No
10. **Other Pollutant Generating Project.** The project is not covered in the categories above, results in the disturbance of one or more acres of land and is expected to generate pollutants post construction, such as fertilizers and pesticides. This does not include projects creating less than 5,000 sf of impervious surface and where added landscaping does not require regular use of pesticides and fertilizers, such as slope stabilization using native plants. Calculation of the square footage of impervious surface need not include linear pathways that are for infrequent vehicle use, such as emergency maintenance access or bicycle pedestrian use, if they are built with pervious surfaces or if they sheet flow to surrounding pervious surfaces. ☐ Yes ☐ No

PART F: Select the appropriate category based on the outcomes of PART C through PART E.

1. The project is **NOT SUBJECT TO PERMANENT STORM WATER REQUIREMENTS.** ☐
2. The project is a **STANDARD DEVELOPMENT PROJECT.** Site design and source control BMP requirements apply. See the [Storm Water Standards Manual](#) for guidance. ☐
3. The project is **PDP EXEMPT.** Site design and source control BMP requirements apply. See the [Storm Water Standards Manual](#) for guidance. ☐
4. The project is a **PRIORITY DEVELOPMENT PROJECT.** Site design, source control, and structural pollutant control BMP requirements apply. See the [Storm Water Standards Manual](#) for guidance on determining if project requires a hydromodification plan management ☐

Name of Owner or Agent (Please Print)

Title

Signature

Date

Project Name:

THIS PAGE INTENTIONALLY LEFT BLANK FOR DOUBLE-SIDED PRINTING

Project Name:

Applicability of Permanent, Post-Construction Storm Water BMP Requirements		Form I-1
Project Identification		
Project Name:		
Permit Application Number:		Date:
Determination of Requirements		
<p>The purpose of this form is to identify permanent, post-construction requirements that apply to the project. This form serves as a short <u>summary</u> of applicable requirements, in some cases referencing separate forms that will serve as the backup for the determination of requirements.</p> <p>Answer each step below, starting with Step 1 and progressing through each step until reaching "Stop". Refer to the manual sections and/or separate forms referenced in each step below.</p>		
Step	Answer	Progression
Step 1: Is the project a "development project"? See Section 1.3 of the manual (Part 1 of Storm Water Standards) for guidance.	<input type="checkbox"/> Yes	Go to Step 2 .
	<input type="checkbox"/> No	Stop. Permanent BMP requirements do not apply. No SWQMP will be required. Provide discussion below.
Discussion / justification if the project is <u>not</u> a "development project" (e.g., the project includes <i>only</i> interior remodels within an existing building):		
Step 2: Is the project a Standard Project, PDP, or PDP Exempt? To answer this item, see Section 1.4 of the manual in its entirety for guidance AND complete Form DS-560, Storm Water Requirements Applicability Checklist.	<input type="checkbox"/> Standard Project	Stop. Standard Project requirements apply
	<input type="checkbox"/> PDP	PDP requirements apply, including PDP SWQMP. Go to Step 3 .
	PDP Exempt	Stop. Standard Project requirements apply. Provide discussion and list any additional requirements below.
Discussion / justification, and additional requirements for exceptions to PDP definitions, if applicable:		

Project Name:

Form I-1 Page 2 of 2		
Step	Answer	Progression
Step 3. Is the project subject to earlier PDP requirements due to a prior lawful approval? See Section 1.10 of the manual (Part 1 of Storm Water Standards) for guidance.	<input type="checkbox"/> Yes	Consult the City Engineer to determine requirements. Provide discussion and identify requirements below. Go to Step 4.
	<input type="checkbox"/> No	BMP Design Manual PDP requirements apply. Go to Step 4.
Discussion / justification of prior lawful approval, and identify requirements (<u>not required if prior lawful approval does not apply</u>):		
Step 4. Do hydromodification control requirements apply? See Section 1.6 of the manual (Part 1 of Storm Water Standards) for guidance.	<input type="checkbox"/> Yes	PDP structural BMPs required for pollutant control (Chapter 5) and hydromodification control (Chapter 6). Go to Step 5.
	<input type="checkbox"/> No	Stop. PDP structural BMPs required for pollutant control (Chapter 5) only. Provide brief discussion of exemption to hydromodification control below.
Discussion / justification if hydromodification control requirements do <u>not</u> apply:		
Step 5. Does protection of critical coarse sediment yield areas apply? See Section 6.2 of the manual (Part 1 of Storm Water Standards) for guidance.	<input type="checkbox"/> Yes	Management measures required for protection of critical coarse sediment yield areas (Chapter 6.2). Stop.
	<input type="checkbox"/> No	Management measures not required for protection of critical coarse sediment yield areas. Provide brief discussion below. Stop.
Discussion / justification if protection of critical coarse sediment yield areas does <u>not</u> apply:		

Project Name:

HMP Exemption Exhibit

Attach a HMP Exemption Exhibit that shows direct storm water runoff discharge from the project site to HMP exempt area. Include project area, applicable underground storm drain line and/or concrete lined channels, outfall information and exempt waterbody.
Reference applicable drawing number(s).

Exhibit must be provided on 11"x17" or larger paper.

Project Name:

THIS PAGE INTENTIONALLY LEFT BLANK FOR DOUBLE-SIDED PRINTING

Project Name:

Site Information Checklist For PDPs		Form I-3B
Project Summary Information		
Project Name		
Project Address		
Assessor's Parcel Number(s) (APN(s))		
Permit Application Number		
Project Watershed	Select One: <input type="checkbox"/> San Dieguito River <input type="checkbox"/> Penasquitos <input type="checkbox"/> Mission Bay <input type="checkbox"/> San Diego River <input type="checkbox"/> San Diego Bay <input type="checkbox"/> Tijuana River	
Hydrologic subarea name with Numeric Identifier up to two decimal places (9XX.XX)		
Project Area (total area of Assessor's Parcel(s) associated with the project or total area of the right-of-way)	_____ Acres (_____ Square Feet)	
Area to be disturbed by the project (Project Footprint)	_____ Acres (_____ Square Feet)	
Project Proposed Impervious Area (subset of Project Footprint)	_____ Acres (_____ Square Feet)	
Project Proposed Pervious Area (subset of Project Footprint)	_____ Acres (_____ Square Feet)	
Note: Proposed Impervious Area + Proposed Pervious Area = Area to be Disturbed by the Project. This may be less than the Project Area.		
The proposed increase or decrease in impervious area in the proposed condition as compared to the pre-project condition	_____ %	

Project Name:

Form I-3B Page 2 of 11
Description of Existing Site Condition and Drainage Patterns
<p>Current Status of the Site (select all that apply):</p> <ul style="list-style-type: none"><input type="checkbox"/> Existing development<input type="checkbox"/> Previously graded but not built out<input type="checkbox"/> Agricultural or other non-impervious use<input type="checkbox"/> Vacant, undeveloped/natural <p>Description / Additional Information:</p>
<p>Existing Land Cover Includes (select all that apply):</p> <ul style="list-style-type: none"><input type="checkbox"/> Vegetative Cover<input type="checkbox"/> Non-Vegetated Pervious Areas<input type="checkbox"/> Impervious Areas <p>Description / Additional Information:</p>
<p>Underlying Soil belongs to Hydrologic Soil Group (select all that apply):</p> <ul style="list-style-type: none"><input type="checkbox"/> NRCS Type A<input type="checkbox"/> NRCS Type B<input type="checkbox"/> NRCS Type C<input type="checkbox"/> NRCS Type D
<p>Approximate Depth to Groundwater:</p> <ul style="list-style-type: none"><input type="checkbox"/> Groundwater Depth < 5 feet<input type="checkbox"/> 5 feet < Groundwater Depth < 10 feet<input type="checkbox"/> 10 feet < Groundwater Depth < 20 feet<input type="checkbox"/> Groundwater Depth > 20 feet
<p>Existing Natural Hydrologic Features (select all that apply):</p> <ul style="list-style-type: none"><input type="checkbox"/> Watercourses<input type="checkbox"/> Seeps<input type="checkbox"/> Springs<input type="checkbox"/> Wetlands<input type="checkbox"/> None <p>Description / Additional Information:</p>

Project Name:

Form I-3B Page 4 of 11
Description of Proposed Site Development and Drainage Patterns
Project Description / Proposed Land Use and/or Activities:
List/describe proposed impervious features of the project (e.g., buildings, roadways, parking lots, courtyards, athletic courts, other impervious features):
List/describe proposed pervious features of the project (e.g., landscape areas):
Does the project include grading and changes to site topography? <input type="checkbox"/> Yes <input type="checkbox"/> No Description / Additional Information:

Project Name:

Form I-3B Page 5 of 11

Does the project include changes to site drainage (e.g., installation of new storm water conveyance systems)?

☐ Yes

☐ No

If yes, provide details regarding the proposed project site drainage conveyance network, including storm drains, concrete channels, swales, detention facilities, storm water treatment facilities, natural and constructed channels, and the method for conveying offsite flows through or around the proposed project site. Identify all discharge locations from the proposed project site along with a summary of the conveyance system size and capacity for each of the discharge locations. Provide a summary of pre and post-project drainage areas and design flows to each of the runoff discharge locations. Reference the drainage study for detailed calculations.

Description / Additional Information:

Project Name:

Form I-3B Page 3 of 11	
Description of Existing Site Topography and Drainage	
<p>How is storm water runoff conveyed from the site? At a minimum, this description should answer:</p> <ol style="list-style-type: none">1. Whether existing drainage conveyance is natural or urban;2. If runoff from offsite is conveyed through the site? If yes, quantification of all offsite drainage areas, design flows, and locations where offsite flows enter the project site and summarize how such flows are conveyed through the site;3. Provide details regarding existing project site drainage conveyance network, including storm drains, concrete channels, swales, detention facilities, storm water treatment facilities, and natural and constructed channels;4. Identify all discharge locations from the existing project along with a summary of the conveyance system size and capacity for each of the discharge locations. Provide summary of the pre-project drainage areas and design flows to each of the existing runoff discharge locations.	
Descriptions/Additional Information	
<div></div>	



Project Name:

Form I-3B Page 6 of 11

Identify whether any of the following features, activities, and/or pollutant source areas will be present (select all that apply):

- ☐ Onsite storm drain inlets
- ☐ Interior floor drains and elevator shaft sump pumps
- ☐ Interior parking garages
- ☐ Need for future indoor & structural pest control
- ☐ Landscape/outdoor pesticide use
- ☐ Pools, spas, ponds, decorative fountains, and other water features
- ☐ Food service
- ☐ Refuse areas
- ☐ Industrial processes
- ☐ Outdoor storage of equipment or materials
- ☐ Vehicle and equipment cleaning
- ☐ Vehicle/equipment repair and maintenance
- ☐ Fuel dispensing areas
- ☐ Loading docks
- ☐ Fire sprinkler test water
- ☐ Miscellaneous drain or wash water
- ☐ Plazas, sidewalks, and parking lots

Description/Additional Information:

Project Name:

Form I-3B Page 7 of 11
Identification and Narrative of Receiving Water
Narrative describing flow path from discharge location(s), through urban storm conveyance system, to receiving creeks, rivers, and lagoons and ultimate discharge location to Pacific Ocean (or bay, lagoon, lake or reservoir, as applicable)
Provide a summary of all beneficial uses of receiving waters downstream of the project discharge locations
Identify all ASBS (areas of special biological significance) receiving waters downstream of the project discharge locations
Provide distance from project outfall location to impaired or sensitive receiving waters
Summarize information regarding the proximity of the permanent, post-construction storm water BMPs to the City's Multi-Habitat Planning Area and environmentally sensitive lands

Project Name:

Form I-3B Page 8 of 11			
Identification of Receiving Water Pollutants of Concern			
List any 303(d) impaired water bodies within the path of storm water from the project site to the Pacific Ocean (or bay, lagoon, lake or reservoir, as applicable), identify the pollutant(s)/stressor(s) causing impairment, and identify any TMDLs and/or Highest Priority Pollutants from the WQIP for the impaired water bodies:			
303(d) Impaired Water Body (Refer to Appendix K)	Pollutant(s)/Stressor(s) (Refer to Appendix K)	TMDLs/WQIP Highest Priority Pollutant (Refer to Table 1-4 in Chapter 1)	
Identification of Project Site Pollutants*			
<p>*Identification of project site pollutants is only required if flow-thru treatment BMPs are implemented onsite in lieu of retention or biofiltration BMPs (note the project must also participate in an alternative compliance program unless prior lawful approval to meet earlier PDP requirements is demonstrated)</p> <p>Identify pollutants anticipated from the project site based on all proposed use(s) of the site (see Appendix B.6):</p>			
Pollutant	Not Applicable to the Project Site	Anticipated from the Project Site	Also a Receiving Water Pollutant of Concern
Sediment			
Nutrients			
Heavy Metals			
Organic Compounds			
Trash & Debris			
Oxygen Demanding Substances			
Oil & Grease			
Bacteria & Viruses			
Pesticides			

Project Name:

Form I-3B Page 9 of 11	
Hydromodification Management Requirements	
Do hydromodification management requirements apply (see Section 1.6)?	
<input type="checkbox"/>	Yes, hydromodification management flow control structural BMPs required.
<input type="checkbox"/>	No, the project will discharge runoff directly to existing underground storm drains discharging directly to water storage reservoirs, lakes, enclosed embayments, or the Pacific Ocean.
<input type="checkbox"/>	No, the project will discharge runoff directly to conveyance channels whose bed and bank are concrete-lined all the way from the point of discharge to water storage reservoirs, lakes, enclosed embayments, or the Pacific Ocean.
<input type="checkbox"/>	No, the project will discharge runoff directly to an area identified as appropriate for an exemption by the WMAA for the watershed in which the project resides.
Description / Additional Information (to be provided if a 'No' answer has been selected above):	
Note: If “No” answer has been selected the SWQMP must include an exhibit that shows the storm water conveyance system from the project site to an exempt water body. The exhibit should include details about the conveyance system and the outfall to the exempt water body.	
Critical Coarse Sediment Yield Areas*	
*This Section only required if hydromodification management requirements apply	
Based on Section 6.2 and Appendix H does CCSYA exist on the project footprint or in the upstream area draining through the project footprint?	
<input type="checkbox"/>	Yes
<input type="checkbox"/>	No
Discussion / Additional Information:	

Project Name:

Form I-3B Page 10 of 11
Flow Control for Post-Project Runoff* *This Section only required if hydromodification management requirements apply
List and describe point(s) of compliance (POCs) for flow control for hydromodification management (see Section 6.3.1). For each POC, provide a POC identification name or number correlating to the project's HMP Exhibit and a receiving channel identification name or number correlating to the project's HMP Exhibit.
Has a geomorphic assessment been performed for the receiving channel(s)? <input type="checkbox"/> No, the low flow threshold is $0.1Q_2$ (default low flow threshold) <input type="checkbox"/> Yes, the result is the low flow threshold is $0.1Q_2$ <input type="checkbox"/> Yes, the result is the low flow threshold is $0.3Q_2$ <input type="checkbox"/> Yes, the result is the low flow threshold is $0.5Q_2$ If a geomorphic assessment has been performed, provide title, date, and preparer:
Discussion / Additional Information: (optional)

Project Name:

Form I-3B Page 11 of 11
Other Site Requirements and Constraints
<p>When applicable, list other site requirements or constraints that will influence storm water management design, such as zoning requirements including setbacks and open space, or local codes governing minimum street width, sidewalk construction, allowable pavement types, and drainage requirements.</p>
Optional Additional Information or Continuation of Previous Sections As Needed
<p>This space provided for additional information or continuation of information from previous sections as needed.</p>

Project Name:

Source Control BMP Checklist for PDPs		Form I-4B	
Source Control BMPs			
All development projects must implement source control BMPs where applicable and feasible. See Chapter 4 and Appendix E of the BMP Design Manual (Part 1 of the Storm Water Standards) for information to implement source control BMPs shown in this checklist.			
Answer each category below pursuant to the following.			
<ul style="list-style-type: none"> • "Yes" means the project will implement the source control BMP as described in Chapter 4 and/or Appendix E of the BMP Design Manual. Discussion / justification is not required. • "No" means the BMP is applicable to the project but it is not feasible to implement. Discussion / justification must be provided. • "N/A" means the BMP is not applicable at the project site because the project does not include the feature that is addressed by the BMP (e.g., the project has no outdoor materials storage areas). Discussion / justification may be provided. 			
Source Control Requirement		Applied?	
4.2.1 Prevention of Illicit Discharges into the MS4	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.2.1 not implemented:			
4.2.2 Storm Drain Stenciling or Signage	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.2.2 not implemented:			
4.2.3 Protect Outdoor Materials Storage Areas from Rainfall, Run-On, Runoff, and Wind Dispersal	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.2.3 not implemented:			
4.2.4 Protect Materials Stored in Outdoor Work Areas from Rainfall, Run-On, Runoff, and Wind Dispersal	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.2.4 not implemented:			
4.2.5 Protect Trash Storage Areas from Rainfall, Run-On, Runoff, and Wind Dispersal	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.2.5 not implemented:			

Project Name:

Form I-4B Page 2 of 2			
Source Control Requirement	Applied?		
4.2.6 Additional BMPs Based on Potential Sources of Runoff Pollutants (must answer for each source listed below)			
On-site storm drain inlets	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Interior floor drains and elevator shaft sump pumps	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Interior parking garages	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Need for future indoor & structural pest control	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Landscape/Outdoor Pesticide Use	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Pools, spas, ponds, decorative fountains, and other water features	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Food service	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Refuse areas	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Industrial processes	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Outdoor storage of equipment or materials	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Vehicle/Equipment Repair and Maintenance	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Fuel Dispensing Areas	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Loading Docks	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Fire Sprinkler Test Water	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Miscellaneous Drain or Wash Water	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Plazas, sidewalks, and parking lots	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
SC-6A: Large Trash Generating Facilities	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
SC-6B: Animal Facilities	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
SC-6C: Plant Nurseries and Garden Centers	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
SC-6D: Automotive Facilities	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.2.6 not implemented. Clearly identify which sources of runoff pollutants are discussed. Justification must be provided for <u>all</u> "No" answers shown above.			

Project Name:

Site Design BMP Checklist for PDPs		Form I-5B	
Site Design BMPs			
<p>All development projects must implement site design BMPs where applicable and feasible. See Chapter 4 and Appendix E of the BMP Design Manual (Part 1 of Storm Water Standards) for information to implement site design BMPs shown in this checklist.</p> <p>Answer each category below pursuant to the following.</p> <ul style="list-style-type: none"> • "Yes" means the project will implement the site design BMP as described in Chapter 4 and/or Appendix E of the BMP Design Manual. Discussion / justification is not required. • "No" means the BMP is applicable to the project but it is not feasible to implement. Discussion / justification must be provided. • "N/A" means the BMP is not applicable at the project site because the project does not include the feature that is addressed by the BMP (e.g., the project site has no existing natural areas to conserve). Discussion / justification may be provided. <p>A site map with implemented site design BMPs must be included at the end of this checklist.</p>			
Site Design Requirement		Applied?	
4.3.1 Maintain Natural Drainage Pathways and Hydrologic Features		<input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> N/A
Discussion / justification if 4.3.1 not implemented:			
1-1 Are existing natural drainage pathways and hydrologic features mapped on the site map?		<input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> N/A
1-2 Are trees implemented? If yes, are they shown on the site map?		<input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> N/A
1-3 Implemented trees meet the design criteria in 4.3.1 Fact Sheet (e.g. soil volume, maximum credit, etc.)?		<input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> N/A
1-4 Is tree credit volume calculated using Appendix B.2.2.1 and SD-1 Fact Sheet in Appendix E?		<input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> N/A
4.3.2 Have natural areas, soils and vegetation been conserved?		<input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> N/A
Discussion / justification if 4.3.2 not implemented:			

Project Name:

Form I-5B Page 2 of 4			
Site Design Requirement	Applied?		
4.3.3 Minimize Impervious Area	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.3.3 not implemented:			
4.3.4 Minimize Soil Compaction	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.3.4 not implemented:			
4.3.5 Impervious Area Dispersion	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.3.5 not implemented:			
5-1 Is the pervious area receiving runoff from impervious area identified on the site map?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
5-2 Does the pervious area satisfy the design criteria in 4.3.5 Fact Sheet in Appendix E (e.g. maximum slope, minimum length, etc.)	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
5-3 Is impervious area dispersion credit volume calculated using Appendix B.2.1.1 and 4.3.5 Fact Sheet in Appendix E?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A

Project Name:

Form I-5B Page 3 of 4			
Site Design Requirement	Applied?		
4.3.6 Runoff Collection	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.3.6 not implemented:			
6a-1 Are green roofs implemented in accordance with design criteria in 4.3.6A Fact Sheet? If yes, are they shown on the site map?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
6a-2 Is the green roof credit volume calculated using Appendix B.2.1.2 and 4.3.6A Fact Sheet in Appendix E?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
6b-1 Are permeable pavements implemented in accordance with design criteria in 4.3.6B Fact Sheet? If yes, are they shown on the site map?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
6b-2 Is the permeable pavement credit volume calculated using Appendix B.2.1.3 and 4.3.6B Fact Sheet in Appendix E?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
4.3.7 Landscaping with Native or Drought Tolerant Species	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.3.7 not implemented:			
4.3.8 Harvest and Use Precipitation	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.3.8 not implemented:			
8-1 Are rain barrels implemented in accordance with design criteria in 4.3.8 Fact Sheet? If yes, are they shown on the site map?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
8-2 Is the rain barrel credit volume calculated using Appendix B.2.2.2 and 4.3.8 Fact Sheet in Appendix E?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A

Project Name:

Form I-5B Page 4 of 4

Insert Site Map with all site design BMPs identified:

Refer to the DMA Map for the site design BMPs.

Project Name:

Summary of PDP Structural BMPs	Form I-6
PDP Structural BMPs	
<p>All PDPs must implement structural BMPs for storm water pollutant control (see Chapter 5 of the BMP Design Manual, Part 1 of Storm Water Standards). Selection of PDP structural BMPs for storm water pollutant control must be based on the selection process described in Chapter 5. PDPs subject to hydromodification management requirements must also implement structural BMPs for flow control for hydromodification management (see Chapter 6 of the BMP Design Manual). Both storm water pollutant control and flow control for hydromodification management can be achieved within the same structural BMP(s).</p> <p>PDP structural BMPs must be verified by the City at the completion of construction. This includes requiring the project owner or project owner's representative to certify construction of the structural BMPs (complete Form DS-563). PDP structural BMPs must be maintained into perpetuity (see Chapter 7 of the BMP Design Manual).</p> <p>Use this form to provide narrative description of the general strategy for structural BMP implementation at the project site in the box below. Then complete the PDP structural BMP summary information sheet (page 3 of this form) for each structural BMP within the project (copy the BMP summary information page as many times as needed to provide summary information for each individual structural BMP).</p> <p>Describe the general strategy for structural BMP implementation at the site. This information must describe how the steps for selecting and designing storm water pollutant control BMPs presented in Section 5.1 of the BMP Design Manual were followed, and the results (type of BMPs selected). For projects requiring hydromodification flow control BMPs, indicate whether pollutant control and flow control BMPs are integrated or separate.</p> <p>(Continue on page 2 as necessary.)</p>	

Project Name:

Form I-6 Page 2 of

(Continued from page 1)

Project Name:

Form I-6 Page of (Copy as many as needed)	
Structural BMP Summary Information	
Structural BMP ID No.	
Construction Plan Sheet No.	
Type of Structural BMP: <input type="checkbox"/> Retention by harvest and use (e.g. HU-1, cistern) <input type="checkbox"/> Retention by infiltration basin (INF-1) <input type="checkbox"/> Retention by bioretention (INF-2) <input type="checkbox"/> Retention by permeable pavement (INF-3) <input type="checkbox"/> Partial retention by biofiltration with partial retention (PR-1) <input type="checkbox"/> Biofiltration (BF-1) <input type="checkbox"/> Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (provide BMP type/description in discussion section below) <input type="checkbox"/> Flow-thru treatment control included as pre-treatment/forebay for an onsite retention or biofiltration BMP (provide BMP type/description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) <input type="checkbox"/> Flow-thru treatment control with alternative compliance (provide BMP type/description in discussion section below) <input type="checkbox"/> Detention pond or vault for hydromodification management <input type="checkbox"/> Other (describe in discussion section below)	
Purpose: <input type="checkbox"/> Pollutant control only <input type="checkbox"/> Hydromodification control only <input type="checkbox"/> Combined pollutant control and hydromodification control <input type="checkbox"/> Pre-treatment/forebay for another structural BMP <input type="checkbox"/> Other (describe in discussion section below)	
Who will certify construction of this BMP? Provide name and contact information for the party responsible to sign BMP verification form DS-563	
Who will be the final owner of this BMP?	
Who will maintain this BMP into perpetuity?	
What is the funding mechanism for maintenance?	

Project Name:

Form I-6 Page of (Copy as many as needed)
Structural BMP ID No.
Construction Plan Sheet No.
Discussion (as needed; must include worksheets showing BMP sizing calculations in the SWQMPs):

Project Name:

Attachment 1

Backup For PDP Pollutant Control BMPs

This is the cover sheet for Attachment 1.

Project Name:

Indicate which Items are Included:

Attachment Sequence	Contents	Checklist
Attachment 1a	DMA Exhibit (Required) See DMA Exhibit Checklist.	<input type="checkbox"/> Included Refer to Lumina SWQMP (PTS # 555609)
Attachment 1b	Tabular Summary of DMAs Showing DMA ID matching DMA Exhibit, DMA Area, and DMA Type (Required)* *Provide table in this Attachment OR on DMA Exhibit in Attachment 1a	<input type="checkbox"/> Included on DMA Exhibit in Attachment 1a <input type="checkbox"/> Included as Attachment 1b, separate from DMA Exhibit
Attachment 1c	Form I-7, Harvest and Use Feasibility Screening Checklist (Required unless the entire project will use infiltration BMPs) Refer to Appendix B.3-1 of the BMP Design Manual to complete Form I-7.	<input type="checkbox"/> Included Refer to Lumina SWQMP (PTS # 555609) <input type="checkbox"/> Not included because the entire project will use infiltration BMPs
Attachment 1d	Infiltration Feasibility Information. Contents of Attachment 1d depend on the infiltration condition: <ul style="list-style-type: none"> • No Infiltration Condition: <ul style="list-style-type: none"> ◦ Infiltration Feasibility Condition Letter (<i>Note: must be stamped and signed by licensed geotechnical engineer</i>) ◦ Form I-8A (optional) ◦ Form I-8B (optional) • Partial Infiltration Condition: <ul style="list-style-type: none"> ◦ Infiltration Feasibility Condition Letter (<i>Note: must be stamped and signed by licensed geotechnical engineer</i>) ◦ Form I-8A ◦ Form I-8B • Full Infiltration Condition: <ul style="list-style-type: none"> ◦ Form I-8A ◦ Form I-8B ◦ Worksheet C.4-3 ◦ Form I-9 Refer to Appendices C and D of the BMP Design Manual for guidance.	Refer to Lumina SWQMP (PTS # 555609) <input type="checkbox"/> Included <input type="checkbox"/> Not included because the entire project will use harvest and use BMPs
Attachment 1e	Pollutant Control BMP Design Worksheets / Calculations (Required) Refer to Appendices B and E of the BMP Design Manual for structural pollutant control BMP design guidelines and site design credit calculations	<input type="checkbox"/> Included Refer to Lumina SWQMP (PTS # 555609)

Project Name:

Attachment 2

Backup for PDP Hydromodification Control Measures

This is the cover sheet for Attachment 2.

☐ Mark this box if this attachment is empty because the project is exempt from PDP hydromodification management requirements.

Refer to Lumina SWQMP (PTS # 555609)

Project Name:

Indicate which Items are Included:

Attachment Sequence	Contents	Checklist
Attachment 2a	Hydromodification Management Exhibit (Required)	<input type="checkbox"/> Included See Hydromodification Management Exhibit Checklist.
Attachment 2b	<p>Management of Critical Coarse Sediment Yield Areas (WMAA Exhibit is required, additional analyses are optional)</p> <p>See Section 6.2 of the BMP Design Manual.</p>	<p><input type="checkbox"/> Exhibit showing project drainage boundaries marked on WMAA Critical Coarse Sediment Yield Area Map (Required)</p> <p>Optional analyses for Critical Coarse Sediment Yield Area Determination</p> <p><input type="checkbox"/> 6.2.1 Verification of Geomorphic Landscape Units Onsite</p> <p><input type="checkbox"/> 6.2.2 Downstream Systems Sensitivity to Coarse Sediment</p> <p><input type="checkbox"/> 6.2.3 Optional Additional Analysis of Potential Critical Coarse Sediment Yield Areas Onsite</p>
Attachment 2c	<p>Geomorphic Assessment of Receiving Channels (Optional)</p> <p>See Section 6.3.4 of the BMP Design Manual.</p>	<p><input type="checkbox"/> Not Performed</p> <p><input type="checkbox"/> Included</p> <p><input type="checkbox"/> Submitted as separate stand-alone document</p>
Attachment 2d	<p>Flow Control Facility Design and Structural BMP Drawdown Calculations (Required)</p> <p>Overflow Design Summary for each structural BMP</p> <p>See Chapter 6 and Appendix G of the BMP Design Manual</p>	<p><input type="checkbox"/> Included</p> <p><input type="checkbox"/> Submitted as separate stand-alone document</p>

Project Name:

Use this checklist to ensure the required information has been included on the Hydromodification Management Exhibit:

The Hydromodification Management Exhibit must identify:

- ☐ Underlying hydrologic soil group
- ☐ Approximate depth to groundwater
- ☐ Existing natural hydrologic features (watercourses, seeps, springs, wetlands)
- ☐ Critical coarse sediment yield areas to be protected OR provide a separate map showing that the project site is outside of any critical coarse sediment yield areas
- ☐ Existing topography
- ☐ Existing and proposed site drainage network and connections to drainage offsite
- ☐ Proposed grading
- ☐ Proposed impervious features
- ☐ Proposed design features and surface treatments used to minimize imperviousness
- ☐ Point(s) of Compliance (POC) for Hydromodification Management
Existing and proposed drainage boundary and drainage area to each POC (when necessary, create separate exhibits for pre-development and post-project conditions)
- ☐ Structural BMPs for hydromodification management (identify location, type of BMP, and size/detail).

Project Name:

Attachment 3 Structural BMP Maintenance Information

This is the cover sheet for Attachment 3.

Refer to Lumina SWQMP (PTS # 555609)

Project Name:

Indicate which Items are Included:

Attachment Sequence	Contents	Checklist
Attachment 3	Maintenance Agreement (Form DS-3247) (when applicable)	<input type="checkbox"/> Included <input type="checkbox"/> Not applicable

Project Name:

Use this checklist to ensure the required information has been included in the Structural BMP Maintenance Information Attachment:

Attachment 3: For private entity operation and maintenance, Attachment 3 must include a Storm Water Management and Discharge Control Maintenance Agreement (Form DS-3247). The following information must be included in the exhibits attached to the maintenance agreement:

- ☐ Vicinity map
- ☐ Site design BMPs for which DCV reduction is claimed for meeting the pollutant control obligations.
- ☐ BMP and HMP location and dimensions
- ☐ BMP and HMP specifications/cross section/model
- ☐ Maintenance recommendations and frequency
- ☐ LID features such as (permeable paver and LS location, dim, SF).

Project Name:

Attachment 4

Copy of Plan Sheets Showing Permanent Storm Water BMPs

This is the cover sheet for Attachment 4.

Refer to Lumina SWQMP (PTS # 555609)

Project Name:

Use this checklist to ensure the required information has been included on the plans:

The plans must identify:

- ☐ Structural BMP(s) with ID numbers matching Form I-6 Summary of PDP Structural BMPs
- ☐ The grading and drainage design shown on the plans must be consistent with the delineation of DMAs shown on the DMA exhibit
- ☐ Details and specifications for construction of structural BMP(s)
- ☐ Signage indicating the location and boundary of structural BMP(s) as required by the City Engineer
- ☐ How to access the structural BMP(s) to inspect and perform maintenance
- ☐ Features that are provided to facilitate inspection (e.g., observation ports, cleanouts, silt posts, or other features that allow the inspector to view necessary components of the structural BMP and compare to maintenance thresholds)
- ☐ Manufacturer and part number for proprietary parts of structural BMP(s) when applicable
- ☐ Maintenance thresholds specific to the structural BMP(s), with a location-specific frame of reference (e.g., level of accumulated materials that triggers removal of the materials, to be identified based on viewing marks on silt posts or measured with a survey rod with respect to a fixed benchmark within the BMP)
- ☐ Recommended equipment to perform maintenance
- ☐ When applicable, necessary special training or certification requirements for inspection and maintenance personnel such as confined space entry or hazardous waste management
- ☐ Include landscaping plan sheets showing vegetation requirements for vegetated structural BMP(s)
- ☐ All BMPs must be fully dimensioned on the plans
- ☐ When proprietary BMPs are used, site specific cross section with outflow, inflow and model number shall be provided. Broucher photocopies are not allowed.

Project Name:

Attachment 5

Drainage Report

Attach project's drainage report. Refer to Drainage Design Manual to determine the reporting requirements.

PRELIMINARY DRAINAGE REPORT
LUMINA III (PTS# _____)
CITY OF SAN DIEGO, CA
September 23rd, 2019

Prepared For:

COLRICH
444 West Beech Street, Suite 300
San Diego, CA 92101

Prepared By:




PROJECT DESIGN CONSULTANTS

Planning | Landscape Architecture | Engineering | Survey

701 B Street, Suite 800
San Diego, CA 92101
619.235.6471 Tel
619.234.0349 Fax

PDC Job No. 2357.60



Prepared by: J.Novoa, E.I.T.
Under the supervision of

Chelisa Pack, PE RCE 71026
Registration Expires 6/30/21

TABLE OF CONTENTS

1.	INTRODUCTION	1
2.	PROJECT BACKGROUND & RELATION TO PREVIOUS STUDIES	2
3.	EXISTING AND PROPOSED DRAINAGE PATTERNS AND IMPROVEMENTS.....	3
3.1	Existing Drainage Patterns.....	3
3.2	Proposed Drainage Improvements	3
4.	HYDROLOGY CRITERIA, METHODOLOGY, AND RESULTS.....	3
5.	CONCLUSION.....	4

APPENDICES

1	Proposed Hydrologic Calculations CIVILD
2	Preliminary Detention Calculations
3	Drainage Exhibit

1. INTRODUCTION

This report describes the proposed storm water drainage improvements for the Lumina III entitlement submittal. The Lumina III project is owned by Colrich, and represents a portion of the Otay Mesa Central Village Specific Plan (CVSP) area. The TM development proposes development consistent with the land use designations of the approved Specific Plan. The overall drainage criteria for the project was identified in the technical report for the Specific Plan, entitled *Preliminary Drainage and Water Quality Summary for the Otay Mesa Central Village Specific Plan* (PTS 408329), which was prepared by Project Design Consultants and is dated January 22, 2016. Subsequent to the development of the Specific Plan report, Project Design Consultants prepared a Tentative Map for the Lumina Project (PTS# 555609) and the project-level drainage study for the Lumina project is dated August 15, 2018. At the time of the development of the Lumina TM, the Lopez property which is now known as the “Lumina III Project” was not owned by Colrich, but was subsequently acquired. Therefore, this subsequent entitlement is for the Lumina III property, which eventually will be developed as part of the overall Lumina project site plan, but a separate entitlement is required. The project is located South of the 905 highway along Cactus Road and northwest of the Siempre Viva intersection. See Figure 1 for a Vicinity Map.




Figure 1: Vicinity Map

2. PROJECT BACKGROUND & RELATION TO PREVIOUS STUDIES

The project site was previously included in the drainage area evaluated in the preliminary Lumina Drainage Study (PTS #555609) because the Lumina project surrounded the Lumina III parcel and therefore incorporated the runoff into the overall study. The Lumina III parcel was modeled in the previous study with a runoff coefficient for a rural site. Therefore, this is updated in this report to display the ultimate condition of a multi unit site. This Lumina III report, as a supplemental document to the approved TM Lumina Preliminary Drainage Study, shows that this Lumina III project is in compliance with the drainage criteria and will be incorporated into the overall Lumina site plan and project.

3. EXISTING AND PROPOSED DRAINAGE PATTERNS AND IMPROVEMENTS

The following sections provide descriptions of the existing and proposed drainage patterns and improvements for the project.

3.1 Existing Drainage Patterns

The site currently has a single family home in the south and a wood shed on the northeastern edge of the project. The rest of the site consists of dirt, shrubs, and trees. Topography within the project site is characterized by mostly gently sloping areas. There are currently minimal drainage improvements within the project boundary. The site drains to the south across the property boundary into the Lumina property, which is also owned by Colrich. From an overall perspective, the site drains to the south to a steep finger canyon (Wruck Creek) located to the west of the existing Cactus Road/Siempre Viva Road intersection. Two of the finger canyons drain to sump areas that are collected and drained to the west and discharged downstream within the canyon via an existing RCP storm drain per City Drawing 23871-21-D.

3.2 Proposed Drainage Improvements

The proposed drainage patterns and drainage improvements have been designed to mimic existing drainage patterns. All proposed drainage improvements from the Lumina III project can be found within the Lumina Preliminary Drainage Study (PTS#555609) and will be further refined during final engineering. The Lumina III project was previously modeled in Lumina TM Drainage Study using the rural runoff coefficient. This report includes an update to that analysis with the ultimate condition using the multi-unit runoff coefficient. The drainage improvements for the proposed Lumina III project will drain into the storm drain improvements for the Lumina project, and the drainage will be detained in the proposed Lumina South Basin.

4. HYDROLOGY CRITERIA, METHODOLOGY, AND RESULTS

The hydrologic analysis was performed for the overall Lumina site and can be found in the approved Lumina Drainage Study (PTS#555609), which is included in this submittal for reference. For the Lumina III project, the land use coefficient for the Lopez property was

updated and updated hydrology is included in the appendix. The increase overall from the original Lumina Study and the change in land use with Lumina III increased the 100-year flow by 0.6 cfs from 151.6 cfs to 152.2 cfs which can be seen in the table below.

	EXISTING CONDITIONS			PROPOSED CONDITIONS		
<u>Outfall of Interest</u>	<u>System</u>	<u>Q₁₀₀ (cfs)</u>	<u>Contrib. Area (acres)</u>	<u>System</u>	<u>Q₁₀₀ (cfs)</u>	<u>Contrib. Area (acres)</u>
North	System 300	37.7	30.1	System 3000	3.9	0.9
	System 500	11.7	7.7	System 4000	105.6 undetained 13.4 detained*	33.9
				System 5000	4.0	1.9
	Subtotal:	49.4	37.8	Subtotal:	49.4	36.7
South(Outfall for Lumina III flows)	System 100	28.4	20.7	System 1000	152.2 undetained 36.7 detained*	63.4
	System 200	54.0	49.3	System 2000	10.2	8.2
	Subtotal:	82.4	70.0	Subtotal:	46.7	71.6
	Total:	131.8	107.8	Total:	≤ 131.8	108.3

Note: *Detained flow rates are based on the preliminary detention calculations. Final detention calculations will be prepared during final engineering.

With the detention updated the overall proposed conditions is still less than the proposed conditions.

5. CONCLUSION

The proposed project development complies with detention criteria outlined in previous studies, and therefore, should not adversely affect downstream drainage conditions. The storm drain infrastructure in the Lumina Drainage Study (PTS#555609) will be adequate to convey the

design flows and will be addressed regionally for both the Lumina and Lumina III projects. The storm drain detention facilities are designed as combined facilities for hydromodification and water quality purposes in addition to peak flow detention.

APPENDIX 1

Proposed Hydrologic Calculations CIVILD

San Diego County Rational Hydrology Program
CIVILCADD/CIVILDESIGN Engineering Software,(c)1991-2003 Version 6.3

Rational method hydrology program based on
San Diego County Flood Control Division 1985 hydrology manual
Rational Hydrology Study Date: 08/08/19

2357.60 LUMINA III
PROPOSED CONDITIONS
SYSTEM 100, FILE: 1000P100

***** Hydrology Study Control Information *****

Program License Serial Number 4049

Rational hydrology study storm event year is 100.0
English (in-lb) input data Units used
English (in) rainfall data used

Standard intensity of Appendix I-B used for year and
Elevation 0 - 1500 feet
Factor (to multiply * intensity) = 1.000
Only used if inside City of San Diego
San Diego hydrology manual 'C' values used
Runoff coefficients by rational method

Process from Point/Station 1000.000 to Point/Station 1001.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Initial subarea flow distance = 343.000(Ft.)
Highest elevation = 497.900(Ft.)
Lowest elevation = 492.100(Ft.)
Elevation difference = 5.800(Ft.)
Time of concentration calculated by the urban
areas overland flow method (App X-C) = 4.20 min.
 $TC = [1.8 * (1.1 - C) * distance(Ft.)^{.5}] / (\% slope^{(1/3)})]$
 $TC = [1.8 * (1.1 - 0.9500) * (343.000^{.5}) / (1.691^{(1/3)})] = 4.20$
Setting time of concentration to 5 minutes
Rainfall intensity (I) = 4.389(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.950
Subarea runoff = 1.209(CFS)
Total initial stream area = 0.290(Ac.)

Process from Point/Station 1001.000 to Point/Station 1003.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 488.500(Ft.)
Downstream point/station elevation = 488.300(Ft.)
Pipe length = 18.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 1.209(CFS)
Nearest computed pipe diameter = 9.00(In.)
Calculated individual pipe flow = 1.209(CFS)
Normal flow depth in pipe = 5.51(In.)
Flow top width inside pipe = 8.77(In.)
Critical Depth = 6.07(In.)
Pipe flow velocity = 4.26(Ft/s)
Travel time through pipe = 0.07 min.
Time of concentration (TC) = 5.07 min.

Process from Point/Station 1002.000 to Point/Station 1003.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 5.07 min.
Rainfall intensity = 4.364(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 2.073(CFS) for 0.500(Ac.)
Total runoff = 3.282(CFS) Total area = 0.79(Ac.)

Process from Point/Station 1003.000 to Point/Station 1007.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 488.300(Ft.)
Downstream point/station elevation = 483.100(Ft.)
Pipe length = 411.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 3.282(CFS)
Nearest computed pipe diameter = 12.00(In.)
Calculated individual pipe flow = 3.282(CFS)
Normal flow depth in pipe = 8.26(In.)
Flow top width inside pipe = 11.11(In.)
Critical Depth = 9.31(In.)
Pipe flow velocity = 5.69(Ft/s)
Travel time through pipe = 1.20 min.
Time of concentration (TC) = 6.27 min.

Process from Point/Station 1003.000 to Point/Station 1007.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 1
Stream flow area = 0.790(Ac.)
Runoff from this stream = 3.282(CFS)
Time of concentration = 6.27 min.
Rainfall intensity = 4.011(In/Hr)

Process from Point/Station 1004.000 to Point/Station 1005.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[MULTI - UNITS area type]
Initial subarea flow distance = 80.000(Ft.)
Highest elevation = 502.500(Ft.)
Lowest elevation = 501.700(Ft.)
Elevation difference = 0.800(Ft.)
Time of concentration calculated by the urban
areas overland flow method (App X-C) = 6.44 min.
 $TC = [1.8 * (1.1 - C) * distance(Ft.)^{.5}] / (\% slope^{(1/3)})]$
 $TC = [1.8 * (1.1 - 0.7000) * (80.000^{.5})] / (1.000^{(1/3)}) = 6.44$
Rainfall intensity (I) = 3.970(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.700
Subarea runoff = 1.195(CFS)
Total initial stream area = 0.430(Ac.)

Process from Point/Station 1005.000 to Point/Station 1006.000
**** IMPROVED CHANNEL TRAVEL TIME ****

Upstream point elevation = 501.700(Ft.)
Downstream point elevation = 496.500(Ft.)
Channel length thru subarea = 532.000(Ft.)
Channel base width = 2.000(Ft.)
Slope or 'Z' of left channel bank = 2.000
Slope or 'Z' of right channel bank = 2.000
Estimated mean flow rate at midpoint of channel = 8.421(CFS)
Manning's 'N' = 0.015
Maximum depth of channel = 2.000(Ft.)
Flow(q) thru subarea = 8.421(CFS)
Depth of flow = 0.537(Ft.), Average velocity = 5.096(Ft/s)
Channel flow top width = 4.150(Ft.)
Flow Velocity = 5.10(Ft/s)
Travel time = 1.74 min.
Time of concentration = 8.18 min.
Critical depth = 0.656(Ft.)
Adding area flow to channel
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[MULTI - UNITS area type]
Rainfall intensity = 3.630(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.700
Subarea runoff = 13.213(CFS) for 5.200(Ac.)
Total runoff = 14.408(CFS) Total area = 5.63(Ac.)

Process from Point/Station 1006.000 to Point/Station 1009.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 483.700(Ft.)
Downstream point/station elevation = 483.400(Ft.)
Pipe length = 31.00(Ft.) Manning's N = 0.013

No. of pipes = 1 Required pipe flow = 14.408(CFS)
Nearest computed pipe diameter = 21.00(In.)
Calculated individual pipe flow = 14.408(CFS)
Normal flow depth in pipe = 15.94(In.)
Flow top width inside pipe = 17.96(In.)
Critical Depth = 16.91(In.)
Pipe flow velocity = 7.36(Ft/s)
Travel time through pipe = 0.07 min.
Time of concentration (TC) = 8.25 min.

Process from Point/Station 1009.000 to Point/Station 1009.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 8.25 min.
Rainfall intensity = 3.619(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 2.750(CFS) for 0.800(Ac.)
Total runoff = 17.158(CFS) Total area = 6.43(Ac.)

Process from Point/Station 1009.000 to Point/Station 1007.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 483.300(Ft.)
Downstream point/station elevation = 483.100(Ft.)
Pipe length = 22.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 17.158(CFS)
Nearest computed pipe diameter = 24.00(In.)
Calculated individual pipe flow = 17.158(CFS)
Normal flow depth in pipe = 16.17(In.)
Flow top width inside pipe = 22.50(In.)
Critical Depth = 17.91(In.)
Pipe flow velocity = 7.62(Ft/s)
Travel time through pipe = 0.05 min.
Time of concentration (TC) = 8.30 min.

Process from Point/Station 1008.000 to Point/Station 1007.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 8.30 min.
Rainfall intensity = 3.611(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 2.813(CFS) for 0.820(Ac.)
Total runoff = 19.971(CFS) Total area = 7.25(Ac.)

Process from Point/Station 1008.000 to Point/Station 1007.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 2
Stream flow area = 7.250(Ac.)
Runoff from this stream = 19.971(CFS)
Time of concentration = 8.30 min.
Rainfall intensity = 3.611(In/Hr)
Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
------------	-----------------	----------	----------------------------

1	3.282	6.27	4.011
2	19.971	8.30	3.611

Qmax(1) =
1.000 * 1.000 * 3.282) +
1.000 * 0.756 * 19.971) + = 18.381

Qmax(2) =
0.900 * 1.000 * 3.282) +
1.000 * 1.000 * 19.971) + = 22.926

Total of 2 streams to confluence:

Flow rates before confluence point:
3.282 19.971

Maximum flow rates at confluence using above data:
18.381 22.926

Area of streams before confluence:
0.790 7.250

Results of confluence:

Total flow rate = 22.926(CFS)
Time of concentration = 8.298 min.
Effective stream area after confluence = 8.040(Ac.)

Process from Point/Station 1007.000 to Point/Station 1027.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 483.100(Ft.)
Downstream point/station elevation = 481.450(Ft.)
Pipe length = 109.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 22.926(CFS)
Nearest computed pipe diameter = 24.00(In.)
Calculated individual pipe flow = 22.926(CFS)
Normal flow depth in pipe = 16.59(In.)
Flow top width inside pipe = 22.17(In.)
Critical Depth = 20.46(In.)
Pipe flow velocity = 9.89(Ft/s)
Travel time through pipe = 0.18 min.
Time of concentration (TC) = 8.48 min.

Process from Point/Station 1007.000 to Point/Station 1027.000
**** CONFLUENCE OF MAIN STREAMS ****

The following data inside Main Stream is listed:
In Main Stream number: 1

Stream flow area = 8.040(Ac.)
Runoff from this stream = 22.926(CFS)
Time of concentration = 8.48 min.
Rainfall intensity = 3.582(In/Hr)
Program is now starting with Main Stream No. 2

Process from Point/Station 1010.000 to Point/Station 1011.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Initial subarea flow distance = 120.000(Ft.)
Highest elevation = 515.000(Ft.)
Lowest elevation = 513.100(Ft.)
Elevation difference = 1.900(Ft.)
Time of concentration calculated by the urban
areas overland flow method (App X-C) = 2.54 min.
TC = [1.8*(1.1-C)*distance(Ft.)^0.5]/(% slope^(1/3))
TC = [1.8*(1.1-0.9500)*(120.000^0.5)/(1.583^(1/3))]= 2.54
Setting time of concentration to 5 minutes
Rainfall intensity (I) = 4.389(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.950
Subarea runoff = 0.792(CFS)
Total initial stream area = 0.190(Ac.)

Process from Point/Station 1011.000 to Point/Station 1013.000
**** STREET FLOW TRAVEL TIME + SUBAREA FLOW ADDITION ****

Top of street segment elevation = 513.100(Ft.)
End of street segment elevation = 495.400(Ft.)
Length of street segment = 772.000(Ft.)
Height of curb above gutter flowline = 6.0(In.)
Width of half street (curb to crown) = 23.000(Ft.)
Distance from crown to crossfall grade break = 18.000(Ft.)
Slope from gutter to grade break (v/hz) = 0.020
Slope from grade break to crown (v/hz) = 0.020
Street flow is on [1] side(s) of the street
Distance from curb to property line = 12.000(Ft.)
Slope from curb to property line (v/hz) = 0.020
Gutter width = 1.500(Ft.)
Gutter hike from flowline = 1.500(In.)
Manning's N in gutter = 0.0150
Manning's N from gutter to grade break = 0.0150
Manning's N from grade break to crown = 0.0180
Estimated mean flow rate at midpoint of street = 2.731(CFS)
Depth of flow = 0.281(Ft.), Average velocity = 2.909(Ft/s)
Streetflow hydraulics at midpoint of street travel:
Halfstreet flow width = 9.315(Ft.)
Flow velocity = 2.91(Ft/s)
Travel time = 4.42 min. TC = 9.42 min.
Adding area flow to street
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000

Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Rainfall intensity = 3.447(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 3.046(CFS) for 0.930(Ac.)
Total runoff = 3.838(CFS) Total area = 1.12(Ac.)
Street flow at end of street = 3.838(CFS)
Half street flow at end of street = 3.838(CFS)
Depth of flow = 0.310(Ft.), Average velocity = 3.124(Ft/s)
Flow width (from curb towards crown) = 10.758(Ft.)

Process from Point/Station 1012.000 to Point/Station 1013.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[MULTI - UNITS area type]
Time of concentration = 9.42 min.
Rainfall intensity = 3.447(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.700
Subarea runoff = 7.481(CFS) for 3.100(Ac.)
Total runoff = 11.319(CFS) Total area = 4.22(Ac.)

Process from Point/Station 1013.000 to Point/Station 1015.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 491.800(Ft.)
Downstream point/station elevation = 488.200(Ft.)
Pipe length = 13.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 11.319(CFS)
Nearest computed pipe diameter = 12.00(In.)
Calculated individual pipe flow = 11.319(CFS)
Normal flow depth in pipe = 6.73(In.)
Flow top width inside pipe = 11.91(In.)
Critical depth could not be calculated.
Pipe flow velocity = 24.99(Ft/s)
Travel time through pipe = 0.01 min.
Time of concentration (TC) = 9.43 min.

Process from Point/Station 1013.000 to Point/Station 1015.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 9.43 min.
Rainfall intensity = 3.446(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 1.506(CFS) for 0.460(Ac.)
Total runoff = 12.825(CFS) Total area = 4.68(Ac.)

Process from Point/Station 1015.000 to Point/Station 1023.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 488.200(Ft.)
Downstream point/station elevation = 483.200(Ft.)
Pipe length = 444.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 12.825(CFS)
Nearest computed pipe diameter = 21.00(In.)
Calculated individual pipe flow = 12.825(CFS)
Normal flow depth in pipe = 13.73(In.)
Flow top width inside pipe = 19.98(In.)
Critical Depth = 16.00(In.)
Pipe flow velocity = 7.70(Ft/s)
Travel time through pipe = 0.96 min.
Time of concentration (TC) = 10.39 min.

Process from Point/Station 1015.000 to Point/Station 1023.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 2 in normal stream number 1
Stream flow area = 4.680(Ac.)
Runoff from this stream = 12.825(CFS)
Time of concentration = 10.39 min.
Rainfall intensity = 3.327(In/Hr)

Process from Point/Station 1018.000 to Point/Station 1021.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Initial subarea flow distance = 371.000(Ft.)
Highest elevation = 494.000(Ft.)
Lowest elevation = 486.700(Ft.)
Elevation difference = 7.300(Ft.)
Time of concentration calculated by the urban
areas overland flow method (App X-C) = 4.15 min.
TC = $[1.8 * (1.1 - C) * \text{distance}(\text{Ft.})^{0.5}] / (\% \text{ slope}^{1/3})$
TC = $[1.8 * (1.1 - 0.9500) * (371.000^{0.5})] / (1.968^{1/3}) = 4.15$
Setting time of concentration to 5 minutes
Rainfall intensity (I) = 4.389(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.950
Subarea runoff = 3.002(CFS)
Total initial stream area = 0.720(Ac.)

Process from Point/Station 1020.000 to Point/Station 1021.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000

Decimal fraction soil group D = 1.000
[RURAL(greater than 0.5 Ac, 0.2 ha) area type]
Time of concentration = 5.00 min.
Rainfall intensity = 4.389(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.450
Subarea runoff = 5.905(CFS) for 2.990(Ac.)
Total runoff = 8.908(CFS) Total area = 3.71(Ac.)

Process from Point/Station 1021.000 to Point/Station 1023.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 483.300(Ft.)
Downstream point/station elevation = 483.200(Ft.)
Pipe length = 15.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 8.908(CFS)
Nearest computed pipe diameter = 21.00(In.)
Calculated individual pipe flow = 8.908(CFS)
Normal flow depth in pipe = 12.80(In.)
Flow top width inside pipe = 20.49(In.)
Critical Depth = 13.31(In.)
Pipe flow velocity = 5.80(Ft/s)
Travel time through pipe = 0.04 min.
Time of concentration (TC) = 5.04 min.

Process from Point/Station 1022.000 to Point/Station 1023.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 5.04 min.
Rainfall intensity = 4.374(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 3.116(CFS) for 0.750(Ac.)
Total runoff = 12.024(CFS) Total area = 4.46(Ac.)

Process from Point/Station 1022.000 to Point/Station 1023.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 2 in normal stream number 2
Stream flow area = 4.460(Ac.)
Runoff from this stream = 12.024(CFS)
Time of concentration = 5.04 min.
Rainfall intensity = 4.374(In/Hr)
Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
1	12.825	10.39	3.327
2	12.024	5.04	4.374
Qmax(1) =			

1.000 * 1.000 * 12.825) +
0.761 * 1.000 * 12.024) + = 21.973
Qmax(2) =
1.000 * 0.485 * 12.825) +
1.000 * 1.000 * 12.024) + = 18.247

Total of 2 streams to confluence:
Flow rates before confluence point:
12.825 12.024
Maximum flow rates at confluence using above data:
21.973 18.247
Area of streams before confluence:
4.680 4.460
Results of confluence:
Total flow rate = 21.973(CFS)
Time of concentration = 10.393 min.
Effective stream area after confluence = 9.140(Ac.)

Process from Point/Station 1023.000 to Point/Station 1027.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 482.900(Ft.)
Downstream point/station elevation = 481.500(Ft.)
Pipe length = 158.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 21.973(CFS)
Nearest computed pipe diameter = 24.00(In.)
Calculated individual pipe flow = 21.973(CFS)
Normal flow depth in pipe = 20.44(In.)
Flow top width inside pipe = 17.07(In.)
Critical Depth = 20.08(In.)
Pipe flow velocity = 7.71(Ft/s)
Travel time through pipe = 0.34 min.
Time of concentration (TC) = 10.73 min.

Process from Point/Station 1023.000 to Point/Station 1027.000
**** CONFLUENCE OF MAIN STREAMS ****

The following data inside Main Stream is listed:

In Main Stream number: 2
Stream flow area = 9.140(Ac.)
Runoff from this stream = 21.973(CFS)
Time of concentration = 10.73 min.
Rainfall intensity = 3.289(In/Hr)
Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
1	22.926	8.48	3.582
2	21.973	10.73	3.289
Qmax(1) =			
	1.000 * 1.000 * 22.926) +		
	1.000 * 0.790 * 21.973) + =		40.287
Qmax(2) =			
	0.918 * 1.000 * 22.926) +		
	1.000 * 1.000 * 21.973) + =		43.021

Total of 2 main streams to confluence:
Flow rates before confluence point:
22.926 21.973
Maximum flow rates at confluence using above data:
40.287 43.021
Area of streams before confluence:
8.040 9.140

Results of confluence:
Total flow rate = 43.021(CFS)
Time of concentration = 10.735 min.
Effective stream area after confluence = 17.180(Ac.)

Process from Point/Station 1024.000 to Point/Station 1027.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 10.73 min.
Rainfall intensity = 3.289(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 2.281(CFS) for 0.730(Ac.)
Total runoff = 45.302(CFS) Total area = 17.91(Ac.)

Process from Point/Station 1025.000 to Point/Station 1027.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 10.73 min.
Rainfall intensity = 3.289(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 2.406(CFS) for 0.770(Ac.)
Total runoff = 47.707(CFS) Total area = 18.68(Ac.)

Process from Point/Station 1027.000 to Point/Station 1030.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 481.500(Ft.)
Downstream point/station elevation = 478.900(Ft.)
Pipe length = 389.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 47.707(CFS)
Nearest computed pipe diameter = 36.00(In.)
Calculated individual pipe flow = 47.707(CFS)
Normal flow depth in pipe = 26.09(In.)
Flow top width inside pipe = 32.16(In.)
Critical Depth = 26.97(In.)

Pipe flow velocity = 8.70(Ft/s)
Travel time through pipe = 0.75 min.
Time of concentration (TC) = 11.48 min.

Process from Point/Station 1027.000 to Point/Station 1030.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 11.48 min.
Rainfall intensity = 3.210(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 0.945(CFS) for 0.310(Ac.)
Total runoff = 48.653(CFS) Total area = 18.99(Ac.)

Process from Point/Station 1029.000 to Point/Station 1030.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 11.48 min.
Rainfall intensity = 3.210(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 1.037(CFS) for 0.340(Ac.)
Total runoff = 49.689(CFS) Total area = 19.33(Ac.)

Process from Point/Station 1030.000 to Point/Station 1033.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 478.900(Ft.)
Downstream point/station elevation = 476.200(Ft.)
Pipe length = 447.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 49.689(CFS)
Nearest computed pipe diameter = 36.00(In.)
Calculated individual pipe flow = 49.689(CFS)
Normal flow depth in pipe = 28.27(In.)
Flow top width inside pipe = 29.57(In.)
Critical Depth = 27.53(In.)
Pipe flow velocity = 8.35(Ft/s)
Travel time through pipe = 0.89 min.
Time of concentration (TC) = 12.37 min.

Process from Point/Station 1030.000 to Point/Station 1033.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 1
Stream flow area = 19.330(Ac.)

Runoff from this stream = 49.689(CFS)
Time of concentration = 12.37 min.
Rainfall intensity = 3.123(In/Hr)

Process from Point/Station 1042.000 to Point/Station 1043.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[MULTI - UNITS area type]
Initial subarea flow distance = 211.000(Ft.)
Highest elevation = 502.000(Ft.)
Lowest elevation = 496.500(Ft.)
Elevation difference = 5.500(Ft.)
Time of concentration calculated by the urban
areas overland flow method (App X-C) = 7.60 min.
TC = $[1.8 * (1.1 - C) * \text{distance}(\text{Ft.})^{.5}] / (\% \text{ slope}^{(1/3)})]$
TC = $[1.8 * (1.1 - 0.7000) * (211.000^{.5}) / (2.607^{(1/3)})] = 7.60$
Rainfall intensity (I) = 3.730(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.700
Subarea runoff = 0.809(CFS)
Total initial stream area = 0.310(Ac.)

Process from Point/Station 1041.000 to Point/Station 1043.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[MULTI - UNITS area type]
Time of concentration = 7.60 min.
Rainfall intensity = 3.730(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.700
Subarea runoff = 1.906(CFS) for 0.730(Ac.)
Total runoff = 2.715(CFS) Total area = 1.04(Ac.)

Process from Point/Station 1043.000 to Point/Station 1044.000
**** IMPROVED CHANNEL TRAVEL TIME ****

Upstream point elevation = 496.500(Ft.)
Downstream point elevation = 487.000(Ft.)
Channel length thru subarea = 1040.000(Ft.)
Channel base width = 2.000(Ft.)
Slope or 'Z' of left channel bank = 2.000
Slope or 'Z' of right channel bank = 2.000
Estimated mean flow rate at midpoint of channel = 24.621(CFS)
Manning's 'N' = 0.015
Maximum depth of channel = 2.000(Ft.)
Flow(q) thru subarea = 24.621(CFS)
Depth of flow = 0.947(Ft.), Average velocity = 6.673(Ft/s)
Channel flow top width = 5.790(Ft.)
Flow Velocity = 6.67(Ft/s)

Travel time = 2.60 min.
Time of concentration = 10.20 min.
Critical depth = 1.156(Ft.)
Adding area flow to channel
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[MULTI - UNITS area type]
Rainfall intensity = 3.350(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.700
Subarea runoff = 39.354(CFS) for 16.780(Ac.)
Total runoff = 42.069(CFS) Total area = 17.82(Ac.)

Process from Point/Station 1044.000 to Point/Station 1032.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 482.000(Ft.)
Downstream point/station elevation = 476.500(Ft.)
Pipe length = 24.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 42.069(CFS)
Nearest computed pipe diameter = 18.00(In.)
Calculated individual pipe flow = 42.069(CFS)
Normal flow depth in pipe = 12.59(In.)
Flow top width inside pipe = 16.51(In.)
Critical depth could not be calculated.
Pipe flow velocity = 31.86(Ft/s)
Travel time through pipe = 0.01 min.
Time of concentration (TC) = 10.21 min.

Process from Point/Station 1032.000 to Point/Station 1032.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 10.21 min.
Rainfall intensity = 3.349(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 2.068(CFS) for 0.650(Ac.)
Total runoff = 44.137(CFS) Total area = 18.47(Ac.)

Process from Point/Station 1032.000 to Point/Station 1033.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 476.400(Ft.)
Downstream point/station elevation = 476.200(Ft.)
Pipe length = 20.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 44.137(CFS)
Nearest computed pipe diameter = 33.00(In.)
Calculated individual pipe flow = 44.137(CFS)
Normal flow depth in pipe = 23.04(In.)
Flow top width inside pipe = 30.30(In.)

Critical Depth = 26.43(In.)
Pipe flow velocity = 9.96(Ft/s)
Travel time through pipe = 0.03 min.
Time of concentration (TC) = 10.24 min.

Process from Point/Station 1031.000 to Point/Station 1033.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 10.24 min.
Rainfall intensity = 3.345(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 1.430(CFS) for 0.450(Ac.)
Total runoff = 45.567(CFS) Total area = 18.92(Ac.)

Process from Point/Station 1031.000 to Point/Station 1033.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 2
Stream flow area = 18.920(Ac.)
Runoff from this stream = 45.567(CFS)
Time of concentration = 10.24 min.
Rainfall intensity = 3.345(In/Hr)
Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
1	49.689	12.37	3.123
2	45.567	10.24	3.345

Qmax(1) =
1.000 * 1.000 * 49.689) +
0.934 * 1.000 * 45.567) + = 92.232

Qmax(2) =
1.000 * 0.828 * 49.689) +
1.000 * 1.000 * 45.567) + = 86.705

Total of 2 streams to confluence:
Flow rates before confluence point:
49.689 45.567
Maximum flow rates at confluence using above data:
92.232 86.705
Area of streams before confluence:
19.330 18.920
Results of confluence:
Total flow rate = 92.232(CFS)
Time of concentration = 12.372 min.
Effective stream area after confluence = 38.250(Ac.)

Process from Point/Station 1033.000 to Point/Station 1040.000

**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 476.200(Ft.)
Downstream point/station elevation = 475.600(Ft.)
Pipe length = 87.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 92.232(CFS)
Nearest computed pipe diameter = 45.00(In.)
Calculated individual pipe flow = 92.232(CFS)
Normal flow depth in pipe = 33.94(In.)
Flow top width inside pipe = 38.75(In.)
Critical Depth = 35.40(In.)
Pipe flow velocity = 10.31(Ft/s)
Travel time through pipe = 0.14 min.
Time of concentration (TC) = 12.51 min.

Process from Point/Station 1033.000 to Point/Station 1040.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 1
Stream flow area = 38.250(Ac.)
Runoff from this stream = 92.232(CFS)
Time of concentration = 12.51 min.
Rainfall intensity = 3.110(In/Hr)

Process from Point/Station 1034.000 to Point/Station 1035.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[MULTI - UNITS area type]
Initial subarea flow distance = 100.000(Ft.)
Highest elevation = 498.000(Ft.)
Lowest elevation = 493.000(Ft.)
Elevation difference = 5.000(Ft.)
Time of concentration calculated by the urban
areas overland flow method (App X-C) = 4.21 min.
TC = [1.8*(1.1-C)*distance(Ft.)^0.5]/(% slope^(1/3))
TC = [1.8*(1.1-0.7000)*(100.000^0.5)]/(5.000^(1/3))= 4.21
Setting time of concentration to 5 minutes
Rainfall intensity (I) = 4.389(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.700
Subarea runoff = 1.075(CFS)
Total initial stream area = 0.350(Ac.)

Process from Point/Station 1035.000 to Point/Station 1036.000
**** IMPROVED CHANNEL TRAVEL TIME ****

Upstream point elevation = 493.000(Ft.)
Downstream point elevation = 476.500(Ft.)
Channel length thru subarea = 1050.000(Ft.)
Channel base width = 2.000(Ft.)
Slope or 'Z' of left channel bank = 2.000
Slope or 'Z' of right channel bank = 2.000

Estimated mean flow rate at midpoint of channel = 9.294(CFS)
Manning's 'N' = 0.015
Maximum depth of channel = 2.000(Ft.)
Flow(q) thru subarea = 9.294(CFS)
Depth of flow = 0.499(Ft.), Average velocity = 6.210(Ft/s)
Channel flow top width = 3.997(Ft.)
Flow Velocity = 6.21(Ft/s)
Travel time = 2.82 min.
Time of concentration = 7.82 min.
Critical depth = 0.688(Ft.)
Adding area flow to channel
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[MULTI - UNITS area type]
Rainfall intensity = 3.691(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.700
Subarea runoff = 13.822(CFS) for 5.350(Ac.)
Total runoff = 14.898(CFS) Total area = 5.70(Ac.)

Process from Point/Station 1036.000 to Point/Station 1037.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 476.500(Ft.)
Downstream point/station elevation = 476.340(Ft.)
Pipe length = 14.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 14.898(CFS)
Nearest computed pipe diameter = 21.00(In.)
Calculated individual pipe flow = 14.898(CFS)
Normal flow depth in pipe = 15.28(In.)
Flow top width inside pipe = 18.70(In.)
Critical Depth = 17.16(In.)
Pipe flow velocity = 7.95(Ft/s)
Travel time through pipe = 0.03 min.
Time of concentration (TC) = 7.85 min.

Process from Point/Station 1037.000 to Point/Station 1039.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 476.340(Ft.)
Downstream point/station elevation = 476.280(Ft.)
Pipe length = 6.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 14.898(CFS)
Nearest computed pipe diameter = 21.00(In.)
Calculated individual pipe flow = 14.898(CFS)
Normal flow depth in pipe = 16.17(In.)
Flow top width inside pipe = 17.67(In.)
Critical Depth = 17.16(In.)
Pipe flow velocity = 7.49(Ft/s)
Travel time through pipe = 0.01 min.
Time of concentration (TC) = 7.86 min.

Process from Point/Station 1037.000 to Point/Station 1039.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[MULTI - UNITS area type]
Time of concentration = 7.86 min.
Rainfall intensity = 3.683(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.700
Subarea runoff = 0.464(CFS) for 0.180(Ac.)
Total runoff = 15.362(CFS) Total area = 5.88(Ac.)

Process from Point/Station 1038.000 to Point/Station 1039.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[MULTI - UNITS area type]
Time of concentration = 7.86 min.
Rainfall intensity = 3.683(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.700
Subarea runoff = 0.464(CFS) for 0.180(Ac.)
Total runoff = 15.826(CFS) Total area = 6.06(Ac.)

Process from Point/Station 1039.000 to Point/Station 1040.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 476.180(Ft.)
Downstream point/station elevation = 475.600(Ft.)
Pipe length = 66.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 15.826(CFS)
Nearest computed pipe diameter = 21.00(In.)
Calculated individual pipe flow = 15.826(CFS)
Normal flow depth in pipe = 18.90(In.)
Flow top width inside pipe = 12.60(In.)
Critical Depth = 17.62(In.)
Pipe flow velocity = 6.94(Ft/s)
Travel time through pipe = 0.16 min.
Time of concentration (TC) = 8.02 min.

Process from Point/Station 1039.000 to Point/Station 1040.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 2
Stream flow area = 6.060(Ac.)
Runoff from this stream = 15.826(CFS)
Time of concentration = 8.02 min.
Rainfall intensity = 3.656(In/Hr)
Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
------------	-----------------	----------	----------------------------

```
1      92.232      12.51      3.110
2      15.826      8.02      3.656
Qmax(1) =
      1.000 *      1.000 *      92.232) +
      0.851 *      1.000 *      15.826) + =      105.693
Qmax(2) =
      1.000 *      0.641 *      92.232) +
      1.000 *      1.000 *      15.826) + =      74.935
```

Total of 2 streams to confluence:
Flow rates before confluence point:

92.232 15.826
Maximum flow rates at confluence using above data:
105.693 74.935

Area of streams before confluence:
38.250 6.060

Results of confluence:
Total flow rate = 105.693(CFS)
Time of concentration = 12.513 min.
Effective stream area after confluence = 44.310(Ac.)

Process from Point/Station 1040.000 to Point/Station 1052.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 475.500(Ft.)
Downstream point/station elevation = 474.950(Ft.)
Pipe length = 91.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 105.693(CFS)
Nearest computed pipe diameter = 48.00(In.)
Calculated individual pipe flow = 105.693(CFS)
Normal flow depth in pipe = 37.22(In.)
Flow top width inside pipe = 40.06(In.)
Critical Depth = 37.31(In.)
Pipe flow velocity = 10.11(Ft/s)
Travel time through pipe = 0.15 min.
Time of concentration (TC) = 12.66 min.

Process from Point/Station 1050.000 to Point/Station 1052.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 12.66 min.
Rainfall intensity = 3.096(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 2.030(CFS) for 0.690(Ac.)
Total runoff = 107.723(CFS) Total area = 45.00(Ac.)

Process from Point/Station 1051.000 to Point/Station 1052.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 12.66 min.
Rainfall intensity = 3.096(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 1.265(CFS) for 0.430(Ac.)
Total runoff = 108.987(CFS) Total area = 45.43(Ac.)

Process from Point/Station 1052.000 to Point/Station 1049.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 474.850(Ft.)
Downstream point/station elevation = 0.000(Ft.)
Pipe length = 236.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 108.987(CFS)
Nearest computed pipe diameter = 18.00(In.)
Calculated individual pipe flow = 108.987(CFS)
Normal flow depth in pipe = 11.44(In.)
Flow top width inside pipe = 17.33(In.)
Critical depth could not be calculated.
Pipe flow velocity = 92.08(Ft/s)
Travel time through pipe = 0.04 min.
Time of concentration (TC) = 12.71 min.

Process from Point/Station 1052.000 to Point/Station 1049.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 1
Stream flow area = 45.430(Ac.)
Runoff from this stream = 108.987(CFS)
Time of concentration = 12.71 min.
Rainfall intensity = 3.093(In/Hr)

Process from Point/Station 1060.000 to Point/Station 1045.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Initial subarea flow distance = 152.000(Ft.)
Highest elevation = 494.000(Ft.)
Lowest elevation = 487.000(Ft.)
Elevation difference = 7.000(Ft.)
Time of concentration calculated by the urban
areas overland flow method (App X-C) = 2.00 min.
TC = $[1.8 * (1.1 - C) * \text{distance}(\text{Ft.})^{0.5}] / (\% \text{ slope}^{1/3})$
TC = $[1.8 * (1.1 - 0.9500) * (152.000^{0.5})] / (4.605^{1/3}) = 2.00$
Setting time of concentration to 5 minutes
Rainfall intensity (I) = 4.389(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.950

Subarea runoff = 1.251(CFS)
Total initial stream area = 0.300(Ac.)

Process from Point/Station 1045.000 to Point/Station 1047.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 483.300(Ft.)
Downstream point/station elevation = 482.900(Ft.)
Pipe length = 6.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 1.251(CFS)
Nearest computed pipe diameter = 6.00(In.)
Calculated individual pipe flow = 1.251(CFS)
Normal flow depth in pipe = 4.30(In.)
Flow top width inside pipe = 5.41(In.)
Critical depth could not be calculated.
Pipe flow velocity = 8.30(Ft/s)
Travel time through pipe = 0.01 min.
Time of concentration (TC) = 5.01 min.

Process from Point/Station 1046.000 to Point/Station 1047.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 5.01 min.
Rainfall intensity = 4.385(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 0.833(CFS) for 0.200(Ac.)
Total runoff = 2.084(CFS) Total area = 0.50(Ac.)

Process from Point/Station 1047.000 to Point/Station 1049.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 482.530(Ft.)
Downstream point/station elevation = 473.500(Ft.)
Pipe length = 260.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 2.084(CFS)
Nearest computed pipe diameter = 9.00(In.)
Calculated individual pipe flow = 2.084(CFS)
Normal flow depth in pipe = 5.42(In.)
Flow top width inside pipe = 8.81(In.)
Critical Depth = 7.83(In.)
Pipe flow velocity = 7.49(Ft/s)
Travel time through pipe = 0.58 min.
Time of concentration (TC) = 5.59 min.

Process from Point/Station 1047.000 to Point/Station 1049.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 2

Stream flow area = 0.500(Ac.)
Runoff from this stream = 2.084(CFS)
Time of concentration = 5.59 min.
Rainfall intensity = 4.196(In/Hr)
Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
------------	-----------------	----------	----------------------------

1	108.987	12.71	3.093
2	2.084	5.59	4.196
Qmax(1) =	1.000 * 1.000 * 108.987) + 0.737 * 1.000 * 2.084) + =		110.523
Qmax(2) =	1.000 * 0.440 * 108.987) + 1.000 * 1.000 * 2.084) + =		50.037

Total of 2 streams to confluence:
Flow rates before confluence point:
108.987 2.084
Maximum flow rates at confluence using above data:
110.523 50.037
Area of streams before confluence:
45.430 0.500
Results of confluence:
Total flow rate = 110.523(CFS)
Time of concentration = 12.706 min.
Effective stream area after confluence = 45.930(Ac.)

Process from Point/Station 1049.000 to Point/Station 1066.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 473.330(Ft.)
Downstream point/station elevation = 467.000(Ft.)
Pipe length = 516.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 110.523(CFS)
Nearest computed pipe diameter = 42.00(In.)
Calculated individual pipe flow = 110.523(CFS)
Normal flow depth in pipe = 34.13(In.)
Flow top width inside pipe = 32.79(In.)
Critical Depth = 38.10(In.)
Pipe flow velocity = 13.20(Ft/s)
Travel time through pipe = 0.65 min.
Time of concentration (TC) = 13.36 min.

Process from Point/Station 1064.000 to Point/Station 1066.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[MULTI - UNITS area type]
Time of concentration = 13.36 min.
Rainfall intensity = 3.036(In/Hr) for a 100.0 year storm

Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.700
Subarea runoff = 26.902(CFS) for 12.660(Ac.)
Total runoff = 137.425(CFS) Total area = 58.59(Ac.)

Process from Point/Station 1049.000 to Point/Station 1066.000
**** CONFLUENCE OF MAIN STREAMS ****

The following data inside Main Stream is listed:

In Main Stream number: 1
Stream flow area = 58.590(Ac.)
Runoff from this stream = 137.425(CFS)
Time of concentration = 13.36 min.
Rainfall intensity = 3.036(In/Hr)
Program is now starting with Main Stream No. 2

Process from Point/Station 1067.000 to Point/Station 1055.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Initial subarea flow distance = 300.000(Ft.)
Highest elevation = 508.000(Ft.)
Lowest elevation = 504.000(Ft.)
Elevation difference = 4.000(Ft.)
Time of concentration calculated by the urban
areas overland flow method (App X-C) = 4.25 min.
TC = $[1.8 * (1.1 - C) * \text{distance}(\text{Ft.})^{.5}] / (\% \text{ slope}^{(1/3)})]$
TC = $[1.8 * (1.1 - 0.9500) * (300.000^{.5})] / (1.333^{(1/3)})] = 4.25$
Setting time of concentration to 5 minutes
Rainfall intensity (I) = 4.389(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.950
Subarea runoff = 1.876(CFS)
Total initial stream area = 0.450(Ac.)

Process from Point/Station 1055.000 to Point/Station 1057.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 499.000(Ft.)
Downstream point/station elevation = 498.900(Ft.)
Pipe length = 9.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 1.876(CFS)
Nearest computed pipe diameter = 12.00(In.)
Calculated individual pipe flow = 1.876(CFS)
Normal flow depth in pipe = 6.00(In.)
Flow top width inside pipe = 12.00(In.)
Critical Depth = 7.00(In.)
Pipe flow velocity = 4.78(Ft/s)
Travel time through pipe = 0.03 min.
Time of concentration (TC) = 5.03 min.

Process from Point/Station 1056.000 to Point/Station 1057.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 5.03 min.
Rainfall intensity = 4.378(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 4.201(CFS) for 1.010(Ac.)
Total runoff = 6.077(CFS) Total area = 1.46(Ac.)

Process from Point/Station 1057.000 to Point/Station 1058.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 498.600(Ft.)
Downstream point/station elevation = 488.800(Ft.)
Pipe length = 477.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 6.077(CFS)
Nearest computed pipe diameter = 15.00(In.)
Calculated individual pipe flow = 6.077(CFS)
Normal flow depth in pipe = 8.86(In.)
Flow top width inside pipe = 14.75(In.)
Critical Depth = 11.95(In.)
Pipe flow velocity = 8.05(Ft/s)
Travel time through pipe = 0.99 min.
Time of concentration (TC) = 6.02 min.

Process from Point/Station 1057.000 to Point/Station 1058.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 6.02 min.
Rainfall intensity = 4.076(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 2.788(CFS) for 0.720(Ac.)
Total runoff = 8.865(CFS) Total area = 2.18(Ac.)

Process from Point/Station 1059.000 to Point/Station 1058.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 6.02 min.
Rainfall intensity = 4.076(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950

Subarea runoff = 2.362(CFS) for 0.610(Ac.)
Total runoff = 11.226(CFS) Total area = 2.79(Ac.)

Process from Point/Station 1058.000 to Point/Station 1063.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 488.360(Ft.)
Downstream point/station elevation = 470.560(Ft.)
Pipe length = 693.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 11.226(CFS)
Nearest computed pipe diameter = 18.00(In.)
Calculated individual pipe flow = 11.226(CFS)
Normal flow depth in pipe = 10.75(In.)
Flow top width inside pipe = 17.66(In.)
Critical Depth = 15.37(In.)
Pipe flow velocity = 10.20(Ft/s)
Travel time through pipe = 1.13 min.
Time of concentration (TC) = 7.15 min.

Process from Point/Station 1062.000 to Point/Station 1063.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 7.15 min.
Rainfall intensity = 3.815(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 3.371(CFS) for 0.930(Ac.)
Total runoff = 14.597(CFS) Total area = 3.72(Ac.)

Process from Point/Station 1063.000 to Point/Station 1061.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 470.230(Ft.)
Downstream point/station elevation = 470.000(Ft.)
Pipe length = 19.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 14.597(CFS)
Nearest computed pipe diameter = 21.00(In.)
Calculated individual pipe flow = 14.597(CFS)
Normal flow depth in pipe = 14.70(In.)
Flow top width inside pipe = 19.25(In.)
Critical Depth = 17.01(In.)
Pipe flow velocity = 8.12(Ft/s)
Travel time through pipe = 0.04 min.
Time of concentration (TC) = 7.19 min.

Process from Point/Station 1060.000 to Point/Station 1061.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000

Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
Time of concentration = 7.19 min.
Rainfall intensity = 3.808(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.950
Subarea runoff = 3.907(CFS) for 1.080(Ac.)
Total runoff = 18.504(CFS) Total area = 4.80(Ac.)

Process from Point/Station 1061.000 to Point/Station 1066.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 469.710(Ft.)
Downstream point/station elevation = 467.000(Ft.)
Pipe length = 52.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 18.504(CFS)
Nearest computed pipe diameter = 18.00(In.)
Calculated individual pipe flow = 18.504(CFS)
Normal flow depth in pipe = 11.86(In.)
Flow top width inside pipe = 17.07(In.)
Critical depth could not be calculated.
Pipe flow velocity = 14.97(Ft/s)
Travel time through pipe = 0.06 min.
Time of concentration (TC) = 7.25 min.

Process from Point/Station 1061.000 to Point/Station 1066.000
**** CONFLUENCE OF MAIN STREAMS ****

The following data inside Main Stream is listed:

In Main Stream number: 2
Stream flow area = 4.800(Ac.)
Runoff from this stream = 18.504(CFS)
Time of concentration = 7.25 min.
Rainfall intensity = 3.796(In/Hr)
Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
1	137.425	13.36	3.036
2	18.504	7.25	3.796
Qmax(1) =	1.000 * 0.800 *	1.000 * 1.000 *	137.425) + 18.504) + = 152.222
Qmax(2) =	1.000 * 1.000 *	0.543 * 1.000 *	137.425) + 18.504) + = 93.081

Total of 2 main streams to confluence:

Flow rates before confluence point:

137.425 18.504

Maximum flow rates at confluence using above data:

152.222 93.081

Area of streams before confluence:

58.590 4.800

Results of confluence:

Total flow rate = 152.222(CFS)
Time of concentration = 13.357 min.
Effective stream area after confluence = 63.390(Ac.)

Process from Point/Station 1066.000 to Point/Station 1066.000
**** SUBAREA FLOW ADDITION ****


Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[RURAL(greater than 0.5 Ac, 0.2 ha) area type]
Time of concentration = 13.36 min.
Rainfall intensity = 3.036(In/Hr) for a 100.0 year storm
Runoff coefficient used for sub-area, Rational method, Q=KCIA, C = 0.450
Subarea runoff = 0.000(CFS) for 0.000(Ac.)
Total runoff = 152.222(CFS) Total area = 63.39(Ac.)

Process from Point/Station 1066.000 to Point/Station 1068.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 465.500(Ft.)
Downstream point/station elevation = 430.000(Ft.)
Pipe length = 264.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 152.222(CFS)
Nearest computed pipe diameter = 30.00(In.)
Calculated individual pipe flow = 152.222(CFS)
Normal flow depth in pipe = 24.94(In.)
Flow top width inside pipe = 22.47(In.)
Critical depth could not be calculated.
Pipe flow velocity = 34.91(Ft/s)
Travel time through pipe = 0.13 min.
Time of concentration (TC) = 13.48 min.
End of computations, total study area = 63.390 (Ac.)

APPENDIX 2

Detention Calculations



RUN DATE 9/30/2019
HYDROGRAPH FILE NAME Text1
TIME OF CONCENTRATION 14 MIN.
6 HOUR RAINFALL 2.2 INCHES
BASIN AREA 63.4 ACRES
RUNOFF COEFFICIENT 0.785
PEAK DISCHARGE 152.2 CFS

TIME (MIN) = 0	DISCHARGE (CFS) = 0
TIME (MIN) = 14	DISCHARGE (CFS) = 6.5
TIME (MIN) = 28	DISCHARGE (CFS) = 6.9
TIME (MIN) = 42	DISCHARGE (CFS) = 7.1
TIME (MIN) = 56	DISCHARGE (CFS) = 7.5
TIME (MIN) = 70	DISCHARGE (CFS) = 7.8
TIME (MIN) = 84	DISCHARGE (CFS) = 8.3
TIME (MIN) = 98	DISCHARGE (CFS) = 8.6
TIME (MIN) = 112	DISCHARGE (CFS) = 9.4
TIME (MIN) = 126	DISCHARGE (CFS) = 9.8
TIME (MIN) = 140	DISCHARGE (CFS) = 10.9
TIME (MIN) = 154	DISCHARGE (CFS) = 11.6
TIME (MIN) = 168	DISCHARGE (CFS) = 13.3
TIME (MIN) = 182	DISCHARGE (CFS) = 14.4
TIME (MIN) = 196	DISCHARGE (CFS) = 17.6
TIME (MIN) = 210	DISCHARGE (CFS) = 20
TIME (MIN) = 224	DISCHARGE (CFS) = 29.4
TIME (MIN) = 238	DISCHARGE (CFS) = 37.7
TIME (MIN) = 252	DISCHARGE (CFS) = 152.2
TIME (MIN) = 266	DISCHARGE (CFS) = 23.6
TIME (MIN) = 280	DISCHARGE (CFS) = 15.8
TIME (MIN) = 294	DISCHARGE (CFS) = 12.3
TIME (MIN) = 308	DISCHARGE (CFS) = 10.3
TIME (MIN) = 322	DISCHARGE (CFS) = 9
TIME (MIN) = 336	DISCHARGE (CFS) = 8
TIME (MIN) = 350	DISCHARGE (CFS) = 7.3
TIME (MIN) = 364	DISCHARGE (CFS) = 6.7
TIME (MIN) = 378	DISCHARGE (CFS) = 0

South Basin

Project Summary	
Title	South Basin
Engineer	PDC
Company	PDC
Date	9/24/2019
Notes	

Table of Contents

	Master Network Summary	2
CM-1	Read Hydrograph	3
1	Elevation-Area Volume Curve	4
Outlet#1		
	Outlet Input Data	5
	Composite Rating Curve	8
1		
	Elevation-Volume-Flow Table (Pond)	18
1 (IN)		
	Level Pool Pond Routing Summary	22

South Basin

Subsection: Master Network Summary

Catchments Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (min)	Peak Flow (ft ³ /s)
CM-1	EX10	0	9.098	252.000	152.20

Node Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (min)	Peak Flow (ft ³ /s)
O-1	EX10	0	9.098	265.000	36.74

Pond Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (min)	Peak Flow (ft ³ /s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ac-ft)
1 (IN)	EX10	0	9.098	252.000	152.20	(N/A)	(N/A)
1 (OUT)	EX10	0	9.098	265.000	36.74	468.90	6.258

South Basin

Subsection: Read Hydrograph
Label: CM-1

Return Event: 100 years
Storm Event:

Peak Discharge	152.20 ft ³ /s
Time to Peak	252.000 min
Hydrograph Volume	9.098 ac-ft

HYDROGRAPH ORDINATES (ft³/s)

Output Time Increment = 14.000 min

Time on left represents time for first value in each row.

Time (min)	Flow (ft ³ /s)	Flow (ft ³ /s)	Flow (ft ³ /s)	Flow (ft ³ /s)	Flow (ft ³ /s)
0.000	0.00	6.50	6.90	7.00	7.50
70.000	7.70	8.30	8.60	9.40	9.80
140.000	10.90	11.60	13.30	14.40	17.60
210.000	20.00	29.40	37.70	152.20	23.60
280.000	15.80	12.30	10.30	9.00	8.00
350.000	7.30	6.70	0.00	(N/A)	(N/A)

South Basin

Subsection: Elevation-Area Volume Curve

Return Event: 100 years

Label: 1

Storm Event:

Elevation (ft)	Planimeter (ft ²)	Area (ft ²)	A1+A2+sqr (A1*A2) (ft ²)	Volume (ac-ft)	Volume (Total) (ac-ft)
460.80	0.0	10.000	0.000	0.000	0.000
463.70	0.0	10.000	30.000	0.001	0.001
463.80	0.0	46,285.000	46,975.331	0.036	0.037
474.00	0.0	76,427.000	182,188.245	14.220	14.257

South Basin

Subsection: Outlet Input Data

Label: Outlet#1

Return Event: 100 years

Storm Event:

Requested Pond Water Surface Elevations

Minimum (Headwater)	460.80 ft
Increment (Headwater)	0.10 ft
Maximum (Headwater)	474.00 ft

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Orifice-Circular	1-Lowflow orifice	Forward	TW	464.30	474.00
Orifice-Circular	2-Midflow orifice	Forward	TW	466.30	474.00
Stand Pipe	Riser - 1	Forward	TW	467.90	474.00
Orifice-Circular	0- Underdrain orifice	Forward	TW	461.05	474.00
Tailwater Settings	Tailwater			(N/A)	(N/A)

South Basin

Subsection: Outlet Input Data

Label: Outlet#1

Return Event: 100 years

Storm Event:

Structure ID: 0-Underdrain orifice
Structure Type: Orifice-Circular

Number of Openings	1
Elevation	461.05 ft
Orifice Diameter	6.0 in
Orifice Coefficient	0.600

Structure ID: 2-Midflow orifice
Structure Type: Orifice-Circular

Number of Openings	2
Elevation	466.30 ft
Orifice Diameter	8.0 in
Orifice Coefficient	0.600

Structure ID: Riser - 1
Structure Type: Stand Pipe

Number of Openings	1
Elevation	467.90 ft
Diameter	36.0 in
Orifice Area	7.1 ft ²
Orifice Coefficient	0.600
Weir Length	9.42 ft
Weir Coefficient	3.00 (ft ^{0.5})/s
K Reverse	1.000
Manning's n	0.000
Kev, Charged Riser	0.000
Weir Submergence	False
Orifice H to crest	True

Structure ID: 1-Lowflow orifice
Structure Type: Orifice-Circular

Number of Openings	2
Elevation	464.30 ft
Orifice Diameter	3.0 in
Orifice Coefficient	0.600

Structure ID: TW
Structure Type: TW Setup, DS Channel

Tailwater Type	Free Outfall
----------------	--------------

Convergence Tolerances

Maximum Iterations	30
--------------------	----

South Basin

Subsection: Outlet Input Data

Label: Outlet#1

Return Event: 100 years

Storm Event:

Convergence Tolerances	
Tailwater Tolerance (Minimum)	0.01 ft
Tailwater Tolerance (Maximum)	0.50 ft
Headwater Tolerance (Minimum)	0.01 ft
Headwater Tolerance (Maximum)	0.50 ft
Flow Tolerance (Minimum)	0.001 ft ³ /s
Flow Tolerance (Maximum)	10.000 ft ³ /s

South Basin

Subsection: Composite Rating Curve
Label: Outlet#1

Return Event: 100 years
Storm Event:

Composite Outflow Summary

Water Surface Elevation (ft)	Flow (ft ³ /s)	Tailwater Elevation (ft)	Convergence Error (ft)
460.80	0.00	(N/A)	0.00
460.90	0.00	(N/A)	0.00
461.00	0.00	(N/A)	0.00
461.05	0.00	(N/A)	0.00
461.10	0.01	(N/A)	0.00
461.20	0.05	(N/A)	0.00
461.30	0.13	(N/A)	0.00
461.40	0.25	(N/A)	0.00
461.50	0.38	(N/A)	0.00
461.60	0.52	(N/A)	0.00
461.70	0.60	(N/A)	0.00
461.80	0.67	(N/A)	0.00
461.90	0.73	(N/A)	0.00
462.00	0.79	(N/A)	0.00
462.10	0.85	(N/A)	0.00
462.20	0.90	(N/A)	0.00
462.30	0.95	(N/A)	0.00
462.40	0.99	(N/A)	0.00
462.50	1.04	(N/A)	0.00
462.60	1.08	(N/A)	0.00
462.70	1.12	(N/A)	0.00
462.80	1.16	(N/A)	0.00
462.90	1.20	(N/A)	0.00
463.00	1.23	(N/A)	0.00
463.10	1.27	(N/A)	0.00
463.20	1.30	(N/A)	0.00
463.30	1.34	(N/A)	0.00
463.40	1.37	(N/A)	0.00
463.50	1.40	(N/A)	0.00
463.60	1.43	(N/A)	0.00
463.70	1.46	(N/A)	0.00
463.80	1.49	(N/A)	0.00
463.90	1.52	(N/A)	0.00
464.00	1.55	(N/A)	0.00
464.10	1.58	(N/A)	0.00
464.20	1.61	(N/A)	0.00
464.30	1.64	(N/A)	0.00
464.40	1.70	(N/A)	0.00
464.50	1.80	(N/A)	0.00
464.60	1.91	(N/A)	0.00
464.70	1.99	(N/A)	0.00
464.80	2.06	(N/A)	0.00
464.90	2.12	(N/A)	0.00

South Basin

Subsection: Composite Rating Curve
Label: Outlet#1

Return Event: 100 years
Storm Event:

Composite Outflow Summary

Water Surface Elevation (ft)	Flow (ft ³ /s)	Tailwater Elevation (ft)	Convergence Error (ft)
465.00	2.18	(N/A)	0.00
465.10	2.23	(N/A)	0.00
465.20	2.28	(N/A)	0.00
465.30	2.33	(N/A)	0.00
465.40	2.38	(N/A)	0.00
465.50	2.43	(N/A)	0.00
465.60	2.47	(N/A)	0.00
465.70	2.52	(N/A)	0.00
465.80	2.56	(N/A)	0.00
465.90	2.60	(N/A)	0.00
466.00	2.64	(N/A)	0.00
466.10	2.68	(N/A)	0.00
466.20	2.72	(N/A)	0.00
466.30	2.76	(N/A)	0.00
466.40	2.85	(N/A)	0.00
466.50	3.05	(N/A)	0.00
466.60	3.33	(N/A)	0.00
466.70	3.68	(N/A)	0.00
466.80	4.10	(N/A)	0.00
466.90	4.56	(N/A)	0.00
467.00	5.05	(N/A)	0.00
467.10	5.34	(N/A)	0.00
467.20	5.61	(N/A)	0.00
467.30	5.86	(N/A)	0.00
467.40	6.09	(N/A)	0.00
467.50	6.31	(N/A)	0.00
467.60	6.52	(N/A)	0.00
467.70	6.72	(N/A)	0.00
467.80	6.91	(N/A)	0.00
467.90	7.09	(N/A)	0.00
468.00	8.16	(N/A)	0.00
468.10	9.97	(N/A)	0.00
468.20	12.25	(N/A)	0.00
468.30	14.92	(N/A)	0.00
468.40	17.92	(N/A)	0.00
468.50	21.22	(N/A)	0.00
468.60	24.79	(N/A)	0.00
468.70	28.61	(N/A)	0.00
468.80	32.66	(N/A)	0.00
468.90	36.94	(N/A)	0.00
469.00	41.42	(N/A)	0.00
469.10	46.11	(N/A)	0.00
469.20	47.86	(N/A)	0.00

South Basin

Subsection: Composite Rating Curve
Label: Outlet#1

Return Event: 100 years
Storm Event:

Composite Outflow Summary

Water Surface Elevation (ft)	Flow (ft ³ /s)	Tailwater Elevation (ft)	Convergence Error (ft)
469.30	49.46	(N/A)	0.00
469.40	51.00	(N/A)	0.00
469.50	52.49	(N/A)	0.00
469.60	53.94	(N/A)	0.00
469.70	55.35	(N/A)	0.00
469.80	56.73	(N/A)	0.00
469.90	58.06	(N/A)	0.00
470.00	59.37	(N/A)	0.00
470.10	60.65	(N/A)	0.00
470.20	61.90	(N/A)	0.00
470.30	63.12	(N/A)	0.00
470.40	64.32	(N/A)	0.00
470.50	65.50	(N/A)	0.00
470.60	66.65	(N/A)	0.00
470.70	67.79	(N/A)	0.00
470.80	68.90	(N/A)	0.00
470.90	70.00	(N/A)	0.00
471.00	71.08	(N/A)	0.00
471.10	72.14	(N/A)	0.00
471.20	73.19	(N/A)	0.00
471.30	74.22	(N/A)	0.00
471.40	75.24	(N/A)	0.00
471.50	76.24	(N/A)	0.00
471.60	77.23	(N/A)	0.00
471.70	78.21	(N/A)	0.00
471.80	79.17	(N/A)	0.00
471.90	80.12	(N/A)	0.00
472.00	81.06	(N/A)	0.00
472.10	81.99	(N/A)	0.00
472.20	82.91	(N/A)	0.00
472.30	83.82	(N/A)	0.00
472.40	84.72	(N/A)	0.00
472.50	85.61	(N/A)	0.00
472.60	86.49	(N/A)	0.00
472.70	87.36	(N/A)	0.00
472.80	88.23	(N/A)	0.00
472.90	89.08	(N/A)	0.00
473.00	89.93	(N/A)	0.00
473.10	90.76	(N/A)	0.00
473.20	91.59	(N/A)	0.00
473.30	92.42	(N/A)	0.00
473.40	93.23	(N/A)	0.00
473.50	94.04	(N/A)	0.00

South Basin

Subsection: Composite Rating Curve
Label: Outlet#1

Return Event: 100 years
Storm Event:

Composite Outflow Summary

Water Surface Elevation (ft)	Flow (ft ³ /s)	Tailwater Elevation (ft)	Convergence Error (ft)
473.60	94.84	(N/A)	0.00
473.70	95.63	(N/A)	0.00
473.80	96.42	(N/A)	0.00
473.90	97.20	(N/A)	0.00
474.00	97.98	(N/A)	0.00

Contributing Structures

[illegible]

South Basin

Subsection: Composite Rating Curve
Label: Outlet#1

Return Event: 100 years
Storm Event:

Composite Outflow Summary

Contributing Structures
0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice

South Basin

Subsection: Composite Rating Curve
Label: Outlet#1

Return Event: 100 years
Storm Event:

Composite Outflow Summary

Contributing Structures
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice

South Basin

Subsection: Composite Rating Curve
Label: Outlet#1

Return Event: 100 years
Storm Event:

Composite Outflow Summary

[illegible]

South Basin

Subsection: Composite Rating Curve
Label: Outlet#1

Return Event: 100 years
Storm Event:

Composite Outflow Summary

[illegible]

South Basin

Subsection: Composite Rating Curve
Label: Outlet#1

Return Event: 100 years
Storm Event:

Composite Outflow Summary

[illegible]

South Basin

Subsection: Composite Rating Curve
Label: Outlet#1

Return Event: 100 years
Storm Event:

Composite Outflow Summary

Contributing Structures
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice
1-Lowflow orifice + 2-Midflow orifice + Riser - 1 + 0-Underdrain orifice

South Basin

Subsection: Elevation-Volume-Flow Table (Pond)

Return Event: 100 years

Label: 1

Storm Event:

Infiltration	
Infiltration Method (Computed)	No Infiltration
Initial Conditions	
Elevation (Water Surface, Initial)	460.80 ft
Volume (Initial)	0.000 ac-ft
Flow (Initial Outlet)	0.00 ft ³ /s
Flow (Initial Infiltration)	0.00 ft ³ /s
Flow (Initial, Total)	0.00 ft ³ /s
Time Increment	1.000 min

Elevation (ft)	Outflow (ft ³ /s)	Storage (ac-ft)	Area (ft ²)	Infiltration (ft ³ /s)	Flow (Total) (ft ³ /s)	2S/t + O (ft ³ /s)
460.80	0.00	0.000	10.000	0.00	0.00	0.00
460.90	0.00	0.000	10.000	0.00	0.00	0.03
461.00	0.00	0.000	10.000	0.00	0.00	0.07
461.05	0.00	0.000	10.000	0.00	0.00	0.08
461.10	0.01	0.000	10.000	0.00	0.01	0.11
461.20	0.05	0.000	10.000	0.00	0.05	0.19
461.30	0.13	0.000	10.000	0.00	0.13	0.30
461.40	0.25	0.000	10.000	0.00	0.25	0.45
461.50	0.38	0.000	10.000	0.00	0.38	0.62
461.60	0.52	0.000	10.000	0.00	0.52	0.78
461.70	0.60	0.000	10.000	0.00	0.60	0.90
461.80	0.67	0.000	10.000	0.00	0.67	1.00
461.90	0.73	0.000	10.000	0.00	0.73	1.10
462.00	0.79	0.000	10.000	0.00	0.79	1.19
462.10	0.85	0.000	10.000	0.00	0.85	1.28
462.20	0.90	0.000	10.000	0.00	0.90	1.36
462.30	0.95	0.000	10.000	0.00	0.95	1.45
462.40	0.99	0.000	10.000	0.00	0.99	1.52
462.50	1.04	0.000	10.000	0.00	1.04	1.60
462.60	1.08	0.000	10.000	0.00	1.08	1.68
462.70	1.12	0.000	10.000	0.00	1.12	1.75
462.80	1.16	0.000	10.000	0.00	1.16	1.82
462.90	1.20	0.000	10.000	0.00	1.20	1.90
463.00	1.23	0.001	10.000	0.00	1.23	1.97
463.10	1.27	0.001	10.000	0.00	1.27	2.03
463.20	1.30	0.001	10.000	0.00	1.30	2.10
463.30	1.34	0.001	10.000	0.00	1.34	2.17
463.40	1.37	0.001	10.000	0.00	1.37	2.24
463.50	1.40	0.001	10.000	0.00	1.40	2.30

South Basin

Subsection: Elevation-Volume-Flow Table (Pond)

Return Event: 100 years

Label: 1

Storm Event:

Elevation (ft)	Outflow (ft ³ /s)	Storage (ac-ft)	Area (ft ²)	Infiltration (ft ³ /s)	Flow (Total) (ft ³ /s)	2S/t + O (ft ³ /s)
463.60	1.43	0.001	10.000	0.00	1.43	2.37
463.70	1.46	0.001	10.000	0.00	1.46	2.43
463.80	1.49	0.037	46,285.000	0.00	1.49	54.66
463.90	1.52	0.143	46,544.013	0.00	1.52	209.40
464.00	1.55	0.250	46,803.749	0.00	1.55	365.01
464.10	1.58	0.358	47,064.208	0.00	1.58	521.48
464.20	1.61	0.466	47,325.389	0.00	1.61	678.83
464.30	1.64	0.575	47,587.293	0.00	1.64	837.04
464.40	1.70	0.685	47,849.920	0.00	1.70	996.16
464.50	1.80	0.795	48,113.269	0.00	1.80	1,156.21
464.60	1.91	0.906	48,377.341	0.00	1.91	1,317.14
464.70	1.99	1.017	48,642.136	0.00	1.99	1,478.91
464.80	2.06	1.129	48,907.654	0.00	2.06	1,641.56
464.90	2.12	1.242	49,173.894	0.00	2.12	1,805.09
465.00	2.18	1.355	49,440.857	0.00	2.18	1,969.51
465.10	2.23	1.469	49,708.543	0.00	2.23	2,134.81
465.20	2.28	1.583	49,976.951	0.00	2.28	2,301.01
465.30	2.33	1.698	50,246.082	0.00	2.33	2,468.09
465.40	2.38	1.814	50,515.936	0.00	2.38	2,636.08
465.50	2.43	1.930	50,786.512	0.00	2.43	2,804.96
465.60	2.47	2.047	51,057.812	0.00	2.47	2,974.75
465.70	2.52	2.165	51,329.834	0.00	2.52	3,145.44
465.80	2.56	2.283	51,602.578	0.00	2.56	3,317.03
465.90	2.60	2.401	51,876.045	0.00	2.60	3,489.54
466.00	2.64	2.521	52,150.235	0.00	2.64	3,662.96
466.10	2.68	2.641	52,425.148	0.00	2.68	3,837.29
466.20	2.72	2.762	52,700.784	0.00	2.72	4,012.54
466.30	2.76	2.883	52,977.142	0.00	2.76	4,188.71
466.40	2.85	3.005	53,254.223	0.00	2.85	4,365.85
466.50	3.05	3.127	53,532.026	0.00	3.05	4,544.02
466.60	3.33	3.251	53,810.552	0.00	3.33	4,723.21
466.70	3.68	3.374	54,089.801	0.00	3.68	4,903.40
466.80	4.10	3.499	54,369.773	0.00	4.10	5,084.58
466.90	4.56	3.624	54,650.467	0.00	4.56	5,266.74
467.00	5.05	3.750	54,931.884	0.00	5.05	5,449.87
467.10	5.34	3.876	55,214.024	0.00	5.34	5,633.74
467.20	5.61	4.003	55,496.887	0.00	5.61	5,818.52
467.30	5.86	4.131	55,780.472	0.00	5.86	6,004.23
467.40	6.09	4.259	56,064.780	0.00	6.09	6,190.87
467.50	6.31	4.389	56,349.810	0.00	6.31	6,378.45
467.60	6.52	4.518	56,635.564	0.00	6.52	6,566.97
467.70	6.72	4.649	56,922.039	0.00	6.72	6,756.43
467.80	6.91	4.780	57,209.238	0.00	6.91	6,946.84

South Basin

Subsection: Elevation-Volume-Flow Table (Pond)

Return Event: 100 years

Label: 1

Storm Event:

Elevation (ft)	Outflow (ft ³ /s)	Storage (ac-ft)	Area (ft ²)	Infiltration (ft ³ /s)	Flow (Total) (ft ³ /s)	2S/t + O (ft ³ /s)
467.90	7.09	4.911	57,497.160	0.00	7.09	7,138.20
468.00	8.16	5.044	57,785.804	0.00	8.16	7,331.41
468.10	9.97	5.177	58,075.171	0.00	9.97	7,526.31
468.20	12.25	5.310	58,365.260	0.00	12.25	7,722.67
468.30	14.92	5.445	58,656.072	0.00	14.92	7,920.37
468.40	17.92	5.580	58,947.607	0.00	17.92	8,119.38
468.50	21.22	5.715	59,239.865	0.00	21.22	8,319.65
468.60	24.79	5.852	59,532.845	0.00	24.79	8,521.18
468.70	28.61	5.989	59,826.548	0.00	28.61	8,723.93
468.80	32.66	6.126	60,120.974	0.00	32.66	8,927.90
468.90	36.94	6.265	60,416.122	0.00	36.94	9,133.07
469.00	41.42	6.404	60,711.994	0.00	41.42	9,339.43
469.10	46.11	6.543	61,008.587	0.00	46.11	9,546.98
469.20	47.86	6.684	61,305.904	0.00	47.86	9,752.59
469.30	49.46	6.825	61,603.943	0.00	49.46	9,959.04
469.40	51.00	6.967	61,902.705	0.00	51.00	10,166.43
469.50	52.49	7.109	62,202.190	0.00	52.49	10,374.76
469.60	53.94	7.252	62,502.397	0.00	53.94	10,584.05
469.70	55.35	7.396	62,803.327	0.00	55.35	10,794.30
469.80	56.73	7.540	63,104.980	0.00	56.73	11,005.52
469.90	58.06	7.686	63,407.356	0.00	58.06	11,217.71
470.00	59.37	7.832	63,710.454	0.00	59.37	11,430.88
470.10	60.65	7.978	64,014.275	0.00	60.65	11,645.04
470.20	61.90	8.126	64,318.818	0.00	61.90	11,860.17
470.30	63.12	8.274	64,624.085	0.00	63.12	12,076.30
470.40	64.32	8.422	64,930.074	0.00	64.32	12,293.42
470.50	65.50	8.572	65,236.785	0.00	65.50	12,511.55
470.60	66.65	8.722	65,544.220	0.00	66.65	12,730.67
470.70	67.79	8.873	65,852.377	0.00	67.79	12,950.80
470.80	68.90	9.024	66,161.257	0.00	68.90	13,171.93
470.90	70.00	9.176	66,470.859	0.00	70.00	13,394.08
471.00	71.08	9.329	66,781.185	0.00	71.08	13,617.25
471.10	72.14	9.483	67,092.233	0.00	72.14	13,841.44
471.20	73.19	9.637	67,404.003	0.00	73.19	14,066.64
471.30	74.22	9.792	67,716.497	0.00	74.22	14,292.87
471.40	75.24	9.948	68,029.713	0.00	75.24	14,520.14
471.50	76.24	10.105	68,343.652	0.00	76.24	14,748.43
471.60	77.23	10.262	68,658.313	0.00	77.23	14,977.75
471.70	78.21	10.420	68,973.697	0.00	78.21	15,208.12
471.80	79.17	10.579	69,289.804	0.00	79.17	15,439.52
471.90	80.12	10.738	69,606.634	0.00	80.12	15,671.97
472.00	81.06	10.898	69,924.186	0.00	81.06	15,905.46
472.10	81.99	11.059	70,242.461	0.00	81.99	16,140.00

South Basin

Subsection: Elevation-Volume-Flow Table (Pond)

Return Event: 100 years

Label: 1

Storm Event:

Elevation (ft)	Outflow (ft ³ /s)	Storage (ac-ft)	Area (ft ²)	Infiltration (ft ³ /s)	Flow (Total) (ft ³ /s)	2S/t + O (ft ³ /s)
472.20	82.91	11.221	70,561.459	0.00	82.91	16,375.59
472.30	83.82	11.383	70,881.179	0.00	83.82	16,612.24
472.40	84.72	11.546	71,201.622	0.00	84.72	16,849.94
472.50	85.61	11.710	71,522.788	0.00	85.61	17,088.71
472.60	86.49	11.875	71,844.677	0.00	86.49	17,328.53
472.70	87.36	12.040	72,167.288	0.00	87.36	17,569.42
472.80	88.23	12.206	72,490.622	0.00	88.23	17,811.38
472.90	89.08	12.373	72,814.678	0.00	89.08	18,054.41
473.00	89.93	12.540	73,139.458	0.00	89.93	18,298.51
473.10	90.76	12.709	73,464.960	0.00	90.76	18,543.69
473.20	91.59	12.878	73,791.185	0.00	91.59	18,789.95
473.30	92.42	13.047	74,118.132	0.00	92.42	19,037.29
473.40	93.23	13.218	74,445.802	0.00	93.23	19,285.71
473.50	94.04	13.389	74,774.195	0.00	94.04	19,535.22
473.60	94.84	13.561	75,103.311	0.00	94.84	19,785.81
473.70	95.63	13.734	75,433.149	0.00	95.63	20,037.50
473.80	96.42	13.908	75,763.710	0.00	96.42	20,290.28
473.90	97.20	14.082	76,094.994	0.00	97.20	20,544.16
474.00	97.98	14.257	76,427.000	0.00	97.98	20,799.14

South Basin

Subsection: Level Pool Pond Routing Summary
Label: 1 (IN)

Return Event: 100 years
Storm Event:

Infiltration			
Infiltration Method (Computed)		No Infiltration	
Initial Conditions			
Elevation (Water Surface, Initial)		460.80 ft	
Volume (Initial)		0.000 ac-ft	
Flow (Initial Outlet)		0.00 ft³/s	
Flow (Initial Infiltration)		0.00 ft³/s	
Flow (Initial, Total)		0.00 ft³/s	
Time Increment		1.000 min	
Inflow/Outflow Hydrograph Summary			
Flow (Peak In)		152.20 ft³/s	Time to Peak (Flow, In)
Flow (Peak Outlet)		36.74 ft³/s	Time to Peak (Flow, Outlet)
			252.000 min
			265.000 min
Peak Conditions			
Elevation (Water Surface, Peak)		468.90 ft	
Volume (Peak)		6.258 ac-ft	
Mass Balance (ac-ft)			
Volume (Initial)		0.000 ac-ft	
Volume (Total Inflow)		9.098 ac-ft	
Volume (Total Infiltration)		0.000 ac-ft	
Volume (Total Outlet Outflow)		9.098 ac-ft	
Volume (Retained)		0.000 ac-ft	
Volume (Unrouted)		0.000 ac-ft	
Error (Mass Balance)		0.0 %	

South Basin

Index

1

1 (Elevation-Area Volume Curve)...

1 (Elevation-Area Volume Curve, 100 years)...4

1 (Elevation-Volume-Flow Table (Pond))...

1 (Elevation-Volume-Flow Table (Pond), 100 years)...18, 19, 20, 21

1 (IN) (Level Pool Pond Routing Summary)...

1 (IN) (Level Pool Pond Routing Summary, 100 years)...22

C

CM-1 (Read Hydrograph)...

CM-1 (Read Hydrograph, 100 years)...3

M

Master Network Summary...2

O

Outlet#1 (Composite Rating Curve)...


Outlet#1 (Composite Rating Curve, 100 years)...8, 9, 10, 11, 12, 13, 14, 15, 16, 17

Outlet#1 (Outlet Input Data)...

Outlet#1 (Outlet Input Data, 100 years)...5, 6, 7

APPENDIX 3

Drainage Exhibit



SCALE 1" = 60'

NOTE: SUPPLEMENTAL TOPOGRAPHY IS 2-FT CONTOURS FROM SANGIS (1997, BEFORE SR 905 WAS BUILT)

LEGEND

PROPERTY BOUNDARY	--- --	HYDROLOGY NODE	⬮
DRAINAGE SUBAREA	▬	AREA FROM UPSTREAM TO DOWNSTREAM NODE	(X.XX AC)
FLOW DIRECTION	→		

SCALE: 1"=60'
JOB #: 2357.60
CREATED: 8/7/19

PREPARED BY:
PROJECT DESIGN CONSULTANTS
Planning | Landscape Architecture | Engineering | Survey
701 B Street, Suite 800
San Diego, CA 92101
619.235.9471 Tel
619.234.0349 Fax

CITY OF SAN DIEGO
LUMINA III
DRAINAGE MAP
PROPOSED CONDITIONS
EXHIBIT B

Project Name:

Attachment 6

Geotechnical and Groundwater Investigation Report

Attach project's geotechnical and groundwater investigation report. Refer to Appendix C.4 to determine the reporting requirements.

Refer to Lumina SWQMP (PTS # 555609)