CULTURAL RESOURCE TESTING FOR THE ECO-BLÖK RESIDENCES PROJECT AT 3977 SHASTA STREET CITY OF SAN DIEGO, CALIFORNIA (Project No. 530514)

Prepared for:

Mr. Ian Gill PFP Coastal Holdings, LLC 4380 La Jolla Village Drive, Suite 250 San Diego, CA 92122

Prepared by:

Laguna Mountain Environmental, Inc. 7969 Engineer Road, Suite 208 San Diego, CA 92111

> Andrew R. Pigniolo, RPA Carol Serr

> > February 2017

National Archaeological Data Base Information *Type of Study:* Cultural Resource Test and Evaluation *Sites:* CA-SDI-11571 (SDM-W-166) *USGS Quadrangle:* La Jolla 7.5' *Area:* 1.7 acres *Key Words:* City of San Diego, Crown Point, 3977 Shasta Street, Shell, CA-SDI-11571, Survey and Test Program

.

TABLE OF CONTENTS

Section	0 <u>n</u>		<u>Page</u>		
ABS	ΓRAC'	Т	iii		
I.	INT	1			
	A.	Project Description	1		
	B.	Project Personnel			
	C.	Structure of the Report			
II.	NAT	FURAL AND CULTURAL SETTING	7		
	A.	Natural Setting	7		
	B.	Cultural Setting			
	C.	Prior Research			
	D.	Native American Consultation/Participation			
III.	RESEARCH DESIGN AND METHODS				
	A.	Research Design			
	B.	Survey Methods			
	C.	Test Methods			
IV.	SURVEY AND TEST RESULTS		16		
	A.	Survey Results			
	В.	Testing Results			
V.	SUN	MMARY AND RECOMMENDATIONS	23		
VI.	REFERENCES				
APPI	ENDIC	CES			
	A.	Resume of Principal Investigator			
	B.	Records Search Confirmation			

- Native American Correspondence Catalogue Photographs and Photo Logs C.
- D.
- E.

LIST OF FIGURES

<u>Number</u>	Title	Page
1	Regional Location Map	2
2	Project Location	3
3	Project Location as Shown on City of San Diego 1:800 Scale Map	
4	Project Plan	
5	Project Overviews	17
6	Concrete Slab	
7	STP Locations	19

LIST OF TABLES

<u>Number</u>	Title	Page
1	Archaeological Investigations within One-quarter Mile of the Project Area	12
2	STP Recovery Summary by Provenience	21

ABSTRACT

Laguna Mountain Environmental, Inc. (Laguna Mountain) conducted an archaeological survey and test at a 1.7-acre parcel located at 3977 Shasta Street. This property has been previously mapped within prehistoric archaeological site CA-SDI-11571 in the Crown Point area of the City of San Diego. The proposed project involves demolishing the existing residential structures and community garden to construct 31 new single-family residences. The archaeological investigation included a records search, literature review, examination of historic maps, field inventory of the property, and subsequent testing.

The goal of the testing effort was to determine if significant portions of prehistoric site CA-SDI-11571 extended within the project area that would be impacted by the project. The current testing and evaluation program was conducted in accordance with the California Environmental Quality Act (CEQA) and the City of San Diego Land Development Code and Historical Resources Guidelines. The City of San Diego will serve as lead agency for the project and CEQA compliance.

A records search was conducted at the South Coastal Information Center at San Diego State University. The record search concluded that the project area had not been previously surveyed, but that at least 12 cultural resource investigations have been conducted within one-quarter mile of the project area. Only one prehistoric cultural resource has been identified through previous research within the one-quarter mile radius of the project. The project area is located within the northern end of the previously recorded boundary of site CA-SDI-11571 (SDM-W-166). The site boundary encompasses a large area, including most of Crown Point, and consists of activity areas within a large sparse marine shell scatter. Two historic structures are also previously recorded within one-quarter mile of the project area. One of the structures is a 1930-built residence at 3776 Shasta Street (P-37-017087); another residence, located at 3976 Lamont Street (P-37-018885), was built in 1942.

The survey and test was conducted by Andrew R. Pigniolo, MA, on February 7 and 8, 2017. Mr. Gabe Kitchen, of Red Tail Monitoring and Research, Inc., served as Native American monitor. The entire project area was surveyed in less than 5-meter transect intervals. Approximately 40 percent of the property was covered by the existing residential structures and hardscape. Within the lawn area and unlandscaped areas of the property, surface visibility was fair to moderate, averaging approximately 40 percent. The testing program included the excavation of 20 Shovel Test Pits (STPs) distributed over the entire project area.

The results of this survey indicated that no significant prehistoric cultural material was present on the surface of the property. Very small quantities (less than 10 pieces) of sparse shell was observed along the eastern side of the property. No associated prehistoric artifacts were observed. The southern portion of the project area includes a concrete slab foundation of a historic-age structure (EBR-H-1). This slab foundation has few features and appears to represent the base of a World War II era multi-family housing unit.

Testing resulted in the recovery of several pieces of weathered marine shell totaling 5 grams (g) that may be cultural in origin. The remainder of the material recovered during testing appears to be modern in age. It includes composted faunal bone, concrete, asphalt, flooring tiles, terra cotta fragments, plastic items, and bottle and window glass fragments. The near absence of cultural material suggests that the project area does not include significant portions of site CA-SDI-11571.

No significant impacts to cultural resources are anticipated to result from the proposed development. Significant portions of site CA-SDI-11571 were not identified within the project area during the survey and testing program. The historic-age slab foundation (EBR-H-1) does not contain additional information potential and does not qualify as a significant cultural resource based on CEQA and City of San Diego Land Development Code criteria. No further treatment is recommended for EBR-H-1.

Because the testing was limited in depth and the project is within the mapped boundary of CA-SDI-11571, monitoring by an archaeological and a Native American monitor is recommended during construction excavation and grading to ensure unidentified sensitive resources are not present or impacted by the project.

I. INTRODUCTION

A. Project Description

The 1.7-acre project area is located in the southwestern portion San Diego County within the Crown Point area in the City of San Diego (Figure 1). It is located west of Interstate 5, east of Ingraham Street, and south of Grand Avenue on the eastern side of Crown Point. The project consists of the residential lots at 3977 Shasta Street (APNs 424-482-14-00 and 424-532-25-00). The project is located in an unsectioned portion of Pueblo Lands in Township 16 South, Range 3 West. The project area is shown on the La Jolla USGS 7.5' Quadrangle (Figure 2) and on the City of San Diego 1:800 scale maps (Figure 3).


The proposed project includes the demolition of existing residential structures and construction of 31 houses on individual lots (Figure 4). As part of the project demolition and construction, removal of existing foundations and grading and excavation for new foundations and utilities will occur.


Cultural resource work was conducted in accordance with the California Environmental Quality Act (CEQA), and the City of San Diego Land Development Code and Historical Resources Guidelines. The City of San Diego will serve as lead agency for the project and CEQA compliance. The survey and testing program was conducted to determine if the project was within as portion of site CA-SDI-11571 that might be eligible for inclusion in the California Register of Historic Resources (California Register) or significant under CEQA.

B. Project Personnel

The cultural resource testing and evaluation program was conducted by Laguna Mountain Environmental, Inc. (Laguna Mountain), whose cultural resources personnel meet state and local requirements. Mr. Andrew Pigniolo served as Principal Investigator for the project in addition to field surveyor and report author. Mr. Pigniolo is a member of the Register of Professional Archaeologists (RPA), and meets the Secretary of the Interior's standards for qualified archaeologists. He is also a qualified archaeologist within the City of San Diego. Mr. Pigniolo has a M.A. degree in Anthropology from San Diego State University, along with 36 years experience in southern California archaeology. His resume is included in Appendix A.

Ms. Carol Serr conducted the records search, prepared the report graphics, catalogued the recovered material, and formatted the report. She has a B.A. in Anthropology from San Diego State University and more than 36 years of experience in San Diego archaeology. Mr. Gabe Kitchen, representative of Red Tail Monitoring and Research, Inc. (Red Tail), served the project as Native American Monitor and has more than five years of experience.





I L








Figure 2 Project Location



Laguna *N*




SOURCE: City of San Diego Engineering and Development Map Book 1989: Sheets 226-1689



Figure 3 Project Location as Shown on City of San Diego 1:800 Scale Map





C. Structure of the Report

This report follows the State Historic Preservation Office's guidelines for Archaeological Resource Management Reports (ARMR). The report introduction provides a description of the project and associated personnel. Section II provides background on the project area and previous research. Section III describes the research design and field methods, while Section IV describes the results of the survey and testing program. Section V provides a summary and recommendations, and Section VI includes the references cited.

II. NATURAL AND CULTURAL SETTING

The following environmental and cultural background provides a context for the cultural resource inventory.

A. Natural Setting

The project area is located in the western portion of San Diego County on Crown Point adjacent to Mission Bay. The property is situated on a relatively flat and low marine terrace on the east side of Crown Point, with the bluff overlooking Mission Bay less than 100 m southeast. The property is developed with a multi-family residential facility in the northern parcel and a community garden space in the southern parcel. Elevation is approximately 40 feet above mean sea level.

The geomorphology of the project area is largely a product of the region's geologic history. During the Jurassic and late Cretaceous (>100 million years ago) a series of volcanic islands paralleled the current coastline in the San Diego region. The remnants of these islands stand as Mount Helix, Black Mountain, and the Jamul Mountains among others. This island arc of volcanoes spewed out vast layers of tuff (volcanic ash) and breccia that have since been metamorphosed into hard rock of the Santiago Peak Volcanic formation. These fine-grained rocks provided a regionally important resource for Native American flaked stone tools.

At about the same time, a granitic and gabbroic batholith was being formed under and east of these volcanoes. This batholith was uplifted and forms the granitic rocks and outcrops of the Peninsular Range and the foothills to the west. In San Diego County the large and varied crystals of these granitic rocks provided particularly good abrasive surfaces for Native American seed processing. These outcrops were frequently used for bedrock milling of seeds. The batholith contains numerous pegmatite dikes. This was a good source of quartz, a material used by Native Americans for flaked stone tools and ceremonial purposes.

As the Peninsular Batholith rose, it warped and metamorphosed the overlying sediments, forming the Julian Schist (Remeika and Lindsay 1992). This formation contains quartzite, a material also used for Native American flaked stone tools. Its relatively poor flaking qualities made this quartzite less popular for tool making than the quartz and Santiago Peak materials.

During the Eocene, a series of marine transgressions and regressions along with sediment and rock deposition from major river systems to the east left behind a series of sandstone, shale, and conglomerate formations. These sedimentary rocks were later flattened by marine erosion to form the current coastal plain and mesas in the San Diego region.

The Bay Point Formation immediately underlies the project area (Kennedy 1975). It is composed of marine and non-marine, poorly consolidated, fine to medium grained, pale brown, fossiliferous sandstone, siltstone, and conglomerate. The Bay Point Formation was laid down on the marine cut Nestor Terrace during the late Pleistocene Sangamon interglacial high sea stand dating to $120,000\pm10,000$ years ago (Kennedy and Tan 1977). Portions of this formation include conglomerate of reworked porphyritic volcanic and quartzite cobble clasts from other nearby Eocene strata that that would be useful for Native Americans.

Soil types in the project area are mapped as Urban Lands where soil classification was not possible due to development. The Huerhuero-urban land complex is mapped to the northeast of the project (Bowman 1973). The Huerhuero series soils consist of moderately well drained loams that have clay subsoil Bowman 1973). These soils developed in sandy marine sediments. In a representative profile the surface layer is brown and pale-brown, strongly acid and medium acid loam about 12 inches thick. The upper part of the subsoil is brown, moderately alkaline clay. It extends to a depth of about 41 inches. Below this, and extending to a depth of more than 60 inches, is brown, mildly alkaline clay loam and sandy loam (Bowman 1973).

The climate of western San Diego County can generally be described as Mediterranean, with cool wet winters and hot dry summers. The coastal plain itself qualifies as a semiarid steppe because it receives only an average of 10 inches (25 cm) of rainfall a year (Pryde 1976). This limits vegetation growth to seasonal or drought tolerant species. The project area was probably dominated in the past by coastal sage scrub vegetation including such species as buckwheat, and various shrubs. Components of this community provided important resources to Native Americans in the region. Sage seed, yucca, buckwheat, acorns, and native grasses formed important food resources to Late Prehistoric Native Americans.

Prior to development, this area would have been rich in natural resources. Animal resources in the region included deer, fox, raccoon, skunk, bobcats, coyotes, rabbits, and various rodent, reptile, and bird species. Small game, dominated by rabbits, was relatively abundant. The various estuaries located along the bay would have provided a variety of plant and animal resources to the region. The close proximity of the bay would have made the location ideal for procuring fish, shellfish, and sea mammals. Rose Creek, which historically flowed west of its current channel, would have provided a seasonal water supply to the area in prehistoric times.

B. Cultural Setting

Paleoindian Period

The earliest well documented prehistoric sites in southern California are identified as belonging to the Paleoindian period, which has locally been termed the San Dieguito complex/tradition. The Paleoindian period is thought to have occurred between 9,000 years ago, or earlier, and 8,000 years ago in this region. Although varying from the well-defined fluted point complexes such as Clovis, the San Dieguito complex is still seen as a hunting-focused economy with limited use of seed grinding technology. The economy is generally seen to focus on highly ranked resources such as large mammals and relatively high mobility, which may be related to following large game. Archaeological evidence associated with this period has been found around inland dry lakes, on old terrace deposits of the California desert, and also near the coast where it was first documented at the Harris Site.

Early Archaic Period

Native Americans during the Archaic period had a generalized economy that focused on hunting and gathering. In many parts of North America, Native Americans chose to replace this economy with types based on horticulture and agriculture. Coastal southern California economies remained largely based on wild resource use until European contact (Willey and Phillips 1958). Changes in hunting technology and other important elements of material culture have created two distinct subdivisions within the Archaic period in southern California.

The Early Archaic period is differentiated from the earlier Paleoindian period by a shift to a more generalized economy and an increased focus on the use of grinding and seed processing technology. At sites dated between approximately 8,000 and 1,500 years before present (B.P.), the increased use of groundstone artifacts and atlatl dart points, along with a mixed core-based tool assemblage, identify a range of adaptations to a more diversified set of plant and animal resources. Variations of the Pinto and Elko series projectile points, large bifaces, manos and portable metates, core tools, and heavy use of marine invertebrates in coastal areas are characteristic of this period, but many coastal sites show limited use of diagnostic atlatl points. Major changes in technology within this relatively long chronological unit appear limited. Several scientists have considered changes in projectile point styles and artifact frequencies within the Early Archaic period to be indicative of population movements or units of cultural change (Moratto 1984), but these units are poorly defined locally due to poor site preservation.

Late Archaic or Late Prehistoric Period

Around 2,000 B.P., Yuman-speaking people from the eastern Colorado River region began migrating into southern California, representing what is called the Late Prehistoric Period. The Late Prehistoric Period in San Diego County is recognized archaeologically by smaller projectile points, the replacement of flexed inhumations with cremation, the introduction of ceramics, and an emphasis on inland plant food collection and processing, especially acorns (True 1966). Inland semi-sedentary villages were established along major watercourses, and montane areas were seasonally occupied to exploit acorns and piñon nuts, resulting in permanent milling features on bedrock outcrops. Mortars for acorn processing increased in frequency relative to seed grinding basins. This period is known archaeologically in southern San Diego County as the Yuman (Rogers 1945) or the Cuyamaca Complex (True 1970).

The Kumeyaay (formerly referred to as Diegueño) who inhabited the southern region of San Diego County, western and central Imperial County, and northern Baja California (Almstedt 1982; Gifford 1931; Hedges 1975; Luomala 1976; Shipek 1982; Spier 1923) are the direct descendants of the early Yuman hunter-gatherers. Kumeyaay territory encompassed a large and diverse environment, which included marine, foothill, mountain, and desert resource zones. Their language is a dialect of the Yuman language, which is related to the large Hokan super family.

There seems to have been considerable variability in the level of social organization and settlement variance. The Kumeyaay were organized by patrilineal, patrilocal lineages that claimed prescribed territories, but did not own the resources except for some minor plants and eagle aeries (Luomala 1976; Spier 1923). Some lineages occupied procurement ranges that required considerable residential mobility, such as those in the deserts (Hicks 1963). In the mountains, some of the larger groups occupied a few large residential bases that would be occupied biannually, such as those occupied in Cuyamaca in the summer and fall, and in Guatay or Descanso during the rest of the year (Almstedt 1982; Rensch 1975). According to Spier (1923), many Eastern Kumeyaay spent the period of time from spring through autumn in larger residential bases in the upland procurement ranges, and wintered in mixed groups in residential bases along the eastern foothills on the edge of the desert (i.e., Jacumba and Mountain Springs). This variability in settlement mobility and organization reflects the great range of environments in the territory.

Acorns were the single most important food source used by the Kumeyaay. Their villages were usually located near water, which was necessary for leaching acorn meal. Other storable resources such as mesquite or agave were equally valuable to groups inhabiting desert areas, at least during certain seasons (Hicks 1963; Shackley 1984). Seeds from grasses, manzanita, sage, sunflowers, lemonade berry, chia, and other plants were also used along with various wild greens and fruits. Deer, small game, and birds were hunted and fish and marine foods were eaten. Houses were arranged in the village without apparent pattern. The houses in primary villages were conical structures covered with tule bundles, having excavated floors and central hearths. Houses constructed at the mountain camps generally lacked any excavation, probably due to the summer occupation. Other structures included sweathouses, ceremonial enclosures, armadas, and acorn granaries. The material culture included ceramic cooking and storage vessels, baskets, flaked lithic and ground stone tools, arrow shaft straighteners, stone, bone, and shell ornaments.

Hunting implements included the bow and arrow, curved throwing sticks, nets and snares. Shell and bone fishhooks, as well as nets, were used for fishing. Lithic materials including quartz and metavolcanics were commonly available throughout much of the Kumeyaay territory. Other lithic resources, such as obsidian, chert, chalcedony, and steatite, occur in more localized areas and were acquired through direct procurement or exchange. Projectile points including the Cottonwood Series points and Desert Side-notched points were commonly produced.

Kumeyaay culture and society remained stable until the advent of missionization and displacement by Hispanic populations during the eighteenth century. The effects of missionization, along with the introduction of European diseases, greatly reduced the native population of southern California. By the early 1820s, California was under Mexico's rule. The establishment of ranchos under the Mexican land grant program further disrupted the way of life of the native inhabitants.

Ethnohistoric Period

The Ethnohistoric period refers to a brief period when Native American culture was initially being affected by Euroamerican culture and historical records on Native American activities were limited. When the Spanish colonists began to settle California, the project area was within the territory of a loosely integrated cultural group historically known as the Kumeyaay or Northern and Southern Diegueño because of their association with the San Diego Mission. The Kumeyaay as a whole speak a Yuman language, which differentiates them from the Luiseño, who speak a Takic language to the north (Kroeber 1976). Both of these groups were huntergatherers with highly developed social systems. European contact introduced diseases that dramatically reduced the Native American population and helped to break down cultural institutions. The transition to a largely Euroamerican lifestyle occurred relatively rapidly in the nineteenth century.

Historic Period

Cultural activities within San Diego County between the late 1700s and the present provide a record of Native American, Spanish, Mexican, and American control, occupation, and land use. An abbreviated history of San Diego County is presented for the purpose of providing a background on the presence, chronological significance, and historical relationship of cultural resources within the county.

Native American control of the southern California region ended in the political views of western nations with Spanish colonization of the area beginning in 1769. De facto Native American control of the majority of the population of California did not end until several decades later. In southern California, Euroamerican control was firmly established by the end of the Garra uprising in the early 1850s (Phillips 1975).

The Spanish Period (1769-1821) represents a period of Euroamerican exploration and settlement. Dual military and religious contingents established the San Diego Presidio and the San Diego and San Luis Rey Missions. The Mission system used Native Americans to build a footing for greater European settlement. The Mission system also introduced horses, cattle, other agricultural goods and implements; and provided construction methods and new architectural styles. The cultural and institutional systems established by the Spanish continued beyond the year 1821, when California came under Mexican rule.

The Mexican Period (1821-1848) includes the retention of many Spanish institutions and laws. The mission system was secularized in 1834, which dispossessed many Native Americans and increased Mexican settlement. After secularization, large tracts of land were granted to individuals and families and the rancho system was established. Cattle ranching dominated other agricultural activities and the development of the hide and tallow trade with the United States increased during the early part of this period. The Pueblo of San Diego was established during this period and Native American influence and control greatly declined. The Mexican Period ended when Mexico ceded California to the United States after the Mexican-American War of 1846-48.

Soon after American control was established (1848-present), gold was discovered in California. The tremendous influx of American and Europeans that resulted quickly drowned out much of the Spanish and Mexican cultural influences and eliminated the last vestiges of de facto Native American control. Few Mexican ranchos remained intact because of land claim disputes and the homestead system increased American settlement beyond the coastal plain.

C. Prior Research

The investigation included archival research and other background studies prior to completing the field survey of the project area. The archival research consisted of conducting a literature and record search at the local archaeological repository, in addition to examining historic maps, and historic site inventories. This information was used to identify previously recorded resources and determine the types of resources that might occur in the survey area.

The records and literature search was conducted at the South Coastal Information Center (SCIC) at San Diego State University (Appendix B). The records search included a one-quarter mile radius of the project area to provide background on the types of sites that would be expected in the region. Access to historic maps and a historic address database was also provided by the SCIC.

At least 12 archaeological investigations have been documented in the vicinity of the project (Table 1). Most of these are surveys or monitoring projects for utility implementation and infrastructures associated with the growth and development of this area over the last 20 years.

Author	Report Title	Year	
Bissel	Cultural Resources Monitoring of the Mission Bay Sewage Inceptor System Phase 1 Project		
Case and Walker	Cultural Resources Monitoring Report for the Ortiz Water Group 501 Project (LDR. No.98-0928/W.O. No. 181501), Community of Pacific Beach, City of San Diego	2003	
Cooley	Report of Results of a Cultural Resource Testing Program for the Mission Bay Sewage Interceptor System, Phase V, City of San Diego		
Cooley	Report of Test Results of a Cultural Resource Testing Program for the Crown Point and Rose Creek Area of the Mission Bay Sewage Interceptor System, Phase V, City of San Diego, California, Dep. No. 90-0540		
Duke	Duke Cultural Resource Assessment Cingular Wireless Facility No. SD 471-02, San Diego County		
Gardner	Archaeological Monitoring of SDG&E Gas Residential Extension Project in Pacific Beach, 1811 Oliver Street, San Diego County, California		
Kyle	Cultural Resource Survey of a Parcel Located at 4014 Honeycutt Street, City of San Diego, California		
Olson, Gonzalez, Goodwin & Berryman	Archaeological Monitoring Results Report for Construction of Mission Bay Sewage Interceptor System, Phase 5, City of San Diego	1994	
Pigniolo	Pigniolo Cultural Resource Survey for the Kendall Street Residences Project at 3811 Kendall Street City of San Diego, California		
Pigniolo Cultural Resource Testing at a Portion of CA-SDI-11571 for the Kendall Street Residen Project at 3811 Kendall Street, City of San Diego, California		2013	
Smith	mith Results of an Archaeological Survey of Portions of the Phase 1 Locations for the Mission Bay Sewage Interceptor System		
Smith	Enhanced Cultural Resources Survey and Evaluation for the Lamont 5 Project, Pacific Beach, San Diego	2000	

 Table 1. Archaeological Investigations within One-quarter Mile of the Project Area

The three cultural resources identified by the previous investigations within the one-quarter mile radius include a large prehistoric site area (CA-SDI-11571/SDM-W-166) and two historic structures. One of the structures is a 1930-built residence at 3776 Shasta Street (P-37-017087); another residence, located at 3976 Lamont Street (P-37-018885), was built in 1942.

The site boundary for CA-SDI-11571 encompasses an expansive area including most of Crown Point that consists of activity areas within a large sparse marine shell scatter. CA-SDI-11571 was initially recorded in the 1920s by Malcolm Rogers of the San Diego Museum of Man. The dimensions of the site area were described as being 1 mile north/south by ¹/₂ mile east/west (Rogers n.d.). The site was described as intermittent camping along the estuary margin with scattered and discontinuous occupation.

Rogers noted:

Although scattered shell, spawls [sic] and a few artifacts occur all over this area under a veneer of Aeolian sands, the occupation is only condensed on the point and around the east side for a distance of 1/2 mile. The shell and charcoal content here even is low to medium in patches. The greatest midden depth found in trenches is 3' wide 8" [sic] of surface sand. One large acorn mortar was found here and a few metates; manos are more common. W. Dieguenos [Kumeyaay] carried water over here from Rose Canyon as late as 1890 to fish yet no sherds were found (Rogers n.d.). Carter describes the soils and stratigraphy of the Crown Point site in detail (Carter 1957). He again noted the diffuse nature of cultural material at the site. He also described a heath feature, isolated artifacts, and a burial within the site area. The burial location appears to be in the vicinity of Roosevelt Street and the bay edge. It was marked with two sandstone metates (Carter 1957).

The site was updated at the SCIC by Pigniolo in 1990, who observed a core tool and flakes associated with shell in the cliff face along the west side of Crown Point to a depth of at least 70 cm (Pigniolo 1990). Trenching in the Crown Point area identified shell, but not intact features (Cooley and Mitchell 1992). Shell and one flake, but no features were observed in monitoring at 3553 Bayonne Drive (Beddow 2001). Testing at 3315 Jewell Street identified shell and debitage in a disturbed context and no further excavation was recommended (Clowery-Moreno 2008). Testing at 3811 Kendall Street in the northeast portion of this large site recovered a minimal amount of debitage and two mano fragments along with faunal shell and bone within a disturbed context (Pigniolo 2013).

Historic research included an examination of a variety of resources. The current listings of the National Register of Historic Places were checked through the National Register of Historic Places website. The California Inventory of Historic Resources (State of California 1976) and the California Historical Landmarks (State of California 1992) were also checked for historic resources. The historic residences in the historic database, located on Shasta Street and Lamont Street, were both determined not significant. The existing project area was initially developed as military housing during the 1940s. The 1953 aerial photograph of the project area shows five multi-family housing structures within the project area (NETR 1953). These structures were removed before 1980 (NETR 1980). A single foundation slab from one of these structures remains in the southern portion of the project area.

D. Native American Consultation/Participation

Native American consultation and participation is an important aspect of the cultural resource evaluation process. To address the potential for Native American concerns, a Sacred Lands Search was conducted. A current Sacred Lands Search response from the California Native American Heritage Commission (NAHC) was received on February 6, 2017 (Appendix C). The results of the Sacred Lands Search were negative in that no resources have been previously identified in the immediate project area. Native American participation in the field survey and testing included the presence of Mr. Gabe Kitchen, of Red Tail, who served as Native American monitor.

III. RESEARCH DESIGN AND METHODS

A. Research Design

The goal of this study was to identify any cultural resources located within the project area so that the effects of the project on these resources can be assessed and minimized. To accomplish this goal, background information was examined and assessed, and a field survey was conducted to identify cultural remains. Additionally, a Sacred Lands record search was requested from the Native American Heritage Commission.

Based on the records search and historic map check, most of the cultural resources that might occur within the project were likely to be prehistoric resources. Historic structures appear within one-quarter mile of the project area on early maps of the area, but are unlikely to occur within the project itself based on early maps. Prehistoric cultural resources such as CA-SDI-11571 could include midden soils, shell and lithic scatters, and hearth features associated with marine and estuary utilization in the area. Special attention was given to naturally exposed soil deposits. Because the project area is developed and located on the margin of the mapped boundary of CA-SDI-11571, testing was required to establish whether archaeological deposits extend into the project area. Both phases of investigation are described in more detail below.

B. Survey Methods

The survey and test was conducted by Andrew R. Pigniolo, MA, on February 7 and 8, 2017. Mr. Gabe Kitchen, of Red Tail, served as Native American monitor. The entire project area was surveyed in less than 5-meter transect intervals. Approximately 40 percent of the property was covered by the existing residential structures and hardscape. Within the lawn area and unlandscaped areas of the property, surface visibility was fair to moderate, averaging approximately 40 percent.

Photographs taken and project records for this inventory will be temporarily curated at Laguna Mountain until final curation arrangements can be made at the San Diego Archaeological Center or another appropriate regional repository.

C. Test Methods

Subsurface testing was conducted in the project area in order to determine if portions of site CA-SDI-11571, or any other previously unrecorded site, were present within the project area. The subsurface testing included the excavation of twenty 30 m by 50 cm shovel test pits (STPs) in order to assess the presence of any subsurface deposits. Testing was conducted subsequent to the survey. Mr. Andrew Pigniolo served as Principal Investigator and Mr. Gabe Kitchen of Red Tail served the project as Native American monitor.

STPs are normally placed in the cardinal directions along a Cartesian grid pattern, but due to the amount of developed area on the property and the limited landscaped areas where soil was exposed, STPs were intuitively placed in open areas distributed across the proposed area of direct impacts. The long axis of each STP was oriented north/south.

STPs were excavated in 10-cm arbitrary levels. All excavated soil was passed through 1/8-inch mesh hardware cloth and dry-screened in the field. Any cultural material was removed from the screens and bagged by level. STP forms noting the recovery and observations were completed following the excavation of each 10-cm level. The information gathered included the type of cultural material recovered, soil types and conditions, and any noted disturbance. Recovered material was taken to the laboratory for processing. All items were weighed on a digital scale. The recovered material was sorted by material class and entered into an Excel spreadsheet that serves as the recovery catalog (Appendix D).

A photographic record was kept to document the testing program (Appendix E). A photographic log was kept to record orientation and subject matter.

IV. SURVEY AND TEST RESULTS

The northern portion of the project area is currently developed with a multi-unit residential facility and related landscaping with a large amount of hardscape and landscape. The southern parcel that makes up the project area previously served as a community garden. Figure 5 provides views of the site conditions.

A. Survey Results

The results of this survey indicated that no significant prehistoric cultural material was present on the surface of the property. A very small amount (less than 10 pieces) of sparse shell was observed along the eastern side of the property. These shell fragments were dominated by *Chione*, but *Argopecten* was also present. A single fragment of *Saxidomus* shell was also noted. All of the surface shell was observed in disturbed landscaping planters along the eastern side of the project area adjacent to the alley. No associated prehistoric artifacts were observed. The shell may or may not be associated with prehistoric activity in the area. It did appear weathered, but fill soil was also noted in the area. The near absence of cultural material suggests that the project area is not within the boundaries of site CA-SDI-11571 or that the site deposit was previously graded away or covered by fill in this area.

The southern portion of the project area includes a concrete slab foundation of a historic-age structure (EBR-H-1). This slab foundation has few features and appears to represent the base of a World War II era multi-family housing unit (Figure 6). Some associated hardscape concrete paths are also present. A rectangular open space within the north end of the slab, may also represent an opening for landscaping. The slab foundation is otherwise generally featureless, but includes some associated steps and has a few previously cut metal upright pieces embedded in the concrete.

The project area is approximately 40 percent covered by development and hardscape. While much of the area was open, lawns and dense weed growth reduced the visibility in undeveloped areas to less than 40 percent. Because the project area is highly developed and visibility was poor, the survey did not adequately serve to determine if cultural resources were present, therefore a testing program was subsequently implemented to identify whether there are any subsurface cultural deposits within the project area.

B. Testing Results

Because survey visibility was limited, and the project is located within the recorded boundaries of site CA-SDI-11571, 20 hand-excavated STPs were excavated within the project area in order to determine if CA-SDI-11571 deposits were present in the project area. Figure 7 shows the STP locations.

Testing indicated a relatively consistent pattern of fill material with pea gravel in the northern and northwestern portions of the project. This fill was underlain in many areas by what appears to be a native light orange-brown loamy sand. STPs were excavated in existing lawn areas and in the former community garden. Varying amounts of modern intrusive material were recovered from all of the STPs, from 0-40 cm, due to previous disturbance.



a. Existing Facilities, Looking Southeast (PR-05719-005)



b. Overgrown Community Garden, Looking South (PR-05720-032)

Figure 5 Site Overviews





a. Foundation Slab, Looking South (PR-05720-041)



b. Foundation Slab and Walkway, Looking West (PR-05720-042)

Figure 6 Concrete Slab








Figure 7 STP Locations



Soils and Stratigraphy

Soil in the STPs showed great variability, but also some patterns. STPs 6, 7, 9, 10, 11, 13, 17, 18, 19, and 20 showed the presence of fill over much of the northern portion of the project area. This fill was thicker in the northwestern portion of the project and often included pea gravel. It was thinner in the southern portions of the project and native soils were reached in most of the STPs, under the fill. Although the lawns may have been associated with a thin layer of imported topsoil, they did not appear to represent imported sod, but material grown on site. STPs 1, 2, 3, 4, 5, and 14 were dominated by native orange brown loam sand. Those STPs in the southern parcel (STPs 1 through 5), showed the addition of organic compost to the upper levels of soil. In addition to disturbance related to garden tilling, the five STPs in the southern parcel all showed evidence of significant bioturbation due to rodents. STPs 8, 12, 15, and 16 had a light brown loamy sand fill that often over laid the native loamy sand.

Most of the STPs were underlain or included native light orange-brown hued loamy sand below the upper fill layers. The sand included less organic material than the upper soil. Portions of the orange-brown sand suggested previous rodent and root disturbance. This light orange-brown sand was found from 5 to 40 cm in depth and probably extends much deeper than the test termination depth. The overall stratigraphic pattern suggests that imported fill was placed directly over native sandy soil.

STP Recovery

The excavation of 20 STPs resulted in the recovery of 5 grams (g) of faunal shell, 7.7 g of faunal bone, which appears to be intrusive, and 1,692.8 g of modern intrusive refuse (Table 2). Additionally, 2.7 g of terrestrial snail shell and 8.7 g of fossil shell were recovered.

The faunal shell came from five STPs, but primarily STP 2 (4.1 g). Types consist of mostly weathered pieces of *Argopecten* (scallop) and one fragment of *Chione* (clam), along with bits of barnacle and tube worm which would have been attached to the exterior of a larger shell. All but 0.3 g of this marine shell came from STPs located in the community garden area in the southernmost portion of the project. The presence of weathered *Argopecten* in STPs 14 and 16 indicates minimal activity in the northern portion of the project.

All of the recovered faunal bone came from the five STPs located within the garden area. While a few fish remains were found, the bone primarily is avian – probably chicken bone, both indicating modern deposition in the garden compost. The few pieces of whole small mammal bones most likely are from natural rodent death. No faunal bone was found in the tested portion of the project north of Roosevelt Avenue. The bone assemblage recovered during testing appears to represent a combination of activity from natural rodents and composting. None of the faunal bone is likely to be associated with prehistoric activity in the area.

The terrestrial snail remains consist of the European brown garden snail (*Cornu aspersum*, formerly *Helix aspersa*) and a predatory decollate snail (*Rumina decollate*). These snails are not burrowing animals but can find shelter in existing burrows or cracks in the soil, resulting in their presence to depths over 30 cm in excavations. Not surprisingly, snails were only found in the five STPs excavated in the community garden area.

	Material Class						
	Marine	Faunal	Modern	Terrestrial	Fossil		
STP No.	Shell	Bone*	Refuse	Snail	Shell	Total	Percent
1		0.2	7.1	0.5		7.8	0.5
2	4.1	4.0	6.0	0.6		14.7	0.9
3	0.5	2.0	58.9	0.4		61.8	3.6
4		1.3	5.1	0.9		7.3	0.4
5	0.1	0.2	82.0	0.3		82.6	4.8
6			280.6			280.6	16.3
7			122.6			122.6	7.1
8			50.2			50.2	2.9
9			30.4			30.4	1.8
10			16.9			16.9	1.0
11			0.7		8.7	9.4	0.5
12			50.0			50.0	2.9
13			151.5			151.5	8.8
14	0.1		185.3			185.4	10.8
15			42.2			42.2	2.5
16	0.2		72.1			72.3	4.2
17			78.2			78.2	4.6
18			2.4			2.4	0.1
19			412.5			412.5	24.0
20			38.1			38.1	2.2
Total Wt. (g)	5.0	7.7	1,692.8	2.7	8. 7	1,716.9	100.0
Percent	0.3	0.4	98.6	0.2	0.5	100.0	

Table 2. STP Recovery Summary by Provenience

* From garden compost

The 8.7 g of fossil Pecten shell fragments were only recovered in all three levels of STP 11. This fossil material was associated with imported fill at this location and was probably imported to the site in soil derived elsewhere from the Pliocene-age San Diego Formation.

The modern intrusive material consists of building refuse of primarily asphalt floor tiles, concrete chunks, terra cotta roof tiles or paving tiles, window glass, nails (badly corroded), asphalt bits, as well as miscellaneous plastic item fragments or food wrappers, bottle glass, and Styrofoam. One saw-cut large mammal bone and pieces of chicken egg shell were also found, only in the garden area STPs.

By weight, STP 19 produced the most intrusive material with a total of 412.5 g (24%), due to concrete chunks. Four other STPs produced over 100 g of refuse each: 6 (280.6 g), 14 (185.3 g), 13 (151.5 g), and 7 (122.6 g). Six STPs (1, 2, 4, 10, 11, and 18) yielded less than 20 g of material each. STP 11, in the middle of the project area, contributed only 0.7 g (flooring and plastic flagging tape) of the refuse. This STP also produced the only fossil shell.

By depth, the trash material was distributed from 0 to 40 cm, but only STPs 2 and 3 produced refuse below 30 cm - most likely due to soil tilling for the garden area. Intrusive material was only found in the upper 20 cm in STPs 10, 11, 15, and 16; the remaining STPs yielded intrusive material from 0-30 cm.

Summary

The survey and testing program indicates that the project area has been disturbed by previous construction and landscaping for the existing structures. The southern portion of the project has been significantly impacted by rodent bioturbation and garden tilling. The lack of any artifacts and minimal shell that could represent cultural material indicates that significant portions of site CA-SDI-11571 are not present within the project area.

V. SUMMARY AND RECOMMENDATIONS

The goal of the project was to identify resources that may be impacted by the project. The limited surface and subsurface shell that may be cultural in nature and absence of any prehistoric artifacts suggest that the project area is not within a significant portion of site CA-SDI-11571.

No significant impacts to cultural resources are anticipated to result from the proposed development. Significant portions of site CA-SDI-11571 were not identified within the project area during the survey and testing program. The historic-age slab foundation (EBR-H-1) does not contain additional information potential and does not qualify as a significant cultural resource based on CEQA and City of San Diego Land Development Code criteria. No further treatment is recommended for EBR-H-1.

Because the testing was limited in depth and the project is within the mapped boundary of CA-SDI-11571, monitoring by an archaeological and a Native American monitor is recommended during construction excavation and grading to ensure unidentified sensitive resources are not present or impacted by the project.

VI. REFERENCES

Almstedt, Ruth F.

1982 Kumeyaay and `IIpay. In *APS/SDG&E Interconnection Native American Cultural Resources*, edited by C. M. Woods, pp. 6-20. Prepared by Wirth Associates, San Diego for San Diego Gas & Electric.

Beddow, Donna

2001 Site form update for CA-SDI-11571. Unpublished site form on file at the South Coastal Information Center, San Diego State University.

Bowman, Roy H.

1973 Soil Survey, San Diego Area, California. United States Department of Agriculture.

Carter, George F.

1975 Pleistocene Man in San Diego. The Johns Hopkins Press, Baltimore.

Clowery-Moreno, Sara

2008 Site form update for CA-SDI-11571. Unpublished site form on file at the South Coastal Information Center, San Diego State University.

Cooley, Theodore, and Patricia Mitchell

1992 Site form update for CA-SDI-11571. Unpublished site form on file at the South Coastal Information Center, San Diego State University.

Gifford, E.W.

1931 *The Kamia of Imperial Valley*. Bulletin 98, Bureau of American Ethnology, Smithsonian Institution, Washington, D.C.

Hedges, Ken

1975 Notes on the Kumeyaay: A Problem of Identification. *Journal of California Anthropology* 2(1):71-83.

Hicks, Fredrick N.

1963 Ecological Aspects of Aboriginal Culture in the Western Yuman Area. Unpublished Ph.D. dissertation, Department of Anthropology, University of California, Los Angeles.

Kennedy, Michael P.

1975 Section A: Western San Diego Metropolitan Area. In *Geology of the San Diego Metropolitan Area, California*. California Division of Mines and Geology, Bulletin 200.

Kennedy, Michael P., and Siang S. Tan

1977 Geology of National City, Imperial Beach and Otay Mesa Quadrangles, Southern San Diego Metropolitan Area, California. California Division of Mines and Geology, Sacramento.

Kroeber, A. L.

1976 *Handbook of the Indians of California*. Reprinted. Drover Publications, New York. Originally published 1925, Bulletin No. 78, Bureau of American Ethnology Smithsonian Institute, Washington, D.C.

Luomala, Katherine

1976 Flexibility in Sib Affiliation among the Diegueño. In *Native Californians: A Theoretical Retrospective*, edited by L. J. Bean, and T. C. Blackburn, pp. 245-270. Ballena Press, Socorro, New Mexico.

Moratto, J. R.

1984 California Archaeology. Academic Press.

Phillips, George Harwood

1975 Chiefs and Challengers: Indian Resistance and Cooperation in Southern California. University of California Press, Los Angeles.

Pigniolo, Andrew

- 1990 Site form for CA-SDI-11571. Unpublished site form on file at the South Coastal Information Center, San Diego State University.
- 2013 Cultural Resource Testing at a Portion of CA-SDI-11571 for the Kendall Street Residences Project at 3811 Kendall Street City of San Diego, California. Prepared by Laguna Mountain Environmental, San Diego, for Marc Cicchetto at Allison James Estates & Homes, San Diego.

Pryde, Philip R.

1976 San Diego: An Introduction to the Region. Kendall /Hunt Publishing Company. Dubuque, Iowa.

Remeika, Paul, and Lowell Lindsay

1992 *Geology of Anza-Borrego: Edge of Creation.* Sunbelt Publications, Inc. San Diego, California.

Rensch, Hero E.

1975 The Indian Place Names of Rancho Cuyamaca. Acoma Books, Ramona, California.

Rogers, Malcolm J.

1945 An Outline of Yuman Prehistory. *Southwestern Journal of Anthropology*, 1(2): 157-198.

n.d. Site form for SDM-W-166. Unpublished site form on file at the San Diego Museum of Man.

Shackley, M. Steven

1984 Archaeological Investigations in the Western Colorado Desert: A Socioecological Approach, Vol. 1. Prepared by Wirth Environmental Services, A Division of Dames & Moore, San Diego for San Diego Gas & Electric.

Shipek, Florence

1982 The Kamia. In *APS/SDG&E Interconnection Project: Native American Cultural Resources*, edited by C. M. Woods, pp. 21-33. Prepared by Wirth Associates, San Diego for San Diego Gas & Electric.

Spier, Leslie

1923 Southern Diegueño Customs. University of California Publications in American Archaeology and Ethnology 20:292-358.

State of California, Department of Parks and Recreation.

- 1976 *California Inventory of Historic Resources.* Department of Parks and Recreation, Sacramento, California.
- 1992 *California Historical Landmarks*. Department of Parks and Recreation, Sacramento California.

True, D.L.

- 1966 Archaeological Differentiation of Shoshonean and Yuman Speaking Groups in Southern California. Unpublished Ph.D. dissertation, Department of Anthropology, University of California, Los Angeles.
- 1970 Investigation of a Late Prehistoric Complex in Cuyamaca Rancho State Park, San Diego County, California. Archaeological Survey Monograph, Department of Anthropology, University of California, Los Angeles.

Willey, G. R., and P. Phillips

1958 Method and Theory in American Archaeology. University of Chicago Press.

APPENDICES

- A. Resume of Principal Investigator
- B. Records Search Confirmation
- C. Native American Correspondence
- D. Catalogue
- E. Photographs and Photo Logs

APPENDIX A

RESUME OF PRINCIPAL INVESTIGATOR

ANDREW R. PIGNIOLO, M.A., RPA Principal Archaeologist Laguna Mountain Environmental, Inc.

Education

San Diego State University, Master of Arts, Anthropology, 1992 San Diego State University, Bachelor of Arts, Anthropology, 1985

Professional Experience

2002-Present	Principal Archaeologist/President, Laguna Mountain Environmental, Inc.,
	San Diego
1997-2002	Senior Archaeologist, Tierra Environmental Services, San Diego
1994-1997	Senior Archaeologist, KEA Environmental, Inc., San Diego
1985-1994	Project Archaeologist/Senior Archaeologist, Ogden Environmental and
	Energy Services, San Diego
1982-1985	Reports Archivist, Cultural Resource Management Center (now the South
	Coastal Information Center), San Diego State University
1980-1985	Archaeological Consultant, San Diego, California
1980-1985	Archaeological Consultant, San Diego, California

Professional Affiliations

Register of Professional Archaeologists (RPA), 1992-present Qualified Archaeology Consultant, San Diego County Qualified Archaeology Consultant, City of San Diego Qualified Archaeology Consultant, City of Chula Vista Qualified Archaeology Consultant, Riverside County Society for American Archaeology Society for California Archaeology Pacific Coast Archaeological Society San Diego County Archaeological Society

Qualifications

Mr. Andrew Pigniolo is a certified archaeology consultant for the County and City of San Diego. Mr. Pigniolo has more than 36 years of experience as an archaeologist, and has conducted more than 800 projects throughout southern California and western Arizona. His archaeological investigations have been conducted for a wide variety of development and resource management projects including water resource facilities, energy utilities, commercial and residential developments, military installations, transportation projects, and projects involving Indian Reservation lands. Mr. Pigniolo has conducted the complete range of technical studies including archaeological overviews and management plans, ethnographic studies, archaeological surveys, test excavations, historical research, evaluations of significance under CEQA and Section 106, data recovery programs, and monitoring projects. He has received 40 hour HAZWOPPER training and holds an active card for hazardous material work.

REPRESENTATIVE PROJECTS

- **Proposed SDG&E Sunrise Powerlink Project, San Diego to Imperial Valley, California** (San Diego Gas and Electric). Mr. Pigniolo served as the Principal Investigator and archaeological monitor for this project whose purpose is the installation of a new transmission line corridor running from San Diego to Imperial Valley. This phase of the project included the preliminary reporting of any cultural resources observed during field visits to the proposed impact areas. Mr. Pigniolo recorded sites encountered during monitoring, and collected GPS points and photographs of the sites for future review. Mr. Pigniolo also conducted the cultural resources portion of the environmental training for this project.
- **Princess Street Monitoring and Data Recovery Project at the Spindrift Site** (*City of San Diego*). Mr. Pigniolo served as a Principal Investigator of an archaeological monitoring and data recovery program at the Spindrift Site in the community of La Jolla. The effort was initially to provide archaeological monitoring of a utility undergrounding project. The presence of the major prehistoric village site within the project alignment quickly became evident prior to construction monitoring and a data recovery plan was prepared prior to the start of work. Data recovery included the excavation of 25 controlled units and the water screening of 100 percent of the archaeological site material impacted during trenching. More than 40 fragmented human burials were encountered. Working with Native American monitors and representatives, the remains were repatriated.
- **Cultural Resource Survey, Geotechnical Monitoring, and Testing for the La Jolla View Reservoir Project, La Jolla, City of San Diego, California** (*IEC*). Mr. Pigniolo served as Principal Investigator and conducted an archaeological survey on an approximately 15-acre study area, in the La Jolla Natural Park area on Mount Soledad above La. In addition to the field survey, geotechnical work was monitored by an archaeologist and Native American monitor. One small prehistoric cobble procurement site (CA-SDI-20843) was tested to determine site significance. Due to surface visibility constraints from dense vegetation, monitoring by an archaeological and a Native American monitor during construction excavation and grading was recommended to ensure sensitive features not identified during the survey are not present or impacted by the project.
- **City of San Diego Sever Group 783 Project, San Diego, California** (Orion Construction Company.) Mr. Pigniolo was the Principal Investigator for an archaeological monitoring project for a sewer line replacement in the eastern portion of the City of San Diego. The project included archaeological construction monitoring in an urban environment.
- **Cultural Resource Monitoring and Treatment of CA-SDI-20861 for the 1941-1945 Columbia Street Project, City of San Diego, California** (*Jeff Svitak Inc.*) Mr. Pigniolo served as Principal Investigator of an archival research and an archaeological and Native American monitoring program of building demolition and construction excavation for a multi-family dwelling in the Little Italy community of the City of San Diego. The project consisted of archaeological and historical research prior to fieldwork, archaeological monitoring of foundation removal and construction excavation, and the recovery and analysis of historic artifacts discovered during monitoring. Site CA-SDI-20861 was treated as a significant cultural resource and the recovery and analysis of the cultural material served as mitigation for the project impacts to the site.

- **Cultural Resource Salvage and Monitoring within a Portion of CA-SDI-39/17372 at 1891 Viking Way, La Jolla, City of San Diego, California** (*Ayers General Contracting, Inc.*) Mr. Pigniolo served as Principal Investigator of an archaeological salvage and documentation program in addition to construction monitoring for the residence located at 1891 Viking Way, in the La Jolla. The project included the demolition and replacement of an existing retaining wall, and the replacement of additional yard hardscape. The City of San Diego archaeologist determined that construction work was occurring within site CA-SDI-39 and required work to stop and a treatment plan to partially mitigate impacts to the site be prepared. The project included a salvage effort to partially mitigate impacts to this portion of the site, through documentation and artifact recovery and to recover any impacted human remains as part of mitigation. Three phases of treatment were conducted including a 100 percent recovery program for human remains and associated grave goods and monitoring of final construction disturbance and backfilling.
- **Muller Residence Archaeological Survey, Testing, and Evaluation, Carmel Valley, City of San Diego, California** (*Mr. Rolf Muller*) Mr. Pigniolo served as Principal Investigator and Project Manager of a cultural resource survey and testing and evaluation program of a residential parcel proposed for development. The survey indicated the presence of a portion of a prehistoric shell midden within the project area. The testing program indicated a deeply buried archaeological deposit with a high level of integrity. Impact avoidance through redesign was recommended under City of San Diego Historical Resources Guidelines.
- Cultural Resource Monitoring for The San Diego County Administration Center Waterfront Park Project, San Diego, California (*McCarthy Building Companies, Inc.*) Mr. Pigniolo served as Principal Investigator of a cultural resource monitoring program for the Water Front Park Project at the San Diego County Administration Building in the City of San Diego. The monitoring program included excavation near the dredge fill/native ground contact. Historic maps indicated that the entire project area was located on man-made land created from bay dredge spoils. The monitoring program identified a small historic-age boat that probably sank in the bayfront prior to filling of the area. Based on the current County guidelines, this resource qualifies as significant for its information potential and has been treated as such. The boat was documented and avoided, and left in place.
- 13th and C Streets Evaluation Project, City of San Diego, California (*WM Builders*) Mr. Pigniolo served as Principal Investigator of a archaeological/historical resource assessment for a commercial development project in the City of San Diego. The project area is in the downtown portion of San Diego. A records search, literature review, examination of historic maps, records, and city directories was used to assess the potential for buried historic resources within the project area. Potential buried historic resource locations were identified and a testing plan was developed.
- **U. S. Army Yuma Proving Ground (YPG) Native American Consultation Plan, Yuma, Arizona** (*Yuma Proving Ground*). Mr. Pigniolo served as principal author of a Native American consultation plan for YPG to provide guidance and information to U.S. Army commanders and Army resource managers at YPG for consultation with Native American groups. Consultation was conducted in a manner that is consistent with federal laws and regulations that mandate consultation and the consultation plan was designed to ensure the participation of Native American groups early in the planning process.

- All American 105 Race Project, West Mesa, Imperial County, California (*Legacy 106, Inc.*). Mr. Pigniolo served as Principal Investigator, report author, and crew chief for an archaeological survey for a proposed off-road vehicle race course in the West Mesa area of Imperial County. The survey covered Bureau of Land Management (BLM) lands and included close coordination with BLM staff. The survey included a proposed 7.5 mile course with a very short time-frame. The goal was project alignment adjustment and realignment to avoid resource impacts where possible. A variety of prehistoric cultural resources including 10 sites and seven isolates were encountered. Human remains were identified and avoided. The race route was realigned to avoid significant resource impacts allowing the race to proceed on schedule.
- Alpine Fire Safe Council Brush Management Monitoring Project, Alpine Region, San Diego County, California (*Alpine Fire Safe Council*) Mr. Pigniolo served as Principal Investigator for a cultural resources monitoring and protection program on four project areas surrounding Alpine. Cultural resources identified during previous surveys within the vegetation treatment areas were flagged for avoidance. The project included hand clearing and chaparral mastication near residential structures to create a fire buffer zone. Vegetation removal was monitored to ensure cultural resources obscured by heavy vegetation were not impacted by the project and that all recorded cultural resources were avoided. The Bureau of Land Management served as Lead Agency for the project.

APPENDIX B

RECORDS SEARCH CONFIRMATION



South Coastal Information Center San Diego State University 5500 Campanile Drive San Diego, CA 92182-5320 Office: (619) 594-5682 www.scic.org scic@mail.sdsu.edu

CALIFORNIA HISTORICAL RESOURCES INFORMATION SYSTEM CLIENT IN-HOUSE RECORDS SEARCH

Company:	Laguna Mountain Enviro	
Company Representative:	Carol Serr	
Date:	11/28/2016	
Project Identification:	Shasta Street Home Survey and Testing #1644	
Search Radius:	1/4 mile	
Historical Resources:		SELF
	s have been reviewed. All sites within the project dius of the project area have been plotted. Copies of the uded for all recorded sites.	
Previous Survey Report Bo	oundaries:	SELF
	en reviewed. National Archaeological Database (NADB) oject boundaries and within the specified radius of the	
Historic Addresses:		SELF
A map and database of historic	properties (formerly Geofinder) has been included.	
Historic Maps:		SELF
The historic maps on file at the s and copies have been included.	South Coastal Information Center have been reviewed,	

Copies: Hours:

4

4



APPENDIX C

NATIVE AMERICAN CORRESPONDENCE



February 2, 2017

Native American Heritage Commission c/o Kathy Sanchez 1550 Harbor Blvd, Suite 100 West Sacramento, CA 95691

Subject: EcoBlok Residences Survey & Testing Project (San Diego), California (#1704)

Dear Ms. Sanchez,

Laguna Mountain Environmental is conducting an archaeological investigation in the Pacific Beach area of the City of San Diego for survey and testing at 3977 Shasta Street for the EcoBlok Residences project. The proposed project includes the demolition of existing residential structures and construction of 31 houses on individual lots. As part of the project demolition and construction, removal of existing foundations and grading and excavation for new foundations and utilities will occur.

The project area (APNs 424-482-14 and 424-532-25) is approximately 1.7 acres, located west of Interstate 5, east of Ingraham Street, and south of Grand Avenue on the eastern side of Crown Point. The project area is shown on the La Jolla 7.5' USGS quadrangle, in Township 16 South, Range 3 West, within an unsectioned portion of Pueblo Lands (see attached figure).


We respectfully request any information and input that you may have regarding Native American concerns either directly or indirectly associated with this project area. We would also appreciate a current list of appropriate Native American contacts for the area in order to elicit local concerns. If you or your files have any information about cultural resources or traditional cultural properties located on or near the project site, please contact me. If I can provide any additional information, please contact me immediately at (858) 505-8164. Thank you for your assistance.

Sincerely,

andrew R. Regines

Andrew Pigniolo, M.A., RPA Principal Archaeologist

Attachments: Project Location map Sacred Lands File & Native American Contacts List Request Form



Source: USGS 7.5' La Jolla Quadrangle



Project Location and Associated Cultural Resource

Sacred Lands File & Native American Contacts List Request

NATIVE AMERICAN HERITAGE COMMISSION

1550 Harbor Blvd, Suite 100 West Sacramento, CA 95501 (916) 373-3710 (916) 373-5471 – Fax <u>nahc@nahc.ca.gov</u>

Information Below is Required for a Sacred Lands File Search

Project:		
County:		
USGS Quadrangle		
Name:		
Township:	Range:	Section(s):
Company/Firm/Agenc	y:	
Contact Person:		
Street Address:		
City:		Zip:
Phone:	Extension:	
Fax:		
Email:		

Project Description:

Project Location Map is attached

Edmund G. Brown, Jr., Governor

NATIVE AMERICAN HERITAGE COMMISSION 1550 Harbor Blvd., Suite 100

West Sacramento, CA 95691 (916) 373-3710 (916) 373-5471 FAX

February 6, 2017

Andrew Pigniolo Laguna Mountain Environmental

Sent by E-mail: laguna@lagunaenv.com

RE: Proposed EcoBlok Residences Survey and Testing Project, City of San Diego; La Jolla USGS Quadrangle, San Diego County, California

Dear Mr. Pigniolo:

Attached is a contact list of tribes with traditional lands or cultural places located within the boundaries of the above referenced counties. <u>A search of the SFL was completed for the USGS guadrangle information provided with negative results.</u>

Our records indicate that the lead agency for this project has not requested a Native American Consultation List for the purposes of formal consultation. Lists for cultural resource assessments are different than consultation lists. Please note that the intent of the referenced codes below is to avoid or mitigate impacts to tribal cultural resources, as defined, for California Environmental Quality Act (CEQA) projects under AB-52.

As of July 1, 2015, Public Resources Code Sections 21080.3.1 and 21080.3.2 **require public agencies** to consult with California Native American tribes identified by the Native American Heritage Commission (NAHC) for the purpose mitigating impacts to tribal cultural resources:

Within 14 days of determining that an application for a project is complete or a decision by a public agency to undertake a project, the lead agency shall provide formal notification to the designated contact of, or a tribal representative of, traditionally and culturally affiliated California Native American tribes that have requested notice, which shall be accomplished by means of at least one written notification that includes a brief description of the proposed project and its location, the lead agency contact information, and a notification that the California Native American tribe has 30 days to request consultation pursuant to this section. (Public Resources Code Section 21080.3.1(d))

The law does not preclude agencies from initiating consultation with the tribes that are culturally and traditionally affiliated with their jurisdictions. The NAHC believes that in fact that this is the best practice to ensure that tribes are consulted commensurate with the intent of the law.

In accordance with Public Resources Code Section 21080.3.1(d), formal notification must include a brief description of the proposed project and its location, the lead agency contact information, and a notification that the California Native American tribe has 30 days to request consultation. The NAHC believes that agencies should also include with their notification letters information regarding any cultural resources assessment that has been completed on the APE, such as:

- 1. The results of any record search that may have been conducted at an Information Center of the California Historical Resources Information System (CHRIS), including, but not limited to:
 - A listing of any and all known cultural resources have already been recorded on or adjacent to the APE;
 - Copies of any and all cultural resource records and study reports that may have been provided by the Information Center as part of the records search response;
 - If the probability is low, moderate, or high that cultural resources are located in the APE.
 - Whether the records search indicates a low, moderate or high probability that unrecorded cultural resources are located in the potential APE; and

- If a survey is recommended by the Information Center to determine whether previously unrecorded cultural resources are present.
- 2. The results of any archaeological inventory survey that was conducted, including:
 - Any report that may contain site forms, site significance, and suggested mitigation measurers.
 - All information regarding site locations, Native American human remains, and associated funerary
 objects should be in a separate confidential addendum, and not be made available for pubic disclosure
 in accordance with Government Code Section 6254.10.
- 3. The results of any Sacred Lands File (SFL) check conducted through Native American Heritage Commission.
- 4. Any ethnographic studies conducted for any area including all or part of the potential APE; and
- 5. Any geotechnical reports regarding all or part of the potential APE.

Lead agencies should be aware that records maintained by the NAHC and CHRIS is not exhaustive, and a negative response to these searches does not preclude the existence of a cultural place. A tribe may be the only source of information regarding the existence of a tribal cultural resource.

This information will aid tribes in determining whether to request formal consultation. In the case that they do, having the information beforehand well help to facilitate the consultation process.

The results of these searches and surveys should be included in the "Tribal Cultural Resources" section or in a separate subsection of the Cultural Resources section of the environmental document submitted for review. Please reference California Natural Resources Agency (2016) "Final Text for tribal cultural resources update to Appendix G: Environmental Checklist Form," <u>http://resources.ca.gov/ceqa/docs/ab52/Clean-final-AB-52-App-G-text-Submitted.pdf</u>.

If you receive notification of change of addresses and phone numbers from tribes, please notify me. With your assistance we are able to assure that our consultation list contains current information.

If you have any questions, please contact me at my email address: gayle.totton@nahc.ca.gov.

Sincerely,

Gayle Totton, M.A., PhD. Associate Governmental Program Analyst

Native American Heritage Commission Tribal Contact List San Diego County 2/6/2017

Barona Group of the Capitan Grande

Clifford LaChappa, Chairperson 1095 Barona Road Lakeside, CA, 92040 Phone: (619) 443 - 6612 Fax: (619) 443-0681 cloyd@barona-nsn.gov

Kumeyaay

Campo Band of Mission Indians

Ralph Goff, Chairperson 36190 Church Road, Suite 1 Kumeyaay Campo, CA, 91906 Phone: (619)478-9046 Fax: (619)478-5818 rgoff@campo-nsn.gov

Ewilaapaayp Tribal Office

Michael Garcia, Vice Chairperson 4054 Willows Road Kumeyaay Alpine, CA, 91901 Phone: (619) 445 - 6315 Fax: (619) 445-9126 michaelg@leaningrock.net

Ewilaapaayp Tribal Office

Robert Pinto, Chairperson 4054 Willows Road I Alpine, CA, 91901 Phone: (619)445-6315 Fax: (619)445-9126

Kumeyaay

lipay Nation of Santa Ysabel

Virgil Perez, Chairperson P.O. Box 130 Santa Ysabel, CA, 92070 Phone: (760)765-0845 Fax: (760)765-0320

Kumeyaay

Kumeyaay

lipay Nation of Santa Ysabel

Clint Linton, Director of Cultural Resources P.O. Box 507 Santa Ysabel, CA, 92070 Phone: (760) 803 - 5694 cilinton73@aol.com

Inaja Band of Mission Indians

Rebecca Osuna, Chairperson 2005 S. Escondido Blvd. Escondido, CA, 92025 Phone: (760)737-7628 Fax: (760)747-8568

Kumeyaay

Kumevaav

Jamul Indian Village

Erica Pinto, Chairperson P.O. Box 612 Jamul, CA, 91935 Phone: (619)669-4785 Fax: (619)669-4817

Kwaaymii Laguna Band of

Mission Indians Carmen Lucas, P.O. Box 775 Pine Valley, CA, 91962 Phone: (619)709-4207

La Posta Band of Mission Indians Javaughn Miller, Tribal Administrator

8 Crestwood Road Boulevard, CA, 91905 Phone: (619) 478 - 2113 Fax: (619) 478-2125 imiller@LPtribe.net

La Posta Band of Mission Indians

Gwendolyn Parada, Chairperson 8 Crestwood Road Boulevard, CA, 91905 Phone: (619)478-2113 Fax: (619)478-2125 LP13boots@aol.com Kumeyaay

Kumeyaay

Kumeyaay

Kumeyaay

This list is current only as of the date of this document. Distribution of this list does not relieve any person of statutory responsibility as defined in Section 7050.5 of the Health and Safety Code, Section 5097.94 of the Public Resource Section 5097.98 of the Public Resources Code.

This list is only applicable for contacting local Native Americans with regard to cultural resources assessment for the proposed EcoBlok Residences Survey and Testing Project, San Diego County.

PROJ-2017-000641 02/06/2017 10:16 AM

1 of 2

Native American Heritage Commission Tribal Contact List San Diego County 2/6/2017

Manzanita Band of Kumeyaay

Nation Nick Elliott, Cultural Resources Coordinator P. O. Box 1302 Boulevard, CA, 91905 Phone: (619) 766 - 4930 Fax: (619) 766-4957 nickmepa@yahoo.com

Kumeyaay

Manzanita Band of Kumeyaay Nation

Angela Elliott Santos, Chairperson P.O. Box 1302 Kumeyaay Boulevard, CA, 91905 Phone: (619) 766 - 4930 Fax: (619) 766-4957

Mesa Grande Band of Mission Indians

Virgil Oyos, Chairperson P.O Box 270 Kumeyaay Santa Ysabel, CA, 92070 Phone: (760)782-3818 Fax: (760)782-9092 mesagrandeband@msn.com

San Pasqual Band of Mission Indians

Allen E. Lawson, Chairperson P.O. Box 365 Valley Center, CA, 92082 Phone: (760)749-3200 Fax: (760)749-3876 allenl@sanpasqualtribe.org

Kumeyaay

Kumeyaay

San Pasqual Band of Mission Indians

John Flores, Environmental Coordinator P. O. Box 365 Valley Center, CA, 92082 Phone: (760) 749 - 3200 Fax: (760) 749-3876 johnf@sanpasqualtribe.org

Sycuan Band of the Kumeyaay

Nation Cody J. Martinez, Chairperson 1 Kwaaypaay Court El Cajon, CA, 92019 Phone: (619)445-2613 Fax: (619)445-1927 ssilva@sycuan-nsn.gov

Kumeyaay

Sycuan Band of the Kumeyaay Nation

Lisa Haws, Cultural Resources Manager 1 Kwaaypaay Court El Cajon, CA, 92019 Phone: (619) 312 - 1935

Kumeyaay

Viejas Band of Kumeyaay Indians

Robert J. Welch, Chairperson 1 Viejas Grade Road Alpine, CA, 91901 Phone: (619)445-3810 Fax: (619)445-5337 jhagen@viejas-nsn.gov

Viejas Band of Kumeyaay Indians

Julie Hagen. 1 Viejas Grade Road Alpine, CA, 91901 Phone: (619) 445 - 3810 Fax: (619) 445-5337 jhagen@viejas-nsn.gov

Kumeyaay

Kumeyaay

This list is current only as of the date of this document. Distribution of this list does not relieve any person of statutory responsibility as defined in Section 7050.5 of the Health and Safety Code, Section 5097.94 of the Public Resource Section 5097.98 of the Public Resources Code.

This list is only applicable for contacting local Native Americans with regard to cultural resources assessment for the proposed EcoBiok Residences Survey and Testing Project, San Diego County.

PROJ-2017-000641

APPENDIX D

CATALOGUE

2017 Testing Recovery for EcoBlok Residences Project - 3977 Shasta St.

Cat# I	Prov.	Level (cm)	Class	Item	Туре	Condition	Material/Species	Wt (g)	Comments	
			Faunal Bone	Bone	Sm. Mammal	Burned	Undiff.	0.1		
		0-10	Intrusive	Modern Item	Various	-	Mixed	0.4	thin cup porcelain; thin plastic items	
		0-10	Intrusive Faunal	Shell	Gastropod	-	Rumina decollata		thin-shelled, spiral "cone" type	
		10-20	Faunal Bone	Bone	Bird	Unburned	Undiff.		long bone	
		10-20	Intrusive	Modern Item	Various	-	Mixed		thin plastic; chicken egg shell	
	STP 1	10-20	Intrusive	Nesting Material	Various	-	Mixed		chewed up carpet fiber, plastic wrapper & bandaid	
			Intrusive Faunal	Shell	Gastropod	-	Rumina decollata	0.1		
		20-30	Intrusive	Modern Item	Various	-	Mixed	5.5	dark red-brown flooring tile with black mastic, yellow hard plastic; window	
		20-30	Intrusive	Nesting Material	Various	-	Mixed	0.2	chewed thin wrapper & foil	
			Faunal Bone	Bone	Sm. Mammal	Burned	Undiff.	0.1		
			Faunal Bone	Bone	Bird	Unburned	Undiff.	1.0		
		0-10	Faunal Shell	Shell	Barnacle	Unburned	Undiff.	0.1		
		0-10	Intrusive	Modern Item	Various	-	Mixed		same flooring, thin white plastic; clear bottle glass	
			Intrusive Faunal	Shell	Gastropod	-	Undiff.		Rumina & Helix	
			Faunal Bone	Bone	Sm. Mammal	Burned	Undiff.	0.1		
			Faunal Bone	Bone	Bird	Unburned	Undiff.	0.1		
			Faunal Bone	Bone	Bird	Burned	Undiff.	2.5	long bone; in 2 pcs; filled with dirt	
			Faunal Shell	Shell	Undiff.	Unburned	Undiff.		worm tube, probably off larger pc in next level	
		10-20	Intrusive	Modern Item	Various	-	Mixed		flooring, thin white semi-melted glass	
15 \$	STP 2	20-30	Faunal Bone	Bone	Bird	Unburned	Undiff.	0.2		
16 \$			Faunal Shell	Shell	Bivalve	Unburned	Chione	0.9		
		20-30	Faunal Shell	Shell	Gastropod	Unburned	Undiff.	0.1	kelp snail	
16 \$	STP 2	20-30	Faunal Shell	Shell	Undiff.	Unburned	Undiff.	2.9	worm tubes on unknown bivalve substrate	
17 \$		20-30	Intrusive	Modern Item	Various	-	Mixed		flooring, green bottle glass; black plastic bits	
18 \$	STP 2	20-30	Intrusive Faunal	Shell	Gastropod	-	Helix	0.1		
19 \$	STP 2	30-40	Intrusive	Modern Item	Unknown	-	Plastic	0.1	white plastic with black lettering "MIXED"; probably a plant tag	
20 \$	STP 3	0-10	Intrusive	Modern Item	Various	-	Mixed	4.8	window glass (pale aqua); plastic "cap"; plant tags; wooden stake frag	
21 \$	STP 3	0-10	Intrusive Faunal	Shell	Gastropod	-	Helix	0.1		
22			Faunal Bone	Bone	Bird	Unburned	Undiff.	0.5		
22 3	STP 3		Faunal Bone	Bone	Bird	Burned	Undiff.	0.1		
23	STP 3	10-20	Intrusive	Modern Item	Various	-	Mixed	29.6	lower portion of zucchin tag; beige flooring; black ziptie; orange yarn; terra cotta sewer pipe (glazed interior)	
24	STP 3	10-20	Intrusive Faunal	Shell	Gastropod	-	Helix	0.1		
			Faunal Bone	Bone	Sm. Mammal	Burned	Undiff.	0.1		
		20-30	Faunal Bone	Bone	Sm. Mammal	Unburned	Undiff.	0.1		
			Faunal Bone	Bone	Bird	Unburned	Undiff.	0.5		
26			Faunal Shell	Shell	Bivalve	Unburned	Argopecten	0.2		
27 \$	STP 3	20-30	Intrusive	Modern Item	Various	-	Mixed	3.3	concrete chunk; flooring; plastic bits; thin, flat glass with ACL label (white speckled; All R[ights Reserved]	
28	STP 3	20-30	Intrusive Faunal	Shell	Gastropod	-	Helix	0.1		
			Faunal Bone	Bone	Bird	Unburned	Undiff.	0.7		
		30-40	Faunal Shell	Shell	Barnacle	Unburned	Undiff.	0.2		
			Faunal Shell	Shell	Bivalve	Unburned	Undiff.	0.1		
			Intrusive	Modern Item	Various	-	Mixed	20.8	flooring; concrete; saw-cut bone; amber bottle glass; window glass; plastic plant tag pcs;	
32 3	STP 3	30-40	Intrusive	Nesting Material	Various	-	Mixed	0.4	chewed plastic wrappers	
			Intrusive Faunal	Shell	Gastropod	-	Helix	0.1		
		0-10	Intrusive	Nesting Material	Wrapper	-	Plastic	0.1	chewed wrapper	
			Intrusive Faunal	Shell	Gastropod	-	Rumina decollata	0.8		
	STP 4	0-10	Intrusive	Modern Item	Shell	-	Egg	0.1	chicken egg shell from compost	

2017 Testing Recovery for EcoBlok Residences Project - 3977 Shasta St.

Cat#	Prov.	Level (cm)	Class	Item	Туре	Condition	Material/Species	Wt (g)	Comments	
		10-20	Faunal Bone	Bone	Fish		Undiff.		bony; vert & parts	
	STP 4	10-20	Faunal Bone	Bone	Undiff.	Unburned	Undiff.	0.1		
	STP 4	10-20	Intrusive	Modern Item	Various	-	Mixed	3.0	flooring; thin plastic pcs (pc of grocery bag handle)	
39	STP 4	20-30	Faunal Bone	Bone	Fish	Unburned	Undiff.	0.1	bony	
		20-30	Faunal Bone	Bone	Bird	Unburned	Undiff.	0.1		
40		20-30	Intrusive	Modern Item	Various	-	Mixed	1.9	concrete blob; styrofoam; thin hard plastic pcs	
	STP 4	20-30	Intrusive Faunal	Shell	Gastropod	-	Helix	0.1		
42		0-10	Intrusive	Modern Item	Various	-	Mixed	36.6	concrete blob (32.5 g); flooring	
43	STP 5	0-10	Intrusive Faunal	Shell	Gastropod	-	Rumina decollata	0.2		
		10-20	Faunal Shell	Shell	Bivalve	Unburned	Argopecten	0.1		
45	STP 5	10-20	Intrusive	Modern Item	Various	-	Mixed	34.2	concrete chunk; flooring; plastic bits; plastic hose washer; window glass; old aqua bottle glass; green bottle glass; foam sheeting	
46	STP 5	10-20	Intrusive Faunal	Shell	Gastropod	-	Helix	0.1		
		20-30	Faunal Bone	Bone	Bird	Burned	Undiff.	0.2		
		20-30	Intrusive	Modern Item	Various	-	Mixed	11.2	concrete chunk; flooring; misc plastic; amber bottle glass (beer)	
		0-10	Intrusive	Modern Item	Bldg Mat	-	Concrete		1 with finished edge and large gravel; other is homogeneous and interior; Discarded	
50	STP 6	10-20	Intrusive	Modern Item	Various	-	Mixed	5.9	flooring; asphalt chunks	
		20-30	Intrusive	Modern Item	Window	-	Glass		clear	
		0-10	Intrusive	Modern Item	Various	-	Mixed	21.4	concrete chunk with large gravel; green plastic sprinkler head frags; black "ribbed" (on interior) plastic "pipe" cutting	
53	STP 7	10-20	Intrusive	Modern Item	Various	-	Mixed	61.3	flooring; asphalt; green plastic pcs; terra cotta roof tile?; bottle glass (1 amber; 2 clear)	
54	STP 7	20-30	Intrusive	Modern Item	Various	-	Mixed	39.9	asphalt chunk; kelly green bottle glass	
		0-10	Intrusive	Modern Item	Various	-	Mixed	19.9	thin concrete; 2-ply hard plastic (pink ext/white int); aqua bottle glass	
									(old/thk wall)	
56	STP 8	10-20	Intrusive	Modern Item	Various	-	Mixed	26.6	concrete with large gravel; clear bottle glass (2); flooring; painted pale pink thin plastic (bent)	
57	STP 8	20-30	Intrusive	Modern Item	Flooring	-	Other	3.7	flooring tile - different color than last level	
		0-10	Intrusive	Modern Item	Flooring	-	Other		2 diff. beiges (& diff. mastic)	
59	STP 9	10-20	Intrusive	Modern Item	Various	-	Mixed		flooring (brown & beige tiles); asphalt roof shingle; bottle glass (amber; clear)	
60	STP 9	20-30	Intrusive	Modern Item	Various	-	Mixed	15.0	Irg pc of brown flooring tile; bottle glass (clear; aqua - old, non-round)	
		0-10	Intrusive	Modern Item	Various	-	Mixed		white, hard plastic; styrofoam	
		10-20	Intrusive	Modern Item	Various	-	Mixed		asphalt chunks (and asphalt covered gravel); concrete; styrofoam	
		0-10	Intrusive	Modern Item	Other	-	Plastic		flaggiing tape?	
		0-10	Fossil	Faunal Shell	Bivalve	-	Shell		pcs of Pecten	
		10-20	Intrusive	Modern Item	Flooring	-	Other	0.6		
		10-20	Fossil	Faunal Shell	Bivalve	-	Shell	3.9		
		20-30	Fossil	Faunal Shell	Bivalve	-	Shell	0.1		
	STP 12		Intrusive	Modern Item	Various	-	Mixed	30.9	terra cotta floor tile; asbestos flooring tile	
	STP 12			Modern Item	Various	-	Mixed		terra cotta chunk; flooring tile	
70	STP 12	20-30	Intrusive	Modern Item	Stake	-	Wood	17.7		
	STP 13		Intrusive	Modern Item	Various	-	Mixed	76.0	concrete pcs (72.6 g; discarded); bottle glass (amber & aqua)	
72	STP 13	10-20	Intrusive	Modern Item	Various	-	Mixed		concrete pcs (71.8 g; discarded); flooring tile	
	STP 13		Intrusive	Modern Item	Various	-	Mixed		floor tile; chunk of tar	
	STP 14		Intrusive	Modern Item	Other	-	Asphalt	13.7		
	STP 14		Intrusive	Modern Item	Various	-	Mixed	72.3	concrete with large gravel; green bottle glass; window glass; flooring;	
									corroded metal (nail, etc.); plastic coffe cup lid (very modern!)	
76	STP 14	10-20	Faunal Shell	Shell	Bivalve	Unburned	Argopecten	0.1	weathered	

2017 Testing Recovery for EcoBlok Residences Project - 3977 Shasta St.

Cat#	Prov.	Level (cm)	Class	Item	Туре	Condition	Material/Species	Wt (g)	Comments	
77	STP 14	20-30	Intrusive	Modern Item	Various	-	Mixed	99.3	concrete with large gravel (84.5 g; discarded); flooring; bottle glass (amber, green, clear); corroded metal; styrofoam	
78	STP 15	0-10	Intrusive	Modern Item	Various	-	Mixed	12.9	flooring; bottle glass (clear); thin plastic wrapper; thin brittle plastic	
79	STP 15	10-20	Intrusive	Modern Item	Various	-	Mixed	29.3	concrete; bottle glass (clear - stippled shoulder; amber)	
80	STP 16	0-10	Intrusive	Modern Item	Various	-	Mixed	8.9	concrete; flooring	
81	STP 16	0-10	Faunal Shell	Shell	Bivalve	Unburned	Argopecten	0.1	weathered	
82	STP 16	10-20	Intrusive	Modern Item	Various	-	Mixed	63.2	concrete; flooring; terra cotta roof tile & other frag; black rubber "plug"	
83	STP 16	10-20	Faunal Shell	Shell	Bivalve	Unburned	Argopecten	0.1	super weathered	
84	STP 17	0-10	Intrusive	Modern Item	Various	-	Mixed	16.3	flooring; super corroded metal (nail?); fleck of black paint	
85	STP 17	10-20	Intrusive	Modern Item	Various	-	Mixed	61.1	heavily corroded metal pcs (nails?)	
86	STP 17	20-30	Intrusive	Modern Item	Various	-	Mixed	0.8	flooring	
87	STP 18	10-20	Intrusive	Modern Item	Other	-	Plastic	0.1	yellow flagging tape	
88	STP 18	20-30	Intrusive	Modern Item	Bottle	-	Glass	2.3	clear; modern with crescent ribs around base perimeter	
89	STP 19	0-10	Intrusive	Modern Item	Other	-	Plastic	0.1	Heinz mustard packet fragment	
90	STP 19	10-20	Intrusive	Modern Item	Various	-	Mixed	211.1	terra cotta pipe frag & other frag; concrete chunk; asphalt chunks; flooring; bent segment of 1/8" dia wire	
91	STP 19	20-30	Intrusive	Modern Item	Various	-	Mixed	201.3	terra cotta frags; concrete chunk (165.2g; discarded); window glass	
92	STP 20	0-10	Intrusive	Modern Item	Various	-	Mixed	11.6	multiply wire coated in red plastic; flooring; bright red plastic "loop"	
93	STP 20	10-20	Intrusive	Modern Item	Various	-	Mixed	10.4	flooring; terra cotta bit; corroded metal (nail?); styrofoam; blue flagging tape	
94	STP 20	20-30	Intrusive	Modern Item	Various	-	Mixed	16.1	concrete; terra cotta bit; styrofoam; paint chip	

APPENDIX E

PHOTOGRAPHS AND PHOTO LOGS

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION PHOTOGRAPH RECORD

Page 1 of 2

Project Name (No.): Eco Blok Residences Survey & Test (1704) Year 2017

Camera Format: FujiChrome Film Type and Speed: Digital

Images Kept at: Laguna Mountain Environmental, Inc.

Mo.	Day	Time	Exp.	Subject/Description	View Toward	Accession #
2	7	8:00	01	Overview of Western Central Portion of the Project	SE	PR-05719-001
2	7	8:00	02	Overview of the Northern Portion of the Project	E	PR-05719-002
2	7	8:00	03	Overview of the Northern Portion of the Project	SE	PR-05719-003
2	7	8:00	04	Overview of the Northern Portion of the Project	SE	PR-05719-004
2	7	8:00	05	Overview of Western Central Portion of the Project	SE	PR-05719-005
2	7	8:00	06	Overview of Western Central Portion of the Project	SE	PR-05719-006
2	7	8:00	07	Overview of the Central Building on the Project	SE	PR-05719-007
2	7	8:00	08	Overview of Western Central and Southern Portion of the Project	SE	PR-05719-008
2	7	8:00	09	Overview of the Southern Building on the Project	ESE	PR-05719-009
2	7	8:00	10	Overview of the Southern Portion of the Project	S	PR-05719-010
2	7	8:00	11	Overview of the Southern Portion of the Project	SE	PR-05719-011
2	7	8:00	12	Overview of the Southern Building on the Project	SE	PR-05719-012
2	7	8:00	13	Overview of the Southern Building on the Project	E	PR-05719-013
2	7	10:00	14	STP 19 30 cm Floor	N	PR-05719-014
2	7	10:00	15	STP 19 30 cm Floor and Sidewall	N	PR-05719-015
2	7	10:00	16	STP 19 30 cm Floor and Sidewall	E	PR-05719-016
2	7	10:00	17	STP 19 30 cm Floor and Sidewall	S	PR-05719-017
2	7	10:00	18	STP 19 30 cm Floor and Sidewall	W	PR-05719-018
2	7	10:00	19	STP 19 30 cm Floor	-	PR-05719-019
2	7	10:30	20	STP 20 30 cm Floor	N	PR-05719-020
2	7	10:30	21	STP 20 30 cm Floor and Sidewall	N	PR-05719-021
2	7	10:30	22	STP 20 30 cm Floor and Sidewall	E	PR-05719-022
2	7	10:30	23	STP 20 30 cm Floor and Sidewall	S	PR-05719-023
2	7	10:30	24	STP 20 30 cm Floor and Sidewall	W	PR-05719-024
2	7	10:30	25	STP 20 30 cm Floor	-	PR-05719-025
2	7	10:30	26	Overview of STP 20 Location	NW	PR-05719-026
2	7	10:30	27	Overview of STP 19 Location	NE	PR-05719-027
2	7	11:00	28	STP 18 30 cm Floor	N	PR-05719-028
2	7	11:00	29	STP 18 30 cm Floor and Sidewall	N	PR-05719-029
2	7	11:00	30	STP 18 30 cm Floor and Sidewall	E-	PR-05719-030
2	7	11:00	31	STP 18 30 cm Floor and Sidewall	S	PR-05719-031
2	7	11:00	32	STP 18 30 cm Floor and Sidewall	W	PR-05719-032
2	7	11:00	33	STP 18 30 cm Floor	-	PR-05719-033
2	7	12:30	34	STP 16 40 cm Floor	N	PR-05719-034
2	7	12:30	35	STP 16 40 cm Floor and Sidewall	N	PR-05719-035
2	7	12:30	36	STP 16 40 cm Floor and Sidewall	E	PR-05719-036
2	7	12:30	37	STP 16 40 cm Floor and Sidewall	S	PR-05719-037
2	7	12:30	38	STP 16 40 cm Floor and Sidewall	W	PR-05719-038
2	7	12:30	39	STP 16 40 cm Floor	-	PR-05719-039
2	7	12:30	40	Overview of STP 16 Location	N	PR-05719-040
2	7	2:00	41	STP 15 30 cm Floor	N	PR-05719-041
2	7	2:00	42	STP 15 30 cm Floor and Sidewall	N	PR-05719-042
2	7	2:00	43	STP 15 30 cm Floor and Sidewall	E	PR-05719-043
2	7	2:00	44	STP 15 30 cm Floor and Sidewall	S	PR-05719-044
2	7	2:00	45	STP 15 30 cm Floor and Sidewall	W	PR-05719-045
2	7	2:00	46	STP 15 30 cm Floor	-	PR-05719-046
2	7	2:00	47	Overview of STP 15 Location	NE	PR-05719-047
_	. 					

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION PHOTOGRAPH RECORD

Page 2 of 2

Project Name (No.): Eco Blok Residences Survey & Test (1704) Year 2017

Camera Format: FujiChrome Film Type and Speed: Digital

Images Kept at: Laguna Mountain Environmental, Inc.

Mo.	Day	Time	Exp.	Subject/Description	View Toward	Accession #
2	7	2:30	48	STP 14 40 cm Floor	N	PR-05719-048
2	7	2:30	49	STP 14 40 cm Floor and Sidewall	N	PR-05719-049
2	7	2:30	50	STP 14 40 cm Floor and Sidewall	E	PR-05719-050
2	7	2:30	51	STP 14 40 cm Floor and Sidewall	S	PR-05719-051
2	7	2:30	52	STP 14 40 cm Floor and Sidewall	W	PR-05719-052
2	7	2:30	53	STP 14 40 cm Floor	-	PR-05719-053
2	7	2:30	54	Overview of STP 14 Location	NE	PR-05719-054
2	7	3:00	55	STP 11 30 cm Floor	N	PR-05719-055
2	7	3:00	56	STP 11 30 cm Floor and Sidewall	N	PR-05719-056
2	7	3:00	57	STP 11 30 cm Floor and Sidewall	E	PR-05719-057
2	7	3:00	58	STP 11 30 cm Floor and Sidewall	S	PR-05719-058
2	7	3:00	59	STP 11 30 cm Floor and Sidewall	W	PR-05719-059
2	7	3:00	60	STP 11 30 cm Floor	-	PR-05719-060
2	7	3:00	61	Overview of STP 11 Location	NE	PR-05719-061
2	7	3:30	62	STP 10 30 cm Floor	N	PR-05719-062
2	7	3:30	63	STP 10 30 cm Floor and Sidewall	N	PR-05719-063
2	7	3:30	64	STP 10 30 cm Floor and Sidewall	E	PR-05719-064
2	7	3:30	65	STP 10 30 cm Floor and Sidewall	S	PR-05719-065
2	7	3:30	66	STP 10 30 cm Floor and Sidewall	W	PR-05719-066
2	7	3:30	67	STP 10 30 cm Floor	-	PR-05719-067
2	7	4:00	68	STP 8 30 cm Floor	N	PR-05719-068
2	7	4:00	69	STP 8 30 cm Floor and Sidewall	N	PR-05719-069
2	7	4:00	70	STP 8 30 cm Floor and Sidewall	E	PR-05719-070
2	7	4:00	71	STP 8 30 cm Floor and Sidewall	S	PR-05719-071
2	7	4:00	72	STP 8 30 cm Floor and Sidewall	W	PR-05719-072
2	7	4:00	73	STP 8 30 cm Floor	-	PR-05719-073
2	7	4:00	74	Overview of STP 8 Location	NE	PR-05719-074
2	7	4:30	75	STP 7 30 cm Floor	N	PR-05719-075
2	7	4:30	76	STP 7 30 cm Floor and Sidewall	N	PR-05719-076
2	7	4:30	77	STP 7 30 cm Floor and Sidewall	E	PR-05719-077
2	7	4:30	78	STP 7 30 cm Floor and Sidewall	S	PR-05719-078
2	7	4:30	79	STP 7 30 cm Floor and Sidewall	W	PR-05719-079
2	7	4:30	80	STP 7 30 cm Floor	-	PR-05719-080
2	7	4:30	81	Overview of STP 7 Location	NE	PR-05719-081
2	7	5:00	82	STP 6 30 cm Floor	N	PR-05719-082
2	7	5:00	83	STP 6 30 cm Floor and Sidewall	N	PR-05719-083
2	7	5:00	84	STP 6 30 cm Floor and Sidewall	E	PR-05719-084
2	7	5:00	85	STP 6 30 cm Floor and Sidewall	S	PR-05719-085
2	7	5:00	86	STP 6 30 cm Floor and Sidewall	W	PR-05719-086
2	7	5:00	87	STP 6 30 cm Floor	-	PR-05719-087
2	7	5:00	88	Overview of STP 6 Location	NE	PR-05719-088




PR-05719-031

PR-05719-032

PR-05719-033

PR-05719-034

PR-05719-035



PR-05719-066

PR-05719-067

PR-05719-069



PR-05719-088

PR-05719-086

PR-05719-087

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION PHOTOGRAPH RECORD

Page 1 of 2

Project Name (No.): Eco Blok Residences Survey & Test (1704) Year 2017

Camera Format: FujiChrome Film Type and Speed: Digital

Images Kept at: Laguna Mountain Environmental, Inc.

Mo.	Day	Time	Exp.	Subject/Description	View Toward	Accession #
2	8	9:00	01	STP 9 30 cm Floor	N	PR-05720-001
2	8	9:00	02	STP 9 30 cm Floor	N	PR-05720-002
2	8	9:00	03	STP 9 30 cm Floor and Sidewall	N	PR-05720-003
2	8	9:00	04	STP 9 30 cm Floor and Sidewall	E	PR-05720-004
2	8	9:00	05	STP 9 30 cm Floor and Sidewall	S	PR-05720-005
2	8	9:00	06	STP 9 30 cm Floor and Sidewall	Ŵ	PR-05720-006
2	8	9:00	07	STP 9 30 cm Floor	-	PR-05720-007
2	8	9:00	08	Overview of STP 9 Location	NE	PR-05720-008
2	8	9:30	09	STP 12 30 cm Floor	N	PR-05720-009
2	8	9:30	10	STP 12 30 cm Floor and Sidewall	N	PR-05720-010
2	8	9:30	11	STP 12 30 cm Floor and Sidewall	E	PR-05720-011
2	8	9:30	12	STP 12 30 cm Floor and Sidewall	S	PR-05720-012
2	8	9:30	13	STP 12 30 cm Floor and Sidewall	Ŵ	PR-05720-012
2	8	9:30	14	STP 12 30 cm Floor	-	PR-05720-014
2	8	9:30	15	Overview of STP 12 Location	NE	PR-05720-015
2	8	10:30	16	STP 13 30 cm Floor	N	PR-05720-016
2	8	10:30	17	STP 13 30 cm Floor and Sidewall	N	PR-05720-017
2	8	10:30	18	STP 13 30 cm Floor and Sidewall	E	PR-05720-018
2	8	10:30	19	STP 13 30 cm Floor and Sidewall	S	PR-05720-019
2	8	10:30	20	STP 13 30 cm Floor and Sidewall	Ŵ	PR-05720-019
2	8	10:30	21	STP 13 30 cm Floor	-	PR-05720-021
2	8	10:30	22	Overview of STP 13 Location	NE	PR-05720-022
2	8	11:00	23	STP 17 30 cm Floor	N	PR-05720-023
2	8	11:00	24	STP 17 30 cm Floor and Sidewall	N	PR-05720-024
2	8	11:00	25	STP 17 30 cm Floor and Sidewall	E	PR-05720-025
2	8	11:00	26	STP 17 30 cm Floor and Sidewall	S	PR-05720-026
2	8	11:00	27	STP 17 30 cm Floor and Sidewall	W	PR-05720-027
2	8	11:00	28	STP 17 30 cm Floor	-	PR-05720-028
2	8	11:00	29	Overview of STP 17 Location	NE	PR-05720-029
2	8	11:30	30	Overview of Vegetation Cover in Community Garden	S-	PR-05720-030
2	8	11:30	31	Overview of Vegetation Cover in Community Garden	SE	PR-05720-031
2	8	11:30	32	Overview of Vegetation Cover in Community Garden	S-	PR-05720-032
2	8	12:00	33	STP 3 40 cm Floor	N	PR-05720-033
2	8	12:00	34	STP 3 40 cm Floor and Sidewall	N	PR-05720-034
2	8	12:00	35	STP 3 40 cm Floor and Sidewall	E	PR-05720-035
2	8	12:00	36	STP 3 40 cm Floor and Sidewall	S	PR-05720-036
2	8	12:00	37	STP 3 40 cm Floor and Sidewall	W	PR-05720-037
2	8	12:00	38	STP 3 40 cm Floor	-	PR-05720-038
2	8	12:00	39	Overview of STP 3 Location	SW	PR-05720-039
2	8	12:00	40	Concrete Slab Foundation	S	PR-05720-040
2	8	12:00	41	Concrete Slab Foundation	SSW	PR-05720-041
2	8	12:00	42	Concrete Slab Foundation	W	PR-05720-042
2	8	1:00	43	STP 1 30 cm Floor	N	PR-05720-043
2	8	1:00	44	STP 1 30 cm Floor and Sidewall	N	PR-05720-044
2	8	1:00	45	STP 1 30 cm Floor and Sidewall	E	PR-05720-045
2	8	1:00	46	STP 1 30 cm Floor and Sidewall	S	PR-05720-046
2	8	1:00	47	STP 1 30 cm Floor and Sidewall	Ŵ	PR-05720-047
-	-					

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION PHOTOGRAPH RECORD


Page 2 of 2

Project Name (No.): Eco Blok Residences Survey & Test (1704) Year 2017

Camera Format: FujiChrome Film Type and Speed: Digital

Images Kept at: Laguna Mountain Environmental, Inc.

Mo.	Day	Time	Exp.	Subject/Description	View Toward	Accession #
2	8	1:00	48	STP 1 30 cm Floor	-	PR-05720-048
2	8	1:00	49	Overview of STP 1 Location	NW	PR-05720-049
2	8	1:30	50	STP 2 40 cm Floor	N	PR-05720-050
2	8	1:30	51	STP 2 40 cm Floor and Sidewall	PR-05720-051	
2	8	1:30	52	STP 2 40 cm Floor and Sidewall	E	PR-05720-052
2	8	1:30	53	STP 2 40 cm Floor and Sidewall	S	PR-05720-053
2	8	1:30	54	STP 2 40 cm Floor and Sidewall	W	PR-05720-054
2	8	1:30	55	STP 2 40 cm Floor	-	PR-05720-055
2	8	1:30	56	Overview of STP 2 Location	SW	PR-05720-056
2	8	2:00	57	STP 4 30 cm Floor	N	PR-05720-057
2	8	2:00	58	STP 4 30 cm Floor and Sidewall	N	PR-05720-058
2	8	2:00	59	STP 4 30 cm Floor and Sidewall	E	PR-05720-059
2	8	2:00	60	STP 4 30 cm Floor and Sidewall	S	PR-05720-060
2	8	2:00	61	STP 4 30 cm Floor and Sidewall	W	PR-05720-061
2	8	2:00	62	STP 4 30 cm Floor	-	PR-05720-062
2	8	2:00	63	STP 4 30 cm Floor Closeup	-	PR-05720-063
2	8	2:00	64	Overview of STP 4 Location	NW	PR-05720-064
2	8	2:30	65	STP 5 30 cm Floor	N	PR-05720-065
2	8	2:30	66	STP 5 30 cm Floor and Sidewall	N	PR-05720-066
2	8	2:30	67	STP 5 30 cm Floor and Sidewall	E	PR-05720-067
2	8	2:30	68	STP 5 30 cm Floor and Sidewall	S	PR-05720-068
2	8	2:30	69	STP 5 30 cm Floor and Sidewall	W	PR-05720-069
2	8	2:30	70	STP 5 30 cm Floor	-	PR-05720-070
2	8	2:30	71	Overview of STP 5 Location	NE	PR-05720-071
	Ű	2.00				1100120011




PR-05720-031

PR-05720-032

PR-05720-033

PR-05720-034

PR-05720-035



PR-05720-066

PR-05720-067

PR-05720-068

PR-05720-069

The Sector

PR-05720-070



PR-05720-071

GEOTECHNICAL INVESTIGATION

ECO BLOK EAST SHASTA STREET SAN DIEGO, CALIFORNIA

PREPARED FOR

PFP COASTAL HOLDINGS, LLC SAN DIEGO, CALIFORNIA

DECEMBER 19, 2016 PROJECT NO. G1832-42-03



GEOTECHNICAL ENVIRONMENTAL MATERIALS GEOTECHNICAL E ENVIRONMENTAL E MATERIALS



ONAL GE

Project No. G1832-42-03 December 19, 2016

PFP Coastal Holdings, LLC 4380 La Jolla Village Drive, Suite 250 San Diego, California 92122

Attention: Mr. Matt Quinn

Subject: GEOTECHNICAL INVESTIGATION ECO BLOK EAST SHASTA STREET SAN DIEGO, CALIFORNIA

Dear Mr. Quinn:

In accordance with your request, we have performed a geotechnical investigation for the subject project. The accompanying report presents the findings of our study and our conclusions and recommendations pertaining to geotechnical aspects of developing the property as proposed. We have also provided design recommendations for storm water management.

It is our opinion that the site can be developed as currently proposed provided the recommendations of this report are followed.

Should you have questions regarding this investigation, or if we may be of further service, please contact the undersigned at your convenience.

Very truly yours,

GEOCON	NINCORPORATED	GARRY WELLS GARRY WELLS GANNON CC CANNON CC No. 2201
Rođney C GE 2533	Mikesel	Garry W. Cannon CEG 2201 RCE 56468 PROFESSION
RCM:GW	VC:dmc	WELLS CRUE
(e-mail) (3/del)	Addressee Golba Architecture, Inc. Attention : Mr. Tim Golba	No. C 056468 O REF BUE + STATE OF CALIFORNIA

TABLE OF CONTENTS

1.	PURF	POSE AND SCOPE	1
2.	SITE	AND PROJECT DESCRIPTION	1
3.	SOIL 3.1 3.2	AND GEOLOGIC CONDITIONS Undocumented Fill (Qudf) Old Terrace Deposits (Qt)	2
4.	GRO	UNDWATER	2
5.	GEOI 5.1 5.2 5.3 5.4 5.5	-OGIC HAZARDS Faulting and Seismicity Ground Rupture Liquefaction and Seismically Induced Settlement. Landslides. Tsunami and Seiche.	3 4 4 4
6.	CON0 6.1 6.2 6.3 6.4 6.5 6.6 6.7 6.8 6.9 6.10	CLUSIONS AND RECOMMENDATIONS. General Excavation and Soil Characteristics Grading Seismic Design Criteria Foundation and Concrete Slabs-On-Grade Recommendations	6 8 9 0 5 7 8
LIM	ITAT	IONS AND UNIFORMITY OF CONDITIONS	

MAPS AND ILLUSTRATIONS

Figure 1, Vicinity Map

Figure 2, Geologic Map

Figure 3, Typical Wall/Column Footing Dimension Detail

Figure 4, Typical Retaining Wall Drain Detail

APPENDIX A

FIELD INVESTIGATION Figures A-1 – A-6, Logs of Geotechnical Borings

APPENDIX B

Table B-I, Summary of Laboratory Maximum Dry Density and Optimum Moisture Content Test Results Table B-II, Summary of Laboratory Remolded Direct Shear Test Results Table B-III, Summary of Laboratory Expansion Index Test Results Table B-IV, Summary of Laboratory Water-Soluble Sulfate Test Results Table B-V, Summary of Laboratory Resistance Value (R-Value) Test Results Figure B-1, Grain Size Distribution Curves Figures B-2 – B-4, Consolidation Curves

TABLE OF CONTENTS (Concluded)

APPENDIX C STORM WATER MANAGEMENT

APPENDIX D RECOMMENDED GRADING SPECIFICATIONS

LIST OF REFERENCES

GEOTECHNICAL INVESTIGATION

1. PURPOSE AND SCOPE

This geotechnical investigation is specific to the proposed development located southeast of the intersection of Shasta Street and Fortuna Avenue in San Diego, California (see Vicinity Map, Figure 1). The purpose of this study is to evaluate surface and subsurface soil conditions and general site geology; to identify geotechnical constraints, if any, that might impact development of the property; and provide geotechnical and storm-water management recommendations for continued development of the property.

The scope of our study included a review of the undated plan prepared by Latitude 33 titled *Shasta East – Preliminary Site Exhibit,* review of previous reports prepared by Geocon Incorporated in the area, a field investigation consisting of exploratory borings and infiltration tests; engineering analyses; laboratory testing; and preparation of this report.

The field investigation consisted of excavating six exploratory borings to depths of approximately 16 feet to examine the underlying soils within portions of the property. The approximate locations of the exploratory borings are shown the Geologic Map, Figure 2. Logs of the exploratory borings and a discussion of the field investigation are presented in Appendix A.

We performed laboratory tests on selected soil samples obtained during our field investigation to evaluate pertinent physical properties for engineering analyses and to assist in providing recommendations for site grading and foundation design criteria. Details of the laboratory testing and a summary of test results are presented in Appendix B.

We performed four, in-place, hydraulic-conductivity tests using a Soilmoisture Corp Aardvark Permeameter. The tests were conducted in 4-inch-diameter hand-excavated borings. The results of the hydraulic-conductivity testing and information relating to geotechnical aspects of storm water management are provided in Appendix C.

The conclusions and recommendations presented herein are based on our analysis of the data obtained from the exploratory field investigation, laboratory test results, and our experience with similar soil and geologic conditions on this and adjacent properties.

2. SITE AND PROJECT DESCRIPTION

The site is located southeast of the intersection of Shasta Street and Fortuna Avenue in San Diego, California. The site is bordered to the north by Fortuna Avenue, to the west by Shasta Street, to the east by an alley and residential homes, and to the south by residential structures. The site slopes gently from

north to south with elevations ranging from approximately 47 feet Mean Sea Level (MSL) at the north end of the property to approximately 33 feet MSL at the southern end. The site is currently occupied by three relatively large residential structures and landscaped areas. The residential structures are currently vacant.

We understand planned development will consist of demolishing the existing structures and landscaping to construct 30, single-family homes. We expected cuts and fills of approximately 3 feet or less across the site to produce the building pads. Sixteen infiltration BMP basins are planned along the perimeter of the property.

The descriptions above are based on a review of the referenced site plan. If development plans differ significantly from those described herein, Geocon Incorporated should be contacted for review and possible revisions to this report.

3. SOIL AND GEOLOGIC CONDITIONS

The site is underlain by undocumented fill and old terrace deposits (formerly Bay Point Formation). The soil and geologic unit are described below. Their approximate lateral extent is shown on the Geologic Map, Figure 2 (Map Pocket).

3.1 Undocumented Fill (Qudf)

We encountered undocumented fill in borings B-4 and B-6 to depths of about 1 to 1.5 feet thick. The fill materials consist of loose, damp to moist, dark brown, silty, fine sand. The undocumented fill is not suitable for support of additional fill or structural loads in its present condition and will require remedial grading in the form of removal, proper moisture conditioning as necessary, and compaction.

3.2 Old Terrace Deposits (Qt)

We encountered Quaternary-age old terrace deposits in all the exploratory borings performed during our site investigation. The terrace deposits generally consist of loose to medium dense, damp to moist, light brown to brown, fine sand. The upper portion of old terrace deposits is not suitable for the support of additional fill or structural loads and will require remedial grading in the form of removal, proper moisture conditioning, and compaction.

4. GROUNDWATER

We did not encounter groundwater during our investigation; however, it is not uncommon for groundwater or seepage conditions to develop where none previously existed. We expect groundwater to be near sea level, or at a depth of approximately 30 to 40 feet below the existing grade. Groundwater

elevation is dependent on seasonal precipitation, irrigation, land use and other factors and will vary as a result. Proper surface drainage will be important to the future performance of the project.

5. GEOLOGIC HAZARDS

5.1 Faulting and Seismicity

We used the computer program *EZ-FRISK* (2016) to locate known active faults within a search radius of 50 miles from the property. The nearest known active fault is the Newport-Inglewood/Rose Canyon Fault Zone, located less than 2 miles west of the site. The Newport-Inglewood/Rose Canyon Fault Zone is the dominant source of potential ground motion. Earthquakes that might occur on the Newport-Inglewood/Rose Canyon Fault Zone or other faults within the southern California and northern Baja California area are potential generators of significant ground motion at the site. The estimated deterministic maximum earthquake magnitude and peak ground acceleration for the Newport-Inglewood/Rose Canyon Fault are 7.5 and 0.53 g, respectively. Table 5.1.1 lists the estimated maximum earthquake magnitude and peak ground acceleration for the most dominant faults in relationship to the site location. We calculated peak ground acceleration (PGA) using Boore and Atkinson (2008), Campbell and Bozorgnia (2008), and Chiou and Youngs (2007) acceleration-attenuation relationships.

			Peak G	round Acceler	ration
Fault Name	Distance from Site (miles)	Maximum Earthquake Magnitude (Mw)	Boore- Atkinson (2008) NGA USGS 2008 (g)	Campbell- Bozorgnia (2008) NGA USGS 2008 (g)	Chiou- Youngs (2007) NGA USGS 2008 (g)
Newport-Inglewood	2	7.5	0.44	0.40	0.53
Rose Canyon	2	6.9	0.42	0.40	0.49
Coronado Bank	12	7.4	0.24	0.18	0.23
Palos Verdes/Coronado Bank	12	7.7	0.26	0.19	0.26
Elsinore	40	7.85	0.14	0.09	0.12
Earthquake Valley	46	6.8	0.08	0.06	0.05

 TABLE 5.1.1

 DETERMINISTIC SPECTRA SITE PARAMETERS

We used the computer program *EZ-FRISK* to perform a probabilistic seismic hazard analysis. The computer program *EZ-FRISK* operates under the assumption that the occurrence rate of earthquakes on each mapped Quaternary fault is proportional to the fault slip rate. The program accounts for earthquake magnitude as a function of fault rupture length. Site acceleration estimates are made using the earthquake magnitude and distance from the site to the rupture zone. The program also accounts for

uncertainty in each of following: (1) earthquake magnitude, (2) rupture length for a given magnitude, (3) location of the rupture zone, (4) maximum possible magnitude of a given earthquake, and (5) acceleration at the site from a given earthquake along each fault. By calculating the expected accelerations from considered earthquake sources, the program calculates the total average annual expected number of occurrences of site acceleration greater than a specified value. We utilized acceleration-attenuation relationships suggested by Boore and Atkinson (2008), Campbell and Bozorgnia (2008), and Chiou and Youngs (2007) in the analysis. Table 5.1.2 presents the site-specific probabilistic seismic hazard parameters including acceleration-attenuation relationships and the probability of exceedence.

 TABLE 5.1.2

 PROBABILISTIC SEISMIC HAZARD PARAMETERS

Probability of Exceedence	Peak Ground Acceleration		
	Boore-Atkinson NGA USGS 2008 (g)	Campbell-Bozorgnia NGA USGS 2008 (g)	Chiou-Youngs (2007) NGA USGS 2008 (g)
2% in a 50 Year Period	0.58	0.51	0.62
5% in a 50 Year Period	0.39	0.35	0.41
10% in a 50 Year Period	0.28	0.24	0.27

While listing peak accelerations is useful for comparison of potential effects of fault activity in a region, other considerations are important in seismic design, including frequency and duration of motion and soil conditions underlying the site. Seismic design of the structures should be evaluated in accordance with the California Building Code (CBC).

5.2 Ground Rupture

The risk associated with ground rupture hazard is low due to the absence of active faults at the subject site.

5.3 Liquefaction and Seismically Induced Settlement

The risk associated with liquefaction hazard is low due to the lack of near surface groundwater and the dense nature and age of the underlying old terrace deposit.

5.4 Landslides

The risk associated with landslide hazard is low due to the generally flat topography of the site and vicinity.

5.5 Tsunami and Seiche

According to CGS (2009) the site is located above the tsunami inundation line; therefore the risk associated with inundation during a tsunami event is low.

The site is located approximately 1,500 feet from the shoreline of Mission Bay at an elevation around 35 feet MSL; therefore, the risk associated with inundation during a seiche event is low.

6. CONCLUSIONS AND RECOMMENDATIONS

6.1 General

- 6.1.1 From a geotechnical engineering standpoint, it is our opinion that the site is suitable for the proposed improvements provided the recommendations presented herein are implemented in design and construction of the project.
- 6.1.2 The site is underlain by undocumented fill and old terrace deposits. Remedial grading in the form of removal and compaction of the undocumented fill and upper portion of the old terrace deposits will be necessary in areas to receive structures or settlement-sensitive improvements.
- 6.1.3 The proposed structures can be supported on conventional shallow footings founded in properly compacted fill as recommended herein.
- 6.1.4 Project grading and foundation plans have not been provided for our review. Geocon Incorporated should review the plans prior to the submittal to regulatory agencies for approval. Additional analysis may be required once the plans have been provided.
- 6.1.5 Groundwater was not encountered during our field investigation and is not expected to be encountered during grading operations.
- 6.1.6 The risk associated with geologic hazards due to ground rupture, liquefaction, landslides, and inundation by tsunami or seiche is low.
- 6.1.7 Subsurface conditions observed may be extrapolated to reflect general soil/geologic conditions at the site; however, some variations in subsurface conditions between boring locations should be expected.

6.2 Excavation and Soil Characteristics

- 6.2.1 Excavation of the site soil should be possible with moderate to heavy effort using conventional heavy-duty equipment.
- 6.2.2 Based on the soil types encountered during our recent field investigation, the onsite soils are expected to be "non-expansive" (expansion index [EI] of 20 or less) as defined by 2016 California Building Code (CBC) Section 1803.5.3. Table 6.2.1 presents soil classifications based on the expansion index. We expect a majority of the soil encountered possess a very low expansion potential (EI of 20 or less).

Expansion Index (EI)	Expansion Classification	2013 CBC Expansion Classification
0-20	Very Low	Non-Expansive
21 – 50	Low	
51 – 90	Medium	
91 – 130	High	Expansive
Greater Than 130	Very High	

TABLE 6.2.1EXPANSION CLASSIFICATION BASED ON EXPANSION INDEX

6.2.3 We performed laboratory tests on samples of the site soils to check the percentage of water-soluble sulfate content. Results from the previous laboratory water-soluble sulfate content tests presented in Appendix B and indicate that the on-site materials tested possess "Not Applicable" and "S0" sulfate exposure to concrete structures as defined by 2016 CBC Section 1904 and ACI 318-14 Chapter 19. Table 6.2.2 presents a summary of concrete requirements set forth by 2016 CBC Section 1904 and ACI 318-000 CBC Section 1904 and ACI 318. We recommend ACI guidelines be followed in determining the type of concrete to be utilized on the project. The presence of water-soluble sulfates is not a visually discernible characteristic; therefore, other soil samples from the site could yield different concentrations. Additionally, over time landscaping activities (i.e., addition of fertilizers and other soil nutrients) may affect the concentration.

Sulfate Exposure	Exposure Class	Water-Soluble Sulfate Percent by Weight	Cement Type	Maximum Water to Cement Ratio by Weight	Minimum Compressive Strength (psi)
Not Applicable	SO	0.00-0.10			2,500
Moderate	S1	0.10-0.20	П	0.50	4,000
Severe	S2	0.20-2.00	V	0.45	4,500
Very Severe	S3	> 2.00	V+Pozzolan or Slag	0.45	4,500

TABLE 6.2.2 REQUIREMENTS FOR CONCRETE EXPOSED TO SULFATE-CONTAINING SOLUTIONS

6.2.4 Geocon Incorporated does not practice in the field of corrosion engineering; therefore, further evaluation by a corrosion engineer may be needed if improvements susceptible to corrosion are planned.

6.3 Grading

- 6.3.1 All grading should be performed in accordance with the *Recommended Grading Specifications* contained in Appendix D. The recommendations of this section take precedence over those presented in Appendix D.
- 6.3.2 Prior to commencing grading, a preconstruction conference should be held at the site with the owner or developer, grading contractor, civil engineer, and geotechnical engineer in attendance. Special soil handling and/or the grading plans can be discussed at that time.
- 6.3.3 Grading should be performed in conjunction with the observation and compaction testing services of Geocon Incorporated. Fill soil should be observed on a full-time basis during placement and tested to check in-place dry density and moisture content.
- 6.3.4 Site preparation should begin with the removal of all deleterious material and vegetation. The depth of removal should be such that material exposed in cut areas or soils to be used as fill are relatively free of organic matter. Material generated during stripping and/or site demolition should be exported from the site.
- 6.3.5 All existing utilities that will be abandoned should be completely removed, capped at the property limits, and the resulting excavation backfilled with compacted fill.
- 6.3.6 To provide support for the new structures, we recommend all of the undocumented fill and the upper portion of the old terrace deposits be removed to a depth of 5 feet below pad grade or 3 feet below the bottom of proposed footings, whichever is deeper, and replaced as properly compacted fill. On site soil, which is free of deleterious material, is suitable for use as compacted fill. The removals should extend a horizontal distanced beyond the edge of the building pads a distance of at least 5 feet.
- 6.3.7 The surface of areas to receive fill should be scarified to a depth of approximately 12 inches; moisture conditioned to above optimum moisture content; and compacted. Fill soils may then be placed and compacted in layers to the design finish grade elevations. The layers should be no thicker than will allow for adequate bonding and compaction. All fill and backfill should be compacted to at least 90 percent of maximum dry density at or slightly above optimum moisture content, as determined by the current version of ASTM D 1557.
- 6.3.8 Imported fill should consist of granular soil with a "very low" to "low" expansion potential (El of 50 or less) and be free of deleterious material and stones larger than 3 inches. Geocon Incorporated should be notified of the import soil source and should perform laboratory

testing prior to its arrival at the site to evaluate its suitability as fill material. In addition, the imported soil should be certified as being free of hazardous contaminants as well as chemical properties that could adversely impact proposed construction material.

6.4 Seismic Design Criteria

6.4.1 We used the computer program U.S. Seismic Design Maps (USGS, 2016). Table 6.4.1 summarizes site-specific design criteria obtained from the 2016 California Building Code (CBC; Based on the 2015 International Building Code [IBC] and ASCE 7-10), Chapter 16 Structural Design, Section 1613 Earthquake Loads. The short spectral response uses a period of 0.2 second. The building structure and improvements should be designed using a Site Class D. We evaluated the site class based on the discussion in Section 1613.3.2 of the 2016 CBC and Table 20.3-1 of ASCE 7-10. The values presented in Table 6.4.1 are for the risk-targeted maximum considered earthquake (MCE_R).

Parameter	Value	2013 CBC Reference
Site Class	D	Section 1613.3.2
MCE _R Ground Motion Spectral Response Acceleration – Class B (short), S _S	1.214 g	Figure 1613.3.1(1)
MCE _R Ground Motion Spectral Response Acceleration – Class B (1 sec), S ₁	0.466 g	Figure 1613.3.1(2)
Site Coefficient, F _A	1.014	Table 1613.3.3(1)
Site Coefficient, Fv	1.534	Table 1613.3.3(2)
Site Class Modified MCE_R Spectral Response Acceleration (short), S_{MS}	1.232 g	Section 1613.3.3 (Eqn 16-37)
Site Class Modified MCE_R Spectral Response Acceleration (1 sec), S_{M1}	0.714 g	Section 1613.3.3 (Eqn 16-38)
5% Damped Design Spectral Response Acceleration (short), S_{DS}	0.821 g	Section 1613.3.4 (Eqn 16-39)
5% Damped Design Spectral Response Acceleration (1 sec), S_{D1}	0.476 g	Section 1613.3.4 (Eqn 16-40)

TABLE 6.4.12016 CBC SEISMIC DESIGN PARAMETERS

6.4.2 Table 6.4.2 presents additional seismic design parameters for projects located in Seismic Design Categories of D through F in accordance with ASCE 7-10 for the mapped maximum considered geometric mean (MCEG).

Parameter	Value	ASCE 7-10 Reference
Mapped MCE_G Peak Ground Acceleration, PGA	0.538 g	Figure 22-7
Site Coefficient, F _{PGA}	1.000	Table 11.8-1
Site Class Modified MCE_G Peak Ground Acceleration, PGA _M	0.538 g	Section 11.8.3 (Eqn 11.8-1)

TABLE 6.4.22016 CBC SITE ACCELERATION DESIGN PARAMETERS

6.4.3 Conformance to the criteria in Tables 6.4.1 and 6.4.2 for seismic design does not constitute any kind of guarantee or assurance that significant structural damage or ground failure will not occur if a large earthquake occurs. The primary goal of seismic design is to protect life, not to avoid all damage, since such design may be economically prohibitive.

6.5 Foundation and Concrete Slabs-On-Grade Recommendations

- 6.5.1 The foundation and slab-on-grade recommendations presented herein are based on soil conditions only and are not intended to be used in lieu of those required for structural purposes.
- 6.5.2 The following foundation recommendations are based on the assumption that remedial grading will be performed as recommended herein and that footings will be founded entirely on properly compacted fill. These recommendations also assume that the soils within 3 feet of finish grade will consist of soils with an Expansion Index of 50 or less.
- 6.5.3 Conventional continuous footings should have a minimum embedment depth of 18 inches below lowest adjacent grade. The footings should be at least 12 inches wide. Isolated spread footings should be at least 2 feet square and founded at least 18 inches below lowest adjacent pad grade. A footing dimension detail is presented on Figure 3.
- 6.5.4 Footings, as proportioned above, may be designed for an allowable soil bearing pressure of 2,000 pounds per square foot (psf), dead plus live loads. We estimate total static settlement as a result of footings imposing the above bearing pressures to be on the order of 1-inch total and ³/₄-inch differential in 40 feet.
- 6.5.5 The allowable bearing pressure may be increased by up to one-third for transient loads due to wind or seismic forces.

- 6.5.6 Continuous footings should be reinforced with four, No. 5 steel, reinforcing bars, two placed near the top of the footing and two near the bottom. The project structural engineer should design reinforcement for spread footings.
- 6.5.7 Foundation excavations should be observed by the geotechnical engineer (a representative of Geocon Incorporated) prior to the placement of reinforcing steel and concrete to assess that the exposed soil conditions are consistent with those expected and that they have been extended to the appropriate bearing strata. If unexpected soil conditions are encountered, foundation modifications may be required.
- 6.5.8 The contractor should maintain the subgrade soils at the soil placement moisture content by sprinkling water in the footing excavations and slab area as necessary.
- 6.5.9 Interior concrete slabs-on-grade for the proposed structure should be at least 4 inches thick. Minimum slab reinforcement should consist of No. 3 steel, reinforcing bars placed 18 inches on center in both horizontal directions and positioned near the slab midpoint.
- 6.5.10 A vapor retarder should underlie slabs that may receive moisture-sensitive floor coverings or may be used to store moisture-sensitive materials. The vapor retarder design should be consistent with the guidelines presented in the American Concrete Institute's (ACI) Guide for Concrete Slabs that Receive Moisture-Sensitive Flooring Materials (ACI 302.2R-06). The vapor retarder should be installed in accordance with manufacturer's recommendations and ASTM requirements in a manner that prevents puncture. The project architect or developer should specify the type of vapor retarder used based on the type of floor covering that will be installed and if the structure will possess a humidity controlled environment.
- 6.5.11 The project foundation engineer, architect, and/or developer should determine the thickness of the bedding sand below the slab. Typically, 3 or 4 inches of sand bedding is used in Southern California. Geocon Incorporated should be contacted to provide recommendations if the bedding sand is thicker than 6 inches.
- 6.5.12 The foundation design engineer should provide appropriate concrete mix design criteria and curing measures to assure proper curing of the slab by reducing the potential for rapid moisture loss and subsequent cracking and/or slab curl. The foundation design engineer should designate the concrete mix design and proper curing methods on the foundation plans. It is critical that the foundation contractor understands and follows the recommendations presented on the foundation plans.

- 6.5.13 Crack control joints should be spaced at intervals not greater than 10 feet and should be constructed using sawcuts or other methods as soon as practical following concrete placement. Crack control joints should extend a minimum depth of one-fourth the slab thickness. Construction joints should be designed by the project structural engineer.
- 6.5.14 As an alternative to the conventional foundation recommendations, consideration should be given to the use of post-tensioned concrete slab and foundation systems for the support of the proposed structures. The post-tensioned systems should be designed by a structural engineer experienced in post-tensioned slab design and design criteria of the Post-Tensioning Institute (PTI), Third Edition, as required by the 2016 California Building Code (CBC Section 1808.6). Although this procedure was developed for expansive soil conditions, it can also be used to reduce the potential for foundation distress due to differential fill settlement. The post-tensioned design should incorporate the geotechnical parameters presented on Table 6.5.1. The parameters presented in Table 6.5.1 are based on the guidelines presented in the PTI, Third Edition design manual.

TABLE 6.5.1
POST-TENSIONED FOUNDATION SYSTEM DESIGN PARAMETERS

Thornthwaite Index	-20
Equilibrium Suction	3.9
Edge Lift Moisture Variation Distance, e_M (feet)	5.1
Edge Lift, y_M (inches)	1.10
Center Lift Moisture Variation Distance, e_M (feet)	9.0
Center Lift, y _M (inches)	0.47

- 6.5.15 The foundations for the post-tensioned slabs should be embedded in accordance with the recommendations of the structural engineer. If a post-tensioned mat foundation system is planned, the slab should possess a thickened edge with a minimum width of 12 inches and extend at least 6 inches below the clean sand or crushed rock layer.
- 6.5.16 If the structural engineer proposes a post-tensioned foundation design method other than PTI, Third Edition:
 - The deflection criteria presented in Table 6.5.1 are still applicable.
 - Interior stiffener beams should be used.
 - The width of the perimeter foundations should be at least 12 inches.
 - The perimeter footing embedment depths should be at least 18 inches. The embedment depths should be measured from the lowest adjacent pad grade.

- 6.5.17 Our experience indicates post-tensioned slabs are susceptible to excessive edge lift, regardless of the underlying soil conditions. Placing reinforcing steel at the bottom of the perimeter footings and the interior stiffener beams may mitigate this potential. The placement of the reinforcing tendons in the top of the slab and the resulting eccentricity after tensioning could reduce the ability of the system to mitigate edge lift. The structural engineer should design the foundation system to reduce the potential of edge lift occurring for the proposed structures.
- 6.5.18 During the construction of the post-tension foundation system, the concrete should be placed monolithically. Under no circumstances should cold joints form between the footings/grade beams and the slab during the construction of the post-tension foundation system.
- 6.5.19 Post-tensioned foundations may be designed for an allowable soil bearing pressure of 2,000 pounds per square foot (psf) (dead plus live load). This bearing pressure may be increased by one-third for transient loads due to wind or seismic forces. The estimated maximum total and differential settlement for the planned structures due to foundation loads is 1 inch and ³/₄ inch, respectively. Differential settlement is estimated to occur over a span of 40 feet.
- 6.5.20 Isolated footings outside of the post-tensioned slab area, if present, should have the minimum embedment depth and width recommended for conventional foundations. The use of isolated footings, which are located beyond the perimeter of the building and support structural elements connected to the building, are not recommended. Where this condition cannot be avoided, the isolated footings should be connected to the building foundation system with grade beams.
- 6.5.21 Special subgrade presaturation is not deemed necessary prior to placing concrete; however, the exposed foundation and slab subgrade soil should be moisture conditioned, as necessary, to maintain a moist condition as would be expected in any such concrete placement.
- 6.5.22 Where buildings or other improvements are planned near the top of a slope steeper than 3:1 (horizontal:vertical), special foundations and/or design considerations are recommended due to the tendency for lateral soil movement to occur.
 - For fill slopes less than 20 feet high or cut slopes regardless of height, building footings should be deepened such that the bottom outside edge of the footing is at least 7 feet horizontally from the face of the slope.
 - When located next to a descending 3:1 (horizontal:vertical) fill slope or steeper, the foundations should be extended to a depth where the minimum horizontal distance is equal to H/3 (where H equals the vertical distance from the top of the fill slope to the base of the fill soil) with a minimum of 7 feet but need not exceed 40 feet. The horizontal distance is measured from the outer, deepest edge of the footing to the

face of the slope. A post-tensioned slab and foundation system or mat foundation system can be used to help reduce potential foundation distress associated with slope creep and lateral fill extension. Specific design parameters or recommendations for either of these alternatives can be provided if desired.

- If swimming pools are planned, Geocon Incorporated should be contacted for a review of specific site conditions.
- Swimming pools located within 7 feet of the top of cut or fill slopes are not recommended. Where such a condition cannot be avoided, the portion of the swimming pool wall within 7 feet of the slope face be designed assuming that the adjacent soil provides no lateral support. This recommendation applies to fill slopes up to 30 feet in height, and cut slopes regardless of height. For swimming pools located near the top of fill slopes greater than 30 feet in height, additional recommendations may be required and Geocon Incorporated should be contacted for a review of specific site conditions.
- Although other improvements, which are relatively rigid or brittle, such as concrete flatwork or masonry walls, may experience some distress if located near the top of a slope, it is generally not economical to mitigate this potential. It may be possible, however, to incorporate design measures which would permit some lateral soil movement without causing extensive distress. Geocon Incorporated should be consulted for specific recommendations.
- 6.5.23 The exterior flatwork recommendations provided herein assumes that grading is performed as recommended above and that the near surface soils are very low to low expansive (El <50). Exterior slabs not subjected to vehicular traffic should be a minimum of 4 inches thick and when in excess of 8 feet wide, reinforced with 6 x 6-6/6 welded wire mesh. The mesh should be placed in the middle of the slab. Proper mesh positioning is critical to future performance of the slabs. The contractor should take extra measures to provide proper mesh placement. Prior to construction of slabs, the upper 12 inches of subgrade soils should be moisture conditioned one to three percent above optimum moisture content and compacted to at least 90 percent of the laboratory maximum dry density per ASTM 1557.
- 6.5.24 To control the location and spread of concrete shrinkage and/or expansion cracks, it is recommended that crack-control joints be included in the design of concrete slabs. Crack-control joint spacing should not exceed, in feet, twice the recommended slab thickness in inches (e.g., 10 feet by 10 feet). Crack-control joints should be created while the concrete is still fresh using a grooving tool or shortly thereafter using saw cuts. The structural engineer should take criteria of the American Concrete Institute into consideration when establishing crack-control spacing patterns.
- 6.5.25 The recommendations of this report are intended to reduce the potential for cracking of slabs due to expansive soil (if present), differential settlement of existing soil or soil with varying

thicknesses. However, even with the incorporation of the recommendations presented herein, foundations, stucco walls, and slabs-on-grade placed on such conditions may still exhibit some cracking due to soil movement and/or shrinkage. The occurrence of concrete shrinkage cracks is independent of the supporting soil characteristics. Their occurrence may be reduced and/or controlled by limiting the slump of the concrete, proper concrete placement and curing, and by the placement of crack control joints at periodic intervals, in particular, where re-entrant slab corners occur.

- 6.5.26 Foundation excavations should be observed by a representative of Geocon Incorporated prior to the placement of reinforcing steel and concrete to check that the exposed soil conditions are consistent with those anticipated and have been extended to appropriate bearing strata. If unexpected soil conditions are encountered, foundation modifications may be required.
- 6.5.27 Geocon Incorporated should be consulted to provide additional design parameters as required by the structural engineer.

6.6 Retaining Walls and Lateral Loads

- 6.6.1 Retaining walls that are allowed to rotate more than 0.001H (where H equals the height of the retaining portion of the wall) at the top of the wall and having a level backfill surface should be designed for an active soil pressure equivalent to the pressure exerted by a fluid density of 35 pcf. Where the backfill will be inclined at 2:1 (horizontal:vertical), an active soil pressure of 50 pcf is recommended. Expansive soil should not be used as backfill material behind retaining walls. Soil placed for retaining wall backfill should have an Expansion Index less than 50.
- 6.6.2 Where walls are restrained from movement at the top, an additional uniform pressure of 7H psf (where H equals the height of the retaining wall portion of the wall in feet) should be added to the active soil pressure where the wall possesses a height of 8 feet or less and 12H where the wall is greater than 8 feet. For retaining walls subject to vehicular loads within a horizontal distance equal to two-thirds the wall height, a surcharge equivalent to two feet of fill soil should be added.
- 6.6.3 Soil contemplated for use as retaining wall backfill, including imported soils, should be identified in the field prior to backfill. At that time Geocon Incorporated should obtain samples for laboratory testing to evaluate its suitability. Modified lateral earth pressures may be necessary if the backfill soil does not meet the required expansion index or shear strength. City or regional standard wall designs, if used, are based on a specific active lateral earth pressure and/or soil friction angle. In this regard, on-site soil or import soil to be used as

backfill may or may not meet the values for standard wall designs. Geocon Incorporated should be consulted to assess the suitability of the on-site soil or imported soil for use as wall backfill if standard wall designs will be used.

- 6.6.4 Unrestrained walls will move laterally when backfilled and loading is applied. The amount of lateral deflection is dependent on the wall height, the type of soil used for backfill, and loads acting on the wall. The wall designer should provide appropriate lateral deflection quantities for planned retaining walls structures, if applicable. These lateral values should be considered when planning types of improvements above retaining wall structures.
- 6.6.5 Retaining walls should be provided with a drainage system adequate to prevent the buildup of hydrostatic forces and should be waterproofed as required by the project architect. The use of drainage openings through the base of the wall (weep holes) is not recommended where the seepage could be a nuisance or otherwise adversely affect the property adjacent to the base of the wall. The above recommendations assume a properly compacted granular (El <50) free-draining backfill material with no hydrostatic forces or imposed surcharge load. A typical retaining wall drainage detail is presented on Figure 4. If conditions different than those described are expected, or if specific drainage details are desired, Geocon Incorporated should be contacted for additional recommendations.
- 6.6.6 In general, wall foundations having a minimum embedment depth and width of 1 foot may be designed for an allowable soil bearing pressure of 2,000 psf. The allowable soil bearing pressure may be increased by an additional 300 psf and 500 psf for each additional foot of foundation width and depth, respectively, to a maximum allowable bearing capacity of 3,500 psf. These values are for dead plus live loads and may be increased by one-third when considering transient loads due to wind or seismic forces.
- 6.6.7 The proximity of the foundation to the top of a slope steeper than 3:1 could impact the allowable soil bearing pressure. Therefore, Geocon Incorporated should be consulted where such a condition is anticipated. As a minimum, wall footings should be deepened such that the bottom outside edge of the footing is at least seven feet from the face of slope when located adjacent and/or at the top of descending slopes.
- 6.6.8 The structural engineer should determine the seismic design category for the project in accordance with Section 1613 of the CBC. If the project possesses a seismic design category of D, E, or F, retaining walls that support more than 6 feet of backfill should be designed with seismic lateral pressure in accordance with Section 1803.5.12 of the 2016 CBC. The seismic load is dependent on the retained height where H is the height of the wall, in feet, and the calculated loads result in pounds per square foot (psf) exerted at the base of the wall

and zero at the top of the wall. A seismic load of 21H should be used for design. We used the peak ground acceleration adjusted for Site Class effects, PGA_M , of 0.538 g calculated from ASCE 7-10 Section 11.8.3 and applied a pseudo-static coefficient of 0.33.

- 6.6.9 For resistance to lateral loads, a passive earth pressure equivalent to a fluid density of 300 pcf is recommended for footings or shear keys poured neat against properly compacted granular fill soils or undisturbed formation materials. The passive pressure assumes a horizontal surface extending away from the base of the wall at least five feet or three times the surface generating the passive pressure, whichever is greater. The upper 12 inches of material not protected by floor slabs or pavement should not be included in the design for lateral resistance. Where walls are planned adjacent to and/or on descending slopes, a passive pressure of 150 pcf should be used in design.
- 6.6.10 An allowable friction coefficient of 0.4 may be used for resistance to sliding between soil and concrete. This friction coefficient may be combined with the passive earth pressure when determining resistance to lateral loads.

6.7 Slope Maintenance

6.7.1 Slopes that are steeper than 3:1 (horizontal:vertical) may, under conditions which are both difficult to prevent and predict, be susceptible to near surface (surficial) slope instability. The instability is typically limited to the outer three feet of a portion of the slope and usually does not directly impact the improvements on the pad areas above or below the slope. The occurrence of surficial instability is more prevalent on fill slopes and is generally preceded by a period of heavy rainfall, excessive irrigation, or the migration of subsurface seepage. The disturbance and/or loosening of the surficial soils, as might result from root growth, soil expansion, or excavation for irrigation lines and slope planting, may also be a significant contributing factor to surficial instability. It is, therefore, recommended that, to the maximum extent practical: (a) disturbed/loosened surficial soils be either removed or properly recompacted, (b) irrigation systems be periodically inspected and maintained to eliminate leaks and excessive irrigation, and (c) surface drains on and adjacent to slopes be periodically maintained to preclude ponding or erosion. It should be noted that although the incorporation of the above recommendations should reduce the potential for surficial slope instability, it will not eliminate the possibility, and, therefore, it may be necessary to rebuild or repair a portion of the project's slopes in the future.

6.8 Storm Water Management

6.8.1 If storm water management devices are not properly designed and constructed, there is a risk for distress to improvements and property located hydrologically down gradient or adjacent

to these devices. Factors such as the amount of water being detained, its residence time, and soil permeability have an important effect on seepage transmission and the potential adverse impacts that may occur if the storm water management features are not properly designed and constructed. We have not performed a hydrogeological study at the site. If infiltration of storm water runoff into the subsurface occurs, downstream improvements may be subjected to seeps, springs, slope instability, raised groundwater, movement of foundations and slabs, or other undesirable impacts as a result of water infiltration.

6.8.2 We performed an infiltration study on the property. A summary of our study and storm water management recommendations are provided in Appendix C. Based on the results of our study, infiltration is considered infeasible.

6.9 Site Drainage and Moisture Protection

- 6.9.1 Adequate site drainage is critical to reduce the potential for differential soil movement, erosion and subsurface seepage. Under no circumstances should water be allowed to pond adjacent to footings. The site should be graded and maintained such that surface drainage is directed away from structures in accordance with 2016 CBC 1804.4 or other applicable standards. In addition, surface drainage should be directed away from the top of slopes into swales or other controlled drainage devices. Roof and pavement drainage should be directed into conduits that carry runoff away from the proposed structure.
- 6.9.2 In the case of basement walls or building walls retaining landscaping areas, a water-proofing system should be used on the wall and joints, and a Miradrain drainage panel (or similar) should be placed over the waterproofing. The project architect or civil engineer should provide detailed specifications on the plans for all waterproofing and drainage.
- 6.9.3 Underground utilities should be leak free. Utility and irrigation lines should be checked periodically for leaks, and detected leaks should be repaired promptly. Detrimental soil movement could occur if water is allowed to infiltrate the soil for prolonged periods of time.
- 6.9.4 Landscaping planters adjacent to paved areas are not recommended due to the potential for surface or irrigation water to infiltrate the pavement's subgrade and base course. We recommend that subdrains to collect excess irrigation water and transmit it to drainage structures or impervious above-grade planter boxes be used. In addition, where landscaping is planned adjacent to the pavement, we recommend construction of a cutoff wall along the edge of the pavement that extends at least 6 inches below the bottom of the base material.

6.10 Grading and Foundation Plan Review


6.10.1 Geocon Incorporated should review the grading and foundation plans for the project prior to final design submittal to determine if additional analysis and/or recommendations are required.

LIMITATIONS AND UNIFORMITY OF CONDITIONS


- 1. The firm that performed the geotechnical investigation for the project should be retained to provide testing and observation services during construction to provide continuity of geotechnical interpretation and to check that the recommendations presented for geotechnical aspects of site development are incorporated during site grading, construction of improvements, and excavation of foundations. If another geotechnical firm is selected to perform the testing and observation services during construction operations, that firm should prepare a letter indicating their intent to assume the responsibilities of project geotechnical engineer of record. A copy of the letter should be provided to the regulatory agency for their records. In addition, that firm should provide revised recommendations concerning the geotechnical aspects of the proposed development, or a written acknowledgement of their concurrence with the recommendations presented in our report. They should also perform additional analyses deemed necessary to assume the role of Geotechnical Engineer of Record.
- 2. The recommendations of this report pertain only to the site investigated and are based upon the assumption that the soil conditions do not deviate from those disclosed in the investigation. If any variations or undesirable conditions are encountered during construction, or if the proposed construction will differ from that anticipated herein, Geocon Incorporated should be notified so that supplemental recommendations can be given. The evaluation or identification of the potential presence of hazardous or corrosive materials was not part of the scope of services provided by Geocon Incorporated.
- 3. This report is issued with the understanding that it is the responsibility of the owner, or of his representative, to ensure that the information and recommendations contained herein are brought to the attention of the architect and engineer for the project and incorporated into the plans, and that the necessary steps are taken to see that the contractor and subcontractors carry out such recommendations in the field.
- 4. The findings of this report are valid as of the present date. However, changes in the conditions of a property can occur with the passage of time, whether they are due to natural processes or the works of man on this or adjacent properties. In addition, changes in applicable or appropriate standards may occur, whether they result from legislation or the broadening of knowledge. Accordingly, the findings of this report may be invalidated wholly or partially by changes outside our control. Therefore, this report is subject to review and should not be relied upon after a period of three years.




Plotted:12/19/2016 2:06PM | By: ALVIN LADRILLONO | File Location:Y:\PROJECTS\G1832-42-03 (Shasta East)\DETAILS\G1832-42-03 Vic Map.dwg



Plotted:12/19/2016 2:09PM | By:ALVIN LADRILLONO | File Location:Y:\PROJECTS\G1832-42-03 (Shasta East)\SHEETS\G1832-42-03 Site Plan.dwg



Plotted:12/19/2016 2:09PM | By:ALVIN LADRILLONO | Flie Location:Y:)PROJECTS\G1832-42-03 (Shasta East)\DETAILS\Wall-Column Footing Dimension Detail (COLFOOT2).dvg



Plotted: 12/19/2016 2:08PM | By:ALVIN LADRILLONO | File Location:Y:PROJECTS\G1832-42-03 (Shasta East)\DETAILS\Typical Retaining Wall Drainage Detail (RWDD7A).dwg





APPENDIX A

FIELD INVESTIGATION

The field investigation was performed on November 7 and 8, 2016, and included drilling six 8-inchdiameter exploratory borings. The small-diameter borings were drilled using a Fraste, limited-access drill rig equipped with hollow-stem augers. The approximate locations of the exploratory borings are shown on the Geologic Map, Figure 2. The boring locations were located in the field based on visual reference points; therefore, actual locations may deviate slightly.

Logs of our borings are presented as Figures A-1 through A-6. The logs depict the soil and geologic conditions encountered and the depth at which samples were obtained. The soil encountered were visually examined, classified, and logged in general accordance with American Society for Testing and Materials (ASTM) practice for Description and Identification of Soils (Visual-Manual Procedure D 2488).

Additionally, we performed four, in-place, hydraulic conductivity tests. The infiltration tests were conducted in 4-inch-diameter, hand excavated-borings ranging in depths from 2 to 3.4 feet below existing ground surface using a Soilmoisture Corp. Aardvark Permeameter. The data was analyzed using USBR 7300-89 methodology. Results from the infiltration testing is presented in Appendix C.

DEPTH)GY	ATER	SOIL	BORING B 1	TION NCE FT.)	SITY (:	MOISTURE CONTENT (%)
IN FEET	SAMPLE NO.	ГІТНОГОСУ	GROUNDWATER	CLASS (USCS)	ELEV. (MSL.) 49' DATE COMPLETED 11-08-2016	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	10ISTU
			GRO	EQUIPMENT FRASTE BY: J. LAYOG	- BE	DR	20	
0 -					MATERIAL DESCRIPTION			
- 0	B1-1			SP-SM/SM	TERRACE DEPOSITS (Qt) Loose, moist, light brown to brown, fine grained SAND with silt to Silty SAND; 2-4" sod at surface	_		
2 -						-		
-	B1-2					_ 7		
4 –						-		
_	B1-3					- 10		
6 -	BIJ					_		
					-Becomes medium dense			
8 –						-		
_			-			-		
10 –	B1-4					- 15		
_						-		
12 –					-Layer of gravel approx. 6" thick	-		
-						-		
14 —						_		
	B1-5					25		
16 -					BORING TERMINATED AT 16 FEET Groundwater not encountered Backfilled with cuttings on 11-08-2016			
igure	A-1,				-64		G183	2-42-03.0
og 01	f Borin	дв	ı, F	_				
SAMP	PLE SYME	BOLS				E SAMPLE (UNDI		



DEPTH		β	ATER	SOIL	BORING B 2	TION NCE FT.)	SITY	RE (%)
IN FEET	SAMPLE NO.	ПТНОГОСУ	GROUNDWATER	CLASS (USCS)	ELEV. (MSL.) 45' DATE COMPLETED 11-08-2016	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE
			GROI	(0000)	EQUIPMENT FRASTE BY: J. LAYOG	PEN (BL	DR	ΣÖ
					MATERIAL DESCRIPTION			
0 –	B2-1		5		2" ASPHALT Over 3" BASE			
-				SP-SM/SM	TERRACE DEPOSITS (Qt) Medium dense, damp to moist, light brown to brown, fine SAND with silt to Silty SAND	-		
2 -	B2-2					18		
_	B2-2					- 18		
4 –						_		
_	B2-3	×				27		
6 -					-Becomes moist	-		
_						_		
8 –						-		
_						-		
10 -						_		
-	B2-4				-Becomes light brown	38		
_						-		
12 –						-		
_								
					-Layer of gravel approx. 6" thick			
14 –					-Becomes dense	-		
-	B2-5					- 50		
16 -								
10					BORING TERMINATED AT 16 FEET Groundwater not encountered			
					Backfilled with cuttings on 11-08-2016			
igure	A-2,				of 1	1	G183	2-42-03.0
.og o	f Borin	ува	∠, ⊧	_				
SAMD	LE SYME	OLS			LING UNSUCCESSFUL I STANDARD PENETRATION TEST DRIVE S RBED OR BAG SAMPLE I WATER	SAMPLE (UNDIS	STURBED)	

DEPTH	SAMPLE	ПТНОГОGY	GROUNDWATER	SOIL	BORING B 3	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE CONTENT (%)
IN FEET	NO.	IDHTI	IND	CLASS (USCS)	ELEV. (MSL.) 43' DATE COMPLETED 11-08-2016	NETR	RY DE (P.C	
			GRO		EQUIPMENT FRASTE BY: J. LAYOG	- Br	ă	- ŭ
0 -					MATERIAL DESCRIPTION			
				SP-SM/SM	TERRACE DEPOSITS (Qt) Loose, damp to moist, light brown to brown, fine SAND with silt to Silty SAND; 3-4" sod at surface	_		
2 -						-		
_	B3-1					_ 14		
4 –								
-								
_	B3-2				-Becomes moist	- 13		
6 -						-		
-						-		
8 –						_		
_								
10 –	B3-3					26		
-						-		
12 –						-		
_						-		
14 –								
14					-Layer of gravel approx. 6" thick -Becomes dense			
_	B3-4		:		-No sample; gravel in shoe	64		
16 —					BORING TERMINATED AT 16FEET Groundwater not encountered Backfilled with cuttings on 11-08-2016			
igure		1					G183	2-42-03.G
	f Boring	g B 3	3, F	Page 1	of 1			
SVWD	LE SYMB			SAMP	LING UNSUCCESSFUL STANDARD PENETRATION TEST DRIVE	SAMPLE (UNDI	STURBED)	



PROJEC	T NO. G18	32-42-0	3					
DEPTH IN FEET	SAMPLE NO.	ГІТНОГОЄУ	GROUNDWATER	SOIL CLASS (USCS)	BORING B 4 ELEV. (MSL.) 39' DATE COMPLETED 11-08-2016 EQUIPMENT FRASTE BY: J. LAYOG	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE CONTENT (%)
					MATERIAL DESCRIPTION			
- 0 -	B4-1			SM	UNDOCUMENTED FILL (Qudf) Loose, moist, dark brown to brown, Silty, fine SAND; 3-4" of sod at surface			
- 2 -	B4-2			SP-SM/SM	TERRACE DEPOSITS (Qt) Loose, moist, light brown to brown, fine SAND with silt to Silty SAND	- 14		
						-		
	B4-3					7 		
					-Becomes medium dense	-		
 - 10 -	B4-4					- - 34		
					¬ -Gravel in shoe			
					BORING TERMINATED AT 11 FEET Groundwater not encountered Backfilled with cuttings on 11-08-2016			
Figure Log o	e A-4, f Boring	gB4	1, F	Page 1	of 1		G183	2-42-03.GPJ
SAMF	PLE SYMB	OLS				SAMPLE (UNDI		



DEPTH IN FEET	SAMPLE NO.	КООТОНТІ	GROUNDWATER	SOIL CLASS (USCS)	BORING B 5 ELEV. (MSL.) 37' DATE COMPLETED 11-08-2016 EQUIPMENT FRASTE BY: J. LAYOG	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE CONTENT (%)
			G			-		
0 -								
_				SP-SM/SM	TERRACE DEPOSITS (Qt) Loose, damp to moist, light brown to brown, fine SAND with silt to Silty SAND; 3-4" of sod at surface	_		
2 -						-		
-	B5-1					- 13		
4 –								
_	B5-2					12		
6 -						-		
_						-		
8 –						-		
_								
10 -					-Layer of gravel approx. 6-12" thick	-		
-						-		
12 –						-		
-								
14								
14 –								
_	В5-3				-Becomes medium dense	15		
16 –					BORING TERMINATED AT 16 FEET Groundwater not encountered Backfilled with cuttings on 11-08-2016			
igure og of	e A-5, f Boring	g B t	5, F	Page 1	of 1	1	G183	32-42-03.v
		-	-	_		SAMPLE (UNDIS		



DEPTH		GY	VTER		BORING B 6) XIIX	RE (%)
IN FEET	SAMPLE NO.	ГІТНОГОСУ	GROUNDWATER	SOIL CLASS (USCS)	ELEV. (MSL.) 38' DATE COMPLETED 11-08-2016	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE
			EQUIPMENT FRASTE BY: J. LAYOG	EQUIPMENT FRASTE BY: J. LAYOG	(BL BL BL	DR	20	
-					MATERIAL DESCRIPTION			
0 -	B6-1			SM	UNDOCUMENTED FILL (Qudf) Loose, damp, dark brown, Silty, fine SAND	_		
2 -				SP-SM/SM	TERRACE DEPOSITS (Qt) Loose, damp to moist, light brown to brown, fine SAND with silt to Silty SAND	-		
-	B6-2	8			SAND	_ 6		
4 –			•			_		
6 -	B6-3					11 -		
_						-		
8 -					-Becomes medium dense	-		
10 –	B6-4					- 19		
_						_		
12 –						_		
14 –			•			-		
-	B6-5				-Becomes medium grained, yellowish brown	- 29		
16 —					-Gravel in shoe BORING TERMINATED AT 16 FEET Groundwater not encountered Backfilled with cuttings on 11-08-2016			
igure	e A-6, f Boring			Page 1	of 1		G183	32-42-03.0
			, г			SAMPLE (UNDIS	STURBED)	





APPENDIX B

LABORATORY TESTING

Laboratory tests were performed in accordance with generally accepted test methods of the American Society for Testing and Materials (ASTM) or other suggested procedures. Selected soil samples were tested for their maximum dry density and optimum moisture content, shear strength, expansion index, water-soluble sulfate content, resistance value (R-value), gradation characteristics, and consolidation characteristics. The results of our laboratory tests are presented on the following tables and graphs.

TABLE B-I SUMMARY OF LABORATORY MAXIMUM DRY DENSITY AND OPTIMUM MOISTURE CONTENT TEST RESULTS ASTM D 1557

Sample No.	Description	Maximum Dry Density (pcf)	Optimum Moisture Content (% dry wt.)
B4-1	Brown, Silty, fine to medium, SAND; trace gravel	119.0	10.0

TABLE B-II SUMMARY OF LABORATORY REMOLDED DIRECT SHEAR TEST RESULTS ASTM D 3080

Sample No.	Dry	Moisture	Peak Unit	Peak Angle of Shear
	Density (pcf)	Content (%)	Cohesion (psf)	Resistance (degrees)
B2-3	102.8	3.3	360	26

TABLE B-III SUMMARY OF LABORATORY EXPANSION INDEX TEST RESULTS ASTM D 4829

Sample No	Moisture Content		Dry Density	Emonster Inden
Sample No.	Before Test (%)	After Test (%)	(pcf)	Expansion Index
B4-1	9.2	16.1	111.4	0

TABLE B-IV SUMMARY OF LABORATORY WATER-SOLUBLE SULFATE TEST RESULTS CALIFORNIA TEST NO. 417

Sample No.	Water-Soluble Sulfate (%)	Classification	
B4-1	0.005	Negligible	

TABLE B-V SUMMARY OF LABORATORY R-VALUE AND SAND EQUIVALENT TEST RESULTS ASTM D 2844

Sample No.	R-Value	
B1-1	61	





Figure B-1

GEOCON



GEOCON





Figure B-3

GEOCON



GEOCON



APPENDIX C

STORM WATER MANAGEMENT

We understand storm water management devices are being proposed in accordance with the current Storm Water Standards (SWS). If not properly constructed, there is a potential for distress to improvements and properties located hydrologically down gradient or adjacent to these devices. Factors such as the amount of water to be detained, its residence time, and soil permeability have an important effect on seepage transmission and the potential adverse impacts that may occur if the storm water management features are not properly designed and constructed. We have not performed a hydrogeological study at the site. If infiltration of storm water runoff occurs, downstream properties and improvements may be subjected to seeps, springs, slope instability, raised groundwater, movement of foundations and slabs, or other undesirable impacts as a result of water infiltration.

Hydrologic Soil Group

The United States Department of Agriculture (USDA), Natural Resources Conservation Services, possesses general information regarding the existing soil conditions for areas within the United States. The USDA website also provides the Hydrologic Soil Group. Table C-1 presents the descriptions of the hydrologic soil groups.

Soil Group	Soil Group Definition
А	Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.
В	Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.
С	Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.
D	Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

TABLE C-1 HYDROLOGIC SOIL GROUP DEFINITIONS

The property is underlain by undocumented fill and old terrace deposits. Table C-2 presents the information from the USDA website for the subject property.

Map Unit Name	Map Unit Symbol	Approximate Percentage of Property	Hydrologic Soil Group	k _{SAT} of Most Limiting Layer (inches/hour)
Urban land	Ur	100	n/a	n/a

 TABLE C-2

 USDA WEB SOIL SURVEY – HYDROLOGIC SOIL GROUP

Infiltration Testing

We performed 4 field-saturated, constant head, hydraulic conductivity tests at depths of approximately 2 to 3.5 feet below the existing ground surface using a Soil Moisture Corp Aardvark Permeameter. Table C-3 presents the results of the field-saturated hydraulic conductivity testing calculated using the USBR 7300-89 method. The approximate locations of the tests are shown on Figure 2. The permeameter test data is attached.

We used the guidelines presented in the Riverside County Low Impact Development BMP Design Handbook, which references the United States Bureau of Reclamation Well Permeameter Test Method (USBR 7300-89). Based on this widely accepted guideline, the saturated hydraulic conductivity (Ksat) is equal to the infiltration rate. Therefore, the Ksat value determined from the Aardvark Permeameter test is the unfactored infiltration rate. The Ksat (infiltration rate) equation provided in the Riverside County Handbook was used to compute the unfactored infiltration rate.

Test No.	Geologic Unit	Test Elevation (feet, MSL)	Field Infiltration Rate, I (inches/hour)
I-1	Qt	42	7.5
I-2	Qt	40	11.3
I-3	Qt	34	12.0
1-4	Qt	29	13.7

TABLE C-3 UNFACTORED HYDRAULIC CONDUCTIVITY TEST RESULTS

We performed grain size distribution tests on samples collected at the depth and location of the hydraulic conductivity tests and the results are presented in Appendix B.

STORM WATER MANAGEMENT CONCLUSIONS

Soil Types

Undocumented Fill (**Qudf**) – We encountered undocumented fill in borings B-4 and B-6 ranging from approximately 1 to 1.5 feet thick. The undocumented fill will be removed and replaced with compacted fill. We do not recommend infiltration into the compacted fill.

Old Terrace Deposits (Qt) – Old terrace deposits (formerly Bay Point Formation) were encountered in all borings to the maximum depth explored. The old terrace deposits generally consist of loose to medium dense, moist, light brown to brown, fine sand. The infiltration rates within the old terrace deposits range from 7.50 to 13.7 inches per hour. However, based on our consolidation testing, the old terrace deposits have a potential for hydro-collapse. Therefore, full or partial infiltration is not recommended.

Groundwater Elevation

Groundwater was not encountered during this investigation. We expect groundwater elevations to be at sea level. The site elevations range from 33 MSL to 47 MSL. Therefore, infiltration is considered feasible due to groundwater greater than 10 feet below the bottom of the proposed infiltration BMPs.

Existing Utilities

Existing utilities are present in the adjacent streets. We recommend proposed basins be set back from existing utilities a distance of at least 10 feet.

Existing and Proposed Foundations

Existing buildings are present on the property. However, we understand they will be removed. We recommend infiltration not occur adjacent to proposed new building foundations due to the potential for settlement related to hydro-collapse.

Soil or Groundwater Contamination

We are unaware of contaminated soil on the property. Therefore, full and partial infiltration associated with this risk is considered feasible.

Slopes

There are no existing or new slopes planned on the property. Therefore, infiltration should be considered feasible.

Infiltration Rates

The results of the infiltration rates show rates ranging from 7.5 to 13.7 inches per hour. The infiltration rates are adequate to support full or partial infiltration.

Storm Water Management Devices

Liners should be incorporated into the design and construction of the planned basins due to the potential for settlement related to hydro-collapse. The liner should be impermeable (e.g. High-density polyethylene, HDPE, with a thickness of about 30 mil or equivalent Polyvinyl Chloride, PVC). Penetration of the liners should be properly sealed. The devices should also be installed in accordance with the manufacturer's recommendations. Overflow protection devices should also be incorporated into the design and construction of the storm water management device.

Storm Water Standard Worksheets

The SWS requests the geotechnical engineer complete the *Categorization of Infiltration Feasibility Condition* (Worksheet C.4-1) worksheet information to help evaluate the potential for infiltration on the property. The attached Worksheet C.4-1 presents the completed information for the submittal process.

The regional storm water standards also have a worksheet (Worksheet Form D.5-1) that helps the project civil engineer estimate the factor of safety based on several factors. Table C-4 describes the suitability assessment input parameters related to the geotechnical engineering aspects for the factor of safety determination.

Consideration	High	Medium	Low
	Concern – 3 Points	Concern – 2 Points	Concern – 1 Point
Assessment Methods	Use of soil survey maps or simple texture analysis to estimate short-term infiltration rates. Use of well permeameter or borehole methods without accompanying continuous boring log. Relatively sparse testing with direct infiltration methods	Use of well permeameter or borehole methods with accompanying continuous boring log. Direct measurement of infiltration area with localized infiltration measurement methods (e.g., Infiltrometer). Moderate spatial resolution	Direct measurement with localized (i.e. small- scale) infiltration testing methods at relatively high resolution or use of extensive test pit infiltration measurement methods.

TABLE C-4 SUITABILITY ASSESSMENT RELATED CONSIDERATIONS FOR INFILTRATION FACILITY SAFETY FACTORS

TABLE C-4 (Concluded) SUITABILITY ASSESSMENT RELATED CONSIDERATIONS FOR INFILTRATION FACILITY SAFETY FACTORS

Consideration	High	Medium	Low
	Concern – 3 Points	Concern – 2 Points	Concern – 1 Point
Predominant Soil Texture	Silty and clayey soils with significant fines	Loamy soils	Granular to slightly loamy soils
Site Soil Variability	Highly variable soils indicated from site assessment or unknown variability	Soil boring/test pits indicate moderately homogenous soils	Soil boring/test pits indicate relatively homogenous soils
Depth to Groundwater/	<5 feet below	5-15 feet below	>15 feet below
Impervious Layer	facility bottom	facility bottom	facility bottom

Based on our geotechnical investigation and the previous table, Table C-5 presents the estimated factor values for the evaluation of the factor of safety. This table only presents the suitability assessment safety factor (Part A) of the worksheet. The project civil engineer should evaluate the safety factor for design (Part B) and use the combined safety factor for the design infiltration rate.

Suitability Assessment Factor Category	Assigned Weight (w)	Factor Value (v)	Product (p = w x v)
Assessment Methods	0.25	2	0.50
Predominant Soil Texture	0.25	1	0.25
Site Soil Variability	0.25	2	0.50
Depth to Groundwater/Impervious Layer	0.25	1	0.25
Suitability Assessment Saf	1.5		

TABLE C-5 FACTOR OF SAFETY WORKSHEET D.5-1 DESIGN VALUES¹

¹ The project civil engineer should complete Worksheet D.5-1 using the data on this table. Additional information is required to evaluate the design factor of safety.

CONCLUSIONS


Our results indicate the site has relatively good infiltration characteristics. However, laboratory test results also indicate the terrace deposits have a potential for hydro-collapse. It is our opinion that full or partial infiltration is not feasible due to the potential for settlement related to hydro-collapse.

Our evaluation included the soil and geologic conditions, estimated settlement and volume change of the underlying soil, slope stability, utility considerations, groundwater mounding, retaining walls, foundations and existing groundwater elevations.



	Aardvark P	ermeamete	r Data Analysis	5			
	Project Name:	Eco E	Blok East	Date:	11/7/2016		
Р	roject Number:	G183	32-42-03	By:	JTL		
Bor	ehole Location:		I-1		Ref. EL (feet, MSL):	44.0	
				Во	ttom EL (feet, MSL):	41.8	
Dis	83.64						
	Distance Between Resevoir and APM, D (inches) Head Height Calculated, h (inches) Head Height Recorded, h (inches) Distance Between Constant Head and Water Table, L (inches)						
Reading	Time (min)	Time Elapsed (min)	Reservoir Water Weight (g)	Resevoir Water Weight (Ibs)	Interval Water Consumption (lbs)	Total Water Consumption (lbs)	*Water Consumption Rate (in ³ /min)
1	0.00			64.345			
2	10.00	10.00		52.520	11.825	11.825	32.778
3	15.00	5.00		48.135	4.385	16.210	24.310
4	20.00	5.00		43.580	4.555	20.765	25.252
5	25.00	5.00		39.220	4.360	25.125	24.171
6	30.00	5.00		34.935	4.285	29.410	23.755
7	35.00	5.00		30.620	4.315	33.725	23.921
8	40.00	5.00		26.360	4.260	37.985	23.617
9	42.00	2.00		24.645	1.715	39.700	23.769


3 15.00 5.00 48.135 4.385 16.210 24.310 4 20.00 5.00 39.220 4.360 25.125 22.4171 6 30.00 5.00 39.220 4.360 25.125 24.171 6 30.00 5.00 34.935 4.285 29.410 23.755 7 35.00 5.00 30.620 4.315 33.725 23.921 8 40.00 5.00 26.360 4.260 37.985 23.617 9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 20.0 22.885 1.760 41.460 24.393 11 46.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 14.635 1.710 49.710 23.700 16 56.00							
5 25.00 5.00 39.220 4.360 25.125 24.171 6 30.00 5.00 34.935 4.285 29.410 23.755 7 35.00 5.00 30.620 4.315 33.725 23.921 8 40.00 5.00 26.360 4.260 37.985 23.617 9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.665 1.730 46.280 23.977 14 52.00 2.00 14.635 1.710 49.710 23.878 17 16 56.00 2.00 12.915 </td <td>3</td> <td>15.00</td> <td>5.00</td> <td>48.135</td> <td>4.385</td> <td>16.210</td> <td>24.310</td>	3	15.00	5.00	48.135	4.385	16.210	24.310
6 30.00 5.00 34.935 4.285 29.410 23.755 7 35.00 5.00 30.620 4.315 33.725 23.921 8 40.00 5.00 26.360 4.260 37.985 23.617 9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 48.000 23.838 17	4	20.00	5.00	43.580	4.555	20.765	25.252
7 35.00 5.00 30.620 4.315 33.725 23.921 8 40.00 5.00 26.360 4.260 37.985 23.617 9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 14.635 1.710 49.710 23.700 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17 20 <	5	25.00	5.00	39.220	4.360	25.125	24.171
8 40.00 5.00 26.360 4.260 37.985 23.617 9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17	6	30.00	5.00	34.935	4.285	29.410	23.755
9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 19.795 1.740 44.550 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17 18 19 21	7	35.00	5.00	30.620	4.315	33.725	23.921
10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17 18 20 21 <td>8</td> <td>40.00</td> <td>5.00</td> <td>26.360</td> <td>4.260</td> <td>37.985</td> <td>23.617</td>	8	40.00	5.00	26.360	4.260	37.985	23.617
11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17	9	42.00	2.00	24.645	1.715	39.700	23.769
12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17	10	44.00	2.00	22.885	1.760	41.460	24.393
13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17	11	46.00	2.00	21.535	1.350	42.810	18.710
14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17	12	48.00	2.00	19.795	1.740	44.550	24.115
$\begin{array}{c c c c c c c c c c c c c c c c c c c $	13	50.00	2.00	18.065	1.730	46.280	23.977
$\begin{array}{c c c c c c c c c c c c c c c c c c c $	14	52.00	2.00	16.345	1.720	48.000	23.838
17andandandandandand18andandandandandand19andandandandandand20andandandandandand21andandandandandand22andandandandandand23andandandandandand24andandandandandand25andandandandandand26andandandandandand27andandandandandand	15	54.00	2.00	14.635	1.710	49.710	23.700
18Image: sector of the sector of	16	56.00	2.00	12.915	1.720	51.430	23.838
19Image: second sec	17						
20andandandandand21andandandandandand22andandandandandand23andandandandandand24andandandandandand25andandandandandand26andandandandandand27andandandandandand	18						
21 <td>19</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	19						
22232324242526272726 <td>20</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	20						
23 24 24 24 24 25 26 26 27 26 27 26 27 26 27 <td< td=""><td>21</td><td></td><td></td><td></td><td></td><td></td><td></td></td<>	21						
24 and	22						
25 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 7	23						
26 27<	24						
27	25						
	26						
	27						
	28						



Field-Saturated Hydraulic Conductivity (Infiltration Rate) 7.501 in/hr Case 1: L/h > 3 1.25E-01 in/min $K_{sat} =$



	/ ar ar ar ar ar ar	criticalitete	Data / maryon				
	Project Name:	Eco E	Blok East	Date:	11/7/2016		
Р	roject Number:	G183	32-42-03	By:	JTL		
Bor	ehole Location:	:	I-2		Ref. EL (feet, MSL):	43.0	
				Bo	ttom EL (feet, MSL):	40.1	
		Borehole	e Diameter (inches):	4.00	1		•
			e Depth, H (inches):	35.00		Wetted Area, A (in ²):	83.97
Dis	tance Between f		of Borehole (inches):	29.00		Welleu Area, A (III).	05.57
			/ater Table, s (feet):	100			
	Heig	-	om Bottom (inches):	2.00			
	- 0				and APM, D (inches):		1
			Distance		Calculated, h (inches):	00	
					Recorded, h (inches):	5.68	
		Dia	tance Detuces Co.			5100	
		Dis	stance Between Cor	nstant Head and W	ater Table, L (inches):	1171	
Reading	Time (min)	Time Elapsed (min)	Reservoir Water Weight (g)	Resevoir Water Weight (lbs)	Interval Water Consumption (Ibs)	Total Water Consumption (lbs)	*Water Consumption Rate (in ³ /min)
1	0.00			109.840			
2	8.00	8.00		92.675	17.165	17.165	59.474
3	18.00	10.00		75.160	17.515	34.680	48.550
4	25.00	7.00		64.455	10.705	45.385	42.390
5	30.00	5.00		56.870	7.585	52.970	42.050
6	32.00	2.00		54.180	2.690	55.660	37.282
7	34.00	2.00		51.445	2.735	58.395	37.906
8	36.00	2.00		48.575	2.870	61.265	39.777
9	38.00	2.00		45.880	2.695	63.960	37.351
10	40.00	2.00		43.110	2.770	66.730	38.391
11	42.00	2.00		40.735	2.375	69.105	32.916
12	44.00	2.00		38.015	2.720	71.825	37.698
13	46.00	2.00		35.230	2.785	74.610	38.599
14	48.00	2.00		32.495	2.735	77.345	37.906
15	50.00	2.00		29.800	2.695	80.040	37.351
16	52.00	2.00		27.135	2.665	82.705	36.936
17	54.00	2.00		24.500	2.635	85.340	36.520
18	56.00	2.00		24.180	0.320	85.660	4.435
19 20	58.00 60.00	2.00		21.830 19.175	2.350 2.655	88.010 90.665	32.570 36.797
20	60.00	2.00		19.175	2.655	90.665	36.312
21	64.00	2.00		13.955	2.600	95.885	36.035
22	66.00	2.00		11.335	2.620	98.505	36.312
23	00.00	2.00		11.335	2.020	20,202	50.512
25							
26							
27							
28							
	80.00				Steady Flo	w Rate, Q (in ³ /min):	36.219
Ę	80.00						




Field-Saturated Hydraulic Conductivity (Infiltration Rate)Case 1: L/h > 3K sat =1.89E-01in/min11.347



	Aardvark P	ermeamete	r Data Analysis	5			
	Project Name:	Eco E	Blok East	Date:	11/7/2016		
Р	roject Number:	G183	32-42-03	By:	JTL		
Bor	ehole Location:		I-3		Ref. EL (feet, MSL):	37.0	
				Bo	ttom EL (feet, MSL):	33.8	
		Wetted Area, A (in ²):	84.12				
Dis	Distance Between Reservoir & Top of Borehole (inches): 28.50 Depth to Water Table, s (feet): 100 Height APM Raised from Bottom (inches): 2.00						
	Distance Between Resevoir and APM, D (inches): Head Height Calculated, h (inches): Head Height Recorded, h (inches): Distance Between Constant Head and Water Table, L (inches):						
Reading	Time (min)	Time Elapsed (min)	Reservoir Water Weight (g)	Resevoir Water Weight (Ibs)	Interval Water Consumption (lbs)	Total Water Consumption (lbs)	*Water Consumption Rate (in ³ /min)
1	0.00			80.795			
2	5.00	5.00		68.975	11.820	11.820	65.528
3	10.00	5.00		60.295	8.680	20.500	48.120
4	15.00	5.00		52.840	7.455	27.955	41.329
5	20.00	5.00		45.270	7.570	35.525	41.967
6	25.00	5.00		38.600	6.670	42.195	36.977
7	20.00			21 (10	6.990	49.185	38.751
	30.00	5.00		31.610	0.990	49.165	30.731
8	30.00	5.00 5.00		24.660	6.950	56.135	38.529
8 9							

1	0.00		80.795			
2	5.00	5.00	68.975	11.820	11.820	65.528
3	10.00	5.00	60.295	8.680	20.500	48.120
4	15.00	5.00	52.840	7.455	27.955	41.329
5	20.00	5.00	45.270	7.570	35.525	41.967
6	25.00	5.00	38.600	6.670	42.195	36.977
7	30.00	5.00	31.610	6.990	49.185	38.751
8	35.00	5.00	24.660	6.950	56.135	38.529
9	40.00	5.00	17.805	6.855	62.990	38.003
10	45.00	5.00	10.880	6.925	69.915	38.391
11	47.00	2.00	8.105	2.775	72.690	38.460
12	49.00	2.00	5.330	2.775	75.465	38.460
13						
14						
15						
16						
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						
28						



Field-Saturated Hydraulic Conductivity (Infiltration Rate)Case 1: L/h > 3 $K_{sat} =$ 2.00E-01in/min12.009in/hr



20.00

			Blok East	Date:	11/7/2016		
Bore	oject Number:	G183	32-42-03	By:	JTL		
	hole Location:		I-4		Ref. EL (feet, MSL):	33.0	
				Bo	ttom EL (feet, MSL):	29.4	
Dista	ance Between F	Borehol	e Diameter (inches): e Depth <i>,</i> H (inches): of Borehole (inches):	4.00 43.00		Wetted Area, A (in ²):	84.29
Dista		Depth to V	/ater Table, s (feet): om Bottom (inches):	28.50 100 2.00			
			Distance		and APM, D (inches):	62.25	
				-	Calculated, h (inches):	5.71	
					Recorded, h (inches):	4.25	
		Dis	tance Between Cor	nstant Head and W	ater Table, L (inches):	1163	
Reading	Time (min)	Time Elapsed (min)	Reservoir Water Weight (g)	Resevoir Water Weight (Ibs)	Interval Water Consumption (Ibs)	Total Water Consumption (lbs)	*Water Consumption Rat (in ³ /min)
1	0.00			114.400			(11 / 1111)
2		F 00		114.400	11 700	11.780	65 206
3	5.00	5.00		92.600	11.780	21.800	65.306
4	10.00 15.00	5.00 5.00		82.845	10.020 9.755	31.555	55.549 54.080
5	20.00	5.00		73.910	8.935	40.490	49.534
6	25.00	5.00		64.800	9.110	49.600	50.504
7	30.00	5.00		56.615	8.185	57.785	45.376
8	35.00	5.00		48.015	8.600	66.385	47.677
9	40.00	5.00		40.045	7.970	74.355	44.184
10	45.00	5.00		32.410	7.635	81.990	42.327
10	50.00	5.00		24.170	8.240	90.230	45.681
12	52.00	2.00		21.760	2.410	92.640	33.401
13	54.00	2.00		18.545	3.215	95.855	44.558
14	56.00	2.00		15.300	3.245	99.100	44.974
15	58.00	2.00		12.115	3.185	102.285	44.142
16	60.00	2.00		8.955	3.160	105.445	43.796
17	62.00	2.00		5.805	3.150	108.595	43.657
18							
19							
20							
21							
21 22							
21 22 23							
21 22 23 24							
21 22 23 24 25							
21 22 23 24 25 26							
21 22 23 24 25							

Water Consu Rate (in³/ 0.00 0 10 20 30 40 50 60 Time (min) Field-Saturated Hydraulic Conductivity (Infiltration Rate) in/hr 2.28E-01 in/min 13.662 Case 1: L/h > 3 $K_{sat} =$

70

Cate	gorization of Infiltration Feasibility Condition	Form I-8						
Would i	Part 1 - Full Infiltration Feasibility Screening Criteria Would infiltration of the full design volume be feasible from a physical perspective without any undesirable consequences that cannot be reasonably mitigated?							
Criteria	Screening Question	Yes	No					
1	Is the estimated reliable infiltration rate below proposed facility locations greater than 0.5 inches per hour? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.2 and Appendix D.	х						
Provide	basis:							
Weenco	ountered field infiltration rates of:							
Based o	I-1: 7.5 in/hr (3.75 in/hr with a FOS of 2)I-2: 11.3 in/hr (5.7 in/hr with a FOS of 2)I-3: 12.0 in/hr (6.0 in/hr with a FOS of 2)I-4: 13.7 in/hr (6.9 in/hr with a FOS of 2)I-4: 13.7 in/hr (6.9 in/hr with a FOS of 2)n the test results, the estimated reliable infiltration rate is greater than 0)).5 inches per h	our.					
2	Can infiltration greater than 0.5 inches per hour be allowed without increasing risk of geotechnical hazards (slope stability, groundwater mounding, utilities, or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.2.							
Provide	basis:							
settleme Decemb 1.25 per	n the comprehensive geotechnical evaluation, infiltration is not feasible int due to the potential for hydro-collapse in the underlying soils. Figur er 19, 2016 report show a hydro-collapse potential ranging from 0.5 to cent over a wetting height of 20 feet, we would expect settlement mag the typically settlement magnitudes that can be accommodated in a co	res B-2 through 2 percent. Usir nitudes of 3 inc	n B-4 of Geocon's ng an average of hes, which					

	Form I-8 Page 2 of 4				
Criteria	Screening Question Yes		No		
3	Can infiltration greater than 0.5 inches per hour be allowed without increasing risk of groundwater contamination (shallow water table, storm water pollutants or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.3.	oundwater contamination (shallow utants or other factors) that cannot e level? The response to this ed on a comprehensive evaluation ofX			
Provide ba	sis:	I	1		
greater th contamin	an 30 feet below existing grade. Infiltration is feasible without increasi ation.	ng the risk of g	roundwater		
4	Can infiltration greater than 0.5 inches per hour be allowed without causing potential water balance issues such as change of seasonality of ephemeral streams or increased discharge of contaminated groundwater to surface waters? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.3.				
	sis: expect infiltration will cause water balance issues such as seasonality discharge of contaminated groundwater to surface waters.	of ephemeral st	reams or		

*To be completed using gathered site information and best professional judgment considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by the City to substantiate findings.

	Form I-8 Page 3 of 4					
Part 2 – F	Partial Infiltration vs. No Infiltration Feasibility Screening Criteria					
Would in	Would infiltration of water in any appreciable amount be physically feasible without any negative consequences that cannot be reasonably mitigated?					
Criteria	Screening Question	Yes	No			
5	Do soil and geologic conditions allow for infiltration in any appreciable rate or volume? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.2 and Appendix D.	х				
Provide ba	isis:					
We measu	ured field infiltration rates of:					
	I-1: 7.5 in/hr (3.75 in/hr with a FOS of 2) I-2: 11.3 in/hr (5.7 in/hr with a FOS of 2) I-3: 12.0 in/hr (6.0 in/hr with a FOS of 2) I-4: 13.7 in/hr (6.9 in/hr with a FOS of 2)					
Based on	the test results, soil conditions allow for an appreciable infiltration ra	te or volume.				
6	Can Infiltration in any appreciable quantity be allowed without increasing risk of geotechnical hazards (slope stability, groundwater mounding, utilities, or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.2.		х			
Provide ba	asis:					
Based on the comprehensive geotechnical evaluation, infiltration is not feasible due to the increased risk of settlement due to the potential for hydro-collapse in the underlying soils. Figures B-2 through B-4 of Geocon's December 19, 2016 report show a hydro-collapse potential ranging from 0.5 to 2 percent. Using an average of 1.25 percent over a wetting height of 20 feet, we would expect settlement magnitudes of 3 inches, which exceeds the typically settlement magnitudes that can be accommodated in a conventional shallow foundation system.						

Appendix I: Forms and Checklists

Worksheet C.4-1 Page 4 of 4				
Criteria	Screening Question Yes		No	
7	Can Infiltration in any appreciable quantity be allowed without posing significant risk for groundwater related concerns (shallow water table, storm water pollutants or other factors)? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.3.			
Provide ba	isis:			
depths g	ot aware of contaminated soil on the site. Furthermore, we estimate g eater than 30 feet below existing grade. Infiltration is feasible withou ater contamination.			
8	Can infiltration be allowed without violating downstream water rights ? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.3.	х		
Provide b	usis: nt provide a study regarding water rights. However, these rights are no	ot typical in the Sa	n Diego area.	
Part 2 Result*	No Infiltration			

*To be completed using gathered site information and best professional judgment considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by the City to substantiate findings.



APPENDIX D

RECOMMENDED GRADING SPECIFICATIONS

FOR

ECO BLOK EAST SHASTA STREET SAN DIEGO, CALIFORNIA

PROJECT NO. G1832-42-03

RECOMMENDED GRADING SPECIFICATIONS

1. GENERAL

- 1.1 These Recommended Grading Specifications shall be used in conjunction with the Geotechnical Report for the project prepared by Geocon. The recommendations contained in the text of the Geotechnical Report are a part of the earthwork and grading specifications and shall supersede the provisions contained hereinafter in the case of conflict.
- 1.2 Prior to the commencement of grading, a geotechnical consultant (Consultant) shall be employed for the purpose of observing earthwork procedures and testing the fills for substantial conformance with the recommendations of the Geotechnical Report and these specifications. The Consultant should provide adequate testing and observation services so that they may assess whether, in their opinion, the work was performed in substantial conformance with these specifications. It shall be the responsibility of the Contractor to assist the Consultant and keep them apprised of work schedules and changes so that personnel may be scheduled accordingly.
- 1.3 It shall be the sole responsibility of the Contractor to provide adequate equipment and methods to accomplish the work in accordance with applicable grading codes or agency ordinances, these specifications and the approved grading plans. If, in the opinion of the Consultant, unsatisfactory conditions such as questionable soil materials, poor moisture condition, inadequate compaction, and/or adverse weather result in a quality of work not in conformance with these specifications, the Consultant will be empowered to reject the work and recommend to the Owner that grading be stopped until the unacceptable conditions are corrected.

2. **DEFINITIONS**

- 2.1 **Owner** shall refer to the owner of the property or the entity on whose behalf the grading work is being performed and who has contracted with the Contractor to have grading performed.
- 2.2 **Contractor** shall refer to the Contractor performing the site grading work.
- 2.3 **Civil Engineer** or **Engineer of Work** shall refer to the California licensed Civil Engineer or consulting firm responsible for preparation of the grading plans, surveying and verifying as-graded topography.
- 2.4 **Consultant** shall refer to the soil engineering and engineering geology consulting firm retained to provide geotechnical services for the project.

- 2.5 **Soil Engineer** shall refer to a California licensed Civil Engineer retained by the Owner, who is experienced in the practice of geotechnical engineering. The Soil Engineer shall be responsible for having qualified representatives on-site to observe and test the Contractor's work for conformance with these specifications.
- 2.6 **Engineering Geologist** shall refer to a California licensed Engineering Geologist retained by the Owner to provide geologic observations and recommendations during the site grading.
- 2.7 **Geotechnical Report** shall refer to a soil report (including all addenda) which may include a geologic reconnaissance or geologic investigation that was prepared specifically for the development of the project for which these Recommended Grading Specifications are intended to apply.

3. MATERIALS

- 3.1 Materials for compacted fill shall consist of any soil excavated from the cut areas or imported to the site that, in the opinion of the Consultant, is suitable for use in construction of fills. In general, fill materials can be classified as *soil* fills, *soil-rock* fills or *rock* fills, as defined below.
 - 3.1.1 **Soil fills** are defined as fills containing no rocks or hard lumps greater than 12 inches in maximum dimension and containing at least 40 percent by weight of material smaller than ³/₄ inch in size.
 - 3.1.2 **Soil-rock fills** are defined as fills containing no rocks or hard lumps larger than 4 feet in maximum dimension and containing a sufficient matrix of soil fill to allow for proper compaction of soil fill around the rock fragments or hard lumps as specified in Paragraph 6.2. **Oversize rock** is defined as material greater than 12 inches.
 - 3.1.3 **Rock fills** are defined as fills containing no rocks or hard lumps larger than 3 feet in maximum dimension and containing little or no fines. Fines are defined as material smaller than ³/₄ inch in maximum dimension. The quantity of fines shall be less than approximately 20 percent of the rock fill quantity.
- 3.2 Material of a perishable, spongy, or otherwise unsuitable nature as determined by the Consultant shall not be used in fills.
- 3.3 Materials used for fill, either imported or on-site, shall not contain hazardous materials as defined by the California Code of Regulations, Title 22, Division 4, Chapter 30, Articles 9


and 10; 40CFR; and any other applicable local, state or federal laws. The Consultant shall not be responsible for the identification or analysis of the potential presence of hazardous materials. However, if observations, odors or soil discoloration cause Consultant to suspect the presence of hazardous materials, the Consultant may request from the Owner the termination of grading operations within the affected area. Prior to resuming grading operations, the Owner shall provide a written report to the Consultant indicating that the suspected materials are not hazardous as defined by applicable laws and regulations.

- 3.4 The outer 15 feet of *soil-rock* fill slopes, measured horizontally, should be composed of properly compacted *soil* fill materials approved by the Consultant. *Rock* fill may extend to the slope face, provided that the slope is not steeper than 2:1 (horizontal:vertical) and a soil layer no thicker than 12 inches is track-walked onto the face for landscaping purposes. This procedure may be utilized provided it is acceptable to the governing agency, Owner and Consultant.
- 3.5 Samples of soil materials to be used for fill should be tested in the laboratory by the Consultant to determine the maximum density, optimum moisture content, and, where appropriate, shear strength, expansion, and gradation characteristics of the soil.
- 3.6 During grading, soil or groundwater conditions other than those identified in the Geotechnical Report may be encountered by the Contractor. The Consultant shall be notified immediately to evaluate the significance of the unanticipated condition.

4. CLEARING AND PREPARING AREAS TO BE FILLED

- 4.1 Areas to be excavated and filled shall be cleared and grubbed. Clearing shall consist of complete removal above the ground surface of trees, stumps, brush, vegetation, man-made structures, and similar debris. Grubbing shall consist of removal of stumps, roots, buried logs and other unsuitable material and shall be performed in areas to be graded. Roots and other projections exceeding 1½ inches in diameter shall be removed to a depth of 3 feet below the surface of the ground. Borrow areas shall be grubbed to the extent necessary to provide suitable fill materials.
- 4.2 Asphalt pavement material removed during clearing operations should be properly disposed at an approved off-site facility or in an acceptable area of the project evaluated by Geocon and the property owner. Concrete fragments that are free of reinforcing steel may be placed in fills, provided they are placed in accordance with Section 6.2 or 6.3 of this document.

- 4.3 After clearing and grubbing of organic matter and other unsuitable material, loose or porous soils shall be removed to the depth recommended in the Geotechnical Report. The depth of removal and compaction should be observed and approved by a representative of the Consultant. The exposed surface shall then be plowed or scarified to a minimum depth of 6 inches and until the surface is free from uneven features that would tend to prevent uniform compaction by the equipment to be used.
- 4.4 Where the slope ratio of the original ground is steeper than 5:1 (horizontal:vertical), or where recommended by the Consultant, the original ground should be benched in accordance with the following illustration.



TYPICAL BENCHING DETAIL

No Scale

- DETAIL NOTES: (1) Key width "B" should be a minimum of 10 feet, or sufficiently wide to permit complete coverage with the compaction equipment used. The base of the key should be graded horizontal, or inclined slightly into the natural slope.
 - (2) The outside of the key should be below the topsoil or unsuitable surficial material and at least 2 feet into dense formational material. Where hard rock is exposed in the bottom of the key, the depth and configuration of the key may be modified as approved by the Consultant.
- 4.5 After areas to receive fill have been cleared and scarified, the surface should be moisture conditioned to achieve the proper moisture content, and compacted as recommended in Section 6 of these specifications.

5. COMPACTION EQUIPMENT

- 5.1 Compaction of *soil* or *soil-rock* fill shall be accomplished by sheepsfoot or segmented-steel wheeled rollers, vibratory rollers, multiple-wheel pneumatic-tired rollers, or other types of acceptable compaction equipment. Equipment shall be of such a design that it will be capable of compacting the *soil* or *soil-rock* fill to the specified relative compaction at the specified moisture content.
- 5.2 Compaction of *rock* fills shall be performed in accordance with Section 6.3.

6. PLACING, SPREADING AND COMPACTION OF FILL MATERIAL

- 6.1 *Soil* fill, as defined in Paragraph 3.1.1, shall be placed by the Contractor in accordance with the following recommendations:
 - 6.1.1 *Soil* fill shall be placed by the Contractor in layers that, when compacted, should generally not exceed 8 inches. Each layer shall be spread evenly and shall be thoroughly mixed during spreading to obtain uniformity of material and moisture in each layer. The entire fill shall be constructed as a unit in nearly level lifts. Rock materials greater than 12 inches in maximum dimension shall be placed in accordance with Section 6.2 or 6.3 of these specifications.
 - 6.1.2 In general, the *soil* fill shall be compacted at a moisture content at or above the optimum moisture content as determined by ASTM D 1557.
 - 6.1.3 When the moisture content of *soil* fill is below that specified by the Consultant, water shall be added by the Contractor until the moisture content is in the range specified.
 - 6.1.4 When the moisture content of the *soil* fill is above the range specified by the Consultant or too wet to achieve proper compaction, the *soil* fill shall be aerated by the Contractor by blading/mixing, or other satisfactory methods until the moisture content is within the range specified.
 - 6.1.5 After each layer has been placed, mixed, and spread evenly, it shall be thoroughly compacted by the Contractor to a relative compaction of at least 90 percent. Relative compaction is defined as the ratio (expressed in percent) of the in-place dry density of the compacted fill to the maximum laboratory dry density as determined in accordance with ASTM D 1557. Compaction shall be continuous over the entire area, and compaction equipment shall make sufficient passes so that the specified minimum relative compaction has been achieved throughout the entire fill.

- 6.1.6 Where practical, soils having an Expansion Index greater than 50 should be placed at least 3 feet below finish pad grade and should be compacted at a moisture content generally 2 to 4 percent greater than the optimum moisture content for the material.
- 6.1.7 Properly compacted *soil* fill shall extend to the design surface of fill slopes. To achieve proper compaction, it is recommended that fill slopes be over-built by at least 3 feet and then cut to the design grade. This procedure is considered preferable to track-walking of slopes, as described in the following paragraph.
- 6.1.8 As an alternative to over-building of slopes, slope faces may be back-rolled with a heavy-duty loaded sheepsfoot or vibratory roller at maximum 4-foot fill height intervals. Upon completion, slopes should then be track-walked with a D-8 dozer or similar equipment, such that a dozer track covers all slope surfaces at least twice.
- 6.2 *Soil-rock* fill, as defined in Paragraph 3.1.2, shall be placed by the Contractor in accordance with the following recommendations:
 - 6.2.1 Rocks larger than 12 inches but less than 4 feet in maximum dimension may be incorporated into the compacted *soil* fill, but shall be limited to the area measured 15 feet minimum horizontally from the slope face and 5 feet below finish grade or 3 feet below the deepest utility, whichever is deeper.
 - 6.2.2 Rocks or rock fragments up to 4 feet in maximum dimension may either be individually placed or placed in windrows. Under certain conditions, rocks or rock fragments up to 10 feet in maximum dimension may be placed using similar methods. The acceptability of placing rock materials greater than 4 feet in maximum dimension shall be evaluated during grading as specific cases arise and shall be approved by the Consultant prior to placement.
 - 6.2.3 For individual placement, sufficient space shall be provided between rocks to allow for passage of compaction equipment.
 - 6.2.4 For windrow placement, the rocks should be placed in trenches excavated in properly compacted *soil* fill. Trenches should be approximately 5 feet wide and 4 feet deep in maximum dimension. The voids around and beneath rocks should be filled with approved granular soil having a Sand Equivalent of 30 or greater and should be compacted by flooding. Windrows may also be placed utilizing an "open-face" method in lieu of the trench procedure, however, this method should first be approved by the Consultant.


- 6.2.5 Windrows should generally be parallel to each other and may be placed either parallel to or perpendicular to the face of the slope depending on the site geometry. The minimum horizontal spacing for windrows shall be 12 feet center-to-center with a 5-foot stagger or offset from lower courses to next overlying course. The minimum vertical spacing between windrow courses shall be 2 feet from the top of a lower windrow to the bottom of the next higher windrow.
- 6.2.6 Rock placement, fill placement and flooding of approved granular soil in the windrows should be continuously observed by the Consultant.
- 6.3 *Rock* fills, as defined in Section 3.1.3, shall be placed by the Contractor in accordance with the following recommendations:
 - 6.3.1 The base of the *rock* fill shall be placed on a sloping surface (minimum slope of 2 percent). The surface shall slope toward suitable subdrainage outlet facilities. The *rock* fills shall be provided with subdrains during construction so that a hydrostatic pressure buildup does not develop. The subdrains shall be permanently connected to controlled drainage facilities to control post-construction infiltration of water.
 - 6.3.2 *Rock* fills shall be placed in lifts not exceeding 3 feet. Placement shall be by rock trucks traversing previously placed lifts and dumping at the edge of the currently placed lift. Spreading of the *rock* fill shall be by dozer to facilitate *seating* of the rock. The *rock* fill shall be watered heavily during placement. Watering shall consist of water trucks traversing in front of the current rock lift face and spraying water continuously during rock placement. Compaction equipment with compactive energy comparable to or greater than that of a 20-ton steel vibratory roller or other compaction equipment providing suitable energy to achieve the required compaction or deflection as recommended in Paragraph 6.3.3 shall be utilized. The number of passes to be made should be determined as described in Paragraph 6.3.3. Once a *rock* fill lift has been covered with *soil* fill, no additional *rock* fill lifts will be permitted over the *soil* fill.
 - 6.3.3 Plate bearing tests, in accordance with ASTM D 1196, may be performed in both the compacted *soil* fill and in the *rock* fill to aid in determining the required minimum number of passes of the compaction equipment. If performed, a minimum of three plate bearing tests should be performed in the properly compacted *soil* fill (minimum relative compaction of 90 percent). Plate bearing tests shall then be performed on areas of *rock* fill having two passes, four passes and six passes of the compaction equipment, respectively. The number of passes required for the *rock* fill shall be determined by comparing the results of the plate bearing tests for the *soil* fill and the *rock* fill and by evaluating the deflection


variation with number of passes. The required number of passes of the compaction equipment will be performed as necessary until the plate bearing deflections are equal to or less than that determined for the properly compacted *soil* fill. In no case will the required number of passes be less than two.

- 6.3.4 A representative of the Consultant should be present during *rock* fill operations to observe that the minimum number of "passes" have been obtained, that water is being properly applied and that specified procedures are being followed. The actual number of plate bearing tests will be determined by the Consultant during grading.
- 6.3.5 Test pits shall be excavated by the Contractor so that the Consultant can state that, in their opinion, sufficient water is present and that voids between large rocks are properly filled with smaller rock material. In-place density testing will not be required in the *rock* fills.
- 6.3.6 To reduce the potential for "piping" of fines into the *rock* fill from overlying *soil* fill material, a 2-foot layer of graded filter material shall be placed above the uppermost lift of *rock* fill. The need to place graded filter material below the *rock* should be determined by the Consultant prior to commencing grading. The gradation of the graded filter material will be determined at the time the *rock* fill is being excavated. Materials typical of the *rock* fill should be submitted to the Consultant in a timely manner, to allow design of the graded filter prior to the commencement of *rock* fill placement.
- 6.3.7 *Rock* fill placement should be continuously observed during placement by the Consultant.

7. SUBDRAINS


7.1 The geologic units on the site may have permeability characteristics and/or fracture systems that could be susceptible under certain conditions to seepage. The use of canyon subdrains may be necessary to mitigate the potential for adverse impacts associated with seepage conditions. Canyon subdrains with lengths in excess of 500 feet or extensions of existing offsite subdrains should use 8-inch-diameter pipes. Canyon subdrains less than 500 feet in length should use 6-inch-diameter pipes.





NO SCALE

7.2 Slope drains within stability fill keyways should use 4-inch-diameter (or lager) pipes.



NOTES:

1_EXCAVATE BACKCUT AT 1:1 INCLINATION (UNLESS OTHERWISE NOTED).

2.....BASE OF STABILITY FILL TO BE 3 FEET INTO FORMATIONAL MATERIAL, SLOPING A MINIMUM 5% INTO SLOPE.

4.....CHIMNEY DRAINS TO BE APPROVED PREFABRICATED CHIMNEY DRAIN PANELS (MIRADRAIN G200N OR EQUIVALENT) SPACED APPROXIMATELY 20 FEET CENTER TO CENTER AND 4 FEET WIDE. CLOSER SPACING WAY BE REQUIRED IF SEEPAGE IS ENCOUNTERED.

5....FILTER MATERIAL TO BE 3/4-INCH, OPEN-GRADED CRUSHED ROCK ENCLOSED IN APPROVED FILTER FABRIC (MIRAFI 140NC).

 COLLECTOR PIPE TO BE 4-INCH MINIMUM DIAMETER, PERFORATED, THICK-WALLED PVC SCHEDULE 40 OR EQUIVALENT, AND SLOPED TO DRAIN AT 1 PERCENT MINIMUM TO APPROVED OUTLET.

NO SCALE


- 7.3 The actual subdrain locations will be evaluated in the field during the remedial grading operations. Additional drains may be necessary depending on the conditions observed and the requirements of the local regulatory agencies. Appropriate subdrain outlets should be evaluated prior to finalizing 40-scale grading plans.
- 7.4 Rock fill or soil-rock fill areas may require subdrains along their down-slope perimeters to mitigate the potential for buildup of water from construction or landscape irrigation. The subdrains should be at least 6-inch-diameter pipes encapsulated in gravel and filter fabric. Rock fill drains should be constructed using the same requirements as canyon subdrains.

^{3.....}STABILITY FILL TO BE COMPOSED OF PROPERLY COMPACTED GRANULAR SOIL.


7.5 Prior to outletting, the final 20-foot segment of a subdrain that will not be extended during future development should consist of non-perforated drainpipe. At the non-perforated/ perforated interface, a seepage cutoff wall should be constructed on the downslope side of the pipe.

TYPICAL CUT OFF WALL DETAIL

FRONT VIEW




SIDE VIEW



01010200000

7.6 Subdrains that discharge into a natural drainage course or open space area should be provided with a permanent headwall structure.

FRONT VIEW



7.7 The final grading plans should show the location of the proposed subdrains. After completion of remedial excavations and subdrain installation, the project civil engineer should survey the drain locations and prepare an "as-built" map showing the drain locations. The final outlet and connection locations should be determined during grading operations. Subdrains that will be extended on adjacent projects after grading can be placed on formational material and a vertical riser should be placed at the end of the subdrain. The grading contractor should consider videoing the subdrains shortly after burial to check proper installation and functionality. The contractor is responsible for the performance of the drains.

8. OBSERVATION AND TESTING

- 8.1 The Consultant shall be the Owner's representative to observe and perform tests during clearing, grubbing, filling, and compaction operations. In general, no more than 2 feet in vertical elevation of *soil* or *soil-rock* fill should be placed without at least one field density test being performed within that interval. In addition, a minimum of one field density test should be performed for every 2,000 cubic yards of *soil* or *soil-rock* fill placed and compacted.
- 8.2 The Consultant should perform a sufficient distribution of field density tests of the compacted *soil* or *soil-rock* fill to provide a basis for expressing an opinion whether the fill material is compacted as specified. Density tests shall be performed in the compacted materials below any disturbed surface. When these tests indicate that the density of any layer of fill or portion thereof is below that specified, the particular layer or areas represented by the test shall be reworked until the specified density has been achieved.
- 8.3 During placement of *rock* fill, the Consultant should observe that the minimum number of passes have been obtained per the criteria discussed in Section 6.3.3. The Consultant should request the excavation of observation pits and may perform plate bearing tests on the placed *rock* fills. The observation pits will be excavated to provide a basis for expressing an opinion as to whether the *rock* fill is properly seated and sufficient moisture has been applied to the material. When observations indicate that a layer of *rock* fill or any portion thereof is below that specified, the affected layer or area shall be reworked until the *rock* fill has been adequately seated and sufficient moisture applied.
- 8.4 A settlement monitoring program designed by the Consultant may be conducted in areas of *rock* fill placement. The specific design of the monitoring program shall be as recommended in the Conclusions and Recommendations section of the project Geotechnical Report or in the final report of testing and observation services performed during grading.
- 8.5 We should observe the placement of subdrains, to check that the drainage devices have been placed and constructed in substantial conformance with project specifications.
- 8.6 Testing procedures shall conform to the following Standards as appropriate:

8.6.1 Soil and Soil-Rock Fills:

8.6.1.1 Field Density Test, ASTM D 1556, Density of Soil In-Place By the Sand-Cone Method.

- 8.6.1.2 Field Density Test, Nuclear Method, ASTM D 6938, Density of Soil and Soil-Aggregate In-Place by Nuclear Methods (Shallow Depth).
- 8.6.1.3 Laboratory Compaction Test, ASTM D 1557, Moisture-Density Relations of Soils and Soil-Aggregate Mixtures Using 10-Pound Hammer and 18-Inch Drop.
- 8.6.1.4. Expansion Index Test, ASTM D 4829, Expansion Index Test.

9. PROTECTION OF WORK

- 9.1 During construction, the Contractor shall properly grade all excavated surfaces to provide positive drainage and prevent ponding of water. Drainage of surface water shall be controlled to avoid damage to adjoining properties or to finished work on the site. The Contractor shall take remedial measures to prevent erosion of freshly graded areas until such time as permanent drainage and erosion control features have been installed. Areas subjected to erosion or sedimentation shall be properly prepared in accordance with the Specifications prior to placing additional fill or structures.
- 9.2 After completion of grading as observed and tested by the Consultant, no further excavation or filling shall be conducted except in conjunction with the services of the Consultant.

10. CERTIFICATIONS AND FINAL REPORTS

- 10.1 Upon completion of the work, Contractor shall furnish Owner a certification by the Civil Engineer stating that the lots and/or building pads are graded to within 0.1 foot vertically of elevations shown on the grading plan and that all tops and toes of slopes are within 0.5 foot horizontally of the positions shown on the grading plans. After installation of a section of subdrain, the project Civil Engineer should survey its location and prepare an *as-built* plan of the subdrain location. The project Civil Engineer should verify the proper outlet for the subdrains and the Contractor should ensure that the drain system is free of obstructions.
- 10.2 The Owner is responsible for furnishing a final as-graded soil and geologic report satisfactory to the appropriate governing or accepting agencies. The as-graded report should be prepared and signed by a California licensed Civil Engineer experienced in geotechnical engineering and by a California Certified Engineering Geologist, indicating that the geotechnical aspects of the grading were performed in substantial conformance with the Specifications or approved changes to the Specifications.

LIST OF REFERENCES

- 1. Kennedy, M. P., and S. S. Tan, 2008, *Geologic Map of the San Diego 30' x 60' Quadrangle, California*, USGS Regional Geologic Map Series, 1:100,000 Scale, Map No. 3;
- 2. Risk Engineering, 2016, *EZ-FRISK* (Version 7.65).
- 3. USGS computer program, U.S. Seismic Design Maps, June 2014.



GEOTECHNICAL E ENVIRONMENTAL MATERIALS



Project No. G1832-42-03 March 2, 2017

PFP Coastal Holdings, LLC 4380 La Jolla Village Drive, Suite 250 San Diego, California 92122

Attention: Mr. Matt Quinn

Subject: RESPONSE TO CITY OF SAN DIEGO REVIEW COMMENTS ECO BLOK EAST SAN DIEGO, CALIFORNIA

- References: 1. Cycle Issues, Preliminary Review, Project No. 530514, prepared by City of San Diego Development Services, LDR-Geology, Patrick Thomas, dated January 18, 2017.
 - 2. *Geotechnical Investigation, Eco Blok East, Shasta Street, San Diego, California,* prepared by Geocon Incorporated, dated December 19, 2016 (Project No. G1832-42-03).

Dear Mr. Quinn:

In accordance with your request, we have prepared this response to the geotechnical review comments presented in Reference 1. The review comments along with our responses are presented herein.

- *Issue 3:* The geotechnical consultant should consider revising their description of geologic units in accordance with the recent Geologic Map of the San Diego Quadrangle (2008).
- **Response:** Acknowledged. Based on the 2008 map, the soils at the site are classified as Old Paralic Deposits (Qop). The description provided in the *Soil and Geologic Conditions* section of our report describes them as Old Terrace Deposits (Qt). The two terms are essentially equivalent. We have modified the geologic map in Reference 2 to reflect the soil deposit as Old Paralic Deposits (Qop). The map is appended to this letter.
- *Issue 4:* The boring log for Sample B1-1 indicates a disturbed or bag sample. Clarify if the consolidation testing as depicted n Figure B-2 was performed on this sample.
- **Response:** Sample B1-1 was an undisturbed sample retrieved by a Modified California Split Spoon sampler. The boring log, Figure A-1 shows sample B1-2 as a "Drive Sample (Undistrubed)". From the same boring, a bulk sample (Sample B-1) was obtained from auger cuttings from the upper 5 feet of the boring. At a depth of approximately 2.5 feet, the drilling was stopped and a drive sample obtained.
- *Issue 5:* The geotechnical consultant must indicate if in their professional opinion the consolidation testing results are representative of the sedimentary old surficial deposits onsite.
- **Response:** It is our professional opinion that the consolidation testing results are representative of the sedimentary old surficial deposits on the project site.

- Issue 6: Based on ASTM D5333 the consolidation test results are considered to have a slight potential for hydro consolidation. Clarify if differential settlement due to hydro consolidation is considered to be a significant effect on the proposed development. *Clarify if the effect can be mitigated to an acceptable level (e.g. foundation design).*
- **Response:** ASTM D5333 test method was withdrawn in 2012 and is no longer a valid test method. The testing procedure is different than the testing produced utilized for our laboratory consolidation test (ASTM D2435). In our opinion differential settlement due to hydro consolidation could have a significant effect on structural improvements.

The hydro-collapse measured on the three consolidation tests performed for this project ranged from 0.6 percent to 2 percent. Based on these results, if a 15-foot column of soil were to become wet from infiltration, we would expect a differential settlement magnitude between 1-inch and 3 inches. It is our experience that differential settlement magnitudes in excess of ³/₄-inch across the building foundation can have significant effects on structural improvements. A structural engineer would need to determine if the effect of differential settlement can reasonably be mitigated to an acceptable level.

- Issue 7: A geotechnical condition created by the proposed development may not be considered a valid geotechnical hazard or constraint as the constraint is proposed by the project.
- **Response:** Acknowledge.
- Issue 8: Based on the responses to the review cycle issues, revise Worksheet C.4-1 as necessary.
- **Response:** Based on our responses to the review cycle issue, Worksheet C.4-1 does not need to be revised.

If there are any questions regarding this correspondence, or if we may be of further service, please contact the undersigned at your convenience.

Very truly yours,

(e-mail)

GEOCON INCORPORATED

GE 2533


RCM:GWC:dmc Addressee

Garry W. Cannon



10.2201 ERTIFIED GINEERING





Plotted:03/02/2017 12:10PM | By:RUBEN AGUILAR | File Location:Y:\PROJECTS\G1832-42-03 ECO BLOK EAST\G1832-42-03 Site Plan.dwg



GEOTECHNICAL
MATERIALS
SPECIAL INSPECTIONS

SBE SLBE SCOOP

4373 Viewridge Avenue, Ste. B San Diego, CA 92123 858.292.7575

PFP Coastal Holdings, LLC 4380 La Jolla Village Drive, Suite 250 San Diego, CA 92122 09 May 2017 NOVA Project No. 2017701

Attention: Mr. Ian Gill

Subject: Report Assessment of the Potential for Infiltration-Related Soil Collapse Eco Blök East San Diego, California

References:

<u>Geocon 2016</u>. *Geotechnical Investigation, Eco Blok East, Shasta Street, San Diego, California,* Geocon Incorporated, Project No. G1832-42-03, December 19, 2016.

San Diego 2017. Cycle Issues, Preliminary Review, Project No. 530514, City of San Diego Development Services, LDR-Geology, January 18, 2017.

<u>Geocon 2017</u>. *Response to City of San Diego Review Comments, Eco Blok East, Shasta Street, San Diego,* California, Geocon Incorporated, March 2, 2017.

Latitude 33 2017. Grading & Drainage Plans for: Eco Blok East, 1765 Fortuna Avenue, 3977 Shasta Street, 1750 Roosevelt Avenue, San Diego, California, Latitude 33, February 27, 2017.

Dear Mr. Gill:

This report provides the findings of a review of geotechnical and infiltration-related considerations for a residential development (hereafter, 'the development' or 'the site') now known as "Eco Blök East." The development located in the Pacific Beach area of the City of San Diego, California. The report is intended to supplement the above-referenced geotechnical investigation (i.e., Geocon 2016).

TERMS OF REFERENCE

The work reported herein was completed by NOVA Services, Inc. (NOVA) for PFP Coastal Holdings, LLC (PCH) in accordance with NOVA's proposal dated April 7, 2017.

OBJECTIVE, SCOPE, USE AND LIMITATIONS OF THIS WORK

Objective

The objective of the work reported herein to determine if the geotechnical-related assessment of the collapse potential of the sands provided therein is appropriate.



Scope

General

The scope and sequence of review which was undertaken by NOVA may be considered as the task-based series of activities described below

- Task 1: Project Familiarization.
- Task 2: Design Data Review and Evaluation.
- Task 3: Confirmation Sampling and Laboratory Testing.
 - o Subtask 3-1, Site Reconnaissance and Permitting
 - Subtask 3-2, Engineering Borings
 - Subtask 3-3, Laboratory Testing
- Task 4: Preliminary Discussion of Findings.
- Task 5: Final Data Review and Reporting.

The following subsections abstract the scope of each of the above tasks.

Understood Use

NOVA expects that the findings and recommendations provided herein will be utilized by PFP Coastal Holdings, LLC and its Design Team in decision-making regarding development of stormwater infiltration BMPs.

Limitations

The findings of this report are limited only to an assessment of the potential for soil strain as a result of saturation by stormwater infiltration BMPs.

This report does <u>not</u> address any environmental matters; including, but not limited to assessment or investigation for the presence or absence of hazardous or toxic materials in the soil, groundwater, or surface water within or beyond the site.

SITE DESCRIPTION

Location

Eco Blök East will be developed within the limits of property now identified as 1765 Fortuna Avenue, 3977 Shasta Street, 1750 Roosevelt Avenue in San Diego. The development encompasses approximately 1.64 acres of developed land, bounded on all sides by light residential and commercial development.



Assessment of the Potential for Soil Collapse Eco Blök East, San Diego, CA

PLANNED DEVELOPMENT

General

Eco Blök East will be comprised of 30 single family residential units set with 'zero lot line', fronting Shasta Street. Figure 1 provides a view of current planning for the development.





Figure 1. Conceptual Development Plan (source: Latitude 33 2017)

Stormwater BMPs

Development will disturb about 1.64 acres, adding about 1.16 acres of created impervious area over the limits of the development. Design for infiltration of stormwater will include the use of biofiltration structures that will be sited at the Shasta Street edge of each of the 30 lots. The biofiltration structures will each extend to a depth of about 4 feet below surrounding ground surface. Figure 2 depicts the plan location of the biofiltration BMPs.



(source: Latitude 33 2017)



Assessment of the Potential for Soil Collapse Eco Blök East, San Diego, CA

ENGINEERING BORINGS

Engineering Borings

General

A NOVA geologist directed drilling and sampling of 3 borings, each drilled to about 12 feet below ground surface (bgs) on April 17. Subsurface conditions disclosed by the borings are the same as reported in Geocon 2016. Records of the engineering borings are provided in Attachment 1.

Figure 3 provides a plan view of the site indicating the location of the borings.




Figure 3. Boring Location Plan

Drilling and Sampling

The engineering borings (referenced herein as 'B-1' through 'B-3') were drilled by a specialty subcontractor retained by NOVA. The boring locations were determined in the field by and estimating distances from existing site features, such that the locations are approximate.

The borings were each extended to a depth of 12 feet below ground surface (bgs). Relatively undisturbed samples were recovered from the borings by use of the Modified California sampler ('ring sampler', after ASTM D 3550). The ring sampler was driven using a 140-pound hammer falling for 30 inches with a total penetration of 18 inches, recording blow counts for each six inches of penetration.

The NOVA geologist maintained a log of all sampling, as well as a depiction of the subsurface materials based on the indications of the samples and observation of the drilling itself. The recovered samples were transferred to NOVA's geotechnical laboratory for visual inspection and laboratory testing.



Assessment of the Potential for Soil Collapse Eco Blök East, San Diego, CA

Closure

Each boring was backfilled upon completion, using soil cuttings to backfill the borehole to a level matching the existing surfacing.

LABORATORY TESTING

General

Soil samples recovered from the engineering borings were transferred to NOVA's geotechnical laboratory where a geotechnical engineer reviewed the soil samples and the field logs.

Representative soil samples were selected and tested in NOVA's materials laboratory to check visual classifications and to determine pertinent engineering properties. The laboratory program included visual classifications of all soil samples as well as index, expansivity and strength testing in general accordance with ASTM standards.

Records of the geotechnical laboratory testing are provided in Attachment 2.

Index Testing

'Index' testing is widely used for soil classification, as well a cost-effective means to support estimates of the mechanical characteristics (strength and compressibility) of a soil by correlation of 'index' characteristics with known characteristics of similar soil.

The visual classifications were further evaluated by performing moisture content/dry density and grain size tests. These index testing may be used to correlate samples across the site and to support estimates of a variety of soil characteristics and physical properties. Table 1 provides a summary of this testing.

Sample Ref		As Sar	As Sampled		ntion	Classification after	
Boring	Depth (feet)	Natural Moisture (%)	Dry Unit Weight (pcf)	Passing #200	Cu	ASTM D2488	
B-1	4	7	104	-	-	SM	
B-1	6	6	102	12	4	SM	
B-1	8	8	105	-	-	SM	
B-2	5	8	106	-	-	SM	
B-2	7	8	106	16	> 10	SM	
B-2	9	8	109	-	-	SM	
B-3	4	6	98	-	-	SM	
B-3	8	9	107	17	>10	SM	

 Table 1. Abstract of the Soil Index Testing by NOVA

Notes:

1. 'Passing #200' percent by weight passing the U.S. # 200 sieve (0.074 mm), after ASTM D6913.

3. C_u' indicates Coefficient of Uniformity = D_{60} / D_{10} , using soil gradation (ASTM D6913).



Compressibility Testing

NOVA

Five (5) ring samples was tested in one dimensional consolidation after ASTM D2435. This testing was modeled to emulate conditions, saturating the soil at slightly above the existing overburden stress.

- 1. <u>Recompression</u>. The samples were loaded to at or above the existing overburden stress.
- 2. <u>Saturation</u>. The samples were saturated, recording soil compression upon saturation.
- 3. <u>Continued Loading</u>. Following stabilization after saturation, the samples were loaded to above 10,000 psf, recording continued soil compression.
- 4. <u>Rebound</u>. The samples were unloaded and the rebound recorded.

Sample Ref		As Sar	npled	Strain on	Saturation	Soil
Boring	Depth (feet)	Natural Moisture (%)	Dry Unit Weight (pcf)	Saturation Pressure (psf)	Strain on Saturation (%)	Classification
1	4	7	104	550	0.4	SM
1	6	6	102	1,000	0.6	SM
1	8	8	105	1,000	0.2	SM
2	5	8	106	1,000	0.1	SM
3	6	9	107	1,000	1.2	SM

Table 2. Abstract of the Compressibility Testing by NOVA

Geocon 2016

Geocon 2016 reports the indications of three tests of ring samples in one dimensional consolidation after ASTM D2435. This testing revealed stress-strain behavior common to sandy soils, with the exception that the sands exhibited a potential to compress ('strain' or 'settle') when first saturated.

Table 3 provides the indication of this testing. Of particular concern is Sample B1-3, which exhibited about 2% strain upon saturation.

Table 3. Abstract of the Indications of the Effects ofSaturation on Strain Reported in Geocon 2017

Saturation on Strain Reported in Geocon 2017										
SampleDepthDry UnitStrain (%) onSoil										
Reference	(feet)	Weight (lb/ft ³)	Saturation	Classification						
B1-1	1	98	0.2	SP-SM/SM						
B1-2	3	99	0.5	SP-SM/SM						
B1-3	5	96	2.1	SP-SM/SM						



DISCUSSION

Review of Geocon 2016

Subsurface Conditions

Geocon 2016 reports that the site is underlain by thick, sandy terrace deposits. The sands within these deposits are of medium dense to dense consistency. Groundwater occurs at or near sea level, at a depth of approximately 30 to 40 feet below the existing grade.

Foundations

Structures may be developed on shallow foundations following remedial grading in the form of removal and compaction of the undocumented fill in the near surface.

Stormwater Infiltration

Geocon 2016 notes the indication of potentially excessive strain/compression that could occur when the near surface sands become saturate by releases from the stormwater infiltration BMP. As shown on Table 3, data developed by the compressibility testing indicates that saturation could cause soil movement that ranges from about 0.5 percent to 2 percent of the thickness of saturated soil.

In response to comments by the City of San Diego, Geocon 2017 utilizes the data from the compressibility testing to estimate that if a column of soil beneath a stormwater infiltration BMP were to become saturated, differential settlement on the order of 1-inch to 3-inches could be expected. Geocon 2017 notes that that differential settlement in excess of ³/₄-inch across the building foundation can have significant effects on structures.

In consideration of the foregoing, as well as the results of site-specific infiltration testing, Geocon 2017 judges that infiltration is infeasible.

Testing by NOVA

Objectives

At the outset of the work, NOVA developed a Laboratory Testing Plan intended to reproduce the testing reported in Geocon 2016 and to addresses the several factors listed below.

- 1. Compressibility Testing Data Base.
 - a. <u>Concern.</u> The three tests reported in Geocon 2016 appear to be unfairly weighted by an estimate of 2.1% hydro-collapse that is indicated by a single test (i.e., Sample B1-3 of Table 3). The results of two other tests are neither unusual, nor alarming. Design now anticipates collapse on the order of 2% over a soil column of 8-10 feet thickness, leading to high settlement estimates.
 - b. <u>Solution</u>. To address the potential that a single, anomalous test may mislead, NOVA conducted five (5) compressibility tests of the same type reported in Geocon 2016. These additional tests will improve the database for estimates of hydro-collapse.



- 2. Depth of the Testing.
 - a. <u>Concern.</u> The testing reported in Geocon 2016 is in the near surface, within the upper five feet of the soil profile. A stormwater infiltration BMP will infiltrate below the level of all but one of the tests reported on Table 3. Moreover, the remedial grading recommended in Geocon 2016 (Section 6.3.6) will remove/replace all of the tested soils, rendering the results moot.
 - b. <u>Solution</u>. The compressibility testing by NOVA expanded the considered range of depth, addressing the potential for saturation-related settlement in soils within the depth interval 4 to 8 feet bgs, the zone of soil that will be saturated by any stormwater infiltration BMP.
- 3. Soil Density.
 - a. <u>Concern</u>. As a matter of practice, soils that are potentially problematic for excessive movement upon saturation (often called 'hydro-collapse') have lower dry unit weight (γ_{DRY}) on the order of $\gamma_{DRY} = 92 \text{ lb/ft}^3$ or less (a value that is, admittedly, a 'rule of thumb' based on NOVA's experience with collapse-prone soils).
 - b. <u>Solution.</u> To cost-effectively test against this index, NOVA completed testing to determine dry density throughout the soil column. These more qualitative data may be correlated with the more rigorous compressibility testing, to add to the evidence data base 'for' or 'against' hydro-collapse.

Indications

The testing by NOVA that is reported herein addresses the several factors listed below.

- <u>Compressibility Testing Data Base</u>. Geocon 2016 and the testing reported herein provide an aggregate of eight tests (3 by Geocon and 5 by NOVA) over a soil column extending to 8 feet depth (level at which the sands become dense). Seven of the eight tests indicate no material compression (averaging about 0.3%) upon saturation. It is the judgment of NOVA that the 2.1% hydro-collapse indicated by Sample B1-3 is unrepresentative of the expected performance of the site soil.
- Depth of the Testing. The testing indicates no material potential for ground settlement upon saturation over the interval 4 feet bgs to 8 feet bgs. As noted, even if the anomalous result of Sample B1-3 (5 feet depth) is accepted, the remedial grading recommended in Geocon 2016 (Section 6.3.6) will remove/replace soil within the depth interval represented by this test, rendering the result moot.
- 3. <u>Soil Density</u>. The dry unit weight (γ_{DRY}) of the sands tested by and Geocon average NOVA γ_{DRY} > 100 lb/ft³. An extensive database of industry research identifies low dry unit weight as a qualitative identifier of collapse-prone soils. As is noted above, NOVA becomes alert for this concern when $\gamma_{DRY} < 92$ lb/ft³. The measured dry unit weights are consistent with sands that would exhibit negligible compression upon saturation. This finding is qualitative but compelling support for the judgment the sand at the site will exhibit negligible compression upon saturation.



09 May 2017 NOVA Project No. 2017701

RECOMMENDATION

In consideration of the indications of the testing reported herein, NOVA recommends that design for stormwater infiltration BMPs be undertaken with no concern for the potential that such infiltration may cause ground settlement that is potentially damaging to the planned residences.

CLOSURE

NOVA appreciates the opportunity to be of service to PFP Coastal Holdings. Should you have any questions regarding this report or other matters, please do not hesitate to call.


Sincerely, NOVA Services, Inc.

Wail Mokhtar Project Manager

John F. O'Brien, P.E, G.E. Principal Geotechnical Engineer



Attachments: Attachment 1- Engineering Borings by NOVA Attachment 2- Laboratory Testing by NOVA



anning & Engineering Hiber Sing & Engineering Hiber Sing & Engineering Hiber Sing & Engineering					
PLATE: 1	SUBSURFACE INVESTIGATION MAP	PROJECT NO: 2017701 DATE: MAY 2017 DESIGN BY: AJS DRAWN BY: AJS CHECKED BY: WM REVIEWED BY: JDB	ECO BLOK EAST 1765 FORTUNA AVE., 3977 SHASTA ST., 1750 ROOSEVELT AVE., SAN DIEGO, CALIFORNIA	858-292-7575 858-292-7570 (FAX) WWW.USA-NOVA.COM	4373 VIEWRIDGE AVENUE, SUITE B SAN DIEGO, CALIFORNIA

Attachment 1 Engineering Borings by NOVA



	BORING LOG B-1											
DATE	EEXO	CAV	ATE	D:	API	IL 17, 2017 EQU	PMENT: B-	51			-	LAB TEST ABBREVIATIONS CR CORROSIVITY
EXC	VA T	ION	DES	SCRIPTI	ON: 6 II		COORD.: <u>N/</u>					MC MAXIMUM DENSITY DS DIRECT SHEAR EI EXPANSION INDEX AL ATTERBERG LIMITS SA SIEVE ANALYSIS
GRO		WAT	ERI	DEPTH:	GR	DUNDWATER NOT ENCOUNTERED ELEV	ATION: 48	8.0 FT				RVRESISTANCE VALUECNCONSOLIDATIONSESAND EQUIVALENT
DEPTH (FT)	GRAPHIC LOG	BULK SAMPLE	CAL/SPT SAMPLE	SOIL CLASS. (USCS)	BLOWS PER 12-INCHES	SOIL D SUMMARY OF SU (USCS; COLOR, MOISTUF		ONDITIO		ER)	LABORATORY	REMARKS
0 _				SM		GRASS AND ORGANICS VERY OLD PARALIC DEPOSITS, UNIT 6	Qvop6): SILTY	SAND;	LIGHT B	ROWN TO		
					12 8	REDDISH-BROWN, MOIST, LOOSE, FINE	GRAINED	<i>671142</i> ,			CN	6.7% 103.7pcf
-		Ì			10						CN SA	6.4% 102.0pcf
_					13 13						CN	7.7% 104.6pcf
10— — —					18	MEDIUM DENSE						
		-			21	BORING TERMINATED AT 13.5 FT. NO GI	ROUNDWATER	RENCOU	NTEREL	D. NO CAVIN	G.	
15 — — —												
 20 	-											
 25 												
_												
30			1		KE	TO SYMBOLS		l	ECO BLO	OK EAST		
▼ ⊠					OUNDWA			1750 I	ROOSE	, 3977 SHAS /ELT AVENU CALIFORNI/	E	ET,
		ę	SPT	SAMPLE	ASTM D1	586) GEOLOGIC CONT			HP	DATE:	MAY 20	NOVA
	С	AL. N	IOD.	SAMPLE	(ASTM D3	550) — — — SOIL TYPE CHAN		ED BY:	AJS	PROJECT	NO.: 1017	701 APPENDIX B-1

DATE EXCAVATED: APRIL 17,2017 EQUIPMENT: 5-51 CONCREDIT EXCAVATION DESCRIPTION: #INCH DAMETER AUGER SORING GPS COORD.: NA GROUNDWATER DEPTH: GROUNDWATER MOTENCOINTERED ELEVATION: 42.0 FT Participation GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER DEPTHON Participation Participation GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER Participation GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER Participation GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER Participation GROUNDWATER DEPTH: GROUNDWATER DATI 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. FOR BLOK EAST 8.3% 108.0 Qpc		BORING LOG B-2								
EXCAVATION DESCRIPTION: INCL DIAMETER AUGREBORING QPS COORDJ: INA PS Difference Series GROUNDWATER DEPTH: GROUNDWATER NOT ENCONTERED ELEVATION: 42.9 fT State Series State Series GROUNDWATER DEPTH: GROUNDWATER NOT ENCONTERED ELEVATION: 42.9 fT State Series State Series USES SUBMARY OF SUBSURFACE CONSTRUCTION 40.9 ft State Series State Series USES SUBMARY OF SUBSURFACE CONSTRUCTIONS State Series State Series USES SUBMARY OF SUBSURFACE CONSTRUCTIONS State Series State Series USES COLOR SUBMARY OF SUBSURFACE CONSTRUCTIONS State Series USES COLOR SUBMARY OF SUBSURFACE SUBMARY OF SUBSURFACE CONSTRUCTIONS USES COLOR SUBMARY OF SUBSURFACE SUBMARY OF SUBSURFACE CONSTRUCTIONS USES SUBMARY SUBMARY OF SUBSURFACE SUBMARY OF	DATE	EEXO	CAV	ATE	D:	API	RIL 17, 2017 EQUIPMENT: B-51			
GROUNDWATER DEPTH: OPCUMUMATER NOTENCOUNTERED ELEVATION: 24 PT CN CN CONSCIDENTION SUMMARY OF SUBSURFACE CONDITIONS (USCS; COLOR, MOISTURE, DENSITY, GRAIN SIZE, OTHER) D 1 1 1 0	EXCA	VAT	ION	DES	SCRIPTI	ON: 6 II	ICH DIAMETER AUGER BORING GPS COORD.: N/A		DS DIRECT SHEAR EI EXPANSION INDEX AL ATTERBERG LIMITS	
Image: Signed biology of the second state o	GRO	JND	WAT	ERI	DEPTH:	GR	DUNDWATER NOT ENCOUNTERED ELEVATION: 42.0 FT		RV RESISTANCE VALUE CN CONSOLIDATION	
SM UNINGS AND PRAILED SEPONENTS. UNIT 6 (Qxxxp6): SILTY SAND: LIGHT BROWN TO REDDISH-BROWN, MOIST, LOOSE, FINE GRAINED 10 10 13 8.5% 106.8pcf 13 8.5% 106.8pcf 14 13 10 8.5% 106.8pcf 11 8.5% 106.8pcf 12 4.3% 109.0pcf 13 8.5% 106.8pcf 14 13 15 34 16 10 17 8.5% 106.8pcf 18 8.5% 106.0pcf 19 34 10 10 11 10 12 11 13 8.5% 106.0pcf 14 10 15 10 16 10 17 10 18 10 19 10 10 11 10 11 10 11 10 11 10 11 10 11	DEPTH (FT)	GRAPHIC LOG	BULK SAMPLE	CAL/SPT SAMPLE	SOIL CLASS. (USCS)	BLOWS PER 12-INCHES	SUMMARY OF SUBSURFACE CONDITIONS	LABORATORY	REMARKS	
Image: Second	0				SM		GRASS AND ORGANICS			
13 13 8.5% 105.6pcf 10 29 MEDIUM DENSE 8.5% 109.0pcf 34 34 34 8.5% 109.0pcf 15 34 80RING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 8.5% 109.0pcf 20 34 80RING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 8.5% 109.0pcf 20 34 80RING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 8.5% 109.0pcf 20 15 10 10 10 20 15 10 10 10 20 15 10 10 10 20 15 10 10 10 20 10 10 10 10 20 10 10 10 10 20 10 10 10 10 20 10 10 10 10 20 10 10 10 10 20 10 10 10 10 20 10 10 10 10 20	-				511	10				
A BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. BULK SAMPLE FRONEOUS BLOWCOUNT FORTUNA AVENUE, 3977 SHASTA STREET, 1750 ROOSEVELT AVENUE SAN DIEGO, CALIFORNIA	5					13		CN	7.8% 106.3pcf	
10 23 MEDIUM DENSE 34 34 15 34 15 34 20 8 20 8 20 8 21 8 22 8 23 8 24 8 25 8 26 8 27 8 28 8 29 8 20 8 20 8 21 8 22 8 23 8 24 8 25 8 26 8 27 8 28 8 29 8 20 8 20 8 21 8 22 8 23 8 24 9 25 8 26 8 27 8 28 8	_					13		SA		
15 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 15 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. 20 BORING TERMINATER ENCOURS BLOWCOUNTERED. 20 BULK SAMPLE 20 BULK SAMPLE 20 BULK SAMPLE 20 BULK SAMPLE 20 SAN DIEGO, CALIFORNIA	10 — —					29	MEDIUM DENSE		6.5% 109.0pci	
15 20 20 20 20 21 25 30 KEY TO SYMBOLS SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SAMPLE SAN DIEGO, CALIFORNIA SAN DIEGO, CALIFORNIA SAN DIEGO, CALIFORNIA	_					34	BORING TERMINATED AT 13.5 ET. NO GROUNDWATER ENCOUNTERED. NO CAVING			
25	15 — — —									
30 KEY TO SYMBOLS 30 ECO BLOK EAST SROUNDWATER # ERRONEOUS BLOWCOUNT MOSAMPLE * NO SAMPLE RECOVERY SAN DIEGO, CALIFORNIA NOVA	 20 									
KEY TO SYMBOLS ECO BLOK EAST GROUNDWATER # ERRONEOUS BLOWCOUNT BULK SAMPLE # ERRONEOUS BLOWCOUNT NO SAMPLE RECOVERY SAN DIEGO, CALIFORNIA	 25									
KEY TO SYMBOLS ECO BLOK EAST GROUNDWATER # ERRONEOUS BLOWCOUNT BULK SAMPLE # ERRONEOUS BLOWCOUNT NO SAMPLE RECOVERY SAN DIEGO, CALIFORNIA										
Image: Second Water # ERHONEOUS BLOWCOUNT 1750 ROOSEVELT AVENUE Image: Second Water Mosample Recovery San Diego, California	00					KE	Y TO SYMBOLS ECO BLOK EAST			
							1750 ROOSEVELT AVENUE	STRE	IET,	
			:	SPT				AV 00	NOVA	
CAL. MOD. SAMPLE (ASTM D3550) — — SOIL TYPE CHANGE REVIEWED BY: AJS PROJECT NO.: 1017701 APPENDIX B-2		С								

	BORING LOG B-3								
								LAB TEST ABBREVIATIONS	
								CR CORROSIVITY MC MAXIMUM DENSITY DS DIRECT SHEAR EI EXPANSION INDEX AL ATTERBERG LIMITS SA SIEVE ANALYSIS	
GRO		WAT		DEPTH:	_GR	DUNDWATER NOT ENCOUNTERED ELEVATION: 37.0 FT		RV RESISTANCE VALUE CN CONSOLIDATION SE SAND EQUIVALENT	
DЕРТН (FT)	GRAPHIC LOG	BULK SAMPLE	CAL/SPT SAMPLE	SOIL CLASS. (USCS)	BLOWS PER 12-INCHES	SOIL DESCRIPTION SUMMARY OF SUBSURFACE CONDITIONS (USCS; COLOR, MOISTURE, DENSITY, GRAIN SIZE, OTHER)	LABORATORY	REMARKS	
0 _	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			SM-ML		UNDOCUMENTED FILL (Qudf): SILTY SAND-SANDY SILT; BROWN, DAMP TO DRY, LOOSE OR SOFT, FINE TO MEDIUM GRAINED			
				SM	13	VERY OLD PARALIC DEPOSITS, UNIT 6 (Qvop6): SILTY SAND; LIGHT BROWN TO REDDISH-BROWN, MOIST, LOOSE, FINE GRAINED		6.2% 97.9pcf	
-					17 18	MEDIUM DENSE	CN	9.4% 107.0pcf	
10 —					15	VERY DENSE GRAVEL			
					89	BORING TERMINATED AT 13.5 FT DUE TO REFUSAL. NO GROUNDWATER ENCOUNTERED. NO CAVING.			
						Y TO SYMBOLS ECO BLOK EAST TER # ERRONEOUS BLOWCOUNT 1765 FORTUNA AVENUE, 3977 SHASTA	STRE	et,	
$\mathbf{\mathbf{X}}$					BULK SAN	1750 ROOSEVELT AVENUE			
		:	SPT	SAMPLE ((ASTM D1	586) GEOLOGIC CONTACT LOGGED BY: HP DATE: M	AY 20	NOVA	
	С	AL. N	10D.	SAMPLE	(ASTM D3	550) — – – SOIL TYPE CHANGE REVIEWED BY: AJS PROJECT NO	: 1017	7701 APPENDIX B-3	

Attachment 2 Laboratory Testing by NOVA



Laboratory tests were performed in accordance with the generally accepted American Society for Testing and Materials (ASTM) test methods or suggested procedures. Brief descriptions of the tests performed are presented below:


- CLASSIFICATION: Field classifications were verified in the laboratory by visual examination. The final soil classifications are in accordance with the Unified Soils Classification System and are presented on the exploration logs in Attachment 1.
- MAXIMUM DENSITY AND OPTIMUM MOISTURE CONTENT (ASTM D1557 METHOD A,B,C): The maximum dry density and optimum moisture content of typical soils were determined in the laboratory in accordance with ASTM Standard Test D1557, Method A, Method B, Method C.
- GRADATION ANALYSIS (ASTM C136 and/or ASTM D422): Tests were performed on selected representative soil samples in general accordance with ASTM D422. The grain size distributions of selected samples were determined in accordance with ASTM C136 and/or ASTM D422 The results of the tests are summarized on Attachment 2.3 through 2.5.
- CONSOLIDATION TESTS (ASTM D2435): Tests were performed on selected relatively undisturbed soil samples in general accordance with ASTM D2435. The samples were inundated during testing to represent adverse field conditions. The percent of consolidation for each load cycle was recorded as a ratio of the amount of vertical compression to the original height of the sample. The results of the tests are summarized on Appendix 2.6 through Appendix 2.10.

			LAB TEST	SUMMARY	
			ECO BLO	OK EAST	
NOVA		1765	FORTUNA AVE., 3977 SHA	STA ST., 1750 ROOSEVELT	AVE.
4373 VIEWRIDGE AVENUE	E, SUITE B		SAN DIEGO,	CALIFORNIA	
SAN DIEGO, CALIFO PHONE: 858-292-7575 F	RNIA AX: 858-292-7570	BY: AJS	DATE: MAY 2017	PROJECT: 2017701	ATTACHMENT: 2.1

Sample	Sample Depth		Moisture	Dry Density
Location	(ft)	Soil Description	(%)	(pcf)
B-1	4.0'	Light Reddish Brown Silty Sand	6.7	103.7
B-1	6.0'	Light Reddish Brown Silty Sand	6.4	102.0
B-1	8.0'	Light Reddish Brown Silty Sand	7.7	104.6
B-2	5.0'	Light Reddish Brown Silty Sand	7.8	106.3
B-2	7.0'	Light Reddish Brown Silty Sand	8.5	105.6
B-2	9.0'	Light Reddish Brown Silty Sand	8.3	109.0
B-3	4.0'	Light Reddish Brown Silty Sand	6.2	97.9
B-3	8.0'	Light Reddish Brown Silty Sand	9.4	107.0


Moisture-Density (ASTM D2937)


		LAB TES	T RESULTS	
NOVA 4373 VIEWRIDGE AVENUE, SUITE B	1765	,	OK EAST STA ST., 1750 ROOSEVELT CALIFORNIA	AVE.
SAN DIEGO, CALIFORNIA PHONE: 858-292-7575 FAX: 858-292-7570	BY: AJS	DATE: MAY 2017	PROJECT: 2017701	ATTACHMENT: 2.2





 $\rightarrow \leftarrow$ Hydrometer Analysis \rightarrow U.S. Standard Sieve Sizes ← 200 100 16 50 30 ω 1.5 1 3/4 1/2 3/8 . Р ġ . Р ۶. ö 100 : 90 ı۱ 80 i **Percent Passing** 70 ľ 60 ١ ۱ 50 L 40 - - - -1 1 ۱ 30 ۱ ۱ 20 ľ 1 ł 10 1 I 0 100 10 0.1 0.01 0.001 1 Grain Size (mm) Gravel Sand Silt or Clay Fine Coarse Fine Medium Coarse Sample Location: B-2 Depth (ft.): 7.0' USCS Soil Type: SM Passing No. 200 (%): 16 **GRADATION ANALYSIS TEST RESULTS** ECO BLOK EAST 1765 FORTUNA AVE., 3977 SHASTA ST., 1750 ROOSEVELT AVE. N()SAN DIEGO, CALIFORNIA 4373 VIEWRIDGE AVENUE, SUITE B SAN DIEGO, CALIFORNIA BY: AJS DATE: MAY 2017 PROJECT: 2017701 ATTACHMENT: 2.4 FAX: 858-292-7570 PHONE: 858-292-7575


— Size (Inches) —> $\rightarrow \leftarrow$ — Hydrometer Analysis — < U.S. Standard Sieve Sizes \rightarrow 200 100 16 50 30 œ 1.5 1 3/4 1/2 3/8 ģ . ۷ ġ 100 90 80 **Percent Passing** 70 60 1 50 40 I 1 30 I Ŀ 1 1 20 i i 10 I 0 100 10 0.1 0.001 0.01 1 Grain Size (mm) Sand Gravel Silt or Clay Fine Coarse Fine Medium Coarse Sample Location: B-3 Depth (ft.): 8.0' USCS Soil Type: SM Passing No. 200 (%): 17 **GRADATION ANALYSIS TEST RESULTS** ECO BLOK EAST 1765 FORTUNA AVE., 3977 SHASTA ST., 1750 ROOSEVELT AVE. N()VА SAN DIEGO, CALIFORNIA 4373 VIEWRIDGE AVENUE, SUITE B SAN DIEGO, CALIFORNIA BY: AJS DATE: MAY 2017 PROJECT: 2017701 ATTACHMENT: 2.5 PHONE: 858-292-7575 FAX: 858-292-7570













GEOTECHNICAL
MATERIALS
SPECIAL INSPECTIONS

SBE SLBE SCOOP

PFP Coastal Holdings, LLC 4380 La Jolla Village Drive, Suite 250 San Diego, CA 92122

July 5, 2017 NOVA Project No. 2017701

Attention: Mr. Ian Gill

Subject: Assumption of Geotechnical Engineer-of-Record Eco Blok East Apartments 1765 Fortuna Avenue, 3977 Shasta Street, 1750 Roosevelt Avenue San Diego, California

References:

- 1. <u>Geocon 2016</u>. *Geotechnical Investigation, Eco Blok East, Shasta Street, San Diego, California*, Geocon, Project No. G1832-42-03, December 19, 2016.
- 2. <u>Geocon 2017</u>. Response to City of San Diego Review Comments, Eco Blok East, San Diego, California, Geocon Project No. G1832-42-03, March 2, 2017.
- 3. <u>Golba 2016.</u> Building Plan Set, Eco Blok Residences, 3977 Shasta Street, San Diego, California; Golba Architecture, December 13, 2016.
- 4. <u>Latitude 33 2017</u>. *Grading & Drainage Plans for: Eco Blok East, 1765 Fortuna Avenue, 3977 Shasta Street, 1750 Roosevelt Avenue, San Diego, California,* Latitude 33 Planning and Engineering, February 27, 2017.
- 5. <u>NOVA 2017</u>. *Report, Assessment of the Potential for Infiltration-Related Soil Collapse, Eco Blok East, San Diego, California,* NOVA Services, Inc., Project No. 2017701, May 9, 2017.

Dear Mr. Gill:

The intent of this letter is to document that NOVA Services, Inc. (NOVA) has been retained by PFP Coastal Holdings, LLC for the subject project. NOVA will assume the role of Geotechnical Engineer-of-Record.

NOVA has reviewed the referenced geotechnical reports and referenced plans for the Eco Blok East Development. With the exception of Potential for Infiltration-Related Collapse, NOVA agrees with the soil and geologic conditions, geologic hazard assessment, site development recommendations, infiltration test data and calculated infiltration rates presented in the referenced geotechnical reports (Geocon 2016, Geocon 2017), building plan (Golba 2016) and grading plans (Latitude 33 2017).

Geocon 2016 reports the indications of three tests of ring samples in one dimensional consolidation after ASTM D2435. This testing revealed stress-strain behavior common to sandy soils, with the exception that the sands exhibited a potential to compress ('strain' or 'settle') when first saturated. Geocon 2016 notes the indication of potentially excessive strain/compression that could occur when the near surface sands become saturated by releases from the stormwater infiltration BMP.

NOVA conducted five (5) compressibility tests of the same type reported in Geocon 2016. The findings of this work are reported in NOVA 2017. The compressibility testing NOVA expanded the considered range of depth, addressing the potential for saturation-related settlement in soils within the depth interval 4 to 8 feet



bgs, the zone of soil that will be saturated by any stormwater infiltration BMP. As is discussed in detail in NOVA 2017, the testing indicates no material potential for ground settlement upon saturation over the interval 4 feet bgs to 8 feet bgs. In consideration of the indications of the testing reported in NOVA 2017, NOVA recommends that design for stormwater infiltration BMPs be undertaken with no concern for the potential that such infiltration may cause ground settlement that is potentially damaging to the planned residences. Attached is infiltration worksheet C.4-1, Categorization of Infiltration Feasibility Conditions that was provided with NOVA 2017.

It is hoped the foregoing is clear. Should you have any questions regarding this letter or other matters, please contact the undersigned at (858) 292-7575.

Sincerely, NOVA Services, Inc.

John F. O'Brien, P.E, G.E. Principal Geotechnical Engineer



Ima Willes - Holy

Bryan Miller-Hicks, P.G., C.E.G. Senior Geologist



SD CLIMATE ACTION PLAN CONSISTENCY CHECKLIST INTRODUCTION

In December 2015, the City adopted a Climate Action Plan (CAP) that outlines the actions that City will undertake to achieve its proportional share of State greenhouse gas (GHG) emission reductions. The purpose of the Climate Action Plan Consistency Checklist (Checklist) is to, in conjunction with the CAP, provide a streamlined review process for proposed new development projects that are subject to discretionary review and trigger environmental review pursuant to the California Environmental Quality Act (CEQA).¹

Analysis of GHG emissions and potential climate change impacts from new development is required under CEQA. The CAP is a plan for the reduction of GHG emissions in accordance with CEQA Guidelines Section 15183.5. Pursuant to CEQA Guidelines Sections 15064(h)(3), 15130(d), and 15183(b), a project's incremental contribution to a cumulative GHG emissions effect may be determined not to be cumulatively considerable if it complies with the requirements of the CAP.

This Checklist is part of the CAP and contains measures that are required to be implemented on a project-by-project basis to ensure that the specified emissions targets identified in the CAP are achieved. Implementation of these measures would ensure that new development is consistent with the CAP's assumptions for relevant CAP strategies toward achieving the identified GHG reduction targets. Projects that are consistent with the CAP as determined through the use of this Checklist may rely on the CAP for the cumulative impacts analysis of GHG emissions. Projects that are not consistent with the CAP must prepare a comprehensive project-specific analysis of GHG emissions, including quantification of existing and projected GHG emissions and incorporation of the measures in this Checklist to the extent feasible. Cumulative GHG impacts would be significant for any project that is not consistent with the CAP.

The Checklist may be updated to incorporate new GHG reduction techniques or to comply with later amendments to the CAP or local, State, or federal law.

¹ Certain projects seeking ministerial approval may be required to complete the Checklist. For example, projects in a Community Plan Implementation Overlay Zone may be required to use the Checklist to qualify for ministerial level review. See Supplemental Development Regulations in the project's community plan to determine applicability.

This page intentionally left blank

SUBMITTAL APPLICATION

- The Checklist is required only for projects subject to CEQA review.²
- If required, the Checklist must be included in the project submittal package. Application submittal procedures can be found in <u>Chapter 11: Land Development Procedures</u> of the City's Municipal Code.
- The requirements in the Checklist will be included in the project's conditions of approval.
- The applicant must provide an explanation of how the proposed project will implement the requirements described herein to the satisfaction of the Planning Department.

			. •
Ann	ication	Inform	nation
	leacion		

Contact Information		
Project No./Name:		
Property Address:		
Applicant Name/Co.:		
Contact Phone:	Contact Email:	
Was a consultant retained to complete this checklist? Consultant Name:	□ Yes □ No Contact Phone:	If Yes, complete the following
Company Name:	Contact Email:	
Project Information		
1. What is the size of the project (acres)?		
 Identify all applicable proposed land uses: □ Residential (indicate # of single-family units): 		
Residential (indicate # of multi-family units):		
Commercial (total square footage):		
Industrial (total square footage):		
 Other (describe): 3. Is the project or a portion of the project located in a Transit Priority Area? 	□ Yes □ No	

4. Provide a brief description of the project proposed:

² Certain projects seeking ministerial approval may be required to complete the Checklist. For example, projects in a Community Plan Implementation Overlay Zone may be required to use the Checklist to qualify for ministerial level review. See Supplemental Development Regulations in the project's community plan to determine applicability.



Step 1: Land Use Consistency

The first step in determining CAP consistency for discretionary development projects is to assess the project's consistency with the growth projections used in the development of the CAP. This section allows the City to determine a project's consistency with the land use assumptions used in the CAP.

	Step 1: Land Use Consistency		
Checklist Item (Check the appropriate box	and provide explanation and supporting documentation for your answer)	Yes	No
 zoning designations?;³ B. If the proposed project includes a land use pla result in an increased actions, as determined C. If the proposed project the project include a la 	consistent with the existing General Plan and Community Plan land use and <u>OR</u> , is not consistent with the existing land use plan and zoning designations, and n and/or zoning designation amendment, would the proposed amendment density within a Transit Priority Area (TPA) ⁴ and implement CAP Strategy 3 in Step 3 to the satisfaction of the Development Services Department?; <u>OR</u> , is not consistent with the existing land use plan and zoning designations, does nd use plan and/or zoning designation amendment that would result in an -intensive project when compared to the existing designations?		

If "**Yes**," proceed to Step 2 of the Checklist. For question B above, complete Step 3. For question C above, provide estimated project emissions under both existing and proposed designation(s) for comparison. Compare the maximum buildout of the existing designation and the maximum buildout of the proposed designation.

If "**No**," in accordance with the City's Significance Determination Thresholds, the project's GHG impact is significant. The project must nonetheless incorporate each of the measures identified in Step 2 to mitigate cumulative GHG emissions impacts unless the decision maker finds that a measure is infeasible in accordance with CEQA Guidelines Section 15091. Proceed and complete Step 2 of the Checklist.

³ This question may also be answered in the affirmative if the project is consistent with SANDAG Series 12 growth projections, which were used to determine the CAP projections, as determined by the Planning Department.

⁴ This category applies to all projects that answered in the affirmative to question 3 on the previous page: Is the project or a portion of the project located in a transit priority area.

Step 2: CAP Strategies Consistency

The second step of the CAP consistency review is to review and evaluate a project's consistency with the applicable strategies and actions of the CAP. Step 2 only applies to development projects that involve permits that would require a certificate of occupancy from the Building Official or projects comprised of one and two family dwellings or townhouses as defined in the California Residential Code and their accessory structures.⁵ All other development projects that would not require a certificate of occupancy from the Building Official shall implement Best Management Practices for construction activities as set forth in the <u>Greenbook</u> (for public projects).

Step 2: CAP Strategies Consistency	/		
Checklist Item (Check the appropriate box and provide explanation for your answer)	Yes	No	N/A
Strategy 1: Energy & Water Efficient Buildings			
1. Cool/Green Roofs.			
 Would the project include roofing materials with a minimum 3-year aged solar reflection and thermal emittance or solar reflection index equal to or greater than the values specified in the voluntary measures under <u>California Green Building</u> <u>Standards Code</u> (Attachment A)?; <u>OR</u> Would the project roof construction have a thermal mass over the roof 			
membrane, including areas of vegetated (green) roofs, weighing at least 25 pounds per square foot as specified in the voluntary measures under <u>California</u> <u>Green Building Standards Code</u> ?; <u>OR</u>			
 Would the project include a combination of the above two options? 			
Check "N/A" only if the project does not include a roof component.			

⁵ Actions that are not subject to Step 2 would include, for example: 1) discretionary map actions that do not propose specific development, 2) permits allowing wireless communication facilities, 3) special events permits, 4) use permits or other permits that do not result in the expansion or enlargement of a building (e.g., decks, garages, etc.), and 5) non-building infrastructure projects such as roads and pipelines. Because such actions would not result in new occupancy buildings from which GHG emissions reductions could be achieved, the items contained in Step 2 would not be applicable.

Strategy 3: Bicycling, Walking, Transit & Land Use		
3. Electric Vehicle Charging		
 <u>Multiple-family projects of 17 dwelling units or less</u>: Would 3% of the total parking spaces required, or a minimum of one space, whichever is greater, be provided with a listed cabinet, box or enclosure connected to a conduit linking the parking spaces with the electrical service, in a manner approved by the building and safety official, to allow for the future installation of electric vehicle supply equipment to provide electric vehicle charging stations at such time as it is needed for use by residents? <u>Multiple-family projects of more than 17 dwelling units</u>: Of the total required listed cabinets, boxes or enclosures, would 50% have the necessary electric vehicle supply equipment installed to provide active electric vehicle charging stations ready for use by residents? <u>Non-residential projects</u>: Of the total required listed cabinets, boxes or enclosures, would 50% have the necessary electric vehicle charging stations ready for use by residents? <u>Non-residential projects</u>: Of the total required listed cabinets, boxes or enclosures, would 50% have the necessary electric vehicle supply equipment installed to provide active electric vehicle charging stations ready for use? <u>Non-residential projects</u>: Of the total required listed cabinets, boxes or enclosures, would 50% have the necessary electric vehicle supply equipment installed to provide active electric vehicle charging stations ready for use? 		
Strategy 3: Bicycling, Walking, Transit & Land Use (Complete this section if project includes non-residential or mixed uses)		
4. Bicycle Parking Spaces Would the project provide more short- and long-term bicycle parking spaces than required in the City's Municipal Code (<u>Chapter 14, Article 2, Division 5</u>)? ⁶ Check "N/A" only if the project is a residential project.		

⁶ Non-portable bicycle corrals within 600 feet of project frontage can be counted towards the project's bicycle parking requirements.

0-10 0 0 11-50 1 shower stall 2 51-100 1 shower stall 3 101-200 1 shower stall 4 1 shower stall plus 1 1 two-tier locker plus 1	Occupants (Employees)	Shower/Changing Facilities Required	Two-Tier (12" X 15" X 72") Personal Effects Lockers Required		
51-1001 shower stall3101-2001 shower stall41 shower stall plus 11 two-tier locker plus 1	0-10	0	0		
101-200 1 shower stall 4 1 shower stall plus 1 1 two-tier locker plus 1	11-50	1 shower stall	2		
1 shower stall plus 1 1 two-tier locker plus 1	51-100	1 shower stall	3		
1 shower stall plus 1 1 two-tier locker plus 1	101-200	1 shower stall	4		
Over 200 additional shower stall two-tier locker for each L for each 200 additional 50 additional tenant- tenant-occupants occupants	Over 200	additional shower stall for each 200 additional	two-tier locker for each 50 additional tenant-		

	Number of Required Parking	Number of Designated Parking			
	Spaces 0-9	Spaces 0			
	10-25	2			
	26-50	4			
	51-75	6	-		
	76-100	-			
	101-150	11			
	151-200	18			
	201 and over	At least 10% of total			
be conside	red eligible for designated pa to be provided within the ove	stickers from expired HOV lane rking spaces. The required desi erall minimum parking requiren	gnated parking		
auditiont	" only if the project is a reside	ential project, or if it does not inc	clude		
Check "N/A	ntial use in a TPA.				

	-	
7. Transportation Demand Management Program		
If the project would accommodate over 50 tenant-occupants (employees), would it include a transportation demand management program that would be applicable to existing tenants and future tenants that includes:		
At least one of the following components:		
Parking cash out program		
 Parking management plan that includes charging employees market-rate for single-occupancy vehicle parking and providing reserved, discounted, or free spaces for registered carpools or vanpools 		
 Unbundled parking whereby parking spaces would be leased or sold separately from the rental or purchase fees for the development for the life of the development 		
And at least three of the following components:		
 Commitment to maintaining an employer network in the SANDAG iCommute program and promoting its RideMatcher service to tenants/employees 		
On-site carsharing vehicle(s) or bikesharing		
Flexible or alternative work hours		
Telework program		
Transit, carpool, and vanpool subsidies		
Pre-tax deduction for transit or vanpool fares and bicycle commute costs		П
 Access to services that reduce the need to drive, such as cafes, commercial stores, banks, post offices, restaurants, gyms, or childcare, either onsite or within 1,320 feet (1/4 mile) of the structure/use? 		
Check "N/A" only if the project is a residential project or if it would not accommodate over 50 tenant-occupants (employees).		

Step 3: Project CAP Conformance Evaluation (if applicable)

The third step of the CAP consistency review only applies if Step 1 is answered in the affirmative under option B. The purpose of this step is to determine whether a project that is located in a TPA but that includes a land use plan and/or zoning designation amendment is nevertheless consistent with the assumptions in the CAP because it would implement CAP Strategy 3 actions. In general, a project that would result in a reduction in density inside a TPA would not be consistent with Strategy 3.The following questions must each be answered in the affirmative and fully explained.

1. Would the proposed project implement the General Plan's City of Villages strategy in an identified Transit Priority Area (TPA) that will result in an increase in the capacity for transit-supportive residential and/or employment densities?

Considerations for this question:

- Does the proposed land use and zoning designation associated with the project provide capacity for transit-supportive residential densities within the TPA?
- Is the project site suitable to accommodate mixed-use village development, as defined in the General Plan, within the TPA?
- Does the land use and zoning associated with the project increase the capacity for transit-supportive employment intensities within the TPA?
- 2. Would the proposed project implement the General Plan's Mobility Element in Transit Priority Areas to increase the use of transit? Considerations for this question:
 - Does the proposed project support/incorporate identified transit routes and stops/stations?
 - Does the project include transit priority measures?
- 3. Would the proposed project implement pedestrian improvements in Transit Priority Areas to increase walking opportunities? Considerations for this question:
 - Does the proposed project circulation system provide multiple and direct pedestrian connections and accessibility to local activity centers (such as transit stations, schools, shopping centers, and libraries)?
 - Does the proposed project urban design include features for walkability to promote a transit supportive environment?

4. Would the proposed project implement the City of San Diego's Bicycle Master Plan to increase bicycling opportunities? Considerations for this question:

- Does the proposed project circulation system include bicycle improvements consistent with the Bicycle Master Plan?
- Does the overall project circulation system provide a balanced, multimodal, "complete streets" approach to accommodate mobility needs of all users?

5. Would the proposed project incorporate implementation mechanisms that support Transit Oriented Development? <u>Considerations for this question:</u>

- Does the proposed project include new or expanded urban public spaces such as plazas, pocket parks, or urban greens in the TPA?
- Does the land use and zoning associated with the proposed project increase the potential for jobs within the TPA?
- Do the zoning/implementing regulations associated with the proposed project support the efficient use of parking through mechanisms such as: shared parking, parking districts, unbundled parking, reduced parking, paid or time-limited parking, etc.?

6. Would the proposed project implement the Urban Forest Management Plan to increase urban tree canopy coverage?

Considerations for this question:

- Does the proposed project provide at least three different species for the primary, secondary and accent trees in order to accommodate varying parkway widths?
- Does the proposed project include policies or strategies for preserving existing trees?
- Does the proposed project incorporate tree planting that will contribute to the City's 20% urban canopy tree coverage goal?

SD CLIMATE ACTION PLAN CONSISTENCY CHECKLIST ATTACHMENT A

This attachment provides performance standards for applicable Climate Action Pan (CAP) Consistency Checklist measures.

Land Use Type	Roof Slope	Minimum 3-Year Aged Solar Reflectance	Thermal Emittance	Solar Reflective Index
Law Diag Desidential	≤2:12	0.55	0.75	64
Low-Rise Residential	> 2:12	0.20	0.75	16
High-Rise Residential Buildings,	≤2:12	0.55	0.75	64
Hotels and Motels	> 2:12	0.20	0.75	16
Nex Desidential	≤2:12	0.55	0.75	64
Non-Residential —	> 2:12	0.20	0.75	16

CALGreen does not include recommended values for low-rise residential buildings with roof slopes of \leq 2:12 for San Diego's climate zones (7 and 10). Therefore, the values for climate zone 15 that covers Imperial County are adapted here.

Solar Reflectance Index (SRI) equal to or greater than the values specified in this table may be used as an alternative to compliance with the aged solar reflectance values and thermal emittance.

Fable 2	e 2 Fixture Flow Rates for Non-Residential Buildings related to Question 2: Plumbing Fixtures a Fittings supporting Strategy 1: Energy & Water Efficient Buildings of the Climate Action Pla			
	Fixture Type	Maximum Flow Rate		
	Showerheads	1.8 gpm @ 80 psi		
	Lavatory Faucets	0.35 gpm @60 psi		
	Kitchen Faucets	1.6 gpm @ 60 psi		
	Wash Fountains	1.6 [rim space(in.)/20 gpm @ 60 psi]		
	Metering Faucets	0.18 gallons/cycle		
	Metering Faucets for Wash Fountains	0.18 [rim space(in.)/20 gpm @ 60 psi]		
	Gravity Tank-type Water Closets	1.12 gallons/flush		
	Flushometer Tank Water Closets	1.12 gallons/flush		
	Flushometer Valve Water Closets	1.12 gallons/flush		
	Electromechanical Hydraulic Water Closets	1.12 gallons/flush		
	Urinals	0.5 gallons/flush		
Source: Adapted	Urinals			

Source: Adapted from the <u>California Green Building Standards Code</u> (CALGreen) Tier 1 non-residential voluntary measures shown in Tables A5.303.2.3.1 and A5.106.11.2.2, respectively. See the <u>California Plumbing Code</u> for definitions of each fixture type.

Where complying faucets are unavailable, aerators rated at 0.35 gpm or other means may be used to achieve reduction.

Acronyms:

gpm = gallons per minute psi = pounds per square inch (unit of pressure)

in. = inch

	es and Fixtures for Commercial Applications and Fixtures for Commercial Applications ittings supporting Strategy 1: Energy & V	-		
Appliance/Fixture Type	Standard			
Clothes Washers	Maximum Water I (WF) that will reduce the use of below the California Energy Comm for commercial clothes washer of the California Code of	water by 10 percent hissions' WF standards s located in Title 20		
Conveyor-type Dishwashers	0.70 maximum gallons per rack (2.6 L) (High-Temperature)	0.62 maximum gallons per rack (4.4 L) (Chemical)		
Door-type Dishwashers	0.95 maximum gallons per rack (3.6 L) (High-Temperature)	1.16 maximum gallons per rack (2.6 L) (Chemical)		
Undercounter-type Dishwashers	0.90 maximum gallons per rack (3.4 L) (High-Temperature)	0.98 maximum gallons per rack (3.7 L) (Chemical)		
Combination Ovens	Consume no more than 10 gallons per hour (38 L/h) in the full operational mode.			
 Commercial Pre-rinse Spray Valves (manufactured on or after January 1, 2006) Function at equal to or less than 1.6 gallons per minute (0.10 L/s) at 60 psi (414 kPa Be capable of cleaning 60 plates in an average time of not more than 30 seconds per plate. Be equipped with an integral automatic shutoff. Operate at static pressure of at least 30 psi (207 kPa) when designed for a rate of 1.3 gallons per minute (0.08 L/s) or less. 				
Source: Adapted from the <u>California Green Building Standa</u> the <u>California Plumbing Code</u> for definitions of each applia		sures shown in Section A5.303.3. See		
Acronyms: L = liter L/h = liters per hour L/s = liters per second psi = pounds per square inch (unit of pressure) kPa = kilopascal (unit of pressure)				

ATTACHMENT A - ECO BLöK RESIDENCES (Project No. 530514)

CAP CONSISTENCY CHECKLIST SUPPORTING DOCUMENTATION

PROJECT DESCRIPTION

The project proposes the removal of an existing assisted living complex, and the construction of thirty new single family homes on the existing 30 legal lots (Lots 1 thru 24, Block 17, Map 894 and Lots 1 thru 6, Block 27, Map 894). The 30 new homes will consist of 6 plan types: Plan A(R) at 1,755-square feet, Plan B(R) at 1,726-square feet, Plan C(R) at 1,780-square feet, Plan D(R) at 1,757-square feet, Plan E(R) at 1,655-square feet, and Plan F(R) at 1,776-square feet. Project will utilize a Lot-Line Adjustment as the mechanism to alter the existing six lot shapes at the corners of the project site to better suit the infill construction in this existing developed neighborhood.

Land Use Consistency

1. The project is consistent with the land use designation in the City's General Plan (Residential) and the Community Plan for Pacific Beach. The project site is designated for multi-family residential development at a density of 9-14 units per acre in the Pacific Beach Community Plan. The RM1-1 zone implements the designated use and density. The proposal of thirty residences on an area of 1.64 acres is 18.3, which is over density for the prescribed use and density of the community plan. Although the project is over density of the community plan designation, the proposed lot line adjustment is not increasing the number of lots. The 30 existing underlying lots are allowed proposed development of 30 residences (one for each legal lot).

CAP Strategies Consistency

STRATEGY 1. ENERGY & WATER EFFICIENT BUILDINGS

1. Cool/Green Roofs - Where applicable, the project will include roofing materials with a minimum 3-year aged solar reflection and thermal emittance or solar reflection index equal to or greater than the values specified in the voluntary measures under California Green Building Standards Code.

2. Plumbing fixtures and fittings - The project will use low-flow fixtures/appliances be consistent with each of the following:

- Kitchen faucets: maximum flow rate not to exceed 1.5. gallons per minute at 60 psi;
- Standard dishwashers: 4.25 gallons per cycle;
- Compact dishwashers: 3.5 gallons per cycle; and
- Clothes washers: water factor of 6 gallons per cubic feet of drum capacity.

STRATEGY 2. CLEAN & RENEWABLE ENERGY

3. Clean & Renewable Energy - designed to have an energy budget that shows a 15% energy improvement when compared to the Title 24, Part 6 Energy Budget for the Proposed Design Building as calculated by Compliance Software certified by the California Energy Commission. The demand reduction will be provided through the list below of sustainable design features of this single family home:

ATTACHMENT A - ECO BLöK RESIDENCES (Project No. 530514)

SUSTAINABLE FEATURES – ECO BLÖK RESIDENCES

- 1. Homes will exceed TITLE-24 by a minimum of 15% and will includes Sustainable features throughout as outlined below.
- 2. Home to be equipped with a SOLAR PHOTO VOLTAIC SYSTEM that shall generate a minimum of 50% of the anticipated energy demand.
- 3. Exterior includes Sustainable fiber cement siding.
- 4. Energy efficient thermal exterior wall insulation to reduce heating and cooling load as well as insulation for all interior floor and wall assemblies as well.
- 5. Dual-pane LOW-E glass panels on doors and windows.
- 6. High efficiency Lighting and occupancy sensors.
- 7. Installation of ENERGY STAR rated appliances throughout the home.
- 8. Use of low VOC paints throughout the home.
- 9. Use of low emitting adhesives, coatings and carpets.
- 10. Framing to use sustainable manufactured lumber where ever possible to preserve old growth lumber.
- 11. Architectural design includes extensive use of passive solar heating and natural ventilation techniques to significantly reduce the heating and cooling load of the home.
- 12. High efficiency building and ductwork sealing to prevent air loss.
- 13. Ultra-high efficiency heating and cooling units
- 14. Use of ceiling fans, operable skylights and clerestory windows to reduce Heat gain and cooling load.
- 15. Use of tank-less energy efficient hot water heating systems.

ATTACHMENT A - ECO BLöK RESIDENCES (Project No. 530514)

STRATEGY 3. BICYCLE, WALKING, TRANSIT & LAND USE

4. Electrical Vehicle Charging - The required parking serving these singlefamily residences will be constructed with a listed cabinet, box or enclosure connected to a raceway linking the required parking space to the electrical service, to allow for the future installation of electric vehicle supply equipment to provide an electric vehicle charging station for use by the resident

5. Bicycle Parking Spaces - Not Applicable for Single-Family Residential Projects per the City of San Diego CAP consistency checklist.

6. Shower Facilities - Not Applicable for Single-Family Residential Projects per the City of San Diego CAP consistency checklist.

7. Designated Parking Spaces - Not Applicable for Single-Family Residential Projects per the City of San Diego CAP consistency checklist.

8. Transportation Demand Management Program - Not Applicable for Single-Family Residential Projects per the City of San Diego CAP consistency checklist. DRAINAGE STUDY FOR:

ECO BLOK HOMES

CITY OF SAN DIEGO, CALIFORNIA

PTS NO. 530514

Prepared for: **Pathfinder Crown Point Apartments, LLC** 4380 La Jolla Village Dr. Suite 250 San Diego, CA 92122 (858) 875-4450

Prepared by: Latitude 33 Planning and Engineering 9968 Hibert Street, 2nd Floor San Diego, California 92131 (858) 751-0633


Giovanni Posillico RCE 66332

TABLE OF CONTENTS

I. PROJECT DESCRIPTION	3
II. EXISTING SITE CONDITION	4
III. DEVELOPED SITE CONDITION	4
IV. HYDROLOGIC METHODOLOGY	5
V. DISCUSSION AND RESULT	6
APPENDIX A: EXISTING & PROPOSED HYDROLOGIC CALCULATIONS	7

I. PROJECT DESCRIPTION

The Eco Blök Homes project is located in the city of San Diego and bounded to the south by Mission Bay, east by Interstate 5, north by Pacific Beach Drive and west by Ingraham Street, see vicinity map below. The project proposes to modify the 1.85-acre site with improvements such as infiltration BMPs, landscaping, sidewalk and single family houses. This report has been prepared to document the analysis of the existing and proposed drainage condition associated with Eco Blök Homess.



NO SCALE

II. EXISTING SITE CONDITION

The project area is approximately 1.85 acres of developed land consisting of 3 existing units and an empty lot containing a garden. The existing site is comprised of buildings, sidewalk and landscaping. The existing site drainage is divided into three basins. The east side of the project (basin 1) drains to the southeast corner of the site and discharges to Roosevelt Avenue. The west side of the project (basin 2) drains to the southwest corner of the site and discharges southerly to curb and gutter along Shasta Avenue and converges with the discharge from basin 1 at Roosevelt Avenue. The southernmost portion of the project (basin 3) drains to the southeast corner of Roosevelt Avenue and Shasta Street. All of the storm water runoff from the project site then flows west down Roosevelt Avenue via curb and gutter where it finally come together at the corner of Roosevelt Avenue and Jewel Street. From there the entire project's runoff flows via curb and gutter to an existing inlet located 550 feet south at the corner of Jewel Street and La Playa Avenue. Storm water then is conveyed via storm drain to Mission Bay

III. DEVELOPED SITE CONDITION

The developed site at the Eco Blök Homes will disturb 1.64 acres and consists of sidewalk, landscaping and infiltration BMPs in addition to 30 single family row homes. The onsite storm water will be treated with infiltration basins.

There are no existing storm drain systems in the vicinity, thus for low flows that are associated with water quality treatment the infiltration systems will be connected through an underground storm drain network which will then discharge to the surface by means of pumps.

For flood control purposes the infiltration BMPs located within Basin 2 & 3 discharge to Shasta Street while those in Basin 1 discharge to the alley on the east side of the project. All water from the project site will be captured and directed to an infiltration BMP. The infiltration BMPs will fill up and the underlying media and aggregate will become saturated. The basins themselves will then begin to pond and fill up to their capacity. Once the proprietary systems reach their capacity the excess flow with simply bypass the BMP and flow into the unnamed alley on the east side of the project. Each standard infiltration BMP contains an overflow system for flows larger than the water quality demand. All of these overflow storm drain systems include a grated catch basin that have an open bottom. These open bottom structures will fill up with water and when a certain water level is reached the overflow will discharge via 3" underdrains to the surrounding curb and gutter. The remaining water that is in the catch basins and infiltration BMPs will then infiltrate through the media and aggregate.

Both overflow and subsurface flows from the project site will discharge through side walk underdrains to either the existing curb and gutter on Shasta Street or to the alley. All discharge points flow via curb and gutter 1,050 feet south to the existing storm drain inlet located at the corner of Jewel Street and La Playa Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue and across Crown Point park and then discharges directly into Mission Bay. The drainage areas have been designed to maintain the overall drainage design and the storm water discharges to the same inlet at the corner of Jewel Street and La Playa Avenue. This project does not propose to dredge or fill materials in water of the U.S. Jurisdictional Waters and will not be required to obtain Clean Water Act Section 401/404 Water Quality Certification.

Please see the Storm Water Quality Management Plan (SWQMP) for details of Water Quality calculations.

IV. HYDROLOGIC METHODOLOGY

This report is intended to support preliminary engineering design, as well as demonstrate compliance with applicable design standards. Specifically, this report will address the 50-yr and 100-yr flow rates for the pre and post condition.

Appendix I of the City of San Diego's 1984 *Drainage Design Manual's* rational method procedure was the basis for the pre and post conditions for the 100-year hydrologic analysis. This study was accomplished through the implementation of the 2015 Autodesk Storm and Sanitary Analysis software, which has the capability to utilize the rational method program based on the City of San Diego storm water design criteria. The input parameters are summarized below and the supporting data is included in Appendix A.

- Intensity-Duration-Frequency: The City's 50-year and 100-year Intensity-Duration-Frequency curve from the *Drainage Design Manual* was used.
- Drainage area: The pre-condition drainage basins were delineated from the base topographic mapping prepared for the project. Proposed condition drainage basins were delineated using the proposed Civil Site Plans which include storm drain layout.
- Manning's Roughness Coefficients: Table 1-104.14A was used to determine appropriate values.
- Run-off Coefficient: Taking into consideration the amount of landscaped area for the precondition a value of 0.50 was used and for the post condition a runoff coefficient of 0.70 was implemented in accordance with Table 2 in Appendix I. A weighted runoff coefficient was used e.g. for existing basin 1 (0.50) => Actual imp. 50%, Tabulated Imp. 70%; (0.50/0.70)*(0.70) = 0.50.
- Flow lengths and elevations: The flow lengths and elevations were obtained from the topographic mapping and grading plans.

V. DISCUSSION AND RESULT

As seen below, the rational method results show that there is an overall increase in flow from the existing condition to the proposed. Basin 1 and 2 in existing conditions will become one basin in proposed conditions via the use of area drains and swales. The volume retained and flow detained by the implementation of the water quality infiltration BMPs will return the post condition flows to existing condition values or lower. For Q100 mitigation, the project will store approximately 1,164 cubic feet of runoff for the west side of the project, and approximately 136 cubic feet of runoff for the east side. For the east side of the project, the Q100 mitigation will be accomplished via 6" of surface ponding as well as 1.2' of gravel storage. For the east side, the all peak storm mitigation will be accomplished with just 6" of surface ponding.


Basin	Area	Runoff Coefficient	100-yr Flows
	(Ac)		(cfs)
1	0.89	0.50	1.09
2	0.63	0.50	0.78
3	0.33	0.50	0.56
Total Area =	1.85	Total Flows =	2.43

Basin	Area	Runoff Coefficient	100-yr Flows	Mitigated Flow
	(Ac)		(cfs)	(cfs)
1	1.52	0.70	4.66	0.78
2	0.33	0.70	1.01	0.56
Total Area =	1.85	Total Flows =	5.67	1.34

Please see Appendix A for the hydrologic calculations and corresponding Drainage Area exhibits.

APPENDIX A: EXISTING & PROPOSED HYDROLOGIC CALCULATIONS

EXISTING



Existing Q100.txt

Autodesk[®] Storm and Sanitary Analysis 2015 - Version 9.1.140 (Build 1)

Project Description

File Name Pre-Condition_100yr.SPF
Description H:\1300\1305.20 - PFP Coastal Holdings Shasta East\Engineering\Reports\Drainage\1305.20
Existing DA's.dwg

Analysis Options *********

Flow Units cfs Subbasin Hydrograph Method. City of San Diego Rational Method Time of Concentration..... SCS TR-55 (5 minutes minimum) Return Period..... 100 years Storage Node Exfiltration. Constant flow Starting Date JUN-28-2017 00:00:00 Ending Date JUN-28-2017 01:00:00 Report Time Step 00:00:10

Subbasin Summary ********

Subbasin	Total
	Area
ID	acres
{_}.E.1	0.89
{_}.E.2	0.63
{_}.E.3	0.33

*********** Node Summary *********** Node	Element	_		Maximum		External
ID	Туре	Elev	ation ft 	Elev. ft	Area ft²	Inflow
POCA POCB POCC	OUTFALL OUTFALL OUTFALL		33.53	32.77 33.53 32.41	0.00	
**************************************	Continuity	Volume acre-ft	-	Depth inches		
Total Precipitat Continuity Error		0.128 0.504		0.829		
**************************************	tinuity	Volume acre-ft		Volume allons		
External Inflow External Outflow Initial Stored V Final Stored Vol Continuity Error	olume ume	0.000 0.063 0.000 0.000 0.000		0.000 0.021 0.000 0.000		

Subbasin {_}.E.1

Soil/Surface Description	Area	Soil	Runoff
	(acres)	Group	Coeff.
-	0.89	D	0.50
Composite Area & Weighted Runoff Coeff.	0.89		0.50

0.50

Subbasin {_}.E.2

Soil/Surface Description	Area	Soil	Runoff
	(acres)	Group	Coeff.
-	0.63	D	0.50
Composite Area & Weighted Runoff Coeff.	0.63		0.50
Subbasin {_}.E.3			
Soil/Surface Description	Area	Soil	Runoff
	(acres)	Group	Coeff.
-	0.33	D	0.50

0.	
Composite Area & Weighted Runoff Coeff. 0	. 33

Sheet Flow Equation

 $Tc = (0.007 * ((n * Lf)^{0.8})) / ((P^{0.5}) * (Sf^{0.4}))$

Where:

Tc = Time of Concentration (hrs) n = Manning's Roughness Lf = Flow Length (ft) P = 2 yr, 24 hr Rainfall (inches) Sf = Slope (ft/ft)

Shallow Concentrated Flow Equation

V = 16.1345 * (Sf^0.5) (unpaved surface) V = 20.3282 * (Sf^0.5) (paved surface) V = 15.0 * (Sf^0.5) (grassed waterway surface)

```
V = 10.0 * (Sf^0.5) (nearly bare & untilled surface)
V = 9.0 * (Sf^0.5) (cultivated straight rows surface)
V = 7.0 * (Sf^0.5) (short grass pasture surface)
V = 5.0 * (Sf^0.5) (woodland surface)
V = 2.5 * (Sf^0.5) (forest w/heavy litter surface)
Tc = (Lf / V) / (3600 sec/hr)
```

Where:

Tc = Time of Concentration (hrs)
Lf = Flow Length (ft)
V = Velocity (ft/sec)
Sf = Slope (ft/ft)

Channel Flow Equation

V = (1.49 * (R^(2/3)) * (Sf^0.5)) / n R = Aq / Wp Tc = (Lf / V) / (3600 sec/hr)

Where:

Tc = Time of Concentration (hrs) Lf = Flow Length (ft) R = Hydraulic Radius (ft) Aq = Flow Area (ft²) Wp = Wetted Perimeter (ft) V = Velocity (ft/sec) Sf = Slope (ft/ft) n = Manning's Roughness

Subbasin {_}.E.1

Sheet Flow Computations

	Subarea A	Subarea B	Subarea C
Manning's Roughness:	0.40	0.00	0.00
Flow Length (ft):	71.83	0.00	0.00
Slope (%):	3.52	0.00	0.00
2 yr, 24 hr Rainfall (in):	1.75	0.00	0.00

		Existing	Q100.txt	
	Velocity (ft/sec):	0.07	0.00	0.00
	Computed Flow Time (minutes):	17.77	0.00	0.00
Shallow	Concentrated Flow Computations			
		Subarea A	Subarea B	Subarea C
	Flow Length (ft):	30.35	0.00	0.00
	Slope (%):	4.02	0.00	0.00
	Surface Type:	Grass pasture	Unpaved	Unpaved
	Velocity (ft/sec):	1.40	0.00	0.00
	Computed Flow Time (minutes):	0.36	0.00	0.00
Channel	l Flow Computations			
		Subarea A	Subarea B	Subarea C
	Manning's Roughness:	0.01	0.00	0.00
	Flow Length (ft):	583.57	0.00	0.00
	Channel Slope (%):	1.59	0.00	0.00
	Cross Section Area (ft ²):	2.00	0.00	0.00
	Wetted Perimeter (ft):	20.00	0.00	0.00
	Velocity (ft/sec):	2.70	0.00	0.00
	Computed Flow Time (minutes):	3.60	0.00	0.00
	Total TOC (minutes):	21.74	=======================================	

Sheet Flow Computations

	Subarea A	Subarea B	Subarea C
Manning's Roughness:	0.40	0.00	0.00
Flow Length (ft):	66.32	0.00	0.00
Slope (%):	3.92	0.00	0.00
2 yr, 24 hr Rainfall (in):	1.75	0.00	0.00
Velocity (ft/sec):	0.07	0.00	0.00
Computed Flow Time (minutes):	15.97	0.00	0.00

Shallow Concentrated Flow Computations

	Existing Q100.txt				
		Subarea A	Subarea B	Subarea C	
	Flow Length (ft):	165.52	0.00	0.00	
	Slope (%):	1.17	0.00	0.00	
	Surface Type:	Grass pasture	Unpaved	Unpaved	
	Velocity (ft/sec):	0.76	0.00	0.00	
	Computed Flow Time (minutes):	3.63	0.00	0.00	
Channel	l Flow Computations				
		Subarea A	Subarea B	Subarea C	
	Manning's Roughness:	0.01	0.00	0.00	
	Flow Length (ft):	409.57	0.00	0.00	
	Channel Slope (%):	2.18	0.00	0.00	
	Cross Section Area (ft ²):	0.31	0.00	0.00	
	Wetted Perimeter (ft):	1.91	0.00	0.00	
	Velocity (ft/sec):	4.36	0.00	0.00	
	Computed Flow Time (minutes):	1.56	0.00	0.00	
======	Total TOC (minutes):	21.17			

Subbasin {_}.E.3

Sheet Flow Computations

	Subarea A	Subarea B	Subarea C
Manning's Roughness:	0.40	0.00	0.00
Flow Length (ft):	37.00	0.00	0.00
Slope (%):	5.14	0.00	0.00
2 yr, 24 hr Rainfall (in):	1.75	0.00	0.00
Velocity (ft/sec):	0.07	0.00	0.00
Computed Flow Time (minutes):	8.99	0.00	0.00


Shallow Concentrated Flow Computations

	Subarea A	Subarea B	Subarea C
Flow Length (ft):	61.67	0.00	0.00
Slope (%):	3.34	0.00	0.00
Surface Type:	Grass pasture	Unpaved	Unpaved
Velocity (ft/sec):	1.28	0.00	0.00


	Existing	Q100.txt	
Computed Flow Time (minutes):	0.80	0.00	0.00
Channel Flow Computations			
	Subarea A	Subarea B	Subarea C
Manning's Roughness:	0.01	0.00	0.00
Flow Length (ft):	121.81	0.00	0.00
Channel Slope (%):	0.96	0.00	0.00
Cross Section Area (ft ²):	0.31	0.00	0.00
Wetted Perimeter (ft):	1.91	0.00	0.00
Velocity (ft/sec):	2.90	0.00	0.00
Computed Flow Time (minutes):	0.70	0.00	0.00
Total TOC (minutes):	10.49		

Subbasin ID	Accumulated Precip in	Rainfall Intensity in/hr	Total Runoff in	Peak Runoff cfs	Weighted Runoff Coeff	Conc days	Time of entration hh:mm:ss
{_}.E.1	0.88	2.44	0.44	1.09	0.500	0	00:21:44
{_}.E.2	0.88	2.48	0.44	0.78	0.500	0	00:21:10
{_}.E.3	0.60	3.42	0.30	0.56	0.500	0	00:10:29

Analysis began on: Thu Jun 29 10:02:08 2017 Analysis ended on: Thu Jun 29 10:02:08 2017 Total elapsed time: < 1 sec



PROPOSED



Q100 Proposed.txt

Autodesk[®] Storm and Sanitary Analysis 2015 - Version 9.1.140 (Build 1)

Project Description

File Name Post Developed-Condition_100yr.SPF
Description H:\1300\1305.20 - PFP Coastal Holdings Shasta East\Engineering\Reports\Drainage\1305.20
Existing DA's.dwg

Analysis Options *********

Flow Units cfs Subbasin Hydrograph Method. City of San Diego Rational Method Time of Concentration.... SCS TR-55 (5 minutes minimum) Return Period..... 100 years Storage Node Exfiltration. Constant flow Starting Date JUN-28-2017 00:00:00 Ending Date JUN-28-2017 01:00:00 Report Time Step 00:00:10

Subbasin Summary

Subbasin	Total
	Area
ID	acres
{_}.P.2	0.33
P.1	1.52

Node Summary *****						
Node	Element	I	nvert	Maximum	Ponded	External
ID	Туре	Elev	ation	Elev.	Area	Inflow
			ft	ft	ft²	
РОСВ	OUTFALL		 33.53		0.00	
POCC	OUTFALL		32.41		0.00	
r occ	OUTTALL		52.41	52.41	0.00	
************	*****	Volume		Depth		
Runoff Quantity	Continuity	acre-ft		inches		
************	*********		-			
Total Precipitat	tion	0.056		0.365		
Continuity Error	r (%)	0.306				
*****	*****	Volume		Volume		
Flow Routing Cor	ntinuity	acre-ft	Mc	gallons		
***********	•		ع، ، 			
External Inflow		0.000		0.000		
External Outflow	N	0.039		0.013		
Initial Stored \	/olume	0.000		0.000		
Final Stored Vol	lume	0.000		0.000		
Continuity Error		0.000				

Subbasin {_}.P.2

Soil/Surface Description	Area	Soil	Runoff
	(acres)	Group	Coeff.
-	0.33	D	0.70
Composite Area & Weighted Runoff Coeff.	0.33		0.70

Subbasin P.1

_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _

Soil/Surface Description	Area	Soil	Runoff
	(acres)	Group	Coeff.
-	1.52	-	0.70
Composite Area & Weighted Runoff Coeff.	1.52		0.70

SCS TR-55 Time of Concentration Computations Report

Sheet Flow Equation

 $Tc = (0.007 * ((n * Lf)^{0.8})) / ((P^{0.5}) * (Sf^{0.4}))$

Where:

Tc = Time of Concentration (hrs)
n = Manning's Roughness
Lf = Flow Length (ft)
P = 2 yr, 24 hr Rainfall (inches)
Sf = Slope (ft/ft)

Shallow Concentrated Flow Equation

V = 16.1345 * (Sf^0.5) (unpaved surface) V = 20.3282 * (Sf^0.5) (paved surface) V = 15.0 * (Sf^0.5) (grassed waterway surface) V = 10.0 * (Sf^0.5) (nearly bare & untilled surface) V = 9.0 * (Sf^0.5) (cultivated straight rows surface) V = 7.0 * (Sf^0.5) (short grass pasture surface) V = 5.0 * (Sf^0.5) (woodland surface) V = 2.5 * (Sf^0.5) (forest w/heavy litter surface) Tc = (Lf / V) / (3600 sec/hr)


Where:

Tc = Time of Concentration (hrs)
Lf = Flow Length (ft)


```
V = Velocity (ft/sec)
    Sf = Slope (ft/ft)
Channel Flow Equation
    V = (1.49 * (R^{(2/3)}) * (Sf^{0.5})) / n
    R = Aq / Wp
    Tc = (Lf / V) / (3600 sec/hr)
    Where:
    Tc = Time of Concentration (hrs)
    Lf = Flow Length (ft)
    R = Hydraulic Radius (ft)
    Aq = Flow Area (ft<sup>2</sup>)
    Wp = Wetted Perimeter (ft)
    V = Velocity (ft/sec)
    Sf = Slope (ft/ft)
    n = Manning's Roughness
 . . . . . . . . . . . . . . . . . . .
Subbasin {_}.P.2
Total TOC (minutes):
                              0.00
_____
-----
Subbasin P.1
_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _
Total TOC (minutes):
                              0.00
_____
******
Subbasin Runoff Summary
*******
Subbasin
     Accumulated
                 Rainfall
                         Total
                               Peak Weighted
                                              Time of
```

				Q100 Prop	posed.txt	
ID	Precip in	Intensity in/hr	Runoff in	Runoff cfs	Runoff Coeff	Concentration days hh:mm:ss
{_}.P.2	0.36	4.38	0.26	1.01	0.700	0 00:05:00
P.1	0.36	4.38	0.26	4.66	0.700	0 00:05:00

Analysis began on: Thu Jun 29 09:53:22 2017 Analysis ended on: Thu Jun 29 09:53:22 2017 Total elapsed time: < 1 sec








	Total Inflow Summary Table
Time period	
	Element ID POCB POCB
From: 06/28/2017, 12:00:00 AM	Maximum Total Inflow (cfs) 0.78 4.66
To: 06/28/2017, 01:00:10 AM	Minimum Total Inflow (cfs) 0.00 0.00
	Event Mean Total Inflow (cfs) 0.28 0.39
Thresholds	Duration of Exceedances (hrs) N/A N/A
Exceedance: 0	Duration of Deficits (hrs) N/A N/A
Deficit: 0	Number of Exceedances N/A N/A
	Number of Deficits N/A N/A
Detention storage	Volume of Exceedance (P) N/A N/A
Max flow: 0.78	Volume of Deficit (I®) N/A N/A
	Total Inflow Volume (IP) 992.61 1398.1
	Detention Storage (it) 1164.10





	Total Inflow Summary Table
Time period	
	Element ID POCC POCC
From: 06/28/2017, 12:00:00 AM	Maximum Total Inflow (cfs) 0.56 1.01
To: 06/28/2017, 01:00:10 AM	Minimum Total Inflow (cfs) 0.00 0.00
	Event Mean Total Inflow (cfs) 0.10 0.08
Thresholds	Duration of Exceedances (hrs) N/A N/A
Exceedance: 0	Duration of Deficits (hrs) N/A N/A
Deficit: 0	Number of Exceedances N/A N/A
	Number of Deficits N/A N/A
Detention storage	Volume of Exceedance (if?) N/A N/A
Max flow: 0.56	Volume of Deficit (I%) N/A N/A
0.00	Total Inflow Volume (ft) 355.37 303.53
	Detention Storage (it*) 135.53 135.53

WASTE MANAGEMENT PLAN

FOR

ECO BLöK Residences

PTS - 530514 3977 Shasta Street San Diego, CA 92109 PTS 530514

Prepared for: City of San Diego Environmental Services Dept. 9601 Ridgehaven Court, MS 1002-A San Diego, CA 92123

> Prepared by: Golba Architecture, Inc. 1940 Garnet Ave., Suite 100 San Diego, CA 92109 619.231.9905

> > August 22, 2017

PROJECT DESCRIPTION

The 1.64-acre *ECO BLöK Residences Project* site is located at 3977 Shasta Street, San Diego, California 92109, and consists of Lots 1 thru 24, Block 17, and Lots 1 thru 6, Block 27, Map 894 of San Diego County. The project proposes the removal of an existing assisted living complex, and the construction of 30 new single family homes on the existing 30 legal lots, with homes that average 1,750 square feet in size.

The project requires discretionary approval including: Coastal Development Permit, Site Development Permit, and Planned Development Permit.

The purpose of this Waste Management Plan (WMP) for the *ECO BLöK Residences Project - PTS 530514* in the City of San Diego is to provide analysis of the solid waste impacts anticipated and how those impacts will be mitigated. The goal of this WMP is to identify sufficient mitigation to reduce the potential impacts of the *ECO BLöK Residences Project* on solid waste services. Two acceptable approaches to managing waste are to reduce the tons disposed to 60 tons or less, or to provide diversion of 75 percent or more, thus meeting the goal established by Assembly Bill 341.

DEMOLITION WASTE

The project site is the location of an existing senior assisted living complex. The demolition phase will include the deconstruction/demolition and removal of 3 existing structures, asphalt parking and walkway areas, and interior landscape. Approximately 41.198 tons of waste is estimated to be generated during demolition. Approximately 39.538 tons of material would be recycled, to include trees, concrete, asphalt, foundations, building structure, masonry walls, curb and gutter, and switch gear and cable. Approximately 1.66 tons of debris would be disposed in a landfill, to include non-useable lumber, drywall, glass, miscellaneous trash, roofing paper, broken roof tiles, and floor tile.

Table 1, *ECO BLöK Residences Project Waste Generation - Demolition*, is included to summarize the type and amount of demolition materials, as well as diversion/disposal.

ECO BLOK Residences Project waste Generation - Demonition						
Material Type	Estimated Waste Quantity (tons)		Estimated Diversion (tons)	Estimated Disposal (tons)		
	CONSTRUCTION WASTE					
Asphalt and Concrete	12.30	Hanson Aggregates 9229 Harris Plant Road San Diego, CA 92126 (100% diversion)	12.30			

 Table 1

 ECO BLöK Residences Project Waste Generation - Demolition

		2		
Foundations/Building Structure	16.51	.51 Vulcan Carroll Canyon Landfill and Recycle Site 10051 Black Mountain Road San Diego, CA 92126 (100% diversion)		
Brick/Masonry/Tile	5.92	Vulcan Carroll Canyon Landfill and Recycle Site 10051 Black Mountain Road San Diego, CA 92126 (100% diversion)	5.92	
Curbs/Gutters	1.02	Vulcan Carroll Canyon Landfill and Recycle Site 10051 Black Mountain Road San Diego, CA 92126 (100% diversion)	1.02	
Switch Gear/Cable	.004	Vulcan Carroll Canyon Landfill and Recycle Site 10051 Black Mountain Road San Diego, CA 92126 (100% diversion)	.004	
Drywall	2.05	EDCO Station Transfer and Buy Back Center 8184 Commercial Street La Mesa, CA 91942 (70% diversion)	1.44	.61
Landscape Materials	1.23	Miramar Greenery 5180 Convoy Street San Diego, CA 92111 (100% diversion)	1.23	
Roofing Materials	1.02	LEED Recycling 8725 Miramar Place San Diego, CA 92121 (100% diversion)	1.02	
Floor Tile	.004	Otay C&D/Inert Debris Processing Facility 1700 Maxwell Road Chula Vista, CA 91913 (76% diversion)	.003	.001
Glass	.08	Otay C&D/Inert Debris Processing Facility 1700 Maxwell Road Chula Vista, CA 91913 (76% diversion)	.061	.019
Non-Useable Lumber	.04	Otay C&D/Inert Debris Processing Facility 1700 Maxwell Road Chula Vista, CA 91913 (76% diversion)	.03	.01
Garbage/Trash	1.02	Miramar Landfill 5180 Convoy Street San Diego, CA 92111 (0% diversion)		1.02
TOTAL	41.198		39.538	1.66

In accordance with State diversion targets, a minimum of 75 percent of construction materials will be recycled. Materials to be recycled would be redirected to appropriate recipients selected from ESD's directory of facilities that recycle demolition materials, scrap metal, and yard waste.

CONSTRUCTION WASTE

Construction activities would generate packaging materials and unpainted wood, including wood pallets, and other miscellaneous debris. Construction debris would be separated on-site into material-specific containers to facilitate reuse and recycling and to increase the efficiency of waste reclamation. Source separation of materials at the construction site is essential to (1) ensure appropriate waste diversion rate, (2) minimize costs associated with

2

transportation and disposal, and (3) facilitate compliance with the C&D ordinance. The types of construction waste anticipated to be generated include:

- Asphalt and Concrete
- Brick/Masonry/Tile
- Cardboard
- Carpet, Padding/Foam
- Drywall
- Landscape Debris
- Mixed C&D Debric
- Roofing Materials
- Scrap Metal
- Unpainted Wood and Pallets
- Garbage/Trash

In accordance with State diversion targets, a minimum of 75 percent of construction materials will be recycled. Materials to be recycled would be redirected to appropriate recipients selected from ESD's directory of facilities that recycle demolition materials, scrap metal, and yard waste.

MANAGING CONSTRUCTION MATERIAL

To facilitate management of construction materials, the developer shall identify one person or agency connected with the proposed development to act as Solid Waste Management Coordinator, whose responsibility it becomes to work with all contractors and subcontractors to ensure material separation and coordinate proper disposal and diversion of waste generated. The Solid Waste Management Coordinator will help to ensure all diversion practices outlined in this Waste Management Plan are upheld and communicate goals to all contractors involved efficiently. The responsibilities of the Solid Waste Management Coordinator, include, but are not limited to, the following:

- Review the Solid Waste Management Plan including responsibilities of Solid Waste Management Coordinator.
- Review and update procedures as needed for material separation and verify availability of containers and bins needed to avoid delays.
- Review and update procedures for periodic solid waste collection and transportation to recycling and disposing facilities.
- The authority to issue stop work orders if proper procedures are not being allowed.

The contractors will perform daily inspections of the construction site to ensure compliance with the requirements of the Waste Management Plan and all other applicable laws and ordinances and report directly to Solid Waste

Management Coordinator. Daily inspections will include verifying the availability and number of dumpsters based on amount of debris being generated, correct labeling of dumpsters, proper sorting and segregation materials, and salvaging of excess materials. Additionally, the following apply:

- Solid waste management coordinator will be responsible for educating contractors and subcontractors regarding waste management plan requirements and ensuring that contractors and subcontractors carry out the measures described in the WMP.
- Solid waste management coordinator will ensure ESD attendance at a Precon and assure compliance with segregation requirements, and verification of recycled content in base materials.
- Recycling areas will be clearly identified with large signs, approved by ESD, and sufficient amounts of material-specific bins will be provided for necessary segregation.
- Recycling bins will be placed in areas that are readily accessible to contractors/subcontractors and in areas that will minimize misuse or contamination by employees and the public.
- Solid waste management coordinator will be responsible for ensuring that contamination rates in bins remain below 5 percent by weight of the bin.

Table 2, *ECO BLöK Residences Project Waste Generation - Construction,* is included to summarize the types of waste generated, the amount of each waste type delivered, and the overall amount remaining to be disposed of in landfills.

ECO BLOK Residences Project Waste Generation - Construction						
	Estimated		Estimated	Estimated		
Material Type	Waste	ste Handling		Disposal		
	Quantity (tons)		(tons)	(tons)		
CONSTRUCTION WASTE						
Asphalt and Concrete	42.89	Hanson Aggregates 9229 Harris Plant Road San Diego, CA 92126 (100% diversion)	42.89			
Brick/Masonry/Tile	12.25	Vulcan Carroll Canyon Landfill and Recycle Site 10051 Black Mountain Road San Diego, CA 92126 (100% diversion)	12.25			
Cardboard	1.22	EDCO Station Transfer and Buy Back Center 8184 Commercial Street La Mesa, CA 91942 (70% diversion)	.85	.37		

 Table 2

 FCO BLöK Residences Project Waste Generation - Construction

		5		
Carpet, Padding/Foam	.61	DFS Flooring 10178 Willow Creek Road San Diego, CA 92131 (100% diversion)	.61	
Drywall	8.58	EDCO Station Transfer and Buy Back Center 8184 Commercial Street La Mesa, CA 91942 (70% diversion)	6.01	2.57
Landscape Debris	1.22	Miramar Greenery 5180 Convoy Street San Diego, CA 92111 (100% diversion)	1.22	
Mixed C&D Debris	36.76	Otay C&D/Inert Debris Processing Facility 1700 Maxwell Road Chula Vista, CA 91913 (76% diversion)	27.94	8.82
Roofing Materials	.61	LEED Recycling 8725 Miramar Place San Diego, CA 92121 (100% diversion)	.61	
Scrap Metal	3.06	EDCO Station Transfer and Buy Back Center 8184 Commercial Street La Mesa, CA 91942 (70% diversion)	2.14	.92
Unpainted Wood & Pallets	14.7	Miramar Greenery 5180 Convoy Street San Diego, CA 92111 (100% diversion)	14.7	
Garbage/Trash	.61	Miramar Landfill 5180 Convoy Street San Diego, CA 92111 (0% diversion)		.61
TOTAL	122.51		109.22	13.29

Б

OCCUPANCY WASTE

While the construction phase for the *ECO BLöK Residences Project* occurs as a onetime waste generation event as construction of the project proceeds, tenant/owner occupancy requires an on-going plan to manage waste disposal to meet the waste reduction goals established by the City and State. The *ECO BLöK Residences Project* will comply with the City's Recycling Ordinance.

In accord with the City's Conservation Element, *ECO BLöK Residences Project* seeks to reduce its "environmental footprint" through a variety of sustainable design features. The project would comply with the Uniform Building Code (UBC) and Title 24 requirements for building materials and insulation in order to reduce unnecessary loss of energy.

The project proposes to utilize portions of areas which are designated for landscaping or other softscape for Low Impact Development (LID) storm water treatment. Landscaped areas would be used in the treatment of runoff prior to entering the storm drain system. These LID BMPs would also function to slow down site runoff, increase times of concentration, improve downstream hydrologic conditions, and treat storm water as compared to the existing condition. These BMPs are extremely effective in creating a low impact site design concerning storm water management.

As a result of the recommended site design, source control measures, and treatment control measures, water quality exceedances are not anticipated, and pollutants are not expected within project runoff that would adversely affect beneficial uses in downstream receiving waters. The project would implement controls designed to limit discharges to the appropriate standard. The project complies with the requirements of the State Regional Water Quality Control Board concerning coverage under the General Construction Permit.

The proposed Landscape Concept Plan includes the use of indigenous and native material, whenever possible. Planting is intended to be a connecting device linking the various pieces of the project and design style. The Landscape Concept Plan emphasizes a garden setting, where plant material would be used to help define spaces, screen objectionable views, encourage circulation paths, highlight entry points, and provide softness and scale to the architecture. Evergreen, deciduous, and flowering material are proposed throughout the project. Located adjacent to open space slopes, the perimeter planting is proposed as a blend of native material and native friendly fire safe planting.

Circulation throughout the project is accentuated with a hierarchy of landscape treatments. Enhanced paving at major intersections and nodes is proposed to signify pedestrian/vehicle interaction areas. Vehicle nodes with small medians are proposed to help slow the traffic flow, as well as break up long linear drives. Street trees are proposed to define vehicle/pedestrian spaces and to provide shade and scale to the street scene. Entry points would be highlighted with decorative trellis work and enhanced plantings.

IMPLEMENTATION

As shown in Table 3, *Estimated Waste Generation from the ECO BLöK Residences Project - Occupancy Phase*, during occupancy, the expected generated waste per year from the *ECO BLöK Residences Project* when fully occupied would be approximately 2.67 tons per single family residence.

 Table 3

 Estimated Waste Generation from the ECO BLöK Residences Project - Occupancy Phase

 Per Single-Family Home

i el enigle i anni j neme				
Use	Intensity (square feet)	Waste Generation Rate	Estimated Waste	
		(tons/year/sq.ft.)	Generated (tons/year)	
Single Family Residential	1,780	.0015	2.67	
		Total	2.67	

In contrast, as shown in Table 4, *Estimated Waste Generation from the Existing Use as an Assisted Living Complex - Occupancy Phase,* during occupancy, the expected generated waste per year from the existing site use as an assisted living complex when fully occupied is approximately 16.18 tons.

 Table 4

 Estimated Waste Generation from the Existing Use as an Assisted Living Complex - Occupancy

 Phase

Thase the second s				
Use	Intensity (square feet)	Waste Generation Rate	Estimated Waste	
		(tons/year/sq.ft.)	Generated (tons/year)	
Assisted Living Complex	10,785	.0015	16.18	
	16.18			

On-site recycling services shall be provided to all residents within the *ECO BLöK Residences Project*. Residents within *ECO BLöK Residences Project* that receive solid waste collection service shall participate in a recycling program by separating recyclable materials from other solid waste and depositing the recyclable materials in the recycling container provided for the occupants. Recycling services are required by Section 66.0707 of the City of San Diego Land Development Code. Based on current requirements, these services shall include the following:

- Collection of recyclable materials as frequently as necessary to meet demand;
- Collection of plastic bottles and jars, paper, newspaper, metal containers, cardboard, and glass containers;
- Collection of other recyclable materials for which markets exist, such as scrap metal, wood pallets
- Use of recycling receptacles or containers which comply with the standards in the Container and Signage Guidelines established by the City of San Diego Environmental Services Department;
- Designated recycling collection and storage areas; and
- Signage on all recycling receptacles, containers, chutes, and/or enclosures which complies with the standards described in the Container and Signage Guidelines established by the City of San Diego Environmental Services Department

As required by Section 66.0707 of the City of San Diego Land Development Code, the building management or other designated personnel shall ensure that occupants are educated about the recycling services as follows:

• Information, including the types of recyclable materials accepted, the location of recycling containers, and the occupants responsibility to recycle shall be distributed to all occupants annually;

- All new occupants shall be given information and instructions upon occupancy; and
- All occupants shall be given information and instructions upon any change in recycling service to the commercial facility.

LANDSCAPE AND GREEN WASTE RECYCLING

Plant material selection will be guided by the macro-and micro-climate characteristics of the project site and surrounding region to encourage long-term sustainability without the excessive use of water pesticides and fertilizers. Irrigation of these areas, where practical, will utilize reclaimed water applied via low precipitation rate spray heads, drip emitters, or other highly efficient systems. Landscape maintenance would include the collection of green waste and disposal of green waste at recycling centers that accept green waste. This will help further reduce the waste generated by developments within the *ECO BLöK Residences Project* during the occupancy phases.

CONCLUSION

The City of San Diego Development Services Department is requiring that this Preliminary WMP be prepared and submitted to the City of San Diego's ESD. Since the project is in the design phase, this is only a preliminary plan, which specifies the intent to meet the requirements of PRC 939 and City ordinances. Prior to the issuance of any permits for construction within each neighborhood of *ECO BLöK Residences Project*, final reports will be submitted to ESD for final review and approval.

This Preliminary WMP will be implemented to the fullest degree of accuracy and efficiency. Additionally, the project will be required to adhere to City ordinances, including the Construction and Demolition Debris Diversion Deposit Program, the City's Recycling Ordinance, and the Refuse and Recyclable Materials Storages Regulations. The WMP plan for the *ECO BLöK Residences Project* is designed to implement and adhere to all city ordnance and regulations with regards to waste management. The measures in the WMP would ensure that impacts are mitigated to below a level of significance.



PRIORITY DEVELOPMENT PROJECT (PDP) FILNAL STORM WATER QUALITY MANAGEMENT PLAN (SWQMP) FOR

ECO BLÖK HOMES

PTS# 530514


ENGINEER OF WORK:

Giovanni Posillico, RCE 66332

PREPARED FOR:

Pathfinder Crown Point Apartments, LLC 4380 La Jolla Village Dr. Suite 250 San Diego, CA 92122 (858) 875-4450

PREPARED BY:



Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor San Diego, CA 92131 (858) 751-0633

> DATE: JUNE 2017

Approved by: City of San Diego

Date

Eco Blök Homes PTS# 530514 June 2017





TABLE OF CONTENTS

- Acronyms
- Certification Page
- Submittal Record
- Project Vicinity Map
- FORM DS-560: Storm Water Applicability Checklist
- FORM I-1: Applicability of Permanent, Post-Construction Storm Water BMP Requirements
- FORM I-3B: Site Information Checklist for PDPs
- FORM I-4: Source Control BMP Checklist for All Development Projects
- FORM I-5: Site Design BMP Checklist for All Development Projects
- FORM I-6: Summary of PDP Structural BMPs
- FORM DS-563: Permanent BMP Construction, Self Certification Form
- Attachment 1: Backup for PDP Pollutant Control BMPs
 - Attachment 1a: DMA Exhibit
 - o Attachment 1b: Tabular Summary of DMAs and Design Capture Volume Calculations
 - Attachment 1c: Harvest and Use Feasibility Screening (when applicable)
 - o Attachment 1d: Categorization of Infiltration Feasibility Condition (when applicable)
 - o Attachment 1e: Pollutant Control BMP Design Worksheets / Calculations
- Attachment 2: Backup for PDP Hydromodification Control Measures
 - o Attachment 2a: Hydromodification Management Exhibit
 - o Attachment 2b: Management of Critical Coarse Sediment Yield Areas
 - o Attachment 2c: Geomorphic Assessment of Receiving Channels
 - o Attachment 2d: Flow Control Facility Design
- Attachment 3: Structural BMP Maintenance Plan
 - Attachment 3a: Structural BMP Maintenance Thresholds and Actions
 - Attachment 3b: Draft Maintenance Agreement (when applicable)
- Attachment 4: Copy of Plan Sheets Showing Permanent Storm Water BMPs
- Attachment 5: Project's Drainage Report
- Attachment 6: Project's Geotechnical and Groundwater Investigation Report





ACRONYMS

APN	Assessor's Parcel Number
ASBS	Area of Special Biological Significance
BMP	Best Management Practice
CEQA	California Environmental Quality Act
CGP	Construction General Permit
DCV	Design Capture Volume
DMA	Drainage Management Areas
ESA	Environmentally Sensitive Area
GLU	Geomorphic Landscape Unit
GW	Ground Water
HMP	Hydromodification Management Plan
HSG	Hydrologic Soil Group
HU	Harvest and Use
INF	Infiltration
LID	Low Impact Development
LUP	Linear Underground/Overhead Projects
MS4	Municipal Separate Storm Sewer System
N/A	Not Applicable
NPDES	National Pollutant Discharge Elimination System
NRCS	Natural Resources Conservation Service
PDP	Priority Development Project
PE	Professional Engineer
POC	Pollutant of Concern
SC	Source Control
SD	Site Design
SDRWQCB	San Diego Regional Water Quality Control Board
SIC	Standard Industrial Classification
SWPPP	Stormwater Pollutant Protection Plan
SWQMP	Storm Water Quality Management Plan
TMDL	Total Maximum Daily Load
WMAA	Watershed Management Area Analysis
WPCP	Water Pollution Control Program
WQIP	Water Quality Improvement Plan
···	1 1 1 1 1 1 1 1 1 1





CERTIFICATION PAGE

Project Name: Eco Blök Homes Permit Application Number: PTS# 530514

I hereby declare that I am the Engineer in Responsible Charge of design of storm water BMPs for this project, and that I have exercised responsible charge over the design of the project as defined in Section 6703 of the Business and Professions Code, and that the design is consistent with the requirements of the Storm Water Standards, which is based on the requirements of SDRWQCB Order No. R9-2013-0001 as amended by R9-2015-0001 and R9-2015-0100 (MS4 Permit).

I have read and understand that the City Engineer has adopted minimum requirements for managing urban runoff, including storm water, from land development activities, as described in the Storm Water Standards. I certify that this PDP SWQMP has been completed to the best of my ability and accurately reflects the project being proposed and the applicable source control and site design BMPs proposed to minimize the potentially negative impacts of this project's land development activities on water quality. I understand and acknowledge that the plan check review of this PDP SWQMP by the City Engineer is confined to a review and does not relieve me, as the Engineer in Responsible Charge of design of storm water BMPs for this project, of my responsibilities for project design.


License Number 66332, Expires - 06/30/2018

Engineer of Work's Signature, PE Number & Expiration Date

Giovanni Posillico Print Name

Latitude 33 Planning & Engineering Company

Date







SUBMITTAL RECORD

Use this Table to keep a record of submittals of this PDP SWQMP. Each time the PDP SWQMP is re-submitted, provide the date and status of the project. In last column indicate changes that have been made or indicate if response to plan check comments is included. When applicable, insert response to plan check comments.


Submittal Number	Date	Project Status	Changes
1	11/2016	⊠ Preliminary Design/Planning/CEQA □ Final Design	Initial Submittal
2	5/2017	⊠ Preliminary Design/Planning/CEQA □ Final Design	Second Submittal
3	7/2017	⊠ Preliminary Design/Planning/CEQA □ Final Design	Third Submittal





PROJECT VICINITY MAP

Project Name: Eco Blök Homes Permit Application Number: PTS# 530514



NO SCALE





STORM WATER REQUIREMENTS APPLICABILITY CHECKLIST

Complete and attach DS-560 Form included in Appendix A.1



City of San Diego	FORM
Development Services Storm Water Requirements	DS-560
	D2-200
Applicability Checklist	October 2016
Project Address: 1765 Fortuna Avenue, 3977 Shasta Street, 1750 Roosevelt Avenue, San Diego, CA 92109 & Project Number (fo	r City Use Only):
SECTION 1. Construction Storm Water BMP Requirements:	
All construction sites are required to implement construction BMPs in accordance with the performa	ince standards
in the <u>Storm Water Standards Manual</u> . Some sites are additionally required to obtain coverage u Construction General Permit (CGP) ¹ , which is administered by the State Water Resources Control B	oard.
For all projects complete PART A: If project is required to submit a SWPPP or WPCP, PART B.	
PART A: Determine Construction Phase Storm Water Requirements.	
 Is the project subject to California's statewide General NPDES permit for Storm Water Discharges with Construction Activities, also known as the State Construction General Permit (CGP)? (Typicall land disturbance greater than or equal to 1 acre.) 	Associated y projects with
X Yes; SWPPP required, skip questions 2-4 🔲 No; next question	
2. Does the project propose construction or demolition activity, including but not limited to, clearing grubbing, excavation, or any other activity resulting in ground disturbance and contact with storn	g, grading, n water runoff?
Yes; WPCP required, skip 3-4 🔲 No; next question	
3. Does the project propose routine maintenance to maintain original line and grade, hydraulic capa nal purpose of the facility? (Projects such as pipeline/utility replacement)	acity, or origi-
Yes; WPCP required, skip 4 No; next question	
4. Does the project only include the following Permit types listed below?	-
 Electrical Permit, Fire Alarm Permit, Fire Sprinkler Permit, Plumbing Permit, Sign Permit, Mecha Spa Permit. 	nical Permit,
 Individual Right of Way Permits that exclusively include only ONE of the following activities: wa sewer lateral, or utility service. 	
 Right of Way Permits with a project footprint less than 150 linear feet that exclusively include of the following activities: curb ramp, sidewalk and driveway apron replacement, pot holing, curb replacement, and retaining wall encroachments. 	
Yes; no document required	
Check one of the boxes below, and continue to PART B:	
If you checked "Yes" for question 1, a SWPPP is REQUIRED. Continue to PART B	
If you checked "No" for question 1, and checked "Yes" for question 2 or 3, a WPCP is REQUIRED. If the project proposes less than 5,000 square feet of ground disturbance AND has less than a 5-foot elevation change over the entire project area, a Minor WPCP may be required instead. Continue to PART B.	
If you checked "No" for all questions 1-3, and checked "Yes" for question 4 PART B does not apply and no document is required. Continue to Section 2.	
1. More information on the City's construction BMP requirements as well as CGP requirements can be found at: www.sandlego.gov/stormwater/regulations/index.shtml	
Printed on recycled paper. Visit our web site at <u>www.sandiego.gov/development-services</u> .	
Upon request, this information is available in alternative formats for persons with disabilities. DS-560 (10-16)	

Page 2 of	4 City of San Diego • Development Services • Storm Water Requirements Applicability Checklist
PART B:	Determine Construction Site Priority
The city r projects a City has a State Cor and recei nificance	itization must be completed within this form, noted on the plans, and included in the SWPPP or WPCP eserves the right to adjust the priority of projects both before and after construction. Construction re assigned an inspection frequency based on if the project has a "high threat to water quality." The ligned the local definition of "high threat to water quality" to the risk determination approach of the struction General Permit (CGP). The CGP determines risk level based on project specific sediment risk ving water risk. Additional inspection is required for projects within the Areas of Special Biological Sig- (ASBS) watershed. NOTE: The construction priority does NOT change construction BMP requirements v to projects; rather, it determines the frequency of inspections that will be conducted by city staff.
Complet	e PART B and continued to Section 2
1.	ASBS
	a. Projects located in the ASBS watershed.
2. 🗵	High Priority
	a. Projects 1 acre or more determined to be Risk Level 2 or Risk Level 3 per the Construction General Permit and not located in the ASBS watershed.
	b. Projects 1 acre or more determined to be LUP Type 2 or LUP Type 3 per the Construction General Permit and not located in the ASBS watershed.
3.	Medium Priority
	a. Projects 1 acre or more but not subject to an ASBS or high priority designation.
	b. Projects determined to be Risk Level 1 or LUP Type 1 per the Construction General Permit and not located in the ASBS watershed.
	Low Priority
. <u>[</u>	
. <u>[</u>]	a. Projects requiring a Water Pollution Control Plan but not subject to ASBS, high, or medium priority designation.
	 a. Projects requiring a Water Pollution Control Plan but not subject to ASBS, high, or medium priority designation. 2. Permanent Storm Water BMP Requirements.

Projects that are considered maintenance, or otherwise not categorized as "new development projects" or "redevelopment projects" according to the <u>Storm Water Standards Manual</u> are not subject to Permanent Storm Water BMPs.

If "yes" is checked for any number in Part C, proceed to Part F and check "Not Subject to Permanent Storm Water BMP Requirements".

If "no" is checked for all	of the numbers in	Part C continue t	o Part D
----------------------------	-------------------	-------------------	----------

1.	Does the project only include interior remodels and/or is the project entirely within an existing enclosed structure and does not have the potential to contact storm water?	Yes	X No
2.	Does the project only include the construction of overhead or underground utilities without creating new impervious surfaces?	🗌 Yes	X No
3.	Does the project fall under routine maintenance? Examples include, but are not limited to: roof or exterior structure surface replacement, resurfacing or reconfiguring surface parking lots or existing roadways without expanding the impervious footprint, and routine replacement of damaged pavement (grinding, overlay, and pothole repair).	Yes	× No

Cit	y of San Diego • Development Services • Storm Water Requirements Applicability Checklist Page 3	3 of 4	
PA	RT D: PDP Exempt Requirements.		
P	PDP Exempt projects are required to implement site design and source control BMPs.		
	"yes" was checked for any questions in Part D, continue to Part F and check the b 'DP Exempt."	ox labeled	
lf	"no" was checked for all questions in Part D, continue to Part E.		
1.	Does the project ONLY include new or retrofit sidewalks, bicycle lanes, or trails that:		
	 Are designed and constructed to direct storm water runoff to adjacent vegetated area non-erodible permeable areas? Or; 	as, or other	
	 Are designed and constructed to be hydraulically disconnected from paved streets an 	· ·	
	 Are designed and constructed with permeable pavements or surfaces in accordance w Green Streets guidance in the City's Storm Water Standards manual? 	vith the	
	Yes; PDP exempt requirements apply		
2.	Does the project ONLY include retrofitting or redeveloping existing paved alleys, streets or roa and constructed in accordance with the Green Streets guidance in the <u>City's Storm Water Stan</u>	ds designed dards Manual?	
	Yes; PDP exempt requirements apply 🛛 🔀 No; project not exempt.		
Pr a S If or If	ART E: Determine if Project is a Priority Development Project (PDP). ojects that match one of the definitions below are subject to additional requirements including p Storm Water Quality Management Plan (SWQMP). "yes" is checked for any number in PART E, continue to PART F and check the box "ity Development Project". "no" is checked for every number in PART E, continue to PART F and check the box tandard Development Project".	labeled "Pri-	
1.	New Development that creates 10,000 square feet or more of impervious surfaces collectively over the project site. This includes commercial, industrial, residential, mixed-use, and public development projects on public or private land.	Yes 🗵 No	
2.	Redevelopment project that creates and/or replaces 5,000 square feet or more of impervious surfaces on an existing site of 10,000 square feet or more of impervious surfaces. This includes commercial, industrial, residential, mixed-use, and public development projects on public or private land.	🛛 Yes 🗖 No	
3.	New development or redevelopment of a restaurant. Facilities that sell prepared foods and drinks for consumption, including stationary lunch counters and refreshment stands sellir prepared foods and drinks for immediate consumption (SIC 5812), and where the land development creates and/or replace 5,000 square feet or more of impervious surface.	ng Yes 🗵 No	
4.	New development or redevelopment on a hillside. The project creates and/or replaces 5,000 square feet or more of impervious surface (collectively over the project site) and where the development will grade on any natural slope that is twenty-five percent or greater.	🗌 Yes 🗵 No	
5,	New development or redevelopment of a parking lot that creates and/or replaces 5,000 square feet or more of impervious surface (collectively over the project site).	□Yes ⊠No	
6.	New development or redevelopment of streets, roads, highways, freeways, and driveways. The project creates and/or replaces 5,000 square feet or more of impervious surface (collectively over the project site).	🗆 Yes 🗵 No	
	•		
		1	

Page 4 of 4 City of San Diego • Development Services • Storm Water Requirements Applicability Checklist		
7. New development or redevelopment discharging directly Sensitive Area. The project creates and/or replaces 2,500 sq (collectively over project site), and discharges directly to an Er Area (ESA). "Discharging directly to" includes flow that is conver- feet or less from the project to the ESA, or conveyed in a pipe as an isolated flow from the project to the ESA (i.e. not comm lands).	uare feet of impervious surface nvironmentally Sensitive eyed overland a distance of 200 or open channel any distance	□Yes ⊠No
8. New development or redevelopment projects of a retail g create and/or replaces 5,000 square feet of impervious su project meets the following criteria: (a) 5,000 square feet or m Average Daily Traffic (ADT) of 100 or more vehicles per day.	irface. The development	Yes 🗵 No
 New development or redevelopment projects of an autor creates and/or replaces 5,000 square feet or more of impor projects categorized in any one of Standard Industrial Classifi 5541, 7532-7534, or 7536-7539. 	ervious surfaces. Development	Yes 🛛 No
10. Other Pollutant Generating Project. The project is not cover results in the disturbance of one or more acres of land and is post construction, such as fertilizers and pesticides. This doe less than 5,000 sf of impervious surface and where added lan use of pesticides and fertilizers, such as slope stabilization us the square footage of impervious surface need not include lin vehicle use, such as emergency maintenance access or bicycle with pervious surfaces of if they sheet flow to surrounding pe	expected to generate pollutants s not include projects creating dscaping does not require regula ing native plants. Calculation of near pathways that are for infreq e pedestrian use, if they are built	ar uent
PART F: Select the appropriate category based on the o	-	PART E.
1. The project is NOT SUBJECT TO PERMANENT STORM WATE	R REQUIREMENTS.	
 The project is a STANDARD DEVELOPMENT PROJECT. Site d BMP requirements apply. See the <u>Storm Water Standards M</u> 	lesign and source control <u>anual</u> for guidance.	
3. The project is PDP EXEMPT . Site design and source control E See the <u>Storm Water Standards Manual</u> for guidance.	3MP requirements apply.	
 The project is a PRIORITY DEVELOPMENT PROJECT. Site des structural pollutant control BMP requirements apply. See the for guidance on determining if project requires a hydromodir 	e <u>Storm Water Standards Manua</u>	
Melanie Foronda	Designer	
Name of Owner or Agent (Please Print)	Title	
Signature	05/16/2017 Date	

THIS PAGE INTENTIONALLY LEFT BLANK



irements struction requirements ts, in some cases re- struction requirement ts, in some cases re- struction reference er Progressi Go to Step Stop. Permanent apply. No Provide c	
Date: irements itruction requirements itruction requirements ts, in some cases re- hrough each step us arate forms reference reference reference Stop. Permanen- apply. No Provide c	ents that apply to the project efferencing separate forms that until reaching "Stop". ced in each step below. on ep 2. nt BMP requirements do no o SWQMP will be required discussion below.
irements struction requirements ts, in some cases re- struction requirement ts, in some cases re- struction reference er Progressi Go to Step Stop. Permanent apply. No Provide c	ents that apply to the project efferencing separate forms that until reaching "Stop". ced in each step below. on ep 2. nt BMP requirements do no o SWQMP will be required discussion below.
irements struction requirements ts, in some cases re- struction requirement ts, in some cases re- struction reference er Progressi Go to Step Stop. Permanent apply. No Provide c	ents that apply to the project efferencing separate forms that until reaching "Stop". ced in each step below. on ep 2. nt BMP requirements do no o SWQMP will be required discussion below.
truction requirements, in some cases re- hrough each step ut arate forms reference references Go to Step Stop. Permanent apply. No Provide c	eferencing separate forms that intil reaching "Stop". ced in each step below. on ep 2. nt BMP requirements do no o SWQMP will be required discussion below.
er Progressi Go to Ste Stop. Permaner apply. No Provide d	on ep 2. nt BMP requirements do no o SWQMP will be required liscussion below.
Go to Ste Stop. Permaner apply. No Provide c	ep 2. nt BMP requirements do no o SWQMP will be required liscussion below.
Stop. Permaner apply. No Provide d	nt BMP requirements do no o SWQMP will be required liscussion below.
Permaner apply. No Provide c	o SWQMP will be required liscussion below.
project" (e.g., the f	project includes <u>only</u> interior
ndard Stop.	
1	Project requirements apply.
	uirements apply, including
	-
P Stop. P Standard Provide d	Project requirements apply. liscussion and list any l requirements below.
1	t Standard PDP req PDP SW Go to Standard Stop. P Standard pt Provide o



Step	I-1 Page 2	
	Answer	Progression
Step 3. Is the project subject to earlier PDP requirements due to a prior lawful approval? See Section 1.10 of the BMP Design Manual (Part 1 of Storm Water Standards) for guidance.	□ Yes	Consult the City Engineer to determine requirements. Provide discussion and identify requirements below. Go to Step 4.
	🖾 No	BMP Design Manual PDP requirements apply. Go to Step 4.
Discussion / justification of prior lawful approval, an <u>approval does not apply</u>):	d identify requi	rements (<u>not required if prior lawful</u>
Step 4. Do hydromodification control requirements apply? See Section 1.6 of the BMP Design Manual (Part 1 of Storm Water Standards) for guidance.	The Yes	PDP structural BMPs required for pollutant control (Chapter 5) and hydromodification control (Chapter 6). Go to Step 5.
	⊠ No	Stop. PDP structural BMPs required for pollutant control (Chapter 5) only. Provide brief discussion of exemption to hydromodification control below.
Discussion / justification if hydromodification contro This project is not subject to Hydromodification requ Manual. This project discharges to storm drains whice	irements set for	rth by Section 1.6 of the BMP Design
Step 5. Does protection of critical coarse sediment yield areas apply? See Section 6.2 of the BMP Design Manual (Part 1 of Storm Water Standards) for guidance.	Tes Yes	Management measures required for protection of critical coarse sediment yield areas (Chapter 6.2). Stop.

Site Information Checklist For PDPs Form I-3B		
Project Sum	mary Information	
Project Name	Eco Blök Homes	
Project Address	1765 Fortuna Ave. San Diego, CA 92109 3977 Shasta St. San Diego, CA 92109 1750 Roosevelt Ave. San Diego, CA 92109 Vacant lot at the southeast corner of Roosevelt Ave and Shasta St.	
Assessor's Parcel Number(s) (APN(s))	424-482-14 424-532-25	
Permit Application Number	PTS# 530514	
Project Watershed	Select One: San Dieguito River Penasquitos Mission Bay San Diego River San Diego Bay Tijuana River	
Hydrologic subarea name with Numeric Identifier up to two decimal places (9XX.XX)	906.30 Scripps Hydrology Area	
Project Area (total area of Assessor's Parcel(s) associated with the project or total area of the right-of-way)	1.64 Acres (71,260 ft ²)	
Area to be disturbed by the project (Project Footprint)	1.64 Acres (71,260 ft ²)	
Project Proposed Impervious Area (subset of Project Footprint)	1.30 Acres (56,699ft ²)	
Project Proposed Pervious Area (subset of Project Footprint)	0.34 Acres (14,561 ft ²)	
Note: Proposed Impervious Area + Proposed Pervio This may be less than the Project Area.	bus Area = Area to be Disturbed by the Project.	
The proposed increase or decrease in impervious area in the proposed condition as compared to the pre-project condition.	62% Increase	



Form I-3B Page 2 of 11
Description of Existing Site Condition and Drainage Patterns
Current Status of the Site (select all that apply): Existing development Previously graded but not built out
☐ Agricultural or other non-impervious use ☐ Vacant, undeveloped/natural Description / Additional Information:
The site is previously developed with three existing buildings, landscaping and sidewalks.
Existing Land Cover Includes (select all that apply):
 □ Non-Vegetated Pervious Areas ⊠ Impervious Areas Description / Additional Information:
The site is previously developed with three existing buildings, landscaping and sidewalks.
Underlying Soil belongs to Hydrologic Soil Group (select all that apply): ⊠ NRCS Type A
□ NRCS Type B □ NRCS Type C □ NRCS Type D
Approximate Depth to Groundwater (GW):
$\Box 5 \text{ feet} < \text{GW Depth} < 10 \text{ feet}$ $\Box 10 \text{ feet} < \text{GW Depth} < 20 \text{ feet}$
\boxtimes GW Depth > 20 feet
Existing Natural Hydrologic Features (select all that apply):
□ Seeps □ Springs □ W(stheads
□ Wetlands ⊠ None Description / Additional Information:
The subject site does not include any Natural Hydrologic Features.



Form I-3B Page 3 of 11

Description of Existing Site Topography and Drainage:

How is storm water runoff conveyed from the site? At a minimum, this description should answer:

- 1. Whether existing drainage conveyance is natural or urban;
- 2. If runoff from offsite is conveyed through the site? If yes, quantification of all offsite drainage areas, design flows, and locations where offsite flows enter the project site and summarize how such flows are conveyed through the site;
- 3. Provide details regarding existing project site drainage conveyance network, including storm drains, concrete channels, swales, detention facilities, storm water treatment facilities, and natural and constructed channels;
- 4. Identify all discharge locations from the existing project along with a summary of the conveyance system size and capacity for each of the discharge locations. Provide summary of the pre-project drainage areas and design flows to each of the existing runoff discharge locations.

Description / Additional Information:

The existing site drainage is divided into three basins. The east side of the project (basin 1) drains to the southeast corner of the site and discharges to the private alley until it meets Roosevelt Avenue. The west side of the project (basin 2) drains to the southwest corner of the site and discharges southerly to curb and gutter along Shasta Avenue and converges with the discharge from basin 1 at Roosevelt Avenue. The southernmost portion of the project (basin 3) drains to the southeast corner of Roosevelt Avenue and Shasta Street. All of the storm water runoff from the project site then flows west down Roosevelt Avenue via curb and gutter where it finally comes together at the corner of Roosevelt Avenue and Jewel Street. From there the entire project's runoff flows via curb and gutter to an existing inlet located 550 feet south at the corner of Jewell Street and La Playa Avenue. Storm water then is conveyed via storm drain to Mission Bay.



|--|

Description of Proposed Site Development and Drainage Patterns

Project Description / Proposed Land Use and/or Activities:

The proposed project will disturb 1.64 acres and consists of sidewalk, landscaping and infiltration basins in addition to 30 single family row homes. The onsite storm water will be treated by infiltration basin BMPs throughout the site and will follow similar flow patterns as the existing condition. The site will outfall to Shasta Street via curb and gutter 1,050 feet south to the existing storm drain inlet located at the corner of Jewell Street and La Playa Avenue. Strom water is then conveyed via storm drain pipes to Mission Bay. The drainage areas have been designed to maintain the overall drainage design and the storm water discharges to the same inlet at the corner of Jewell Street and La Playa Avenue.

List/describe proposed impervious features of the project (e.g., buildings, roadways, parking lots, courtyards, athletic courts, other impervious features):

Project impervious features include the following:

- Concrete sidewalk
- Single Family Homes

List/describe proposed pervious features of the project (e.g., landscape areas):

Project pervious features include the following:

- Landscaped Area
- Infiltration Basins

Does the project include grading and changes to site topography? ⊠ Yes

□ No

Description / Additional Information:

There will be a minor amount of grading for buildings and landscaped areas.





Form I-3B Page 5 of 11

Does the project include changes to site drainage (e.g., installation of new storm water conveyance systems)? Xes

🗆 No

If yes, provide details regarding the proposed project site drainage conveyance network, including storm drains, concrete channels, swales, detention facilities, storm water treatment facilities, natural and constructed channels, and the method for conveying offsite flows through or around the proposed project site. Identify all discharge locations from the proposed project site along with a summary of the conveyance system size and capacity for each of the discharge locations. Provide a summary of pre and post-project drainage areas and design flows to each of the runoff discharge locations. Reference the drainage study for detailed calculations.

Description / Additional Information:

The proposed project will add atrium landscape drains to convey storm water to the water treatment facilities. This conveyance system captures and directs the storm water runoff to infiltration basin BMPs. The treatment control BMPs for the Eco Blök Homes are infiltration basins designed using BMP fact sheet E.9 from the City of San Diego BMP Design Manual Appendix. See infiltration basin detail on sheet C-2.

For flows that are associated with water quality treatment, infiltration basins will be provided on each lot. To regulate flows larger than the water quality demand the full infiltration BMPs are fitted with overflow structures and sidewalk underdrains. These overflow systems will direct the runoff to Shasta Street. Please refer to the drainage report for a more detailed description of the flood control measures that have been put into place and their associated calculations.



Form I-3B Page 6 of 11
Identify whether any of the following features, activities, and/or pollutant source areas will be present (select
all that apply):
On-site storm drain inlets
□ Interior floor drains and elevator shaft sump pumps
Interior parking garages
□ Need for future indoor & structural pest control
⊠ Landscape/Outdoor Pesticide Use
□ Pools, spas, ponds, decorative fountains, and other water features
□ Food service
□ Refuse areas
Industrial processes
Outdoor storage of equipment or materials
□ Vehicle and Equipment Cleaning
□ Vehicle/Equipment Repair and Maintenance
Fuel Dispensing Areas
Fire Sprinkler Test Water
Miscellaneous Drain or Wash Water
☐ Plazas, sidewalks, and parking lots
Large Trash Generating Facilities
Animal Facilities
Plant Nurseries and Garden Centers
Automotive-related Uses

Description / Additional Information:



	Fo	orm	I-3	BB I	Pag	e 7	of 1	1									
Identif	icatio	on ar	nd N	arra	tive	of R	ecei	ving	Wat	er							
Narrative describing flow path from di creeks, rivers, and lagoons and ultima as applicable)																	
The proposed flow path is very similar Shasta Street. The water on Shasta stre then travel via curb and gutter to the an existing drainage inlet. This storm of	eet w	vill tr er of	avel Jew	via rell S	curb tree	and t and	gut I La	ter s Play	outh ra Av	i to l venu	Roos le wł	sevel nere	lt Av it wi	re. T ll be	he w	vater	will
Provide a summary of all beneficial us	es of	rece	ivin	g wa	ters	dow	nstr	eam	of t	he p	rojeo	t dis	schar	ge lo	ocati	ons.	
 Existing Beneficial Use Potential Beneficial Use Except from Municipal Use Beneficial use is impaired based on the 2010 303(d) list 									cial (,			0			
Receiving Water (Hydrologic Unit Code)	M U N	I N D	R E C 1	R E C 2	B I O L	W A R M	W I L D	R A R E	S P W N	N A V	C O M M	E S T	M A R	A Q U A	M I G R	S H L L	-
Mission Bay Shoreline, at North Crown Point (906.3)												۲	۲				
*Source: Table TC-1, Beneficial Uses of the 2010 30	3(d) L	isted V	Water	bodies	s in M	ission	Bay V	VMA;	Missi	on Ba	ıy WN	IA Wa	ater Q	uality	Impro	ovemen	nt
Plan, Appendix C – Beneficial Uses of 303(d) Listed	Wate	rbodie	s in N	lissior	n Bay	WMA	, Febr	ruary 2	2016.								
Identify all ASBS (areas of special biolo locations. No areas of ASBS have been identified	0	0) rec	eivir	ıg wa	aters	dov	vnst	ream	n of t	the p	roje	ct dis	schar	ge
Provide distance from project outfall l	ocati	on te	o im	paire	ed o:	r sen	sitiv	e rec	ceivi	ng w	ater	s.					
The site will outfall 1,050 feet south to La Playa Avenue. Strom water is then	o the	exis	ting	stor	m d	rain	inlet	loca	ated	at th	ne co	orner					nd
Summarize information regarding the p City's Multi-Habitat Planning Area and									onst	ruct	ion s	storn	n wa	ter F	BMP	s to t	he
There are no existing MHPA and oper approximately 1025 ft to the southeast project site to the west, south and east	oft	he si	te. T	here	e are	env	iron	men							ndin	g thi	S



			Page 8 of 11		
			Water Pollutants of		
	servoir, as	s applicable), ident	ify the pollutant(s),	/stressor(ect site to the Pacific Ocean s) causing impairment, and paired water bodies:
303(d) Impaired Water	Ŭ		/Stressor(s)	^	s/ WQIP Highest Priority Pollutant
Mission Bay Shoreline, North Cr	own Point	Enterc	ococcus		*To be developed
		Total C	oliform		
		1	pject Site Pollutants	ļ	
in lieu of retention or biol program unless prior lawfu	filtration H l approva ted from	BMPs (note the pr l to meet earlier PI the project site ba	oject must also par DP requirements is sed on all proposed	rticipate ir demonstr	IPs are implemented onsite n an alternative compliance ated) f the site (see BMP Design
Pollutant		pplicable to the Project Site	Anticipated fro Project Sit		Also a Receiving Water Pollutant of Concern
Sediment			x		х
Nutrients					
Heavy Metals			х		
Organic Compounds			х		
Trash & Debris			x		
Oxygen Demanding Substances					
Oil & Grease			x		
Bacteria & Viruses			х		Х
Pesticides			х		

*Source Table 2-1, 2010 303(d) or TMDL Listed Waterbodies in the Mission Bay WMA; Mission Bay WMA Water Quality Improvement Plan, 2 – Priority Water Quality Conditions, February 2016.

PTS# 530514 latitude 33		Form I-3B Page 9 of 1	
□ Control for the project will discharge runoff directly to existing underground storm drains discharging directly to water storage reservoirs, lakes, enclosed embayments, or the Pacific Ocean. □ No, the project will discharge runoff directly to conveyance channels whose bed and bank are concrete-lined all the way from the point of discharge to water storage reservoirs, lakes, enclosed embayments, or the Pacific Ocean. □ No, the project will discharge runoff directly to an area identified as appropriate for an exemption by the WMAA for the watershed in which the project resides. Description / Additional Information (to be provided if a 'No' answer has been selected above): The proposed site will discharge through sidewalk underdrains to the curb and gutter on Shata Street. All discharge or unit auch and gutter 1,050 feet south to the existing storm drain inlet located at the corner of Jewell Street and La Playa Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue and across Crown Point park and then discharges directly into Mission Bay (See figure on Form 1-3 Page 11 of 11). This routes astifies the HAP exemption shown as criteria 3 in Figure 1-2 of section 1.6 of the City of San Dicgo's BMP Design Manual. Critical Coarse Sectiment Yield Areas* *This Section only required if hydromodification management requirements apply Based on Section 6.2 and Appendix H does CCSYA exist on the project footprint or in the upstream area draining through the project footprint? □ No Discussion / Additional Information: There are no existing Course Sediment Yield Areas (CCYAs) onsite nor upstream of the project site.			
Description / Additional Information (to be provided if a 'No' answer has been selected above): The proposed site will discharge through sidewalk underdrains to the curb and gutter on Shasta Street. All discharge points will flow via curb and gutter 1,050 feet south to the existing storm drain inlet located at the corner of Jewell Street and La Playa Avenue. Storm water is then conveyed via storm drain inpes east down La Playa Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue. Storm Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue. Storm Avenue and across Corow Point Hard and then discharges dottered in Mission Bay (See figure on Form 1-3 Page 11 of 11). This route satisfies the HMP exemption shown as criteria 3 in Figure 1-2 of section 1.6 of the City of San Diego's BMP Design Manual. Critical Coarse Sediment Yield Areas* "This Section only required if hydromodification management requirements apply Based on Section 6.2 and Appendix H does CCSYA exist on the project footprint or in the upstream area draining through the project footprint?	 Yes, hydromodifica No, the project will to water storage res No, the project will lined all the way fr the Pacific Ocean. No, the project will 	ation management flow control structural BM l discharge runoff directly to existing undergr servoirs, lakes, enclosed embayments, or the I ll discharge runoff directly to conveyance ch om the point of discharge to water storage r ll discharge runoff directly to an area identifie	Ps required. round storm drains discharging directly Pacific Ocean. annels whose bed and bank are concrete- reservoirs, lakes, enclosed embayments, or
The proposed site will discharge through sidewalk underdrains to the curb and gutter on Shasta Street. All discharge points will flow via curb and gutter 1,050 feet south to the existing storm drain inlet located at the corner of Jewell Street and La Playa Avenue. Storm water is then conveyed via storm drain inplet south to the existing storm drain inplet located at the corner of Jewell Street and La Playa Avenue. Storm water is then conveyed via storm drain inplet south La Playa Avenue. Storm water is then conveyed via storm drain inplet located at the corner of Jewell Street and La Playa Avenue. Storm water is then conveyed via storm drain inplet south La Playa Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue and across Crown Point park and then discharges directly into Mission Bay (See figure on Form 13 Page 11 of 11). This route satisfies the HMP exemption shown as criteria 3 in Figure 1-2 of section 1.6 of the City of San Diego's BMP Design Manual. Critical Coarse Sediment Yield Areas* *This Section only required if hydromodification management requirements apply Based on Section 6.2 and Appendix H does CCSYA exist on the project footprint or in the upstream area draining through the project footprint? By o Discussion / Additional Information: There are no existing Course Sediment Yield Areas (CCYAs) onsite nor upstream of the project site. Stor Blick Homes TiSM 530514		* /	er has been selected above):
*This Section only required if hydromodification management requirements apply Based on Section 6.2 and Appendix H does CCSYA exist on the project footprint or in the upstream area draining through the project footprint? Yes No Discussion / Additional Information: There are no existing Course Sediment Yield Areas (CCYAs) onsite nor upstream of the project site.	The proposed site will c discharge points will flo corner of Jewell Street a Playa Avenue and acros I-3 Page 11 of 11). This	discharge through sidewalk underdrains to the ow via curb and gutter 1,050 feet south to the and La Playa Avenue. Storm water is then con as Crown Point park and then discharges dire route satisfies the HMP exemption shown a	e curb and gutter on Shasta Street. All existing storm drain inlet located at the nveyed via storm drain pipes east down La ctly into Mission Bay (See figure on Form
draining through the project footprint? ☐ Yes ⊠ No Discussion / Additional Information: There are no existing Course Sediment Yield Areas (CCYAs) onsite nor upstream of the project site. Seo Blök Homes YIS# 530514	*This Sec		
There are no existing Course Sediment Yield Areas (CCYAs) onsite nor upstream of the project site.	draining through the pro □Yes		project footprint or in the upstream area
Eco Blök Homes 2TS# 530514	Discussion / Additional	Information:	
PTS# 530514 latitude 33	There are no existing Co	ourse Sediment Yield Areas (CCYAs) onsite r	or upstream of the project site.
	Eco Blök Homes PTS# 530514 March 2017	25	latitude 33

Form I-3B Page 10 of 11
Flow Control for Post-Project Runoff*
*This Section only required if hydromodification management requirements apply
List and describe point(s) of compliance (POCs) for flow control for hydromodification management (see Section 6.3.1). For each POC, provide a POC identification name or number correlating to the project's HMP Exhibit and a receiving channel identification name or number correlating to the project's HMP Exhibit.
Has a geomorphic assessment been performed for the receiving channel(s)? No, the low flow threshold is 0.1Q2 (default low flow threshold) Yes, the result is the low flow threshold is 0.1Q2 Yes, the result is the low flow threshold is 0.3Q2 Yes, the result is the low flow threshold is 0.5Q2
If a geomorphic assessment has been performed, provide title, date, and preparer:
Discussion / Additional Information: (optional)
Eco Blök Homes



Form I-3B Page 11 of 11 Other Site Requirements and Constraints When applicable, list other site requirements or constraints that will influence storm water management design, such as zoning requirements including setbacks and open space, or local codes governing minimum street width, sidewalk construction, allowable pavement types, and drainage requirements. Optional Additional Information or Continuation of Previous Sections As Needed This space provided for additional information or continuation of information from previous sections as needed. SED ECO OK HOMES DRAINAGE PATH TO INL EXISITNG STORM DRAIN INLET PER DRAWING NO. 10511-2-D EXISITNG STORM DRAIN PER DRAWING NO. 10511-2-D STORM DRAIN LOCATION FIGURE

Eco Blök Homes PTS# 530514 March 2017





Source Control BMP Checklist for All Development Projects Source Control BMPs	I	Form I-4	4
All development projects must implement source control BMPs SC-1 thro feasible. See Chapter 4 and Appendix E of the BMP Design Manual (Part 1 of information to implement source control BMPs shown in this checklist.			
 Answer each category below pursuant to the following. "Yes" means the project will implement the source control BMP as Appendix E of the BMP Design Manual. Discussion / justification is a "No" means the BMP is applicable to the project but it is not fease justification must be provided. "N/A" means the BMP is not applicable at the project site because feature that is addressed by the BMP (e.g., the project has no o Discussion / justification may be provided. 	not required ible to impl the project	l. lement. D does not terials sto:	iscussion / include the rage areas).
Source Control Requirement		Applied	
SC-1 Prevention of Illicit Discharges into the MS4 Discussion / justification if SC-1 not implemented:	🛛 Yes	🗌 No	□ N/A
SC-2 Storm Drain Stenciling or Signage Discussion / justification if SC-2 not implemented:	X Yes	□ No	□ N/A
SC-3 Protect Outdoor Materials Storage Areas from Rainfall, Run-On, Runoff, and Wind Dispersal	Tes Yes	🗌 No	🛛 N/A
Discussion / justification if SC-3 not implemented: The proposed project does not include outdoor material storage.			
SC-4 Protect Materials Stored in Outdoor Work Areas from Rainfall, Run- On, Runoff, and Wind Dispersal	☐ Yes	□ No	⊠ N/A
Discussion / justification if SC-4 not implemented: The proposed project does not include outdoor work area.			
SC-5 Protect Trash Storage Areas from Rainfall, Run-On, Runoff, and Wind Dispersal	🛛 Yes	□ No	□ N/A
Discussion / justification if SC-5 not implemented:			

Form I-4 Page 2 of 2			
Source Control Requirement		Applied	
SC-6 Additional BMPs Based on Potential Sources of Runoff Pollutant	ts (must answer :	for each so	ource listed
below)			
On-site storm drain inlets	🛛 Yes	🗌 No	□ N/A
Interior floor drains and elevator shaft sump pumps	🗌 Yes	🗌 No	🛛 N/A
Interior parking garages	🗌 Yes	🗌 No	🛛 N/A
Need for future indoor & structural pest control	🗌 Yes	🗌 No	🛛 N/A
Landscape/Outdoor Pesticide Use	🛛 Yes	🗌 No	□ N/A
Pools, spas, ponds, decorative fountains, and other water features	🗌 Yes	🗌 No	🛛 N/A
Food service	🗌 Yes	🗌 No	🛛 N/A
Refuse areas	🗌 Yes	🗌 No	🛛 N/A
Industrial processes	🗌 Yes	🗌 No	🛛 N/A
Outdoor storage of equipment or materials	🗌 Yes	🗌 No	🛛 N/A
Vehicle/Equipment Repair and Maintenance	🗌 Yes	🗌 No	🛛 N/A
Fuel Dispensing Areas	🗌 Yes	🗌 No	🛛 N/A
Loading Docks	🗌 Yes	🗌 No	🛛 N/A
Fire Sprinkler Test Water	🗌 Yes	🗌 No	🛛 N/A
Miscellaneous Drain or Wash Water	🗌 Yes	🗌 No	🛛 N/A
Plazas, sidewalks, and parking lots	🛛 Yes	🗌 No	□ N/A
SC-6A: Large Trash Generating Facilities	🗌 Yes	🗌 No	🛛 N/A
SC-6B: Animal Facilities	🗌 Yes	🗌 No	🛛 N/A
SC-6C: Plant Nurseries and Garden Centers	🗌 Yes	🗌 No	🛛 N/A
SC-6D: Automotive-related Uses	🗌 Yes	🗌 No	🛛 N/A

Discussion / justification if SC-6 not implemented. Clearly identify which sources of runoff pollutants are discussed. Justification must be provided for <u>all</u> "No" answers shown above.



Source Control BMP Checklist for All Development Projects	l	Form I-5	5
Site Design BMPs			
All development projects must implement site design BMPs SD-1 through SD-8 will See Chapter 4 and Appendix E of the BMP Design Manual (Part 1 of Storm Water to implement site design BMPs shown in this checklist.			
 Answer each category below pursuant to the following. "Yes" means the project will implement the site design BMP as descended as the BMP Design Manual. Discussion / justification is not response to the BMP is applicable to the project but it is not feasible to justification must be provided. "N(A" means the BMP is not explicible at the project site because the BMP. 	equired. o implen	nent. Disc	ussion /
 "N/A" means the BMP is not applicable at the project site because the p feature that is addressed by the BMP (e.g., the project site has no existing Discussion / justification may be provided. 			
A site map with implemented site design BMPs must be included at the end of this	checklist.		
Site Design Requirement		Applied?	
SD-1 Maintain Natural Drainage Pathways and Hydrologic Features	Series Yes	🗌 No	🛛 N/A
1-1 Are existing natural drainage pathways and hydrologic features mapped on	TYes	No No	
the site map?1-2Are trees implemented? If yes, are they shown on the site map?			
1-3 Implemented trees meet the design criteria in SD-1 Fact Sheet (e.g. soil	☐ Yes	No No	
volume, maximum credit, etc.)?	☐ Yes	🛛 No	
1-4 Is tree credit volume calculated using Appendix B.2.2.1 and SD-1 Fact Sheet in Appendix E?	🗌 Yes	🛛 No	
SD-2 Have natural areas, soils and vegetation been conserved?	Tes Yes	🗌 No	
Discussion / justification if SD-2 not implemented:			N/A




Form I-5 Page 2 of 4			
Site Design Requirement		Applied?	
SD-3 Minimize Impervious Area	🛛 Yes	🗌 No	□ N/A
Discussion / justification if SD-3 not implemented:			
SD-4 Minimize Soil Compaction	Xes	□ No	□ N/A
Discussion / justification if SD-4 not implemented:			
	1		
SD-5 Impervious Area Dispersion	Xes	🗌 No	□ N/A
Discussion / justification if SD-5 not implemented: Grading limitations prevent the implementation of such areas.			
5-1 Is the pervious area receiving runon from impervious area identified on the site map?	Tes Yes	No No	
5-2 Does the pervious area satisfy the design criteria in SD-5 Fact Sheet in Appendix E (e.g. maximum slope, minimum length, etc.)	Tes Yes	No No	
5-3 Is impervious area dispersion credit volume calculated using Appendix B.2.1.1 and SD-5 Fact Sheet in Appendix E?	Tes Yes	No No	



Form I-5 Page 3 of 4			
Site Design Requirement		Applied?	Γ
SD-6 Runoff Collection	🛛 Yes	🗌 No	□ N/A
Discussion / justification if SD-6 not implemented: Landscape areas, overflow structures, and infiltration BMPs have been placed throughout the project site			
 to reduce the transportation of pollutants to receiving waters. 6a-1 Are green roofs implemented in accordance with design criteria in SD-6A Fact Sheet? If yes, are they shown on the site map? 6a-2 Is green roof credit volume calculated using Appendix B.2.1.2 and SD-6A Fact Sheet in Appendix E? 6b-1 Are permeable pavements implemented in accordance with design 	☐ Yes ☐ Yes ☐ Yes	No No	
criteria in SD-6B Fact Sheet? If yes, are they shown on the site			
6b-2 Is permeable pavement credit volume calculated using Appendix B.2.1.3 and SD-6B Fact Sheet in Appendix E?	Tes Yes	🛛 No	
SD-7 Landscaping with Native or Drought Tolerant Species	🛛 Yes	🗌 No	□ N/A
SD-8 Harvesting and Using Precipitation	Tes Yes	No No	□ N/A
Discussion / justification if SD-8 not implemented: There are no feasible opportunities to harvest runoff for later use before system. See Form I-7 of Attachment 1c.	it enters the	existing stor	rm drain
8-1 Are rain barrels implemented in accordance with design criteria in SD-8 Fact Sheet? If yes, are they shown on the site map?	Tes Yes	🛛 No	
8-2 Is rain barrel credit volume calculated using Appendix B.2.2.2 and SD-8 Fact Sheet in Appendix E?	TYes	No No	







Summary of PDP Structural BMPs	Form I-6	
PDP Structural BMPs		

All PDPs must implement structural BMPs for storm water pollutant control (see Chapter 5 of the BMP Design Manual, Part 1 of Storm Water Standards). Selection of PDP structural BMPs for storm water pollutant control must be based on the selection process described in Chapter 5. PDPs subject to hydromodification management requirements must also implement structural BMPs for flow control for hydromodification management (see Chapter 6 of the BMP Design Manual). Both storm water pollutant control and flow control for hydromodification management can be achieved within the same structural BMP(s).

PDP structural BMPs must be verified by the City at the completion of construction. This includes requiring the project owner or project owner's representative to certify construction of the structural BMPs (complete Form DS-563). PDP structural BMPs must be maintained into perpetuity (see Chapter 7 of the BMP Design Manual).

Use this form to provide narrative description of the general strategy for structural BMP implementation at the project site in the box below. Then complete the PDP structural BMP summary information sheet (page 3 of this form) for each structural BMP within the project (copy the BMP summary information page as many times as needed to provide summary information for each individual structural BMP).

Describe the general strategy for structural BMP implementation at the site. This information must describe how the steps for selecting and designing storm water pollutant control BMPs presented in Section 5.1 of the BMP Design Manual were followed, and the results (type of BMPs selected). For projects requiring hydromodification flow control BMPs, indicate whether pollutant control and flow control BMPs are integrated or separate.

- **Step 1.** Sites were located for water pollutant control BMPs and DMAs were delineated and DCVs calculated.
- **Step 2.** Per the included Harvest and Use feasibility screening the proposed project is considered to be infeasible for harvest and use.
- **Step 3.** Per the "Assessment of the Potential for Infiltration-Related Soil Collapse" Report by Nova dated May 9, 2017, infiltration is feasible.
- Step 4. Infiltration BMPs have been strategically placed throughout the project site. For each infiltration BMP the "Design Capture Volume" Worksheet B.2-1 and B-4.1 was used to determine the minimum footprint required. It is important to note that the minimum footprint for every infiltration BMP was governed by the drawdown time less than 36 hours.
- **Step 5.** Flow-thru treatment devices are not proposed for this site as we are able to treat the DCV onsite with the proposed infiltration basins.

The project is not subject to hydromodification requirements. The site discharges to an existing inlet and storm drain system that discharges directly to Mission Bay.




Form I-6 Page 2 of 62 (Page reserved for continuation of description of general strategy for structural BMP implementation at the		
(Page reserved for continuation of de	escription of general strategy for structu site)	aral BMP implementation at the
(Continued from page 1)		
Eco Blök Homes		
PTS# 530514 March 2017	36	


36

Form I-6 Page 3 of 62 (Copy as many as needed)			
Structural B	Structural BMP Summary Information		
Structural BMP ID No. BMP 1			
Construction Plan Sheet No. C-2			
Type of structural BMP:			
□ Retention by harvest and use (HU-1)			
\boxtimes Retention by infiltration basin (INF-1)	Retention by infiltration basin (INF-1)		
Retention by bioretention (INF-2)			
Retention by permeable pavement (INF-3	,		
Partial retention by biofiltration with parti	al retention (PR-1)		
Biofiltration (BF-1)			
How-thru treatment control with prior law type / Description in discussion section b	wful approval to meet earlier PDP requirements (Provide BMP elow		
Flow-thru treatment control with alternative section below	ve compliance (provide BMP type / description in discussion		
Detention pond of vault for hydromodific	ation management		
Other (describe in discussion section below	w)		
Purpose:			
Pollutant control only			
Hydromodification control only	11/7		
 Combined pollutant control and hydromo Pre-treatment / forebay for another struct 			
 Other (describe in discussion section below 			
	Giovanni Posillico, RCE 66332		
Who will certify construction of this BMP?	Latitude 33 Planning & Engineering		
Provide name and contact information for the	8 8 8		
responsible to sign BMP verification form DS-5	63 San Diego, CA 92131		
	(858) 751-0633		
Who will be the final owner of this BMP? Pathfinder Crown Point Apartments, LLC			
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC			
What is the funding mechanism for maintenanc	e? Pathfinder Crown Point Apartments, LLC		






Form I-6 Page 5 of 62 (Copy as many as needed)			
	Structural BMP Summary Information		
	ctural BMP ID No. BMP 2		
	struction Plan Sheet No. C-2		
Тур	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\square	Retention by infiltration basin (INF-1)		
	Retention by bioretention (INF-2)		
	Retention by permeable pavement (INF-3)		
	Partial retention by biofiltration with partial reten	tion (PR-1)	
	Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful app type / Description in discussion section below	proval to meet earlier PDP requirements (Provide BMP	
	 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
	Detention pond of vault for hydromodification m	anagement	
	Other (describe in discussion section below)	-	
Purp	oose:		
\square	Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	ſP	
	Other (describe in discussion section below		
		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP?	Latitude 33 Planning & Engineering	
	vide name and contact information for the party	9968 Hibert Street Second Floor	
resp	onsible to sign BMP verification form DS-563	San Diego, CA 92131 (858) 751-0633	
		(838) / 31-0033	
Whe	Who will be the final owner of this BMP? Pathfinder Crown Point Apartments, LLC		
Whe	Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
Wha	at is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	




Eco Blök Homes PTS# 530514 March 2017



	Form I-6 Page 7 of 62 (Copy as many as needed)		
	Structural BMP Summary Information		
Stru	ctural BMP ID No. BMP 3		
Con	struction Plan Sheet No. C-2		
Тур	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\square	Retention by infiltration basin (INF-1)		
	Retention by bioretention (INF-2)		
	Retention by permeable pavement (INF-3)		
	Partial retention by biofiltration with partial reten	ation (PR-1)	
	Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful app type / Description in discussion section below	proval to meet earlier PDP requirements (Provide BMP	
	 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
	Flow-thru treatment control with alternative comp section below	pliance (provide BMP type / description in discussion	
	Detention pond of vault for hydromodification m	nanagement	
	Other (describe in discussion section below)		
Purp	oose:		
\square	Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	ЯΡ	
	Other (describe in discussion section below		
		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP?	Latitude 33 Planning & Engineering	
	vide name and contact information for the party onsible to sign BMP verification form DS-563	9968 Hibert Street Second Floor San Diego, CA 92131	
resp	onsidie to sign Diffi Vernication form Do 505	(858) 751-0633	
		(000) / 01 0000	
Whe	Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Whe	Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
Wha	at is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	




	Form I-6 Page 9 of 62 (Copy as many as needed)		
	Structural BMP Summary Information		
Stru	ctural BMP ID No. BMP 4		
Con	struction Plan Sheet No. C-2		
Тур	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\boxtimes	Retention by infiltration basin (INF-1)		
	Retention by bioretention (INF-2)		
	Retention by permeable pavement (INF-3)		
	Partial retention by biofiltration with partial reten	tion (PR-1)	
	Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful app type / Description in discussion section below	proval to meet earlier PDP requirements (Provide BMP	
	 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
	Detention pond of vault for hydromodification m	anagement	
	* · ·		
Purp	bose:		
\square	Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	112	
	Other (describe in discussion section below		
		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP?	Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor	
	vide name and contact information for the party consible to sign BMP verification form DS-563	San Diego, CA 92131	
resp	onsible to sign Divit vernication form Do 505	(858) 751-0633	
		(000) / 01 0000	
Whe	Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Whe	Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
Wha	at is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	




Eco Blök Homes PTS# 530514 March 2017




	Form I-6 Page 11 of 62 (Copy as many as needed)		
	Structural BMP Summary Information		
	ctural BMP ID No. BMP 105		
	struction Plan Sheet No. C-2		
Тур	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\square	Retention by infiltration basin (INF-1)		
	Retention by bioretention (INF-2)		
	Retention by permeable pavement (INF-3)		
	Partial retention by biofiltration with partial reten	tion (PR-1)	
	Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful app type / Description in discussion section below	proval to meet earlier PDP requirements (Provide BMP	
	 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
	Flow-thru treatment control with alternative comp section below	pliance (provide BMP type / description in discussion	
	Detention pond of vault for hydromodification m	anagement	
	Other (describe in discussion section below)		
Purp	bose:		
\square	Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	117	
	Other (describe in discussion section below	C' ' D '''' D CE ((222	
W/b	o will certify construction of this BMP?	Giovanni Posillico, RCE 66332 Latitude 33 Planning & Engineering	
	vide name and contact information for the party	9968 Hibert Street Second Floor	
	onsible to sign BMP verification form DS-563	San Diego, CA 92131	
-		(858) 751-0633	
Whe	Who will be the final owner of this BMP? Pathfinder Crown Point Apartments, LLC		
Whe	Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
Wh	at is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	




	Form I-6 Page 13 of 62 (Copy as many as needed)		
	Structural BMP Sur	nmary Information	
Stru	ctural BMP ID No. BMP 6		
Con	struction Plan Sheet No. C-2		
Тур	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\boxtimes	Retention by infiltration basin (INF-1)		
	Retention by bioretention (INF-2)		
	Retention by permeable pavement (INF-3)		
	Partial retention by biofiltration with partial reten	tion (PR-1)	
	Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful app type / Description in discussion section below	proval to meet earlier PDP requirements (Provide BMP	
	 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
	Detention pond of vault for hydromodification m	anagement	
	Other (describe in discussion section below)		
Purp	bose:		
\square	Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	1P	
	Other (describe in discussion section below		
33771		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP? vide name and contact information for the party	Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor	
	onsible to sign BMP verification form DS-563	San Diego, CA 92131	
reop		(858) 751-0633	
W/h	o will be the final owner of this BMP?		
WII	5 will be the final owner of this DMF?	Pathfinder Crown Point Apartments, LLC	
Whe	Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
Wha	at is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	




Form I-6 Page 15 of 62 (Copy as many as needed)			
	Structural BMP Summary Information		
	ctural BMP ID No. BMP 7		
Con	struction Plan Sheet No. C-2		
Тур	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\boxtimes	Retention by infiltration basin (INF-1)		
	Retention by bioretention (INF-2)		
	Retention by permeable pavement (INF-3)		
	Partial retention by biofiltration with partial reten	tion (PR-1)	
	Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful app type / Description in discussion section below	proval to meet earlier PDP requirements (Provide BMP	
	 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
	Detention pond of vault for hydromodification m	anagement	
	Other (describe in discussion section below)		
Purp	oose:		
\boxtimes	Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	1P	
	Other (describe in discussion section below		
		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP?	Latitude 33 Planning & Engineering	
	vide name and contact information for the party onsible to sign BMP verification form DS-563	9968 Hibert Street Second Floor	
resp	onsidie to sign Divin Vermeauon form Do 505	San Diego, CA 92131 (858) 751-0633	
		(050) / 51-0055	
Whe	Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Whe	Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
Wha	at is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	




	Form I-6 Page 17 of 62 (Copy as many as needed)		
	Structural BMP Summary Information		
	ctural BMP ID No. BMP 8		
Con	struction Plan Sheet No. C-2		
Туре	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\boxtimes	Retention by infiltration basin (INF-1)		
	Retention by bioretention (INF-2)		
	Retention by permeable pavement (INF-3)		
	Partial retention by biofiltration with partial reten	tion (PR-1)	
	Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful app type / Description in discussion section below	proval to meet earlier PDP requirements (Provide BMP	
	 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
	Detention pond of vault for hydromodification m	anagement	
	Other (describe in discussion section below)	-	
Purp	oose:		
\boxtimes	Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	ſP	
	Other (describe in discussion section below		
		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP?	Latitude 33 Planning & Engineering	
	vide name and contact information for the party	9968 Hibert Street Second Floor	
resp	onsible to sign BMP verification form DS-563	San Diego, CA 92131 (858) 751-0633	
		(838) 751-0055	
Who	Who will be the final owner of this BMP? Pathfinder Crown Point Apartments, LLC		
Who	Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
Wha	at is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	



Form I-6 Page 19 of 62 (Copy as many as needed)			
	Structural BMP Summary Information		
	ctural BMP ID No. BMP 9		
Con	struction Plan Sheet No. C-2		
Тур	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\boxtimes	Retention by infiltration basin (INF-1)		
	□ Retention by bioretention (INF-2)		
	□ Retention by permeable pavement (INF-3)		
	□ Partial retention by biofiltration with partial retention (PR-1)		
	□ Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BM) type / Description in discussion section below		
	Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below)		
	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
	Detention pond of vault for hydromodification m	anagement	
	Other (describe in discussion section below)		
Purp	oose:		
\boxtimes	Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	ſP	
	Other (describe in discussion section below		
		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP?	Latitude 33 Planning & Engineering	
	vide name and contact information for the party onsible to sign BMP verification form DS-563	9968 Hibert Street Second Floor	
resp	onsidie to sign divin vernication form DS-505	San Diego, CA 92131 (858) 751-0633	
	(858) / 51-0035		
Whe	Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity?		Pathfinder Crown Point Apartments, LLC	
What is the funding mechanism for maintenance? P		Pathfinder Crown Point Apartments, LLC	




Form I-6 Page 21 of 62 (Copy as many as needed)			
	Structural BMP Summary Information		
Stru	ctural BMP ID No. BMP 10		
Con	struction Plan Sheet No. C-2		
Тур	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\boxtimes	Retention by infiltration basin (INF-1)		
	□ Retention by bioretention (INF-2)		
	□ Retention by permeable pavement (INF-3)		
	□ Partial retention by biofiltration with partial retention (PR-1)		
	□ Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BM type / Description in discussion section below		
	Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below)		
	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
	Detention pond of vault for hydromodification management		
Purp	bose:		
\boxtimes	☑ Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	1P	
	Other (describe in discussion section below		
33771		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP? vide name and contact information for the party	Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor	
	onsible to sign BMP verification form DS-563	San Diego, CA 92131	
reop		(858) 751-0633	
	(050) 751-0055		
Whe	Who will be the final owner of this BMP? Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity?		Pathfinder Crown Point Apartments, LLC	
What is the funding mechanism for maintenance?		Pathfinder Crown Point Apartments, LLC	






Form I-6 Page 23 of 62 (Copy as many as needed)			
	Structural BMP Summary Information		
	ctural BMP ID No. BMP 11		
Con	struction Plan Sheet No. C-2		
Тур	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\square			
	□ Retention by bioretention (INF-2)		
	□ Retention by permeable pavement (INF-3)		
	□ Partial retention by biofiltration with partial retention (PR-1)		
	Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BM) type / Description in discussion section below		
	Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below)		
	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
	Detention pond of vault for hydromodification m	nanagement	
	Other (describe in discussion section below)		
Purp	pose:		
\boxtimes	Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	ЯΡ	
	Other (describe in discussion section below		
		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP?	Latitude 33 Planning & Engineering	
	vide name and contact information for the party onsible to sign BMP verification form DS-563	9968 Hibert Street Second Floor San Diego, CA 92131	
resp	onsible to sign Divit vernication form Do 505	(858) 751-0633	
	(838) / 31-0033		
Whe	Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity?		Pathfinder Crown Point Apartments, LLC	
What is the funding mechanism for maintenance?		Pathfinder Crown Point Apartments, LLC	







Form I-6 Page 25 of 62 (Copy as many as needed)			
	Structural BMP Summary Information		
	ctural BMP ID No. BMP 12		
Con	struction Plan Sheet No. C-2		
Тур	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\boxtimes			
	□ Retention by bioretention (INF-2)		
	□ Retention by permeable pavement (INF-3)		
	Partial retention by biofiltration with partial retention (PR-1)		
	Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMI type / Description in discussion section below		
	Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below)		
	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
	Detention pond of vault for hydromodification m	nanagement	
	Other (describe in discussion section below)		
Purp	oose:		
\boxtimes	Dellutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	ЯΡ	
	Other (describe in discussion section below		
		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP?	Latitude 33 Planning & Engineering	
	vide name and contact information for the party onsible to sign BMP verification form DS-563	9968 Hibert Street Second Floor San Diego, CA 92131	
resp	onsidie to sign Diffi Vernication form Do 505	(858) 751-0633	
	(838) / 31-0033		
Whe	Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity?		Pathfinder Crown Point Apartments, LLC	
What is the funding mechanism for maintenance?		Pathfinder Crown Point Apartments, LLC	



Form I-6 Page 27 of 62 (Copy as many as needed)			
	Structural BMP Summary Information		
	ctural BMP ID No. BMP 13		
Con	struction Plan Sheet No. C-2		
Тур	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\boxtimes			
	□ Retention by bioretention (INF-2)		
	□ Retention by permeable pavement (INF-3)		
	Partial retention by biofiltration with partial retention (PR-1)		
	Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMI type / Description in discussion section below		
	 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
	Detention pond of vault for hydromodification m	nanagement	
	Other (describe in discussion section below)		
Purp	pose:		
\boxtimes	Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	ЯΡ	
	Other (describe in discussion section below		
		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP?	Latitude 33 Planning & Engineering	
	vide name and contact information for the party onsible to sign BMP verification form DS-563	9968 Hibert Street Second Floor San Diego, CA 92131	
resp	onsible to sign Divit vernication form Do 505	(858) 751-0633	
	(838) / 31-0033		
Whe	Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity?		Pathfinder Crown Point Apartments, LLC	
What is the funding mechanism for maintenance?		Pathfinder Crown Point Apartments, LLC	




Form I-6 Page 28 of 62 (Copy as many as needed)			
	Structural BMP Summary Information		
Stru	ctural BMP ID No. BMP 14		
Con	struction Plan Sheet No. C-2		
Туре	e of structural BMP:		
	Retention by harvest and use (HU-1)		
\boxtimes	Retention by infiltration basin (INF-1)		
	□ Retention by bioretention (INF-2)		
	□ Partial retention by biofiltration with partial retention (PR-1)		
	Biofiltration (BF-1)		
	Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BM type / Description in discussion section below		
	Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below)		
	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
	Detention pond of vault for hydromodification m	nanagement	
Purp	oose:		
\boxtimes	Pollutant control only		
	Hydromodification control only		
	Combined pollutant control and hydromodification		
	Pre-treatment / forebay for another structural BM	ЯΡ	
	Other (describe in discussion section below		
		Giovanni Posillico, RCE 66332	
	o will certify construction of this BMP?	Latitude 33 Planning & Engineering	
	vide name and contact information for the party onsible to sign BMP verification form DS-563	9968 Hibert Street Second Floor	
resp	onsidie to sign Divin Verineation form Do 505	San Diego, CA 92131 (858) 751-0633	
	(858) / 51-0055		
Who	Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity?		Pathfinder Crown Point Apartments, LLC	
What is the funding mechanism for maintenance?		Pathfinder Crown Point Apartments, LLC	




Eco Blök Homes PTS# 530514 March 2017


Form I-6 Page 31 of 62 (Copy as many as needed)			
Structural BMP Summary Information			
Structural BMP ID No. BMP 15			
Construction Plan Sheet No. C-2			
Type of structural BMP:			
Retention by harvest and use (HU-1)	Retention by harvest and use (HU-1)		
Retention by infiltration basin (INF-1)			
Retention by bioretention (INF-2)			
Retention by permeable pavement (INF-3)			
Partial retention by biofiltration with partial retention	Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)			
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below			
Flow-thru treatment control with alternative comsection below	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
Detention pond of vault for hydromodification n	nanagement		
□ Other (describe in discussion section below)			
Purpose:			
Pollutant control only	☑ Pollutant control only		
	Hydromodification control only		
Combined pollutant control and hydromodificati			
Pre-treatment / forebay for another structural BN	мР		
Other (describe in discussion section below			
	Giovanni Posillico, RCE 66332		
Who will certify construction of this BMP?	Latitude 33 Planning & Engineering		
Provide name and contact information for the party responsible to sign BMP verification form DS-563	9968 Hibert Street Second Floor San Diego, CA 92131		
responsible to sign binn vernication form bo 505	(858) 751-0633		
(838) / 31-0033			
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC			
Who will maintain this BMP into perpetuity?	Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC		




Form I-6 Page 33 of 62 (Copy as many as needed)			
Structural BMP Su	mmary Information		
Structural BMP ID No. BMP 16			
Construction Plan Sheet No. C-2			
Type of structural BMP:			
□ Retention by harvest and use (HU-1)	Retention by harvest and use (HU-1)		
Retention by infiltration basin (INF-1)			
☐ Retention by bioretention (INF-2)			
□ Retention by permeable pavement (INF-3)			
Partial retention by biofiltration with partial retention (PR-1)			
□ Biofiltration (BF-1)			
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below			
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 			
Flow-thru treatment control with alternative comsection below	Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
Detention pond of vault for hydromodification r	nanagement		
□ Other (describe in discussion section below)			
Purpose:			
➢ Pollutant control only			
Hydromodification control only			
Combined pollutant control and hydromodificati			
Pre-treatment / forebay for another structural B	MP		
Other (describe in discussion section below			
	Giovanni Posillico, RCE 66332		
Who will certify construction of this BMP? Provide name and contact information for the party	Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor		
responsible to sign BMP verification form DS-563	San Diego, CA 92131		
	(858) 751-0633		
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC			
Who will maintain this BMP into perpetuity?	Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC		




Form I-6 Page 35 of 62 (Copy as many as needed)			
	Summary Information		
Structural BMP ID No. BMP 17			
Construction Plan Sheet No. C-2			
Type of structural BMP:			
Retention by harvest and use (HU-1)			
Retention by infiltration basin (INF-1)			
Retention by bioretention (INF-2)			
Retention by permeable pavement (INF-3)			
Partial retention by biofiltration with partial retention (PR-1)			
□ Biofiltration (BF-1)			
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below			
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 			
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below			
Detention pond of vault for hydromodificatio	n management		
□ Other (describe in discussion section below)			
Purpose:			
Pollutant control only			
Hydromodification control only			
Combined pollutant control and hydromodification control			
Pre-treatment / forebay for another structural	BMP		
Other (describe in discussion section below			
	Giovanni Posillico, RCE 66332		
Who will certify construction of this BMP?	Latitude 33 Planning & Engineering		
Provide name and contact information for the par responsible to sign BMP verification form DS-563	ty 9968 Hibert Street Second Floor San Diego, CA 92131		
responsible to sign bivit vernication form bio 505	(858) 751-0633		
	(050) 751-0055		
Who will be the final owner of this BMP? Pathfinder Crown Point Apartments, LLC			
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC			
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC		




Form I-6 Page 37 of 62 (Copy as many as needed)		
Structural BMP Su	mmary Information	
Structural BMP ID No. BMP 18		
Construction Plan Sheet No. C-2		
Type of structural BMP:		
□ Retention by harvest and use (HU-1)		
Retention by infiltration basin (INF-1)		
Retention by bioretention (INF-2)		
Retention by permeable pavement (INF-3)		
□ Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)		
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below		
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
Detention pond of vault for hydromodification n	nanagement	
□ Other (describe in discussion section below)		
Purpose:		
Pollutant control only		
Hydromodification control only		
Combined pollutant control and hydromodificati		
Pre-treatment / forebay for another structural BN	мР	
Other (describe in discussion section below		
	Giovanni Posillico, RCE 66332	
Who will certify construction of this BMP?	Latitude 33 Planning & Engineering	
Provide name and contact information for the party responsible to sign BMP verification form DS-563	9968 Hibert Street Second Floor San Diego, CA 92131	
responsible to sign binn vernication form bo 505	(858) 751-0633	
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	




Form I-6 Page 39 of 62 (Copy as many as needed)		
	Summary Information	
Structural BMP ID No. BMP 19		
Construction Plan Sheet No. C-2		
Type of structural BMP:		
Retention by harvest and use (HU-1)		
Retention by infiltration basin (INF-1)		
Retention by bioretention (INF-2)		
Retention by permeable pavement (INF-3)		
Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)		
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below		
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
Detention pond of vault for hydromodification	n management	
□ Other (describe in discussion section below)		
Purpose:		
Pollutant control only		
Hydromodification control only		
Combined pollutant control and hydromodification control		
Pre-treatment / forebay for another structural	BMP	
Other (describe in discussion section below		
	Giovanni Posillico, RCE 66332	
Who will certify construction of this BMP?	Latitude 33 Planning & Engineering	
Provide name and contact information for the part responsible to sign BMP verification form DS-563	y 9968 Hibert Street Second Floor San Diego, CA 92131	
responsible to sign binn vernication form bo 505	(858) 751-0633	
	(050) 751-0055	
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	




Form I-6 Page 41 of 62 (Copy as many as needed)			
	mmary Information		
Structural BMP ID No. BMP 20			
Construction Plan Sheet No. C-2			
Type of structural BMP:			
Retention by harvest and use (HU-1)			
Retention by infiltration basin (INF-1)			
Retention by bioretention (INF-2)			
Retention by permeable pavement (INF-3)			
Partial retention by biofiltration with partial retention			
□ Biofiltration (BF-1)	□ Biofiltration (BF-1)		
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below			
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 			
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below			
Detention pond of vault for hydromodification n	nanagement		
□ Other (describe in discussion section below)			
Purpose:			
Pollutant control only			
Hydromodification control only			
Combined pollutant control and hydromodification control			
Pre-treatment / forebay for another structural BN	MP		
Other (describe in discussion section below			
Who will certify construction of this BMP? Provide name and contact information for the party responsible to sign BMP verification form DS-563	Giovanni Posillico, RCE 66332 Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor San Diego, CA 92131 (858) 751-0633		
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC			
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC			
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC		



Form I-6 Page 43 of 62 (Copy as many as needed)		
Structural BMP Summary Information		
Structural BMP ID No. BMP 21		
Construction Plan Sheet No. C-2		
Type of structural BMP:		
Retention by harvest and use (HU-1)		
Retention by infiltration basin (INF-1)		
□ Retention by bioretention (INF-2)		
□ Retention by permeable pavement (INF-3)		
□ Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)	□ Biofiltration (BF-1)	
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below		
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
Detention pond of vault for hydromodification management		
□ Other (describe in discussion section below)		
Purpose:		
Pollutant control only		
Hydromodification control only		
Combined pollutant control and hydromodification control		
Pre-treatment / forebay for another structural Bl	MP	
Other (describe in discussion section below		
	Giovanni Posillico, RCE 66332	
Who will certify construction of this BMP?	Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor	
Provide name and contact information for the party responsible to sign BMP verification form DS-563	San Diego, CA 92131	
	(858) 751-0633	
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	




Form I-6 Page 45 of 62 (Copy as many as needed)		
Structural BMP Su	mmary Information	
Structural BMP ID No. BMP 22		
Construction Plan Sheet No. C-2		
Type of structural BMP:		
Retention by harvest and use (HU-1)		
Retention by infiltration basin (INF-1)		
Retention by bioretention (INF-2)		
Retention by permeable pavement (INF-3)		
□ Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)		
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below		
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
Detention pond of vault for hydromodification r	nanagement	
□ Other (describe in discussion section below)		
Purpose:		
Pollutant control only		
Hydromodification control only		
Combined pollutant control and hydromodification control		
Pre-treatment / forebay for another structural Bi	MP	
Other (describe in discussion section below		
	Giovanni Posillico, RCE 66332	
Who will certify construction of this BMP?	Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor	
Provide name and contact information for the party responsible to sign BMP verification form DS-563	San Diego, CA 92131	
	(858) 751-0633	
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	






Form I-6 Page 47 of 62 (Copy as many as needed)		
	Immary Information	
Structural BMP ID No. BMP 23		
Construction Plan Sheet No. C-2		
Type of structural BMP:		
Retention by harvest and use (HU-1)		
Retention by infiltration basin (INF-1)		
Retention by bioretention (INF-2)		
Retention by permeable pavement (INF-3)		
□ Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)	□ Biofiltration (BF-1)	
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below		
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
Detention pond of vault for hydromodification r	nanagement	
□ Other (describe in discussion section below)		
Purpose:		
Pollutant control only		
Hydromodification control only		
Combined pollutant control and hydromodification control		
Pre-treatment / forebay for another structural Bl	MP	
Other (describe in discussion section below		
	Giovanni Posillico, RCE 66332	
Who will certify construction of this BMP?	Latitude 33 Planning & Engineering	
Provide name and contact information for the party responsible to sign BMP verification form DS-563	9968 Hibert Street Second Floor San Diego, CA 92131	
responsible to sign bian vernication form bo 505	(858) 751-0633	
	(000) 701 0000	
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	







Form I-6 Page 49 of 62 (Copy as many as needed)		
Structural BMP Summary Information		
Structural BMP ID No. BMP 24		
Construction Plan Sheet No. C-2		
Type of structural BMP:		
Retention by harvest and use (HU-1)		
Retention by infiltration basin (INF-1)		
Retention by bioretention (INF-2)		
Retention by permeable pavement (INF-3)		
□ Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)	□ Biofiltration (BF-1)	
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below		
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
Detention pond of vault for hydromodification management		
□ Other (describe in discussion section below)		
Purpose:		
Pollutant control only		
Hydromodification control only		
Combined pollutant control and hydromodification control		
Pre-treatment / forebay for another structural Bl	MP	
Other (describe in discussion section below		
	Giovanni Posillico, RCE 66332	
Who will certify construction of this BMP? Provide page and contact information for the party	Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor	
Provide name and contact information for the party responsible to sign BMP verification form DS-563	San Diego, CA 92131	
	(858) 751-0633	
Who will be the final owner of this BMP? Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	




Form I-6 Page 51 of 62 (Copy as many as needed)		
Structural BMP Su	mmary Information	
Structural BMP ID No. BMP 25		
Construction Plan Sheet No. C-2		
Type of structural BMP:		
Retention by harvest and use (HU-1)		
Retention by infiltration basin (INF-1)		
☐ Retention by bioretention (INF-2)		
Retention by permeable pavement (INF-3)		
Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)		
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below		
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
Detention pond of vault for hydromodification n	nanagement	
□ Other (describe in discussion section below)		
Purpose:		
☑ Pollutant control only		
Hydromodification control only		
Combined pollutant control and hydromodification control		
Pre-treatment / forebay for another structural BN	MP	
Other (describe in discussion section below		
	Giovanni Posillico, RCE 66332	
Who will certify construction of this BMP?	Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor	
Provide name and contact information for the party responsible to sign BMP verification form DS-563	San Diego, CA 92131	
responsible to sign binn vernication form bo 505	(858) 751-0633	
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	



Form I-6 Page 53 of 62 (Copy as many as needed)		
	Summary Information	
Structural BMP ID No. BMP 26		
Construction Plan Sheet No. C-2		
Type of structural BMP:		
Retention by harvest and use (HU-1)		
Retention by infiltration basin (INF-1)		
Retention by bioretention (INF-2)		
Retention by permeable pavement (INF-3)		
Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)		
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below		
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
Detention pond of vault for hydromodification	1 management	
□ Other (describe in discussion section below)		
Purpose:		
Pollutant control only		
Hydromodification control only		
Combined pollutant control and hydromodification control		
Pre-treatment / forebay for another structural	BMP	
Other (describe in discussion section below		
	Giovanni Posillico, RCE 66332	
Who will certify construction of this BMP?	Latitude 33 Planning & Engineering	
Provide name and contact information for the part responsible to sign BMP verification form DS-563	y 9968 Hibert Street Second Floor San Diego, CA 92131	
responsible to sign bion verification form bo 505	(858) 751-0633	
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	




Form I-6 Page 55 of 62 (Copy as many as needed)		
Structural BMP Su	ummary Information	
Structural BMP ID No. BMP 27		
Construction Plan Sheet No. C-2		
Type of structural BMP:		
Retention by harvest and use (HU-1)		
Retention by infiltration basin (INF-1)		
□ Retention by bioretention (INF-2)		
Retention by permeable pavement (INF-3)		
□ Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)		
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below		
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 		
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below		
Detention pond of vault for hydromodification a	management	
□ Other (describe in discussion section below)		
Purpose:		
Pollutant control only		
Hydromodification control only		
Combined pollutant control and hydromodification control		
Pre-treatment / forebay for another structural B	MP	
Other (describe in discussion section below		
	Giovanni Posillico, RCE 66332	
Who will certify construction of this BMP?	Latitude 33 Planning & Engineering	
Provide name and contact information for the party responsible to sign BMP verification form DS-563	9968 Hibert Street Second Floor San Diego, CA 92131	
responsible to sign bivit vernication form by 505	(858) 751-0633	
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	







Form I-6 Page 57 of 62 (Copy as many as needed)			
	Structural BMP Sur	nmary Information	
Structural BMP ID No. BMP 28			
Construction Plan S	Construction Plan Sheet No. C-2		
Type of structural E	BMP:		
Retention by harvest and use (HU-1)			
\boxtimes Retention by	• • • • •		
□ Retention by			
□ Retention by			
Partial retenti			
□ Biofiltration (
	Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below		
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 			
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below			
Detention por	nd of vault for hydromodification m	nanagement	
D Other (descril	be in discussion section below)		
Purpose:			
Pollutant con	trol only		
Hydromodification control only			
Combined pollutant control and hydromodification control			
	: / forebay for another structural BM	ЯΡ	
Other (descril	be in discussion section below		
		Giovanni Posillico, RCE 66332	
	nstruction of this BMP?	Latitude 33 Planning & Engineering	
	contact information for the party BMP verification form DS-563	9968 Hibert Street Second Floor	
responsible to sign	Divit vermeation form D3-505	San Diego, CA 92131 (858) 751-0633	
		(838) 731-0033	
Who will be the final owner of this BMP?Pathfinder Crown Point Apartments, LLC			
Who will maintain this BMP into perpetuity? Pathfinder Crown Point Apartments, LLC		Pathfinder Crown Point Apartments, LLC	
What is the funding	g mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC	



Form I-6 Page 59 of 62 (Copy as many as needed)			
Structural BMP Summary Information			
Structural BMP ID No. BMP 29			
Construction Plan Sheet No. C-2			
Type of structural BMP:			
Retention by harvest and use (HU-1)			
Retention by infiltration basin (INF-1)			
Retention by bioretention (INF-2)			
□ Retention by permeable pavement (INF-3)	Retention by permeable pavement (INF-3)		
Partial retention by biofiltration with partial reter	Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)			
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below			
Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below)			
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below			
Detention pond of vault for hydromodification r	nanagement		
□ Other (describe in discussion section below)			
Purpose:			
Pollutant control only			
Hydromodification control only			
Combined pollutant control and hydromodificati			
Pre-treatment / forebay for another structural Bl	MI ²		
Other (describe in discussion section below			
	Giovanni Posillico, RCE 66332		
Who will certify construction of this BMP? Provide name and contact information for the party	Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor		
responsible to sign BMP verification form DS-563	San Diego, CA 92131		
	(858) 751-0633		
Who will be the final owner of this BMP?	Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity?	Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC		



Form I-6 Page 61 of 62 (Copy as many as needed)			
Structural BMP Summary Information			
Structural BMP ID No. BMP 30			
Construction Plan Sheet No. C-2			
Type of structural BMP:			
Retention by harvest and use (HU-1)			
Retention by infiltration basin (INF-1)			
Retention by bioretention (INF-2)			
Retention by permeable pavement (INF-3)			
Partial retention by biofiltration with partial retention	Partial retention by biofiltration with partial retention (PR-1)		
□ Biofiltration (BF-1)			
Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (Provide BMP type / Description in discussion section below			
 Flow-thru treatment control included as pre-treatment / forebay for an onsite retention or biofiltration BMP (provide BMP type / description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) 			
Flow-thru treatment control with alternative compliance (provide BMP type / description in discussion section below			
Detention pond of vault for hydromodification n	nanagement		
□ Other (describe in discussion section below)			
Purpose:			
Pollutant control only			
Hydromodification control only			
Combined pollutant control and hydromodificati			
Pre-treatment / forebay for another structural BN	мР		
Other (describe in discussion section below			
	Giovanni Posillico, RCE 66332		
Who will certify construction of this BMP? Provide page and contact information for the party	Latitude 33 Planning & Engineering 9968 Hibert Street Second Floor		
Provide name and contact information for the party responsible to sign BMP verification form DS-563	San Diego, CA 92131		
	(858) 751-0633		
Who will be the final owner of this BMP?	Pathfinder Crown Point Apartments, LLC		
Who will maintain this BMP into perpetuity?	Pathfinder Crown Point Apartments, LLC		
What is the funding mechanism for maintenance?	Pathfinder Crown Point Apartments, LLC		





City of San Diego Development Services 1222 First Ave., MD-302 San Diego, CA 92101 (619) 446-5000

Permanent BMP Construction

Self Certification Form

Date Prepared:	Project No.:
Date Treparea.	110)000110
Project Applicant:	Phone:
roject Applicant.	I none.
Project Address:	
1 Tojeet Muuress.	

Project Engineer:

Phone:

The purpose of this form is to verify that the site improvements for the project, identified above, have been constructed in conformance with the approved Storm Water Quality Management Plan (SWQMP) documents and drawings.

This form must be completed by the engineer and submitted prior to final inspection of the construction permit. Completion and submittal of this form is required for all new development and redevelopment projects in order to comply with the City's Storm Water ordinances and NDPES Permit Order No. R9-2013-0001 as amended by R9-2015-0001 and R9-2015-0100. Final inspection for occupancy and/or release of grading or public improvement bonds may be delayed if this form is not submitted and approved by the City of San Diego.

CERTIFICATION:

As the professional in responsible charge for the design of the above project, I certify that I have inspected all constructed Low Impact Development (LID) site design, source control and structural BMP's required per the approved SWQMP and Construction Permit No.______; and that said BMP's have been constructed in compliance with the approved plans and all applicable specifications, permits, ordinances and Order No. R9-2013-0001 as amended by R9-2015-0001 and R9-2015-0100 of the San Diego Regional Water Quality Control Board.

I understand that this BMP certification statement does not constitute an operation and maintenance verification.

Signature:			
Date of Signature:			
Printed Name:			
Title:			
Phone No.		r	
	DS-563	(01-16)	gineer's Stamp



THIS PAGE INTENTIONALLY LEFT BLANK FOR DOUBLE-SIDED PRINTING



ATTACHMENT 1 BACKUP FOR PDP POLLUTANT CONTROL BMPS

This is the cover sheet for Attachment 1.



THIS PAGE INTENTIONALLY LEFT BLANK FOR DOUBLE-SIDED PRINTING



Indicate which Items are Included:

Attachment Sequence	Contents	Checklist
Attachment 1a	DMA Exhibit (Required) See DMA Exhibit Checklist.	⊠ Included
Attachment 1b	Tabular Summary of DMAs Showing DMA ID matching DMA Exhibit, DMA Area, and DMA Type (Required)* *Provide table in this Attachment OR on DMA Exhibit in Attachment 1a	 Included on DMA Exhibit in Attachment 1a Included as Attachment 1b, separate from DMA Exhibit
Attachment 1c	Form I-7, Harvest and Use Feasibility Screening Checklist (Required unless the entire project will use infiltration BMPs) Refer to Appendix B.3-1 of the BMP Design Manual to complete Form I-7.	 Included Not included because the entire project will use infiltration BMPs
Attachment 1d	Form I-8, Categorization of Infiltration Feasibility Condition (Required unless the project will use harvest and use BMPs) Refer to Appendices C and D of the BMP Design Manual to complete Form I-8.	 Included Not included because the entire project will use harvest and use BMPs
Attachment 1e	Pollutant Control BMP Design Worksheets / Calculations (Required) Refer to Appendices B and E of the BMP Design Manual for structural pollutant control BMP design guidelines and site design credit calculations	⊠ Included





Use this checklist to ensure the required information has been included on the DMA Exhibit:

The DMA Exhibit must identify:

- □ Underlying hydrologic soil group N/A
- Approximate depth to groundwater N/A
- Existing natural hydrologic features (watercourses, seeps, springs, wetlands) N/A
- Critical coarse sediment yield areas to be protected N/A
- Existing topography and impervious areas
- Existing and proposed site drainage network and connections to drainage offsite
- Proposed grading
- \boxtimes Proposed impervious features
- Dependence of the proposed design features and surface treatments used to minimize imperviousness N/A
- ☑ Drainage management area (DMA) boundaries, DMA ID numbers, and DMA areas (square footage or acreage), and DMA type (i.e., drains to BMP, self-retaining, or self-mitigating)
- Potential pollutant source areas and corresponding required source controls (see Chapter 4, Appendix E.1, and Form I-3B) N/A
- Structural BMPs (identify location, type of BMP, and size/detail)







SCALE:	NO SCALE	JOB
	05-15-2017	



Form I-7

1. Is there a demand for harvested water (check all that apply) at the project site that is reliably present during the wet season?

- ☑ Toilet and urinal flushing
- Landscape Irrigation
- Other:

2. If there is a demand; estimate the anticipated average wet season demand over a period of 36 hours. Guidance for planning level demand calculations for toilet/urinal flushing and landscape irrigation is provided in Section B.3.2.

Per Table B.3-1, Residential flushes per day amounts to 18.5/3.45 = 5.36 flushes/day. This is a new development which will employ the use of low-flow toilets. So, (5.36 flushes/day)x(1.6 gallons/flush)x(0.5 WEF) = (4.3 gallons/resident-day)*(126 residents) = (541.8 gallons/day)(541.8 gallons/day)*1.5 = 812.7 gallons 36 hour demand

(812.7 gallons) * (1 cubic foot/7.48 gallons) => 36 Hour Demand = 109 Cubic Feet

Assumed Moderate Plant Water use per Table B3-3.

Landscape = (1,470 gallons/irrigated acre)*(0.34 acres) = 499.8 gallons 36 hour demand(466.8 gallons)*(1 cubic foot/7.48 gallons) => 36 Hour Demand = **62 Cubic Feet**

Total 36 Hour Demand = **171 Cubic Feet**

3. Calculate the DCV using worksheet B-2.1.

DCV= 2,230 cubic feet > 171 cubic feet

0.25 DCV= **557.5 cubic feet > 171 cubic feet**

3a. Is the 36-hour demand greater than or equal to the DCV? Yes / No ➡ ↓	3b. Is the 36-hour demand greater than 0.25 DCV but less than the full DCV? Yes / No ➡ ↓	3c. Is the 36-hour demand less than 0.25DCV? Yes
Harvest and use appears to be feasible. Conduct more detailed evaluation and sizing calculations to confirm that DCV can be used at an adequate rate to meet drawdown criteria.	Harvest and use may be feasible. Conduct more detailed evaluation and sizing calculations to determine feasibility. Harvest and use may only be able to be used for a portion of the site, or (optionally) the storage may need to be upsized to meet long term capture targets while draining in longer than 36 hours.	Harvest and use is considered to be infeasible.
Is harvest and use feasible based on □ Yes, refer to appendix E to sele ⊠ No, select alternate BMPs	further evaluation? ect and size harvest and use BMPs	

Worksheet C.4-1: Categorization of Infiltration Feasibility Condition

Categ	Categorization of Infiltration Feasibility Condition Worksheet C.4-1					
Would in consequ Note th preclude	Full Infiltration Feasibility Screening Criteria Infiltration of the full design volume be feasible from a physical pers ences that cannot be reasonably mitigated? at it is not necessary to investigate each and every criterion in d. Instead a letter of justification from a geotechnical professional f iating any geotechnical issues will be required.	the workshee	t if infiltration is			
Criteria	Screening Question	Yes	No			
1	Is the estimated reliable infiltration rate below proposed facility locations greater than 0.5 inches per hour? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.2 and Appendix D.	X				
	n study conducted by Geocon (2016) was calculated to be more than 0.3 a minimum factor of safety. I-1: 7.5 in/hr (3.75 in/hr with a FOS of 2) I-2: 11.3 in/hr (5.7 in/hr with a FOS of 2) I-3: 12.0 in/hr (6.0 in/hr with a FOS of 2) I-4: 13.7 in/hr (6.9 in/hr with a FOS of 2)	o inches per hou	r after			
	Geocon (2016)					
2	Can infiltration greater than 0.5 inches per hour be allowed without increasing risk of geotechnical hazards (slope stability, groundwater mounding, utilities, or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.2.	X				
Provide l		L	1			
C2.2 Afta exhibit n C2.3 No C2.4 BM C2.5 Sto groundw grade. C2.6 BM C2.7 Oth	eologic investigation was performed at the subject site by Geocon 2016 er the investigation performed by NOVA 2017, the findings support the ju- egligible compression upon saturation. slopes are within close proximity to the site. Ps should be at minimum of 10 feet from any utilities. rmwater infiltration can result in damaging ground water mounding dur ater elevations were estimated by Geocon to be at depths greater than 3 Ps should be at a minimum of 10 feet from retaining walls and foundation ere Factors: After evaluating the compressibility, depth of testing, and so hat the site is capable of full infiltration.	udgment that th ing wet periods 0 feet below exi ons.	e site will , however sting			

	Worksheet C.4-1 Page 2 of 4		
Criteria	Screening Question	Yes	No
3	Can infiltration greater than 0.5 inches per hour be allowed without increasing risk of groundwater contamination (shallow water table, storm water pollutants or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.3.		
Provide	basis: contamination was not evaluated by Geocon nor NOVA services.	I.	
	Can infiltration greater than 0.5 inches per hour be allowed without causing potential water balance issues such as change of seasonality of ephemeral streams or increased discharge of		
4	contaminated groundwater to surface waters? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.3.		
Provide <i>The pote</i>	basis: ntial for water balance was not evaluated by Geocon nor NOVA services.		
Part 1	If all answers to rows 1 - 4 are " Yes " a full infiltration design is potential. The feasibility screening category is Full Infiltration		YES
Result*	If any answer from row 1-4 is " No ", infiltration may be possible to some would not generally be feasible or desirable to achieve a "full infiltration" Proceed to Part 2		

*To be completed using gathered site information and best professional judgment considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by County staff to substantiate findings.

1	Worksheet C.4-1 Page 3 of 4							
<u>Part 2 – P</u>	artial Infiltration vs. No Infiltration Feasibility Screening Criteria							
Would ir	Would infiltration of water in any appreciable amount be physically feasible without any negative consequences that cannot be reasonably mitigated?							
Criteria	Screening Question	Yes	No					
5	Do soil and geologic conditions allow for infiltration in any appreciable rate or volume? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.2 and Appendix D.	Х						
Provide ba	asis: <i>See criteria 1.</i>							
6	Can Infiltration in any appreciable quantity be allowed without increasing risk of geotechnical hazards (slope stability, groundwater mounding, utilities, or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.2.	Х						
Provide b	asis: <i>See criteria 2</i> .							

Worksheet C.4-1 Page 4 of 4						
Criteria	Screening Question	Yes	No			
7	Can Infiltration in any appreciable quantity be allowed without posing significant risk for groundwater related concerns (shallow water table, storm water pollutants or other factors)? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.3.					
Provide basis: Water contamination was not evaluated by Geocon nor NOVA services.						
8	Can infiltration be allowed without violating downstream water rights ? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.3.					
Provide basis: The potential for water balance was not evaluated by Geocon nor NOVA services.						
Part 2 Result*						

*To be completed using gathered site information and best professional judgment considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by Agency/Jurisdictions to substantiate findings

Shasta East DMA 1 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C·A (ac)	% DCV
Hardscape	1446.78	0.033213	0.90	0.030	96.8%
Landscape	428.37	0.009834	0.10	0.000983	3.2%
TOTAL	1875.15	0.04	1.00	0.03	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches	
2	Area tributary to BMP (s)	A=		acres	
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless	
4	Street trees volume reduction	TCV=		cubic-feet	
5	Rain barrels volume reduction	RCV=		cubic-feet	
	Calculate DCV =				
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet	

Worksheet B.2-1. DCV

	Design Capture Volume		Norksheet B-	2.1
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches
2	AREA TRIBUTARY TO BMP (s)	A=	0.04	acres
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.72	unitless
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	57.16	cubic-feet

	Design Capture Volume	V	Worksheet B-4.1			
1	DCV (Worksheet B-2.1)	DCV=	57.16	cubic-feet		
2	Estimated design infiltration rate (Worksheet D.5-1)	Kdesign=	3.75	in/hr		
3	Available BMP surface area	ABMP=	10.00	sq-ft		
4	Average Effective Depth in the BMP footprint (DCV/ABMP)	Davg=	5.72	feet		
5	Drawdown time, T (Davg*12/Kdesign)	Т=	18.29	hours		
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 2 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	C	C·A (ac)	% DCV
Hardscape	1962.37	0.04505	0.90	0.041	95.1%
Landscape	914.95	0.021004	0.10	0.0021	4.9%
TOTAL	2877.32	0.07	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=	in	ches	
2	Area tributary to BMP (s)	A=	a	cres	
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=	u	nitless	
4	Street trees volume reduction	TCV=	ci	abic-feet	
5	Rain barrels volume reduction	RCV=	c	ibic-feet	
	Calculate DCV =				
6	(3630 x C x d x A) – TCV - RCV	DCV=	ci	abic-feet	

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.07	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.65	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	78.95	cubic-feet	

	Design Capture Volume			Worksheet B-4.1		
1	DCV (Worksheet B-2.1)			DCV=	78.95	cubic-feet
2	Estimated design infiltration rate (Worksheet D	0.5-1)		Kdesign=	3.75	in/hr
3	Available BMP surface area			Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint (DCV/ABMP)		Davg=	7.89	feet	
5	Drawdown time, T (Davg*12/Kdesign)			T=	25.26	hours
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 3 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1947.80	0.044715	0.90	0.040	97.6%
Landscape	428.34	0.009833	0.10	0.000983	2.4%
TOTAL	2376.14	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume		Worksheet B-2.1				
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches			
2	Area tributary to BMP (s)	A=		acres			
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless			
4	Street trees volume reduction	TCV=		cubic-feet			
5	Rain barrels volume reduction	RCV=		cubic-feet			
	Calculate DCV =						
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet			

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.76	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.32	cubic-feet	

	Design Capture Volume			Worksheet B-4.1		
1	DCV (Worksheet B-2.1)			DCV=	76.32	cubic-feet
2	Estimated design infiltration rate (Worksheet D.	5-1)		Kdesign=	3.75	in/hr
3	Available BMP surface area			Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint (DCV/ABMP)		Davg=	7.63	feet	
5	Drawdown time, T (Davg*12/Kdesign)			T=	24.42	hours
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 4 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1912.68	0.043909	0.90	0.040	97.4%
Landscape	463.37	0.010638	0.10	0.001064	2.6%
TOTAL	2376.05	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume		Worksheet B-2.1				
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches			
2	Area tributary to BMP (s)	A=		acres			
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless			
4	Street trees volume reduction	TCV=		cubic-feet			
5	Rain barrels volume reduction	RCV=		cubic-feet			
	Calculate DCV =						
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet			

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.74	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	75.13	cubic-feet	

	Design Capture Volume			Worksheet B-4.1		
1	DCV (Worksheet B-2.1)		DCV=	75.13	cubic-feet	
2	Estimated design infiltration rate (Worksheet D.5-1)		Kdesign=	3.75	in/hr	
3	Available BMP surface area		ABMP=	10.00	sq-ft	
4	Average Effective Depth in the BMP footprint (DCV/A	Average Effective Depth in the BMP footprint (DCV/ABMP)		7.51	feet	
5	Drawdown time, T (Davg*12/Kdesign)		T=	24.04	hours	
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 5 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1954.74	0.044875	0.90	0.040	97.7%
Landscape	421.23	0.00967	0.10	0.000967	2.3%
TOTAL	2375.97	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume		Worksheet B-2.1			
1	85 th percentile 24-hr storm depth from Figure B.1-1	d=	i	inches		
2	Area tributary to BMP (s)	A=	:	acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=	,	unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.76	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.56	cubic-feet	

	Design Capture Volume			Worksheet B-4.1			
1	DCV (Worksheet B-2.1)		DCV=	76.56	cubic-feet		
2	Estimated design infiltration rate (Worksheet D.5-1)		Kdesign=	3.75	in/hr		
3	Available BMP surface area		Авмр=	10.00	sq-ft		
4	Average Effective Depth in the BMP footprint (DCV/ABMP)			7.66	feet		
5	Drawdown time, T (Davg*12/Kdesign)		T=	24.50	hours		
6	Provide alternative calculation of drawdown time, if needed.						

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 6 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C·A (ac)	% DCV
Hardscape	1975.74	0.045357	0.90	0.041	97.8%
Landscape	400.14	0.009186	0.10	0.000919	2.2%
TOTAL	2375.88	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume		Worksheet B-2.1				
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches			
2	Area tributary to BMP (s)	A=		acres			
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless			
4	Street trees volume reduction	TCV=		cubic-feet			
5	Rain barrels volume reduction	RCV=		cubic-feet			
	Calculate DCV =						
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet			

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.77	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	77.27	cubic-feet	

	Design Capture Volume	V	Worksheet B-4.1			
1	DCV (Worksheet B-2.1)	DCV=	77.27	cubic-feet		
2	Estimated design infiltration rate (Worksheet D.5-1)	Kdesign=	3.75	in/hr		
3	Available BMP surface area	ABMP=	10.00	sq-ft		
4	Average Effective Depth in the BMP footprint (DCV/ABMP)	Davg=	7.73	feet		
5	Drawdown time, T (Davg*12/Kdesign)	T=	24.73	hours		
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 7 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1955.17	0.044885	0.90	0.040	97.7%
Landscape	420.61	0.009656	0.10	0.000966	2.3%
TOTAL	2375.78	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume		Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.76	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.57	cubic-feet	

	Design Capture Volume				W	/orksheet B-	4.1
1	DCV (Worksheet B-2.1)				DCV=	76.57	cubic-feet
2	Estimated design infiltration rate (Worksheet	D.5-1)			Kdesign=	3.75	in/hr
3	Available BMP surface area				ABMP=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint (DCV/ABMP)				Davg=	7.66	feet
5	Drawdown time, T (Davg*12/Kdesign)				T=	24.50	hours
6	Provide alternative calculation of drawdown time, if needed.						

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 8 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1957.49	0.044938	0.90	0.040	97.7%
Landscape	418.21	0.009601	0.10	0.00096	2.3%
TOTAL	2375.70	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume		Worksheet B-2.1				
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches			
2	Area tributary to BMP (s)	A=		acres			
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless			
4	Street trees volume reduction	TCV=		cubic-feet			
5	Rain barrels volume reduction	RCV=		cubic-feet			
	Calculate DCV =						
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet			

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.76	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.65	cubic-feet	

	Design Capture Volume			Worksheet B-4.1		
1	DCV (Worksheet B-2.1)		DCV=	76.65	cubic-feet	
2	Estimated design infiltration rate (Worksheet D.5-1)		Kdesign=	3.75	in/hr	
3	Available BMP surface area		Авмр=	10.00	sq-ft	
4	Average Effective Depth in the BMP footprint (DCV/ABMP)		Davg=	7.67	feet	
5	Drawdown time, T (Davg*12/Kdesign)		T=	24.53	hours	
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 9 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1783.02	0.040933	0.90	0.037	96.4%
Landscape	592.59	0.013604	0.10	0.00136	3.6%
TOTAL	2375.61	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Worksheet D.2-1. DOV						
	Design Capture Volume	Worksheet B-2.1					
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches			
2	Area tributary to BMP (s)	A=		acres			
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless			
4	Street trees volume reduction	TCV=		cubic-feet			
5	Rain barrels volume reduction	RCV=		cubic-feet			
	Calculate DCV =						
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet			

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.70	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	70.72	cubic-feet	

	Design Capture Volume				/orksheet B-	4.1
1	DCV (Worksheet B-2.1)			DCV=	70.72	cubic-feet
2	Estimated design infiltration rate (Worksheet	D.5-1)		Kdesign=	3.75	in/hr
3	Available BMP surface area			Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint (DCV/ABMP)		Davg=	7.07	feet	
5	Drawdown time, T (Davg*12/Kdesign)			T=	22.63	hours
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 10 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1953.50	0.044846	0.90	0.040	97.7%
Landscape	422.03	0.009688	0.10	0.000969	2.3%
TOTAL	2375.53	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	Worksheet B-2.1					
1	85th percentile 24-hr storm depth from Figure B.1-1	d=	inches				
2	Area tributary to BMP (s)	A=	acres				
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=	unitless				
4	Street trees volume reduction	TCV=	cubic-feet				
5	Rain barrels volume reduction	RCV=	cubic-feet				
	Calculate DCV =						
6	(3630 x C x d x A) – TCV - RCV	DCV=	cubic-feet				

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.76	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.52	cubic-feet	

	Design Capture Volume			Worksheet B-4.1		
1	DCV (Worksheet B-2.1)		DCV=	76.52	cubic-feet	
2	Estimated design infiltration rate (Worksheet D.5-1)		Kdesign=	3.75	in/hr	
3	Available BMP surface area		Авмр=	10.00	sq-ft	
4	Average Effective Depth in the BMP footprint (DCV/ABMP)		Davg=	7.65	feet	
5	Drawdown time, T (Davg*12/Kdesign)		T=	24.48	hours	
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 11 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1960.69	0.045011	0.90	0.041	97.7%
Landscape	414.75	0.009521	0.10	0.000952	2.3%
TOTAL	2375.44	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	X	Worksheet B-2.1				
1	85 th percentile 24-hr storm depth from Figure B.1-1	d=	i	inches			
2	Area tributary to BMP (s)	A=		acres			
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=	,	unitless			
4	Street trees volume reduction	TCV=		cubic-feet			
5	Rain barrels volume reduction	RCV=		cubic-feet			
	Calculate DCV =						
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet			

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.76	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.76	cubic-feet	

	Design Capture Volume				Worksheet B-4.1		
1	DCV (Worksheet B-2.1)			DCV=	76.76	cubic-feet	
2	Estimated design infiltration rate (Worksheet	D.5-1)		Kdesign=	3.75	in/hr	
3	Available BMP surface area			ABMP=	10.00	sq-ft	
4	Average Effective Depth in the BMP footprint	(DCV/Abmp)		Davg=	7.68	feet	
5	Drawdown time, T (Davg*12/Kdesign)			T=	24.56	hours	
6	Provide alternative calculation of drawdown time, if needed.						

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 12 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1937.68	0.044483	0.90	0.040	97.6%
Landscape	437.67	0.010048	0.10	0.001005	2.4%
TOTAL	2375.35	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume		Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.75	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	75.98	cubic-feet	

	Design Capture Volume				Worksheet B-4.1		
1	DCV (Worksheet B-2.1)				DCV=	75.98	cubic-feet
2	Estimated design infiltration rate (Worksheet	D.5-1)			Kdesign=	3.75	in/hr
3	Available BMP surface area				Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint (DCV/ABMP)			Davg=	7.60	feet	
5	Drawdown time, T (Davg*12/Kdesign)				T=	24.31	hours
6	Provide alternative calculation of drawdown time, if needed.						

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 13 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C·A (ac)	% DCV
Hardscape	1808.22	0.041511	0.90	0.037	96.6%
Landscape	567.05	0.013018	0.10	0.001302	3.4%
TOTAL	2375.27	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume		Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.71	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	71.57	cubic-feet	

	Design Capture Volume				Worksheet B-4.1		
1	DCV (Worksheet B-2.1)			DCV=	71.57	cubic-feet	
2	Estimated design infiltration rate (Worksheet D	0.5-1)		Kdesign=	3.75	in/hr	
3	Available BMP surface area			Авмр=	10.00	sq-ft	
4	Average Effective Depth in the BMP footprint (DCV/ABMP)			Davg=	7.16	feet	
5	Drawdown time, T (Davg*12/Kdesign)			T=	22.90	hours	
6	Provide alternative calculation of drawdown time, if needed.						

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 14 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1941.10	0.044562	0.90	0.040	97.6%
Landscape	434.08	0.009965	0.10	0.000997	2.4%
TOTAL	2375.18	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume		Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.75	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.09	cubic-feet	

	Design Capture Volume	۷	Worksheet B-4.1		
1	DCV (Worksheet B-2.1)	DCV=	76.09	cubic-feet	
2	Estimated design infiltration rate (Worksheet D.5-1)		3.75	in/hr	
3	Available BMP surface area	ABMP=	10.00	sq-ft	
4	Average Effective Depth in the BMP footprint (DCV/ABMP)	Davg=	7.61	feet	
5	Drawdown time, T (Davg*12/Kdesign)	T=	24.35	hours	
6	Provide alternative calculation of drawdown time, if needed.				

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 15 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C·A (ac)	% DCV
Hardscape	1947.06	0.044698	0.90	0.040	97.6%
Landscape	428.03	0.009826	0.10	0.000983	2.4%
TOTAL	2375.09	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume		Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.76	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.29	cubic-feet	

Design Capture Volume				Worksheet B-4.1			
1	DCV (Worksheet B-2.1)				DCV=	76.29	cubic-feet
2	Estimated design infiltration rate (Worksheet	D.5-1)			Kdesign=	3.75	in/hr
3	Available BMP surface area				Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint	(DCV/ABMP)			Davg=	7.63	feet
5	Drawdown time, T (Davg*12/Kdesign)				T=	24.41	hours
6	Provide alternative calculation of drawdown time, if needed.						

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 16 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1975.87	0.04536	0.90	0.041	97.8%
Landscape	399.13	0.009163	0.10	0.000916	2.2%
TOTAL	2375.00	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	v	Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume	Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.77	unitless
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	77.27	cubic-feet

	Design Capture Volume			Worksheet B-4.1		
1	DCV (Worksheet B-2.1)			DCV=	77.27	cubic-feet
2	Estimated design infiltration rate (Worksheet	D.5-1)		Kdesign=	3.75	in/hr
3	Available BMP surface area			Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint	(DCV/Abmp)		Davg=	7.73	feet
5	Drawdown time, T (Davg*12/Kdesign)			T=	24.73	hours
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 17 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1979.76	0.045449	0.90	0.041	97.8%
Landscape	395.15	0.009071	0.10	0.000907	2.2%
TOTAL	2374.91	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	x	Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume	Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.77	unitless
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	77.41	cubic-feet

	Design Capture Volume			Worksheet B-4.1		
1	DCV (Worksheet B-2.1)			DCV=	77.41	cubic-feet
2	Estimated design infiltration rate (Worksheet I	0.5-1)		Kdesign=	3.75	in/hr
3	Available BMP surface area			Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint (DCV/Авмр)		Davg=	7.74	feet
5	Drawdown time, T (Davg*12/Kdesign)			T=	24.77	hours
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 18 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1923.88	0.044166	0.90	0.040	97.5%
Landscape	450.95	0.010352	0.10	0.001035	2.5%
TOTAL	2374.83	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	v	Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume	Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.75	unitless
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	75.50	cubic-feet

	Design Capture Volume				Worksheet B-4.1		
1	DCV (Worksheet B-2.1)		DCV=	75.50	cubic-feet		
2	Estimated design infiltration rate (Worksheet D.5-1)		Kdesign=	3.75	in/hr		
3	Available BMP surface area		ABMP=	10.00	sq-ft		
4	Average Effective Depth in the BMP footprint (DCV/A	вмр)	Davg=	7.55	feet		
5	Drawdown time, T (Davg*12/Kdesign)		T=	24.16	hours		
6	Provide alternative calculation of drawdown time, if needed.						

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 19 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1946.52	0.044686	0.90	0.040	97.6%
Landscape	428.22	0.009831	0.10	0.000983	2.4%
TOTAL	2374.74	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	V	Worksheet B-2.1				
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches			
2	Area tributary to BMP (s)	A=		acres			
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless			
4	Street trees volume reduction	TCV=		cubic-feet			
5	Rain barrels volume reduction	RCV=		cubic-feet			
	Calculate DCV =						
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet			

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.76	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.27	cubic-feet	

	Design Capture Volume			Worksheet B-4.1		
1	DCV (Worksheet B-2.1)			DCV=	76.27	cubic-feet
2	Estimated design infiltration rate (Worksheet	D.5-1)		Kdesign=	3.75	in/hr
3	Available BMP surface area			Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint	(DCV/Авмр)		Davg=	7.63	feet
5	Drawdown time, T (Davg*12/Kdesign)			T=	24.41	hours
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 20 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1964.61	0.045101	0.90	0.041	97.7%
Landscape	410.05	0.009413	0.10	0.000941	2.3%
TOTAL	2374.66	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	V	Worksheet B-2.1				
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches			
2	Area tributary to BMP (s)	A=		acres			
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless			
4	Street trees volume reduction	TCV=		cubic-feet			
5	Rain barrels volume reduction	RCV=		cubic-feet			
	Calculate DCV =						
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet			

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.76	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.89	cubic-feet	

	Design Capture Volume			-4.1		
1	DCV (Worksheet B-2.1)	DCV=	76.89	cubic-feet		
2	Estimated design infiltration rate (Worksheet D.5-1)	Kdesign=	3.75	in/hr		
3	Available BMP surface area	ABMP=	10.00	sq-ft		
4	Average Effective Depth in the BMP footprint (DCV/ABMP)	Davg=	7.69	feet		
5	Drawdown time, T (Davg*12/Kdesign)	T=	24.60	hours		
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 21 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	C	C·A (ac)	% DCV
Hardscape	1808.22	0.041511	0.90	0.037	96.6%
Landscape	566.35	0.013002	0.10	0.0013	3.4%
TOTAL	2374.57	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	x	Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.71	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	71.57	cubic-feet	

	Design Capture Volume			Worksheet B-4.1		
1	DCV (Worksheet B-2.1)			DCV=	71.57	cubic-feet
2	Estimated design infiltration rate (Worksheet D	0.5-1)		Kdesign=	3.75	in/hr
3	Available BMP surface area			Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint (DCV/Авмр)		Davg=	7.16	feet
5	Drawdown time, T (Davg*12/Kdesign)			T=	22.90	hours
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 22 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1921.67	0.044115	0.90	0.040	97.4%
Landscape	452.81	0.010395	0.10	0.00104	2.6%
TOTAL	2374.48	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	V	Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=	inches			
2	Area tributary to BMP (s)	A=	acres			
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=	unitless			
4	Street trees volume reduction	TCV=	cubic-feet			
5	Rain barrels volume reduction	RCV=	cubic-feet			
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=	cubic-feet			

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.75	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	75.43	cubic-feet	

	Design Capture Volume			V	/orksheet B-	4.1
1	DCV (Worksheet B-2.1)			DCV=	75.43	cubic-feet
2	Estimated design infiltration rate (Worksheet I	0.5-1)		Kdesign=	3.75	in/hr
3	Available BMP surface area			Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint (DCV/Авмр)		Davg=	7.54	feet
5	Drawdown time, T (Davg*12/Kdesign)			T=	24.14	hours
6	Provide alternative calculation of drawdown ti	me, if needed.	•			

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 23 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1447.11	0.033221	0.90	0.030	96.7%
Landscape	438.35	0.010063	0.10	0.001006	3.3%
TOTAL	1885.46	0.04	1.00	0.03	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	x	Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.04	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.71	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	57.21	cubic-feet	

	Design Capture Volume			-4.1		
1	DCV (Worksheet B-2.1)	DCV=	57.21	cubic-feet		
2	Estimated design infiltration rate (Worksheet D.5-1)	Kdesign=	3.75	in/hr		
3	Available BMP surface area	ABMP=	10.00	sq-ft		
4	Average Effective Depth in the BMP footprint (DCV/ABMP)	Davg=	5.72	feet		
5	Drawdown time, T (Davg*12/Kdesign)	T=	18.31	hours		
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 24 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C·A (ac)	% DCV
Hardscape	1958.32	0.044957	0.90	0.040	95.1%
Landscape	906.04	0.0208	0.10	0.00208	4.9%
TOTAL	2864.36	0.07	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	X	Worksheet B-2.1			
1	85 th percentile 24-hr storm depth from Figure B.1-1	d=	i	inches		
2	Area tributary to BMP (s)	A=	:	acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=	,	unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.07	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.65	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	78.76	cubic-feet	

	Design Capture Volume			/orksheet B-	4.1
1	DCV (Worksheet B-2.1)		DCV=	78.76	cubic-feet
2	Estimated design infiltration rate (Worksheet D.5-1)		Kdesign=	3.75	in/hr
3	Available BMP surface area		Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint (DCV/ABMP)		Davg=	7.88	feet
5	Drawdown time, T (Davg*12/Kdesign)		T=	25.20	hours
6	Provide alternative calculation of drawdown time, if needed.				

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 25 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1457.62	0.033462	0.90	0.030	96.8%
Landscape	437.51	0.010044	0.10	0.001004	3.2%
TOTAL	1895.13	0.04	1.00	0.03	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	X	Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=	in	ches		
2	Area tributary to BMP (s)	A=	a	cres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=	u	nitless		
4	Street trees volume reduction	TCV=	ci	abic-feet		
5	Rain barrels volume reduction	RCV=	c	ibic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=	ci	abic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume	Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches
2	AREA TRIBUTARY TO BMP (s)	A=	0.04	acres
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.72	unitless
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	57.61	cubic-feet

	Design Capture Volume				Worksheet B-4.1		
1	DCV (Worksheet B-2.1)			DCV=	57.61	cubic-feet	
2	Estimated design infiltration rate (Worksheet D	0.5-1)		Kdesign=	3.75	in/hr	
3	Available BMP surface area			Авмр=	10.00	sq-ft	
4	Average Effective Depth in the BMP footprint (I	DCV/Авмр)		Davg=	5.76	feet	
5	Drawdown time, T (Davg*12/Kdesign)			T=	18.44	hours	
6	Provide alternative calculation of drawdown time, if needed.						

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 26 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1959.33	0.04498	0.90	0.040	95.2%
Landscape	895.71	0.020563	0.10	0.002056	4.8%
TOTAL	2855.04	0.07	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	V	Worksheet B-2.1				
1	85th percentile 24-hr storm depth from Figure B.1-1	d=	inches				
2	Area tributary to BMP (s)	A=	acres				
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=	unitless				
4	Street trees volume reduction	TCV=	cubic-feet				
5	Rain barrels volume reduction	RCV=	cubic-feet				
	Calculate DCV =						
6	(3630 x C x d x A) – TCV - RCV	DCV=	cubic-feet				

Worksheet B.2-1. DCV

	Design Capture Volume	Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches
2	AREA TRIBUTARY TO BMP (s)	A=	0.07	acres
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.65	unitless
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	78.75	cubic-feet

	Design Capture Volume			-4.1		
1	DCV (Worksheet B-2.1)	DCV=	78.75	cubic-feet		
2	Estimated design infiltration rate (Worksheet D.5-1)	Kdesign=	3.75	in/hr		
3	Available BMP surface area	ABMP=	10.00	sq-ft		
4	Average Effective Depth in the BMP footprint (DCV/ABMP)	Davg=	7.88	feet		
5	Drawdown time, T (Davg*12/Kdesign)	T=	25.20	hours		
6	Provide alternative calculation of drawdown time, if needed.					

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 27 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1966.37	0.045142	0.90	0.041	97.7%
Landscape	408.80	0.009385	0.10	0.000938	2.3%
TOTAL	2375.17	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	v	Worksheet B-2.1				
1	85th percentile 24-hr storm depth from Figure B.1-1	d=	inches				
2	Area tributary to BMP (s)	A=	acres				
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=	unitless				
4	Street trees volume reduction	TCV=	cubic-feet				
5	Rain barrels volume reduction	RCV=	cubic-feet				
	Calculate DCV =						
6	(3630 x C x d x A) – TCV - RCV	DCV=	cubic-feet				

Worksheet B.2-1. DCV

	Design Capture Volume	Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.76	unitless
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.95	cubic-feet

	Design Capture Volume				Worksheet B-4.1		
1	DCV (Worksheet B-2.1)			DCV=	76.95	cubic-feet	
2	Estimated design infiltration rate (Worksheet	D.5-1)		Kdesign=	3.75	in/hr	
3	Available BMP surface area			ABMP=	10.00	sq-ft	
4	Average Effective Depth in the BMP footprint	(DCV/ABMP)		Davg=	7.70	feet	
5	Drawdown time, T (Davg*12/Kdesign)			T=	24.62	hours	
6	Provide alternative calculation of drawdown time, if needed.						

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 28 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1947.82	0.044716	0.90	0.040	97.6%
Landscape	427.42	0.009812	0.10	0.000981	2.4%
TOTAL	2375.24	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	v	Worksheet B-2.1			
1	85th percentile 24-hr storm depth from Figure B.1-1	d=	inches			
2	Area tributary to BMP (s)	A=	acres			
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=	unitless			
4	Street trees volume reduction	TCV=	cubic-feet			
5	Rain barrels volume reduction	RCV=	cubic-feet			
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=	cubic-feet			

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.76	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	76.32	cubic-feet	

	Design Capture Volume			-4.1	
1	DCV (Worksheet B-2.1)	DCV=	76.32	cubic-feet	
2	Estimated design infiltration rate (Worksheet D.5-1)	Kdesign=	3.75	in/hr	
3	Available BMP surface area	ABMP=	10.00	sq-ft	
4	Average Effective Depth in the BMP footprint (DCV/ABMP)	Davg=	7.63	feet	
5	Drawdown time, T (Davg*12/Kdesign)	T=	24.42	hours	
6	Provide alternative calculation of drawdown time, if needed.				

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 29 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	2014.29	0.046242	0.90	0.042	98.0%
Landscape	361.01	0.008288	0.10	0.000829	2.0%
TOTAL	2375.30	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	Worksheet B-2.1				
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.78	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	78.58	cubic-feet	

	Design Capture Volume			V	/orksheet B-	4.1
1	DCV (Worksheet B-2.1)			DCV=	78.58	cubic-feet
2	Estimated design infiltration rate (Worksheet D	0.5-1)		Kdesign=	3.75	in/hr
3	Available BMP surface area			Авмр=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint (I	DCV/Авмр)		Davg=	7.86	feet
5	Drawdown time, T (Davg*12/Kdesign)			T=	25.15	hours
6	Provide alternative calculation of drawdown tir	ne, if needed.				

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).

The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

Shasta East DMA 30 DESIGN CAPTURE VOLUME

Use	Area (SF)	Area (ac)	С	C∙A (ac)	% DCV
Hardscape	1983.66	0.045539	0.90	0.041	97.9%
Landscape	391.70	0.008992	0.10	0.000899	2.1%
TOTAL	2375.36	0.05	1.00	0.04	100%

B.1.1 Runoff Factor

Estimate the area weighted runoff factor for the tributary area to the BMP using runoff factor (from Table B.1-1) and area of each surface type in the tributary area and the following equation:

$$C = \frac{\sum C_x A_x}{\sum A_x}$$

	Design Capture Volume	Worksheet B-2.1				
1	85th percentile 24-hr storm depth from Figure B.1-1	d=		inches		
2	Area tributary to BMP (s)	A=		acres		
3	Area weighted runoff factor (estimate using Appendix B.1.1 and B.2.1)	C=		unitless		
4	Street trees volume reduction	TCV=		cubic-feet		
5	Rain barrels volume reduction	RCV=		cubic-feet		
	Calculate DCV =					
6	(3630 x C x d x A) – TCV - RCV	DCV=		cubic-feet		

Worksheet B.2-1. DCV

	Design Capture Volume		Worksheet B-2.1		
1	85TH PERCENTILE 24-HR STORM	D=	0.51	inches	
2	AREA TRIBUTARY TO BMP (s)	A=	0.05	acres	
3	AREA WEIGHTED RUNOFF FACTOR (ESTIMATE USING APPENDIX B.1.1 AND B.2.1)	C=	0.77	unitless	
4	STREET TREES VOLUME REDUCTION	TCV=	-	cubic-feet	
5	RAIN BARRELS VOLUME REDUCTION	RCV=	-	cubic-feet	
6	CALCULATE DCV=(3630 X C X D X A) - TCV - RCV	DCV=	77.54	cubic-feet	

	Design Capture Volume			/orksheet B	-4.1
1	DCV (Worksheet B-2.1)		DCV=	77.54	cubic-feet
2	Estimated design infiltration rate (Worksheet D.5-1)		Kdesign=	3.75	in/hr
3	Available BMP surface area		ABMP=	10.00	sq-ft
4	Average Effective Depth in the BMP footprint (DCV/ABMP)		Davg=	7.75	feet
5	Drawdown time, T (Davg*12/Kdesign)		T=	24.81	hours
6	Provide alternative calculation of drawdown time, if needed.				

Notes:

Drawdown time must be less than 36 hours. This criterion was set to achieve average annual capture of 80% to account for back to back storms (See rationale in section B.4.3). In order to use a different drawdown time, BMPs should be sized using the percent capture method (Section B.4.2).


The average effective depth calculation should account for any aggregate/media in the BMP. For example, 4 feet of stone at a porosity of 0.4 would equate to 1.6 feet of effective depth.

ATTACHMENT 2 BACKUP FOR PDP HYDROMODIFICATION CONTROL MEASURES

This is the cover sheet for Attachment 2.

Mark this box if this attachment is empty because the project is exempt from PDP hydromodification management requirements.







MISSION BAY PARK

CORONA ORIENTE RD



THIS PAGE INTENTIONALLY LEFT BLANK FOR DOUBLE-SIDED PRINTING



ATTACHMENT 3 STRUCTURAL BMP MAINTENANCE INFORMATION

This is the cover sheet for Attachment 3.



THIS PAGE INTENTIONALLY LEFT BLANK FOR DOUBLE-SIDED PRINTING



Indicate which Items are Included:

Attachment Sequence	Contents	Checklist
Attachment 3a	Structural BMP Maintenance Thresholds and Actions (Required)	⊠ Included See Structural BMP Maintenance Information Checklist.
Attachment 3b	Maintenance Agreement (Form DS- 3247) (when applicable)	⊠ Included □ Not Applicable



THIS PAGE INTENTIONALLY LEFT BLANK FOR DOUBLE-SIDED PRINTING



Use this checklist to ensure the required information has been included in the Structural BMP Maintenance Information Attachment:

Preliminary Design / Planning / CEQA level submittal:

- Attachment 3a must identify:
 - Typical maintenance indicators and actions for proposed structural BMP(s) based on Section 7.7 of the BMP Design Manual
- Attachment 3b is not required for preliminary design / planning / CEQA level submittal.



Final Design level submittal:

Attachment 3a must identify:

- □ Specific maintenance indicators and actions for proposed structural BMP(s). This shall be based on Section 7.7 of the BMP Design Manual and enhanced to reflect actual proposed components of the structural BMP(s)
- How to access the structural BMP(s) to inspect and perform maintenance
- ☐ Features that are provided to facilitate inspection (e.g., observation ports, cleanouts, silt posts, or other features that allow the inspector to view necessary components of the structural BMP and compare to maintenance thresholds)
- ☐ Manufacturer and part number for proprietary parts of structural BMP(s) when applicable
- ☐ Maintenance thresholds specific to the structural BMP(s), with a location-specific frame of reference (e.g., level of accumulated materials that triggers removal of the materials, to be identified based on viewing marks on silt posts or measured with a survey rod with respect to a fixed benchmark within the BMP)
- □ When applicable, frequency of bioretention soil media replacement.
- Recommended equipment to perform maintenance
- □ When applicable, necessary special training or certification requirements for inspection and maintenance personnel such as confined space entry or hazardous waste management

Attachment 3b: For private entity operation and maintenance, Attachment 3b must include a Storm Water Management and Discharge Control Maintenance Agreement (Form DS-3247). The following information must be included in the exhibits attached to the maintenance agreement:

- □ Vicinity map
- □ Site design BMPs for which DCV reduction is claimed for meeting the pollutant control obligations.
- BMP and HMP location and dimensions
- BMP and HMP specifications/cross section/model
- ☐ Maintenance recommendations and frequency
- LID features such as (permeable paver and LS location, dim, SF).



Typical Maintenance Indicator(s) for Vegetated BMPs	Maintenance Actions
Accumulation of sediment, litter, or debris	Remove and properly dispose of accumulated materials, without damage to the vegetation.
Poor vegetation establishment	Re-seed, re-plant, or re-establish vegetation per original plans.
Overgrown vegetation	Mow or trim as appropriate, but not less than the design height of the vegetation per original plans when applicable (e.g. a vegetated swale may require a minimum vegetation height).
Erosion due to concentrated irrigation flow	Repair/re-seed/re-plant eroded areas and adjust the irrigation system.
Erosion due to concentrated storm water runoff flow	Repair/re-seed/re-plant eroded areas, and make appropriate corrective measures such as adding erosion control blankets, adding stone at flow entry points, or minor re-grading to restore proper drainage according to the original plan. If the issue is not corrected by restoring the BMP to the original plan and grade, the City Engineer shall be contacted prior to any additional repairs or reconstruction.
Standing water in vegetated swales	Make appropriate corrective measures such as adjusting irrigation system, removing obstructions of debris or invasive vegetation, loosening or replacing top soil to allow for better infiltration, or minor re-grading for proper drainage. If the issue is not corrected by restoring the BMP to the original plan and grade, the City Engineer shall be contacted prior to any additional repairs or reconstruction.
Standing water in bioretention, biofiltration with partial retention, or biofiltration areas, or flow-through planter boxes for longer than 96 hours following a storm event*	Make appropriate corrective measures such as adjusting irrigation system, removing obstructions of debris or invasive vegetation, clearing underdrains (where applicable), or repairing/replacing clogged or compacted soils.
Obstructed inlet or outlet structure	Clear obstructions.
Damage to structural components such as weirs, inlet or outlet structures	Repair or replace as applicable.
*These BMPs typically include a surface p	ponding layer as part of their function which may take 96 hours to

drain following a storm event.

Typical Maintenance Indicator(s) for Detention Basins	Maintenance Actions
Poor vegetation establishment	Re-seed, re-establish vegetation.
Overgrown vegetation	Mow or trim as appropriate.
Erosion due to concentrated irrigation flow	Repair/re-seed/re-plant eroded areas and adjust the irrigation system.
Erosion due to concentrated storm water runoff flow	Repair/re-seed/re-plant eroded areas and make appropriate corrective measures such as adding erosion control blankets, adding stone at flow entry points, or re-grading where necessary.
Accumulation of sediment, litter, or debris	Remove and properly dispose of accumulated materials.
Standing water	Make appropriate corrective measures such as adjusting irrigation system, removing obstructions of debris or invasive vegetation, or minor re-grading for proper drainage.
Obstructed inlet or outlet structure	Clear obstructions.
Damage to structural components such as weirs, inlet or outlet structures	Repair or replace as applicable.

The City of	
SAN	DIEGO

RECORDING REQUESTED BY: THE CITY OF SAN DIEGO AND WHEN RECORDED MAIL TO:

Pathfinder Crown Point Apartments, LLC

(THIS SPACE IS FOR RECORDER'S USE ONLY)

STORM WATER MANAGEMENT AND DISCHARGE CONTROL MAINTENANCE AGREEMENT

APPROVAL NUMBER:

ASSESSORS PARCEL NUMBER:

PROJECT NUMBER:

This agreement is made by and between the City of San Diego, a municipal corporation [City] and _____

the owner or duly authorized representative of the owner [Property Owner] of property located at

(PROPERTY ADDRESS)

and more particularly described as: _____

(LEGAL DESCRIPTION OF PROPERTY)

in the City of San Diego, County of San Diego, State of California.

Property Owner is required pursuant to the City of San Diego Municipal Code, Chapter 4, Article 3, Division 3, Chapter 14, Article 2, Division 2, and the Land Development Manual, Storm Water Standards to enter into a Storm Water Management and Discharge Control Maintenance Agreement [Maintenance Agreement] for the installation and maintenance of Permanent Storm Water Best Management Practices [Permanent Storm Water BMP's] prior to the issuance of construction permits. The Maintenance Agreement is intended to ensure the establishment and maintenance of Permanent Storm Water BMP's onsite, as described in the attached exhibit(s), the project's Storm Water Quality Management Plan [SWQMP] and Grading and/or Improvement Plan Drawing No(s), or Building Plan Project No(s): ______.

Property Owner wishes to obtain a building or engineering permit according to the Grading and/or Improvement Plan Drawing No(s) or Building Plan Project No(s): ______.

Continued on Page 2

NOW, THEREFORE, the parties agree as follows:

- 1. Property Owner shall have prepared, or if qualified, shall prepare an Operation and Maintenance Procedure [OMP] for Permanent Storm Water BMP's, satisfactory to the City, according to the attached exhibit(s), consistent with the Grading and/or Improvement Plan Drawing No(s), or Building Plan Project No(s): ______.
- 2. Property Owner shall install, maintain and repair or replace all Permanent Storm Water BMP's within their property, according to the OMP guidelines as described in the attached exhibit(s), the project's SWQMP and Grading and/or Improvement Plan Drawing No(s), or Building Plan Project No(s) ______.
- 3. Property Owner shall maintain operation and maintenance records for at least five (5) years. These records shall be made available to the City for inspection upon request at any time.

This Maintenance Agreement shall commence upon execution of this document by all parties named hereon, and shall run with the land.

Executed by the City of San Diego and by Property Owner in San Diego, California.

See Attached Exhibit(s): _____

(Owner Signature)

THE CITY OF SAN DIEGO

APPROVED:

(Print Name and Title)

(Company/Organization Name)


(City Control Engineer Signature)

(Print Name)

(Date)


(Date)

NOTE: ALL SIGNATURES MUST INCLUDE NOTARY ACKNOWLEDGMENTS PER CIVIL CODE SEC. 1180 ET.SEQ.




		OPI	EXHIBIT 'B' ERATION AND MAINTENANCE		SHEET 2	? OF 5
	SITE D	•	OURCE CONTROL, AND POLLUTANT CO ERATION + MAINTENANCE PROCEDURE		L BMF	>
	STORM WATER	MANAGEMENT A	ND DISCHARGE CONTROL MAINTENANCE AGREEMENT APPROVAL NO.:			
	0&M RESPONS	SIBLE PARTY DES	IGNEE: PROPERTY OWNER / HOA / CITY / OTHER			
BMP DESCRIPTION	INSPECTION FREQUENCY	MAINTENANCE FREQUENCY	MAINTENANCE METHOD	QUANTITY	INCLUDED IN O&M MANUAL	SHEE1 #
SITE DESIGN ELEMENTS	S				YES	
SD-3, SD-4, SD-5, SD-6	MONTHLY & AS-NEEDED BEFORE AND AFTER RAIN EVENTS	AS–NEEDED AND BEFORE AND AFTER RAIN EVENTS	INFILTRATION. ENSURE THAT IMPERVIOUS AREAS DRAIN TO	N/A		7
SOURCE CONTROL ELE	MENTS				YES	
SC-1, SC-2, SC-5	WEEKLY, MONTHLY & AS-NEEDED BEFORE AND AFTER RAIN EVENTS	AS-NEEDED BEFORE AND	INSPECT AND MAKE CORRECTIVE ACTIONS AS NECESSARY TO PREVENT ANY ILLICIT DISCHARGES. REMOVE AND REPLACE SIGNS, SCREENS AND/OR COVERS AS—NEEDED. SWEEP AND CLEAN THE WASTE MANAGEMENT AREAS REGULARLY. USE DRY METHODS WHEN POSSIBLE WHEN CLEANING AROUND DUMPSTER AREAS. IF WATER MUST BE USED AFTER SWEEPING, USE ABSORBENTS, COLLECT WATER, AND DISCHARGE THROUGH GREASE INTERCEPTORS TO THE SEWER.	N/A		7
POLLUTANT CONTROL	BMP(S)				YES	
INF–1 INFILTRATION BASIN	EVERY 3 MONTHS & AS-NEEDED BEFORE AND AFTER RAIN EVENTS	EVERY 3 MONTHS & AS-NEEDED BEFORE AND AFTER RAIN EVENTS	PRUNE AND/OR MOW OVERGROWN VEGETATION. WATER VEGETATION UNTIL ESTABLISHMENT AND AS NEEDED FOR PLANT HEALTH. REMOVE AND REPLACE ANY DEAD OR DISEASED VEGETATION AS NEEDED. REPAIR, RE-SEED AND/OR RE-PLANT ERODED AREAS. REMOVE ACCUMULATED SEDIMENT AND DEBRIS FROM BASIN AND OUTLET STRUCTURES.	11		3-4
HMP EXEMPT				1	1	


H:\1300\1305.20 - PFP Coastal Holdings Shasta East\Engineering\Reports\Water Quality\SWQMP\3rd Submittal\ATTACHMENT 3\ATTACHMENT 3B SWMDCA.dwg 5/16/2017 7:36:00 AM



H:\1300\1305.20 - PFP Coastal Holdings Shasta East\Engineering\Reports\Water Quality\SWQMP\3rd Submittal\ATTACHMENT 3\ATTACHMENT 3B SWMDCA.dwg 5/16/2017 7:36:00 AM



H:\1300\1305.20 - PFP Coastal Holdings Shasta East\Engineering\Reports\Water Quality\SWQMP\3rd Submittal\ATTACHMENT 3\ATTACHMENT 3B SWMDCA.dwg 5/16/2017 7:36:00 AM



H:\1300\1305.20 - PFP Coastal Holdings Shasta East\Engineering\Reports\Water Quality\SWQMP\3rd Submittal\ATTACHMENT 3\ATTACHMENT 3B SWMDCA.dwg 7/6/2017 8:04:15 AM

ATTACHMENT 4 COPY OF PLAN SHEETS SHOWING PERMANENT STORM WATER BMPS

This is the cover sheet for Attachment 4.



THIS PAGE INTENTIONALLY LEFT BLANK FOR DOUBLE-SIDED PRINTING




Use this checklist to ensure the required information has been included on the plans:

The plans must identify:

- Structural BMP(s) with ID numbers matching Form I-6 Summary of PDP Structural BMPs
- ☐ The grading and drainage design shown on the plans must be consistent with the delineation of DMAs shown on the DMA exhibit
- Details and specifications for construction of structural BMP(s)
- Signage indicating the location and boundary of structural BMP(s) as required by the City Engineer
- How to access the structural BMP(s) to inspect and perform maintenance
- ☐ Features that are provided to facilitate inspection (e.g., observation ports, cleanouts, silt posts, or other features that allow the inspector to view necessary components of the structural BMP and compare to maintenance thresholds)
- Manufacturer and part number for proprietary parts of structural BMP(s) when applicable
- ☐ Maintenance thresholds specific to the structural BMP(s), with a location-specific frame of reference (e.g., level of accumulated materials that triggers removal of the materials, to be identified based on viewing marks on silt posts or measured with a survey rod with respect to a fixed benchmark within the BMP)
- Recommended equipment to perform maintenance
- □ When applicable, necessary special training or certification requirements for inspection and maintenance personnel such as confined space entry or hazardous waste management
- Include landscaping plan sheets showing vegetation requirements for vegetated structural BMP(s)
- □ All BMPs must be fully dimensioned on the plans
- □ When proprietary BMPs are used, site specific cross section with outflow, inflow and model number shall be provided. Boucher photocopies are not allowed.





1.64 ACRES 0.58 ACRES 1.16 ACRES 0.00 ACRES

0.00 ACRES 1.16 ACRES 100.0% 100.0% 0 ACRES 0%

2056 CUBIC YARDS 567 CUBIC YARDS

2.5 2.8' FEET 1488 CUBIC YARDS

0%

25'

	\sim			
_	(-	-	N	1 1
	J		IN	

EXISTING IMPROVEMENT	STANDARD DWGS.	<u>SYMBOL</u>
PROPERTY BOUNDARY		
EXISTING LOT LINE		
EXISTING CONTOURS		40
EXISTING LOT NO.		(5)
EXISTING SURFACE ELEVATION PROPOSED IMPROVEMENT	<u>STANDARD_DWGS.</u>	<u>(30.45 FS)</u> <u>SYMBOL</u>
PROPOSED PROPERTY LINE		
NFILTRATION BASIN	(SEE DETAIL SHEET C-2)	
EDESTRIAN RAMP		
ISIBILITY TRIANGLE		. 🔨
6" AREA DRAIN		·· – — sd —
12" BROOKS BOX OR APPROVED EQUA	4L	. 🗉
3" PVC SIDEWALK UNDERDRAIN PIPE .	(D–27)	
CONCRETE DRIVEWAY APPROACH	(SEE L1.07)	
AC PAVEMENT		
DRAINAGE ARROW		·
TREE LOCATION (SEE LANDSCAPE PLA	INS)	
PROPOSED CONTOURS		
PERMEABLE PAVERS		
DISTURBED AREA		$\langle \langle \rangle$
PROPOSED SURFACE ELEVATION		32.15 FS
PROPOSED PAD ELEVATION		(45.0)
PROPOSED LOT		LOT 06
PROPOSED 4" SEWER LATERAL		<u> </u>
PROPOSED 8" PVC SEWER MAIN		— — s —
PROPOSED 6" PVC WATER MAIN		— — w—
PROPOSED 1" COPPER WATER SERVICE	ESDW-134, SDW-150, SDW-150 WS-03	8
	ER	8

Underground Service Alert

TWO WORKING DAYS BEFORE YOU DIG



Call: TOLL FREE "811

EARTHWORK QUANTITES

TOTAL DISTURBED AREA:
EXISTING REMOVED IMPERVIOUS AREA:
AMOUNT OF CREATED IMPERVIOUS AREA:
AMOUNT OF REPLACE IMPERVIOUS AREA:
TOTAL 00000000 UN00000 1001
TOTAL PROPOSED IMPERVIOUS AREA:

- TOTAL PROPOSED IMPERVIOUS AREA: IMPERVIOUS % INCREASE: PERCENT OF TOTAL SITE TO BE GRADED: AMOUNT OF SITE WITH 25 PERCENT SLOPES OR GREATER: PERCENT OF TOTAL SITE WITH 25 PERCENT SLOPES OR GREATER: PERCENT OF THE EXISTING SLOPES STEEPER THAN 25% PROPOSED TO BE GRADED: MUNINT OF CHT.

- 11. 12. AMOUNT OF CUT: AMOUNT OF FILL:
- 13 MAXIMUM HEIGHT OF FUL SLOPE(S)
- MAXIMUM HEIGHT OF FILL SLOPE(S): MAXIMUM HEIGHT OF CUT SLOPE(S): AMOUNT OF EXPORT SOIL:

SITE DEVELOPMENT

- GRADING AS SHOWN ON THESE PLANS SHALL BE IN CONFORMANCE WITH THE CITY STANDARD DRAWINGS SDL-101 AND SDL-102, CURRENT STANDARD SPECIFICATIONS AND DIVISION 4, SECTION 62 OF THE SAN DIEGO MUNICAL CODE. PLANT AND IRRIGATE ALL CUT AND FILL SLOPES AS REQUIRED BY DIVISION 4, SECTION 62, OF THE SAN
- DECO MUNCIPAL CODE AND ACCORDING TO CITY ENGLISHER'S SPECIFICATION FOR LANDSCAPING AND IRRIGATION FOR LAND DEVELOPMENT, DOCUMENT 746595, FILES FEBRUARY 20, 1974. SEE LANDSCAPE ARCHITECTURAL PLANS FOR ELEVATIONS AND HARDSCAPE DIMENSIONING BETWEEN CURB AND DIMENSION FACT.
- AND BUILDING FACE

BENCHMARK

BRASS PLUG ON THE NORTH EAST CORNER OF SHASTA STREET AND CROWN POINT DRIVE PER THE CITY OF SAN DIEGO VERTICAL CONTROL BENCHMARK. ELEVATION = 31.115 MSL SOURCE: PATHFINDER PARTNERS, LLC. DATE: MARCH 31, 2015 MSL DATUM: NAVD 29

REFERENCE DRAWINGS

22760-D 26005-D 5429-W

DECLARATION OF RESPONSIBLE CHARGE

I HEREBY DECLARE THAT I AM THE ENGINEER OF WORK FOR THIS PROJECT, THAT I HAVE EXERCISED RESPONSIBLE CHARGE OVER THE DESIGN OF THE PROJECT AS DEFINED IN SECTION 6703 OF THE BUSINESS AND PROFESSIONS CODE. AND THAT THE DESIGN IS CONSISTENT WITH CURRENT STANDARDS.

I UNDERSTAND THAT THE CHECK OF PROJECT DRAWINGS AND SPECIFICATIONS BY THE CITY OF SAN DIEGO IS CONFINED TO A REVIEW ONLY AND DOES NOT RELIEVE ME, AS ENGINEER OF WORK, OF MY RESPONSIBILITIES FOR PROJECT DESIGN.

GIOVANNI POSILLICO R.C.E 66332

DATE

LEGAL DESCRIPTION

01180-150645, DATED AS OF APRIL 30, 2015 AT 7:30 AM

OWNER/APPLICANT

PATHFINDER PARTNERS COASTAL HOLDINGS, LLC 4380 LA JOLLA VILLAGE DRIVE, SUITE 250 SAN DIEGO, CA 92122 TEL: 858–875–4400

RECORDED APRIL 22, 1992 AS INSTRUMENT NO. 1992-0236618 OF OFFICIAL RECORDS

RECORDED APRIL 22, 1992 AS INSTRUMENT NO. 1992-0236618 OF OFFICIAL RECORDS


ASSESSOR'S PARCEL NUMBER


PARCEL 2.

PARCEL 3:

424-482-14, 424-532-25







TWO WORKING DAYS BEFORE YOU DIG



10	PERMIT XX/XX/16		
DESCRIPTION	COASTAL DEVELOPMENT PERMIT		
ISSUE	1		
		VE 3977 SHASTA ST 1750 RONSEVELT AVE	
	C	\neg	
		FORTINA A	
UADE DA DE		1765 FORTINA A	

DETAILS AND SECTIONS

PREPARED BY:

LOT NUMBER:

PROJECT NAME:

APN:

LATITUDE 33 9968 HIBERT STREET SECOND FLOOR SAN DIEGO, CA 92131

PARCEL 2: 1–24 PARCEL 3: 1–6

2 OF 4

DETAILS AND SECTIONS


SHEET TITLE:

SHEET COUNT:

424–482–14 424–532–25 ECO BLÖK HOMES

REVISION 6: REVISION 5: REVISION 4: REVISION 3: REVISION 2: REVISION 1: ORIGINAL DATE: XX-XX-16

PTS #: 530514



EMRA NOTE:

AN EMRA WILL BE REQUIRED FOR THE PRIVATE CONCRETE WALKWAYS, SIDEWALK UNDERDRAINS, LANDSCAPE AND IRRIGATION, AND SEWER LATERALS WITHIN THE PUBLIC RIGHT OF WAY.

NOTE:

CONTRACTOR TO VERIFY SEWER LATERAL LOCATIONS PRIOR TO CONSTRUCTION, NOTIFY ENGINEER OF ANY DISCREPANCIES.

DEMOLITION NOTES

- (1) EXISTING SIDEWALK TO BE REMOVED
- 2 EXISTING WALL TO BE REMOVED
- 3 EXISTING CURB AND GUTTER TO BE REMOVED
- 4 EXISTING AC PAVEMENT TO BE REMOVED
- 5 EXISTING BUILDING TO BE REMOVED
- EXISTING IMPROVEMENTS TO BE REMOVED FOR PROPOSED
 PUBLIC DRIVEWAY
- T EXISTING IMPROVEMENT TO REMAIN AND PROTECT IN PLACE
- 8 EXISTING TREE TO REMAIN
- EXISTING IMPROVEMENTS TO BE REMOVED FOR PROPOSED CURB RAMP, CURB AND GUTTER, CONCRETE APRON, AND SIDEWALK
- () EXISTING IMPROVEMENTS TO BE REMOVED FOR PROPOSED 5' RIGHT OF WAY DEDICATION

DEMOLITION PLAN

PREPARED BY:

LATITUDE 33 9968 HIBERT STREET SECOND FLOOR SAN DIEGO, CA 92131

ECO BLOK HOMES

DEMOLITION PLAN

3 OF 4


SHEET COUNT:

PARCEL 2: 1–24 PARCEL 3: 1–6 424–482–14 424–532–25

REVISION 6: REVISION 5: REVISION 4: REVISION 3: REVISION 2: BEVISION 1: ORIGINAL DATE: XX-XX-16

PTS #: 530514

	ISSUE DESCRIPTION DATE	1 COASTAL DEVELOPMENT PERMIT XX/XX/16				
			1766 FORTLINA AVE 3077 SHASTA ST 1750 RODSEVELT AVE		SAN DIEGO, CA: 3ZIUS	
		TE:	02.2	7.17		
	JO	AW B: EET		3		



THIS PAGE INTENTIONALLY LEFT BLANK FOR DOUBLE-SIDED PRINTING



ATTACHMENT 5 DRAINAGE REPORT

Attach project's drainage report. Refer to Drainage Design Manual to determine the reporting requirements.



DRAINAGE STUDY FOR:

ECO BLOK HOMES

CITY OF SAN DIEGO, CALIFORNIA

PTS NO. 530514

Prepared for: **Pathfinder Crown Point Apartments, LLC** 4380 La Jolla Village Dr. Suite 250 San Diego, CA 92122 (858) 875-4450

Prepared by: Latitude 33 Planning and Engineering 9968 Hibert Street, 2nd Floor San Diego, California 92131 (858) 751-0633


Giovanni Posillico RCE 66332

TABLE OF CONTENTS

I. PROJECT DESCRIPTION	3
II. EXISTING SITE CONDITION	4
III. DEVELOPED SITE CONDITION	4
IV. HYDROLOGIC METHODOLOGY	5
V. DISCUSSION AND RESULT	6
APPENDIX A: EXISTING & PROPOSED HYDROLOGIC CALCULATIONS	7

I. PROJECT DESCRIPTION

The Eco Blök Homes project is located in the city of San Diego and bounded to the south by Mission Bay, east by Interstate 5, north by Pacific Beach Drive and west by Ingraham Street, see vicinity map below. The project proposes to modify the 1.85-acre site with improvements such as infiltration BMPs, landscaping, sidewalk and single family houses. This report has been prepared to document the analysis of the existing and proposed drainage condition associated with Eco Blök Homess.



NO SCALE

II. EXISTING SITE CONDITION

The project area is approximately 1.85 acres of developed land consisting of 3 existing units and an empty lot containing a garden. The existing site is comprised of buildings, sidewalk and landscaping. The existing site drainage is divided into three basins. The east side of the project (basin 1) drains to the southeast corner of the site and discharges to Roosevelt Avenue. The west side of the project (basin 2) drains to the southwest corner of the site and discharges southerly to curb and gutter along Shasta Avenue and converges with the discharge from basin 1 at Roosevelt Avenue. The southernmost portion of the project (basin 3) drains to the southeast corner of Roosevelt Avenue and Shasta Street. All of the storm water runoff from the project site then flows west down Roosevelt Avenue via curb and gutter where it finally come together at the corner of Roosevelt Avenue and Jewel Street. From there the entire project's runoff flows via curb and gutter to an existing inlet located 550 feet south at the corner of Jewel Street and La Playa Avenue. Storm water then is conveyed via storm drain to Mission Bay

III. DEVELOPED SITE CONDITION

The developed site at the Eco Blök Homes will disturb 1.64 acres and consists of sidewalk, landscaping and infiltration BMPs in addition to 30 single family row homes. The onsite storm water will be treated with infiltration basins.

There are no existing storm drain systems in the vicinity, thus flows will be collected by onsite brooks boxes and storm drain pipes that flow into the proposed infiltration basins for water quality treatment control purposes.

For flood control purposes the infiltration BMPs located within Basin P.1 & P.2 discharge to Shasta Street. All water from the project site will be captured and directed to an infiltration BMP. The infiltration BMPs will fill up and the underlying media and aggregate will become saturated. The basins themselves will then begin to pond and fill up to their capacity. Each standard infiltration BMP contains an overflow system for flows larger than the water quality demand. All of these overflow storm drain systems include a grated catch basin that have an open bottom. These open bottom structures will fill up with water and when a certain water level is reached the overflow will discharge via 3" underdrains to the surrounding curb and gutter. The remaining water that is in the catch basins and infiltration BMPs will then infiltrate through the media and aggregate.

Both overflow and subsurface flows from the project site will discharge through side walk underdrains to either the existing curb and gutter on Shasta Street or to the alley. All discharge points flow via curb and gutter 1,050 feet south to the existing storm drain inlet located at the corner of Jewel Street and La Playa Avenue. Storm water is then conveyed via storm drain pipes east down La Playa Avenue and across Crown Point park and then discharges directly into Mission Bay. The drainage areas have been designed to maintain the overall drainage design and the storm water discharges to the same inlet at the corner of Jewel Street and La Playa Avenue. This project does not propose to dredge or fill materials in water of the U.S. Jurisdictional Waters and will not be required to obtain Clean Water Act Section 401/404 Water Quality Certification.

Please see the Storm Water Quality Management Plan (SWQMP) for details of Water Quality calculations.

IV. HYDROLOGIC METHODOLOGY

This report is intended to support preliminary engineering design, as well as demonstrate compliance with applicable design standards. Specifically, this report will address the 50-yr and 100-yr flow rates for the pre and post condition.

Appendix I of the City of San Diego's 1984 *Drainage Design Manual's* rational method procedure was the basis for the pre and post conditions for the 100-year hydrologic analysis. This study was accomplished through the implementation of the 2015 Autodesk Storm and Sanitary Analysis software, which has the capability to utilize the rational method program based on the City of San Diego storm water design criteria. The input parameters are summarized below and the supporting data is included in Appendix A.

- Intensity-Duration-Frequency: The City's 50-year and 100-year Intensity-Duration-Frequency curve from the *Drainage Design Manual* was used.
- Drainage area: The pre-condition drainage basins were delineated from the base topographic mapping prepared for the project. Proposed condition drainage basins were delineated using the proposed Civil Site Plans which include storm drain layout.
- Manning's Roughness Coefficients: Table 1-104.14A was used to determine appropriate values.
- Run-off Coefficient: Taking into consideration the amount of landscaped area for the precondition a value of 0.50 was used and for the post condition a runoff coefficient of 0.70 was implemented in accordance with Table 2 in Appendix I. A weighted runoff coefficient was used for both existing and proposed conditions e.g. for existing basin E.1 (0.50) => Actual imp. 50%, Tabulated Imp. 70%; (0.50/0.70)*(0.70) = 0.50. For proposed basin P.1 (0.70) => Actual imp. 70%, Tabulated Imp. 80%; (0.70/0.80)*(0.80) = 0.70.
- Flow lengths and elevations: The flow lengths and elevations were obtained from the topographic mapping and grading plans.

V. DISCUSSION AND RESULT

As seen below, the rational method results show that there is an overall increase in flow from the existing condition to the proposed. Basin 1 and 2 in existing conditions will become one basin in proposed conditions via the use of area drains and swales. The volume retained and flow detained by the implementation of the water quality infiltration BMPs will return the post condition flows to existing condition values or lower. For Q100 mitigation, the project will store approximately 1,164 cubic feet of runoff for the west side of the project, and approximately 136 cubic feet of runoff for the east side. For the east side of the project, the Q100 mitigation will be accomplished via 6" of surface ponding as well as 1.2' of gravel storage. For the east side, the all peak storm mitigation will be accomplished with just 6" of surface ponding.

Basin	Area	Runoff Coefficient	100-yr Flows
	(Ac)		(cfs)
1	0.89	0.50	1.09
2	0.63	0.50	0.78
3	0.33	0.50	0.56
Total Area =	1.85	Total Flows =	2.43

EXISTING CONDITIONS


PROPOSED CONDITIONS

Basin	Area	Runoff Coefficient	100-yr Flows	Mitigated Flow
	(Ac)		(cfs)	(cfs)
1	1.52	0.70	4.66	0.78
2	0.33	0.70	1.01	0.56
Total Area =	1.85	Total Flows =	5.67	1.34

Please see Appendix A for the hydrologic calculations and corresponding Drainage Area exhibits.

APPENDIX A: EXISTING & PROPOSED HYDROLOGIC CALCULATIONS

EXISTING



Existing Q100.txt

Autodesk[®] Storm and Sanitary Analysis 2015 - Version 9.1.140 (Build 1)

Project Description

File Name Pre-Condition_100yr.SPF
Description H:\1300\1305.20 - PFP Coastal Holdings Shasta East\Engineering\Reports\Drainage\1305.20
Existing DA's.dwg

Analysis Options *********

Flow Units cfs Subbasin Hydrograph Method. City of San Diego Rational Method Time of Concentration..... SCS TR-55 (5 minutes minimum) Return Period..... 100 years Storage Node Exfiltration. Constant flow Starting Date JUN-28-2017 00:00:00 Ending Date JUN-28-2017 01:00:00 Report Time Step 00:00:10

Subbasin Summary ********

Subbasin	Total
	Area
ID	acres
{_}.E.1	0.89
{_}.E.2	0.63
{_}.E.3	0.33

*********** Node Summary *********** Node	Element	_		Maximum		External
ID	Туре	Elev	ation ft 	Elev. ft	Area ft²	Inflow
POCA POCB POCC	OUTFALL OUTFALL OUTFALL		33.53	32.77 33.53 32.41	0.00	
**************************************	Continuity	Volume acre-ft	_	Depth inches		
Total Precipitat Continuity Error		0.128 0.504		0.829		
**************************************	tinuity	Volume acre-ft		Volume allons		
External Inflow External Outflow Initial Stored V Final Stored Vol Continuity Error	olume ume	0.000 0.063 0.000 0.000 0.000		0.000 0.021 0.000 0.000		

Subbasin {_}.E.1

Soil/Surface Description	Area	Soil	Runoff
	(acres)	Group	Coeff.
-	0.89	D	0.50
Composite Area & Weighted Runoff Coeff.	0.89		0.50

0.50

Subbasin {_}.E.2

Soil/Surface Description	Area	Soil	Runoff
	(acres)	Group	Coeff.
-	0.63	D	0.50
Composite Area & Weighted Runoff Coeff.	0.63		0.50
Subbasin {_}.E.3			
Soil/Surface Description	Area	Soil	Runoff
	(acres)	Group	Coeff.
-	0.33	D	0.50

0.	
Composite Area & Weighted Runoff Coeff. 0	. 33

Sheet Flow Equation

 $Tc = (0.007 * ((n * Lf)^{0.8})) / ((P^{0.5}) * (Sf^{0.4}))$

Where:

Tc = Time of Concentration (hrs)
n = Manning's Roughness
Lf = Flow Length (ft)
P = 2 yr, 24 hr Rainfall (inches)
Sf = Slope (ft/ft)

Shallow Concentrated Flow Equation

V = 16.1345 * (Sf^0.5) (unpaved surface) V = 20.3282 * (Sf^0.5) (paved surface) V = 15.0 * (Sf^0.5) (grassed waterway surface)

```
V = 10.0 * (Sf^0.5) (nearly bare & untilled surface)
V = 9.0 * (Sf^0.5) (cultivated straight rows surface)
V = 7.0 * (Sf^0.5) (short grass pasture surface)
V = 5.0 * (Sf^0.5) (woodland surface)
V = 2.5 * (Sf^0.5) (forest w/heavy litter surface)
Tc = (Lf / V) / (3600 sec/hr)
```

Where:

Tc = Time of Concentration (hrs)
Lf = Flow Length (ft)
V = Velocity (ft/sec)
Sf = Slope (ft/ft)

Channel Flow Equation

V = (1.49 * (R^(2/3)) * (Sf^0.5)) / n R = Aq / Wp Tc = (Lf / V) / (3600 sec/hr)

Where:

```
Tc = Time of Concentration (hrs)
Lf = Flow Length (ft)
R = Hydraulic Radius (ft)
Aq = Flow Area (ft<sup>2</sup>)
Wp = Wetted Perimeter (ft)
V = Velocity (ft/sec)
Sf = Slope (ft/ft)
n = Manning's Roughness
```

Subbasin {_}.E.1

Sheet Flow Computations

	Subarea A	Subarea B	Subarea C
Manning's Roughness:	0.40	0.00	0.00
Flow Length (ft):	71.83	0.00	0.00
Slope (%):	3.52	0.00	0.00
2 yr, 24 hr Rainfall (in):	1.75	0.00	0.00

		Existing	Q100.txt	
	Velocity (ft/sec):	0.07	0.00	0.00
	Computed Flow Time (minutes):	17.77	0.00	0.00
Shallow	Concentrated Flow Computations			
		Subarea A	Subarea B	Subarea C
	Flow Length (ft):	30.35	0.00	0.00
	Slope (%):	4.02	0.00	0.00
	Surface Type:	Grass pasture	Unpaved	Unpaved
	Velocity (ft/sec):	1.40	0.00	0.00
	Computed Flow Time (minutes):	0.36	0.00	0.00
Channel	l Flow Computations			
		Subarea A	Subarea B	Subarea C
	Manning's Roughness:	0.01	0.00	0.00
	Flow Length (ft):	583.57	0.00	0.00
	Channel Slope (%):	1.59	0.00	0.00
	Cross Section Area (ft ²):	2.00	0.00	0.00
	Wetted Perimeter (ft):	20.00	0.00	0.00
	Velocity (ft/sec):	2.70	0.00	0.00
	Computed Flow Time (minutes):	3.60	0.00	0.00
	Total TOC (minutes):	21.74	=======================================	

Sheet Flow Computations

	Subarea A	Subarea B	Subarea C
Manning's Roughness:	0.40	0.00	0.00
Flow Length (ft):	66.32	0.00	0.00
Slope (%):	3.92	0.00	0.00
2 yr, 24 hr Rainfall (in):	1.75	0.00	0.00
Velocity (ft/sec):	0.07	0.00	0.00
Computed Flow Time (minutes):	15.97	0.00	0.00

Shallow Concentrated Flow Computations

	Existing Q100.txt			
		Subarea A	Subarea B	Subarea C
	Flow Length (ft):	165.52	0.00	0.00
	Slope (%):	1.17	0.00	0.00
	Surface Type:	Grass pasture	Unpaved	Unpaved
	Velocity (ft/sec):	0.76	0.00	0.00
	Computed Flow Time (minutes):	3.63	0.00	0.00
Channel	l Flow Computations			
		Subarea A	Subarea B	Subarea C
	Manning's Roughness:	0.01	0.00	0.00
	Flow Length (ft):	409.57	0.00	0.00
	Channel Slope (%):	2.18	0.00	0.00
	Cross Section Area (ft ²):	0.31	0.00	0.00
	Wetted Perimeter (ft):	1.91	0.00	0.00
	Velocity (ft/sec):	4.36	0.00	0.00
	Computed Flow Time (minutes):	1.56	0.00	0.00
======	Total TOC (minutes):	21.17		

Subbasin {_}.E.3

Sheet Flow Computations

	Subarea A	Subarea B	Subarea C
Manning's Roughness:	0.40	0.00	0.00
Flow Length (ft):	37.00	0.00	0.00
Slope (%):	5.14	0.00	0.00
2 yr, 24 hr Rainfall (in):	1.75	0.00	0.00
Velocity (ft/sec):	0.07	0.00	0.00
Computed Flow Time (minutes):	8.99	0.00	0.00


Shallow Concentrated Flow Computations

	Subarea A	Subarea B	Subarea C
Flow Length (ft):	61.67	0.00	0.00
Slope (%):	3.34	0.00	0.00
Surface Type:	Grass pasture	Unpaved	Unpaved
Velocity (ft/sec):	1.28	0.00	0.00


	Existing	Q100.txt	
Computed Flow Time (minutes):	0.80	0.00	0.00
Channel Flow Computations			
	Subarea A	Subarea B	Subarea C
Manning's Roughness:	0.01	0.00	0.00
Flow Length (ft):	121.81	0.00	0.00
Channel Slope (%):	0.96	0.00	0.00
Cross Section Area (ft ²):	0.31	0.00	0.00
Wetted Perimeter (ft):	1.91	0.00	0.00
Velocity (ft/sec):	2.90	0.00	0.00
Computed Flow Time (minutes):	0.70	0.00	0.00
Total TOC (minutes):	10.49		

Subbasin ID	Accumulated Precip in	Rainfall Intensity in/hr	Total Runoff in	Peak Runoff cfs	Weighted Runoff Coeff	Conc days	Time of entration hh:mm:ss
{_}.E.1	0.88	2.44	0.44	1.09	0.500	0	00:21:44
{_}.E.2	0.88	2.48	0.44	0.78	0.500	0	00:21:10
{_}.E.3	0.60	3.42	0.30	0.56	0.500	0	00:10:29

Analysis began on: Thu Jun 29 10:02:08 2017 Analysis ended on: Thu Jun 29 10:02:08 2017 Total elapsed time: < 1 sec



PROPOSED



Q100 Proposed.txt

Autodesk[®] Storm and Sanitary Analysis 2015 - Version 9.1.140 (Build 1)

Project Description

File Name Post Developed-Condition_100yr.SPF
Description H:\1300\1305.20 - PFP Coastal Holdings Shasta East\Engineering\Reports\Drainage\1305.20
Existing DA's.dwg

Analysis Options ********

Flow Units cfs Subbasin Hydrograph Method. City of San Diego Rational Method Time of Concentration..... SCS TR-55 (5 minutes minimum) Return Period..... 100 years Storage Node Exfiltration. Constant flow Starting Date JUN-28-2017 00:00:00 Ending Date JUN-28-2017 01:00:00 Report Time Step 00:00:10

Subbasin Summary

Subbasin	Total
	Area
ID	acres
{_}.P.2	0.33
P.1	1.52

Node Summary *****						
Node	Element	I	nvert	Maximum	Ponded	External
ID	Туре	Elev	ation	Elev.	Area	Inflow
			ft	ft	ft²	
РОСВ	OUTFALL		 33.53		0.00	
POCC	OUTFALL		32.41		0.00	
r occ	OUTTALL		52.41	52.41	0.00	
************	*****	Volume		Depth		
Runoff Quantity	Continuity	acre-ft		inches		
************	*********		-			
Total Precipitat	tion	0.056		0.365		
Continuity Error	r (%)	0.306				
*****	*****	Volume		Volume		
Flow Routing Cor	ntinuity	acre-ft	Mc	gallons		
*****	•		ع، ، 			
External Inflow		0.000		0.000		
External Outflow	N	0.039		0.013		
Initial Stored \	/olume	0.000		0.000		
Final Stored Vol	lume	0.000		0.000		
Continuity Error		0.000				

Subbasin {_}.P.2

Soil/Surface Description	Area	Soil	Runoff
	(acres)	Group	Coeff.
-	0.33	D	0.70
Composite Area & Weighted Runoff Coeff.	0.33		0.70

Subbasin P.1

_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _

Soil/Surface Description	Area	Soil	Runoff
	(acres)	Group	Coeff.
-	1.52	-	0.70
Composite Area & Weighted Runoff Coeff.	1.52		0.70

SCS TR-55 Time of Concentration Computations Report

Sheet Flow Equation

 $Tc = (0.007 * ((n * Lf)^{0.8})) / ((P^{0.5}) * (Sf^{0.4}))$

Where:

Tc = Time of Concentration (hrs)
n = Manning's Roughness
Lf = Flow Length (ft)
P = 2 yr, 24 hr Rainfall (inches)
Sf = Slope (ft/ft)

Shallow Concentrated Flow Equation

V = 16.1345 * (Sf^0.5) (unpaved surface) V = 20.3282 * (Sf^0.5) (paved surface) V = 15.0 * (Sf^0.5) (grassed waterway surface) V = 10.0 * (Sf^0.5) (nearly bare & untilled surface) V = 9.0 * (Sf^0.5) (cultivated straight rows surface) V = 7.0 * (Sf^0.5) (short grass pasture surface) V = 5.0 * (Sf^0.5) (woodland surface) V = 2.5 * (Sf^0.5) (forest w/heavy litter surface) Tc = (Lf / V) / (3600 sec/hr)


Where:

Tc = Time of Concentration (hrs)
Lf = Flow Length (ft)


```
V = Velocity (ft/sec)
    Sf = Slope (ft/ft)
Channel Flow Equation
    V = (1.49 * (R^{(2/3)}) * (Sf^{0.5})) / n
    R = Aq / Wp
    Tc = (Lf / V) / (3600 sec/hr)
    Where:
    Tc = Time of Concentration (hrs)
    Lf = Flow Length (ft)
    R = Hydraulic Radius (ft)
    Aq = Flow Area (ft<sup>2</sup>)
    Wp = Wetted Perimeter (ft)
    V = Velocity (ft/sec)
    Sf = Slope (ft/ft)
    n = Manning's Roughness
 . . . . . . . . . . . . . . . . . . .
Subbasin {_}.P.2
Total TOC (minutes):
                              0.00
_____
-----
Subbasin P.1
_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _
Total TOC (minutes):
                              0.00
_____
******
Subbasin Runoff Summary
*******
Subbasin
     Accumulated
                 Rainfall
                         Total
                               Peak Weighted
                                              Time of
```

				Q100 Prop	posed.txt	
ID	Precip in	Intensity in/hr	Runoff in	Runoff cfs	Runoff Coeff	Concentration days hh:mm:ss
{_}.P.2	0.36	4.38	0.26	1.01	0.700	0 00:05:00
P.1	0.36	4.38	0.26	4.66	0.700	0 00:05:00

Analysis began on: Thu Jun 29 09:53:22 2017 Analysis ended on: Thu Jun 29 09:53:22 2017 Total elapsed time: < 1 sec








	Total Inflow Summary Table								
Time period		Element ID	POCB	DOCR					
From:	06/28/2017, 12:00:00 AM		0.78						
	06/28/2017, 01:00:10 AM	Minimum Total Inflow (cfs)							
To:	0672872017, 01:00:10 AM	Event Mean Total Inflow (cfs)							
Thresholds		Duration of Exceedances (hrs) N/A	N/A					
Exceedance	x 0	Duration of Deficits (hrs)	N/A	N/A					
Deficit	0	Number of Exceedances		N/A					
		Number of Deficits	N/A						
Detention sto	orage	Volume of Exceedance (ft ³)		N/A					
Max flow:	0.78	Volume of Deficit (ft ^e)	N/A						
		Total Inflow Volume (ft [®])	992.61						
		Detention Storage (ft ³)	1164.10	1164.10					





	Total Inflow Summary Table					
Time period						
		Element ID	POCC POC			
From: 06/28/20	2017, 12:00:00 AM	Maximum Total Inflow (cfs)	0.56 1.0	1.01		
To: 06/28/20	2017, 01:00:10 AM	Minimum Total Inflow (cfs)	0.00 0.0	0.00		
		Event Mean Total Inflow (cfs)	0.10 0.0	0.08		
Thresholds		Duration of Exceedances (hrs)	j N/A N/A	N/A		
Exceedance: 0		Duration of Deficits (hrs)	N/A N/A	N/A		
Deficit: 0		Number of Exceedances	N/A N/A	N/A		
		Number of Deficits	N/A N/A	N/A		
Detention storage		Volume of Exceedance (ft ^e)	N/A N/A	N/A		
Max flow: 0.56		Volume of Deficit (ft ^e)	N/A N/A	N/A		
Max now.		Total Inflow Volume (ft®)	355.37 303	303.53		
		Detention Storage (ft ^a)	135.53 135	135.53		

THIS PAGE INTENTIONALLY LEFT BLANK FOR DOUBLE-SIDED PRINTING



ATTACHMENT 6 GEOTECHNICAL AND GROUNDWATER INVESTIGATION REPORT

Attach project's geotechnical and groundwater investigation report. Refer to Appendix C.4 to determine the reporting requirements.



GEOTECHNICAL INVESTIGATION

ECO BLOK EAST SHASTA STREET SAN DIEGO, CALIFORNIA

PREPARED FOR

PFP COASTAL HOLDINGS, LLC SAN DIEGO, CALIFORNIA

DECEMBER 19, 2016 PROJECT NO. G1832-42-03



GEOTECHNICAL ENVIRONMENTAL MATERIALS GEOTECHNICAL E ENVIRONMENTAL E MATERIALS



ONAL GE

Project No. G1832-42-03 December 19, 2016

PFP Coastal Holdings, LLC 4380 La Jolla Village Drive, Suite 250 San Diego, California 92122

Attention: Mr. Matt Quinn

Subject: GEOTECHNICAL INVESTIGATION ECO BLOK EAST SHASTA STREET SAN DIEGO, CALIFORNIA

Dear Mr. Quinn:

In accordance with your request, we have performed a geotechnical investigation for the subject project. The accompanying report presents the findings of our study and our conclusions and recommendations pertaining to geotechnical aspects of developing the property as proposed. We have also provided design recommendations for storm water management.

It is our opinion that the site can be developed as currently proposed provided the recommendations of this report are followed.

Should you have questions regarding this investigation, or if we may be of further service, please contact the undersigned at your convenience.

Very truly yours,

GEOCON	NINCORPORATED	GARRY WELLS GARRY WELLS GANNON CC CANNON CC No. 2201
Rođney C GE 2533	Mikesel	Garry W. Cannon CEG 2201 RCE 56468 PROFESSION
RCM:GW	VC:dmc	WELLS CRUE
(e-mail) (3/del)	Addressee Golba Architecture, Inc. Attention : Mr. Tim Golba	No. C 056468 O REF BUE + STATE OF CALLFORTINE

TABLE OF CONTENTS

1.	PURF	POSE AND SCOPE	1
2.	SITE	AND PROJECT DESCRIPTION	1
3.	SOIL 3.1 3.2	AND GEOLOGIC CONDITIONS Undocumented Fill (Qudf) Old Terrace Deposits (Qt)	2
4.	GRO	UNDWATER	2
5.	GEOI 5.1 5.2 5.3 5.4 5.5	-OGIC HAZARDS Faulting and Seismicity Ground Rupture Liquefaction and Seismically Induced Settlement. Landslides. Tsunami and Seiche.	3 4 4 4
6.	CON0 6.1 6.2 6.3 6.4 6.5 6.6 6.7 6.8 6.9 6.10	CLUSIONS AND RECOMMENDATIONS. General Excavation and Soil Characteristics Grading Seismic Design Criteria Foundation and Concrete Slabs-On-Grade Recommendations	6 8 9 0 5 7 8
LIM	ITAT	IONS AND UNIFORMITY OF CONDITIONS	

MAPS AND ILLUSTRATIONS

Figure 1, Vicinity Map

Figure 2, Geologic Map

Figure 3, Typical Wall/Column Footing Dimension Detail

Figure 4, Typical Retaining Wall Drain Detail

APPENDIX A

FIELD INVESTIGATION Figures A-1 – A-6, Logs of Geotechnical Borings

APPENDIX B

Table B-I, Summary of Laboratory Maximum Dry Density and Optimum Moisture Content Test Results Table B-II, Summary of Laboratory Remolded Direct Shear Test Results Table B-III, Summary of Laboratory Expansion Index Test Results Table B-IV, Summary of Laboratory Water-Soluble Sulfate Test Results Table B-V, Summary of Laboratory Resistance Value (R-Value) Test Results Figure B-1, Grain Size Distribution Curves Figures B-2 – B-4, Consolidation Curves

TABLE OF CONTENTS (Concluded)

APPENDIX C STORM WATER MANAGEMENT

APPENDIX D RECOMMENDED GRADING SPECIFICATIONS

LIST OF REFERENCES

GEOTECHNICAL INVESTIGATION

1. PURPOSE AND SCOPE

This geotechnical investigation is specific to the proposed development located southeast of the intersection of Shasta Street and Fortuna Avenue in San Diego, California (see Vicinity Map, Figure 1). The purpose of this study is to evaluate surface and subsurface soil conditions and general site geology; to identify geotechnical constraints, if any, that might impact development of the property; and provide geotechnical and storm-water management recommendations for continued development of the property.

The scope of our study included a review of the undated plan prepared by Latitude 33 titled *Shasta East – Preliminary Site Exhibit,* review of previous reports prepared by Geocon Incorporated in the area, a field investigation consisting of exploratory borings and infiltration tests; engineering analyses; laboratory testing; and preparation of this report.

The field investigation consisted of excavating six exploratory borings to depths of approximately 16 feet to examine the underlying soils within portions of the property. The approximate locations of the exploratory borings are shown the Geologic Map, Figure 2. Logs of the exploratory borings and a discussion of the field investigation are presented in Appendix A.

We performed laboratory tests on selected soil samples obtained during our field investigation to evaluate pertinent physical properties for engineering analyses and to assist in providing recommendations for site grading and foundation design criteria. Details of the laboratory testing and a summary of test results are presented in Appendix B.

We performed four, in-place, hydraulic-conductivity tests using a Soilmoisture Corp Aardvark Permeameter. The tests were conducted in 4-inch-diameter hand-excavated borings. The results of the hydraulic-conductivity testing and information relating to geotechnical aspects of storm water management are provided in Appendix C.

The conclusions and recommendations presented herein are based on our analysis of the data obtained from the exploratory field investigation, laboratory test results, and our experience with similar soil and geologic conditions on this and adjacent properties.

2. SITE AND PROJECT DESCRIPTION

The site is located southeast of the intersection of Shasta Street and Fortuna Avenue in San Diego, California. The site is bordered to the north by Fortuna Avenue, to the west by Shasta Street, to the east by an alley and residential homes, and to the south by residential structures. The site slopes gently from

north to south with elevations ranging from approximately 47 feet Mean Sea Level (MSL) at the north end of the property to approximately 33 feet MSL at the southern end. The site is currently occupied by three relatively large residential structures and landscaped areas. The residential structures are currently vacant.

We understand planned development will consist of demolishing the existing structures and landscaping to construct 30, single-family homes. We expected cuts and fills of approximately 3 feet or less across the site to produce the building pads. Sixteen infiltration BMP basins are planned along the perimeter of the property.

The descriptions above are based on a review of the referenced site plan. If development plans differ significantly from those described herein, Geocon Incorporated should be contacted for review and possible revisions to this report.

3. SOIL AND GEOLOGIC CONDITIONS

The site is underlain by undocumented fill and old terrace deposits (formerly Bay Point Formation). The soil and geologic unit are described below. Their approximate lateral extent is shown on the Geologic Map, Figure 2 (Map Pocket).

3.1 Undocumented Fill (Qudf)

We encountered undocumented fill in borings B-4 and B-6 to depths of about 1 to 1.5 feet thick. The fill materials consist of loose, damp to moist, dark brown, silty, fine sand. The undocumented fill is not suitable for support of additional fill or structural loads in its present condition and will require remedial grading in the form of removal, proper moisture conditioning as necessary, and compaction.

3.2 Old Terrace Deposits (Qt)

We encountered Quaternary-age old terrace deposits in all the exploratory borings performed during our site investigation. The terrace deposits generally consist of loose to medium dense, damp to moist, light brown to brown, fine sand. The upper portion of old terrace deposits is not suitable for the support of additional fill or structural loads and will require remedial grading in the form of removal, proper moisture conditioning, and compaction.

4. GROUNDWATER

We did not encounter groundwater during our investigation; however, it is not uncommon for groundwater or seepage conditions to develop where none previously existed. We expect groundwater to be near sea level, or at a depth of approximately 30 to 40 feet below the existing grade. Groundwater

elevation is dependent on seasonal precipitation, irrigation, land use and other factors and will vary as a result. Proper surface drainage will be important to the future performance of the project.

5. GEOLOGIC HAZARDS

5.1 Faulting and Seismicity

We used the computer program *EZ-FRISK* (2016) to locate known active faults within a search radius of 50 miles from the property. The nearest known active fault is the Newport-Inglewood/Rose Canyon Fault Zone, located less than 2 miles west of the site. The Newport-Inglewood/Rose Canyon Fault Zone is the dominant source of potential ground motion. Earthquakes that might occur on the Newport-Inglewood/Rose Canyon Fault Zone or other faults within the southern California and northern Baja California area are potential generators of significant ground motion at the site. The estimated deterministic maximum earthquake magnitude and peak ground acceleration for the Newport-Inglewood/Rose Canyon Fault are 7.5 and 0.53 g, respectively. Table 5.1.1 lists the estimated maximum earthquake magnitude and peak ground acceleration for the most dominant faults in relationship to the site location. We calculated peak ground acceleration (PGA) using Boore and Atkinson (2008), Campbell and Bozorgnia (2008), and Chiou and Youngs (2007) acceleration-attenuation relationships.

			Peak Ground Acceleration			
Fault Name	Distance from Site (miles)	Maximum Earthquake Magnitude (Mw)	Boore- Atkinson (2008) NGA USGS 2008 (g)	Campbell- Bozorgnia (2008) NGA USGS 2008 (g)	Chiou- Youngs (2007) NGA USGS 2008 (g)	
Newport-Inglewood	2	7.5	0.44	0.40	0.53	
Rose Canyon	2	6.9	0.42	0.40	0.49	
Coronado Bank	12	7.4	0.24	0.18	0.23	
Palos Verdes/Coronado Bank	12	7.7	0.26	0.19	0.26	
Elsinore	40	7.85	0.14	0.09	0.12	
Earthquake Valley	46	6.8	0.08	0.06	0.05	

 TABLE 5.1.1

 DETERMINISTIC SPECTRA SITE PARAMETERS

We used the computer program *EZ-FRISK* to perform a probabilistic seismic hazard analysis. The computer program *EZ-FRISK* operates under the assumption that the occurrence rate of earthquakes on each mapped Quaternary fault is proportional to the fault slip rate. The program accounts for earthquake magnitude as a function of fault rupture length. Site acceleration estimates are made using the earthquake magnitude and distance from the site to the rupture zone. The program also accounts for

uncertainty in each of following: (1) earthquake magnitude, (2) rupture length for a given magnitude, (3) location of the rupture zone, (4) maximum possible magnitude of a given earthquake, and (5) acceleration at the site from a given earthquake along each fault. By calculating the expected accelerations from considered earthquake sources, the program calculates the total average annual expected number of occurrences of site acceleration greater than a specified value. We utilized acceleration-attenuation relationships suggested by Boore and Atkinson (2008), Campbell and Bozorgnia (2008), and Chiou and Youngs (2007) in the analysis. Table 5.1.2 presents the site-specific probabilistic seismic hazard parameters including acceleration-attenuation relationships and the probability of exceedence.

 TABLE 5.1.2

 PROBABILISTIC SEISMIC HAZARD PARAMETERS

	Peak Ground Acceleration				
Probability of Exceedence	Boore-Atkinson NGA USGS 2008 (g)	Campbell-Bozorgnia NGA USGS 2008 (g)	Chiou-Youngs (2007) NGA USGS 2008 (g)		
2% in a 50 Year Period	0.58	0.51	0.62		
5% in a 50 Year Period	0.39	0.35	0.41		
10% in a 50 Year Period	0.28	0.24	0.27		

While listing peak accelerations is useful for comparison of potential effects of fault activity in a region, other considerations are important in seismic design, including frequency and duration of motion and soil conditions underlying the site. Seismic design of the structures should be evaluated in accordance with the California Building Code (CBC).

5.2 Ground Rupture

The risk associated with ground rupture hazard is low due to the absence of active faults at the subject site.

5.3 Liquefaction and Seismically Induced Settlement

The risk associated with liquefaction hazard is low due to the lack of near surface groundwater and the dense nature and age of the underlying old terrace deposit.

5.4 Landslides

The risk associated with landslide hazard is low due to the generally flat topography of the site and vicinity.

5.5 Tsunami and Seiche

According to CGS (2009) the site is located above the tsunami inundation line; therefore the risk associated with inundation during a tsunami event is low.

The site is located approximately 1,500 feet from the shoreline of Mission Bay at an elevation around 35 feet MSL; therefore, the risk associated with inundation during a seiche event is low.

6. CONCLUSIONS AND RECOMMENDATIONS

6.1 General

- 6.1.1 From a geotechnical engineering standpoint, it is our opinion that the site is suitable for the proposed improvements provided the recommendations presented herein are implemented in design and construction of the project.
- 6.1.2 The site is underlain by undocumented fill and old terrace deposits. Remedial grading in the form of removal and compaction of the undocumented fill and upper portion of the old terrace deposits will be necessary in areas to receive structures or settlement-sensitive improvements.
- 6.1.3 The proposed structures can be supported on conventional shallow footings founded in properly compacted fill as recommended herein.
- 6.1.4 Project grading and foundation plans have not been provided for our review. Geocon Incorporated should review the plans prior to the submittal to regulatory agencies for approval. Additional analysis may be required once the plans have been provided.
- 6.1.5 Groundwater was not encountered during our field investigation and is not expected to be encountered during grading operations.
- 6.1.6 The risk associated with geologic hazards due to ground rupture, liquefaction, landslides, and inundation by tsunami or seiche is low.
- 6.1.7 Subsurface conditions observed may be extrapolated to reflect general soil/geologic conditions at the site; however, some variations in subsurface conditions between boring locations should be expected.

6.2 Excavation and Soil Characteristics

- 6.2.1 Excavation of the site soil should be possible with moderate to heavy effort using conventional heavy-duty equipment.
- 6.2.2 Based on the soil types encountered during our recent field investigation, the onsite soils are expected to be "non-expansive" (expansion index [EI] of 20 or less) as defined by 2016 California Building Code (CBC) Section 1803.5.3. Table 6.2.1 presents soil classifications based on the expansion index. We expect a majority of the soil encountered possess a very low expansion potential (EI of 20 or less).

Expansion Index (EI)	Expansion Classification	2013 CBC Expansion Classification
0-20	Very Low	Non-Expansive
21 – 50	Low	
51 – 90	Medium	
91 – 130	High	Expansive
Greater Than 130	Very High	

TABLE 6.2.1EXPANSION CLASSIFICATION BASED ON EXPANSION INDEX

6.2.3 We performed laboratory tests on samples of the site soils to check the percentage of water-soluble sulfate content. Results from the previous laboratory water-soluble sulfate content tests presented in Appendix B and indicate that the on-site materials tested possess "Not Applicable" and "S0" sulfate exposure to concrete structures as defined by 2016 CBC Section 1904 and ACI 318-14 Chapter 19. Table 6.2.2 presents a summary of concrete requirements set forth by 2016 CBC Section 1904 and ACI 318-000 CBC Section 1904 and ACI 318. We recommend ACI guidelines be followed in determining the type of concrete to be utilized on the project. The presence of water-soluble sulfates is not a visually discernible characteristic; therefore, other soil samples from the site could yield different concentrations. Additionally, over time landscaping activities (i.e., addition of fertilizers and other soil nutrients) may affect the concentration.

Sulfate Exposure	Exposure Class	Water-Soluble Sulfate Percent by Weight	Cement Type	Maximum Water to Cement Ratio by Weight	Minimum Compressive Strength (psi)
Not Applicable	SO	0.00-0.10			2,500
Moderate	S1	0.10-0.20	П	0.50	4,000
Severe	S2	0.20-2.00	V	0.45	4,500
Very Severe	S3	> 2.00	V+Pozzolan or Slag	0.45	4,500

TABLE 6.2.2 REQUIREMENTS FOR CONCRETE EXPOSED TO SULFATE-CONTAINING SOLUTIONS

6.2.4 Geocon Incorporated does not practice in the field of corrosion engineering; therefore, further evaluation by a corrosion engineer may be needed if improvements susceptible to corrosion are planned.

6.3 Grading

- 6.3.1 All grading should be performed in accordance with the *Recommended Grading Specifications* contained in Appendix D. The recommendations of this section take precedence over those presented in Appendix D.
- 6.3.2 Prior to commencing grading, a preconstruction conference should be held at the site with the owner or developer, grading contractor, civil engineer, and geotechnical engineer in attendance. Special soil handling and/or the grading plans can be discussed at that time.
- 6.3.3 Grading should be performed in conjunction with the observation and compaction testing services of Geocon Incorporated. Fill soil should be observed on a full-time basis during placement and tested to check in-place dry density and moisture content.
- 6.3.4 Site preparation should begin with the removal of all deleterious material and vegetation. The depth of removal should be such that material exposed in cut areas or soils to be used as fill are relatively free of organic matter. Material generated during stripping and/or site demolition should be exported from the site.
- 6.3.5 All existing utilities that will be abandoned should be completely removed, capped at the property limits, and the resulting excavation backfilled with compacted fill.
- 6.3.6 To provide support for the new structures, we recommend all of the undocumented fill and the upper portion of the old terrace deposits be removed to a depth of 5 feet below pad grade or 3 feet below the bottom of proposed footings, whichever is deeper, and replaced as properly compacted fill. On site soil, which is free of deleterious material, is suitable for use as compacted fill. The removals should extend a horizontal distanced beyond the edge of the building pads a distance of at least 5 feet.
- 6.3.7 The surface of areas to receive fill should be scarified to a depth of approximately 12 inches; moisture conditioned to above optimum moisture content; and compacted. Fill soils may then be placed and compacted in layers to the design finish grade elevations. The layers should be no thicker than will allow for adequate bonding and compaction. All fill and backfill should be compacted to at least 90 percent of maximum dry density at or slightly above optimum moisture content, as determined by the current version of ASTM D 1557.
- 6.3.8 Imported fill should consist of granular soil with a "very low" to "low" expansion potential (El of 50 or less) and be free of deleterious material and stones larger than 3 inches. Geocon Incorporated should be notified of the import soil source and should perform laboratory

testing prior to its arrival at the site to evaluate its suitability as fill material. In addition, the imported soil should be certified as being free of hazardous contaminants as well as chemical properties that could adversely impact proposed construction material.

6.4 Seismic Design Criteria

6.4.1 We used the computer program U.S. Seismic Design Maps (USGS, 2016). Table 6.4.1 summarizes site-specific design criteria obtained from the 2016 California Building Code (CBC; Based on the 2015 International Building Code [IBC] and ASCE 7-10), Chapter 16 Structural Design, Section 1613 Earthquake Loads. The short spectral response uses a period of 0.2 second. The building structure and improvements should be designed using a Site Class D. We evaluated the site class based on the discussion in Section 1613.3.2 of the 2016 CBC and Table 20.3-1 of ASCE 7-10. The values presented in Table 6.4.1 are for the risk-targeted maximum considered earthquake (MCE_R).

Parameter	Value	2013 CBC Reference
Site Class	D	Section 1613.3.2
MCE _R Ground Motion Spectral Response Acceleration – Class B (short), S _S	1.214 g	Figure 1613.3.1(1)
MCE _R Ground Motion Spectral Response Acceleration – Class B (1 sec), S ₁	0.466 g	Figure 1613.3.1(2)
Site Coefficient, F _A	1.014	Table 1613.3.3(1)
Site Coefficient, Fv	1.534	Table 1613.3.3(2)
Site Class Modified MCE_R Spectral Response Acceleration (short), S_{MS}	1.232 g	Section 1613.3.3 (Eqn 16-37)
Site Class Modified MCE_R Spectral Response Acceleration (1 sec), S_{M1}	0.714 g	Section 1613.3.3 (Eqn 16-38)
5% Damped Design Spectral Response Acceleration (short), S_{DS}	0.821 g	Section 1613.3.4 (Eqn 16-39)
5% Damped Design Spectral Response Acceleration (1 sec), S_{D1}	0.476 g	Section 1613.3.4 (Eqn 16-40)

TABLE 6.4.12016 CBC SEISMIC DESIGN PARAMETERS

6.4.2 Table 6.4.2 presents additional seismic design parameters for projects located in Seismic Design Categories of D through F in accordance with ASCE 7-10 for the mapped maximum considered geometric mean (MCEG).

Parameter	Value	ASCE 7-10 Reference
Mapped MCE_G Peak Ground Acceleration, PGA	0.538 g	Figure 22-7
Site Coefficient, F _{PGA}	1.000	Table 11.8-1
Site Class Modified MCE_G Peak Ground Acceleration, PGA _M	0.538 g	Section 11.8.3 (Eqn 11.8-1)

TABLE 6.4.22016 CBC SITE ACCELERATION DESIGN PARAMETERS

6.4.3 Conformance to the criteria in Tables 6.4.1 and 6.4.2 for seismic design does not constitute any kind of guarantee or assurance that significant structural damage or ground failure will not occur if a large earthquake occurs. The primary goal of seismic design is to protect life, not to avoid all damage, since such design may be economically prohibitive.

6.5 Foundation and Concrete Slabs-On-Grade Recommendations

- 6.5.1 The foundation and slab-on-grade recommendations presented herein are based on soil conditions only and are not intended to be used in lieu of those required for structural purposes.
- 6.5.2 The following foundation recommendations are based on the assumption that remedial grading will be performed as recommended herein and that footings will be founded entirely on properly compacted fill. These recommendations also assume that the soils within 3 feet of finish grade will consist of soils with an Expansion Index of 50 or less.
- 6.5.3 Conventional continuous footings should have a minimum embedment depth of 18 inches below lowest adjacent grade. The footings should be at least 12 inches wide. Isolated spread footings should be at least 2 feet square and founded at least 18 inches below lowest adjacent pad grade. A footing dimension detail is presented on Figure 3.
- 6.5.4 Footings, as proportioned above, may be designed for an allowable soil bearing pressure of 2,000 pounds per square foot (psf), dead plus live loads. We estimate total static settlement as a result of footings imposing the above bearing pressures to be on the order of 1-inch total and ³/₄-inch differential in 40 feet.
- 6.5.5 The allowable bearing pressure may be increased by up to one-third for transient loads due to wind or seismic forces.

- 6.5.6 Continuous footings should be reinforced with four, No. 5 steel, reinforcing bars, two placed near the top of the footing and two near the bottom. The project structural engineer should design reinforcement for spread footings.
- 6.5.7 Foundation excavations should be observed by the geotechnical engineer (a representative of Geocon Incorporated) prior to the placement of reinforcing steel and concrete to assess that the exposed soil conditions are consistent with those expected and that they have been extended to the appropriate bearing strata. If unexpected soil conditions are encountered, foundation modifications may be required.
- 6.5.8 The contractor should maintain the subgrade soils at the soil placement moisture content by sprinkling water in the footing excavations and slab area as necessary.
- 6.5.9 Interior concrete slabs-on-grade for the proposed structure should be at least 4 inches thick. Minimum slab reinforcement should consist of No. 3 steel, reinforcing bars placed 18 inches on center in both horizontal directions and positioned near the slab midpoint.
- 6.5.10 A vapor retarder should underlie slabs that may receive moisture-sensitive floor coverings or may be used to store moisture-sensitive materials. The vapor retarder design should be consistent with the guidelines presented in the American Concrete Institute's (ACI) Guide for Concrete Slabs that Receive Moisture-Sensitive Flooring Materials (ACI 302.2R-06). The vapor retarder should be installed in accordance with manufacturer's recommendations and ASTM requirements in a manner that prevents puncture. The project architect or developer should specify the type of vapor retarder used based on the type of floor covering that will be installed and if the structure will possess a humidity controlled environment.
- 6.5.11 The project foundation engineer, architect, and/or developer should determine the thickness of the bedding sand below the slab. Typically, 3 or 4 inches of sand bedding is used in Southern California. Geocon Incorporated should be contacted to provide recommendations if the bedding sand is thicker than 6 inches.
- 6.5.12 The foundation design engineer should provide appropriate concrete mix design criteria and curing measures to assure proper curing of the slab by reducing the potential for rapid moisture loss and subsequent cracking and/or slab curl. The foundation design engineer should designate the concrete mix design and proper curing methods on the foundation plans. It is critical that the foundation contractor understands and follows the recommendations presented on the foundation plans.

- 6.5.13 Crack control joints should be spaced at intervals not greater than 10 feet and should be constructed using sawcuts or other methods as soon as practical following concrete placement. Crack control joints should extend a minimum depth of one-fourth the slab thickness. Construction joints should be designed by the project structural engineer.
- 6.5.14 As an alternative to the conventional foundation recommendations, consideration should be given to the use of post-tensioned concrete slab and foundation systems for the support of the proposed structures. The post-tensioned systems should be designed by a structural engineer experienced in post-tensioned slab design and design criteria of the Post-Tensioning Institute (PTI), Third Edition, as required by the 2016 California Building Code (CBC Section 1808.6). Although this procedure was developed for expansive soil conditions, it can also be used to reduce the potential for foundation distress due to differential fill settlement. The post-tensioned design should incorporate the geotechnical parameters presented on Table 6.5.1. The parameters presented in Table 6.5.1 are based on the guidelines presented in the PTI, Third Edition design manual.

TABLE 6.5.1
POST-TENSIONED FOUNDATION SYSTEM DESIGN PARAMETERS

Thornthwaite Index	-20
Equilibrium Suction	3.9
Edge Lift Moisture Variation Distance, e_M (feet)	5.1
Edge Lift, y_M (inches)	1.10
Center Lift Moisture Variation Distance, e_M (feet)	9.0
Center Lift, y _M (inches)	0.47

- 6.5.15 The foundations for the post-tensioned slabs should be embedded in accordance with the recommendations of the structural engineer. If a post-tensioned mat foundation system is planned, the slab should possess a thickened edge with a minimum width of 12 inches and extend at least 6 inches below the clean sand or crushed rock layer.
- 6.5.16 If the structural engineer proposes a post-tensioned foundation design method other than PTI, Third Edition:
 - The deflection criteria presented in Table 6.5.1 are still applicable.
 - Interior stiffener beams should be used.
 - The width of the perimeter foundations should be at least 12 inches.
 - The perimeter footing embedment depths should be at least 18 inches. The embedment depths should be measured from the lowest adjacent pad grade.

- 6.5.17 Our experience indicates post-tensioned slabs are susceptible to excessive edge lift, regardless of the underlying soil conditions. Placing reinforcing steel at the bottom of the perimeter footings and the interior stiffener beams may mitigate this potential. The placement of the reinforcing tendons in the top of the slab and the resulting eccentricity after tensioning could reduce the ability of the system to mitigate edge lift. The structural engineer should design the foundation system to reduce the potential of edge lift occurring for the proposed structures.
- 6.5.18 During the construction of the post-tension foundation system, the concrete should be placed monolithically. Under no circumstances should cold joints form between the footings/grade beams and the slab during the construction of the post-tension foundation system.
- 6.5.19 Post-tensioned foundations may be designed for an allowable soil bearing pressure of 2,000 pounds per square foot (psf) (dead plus live load). This bearing pressure may be increased by one-third for transient loads due to wind or seismic forces. The estimated maximum total and differential settlement for the planned structures due to foundation loads is 1 inch and ³/₄ inch, respectively. Differential settlement is estimated to occur over a span of 40 feet.
- 6.5.20 Isolated footings outside of the post-tensioned slab area, if present, should have the minimum embedment depth and width recommended for conventional foundations. The use of isolated footings, which are located beyond the perimeter of the building and support structural elements connected to the building, are not recommended. Where this condition cannot be avoided, the isolated footings should be connected to the building foundation system with grade beams.
- 6.5.21 Special subgrade presaturation is not deemed necessary prior to placing concrete; however, the exposed foundation and slab subgrade soil should be moisture conditioned, as necessary, to maintain a moist condition as would be expected in any such concrete placement.
- 6.5.22 Where buildings or other improvements are planned near the top of a slope steeper than 3:1 (horizontal:vertical), special foundations and/or design considerations are recommended due to the tendency for lateral soil movement to occur.
 - For fill slopes less than 20 feet high or cut slopes regardless of height, building footings should be deepened such that the bottom outside edge of the footing is at least 7 feet horizontally from the face of the slope.
 - When located next to a descending 3:1 (horizontal:vertical) fill slope or steeper, the foundations should be extended to a depth where the minimum horizontal distance is equal to H/3 (where H equals the vertical distance from the top of the fill slope to the base of the fill soil) with a minimum of 7 feet but need not exceed 40 feet. The horizontal distance is measured from the outer, deepest edge of the footing to the

face of the slope. A post-tensioned slab and foundation system or mat foundation system can be used to help reduce potential foundation distress associated with slope creep and lateral fill extension. Specific design parameters or recommendations for either of these alternatives can be provided if desired.

- If swimming pools are planned, Geocon Incorporated should be contacted for a review of specific site conditions.
- Swimming pools located within 7 feet of the top of cut or fill slopes are not recommended. Where such a condition cannot be avoided, the portion of the swimming pool wall within 7 feet of the slope face be designed assuming that the adjacent soil provides no lateral support. This recommendation applies to fill slopes up to 30 feet in height, and cut slopes regardless of height. For swimming pools located near the top of fill slopes greater than 30 feet in height, additional recommendations may be required and Geocon Incorporated should be contacted for a review of specific site conditions.
- Although other improvements, which are relatively rigid or brittle, such as concrete flatwork or masonry walls, may experience some distress if located near the top of a slope, it is generally not economical to mitigate this potential. It may be possible, however, to incorporate design measures which would permit some lateral soil movement without causing extensive distress. Geocon Incorporated should be consulted for specific recommendations.
- 6.5.23 The exterior flatwork recommendations provided herein assumes that grading is performed as recommended above and that the near surface soils are very low to low expansive (El <50). Exterior slabs not subjected to vehicular traffic should be a minimum of 4 inches thick and when in excess of 8 feet wide, reinforced with 6 x 6-6/6 welded wire mesh. The mesh should be placed in the middle of the slab. Proper mesh positioning is critical to future performance of the slabs. The contractor should take extra measures to provide proper mesh placement. Prior to construction of slabs, the upper 12 inches of subgrade soils should be moisture conditioned one to three percent above optimum moisture content and compacted to at least 90 percent of the laboratory maximum dry density per ASTM 1557.
- 6.5.24 To control the location and spread of concrete shrinkage and/or expansion cracks, it is recommended that crack-control joints be included in the design of concrete slabs. Crack-control joint spacing should not exceed, in feet, twice the recommended slab thickness in inches (e.g., 10 feet by 10 feet). Crack-control joints should be created while the concrete is still fresh using a grooving tool or shortly thereafter using saw cuts. The structural engineer should take criteria of the American Concrete Institute into consideration when establishing crack-control spacing patterns.
- 6.5.25 The recommendations of this report are intended to reduce the potential for cracking of slabs due to expansive soil (if present), differential settlement of existing soil or soil with varying

thicknesses. However, even with the incorporation of the recommendations presented herein, foundations, stucco walls, and slabs-on-grade placed on such conditions may still exhibit some cracking due to soil movement and/or shrinkage. The occurrence of concrete shrinkage cracks is independent of the supporting soil characteristics. Their occurrence may be reduced and/or controlled by limiting the slump of the concrete, proper concrete placement and curing, and by the placement of crack control joints at periodic intervals, in particular, where re-entrant slab corners occur.

- 6.5.26 Foundation excavations should be observed by a representative of Geocon Incorporated prior to the placement of reinforcing steel and concrete to check that the exposed soil conditions are consistent with those anticipated and have been extended to appropriate bearing strata. If unexpected soil conditions are encountered, foundation modifications may be required.
- 6.5.27 Geocon Incorporated should be consulted to provide additional design parameters as required by the structural engineer.

6.6 Retaining Walls and Lateral Loads

- 6.6.1 Retaining walls that are allowed to rotate more than 0.001H (where H equals the height of the retaining portion of the wall) at the top of the wall and having a level backfill surface should be designed for an active soil pressure equivalent to the pressure exerted by a fluid density of 35 pcf. Where the backfill will be inclined at 2:1 (horizontal:vertical), an active soil pressure of 50 pcf is recommended. Expansive soil should not be used as backfill material behind retaining walls. Soil placed for retaining wall backfill should have an Expansion Index less than 50.
- 6.6.2 Where walls are restrained from movement at the top, an additional uniform pressure of 7H psf (where H equals the height of the retaining wall portion of the wall in feet) should be added to the active soil pressure where the wall possesses a height of 8 feet or less and 12H where the wall is greater than 8 feet. For retaining walls subject to vehicular loads within a horizontal distance equal to two-thirds the wall height, a surcharge equivalent to two feet of fill soil should be added.
- 6.6.3 Soil contemplated for use as retaining wall backfill, including imported soils, should be identified in the field prior to backfill. At that time Geocon Incorporated should obtain samples for laboratory testing to evaluate its suitability. Modified lateral earth pressures may be necessary if the backfill soil does not meet the required expansion index or shear strength. City or regional standard wall designs, if used, are based on a specific active lateral earth pressure and/or soil friction angle. In this regard, on-site soil or import soil to be used as

backfill may or may not meet the values for standard wall designs. Geocon Incorporated should be consulted to assess the suitability of the on-site soil or imported soil for use as wall backfill if standard wall designs will be used.

- 6.6.4 Unrestrained walls will move laterally when backfilled and loading is applied. The amount of lateral deflection is dependent on the wall height, the type of soil used for backfill, and loads acting on the wall. The wall designer should provide appropriate lateral deflection quantities for planned retaining walls structures, if applicable. These lateral values should be considered when planning types of improvements above retaining wall structures.
- 6.6.5 Retaining walls should be provided with a drainage system adequate to prevent the buildup of hydrostatic forces and should be waterproofed as required by the project architect. The use of drainage openings through the base of the wall (weep holes) is not recommended where the seepage could be a nuisance or otherwise adversely affect the property adjacent to the base of the wall. The above recommendations assume a properly compacted granular (El <50) free-draining backfill material with no hydrostatic forces or imposed surcharge load. A typical retaining wall drainage detail is presented on Figure 4. If conditions different than those described are expected, or if specific drainage details are desired, Geocon Incorporated should be contacted for additional recommendations.
- 6.6.6 In general, wall foundations having a minimum embedment depth and width of 1 foot may be designed for an allowable soil bearing pressure of 2,000 psf. The allowable soil bearing pressure may be increased by an additional 300 psf and 500 psf for each additional foot of foundation width and depth, respectively, to a maximum allowable bearing capacity of 3,500 psf. These values are for dead plus live loads and may be increased by one-third when considering transient loads due to wind or seismic forces.
- 6.6.7 The proximity of the foundation to the top of a slope steeper than 3:1 could impact the allowable soil bearing pressure. Therefore, Geocon Incorporated should be consulted where such a condition is anticipated. As a minimum, wall footings should be deepened such that the bottom outside edge of the footing is at least seven feet from the face of slope when located adjacent and/or at the top of descending slopes.
- 6.6.8 The structural engineer should determine the seismic design category for the project in accordance with Section 1613 of the CBC. If the project possesses a seismic design category of D, E, or F, retaining walls that support more than 6 feet of backfill should be designed with seismic lateral pressure in accordance with Section 1803.5.12 of the 2016 CBC. The seismic load is dependent on the retained height where H is the height of the wall, in feet, and the calculated loads result in pounds per square foot (psf) exerted at the base of the wall

and zero at the top of the wall. A seismic load of 21H should be used for design. We used the peak ground acceleration adjusted for Site Class effects, PGA_M , of 0.538 g calculated from ASCE 7-10 Section 11.8.3 and applied a pseudo-static coefficient of 0.33.

- 6.6.9 For resistance to lateral loads, a passive earth pressure equivalent to a fluid density of 300 pcf is recommended for footings or shear keys poured neat against properly compacted granular fill soils or undisturbed formation materials. The passive pressure assumes a horizontal surface extending away from the base of the wall at least five feet or three times the surface generating the passive pressure, whichever is greater. The upper 12 inches of material not protected by floor slabs or pavement should not be included in the design for lateral resistance. Where walls are planned adjacent to and/or on descending slopes, a passive pressure of 150 pcf should be used in design.
- 6.6.10 An allowable friction coefficient of 0.4 may be used for resistance to sliding between soil and concrete. This friction coefficient may be combined with the passive earth pressure when determining resistance to lateral loads.

6.7 Slope Maintenance

6.7.1 Slopes that are steeper than 3:1 (horizontal:vertical) may, under conditions which are both difficult to prevent and predict, be susceptible to near surface (surficial) slope instability. The instability is typically limited to the outer three feet of a portion of the slope and usually does not directly impact the improvements on the pad areas above or below the slope. The occurrence of surficial instability is more prevalent on fill slopes and is generally preceded by a period of heavy rainfall, excessive irrigation, or the migration of subsurface seepage. The disturbance and/or loosening of the surficial soils, as might result from root growth, soil expansion, or excavation for irrigation lines and slope planting, may also be a significant contributing factor to surficial instability. It is, therefore, recommended that, to the maximum extent practical: (a) disturbed/loosened surficial soils be either removed or properly recompacted, (b) irrigation systems be periodically inspected and maintained to eliminate leaks and excessive irrigation, and (c) surface drains on and adjacent to slopes be periodically maintained to preclude ponding or erosion. It should be noted that although the incorporation of the above recommendations should reduce the potential for surficial slope instability, it will not eliminate the possibility, and, therefore, it may be necessary to rebuild or repair a portion of the project's slopes in the future.

6.8 Storm Water Management

6.8.1 If storm water management devices are not properly designed and constructed, there is a risk for distress to improvements and property located hydrologically down gradient or adjacent

to these devices. Factors such as the amount of water being detained, its residence time, and soil permeability have an important effect on seepage transmission and the potential adverse impacts that may occur if the storm water management features are not properly designed and constructed. We have not performed a hydrogeological study at the site. If infiltration of storm water runoff into the subsurface occurs, downstream improvements may be subjected to seeps, springs, slope instability, raised groundwater, movement of foundations and slabs, or other undesirable impacts as a result of water infiltration.

6.8.2 We performed an infiltration study on the property. A summary of our study and storm water management recommendations are provided in Appendix C. Based on the results of our study, infiltration is considered infeasible.

6.9 Site Drainage and Moisture Protection

- 6.9.1 Adequate site drainage is critical to reduce the potential for differential soil movement, erosion and subsurface seepage. Under no circumstances should water be allowed to pond adjacent to footings. The site should be graded and maintained such that surface drainage is directed away from structures in accordance with 2016 CBC 1804.4 or other applicable standards. In addition, surface drainage should be directed away from the top of slopes into swales or other controlled drainage devices. Roof and pavement drainage should be directed into conduits that carry runoff away from the proposed structure.
- 6.9.2 In the case of basement walls or building walls retaining landscaping areas, a water-proofing system should be used on the wall and joints, and a Miradrain drainage panel (or similar) should be placed over the waterproofing. The project architect or civil engineer should provide detailed specifications on the plans for all waterproofing and drainage.
- 6.9.3 Underground utilities should be leak free. Utility and irrigation lines should be checked periodically for leaks, and detected leaks should be repaired promptly. Detrimental soil movement could occur if water is allowed to infiltrate the soil for prolonged periods of time.
- 6.9.4 Landscaping planters adjacent to paved areas are not recommended due to the potential for surface or irrigation water to infiltrate the pavement's subgrade and base course. We recommend that subdrains to collect excess irrigation water and transmit it to drainage structures or impervious above-grade planter boxes be used. In addition, where landscaping is planned adjacent to the pavement, we recommend construction of a cutoff wall along the edge of the pavement that extends at least 6 inches below the bottom of the base material.

6.10 Grading and Foundation Plan Review


6.10.1 Geocon Incorporated should review the grading and foundation plans for the project prior to final design submittal to determine if additional analysis and/or recommendations are required.

LIMITATIONS AND UNIFORMITY OF CONDITIONS


- 1. The firm that performed the geotechnical investigation for the project should be retained to provide testing and observation services during construction to provide continuity of geotechnical interpretation and to check that the recommendations presented for geotechnical aspects of site development are incorporated during site grading, construction of improvements, and excavation of foundations. If another geotechnical firm is selected to perform the testing and observation services during construction operations, that firm should prepare a letter indicating their intent to assume the responsibilities of project geotechnical engineer of record. A copy of the letter should be provided to the regulatory agency for their records. In addition, that firm should provide revised recommendations concerning the geotechnical aspects of the proposed development, or a written acknowledgement of their concurrence with the recommendations presented in our report. They should also perform additional analyses deemed necessary to assume the role of Geotechnical Engineer of Record.
- 2. The recommendations of this report pertain only to the site investigated and are based upon the assumption that the soil conditions do not deviate from those disclosed in the investigation. If any variations or undesirable conditions are encountered during construction, or if the proposed construction will differ from that anticipated herein, Geocon Incorporated should be notified so that supplemental recommendations can be given. The evaluation or identification of the potential presence of hazardous or corrosive materials was not part of the scope of services provided by Geocon Incorporated.
- 3. This report is issued with the understanding that it is the responsibility of the owner, or of his representative, to ensure that the information and recommendations contained herein are brought to the attention of the architect and engineer for the project and incorporated into the plans, and that the necessary steps are taken to see that the contractor and subcontractors carry out such recommendations in the field.
- 4. The findings of this report are valid as of the present date. However, changes in the conditions of a property can occur with the passage of time, whether they are due to natural processes or the works of man on this or adjacent properties. In addition, changes in applicable or appropriate standards may occur, whether they result from legislation or the broadening of knowledge. Accordingly, the findings of this report may be invalidated wholly or partially by changes outside our control. Therefore, this report is subject to review and should not be relied upon after a period of three years.




Plotted:12/19/2016 2:06PM | By: ALVIN LADRILLONO | File Location:Y:\PROJECTS\G1832-42-03 (Shasta East)\DETAILS\G1832-42-03 Vic Map.dwg



Plotted:12/19/2016 2:09PM | By:ALVIN LADRILLONO | File Location:Y:\PROJECTS\G1832-42-03 (Shasta East)\SHEETS\G1832-42-03 Site Plan.dwg



Plotted:12/19/2016 2:09PM | By:ALVIN LADRILLONO | Flie Location:Y:)PROJECTS\G1832-42-03 (Shasta East)\DETAILS\Wall-Column Footing Dimension Detail (COLFOOT2).dvg



Plotted: 12/19/2016 2:08PM | By:ALVIN LADRILLONO | File Location:Y:PROJECTS\G1832-42-03 (Shasta East)\DETAILS\Typical Retaining Wall Drainage Detail (RWDD7A).dwg





APPENDIX A

FIELD INVESTIGATION

The field investigation was performed on November 7 and 8, 2016, and included drilling six 8-inchdiameter exploratory borings. The small-diameter borings were drilled using a Fraste, limited-access drill rig equipped with hollow-stem augers. The approximate locations of the exploratory borings are shown on the Geologic Map, Figure 2. The boring locations were located in the field based on visual reference points; therefore, actual locations may deviate slightly.

Logs of our borings are presented as Figures A-1 through A-6. The logs depict the soil and geologic conditions encountered and the depth at which samples were obtained. The soil encountered were visually examined, classified, and logged in general accordance with American Society for Testing and Materials (ASTM) practice for Description and Identification of Soils (Visual-Manual Procedure D 2488).

Additionally, we performed four, in-place, hydraulic conductivity tests. The infiltration tests were conducted in 4-inch-diameter, hand excavated-borings ranging in depths from 2 to 3.4 feet below existing ground surface using a Soilmoisture Corp. Aardvark Permeameter. The data was analyzed using USBR 7300-89 methodology. Results from the infiltration testing is presented in Appendix C.

DEPTH)GY	ATER	SOIL	BORING B 1	TION NCE FT.)	SITY (:	MOISTURE CONTENT (%)
IN FEET	SAMPLE NO.	ГІТНОГОСУ	GROUNDWATER	CLASS (USCS)	ELEV. (MSL.) 49' DATE COMPLETED 11-08-2016	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	10ISTU
			GRO		EQUIPMENT FRASTE BY: J. LAYOG	- BE	DR	20
0 -					MATERIAL DESCRIPTION			
0 _	B1-1			SP-SM/SM	TERRACE DEPOSITS (Qt) Loose, moist, light brown to brown, fine grained SAND with silt to Silty SAND; 2-4" sod at surface	_		
2 -						-		
-	B1-2					_ 7		
4 –						-		
_	B1-3					- 10		
6 -	BIJ					_		
					-Becomes medium dense			
8 –						-		
_			-			-		
10 –	B1-4					- 15		
_						-		
12 –					-Layer of gravel approx. 6" thick	-		
-						-		
14 —						_		
	B1-5					25		
16 -					BORING TERMINATED AT 16 FEET Groundwater not encountered Backfilled with cuttings on 11-08-2016			
igure	A-1,				-64		G183	2-42-03.0
og 01	f Borin	дв	ı, F	_				
SAMP	PLE SYME	BOLS				E SAMPLE (UNDI		



DEPTH		β	ATER	SOIL	BORING B 2	TION NCE FT.)	SITY	RE (%)
IN FEET	SAMPLE NO.	ПТНОГОСУ	GROUNDWATER	CLASS (USCS)	ELEV. (MSL.) 45' DATE COMPLETED 11-08-2016	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE
			GROI	(0000)	EQUIPMENT FRASTE BY: J. LAYOG	PEN (BL	DR	ΣÖ
					MATERIAL DESCRIPTION			
0 –	B2-1		5		2" ASPHALT Over 3" BASE			
-				SP-SM/SM	TERRACE DEPOSITS (Qt) Medium dense, damp to moist, light brown to brown, fine SAND with silt to Silty SAND	-		
2 -	B2-2					18		
_	B2-2					- 18		
4 –						_		
_	B2-3	×				27		
6 -					-Becomes moist	-		
_						_		
8 –						-		
_						-		
10 -						_		
-	B2-4				-Becomes light brown	38		
_						-		
12 –						-		
_								
					-Layer of gravel approx. 6" thick			
14 –					-Becomes dense	-		
-	B2-5					- 50		
16 -								
10					BORING TERMINATED AT 16 FEET Groundwater not encountered			
					Backfilled with cuttings on 11-08-2016			
igure	A-2,				of 1	1	G183	2-42-03.0
.og o	f Borin	ува	∠, ⊧	_				
SAMD	LE SYME	OLS			LING UNSUCCESSFUL I STANDARD PENETRATION TEST DRIVE S RBED OR BAG SAMPLE I WATER	SAMPLE (UNDIS	STURBED)	

DEPTH	SAMPLE	ПТНОГОGY	GROUNDWATER	SOIL	BORING B 3	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE CONTENT (%)
IN FEET	NO.	IDHTI	IND	CLASS (USCS)	ELEV. (MSL.) 43' DATE COMPLETED 11-08-2016	NETR	RY DE (P.C	
			GRO		EQUIPMENT FRASTE BY: J. LAYOG	- Br	ă	- ŭ
0 -					MATERIAL DESCRIPTION			
				SP-SM/SM	TERRACE DEPOSITS (Qt) Loose, damp to moist, light brown to brown, fine SAND with silt to Silty SAND; 3-4" sod at surface	_		
2 -						-		
_	B3-1					_ 14		
4 –								
-								
_	B3-2				-Becomes moist	- 13		
6 -						-		
-						-		
8 –						_		
_								
10 –	B3-3					26		
-						-		
12 –						-		
_						-		
14 –								
14					-Layer of gravel approx. 6" thick -Becomes dense			
_	B3-4		:		-No sample; gravel in shoe	64		
16 —					BORING TERMINATED AT 16FEET Groundwater not encountered Backfilled with cuttings on 11-08-2016			
igure		1					G183	2-42-03.G
	f Boring	g B 3	3, F	Page 1	of 1			
SAMPLE SYMBOLS Image: Sampling unsuccessful Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetration test Image: Standard penetratis Image: Standard penetration test								



PROJEC	T NO. G18	32-42-0	3					
DEPTH IN FEET	SAMPLE NO.	ГІТНОГОЄУ	GROUNDWATER	SOIL CLASS (USCS)	BORING B 4 ELEV. (MSL.) 39' DATE COMPLETED 11-08-2016 EQUIPMENT FRASTE BY: J. LAYOG	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE CONTENT (%)
					MATERIAL DESCRIPTION			
- 0 -	B4-1			SM	UNDOCUMENTED FILL (Qudf) Loose, moist, dark brown to brown, Silty, fine SAND; 3-4" of sod at surface			
- 2 -	B4-2			SP-SM/SM	TERRACE DEPOSITS (Qt) Loose, moist, light brown to brown, fine SAND with silt to Silty SAND	- 14		
						-		
	B4-3					7 		
					-Becomes medium dense	-		
 - 10 -	B4-4					- - 34		
					\neg -Gravel in shoe			
					BORING TERMINATED AT 11 FEET Groundwater not encountered Backfilled with cuttings on 11-08-2016			
Figure Log o	e A-4, f Boring	gB4	1, F	Page 1	of 1		G183	2-42-03.GPJ
SAMF	PLE SYMB	OLS				SAMPLE (UNDI		



DEPTH IN FEET	SAMPLE NO.	КООТОНТІ	GROUNDWATER	SOIL CLASS (USCS)	BORING B 5 ELEV. (MSL.) 37' DATE COMPLETED 11-08-2016 EQUIPMENT FRASTE BY: J. LAYOG	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE CONTENT (%)
			G			-		
0 -								
_				SP-SM/SM	TERRACE DEPOSITS (Qt) Loose, damp to moist, light brown to brown, fine SAND with silt to Silty SAND; 3-4" of sod at surface	_		
2 -						-		
-	B5-1					- 13		
4 –								
_	B5-2					12		
6 -						-		
_						-		
8 –						-		
_								
10 -					-Layer of gravel approx. 6-12" thick	-		
-						-		
12 –						-		
-								
14								
14 –								
_	В5-3				-Becomes medium dense	15		
16 –					BORING TERMINATED AT 16 FEET Groundwater not encountered Backfilled with cuttings on 11-08-2016			
igure og of	e A-5, f Boring	g B t	5, F	Page 1	of 1	1	G183	32-42-03.v
		-	-	_		SAMPLE (UNDIS		



DEPTH		GY	VTER		BORING B 6) XIIX	RE (%)
IN FEET	SAMPLE NO.	ГІТНОГОСУ	GROUNDWATER	SOIL CLASS (USCS)	ELEV. (MSL.) 38' DATE COMPLETED 11-08-2016	PENETRATION RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE
			GRO	. ,	EQUIPMENT FRASTE BY: J. LAYOG	(BL BL BL	DR	20
-					MATERIAL DESCRIPTION			
0 -	B6-1			SM	UNDOCUMENTED FILL (Qudf) Loose, damp, dark brown, Silty, fine SAND	_		
2 -				SP-SM/SM	TERRACE DEPOSITS (Qt) Loose, damp to moist, light brown to brown, fine SAND with silt to Silty SAND	-		
-	B6-2	8			SAND	_ 6		
4 –			•			_		
6 -	B6-3					11 -		
_						-		
8 -					-Becomes medium dense	-		
10 –	B6-4					- 19		
_						_		
12 –						_		
14 –			•			-		
-	B6-5				-Becomes medium grained, yellowish brown	- 29		
16 —					-Gravel in shoe BORING TERMINATED AT 16 FEET Groundwater not encountered Backfilled with cuttings on 11-08-2016			
igure	e A-6, f Boring			Page 1	of 1		G183	32-42-03.0
			, г			SAMPLE (UNDIS	STURBED)	





APPENDIX B

LABORATORY TESTING

Laboratory tests were performed in accordance with generally accepted test methods of the American Society for Testing and Materials (ASTM) or other suggested procedures. Selected soil samples were tested for their maximum dry density and optimum moisture content, shear strength, expansion index, water-soluble sulfate content, resistance value (R-value), gradation characteristics, and consolidation characteristics. The results of our laboratory tests are presented on the following tables and graphs.

TABLE B-I SUMMARY OF LABORATORY MAXIMUM DRY DENSITY AND OPTIMUM MOISTURE CONTENT TEST RESULTS ASTM D 1557

Sample No.	Description	Maximum Dry Density (pcf)	Optimum Moisture Content (% dry wt.)
B4-1	Brown, Silty, fine to medium, SAND; trace gravel	119.0	10.0

TABLE B-II SUMMARY OF LABORATORY REMOLDED DIRECT SHEAR TEST RESULTS ASTM D 3080

Sample No.	Dry	Moisture	Peak Unit	Peak Angle of Shear
	Density (pcf)	Content (%)	Cohesion (psf)	Resistance (degrees)
B2-3	102.8	3.3	360	26

TABLE B-III SUMMARY OF LABORATORY EXPANSION INDEX TEST RESULTS ASTM D 4829

Sample No	Moisture	Content	Dry Density	Expansion Index
Sample No.	Before Test (%)	After Test (%)	(pcf)	Expansion muex
B4-1	9.2	16.1	111.4	0

TABLE B-IV SUMMARY OF LABORATORY WATER-SOLUBLE SULFATE TEST RESULTS CALIFORNIA TEST NO. 417

Sample No.	Water-Soluble Sulfate (%)	Classification
B4-1	0.005	Negligible

TABLE B-V SUMMARY OF LABORATORY R-VALUE AND SAND EQUIVALENT TEST RESULTS ASTM D 2844

Sample No.	R-Value
B1-1	61





Figure B-1

GEOCON



GEOCON





Figure B-3

GEOCON



GEOCON



APPENDIX C

STORM WATER MANAGEMENT

We understand storm water management devices are being proposed in accordance with the current Storm Water Standards (SWS). If not properly constructed, there is a potential for distress to improvements and properties located hydrologically down gradient or adjacent to these devices. Factors such as the amount of water to be detained, its residence time, and soil permeability have an important effect on seepage transmission and the potential adverse impacts that may occur if the storm water management features are not properly designed and constructed. We have not performed a hydrogeological study at the site. If infiltration of storm water runoff occurs, downstream properties and improvements may be subjected to seeps, springs, slope instability, raised groundwater, movement of foundations and slabs, or other undesirable impacts as a result of water infiltration.

Hydrologic Soil Group

The United States Department of Agriculture (USDA), Natural Resources Conservation Services, possesses general information regarding the existing soil conditions for areas within the United States. The USDA website also provides the Hydrologic Soil Group. Table C-1 presents the descriptions of the hydrologic soil groups.

Soil Group	Soil Group Definition
А	Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.
В	Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.
с	Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.
D	Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

TABLE C-1 HYDROLOGIC SOIL GROUP DEFINITIONS

The property is underlain by undocumented fill and old terrace deposits. Table C-2 presents the information from the USDA website for the subject property.

Map Unit Name	Map Unit Symbol	Approximate Percentage of Property	Hydrologic Soil Group	k _{SAT} of Most Limiting Layer (inches/hour)
Urban land	Ur	100	n/a	n/a

 TABLE C-2

 USDA WEB SOIL SURVEY – HYDROLOGIC SOIL GROUP

Infiltration Testing

We performed 4 field-saturated, constant head, hydraulic conductivity tests at depths of approximately 2 to 3.5 feet below the existing ground surface using a Soil Moisture Corp Aardvark Permeameter. Table C-3 presents the results of the field-saturated hydraulic conductivity testing calculated using the USBR 7300-89 method. The approximate locations of the tests are shown on Figure 2. The permeameter test data is attached.

We used the guidelines presented in the Riverside County Low Impact Development BMP Design Handbook, which references the United States Bureau of Reclamation Well Permeameter Test Method (USBR 7300-89). Based on this widely accepted guideline, the saturated hydraulic conductivity (Ksat) is equal to the infiltration rate. Therefore, the Ksat value determined from the Aardvark Permeameter test is the unfactored infiltration rate. The Ksat (infiltration rate) equation provided in the Riverside County Handbook was used to compute the unfactored infiltration rate.

Test No.	Geologic Unit	Test Elevation (feet, MSL)	Field Infiltration Rate, I (inches/hour)
I-1	Qt	42	7.5
I-2	Qt	40	11.3
I-3	Qt	34	12.0
1-4	Qt	29	13.7

TABLE C-3 UNFACTORED HYDRAULIC CONDUCTIVITY TEST RESULTS

We performed grain size distribution tests on samples collected at the depth and location of the hydraulic conductivity tests and the results are presented in Appendix B.

STORM WATER MANAGEMENT CONCLUSIONS

Soil Types

Undocumented Fill (**Qudf**) – We encountered undocumented fill in borings B-4 and B-6 ranging from approximately 1 to 1.5 feet thick. The undocumented fill will be removed and replaced with compacted fill. We do not recommend infiltration into the compacted fill.

Old Terrace Deposits (Qt) – Old terrace deposits (formerly Bay Point Formation) were encountered in all borings to the maximum depth explored. The old terrace deposits generally consist of loose to medium dense, moist, light brown to brown, fine sand. The infiltration rates within the old terrace deposits range from 7.50 to 13.7 inches per hour. However, based on our consolidation testing, the old terrace deposits have a potential for hydro-collapse. Therefore, full or partial infiltration is not recommended.

Groundwater Elevation

Groundwater was not encountered during this investigation. We expect groundwater elevations to be at sea level. The site elevations range from 33 MSL to 47 MSL. Therefore, infiltration is considered feasible due to groundwater greater than 10 feet below the bottom of the proposed infiltration BMPs.

Existing Utilities

Existing utilities are present in the adjacent streets. We recommend proposed basins be set back from existing utilities a distance of at least 10 feet.

Existing and Proposed Foundations

Existing buildings are present on the property. However, we understand they will be removed. We recommend infiltration not occur adjacent to proposed new building foundations due to the potential for settlement related to hydro-collapse.

Soil or Groundwater Contamination

We are unaware of contaminated soil on the property. Therefore, full and partial infiltration associated with this risk is considered feasible.

Slopes

There are no existing or new slopes planned on the property. Therefore, infiltration should be considered feasible.

Infiltration Rates

The results of the infiltration rates show rates ranging from 7.5 to 13.7 inches per hour. The infiltration rates are adequate to support full or partial infiltration.

Storm Water Management Devices

Liners should be incorporated into the design and construction of the planned basins due to the potential for settlement related to hydro-collapse. The liner should be impermeable (e.g. High-density polyethylene, HDPE, with a thickness of about 30 mil or equivalent Polyvinyl Chloride, PVC). Penetration of the liners should be properly sealed. The devices should also be installed in accordance with the manufacturer's recommendations. Overflow protection devices should also be incorporated into the design and construction of the storm water management device.

Storm Water Standard Worksheets

The SWS requests the geotechnical engineer complete the *Categorization of Infiltration Feasibility Condition* (Worksheet C.4-1) worksheet information to help evaluate the potential for infiltration on the property. The attached Worksheet C.4-1 presents the completed information for the submittal process.

The regional storm water standards also have a worksheet (Worksheet Form D.5-1) that helps the project civil engineer estimate the factor of safety based on several factors. Table C-4 describes the suitability assessment input parameters related to the geotechnical engineering aspects for the factor of safety determination.

Consideration	High	Medium	Low
	Concern – 3 Points	Concern – 2 Points	Concern – 1 Point
Assessment Methods	Use of soil survey maps or simple texture analysis to estimate short-term infiltration rates. Use of well permeameter or borehole methods without accompanying continuous boring log. Relatively sparse testing with direct infiltration methods	Use of well permeameter or borehole methods with accompanying continuous boring log. Direct measurement of infiltration area with localized infiltration measurement methods (e.g., Infiltrometer). Moderate spatial resolution	Direct measurement with localized (i.e. small- scale) infiltration testing methods at relatively high resolution or use of extensive test pit infiltration measurement methods.

TABLE C-4 SUITABILITY ASSESSMENT RELATED CONSIDERATIONS FOR INFILTRATION FACILITY SAFETY FACTORS

TABLE C-4 (Concluded) SUITABILITY ASSESSMENT RELATED CONSIDERATIONS FOR INFILTRATION FACILITY SAFETY FACTORS

Consideration	High	Medium	Low
	Concern – 3 Points	Concern – 2 Points	Concern – 1 Point
Predominant Soil Texture	Silty and clayey soils with significant fines	Loamy soils	Granular to slightly loamy soils
Site Soil Variability	Highly variable soils indicated from site assessment or unknown variability	Soil boring/test pits indicate moderately homogenous soils	Soil boring/test pits indicate relatively homogenous soils
Depth to Groundwater/	<5 feet below	5-15 feet below	>15 feet below
Impervious Layer	facility bottom	facility bottom	facility bottom

Based on our geotechnical investigation and the previous table, Table C-5 presents the estimated factor values for the evaluation of the factor of safety. This table only presents the suitability assessment safety factor (Part A) of the worksheet. The project civil engineer should evaluate the safety factor for design (Part B) and use the combined safety factor for the design infiltration rate.

Suitability Assessment Factor Category	Assigned Weight (w)	Factor Value (v)	Product (p = w x v)
Assessment Methods	0.25	2	0.50
Predominant Soil Texture	0.25	1	0.25
Site Soil Variability	0.25	2	0.50
Depth to Groundwater/Impervious Layer	0.25	1	0.25
Suitability Assessment Saf	tety Factor, $S_A = \Sigma p$		1.5

TABLE C-5 FACTOR OF SAFETY WORKSHEET D.5-1 DESIGN VALUES¹

¹ The project civil engineer should complete Worksheet D.5-1 using the data on this table. Additional information is required to evaluate the design factor of safety.

CONCLUSIONS


Our results indicate the site has relatively good infiltration characteristics. However, laboratory test results also indicate the terrace deposits have a potential for hydro-collapse. It is our opinion that full or partial infiltration is not feasible due to the potential for settlement related to hydro-collapse.

Our evaluation included the soil and geologic conditions, estimated settlement and volume change of the underlying soil, slope stability, utility considerations, groundwater mounding, retaining walls, foundations and existing groundwater elevations.



	Aardvark P	ermeamete	r Data Analysis	5			
	Project Name:	Eco E	Blok East	Date:	11/7/2016		
Р	roject Number:	G183	32-42-03	By:	JTL		
Bor	ehole Location:		I-1		Ref. EL (feet, MSL):	44.0	
				Во	ttom EL (feet, MSL):	41.8	
Dis		Borehol eservoir & Top c Depth to W	e Diameter (inches): e Depth, H (inches): f Borehole (inches): /ater Table, s (feet): om Bottom (inches):	27.00 29.00 100		Wetted Area, A (in ²):	83.64
		Dis		Head Height (Head Height	and APM, D (inches): Calculated, h (inches): Recorded, h (inches): ater Table, L (inches):	5.66	
Reading	Time (min)	Time Elapsed (min)	Reservoir Water Weight (g)	Resevoir Water Weight (Ibs)	Interval Water Consumption (lbs)	Total Water Consumption (lbs)	*Water Consumption Rate (in ³ /min)
1	0.00			64.345			
2	10.00	10.00		52.520	11.825	11.825	32.778
3	15.00	5.00		48.135	4.385	16.210	24.310
4	20.00	5.00		43.580	4.555	20.765	25.252
5	25.00	5.00		39.220	4.360	25.125	24.171
6	30.00	5.00		34.935	4.285	29.410	23.755
7	35.00	5.00		30.620	4.315	33.725	23.921
8	40.00	5.00		26.360	4.260	37.985	23.617
9	42.00	2.00		24.645	1.715	39.700	23.769


3 15.00 5.00 48.135 4.385 16.210 24.310 4 20.00 5.00 39.220 4.360 25.125 22.4171 6 30.00 5.00 39.220 4.360 25.125 24.171 6 30.00 5.00 34.935 4.285 29.410 23.755 7 35.00 5.00 30.620 4.315 33.725 23.921 8 40.00 5.00 26.360 4.260 37.985 23.617 9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 20.0 22.885 1.760 41.460 24.393 11 46.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 14.635 1.710 49.710 23.700 16 56.00							
5 25.00 5.00 39.220 4.360 25.125 24.171 6 30.00 5.00 34.935 4.285 29.410 23.755 7 35.00 5.00 30.620 4.315 33.725 23.921 8 40.00 5.00 26.360 4.260 37.985 23.617 9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.665 1.730 46.280 23.977 14 52.00 2.00 14.635 1.710 49.710 23.878 17 16 56.00 2.00 12.915 </td <td>3</td> <td>15.00</td> <td>5.00</td> <td>48.135</td> <td>4.385</td> <td>16.210</td> <td>24.310</td>	3	15.00	5.00	48.135	4.385	16.210	24.310
6 30.00 5.00 34.935 4.285 29.410 23.755 7 35.00 5.00 30.620 4.315 33.725 23.921 8 40.00 5.00 26.360 4.260 37.985 23.617 9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 48.000 23.838 17	4	20.00	5.00	43.580	4.555	20.765	25.252
7 35.00 5.00 30.620 4.315 33.725 23.921 8 40.00 5.00 26.360 4.260 37.985 23.617 9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 14.635 1.710 49.710 23.700 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17 20 <	5	25.00	5.00	39.220	4.360	25.125	24.171
8 40.00 5.00 26.360 4.260 37.985 23.617 9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17	6	30.00	5.00	34.935	4.285	29.410	23.755
9 42.00 2.00 24.645 1.715 39.700 23.769 10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 19.795 1.740 44.550 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17 18 19 21	7	35.00	5.00	30.620	4.315	33.725	23.921
10 44.00 2.00 22.885 1.760 41.460 24.393 11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17 18 20 21 <td>8</td> <td>40.00</td> <td>5.00</td> <td>26.360</td> <td>4.260</td> <td>37.985</td> <td>23.617</td>	8	40.00	5.00	26.360	4.260	37.985	23.617
11 46.00 2.00 21.535 1.350 42.810 18.710 12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17	9	42.00	2.00	24.645	1.715	39.700	23.769
12 48.00 2.00 19.795 1.740 44.550 24.115 13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17	10	44.00	2.00	22.885	1.760	41.460	24.393
13 50.00 2.00 18.065 1.730 46.280 23.977 14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17	11	46.00	2.00	21.535	1.350	42.810	18.710
14 52.00 2.00 16.345 1.720 48.000 23.838 15 54.00 2.00 14.635 1.710 49.710 23.700 16 56.00 2.00 12.915 1.720 51.430 23.838 17	12	48.00	2.00	19.795	1.740	44.550	24.115
$\begin{array}{c c c c c c c c c c c c c c c c c c c $	13	50.00	2.00	18.065	1.730	46.280	23.977
$\begin{array}{c c c c c c c c c c c c c c c c c c c $	14	52.00	2.00	16.345	1.720	48.000	23.838
17andandandandandand18andandandandandand19andandandandandand20andandandandandand21andandandandandand22andandandandandand23andandandandandand24andandandandandand25andandandandandand26andandandandandand27andandandandandand	15	54.00	2.00	14.635	1.710	49.710	23.700
18Image: sector of the sector of	16	56.00	2.00	12.915	1.720	51.430	23.838
19Image: second sec	17						
20andandandandand21andandandandandand22andandandandandand23andandandandandand24andandandandandand25andandandandandand26andandandandandand27andandandandandand	18						
21 <td>19</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	19						
22232324242526272726 <td>20</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	20						
23 24 24 24 24 25 26 26 27 26 27 26 27 26 27 <td< td=""><td>21</td><td></td><td></td><td></td><td></td><td></td><td></td></td<>	21						
24 and	22						
25 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 7	23						
26 27<	24						
27	25						
	26						
	27						
	28						



Field-Saturated Hydraulic Conductivity (Infiltration Rate) 7.501 in/hr Case 1: L/h > 3 1.25E-01 in/min $K_{sat} =$



	/ ar ar ar ar ar ar ar	criticalitete	Data / maryon				
	Project Name:	Eco E	Blok East	Date:	11/7/2016		
Р	roject Number:	G183	32-42-03	By:	JTL		
Bor	ehole Location:	:	I-2		Ref. EL (feet, MSL):	43.0	
				Bo	ttom EL (feet, MSL):	40.1	
		Borehole	e Diameter (inches):	4.00	1		•
			e Depth, H (inches):	35.00		Wetted Area, A (in ²):	83.97
Dis	tance Between f		of Borehole (inches):	29.00		Welleu Area, A (III).	05.57
			/ater Table, s (feet):	100			
	Heig	-	om Bottom (inches):	2.00			
	- 0				and APM, D (inches):		1
			Distance		Calculated, h (inches):	00	
					Recorded, h (inches):	5.68	
		Dia	tance Detuces Co.			5100	
		Dis	stance Between Cor	nstant Head and W	ater Table, L (inches):	1171	
Reading	Time (min)	Time Elapsed (min)	Reservoir Water Weight (g)	Resevoir Water Weight (lbs)	Interval Water Consumption (Ibs)	Total Water Consumption (lbs)	*Water Consumption Rate (in ³ /min)
1	0.00			109.840			
2	8.00	8.00		92.675	17.165	17.165	59.474
3	18.00	10.00		75.160	17.515	34.680	48.550
4	25.00	7.00		64.455	10.705	45.385	42.390
5	30.00	5.00		56.870	7.585	52.970	42.050
6	32.00	2.00		54.180	2.690	55.660	37.282
7	34.00	2.00		51.445	2.735	58.395	37.906
8	36.00	2.00		48.575	2.870	61.265	39.777
9	38.00	2.00		45.880	2.695	63.960	37.351
10	40.00	2.00		43.110	2.770	66.730	38.391
11	42.00	2.00		40.735	2.375	69.105	32.916
12	44.00	2.00		38.015	2.720	71.825	37.698
13	46.00	2.00		35.230	2.785	74.610	38.599
14	48.00	2.00		32.495	2.735	77.345	37.906
15	50.00	2.00		29.800	2.695	80.040	37.351
16	52.00	2.00		27.135	2.665	82.705	36.936
17	54.00	2.00		24.500	2.635	85.340	36.520
18	56.00	2.00		24.180	0.320	85.660	4.435
19 20	58.00 60.00	2.00		21.830 19.175	2.350 2.655	88.010 90.665	32.570 36.797
20	60.00	2.00		19.175	2.655	90.665	36.312
21	64.00	2.00		13.955	2.600	95.885	36.035
22	66.00	2.00		11.335	2.620	98.505	36.312
23	00.00	2.00		11.335	2.020	20,202	50.512
25							
26							
27							
28							
	80.00				Steady Flo	w Rate, Q (in ³ /min):	36.219
Ę	80.00						




Field-Saturated Hydraulic Conductivity (Infiltration Rate)Case 1: L/h > 3K sat =1.89E-01in/min11.347



	Aardvark P	ermeamete	r Data Analysis	5			
	Project Name:	Eco E	Blok East	Date:	11/7/2016		
Р	roject Number:	G183	32-42-03	By:	JTL		
Bor	ehole Location:		I-3		Ref. EL (feet, MSL):	37.0	
				Во	ttom EL (feet, MSL):	33.8	
		Borehol	e Diameter (inches): e Depth, H (inches):	39.00		Wetted Area, A (in ²):	84.12
Dis		Depth to W	of Borehole (inches): /ater Table, s (feet): fom Bottom (inches):	100			
		Dis		Head Height C Head Height	and APM, D (inches): Calculated, h (inches): Recorded, h (inches): ater Table, L (inches):	5.69	
Reading	Time (min)	Time Elapsed (min)	Reservoir Water Weight (g)	Resevoir Water Weight (Ibs)	Interval Water Consumption (lbs)	Total Water Consumption (lbs)	*Water Consumption Rate (in ³ /min)
1	0.00			80.795			
2	5.00	5.00		68.975	11.820	11.820	65.528
3	10.00	5.00		60.295	8.680	20.500	48.120
4	15.00	5.00		52.840	7.455	27.955	41.329
5	20.00	5.00		45.270	7.570	35.525	41.967
6	25.00	5.00		38.600	6.670	42.195	36.977
7	20.00			21 (10	6.990	49.185	38.751
	30.00	5.00		31.610	0.990	49.165	30.731
8	30.00	5.00 5.00		24.660	6.950	56.135	38.529
8 9							

1	0.00		80.795			
2	5.00	5.00	68.975	11.820	11.820	65.528
3	10.00	5.00	60.295	8.680	20.500	48.120
4	15.00	5.00	52.840	7.455	27.955	41.329
5	20.00	5.00	45.270	7.570	35.525	41.967
6	25.00	5.00	38.600	6.670	42.195	36.977
7	30.00	5.00	31.610	6.990	49.185	38.751
8	35.00	5.00	24.660	6.950	56.135	38.529
9	40.00	5.00	17.805	6.855	62.990	38.003
10	45.00	5.00	10.880	6.925	69.915	38.391
11	47.00	2.00	8.105	2.775	72.690	38.460
12	49.00	2.00	5.330	2.775	75.465	38.460
13						
14						
15						
16						
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						
28						



Field-Saturated Hydraulic Conductivity (Infiltration Rate)Case 1: L/h > 3 $K_{sat} =$ 2.00E-01in/min12.009in/hr



20.00

	Project Name:		Blok East	Date:	11/7/2016		
Р	roject Number:	G183	32-42-03	By:	JTL		
Bor	ehole Location:		I-4		Ref. EL (feet, MSL):	33.0	
				Во	ttom EL (feet, MSL):	29.4	
Dic	tanco Botwoon I	Borehol	e Diameter (inches): e Depth <i>,</i> H (inches): of Borehole (inches):	4.00 43.00		Wetted Area, A (in ²):	84.29
DIS		Depth to V	/ater Table, s (feet): om Bottom (inches):	28.50 100 2.00			
			Distance		and APM, D (inches):	62.25	
				-	Calculated, h (inches):	5.71	
				Head Height	Recorded, h (inches):	4.25	
		Dis	tance Between Cor	nstant Head and W	ater Table, L (inches):	1163	1
Reading	Time (min)	Time Elapsed (min)	Reservoir Water Weight (g)	Resevoir Water Weight (lbs)	Interval Water Consumption (Ibs)	Total Water Consumption (lbs)	*Water Consumption Rat (in ³ /min)
1	0.00			114 400			(11 / 1111)
1	0.00	F 00		114.400	11 700	11 700	CE 20C
2	5.00	5.00		102.620	11.780	11.780	65.306
3	10.00 15.00	5.00		92.600 82.845	10.020	21.800 31.555	55.549 54.080
5	20.00	5.00 5.00		73.910	9.755 8.935	40.490	49.534
6 7	25.00	5.00		64.800	9.110	49.600	50.504
8	30.00	5.00		56.615	8.185	57.785	45.376
	35.00	5.00		48.015	8.600	66.385	47.677
9 10	40.00	5.00		40.045	7.970	74.355	44.184
10	45.00 50.00	5.00 5.00		32.410 24.170	7.635 8.240	81.990 90.230	42.327 45.681
11	52.00	2.00		21.760	2.410	90.230	33.401
12	54.00	2.00		18.545	3.215	95.855	44.558
13	56.00	2.00		15.300	3.245	99.100	44.558
14	58.00	2.00		12.115	3.185	102.285	44.974
15	60.00	2.00		8.955	3.160	105.445	43.796
10	62.00	2.00		5.805	3.150	103.445	43.657
17	02.00	2.00		3.803	5.150	108.333	43.037
10							
20							
21							
22							
23							
24							
25							
26							
27							
28							
nsumption n³/min)	80.00				Steady Flo	w Rate, Q (in ³ /min):	43.865

Water Consu Rate (in³/ 0.00 0 10 20 30 40 50 60 Time (min) Field-Saturated Hydraulic Conductivity (Infiltration Rate) in/hr 2.28E-01 in/min 13.662 Case 1: L/h > 3 $K_{sat} =$

70

Cate	gorization of Infiltration Feasibility Condition	Form I-8		
Part 1 - Full Infiltration Feasibility Screening Criteria Would infiltration of the full design volume be feasible from a physical perspective without any undesirable consequences that cannot be reasonably mitigated?				
Criteria	Screening Question	Yes	No	
1	Is the estimated reliable infiltration rate below proposed facility locations greater than 0.5 inches per hour? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.2 and Appendix D.	х		
Provide	basis:			
Weenco	ountered field infiltration rates of:			
Based o	I-1: 7.5 in/hr (3.75 in/hr with a FOS of 2)I-2: 11.3 in/hr (5.7 in/hr with a FOS of 2)I-3: 12.0 in/hr (6.0 in/hr with a FOS of 2)I-4: 13.7 in/hr (6.9 in/hr with a FOS of 2)I-4: 13.7 in/hr (6.9 in/hr with a FOS of 2)n the test results, the estimated reliable infiltration rate is greater than 0).5 inches per h	OUr.	
2	Can infiltration greater than 0.5 inches per hour be allowed without increasing risk of geotechnical hazards (slope stability, groundwater mounding, utilities, or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.2.		x	
Provide	basis:			
settleme Decemb 1.25 per	n the comprehensive geotechnical evaluation, infiltration is not feasible int due to the potential for hydro-collapse in the underlying soils. Figur er 19, 2016 report show a hydro-collapse potential ranging from 0.5 to cent over a wetting height of 20 feet, we would expect settlement mag the typically settlement magnitudes that can be accommodated in a co	res B-2 through 2 percent. Usir nitudes of 3 inc	n B-4 of Geocon's ng an average of hes, which	

	Form I-8 Page 2 of 4		
Criteria	Screening Question	Yes	No
3	Can infiltration greater than 0.5 inches per hour be allowed without increasing risk of groundwater contamination (shallow water table, storm water pollutants or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.3.		
Provide ba	sis:	I	1
greater th contamin	an 30 feet below existing grade. Infiltration is feasible without increasi ation.	ng the risk of g	roundwater
4	Can infiltration greater than 0.5 inches per hour be allowed without causing potential water balance issues such as change of seasonality of ephemeral streams or increased discharge of contaminated groundwater to surface waters? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.3.	x	
	sis: expect infiltration will cause water balance issues such as seasonality discharge of contaminated groundwater to surface waters.	of ephemeral st	reams or

*To be completed using gathered site information and best professional judgment considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by the City to substantiate findings.

	Form I-8 Page 3 of 4					
Part 2 – Partial Infiltration vs. No Infiltration Feasibility Screening Criteria						
Would in	Would infiltration of water in any appreciable amount be physically feasible without any negative consequences that cannot be reasonably mitigated?					
Criteria	Screening Question	Yes	No			
5	Do soil and geologic conditions allow for infiltration in any appreciable rate or volume? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.2 and Appendix D.	х				
Provide ba	isis:					
We measu	ured field infiltration rates of:					
	I-1: 7.5 in/hr (3.75 in/hr with a FOS of 2) I-2: 11.3 in/hr (5.7 in/hr with a FOS of 2) I-3: 12.0 in/hr (6.0 in/hr with a FOS of 2) I-4: 13.7 in/hr (6.9 in/hr with a FOS of 2)					
Based on the test results, soil conditions allow for an appreciable infiltration rate or volume.						
6	Can Infiltration in any appreciable quantity be allowed without increasing risk of geotechnical hazards (slope stability, groundwater mounding, utilities, or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.2.		х			
Provide ba	asis:					
Based on the comprehensive geotechnical evaluation, infiltration is not feasible due to the increased risk of settlement due to the potential for hydro-collapse in the underlying soils. Figures B-2 through B-4 of Geocon's December 19, 2016 report show a hydro-collapse potential ranging from 0.5 to 2 percent. Using an average of 1.25 percent over a wetting height of 20 feet, we would expect settlement magnitudes of 3 inches, which exceeds the typically settlement magnitudes that can be accommodated in a conventional shallow foundation system.						

Appendix I: Forms and Checklists

Worksheet C.4-1 Page 4 of 4					
Criteria	Screening Question	Yes	No		
7	Can Infiltration in any appreciable quantity be allowed without posing significant risk for groundwater related concerns (shallow water table, storm water pollutants or other factors)? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.3.	Х			
Provide ba	isis:				
depths g	ot aware of contaminated soil on the site. Furthermore, we estimate g eater than 30 feet below existing grade. Infiltration is feasible withou ater contamination.				
8	Can infiltration be allowed without violating downstream water rights ? The response to this Screening Question shall be based on a comprehensive evaluation of the factors presented in Appendix C.3.	х			
Provide basis: We did not provide a study regarding water rights. However, these rights are not typical in the San Diego area.					
Part 2 Result*					

*To be completed using gathered site information and best professional judgment considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by the City to substantiate findings.



APPENDIX D

RECOMMENDED GRADING SPECIFICATIONS

FOR

ECO BLOK EAST SHASTA STREET SAN DIEGO, CALIFORNIA

PROJECT NO. G1832-42-03

RECOMMENDED GRADING SPECIFICATIONS

1. GENERAL

- 1.1 These Recommended Grading Specifications shall be used in conjunction with the Geotechnical Report for the project prepared by Geocon. The recommendations contained in the text of the Geotechnical Report are a part of the earthwork and grading specifications and shall supersede the provisions contained hereinafter in the case of conflict.
- 1.2 Prior to the commencement of grading, a geotechnical consultant (Consultant) shall be employed for the purpose of observing earthwork procedures and testing the fills for substantial conformance with the recommendations of the Geotechnical Report and these specifications. The Consultant should provide adequate testing and observation services so that they may assess whether, in their opinion, the work was performed in substantial conformance with these specifications. It shall be the responsibility of the Contractor to assist the Consultant and keep them apprised of work schedules and changes so that personnel may be scheduled accordingly.
- 1.3 It shall be the sole responsibility of the Contractor to provide adequate equipment and methods to accomplish the work in accordance with applicable grading codes or agency ordinances, these specifications and the approved grading plans. If, in the opinion of the Consultant, unsatisfactory conditions such as questionable soil materials, poor moisture condition, inadequate compaction, and/or adverse weather result in a quality of work not in conformance with these specifications, the Consultant will be empowered to reject the work and recommend to the Owner that grading be stopped until the unacceptable conditions are corrected.

2. **DEFINITIONS**

- 2.1 **Owner** shall refer to the owner of the property or the entity on whose behalf the grading work is being performed and who has contracted with the Contractor to have grading performed.
- 2.2 **Contractor** shall refer to the Contractor performing the site grading work.
- 2.3 **Civil Engineer** or **Engineer of Work** shall refer to the California licensed Civil Engineer or consulting firm responsible for preparation of the grading plans, surveying and verifying as-graded topography.
- 2.4 **Consultant** shall refer to the soil engineering and engineering geology consulting firm retained to provide geotechnical services for the project.

- 2.5 **Soil Engineer** shall refer to a California licensed Civil Engineer retained by the Owner, who is experienced in the practice of geotechnical engineering. The Soil Engineer shall be responsible for having qualified representatives on-site to observe and test the Contractor's work for conformance with these specifications.
- 2.6 **Engineering Geologist** shall refer to a California licensed Engineering Geologist retained by the Owner to provide geologic observations and recommendations during the site grading.
- 2.7 **Geotechnical Report** shall refer to a soil report (including all addenda) which may include a geologic reconnaissance or geologic investigation that was prepared specifically for the development of the project for which these Recommended Grading Specifications are intended to apply.

3. MATERIALS

- 3.1 Materials for compacted fill shall consist of any soil excavated from the cut areas or imported to the site that, in the opinion of the Consultant, is suitable for use in construction of fills. In general, fill materials can be classified as *soil* fills, *soil-rock* fills or *rock* fills, as defined below.
 - 3.1.1 **Soil fills** are defined as fills containing no rocks or hard lumps greater than 12 inches in maximum dimension and containing at least 40 percent by weight of material smaller than ³/₄ inch in size.
 - 3.1.2 **Soil-rock fills** are defined as fills containing no rocks or hard lumps larger than 4 feet in maximum dimension and containing a sufficient matrix of soil fill to allow for proper compaction of soil fill around the rock fragments or hard lumps as specified in Paragraph 6.2. **Oversize rock** is defined as material greater than 12 inches.
 - 3.1.3 **Rock fills** are defined as fills containing no rocks or hard lumps larger than 3 feet in maximum dimension and containing little or no fines. Fines are defined as material smaller than ³/₄ inch in maximum dimension. The quantity of fines shall be less than approximately 20 percent of the rock fill quantity.
- 3.2 Material of a perishable, spongy, or otherwise unsuitable nature as determined by the Consultant shall not be used in fills.
- 3.3 Materials used for fill, either imported or on-site, shall not contain hazardous materials as defined by the California Code of Regulations, Title 22, Division 4, Chapter 30, Articles 9


and 10; 40CFR; and any other applicable local, state or federal laws. The Consultant shall not be responsible for the identification or analysis of the potential presence of hazardous materials. However, if observations, odors or soil discoloration cause Consultant to suspect the presence of hazardous materials, the Consultant may request from the Owner the termination of grading operations within the affected area. Prior to resuming grading operations, the Owner shall provide a written report to the Consultant indicating that the suspected materials are not hazardous as defined by applicable laws and regulations.

- 3.4 The outer 15 feet of *soil-rock* fill slopes, measured horizontally, should be composed of properly compacted *soil* fill materials approved by the Consultant. *Rock* fill may extend to the slope face, provided that the slope is not steeper than 2:1 (horizontal:vertical) and a soil layer no thicker than 12 inches is track-walked onto the face for landscaping purposes. This procedure may be utilized provided it is acceptable to the governing agency, Owner and Consultant.
- 3.5 Samples of soil materials to be used for fill should be tested in the laboratory by the Consultant to determine the maximum density, optimum moisture content, and, where appropriate, shear strength, expansion, and gradation characteristics of the soil.
- 3.6 During grading, soil or groundwater conditions other than those identified in the Geotechnical Report may be encountered by the Contractor. The Consultant shall be notified immediately to evaluate the significance of the unanticipated condition.

4. CLEARING AND PREPARING AREAS TO BE FILLED

- 4.1 Areas to be excavated and filled shall be cleared and grubbed. Clearing shall consist of complete removal above the ground surface of trees, stumps, brush, vegetation, man-made structures, and similar debris. Grubbing shall consist of removal of stumps, roots, buried logs and other unsuitable material and shall be performed in areas to be graded. Roots and other projections exceeding 1½ inches in diameter shall be removed to a depth of 3 feet below the surface of the ground. Borrow areas shall be grubbed to the extent necessary to provide suitable fill materials.
- 4.2 Asphalt pavement material removed during clearing operations should be properly disposed at an approved off-site facility or in an acceptable area of the project evaluated by Geocon and the property owner. Concrete fragments that are free of reinforcing steel may be placed in fills, provided they are placed in accordance with Section 6.2 or 6.3 of this document.

- 4.3 After clearing and grubbing of organic matter and other unsuitable material, loose or porous soils shall be removed to the depth recommended in the Geotechnical Report. The depth of removal and compaction should be observed and approved by a representative of the Consultant. The exposed surface shall then be plowed or scarified to a minimum depth of 6 inches and until the surface is free from uneven features that would tend to prevent uniform compaction by the equipment to be used.
- 4.4 Where the slope ratio of the original ground is steeper than 5:1 (horizontal:vertical), or where recommended by the Consultant, the original ground should be benched in accordance with the following illustration.



TYPICAL BENCHING DETAIL

No Scale

- DETAIL NOTES: (1) Key width "B" should be a minimum of 10 feet, or sufficiently wide to permit complete coverage with the compaction equipment used. The base of the key should be graded horizontal, or inclined slightly into the natural slope.
 - (2) The outside of the key should be below the topsoil or unsuitable surficial material and at least 2 feet into dense formational material. Where hard rock is exposed in the bottom of the key, the depth and configuration of the key may be modified as approved by the Consultant.
- 4.5 After areas to receive fill have been cleared and scarified, the surface should be moisture conditioned to achieve the proper moisture content, and compacted as recommended in Section 6 of these specifications.

5. COMPACTION EQUIPMENT

- 5.1 Compaction of *soil* or *soil-rock* fill shall be accomplished by sheepsfoot or segmented-steel wheeled rollers, vibratory rollers, multiple-wheel pneumatic-tired rollers, or other types of acceptable compaction equipment. Equipment shall be of such a design that it will be capable of compacting the *soil* or *soil-rock* fill to the specified relative compaction at the specified moisture content.
- 5.2 Compaction of *rock* fills shall be performed in accordance with Section 6.3.

6. PLACING, SPREADING AND COMPACTION OF FILL MATERIAL

- 6.1 *Soil* fill, as defined in Paragraph 3.1.1, shall be placed by the Contractor in accordance with the following recommendations:
 - 6.1.1 *Soil* fill shall be placed by the Contractor in layers that, when compacted, should generally not exceed 8 inches. Each layer shall be spread evenly and shall be thoroughly mixed during spreading to obtain uniformity of material and moisture in each layer. The entire fill shall be constructed as a unit in nearly level lifts. Rock materials greater than 12 inches in maximum dimension shall be placed in accordance with Section 6.2 or 6.3 of these specifications.
 - 6.1.2 In general, the *soil* fill shall be compacted at a moisture content at or above the optimum moisture content as determined by ASTM D 1557.
 - 6.1.3 When the moisture content of *soil* fill is below that specified by the Consultant, water shall be added by the Contractor until the moisture content is in the range specified.
 - 6.1.4 When the moisture content of the *soil* fill is above the range specified by the Consultant or too wet to achieve proper compaction, the *soil* fill shall be aerated by the Contractor by blading/mixing, or other satisfactory methods until the moisture content is within the range specified.
 - 6.1.5 After each layer has been placed, mixed, and spread evenly, it shall be thoroughly compacted by the Contractor to a relative compaction of at least 90 percent. Relative compaction is defined as the ratio (expressed in percent) of the in-place dry density of the compacted fill to the maximum laboratory dry density as determined in accordance with ASTM D 1557. Compaction shall be continuous over the entire area, and compaction equipment shall make sufficient passes so that the specified minimum relative compaction has been achieved throughout the entire fill.

- 6.1.6 Where practical, soils having an Expansion Index greater than 50 should be placed at least 3 feet below finish pad grade and should be compacted at a moisture content generally 2 to 4 percent greater than the optimum moisture content for the material.
- 6.1.7 Properly compacted *soil* fill shall extend to the design surface of fill slopes. To achieve proper compaction, it is recommended that fill slopes be over-built by at least 3 feet and then cut to the design grade. This procedure is considered preferable to track-walking of slopes, as described in the following paragraph.
- 6.1.8 As an alternative to over-building of slopes, slope faces may be back-rolled with a heavy-duty loaded sheepsfoot or vibratory roller at maximum 4-foot fill height intervals. Upon completion, slopes should then be track-walked with a D-8 dozer or similar equipment, such that a dozer track covers all slope surfaces at least twice.
- 6.2 *Soil-rock* fill, as defined in Paragraph 3.1.2, shall be placed by the Contractor in accordance with the following recommendations:
 - 6.2.1 Rocks larger than 12 inches but less than 4 feet in maximum dimension may be incorporated into the compacted *soil* fill, but shall be limited to the area measured 15 feet minimum horizontally from the slope face and 5 feet below finish grade or 3 feet below the deepest utility, whichever is deeper.
 - 6.2.2 Rocks or rock fragments up to 4 feet in maximum dimension may either be individually placed or placed in windrows. Under certain conditions, rocks or rock fragments up to 10 feet in maximum dimension may be placed using similar methods. The acceptability of placing rock materials greater than 4 feet in maximum dimension shall be evaluated during grading as specific cases arise and shall be approved by the Consultant prior to placement.
 - 6.2.3 For individual placement, sufficient space shall be provided between rocks to allow for passage of compaction equipment.
 - 6.2.4 For windrow placement, the rocks should be placed in trenches excavated in properly compacted *soil* fill. Trenches should be approximately 5 feet wide and 4 feet deep in maximum dimension. The voids around and beneath rocks should be filled with approved granular soil having a Sand Equivalent of 30 or greater and should be compacted by flooding. Windrows may also be placed utilizing an "open-face" method in lieu of the trench procedure, however, this method should first be approved by the Consultant.


- 6.2.5 Windrows should generally be parallel to each other and may be placed either parallel to or perpendicular to the face of the slope depending on the site geometry. The minimum horizontal spacing for windrows shall be 12 feet center-to-center with a 5-foot stagger or offset from lower courses to next overlying course. The minimum vertical spacing between windrow courses shall be 2 feet from the top of a lower windrow to the bottom of the next higher windrow.
- 6.2.6 Rock placement, fill placement and flooding of approved granular soil in the windrows should be continuously observed by the Consultant.
- 6.3 *Rock* fills, as defined in Section 3.1.3, shall be placed by the Contractor in accordance with the following recommendations:
 - 6.3.1 The base of the *rock* fill shall be placed on a sloping surface (minimum slope of 2 percent). The surface shall slope toward suitable subdrainage outlet facilities. The *rock* fills shall be provided with subdrains during construction so that a hydrostatic pressure buildup does not develop. The subdrains shall be permanently connected to controlled drainage facilities to control post-construction infiltration of water.
 - 6.3.2 *Rock* fills shall be placed in lifts not exceeding 3 feet. Placement shall be by rock trucks traversing previously placed lifts and dumping at the edge of the currently placed lift. Spreading of the *rock* fill shall be by dozer to facilitate *seating* of the rock. The *rock* fill shall be watered heavily during placement. Watering shall consist of water trucks traversing in front of the current rock lift face and spraying water continuously during rock placement. Compaction equipment with compactive energy comparable to or greater than that of a 20-ton steel vibratory roller or other compaction equipment providing suitable energy to achieve the required compaction or deflection as recommended in Paragraph 6.3.3 shall be utilized. The number of passes to be made should be determined as described in Paragraph 6.3.3. Once a *rock* fill lift has been covered with *soil* fill, no additional *rock* fill lifts will be permitted over the *soil* fill.
 - 6.3.3 Plate bearing tests, in accordance with ASTM D 1196, may be performed in both the compacted *soil* fill and in the *rock* fill to aid in determining the required minimum number of passes of the compaction equipment. If performed, a minimum of three plate bearing tests should be performed in the properly compacted *soil* fill (minimum relative compaction of 90 percent). Plate bearing tests shall then be performed on areas of *rock* fill having two passes, four passes and six passes of the compaction equipment, respectively. The number of passes required for the *rock* fill shall be determined by comparing the results of the plate bearing tests for the *soil* fill and the *rock* fill and by evaluating the deflection


variation with number of passes. The required number of passes of the compaction equipment will be performed as necessary until the plate bearing deflections are equal to or less than that determined for the properly compacted *soil* fill. In no case will the required number of passes be less than two.

- 6.3.4 A representative of the Consultant should be present during *rock* fill operations to observe that the minimum number of "passes" have been obtained, that water is being properly applied and that specified procedures are being followed. The actual number of plate bearing tests will be determined by the Consultant during grading.
- 6.3.5 Test pits shall be excavated by the Contractor so that the Consultant can state that, in their opinion, sufficient water is present and that voids between large rocks are properly filled with smaller rock material. In-place density testing will not be required in the *rock* fills.
- 6.3.6 To reduce the potential for "piping" of fines into the *rock* fill from overlying *soil* fill material, a 2-foot layer of graded filter material shall be placed above the uppermost lift of *rock* fill. The need to place graded filter material below the *rock* should be determined by the Consultant prior to commencing grading. The gradation of the graded filter material will be determined at the time the *rock* fill is being excavated. Materials typical of the *rock* fill should be submitted to the Consultant in a timely manner, to allow design of the graded filter prior to the commencement of *rock* fill placement.
- 6.3.7 *Rock* fill placement should be continuously observed during placement by the Consultant.

7. SUBDRAINS


7.1 The geologic units on the site may have permeability characteristics and/or fracture systems that could be susceptible under certain conditions to seepage. The use of canyon subdrains may be necessary to mitigate the potential for adverse impacts associated with seepage conditions. Canyon subdrains with lengths in excess of 500 feet or extensions of existing offsite subdrains should use 8-inch-diameter pipes. Canyon subdrains less than 500 feet in length should use 6-inch-diameter pipes.





NO SCALE

7.2 Slope drains within stability fill keyways should use 4-inch-diameter (or lager) pipes.



NOTES:

1_EXCAVATE BACKCUT AT 1:1 INCLINATION (UNLESS OTHERWISE NOTED).

2.....BASE OF STABILITY FILL TO BE 3 FEET INTO FORMATIONAL MATERIAL, SLOPING A MINIMUM 5% INTO SLOPE.

4.....CHIMNEY DRAINS TO BE APPROVED PREFABRICATED CHIMNEY DRAIN PANELS (MIRADRAIN G200N OR EQUIVALENT) SPACED APPROXIMATELY 20 FEET CENTER TO CENTER AND 4 FEET WIDE. CLOSER SPACING WAY BE REQUIRED IF SEEPAGE IS ENCOUNTERED.

5....FILTER MATERIAL TO BE 3/4-INCH, OPEN-GRADED CRUSHED ROCK ENCLOSED IN APPROVED FILTER FABRIC (MIRAFI 140NC).

 COLLECTOR PIPE TO BE 4-INCH MINIMUM DIAMETER, PERFORATED, THICK-WALLED PVC SCHEDULE 40 OR EQUIVALENT, AND SLOPED TO DRAIN AT 1 PERCENT MINIMUM TO APPROVED OUTLET.

NO SCALE


- 7.3 The actual subdrain locations will be evaluated in the field during the remedial grading operations. Additional drains may be necessary depending on the conditions observed and the requirements of the local regulatory agencies. Appropriate subdrain outlets should be evaluated prior to finalizing 40-scale grading plans.
- 7.4 Rock fill or soil-rock fill areas may require subdrains along their down-slope perimeters to mitigate the potential for buildup of water from construction or landscape irrigation. The subdrains should be at least 6-inch-diameter pipes encapsulated in gravel and filter fabric. Rock fill drains should be constructed using the same requirements as canyon subdrains.

^{3.....}STABILITY FILL TO BE COMPOSED OF PROPERLY COMPACTED GRANULAR SOIL.


7.5 Prior to outletting, the final 20-foot segment of a subdrain that will not be extended during future development should consist of non-perforated drainpipe. At the non-perforated/ perforated interface, a seepage cutoff wall should be constructed on the downslope side of the pipe.

TYPICAL CUT OFF WALL DETAIL

FRONT VIEW




SIDE VIEW



01010200000

7.6 Subdrains that discharge into a natural drainage course or open space area should be provided with a permanent headwall structure.

FRONT VIEW



7.7 The final grading plans should show the location of the proposed subdrains. After completion of remedial excavations and subdrain installation, the project civil engineer should survey the drain locations and prepare an "as-built" map showing the drain locations. The final outlet and connection locations should be determined during grading operations. Subdrains that will be extended on adjacent projects after grading can be placed on formational material and a vertical riser should be placed at the end of the subdrain. The grading contractor should consider videoing the subdrains shortly after burial to check proper installation and functionality. The contractor is responsible for the performance of the drains.

8. OBSERVATION AND TESTING

- 8.1 The Consultant shall be the Owner's representative to observe and perform tests during clearing, grubbing, filling, and compaction operations. In general, no more than 2 feet in vertical elevation of *soil* or *soil-rock* fill should be placed without at least one field density test being performed within that interval. In addition, a minimum of one field density test should be performed for every 2,000 cubic yards of *soil* or *soil-rock* fill placed and compacted.
- 8.2 The Consultant should perform a sufficient distribution of field density tests of the compacted *soil* or *soil-rock* fill to provide a basis for expressing an opinion whether the fill material is compacted as specified. Density tests shall be performed in the compacted materials below any disturbed surface. When these tests indicate that the density of any layer of fill or portion thereof is below that specified, the particular layer or areas represented by the test shall be reworked until the specified density has been achieved.
- 8.3 During placement of *rock* fill, the Consultant should observe that the minimum number of passes have been obtained per the criteria discussed in Section 6.3.3. The Consultant should request the excavation of observation pits and may perform plate bearing tests on the placed *rock* fills. The observation pits will be excavated to provide a basis for expressing an opinion as to whether the *rock* fill is properly seated and sufficient moisture has been applied to the material. When observations indicate that a layer of *rock* fill or any portion thereof is below that specified, the affected layer or area shall be reworked until the *rock* fill has been adequately seated and sufficient moisture applied.
- 8.4 A settlement monitoring program designed by the Consultant may be conducted in areas of *rock* fill placement. The specific design of the monitoring program shall be as recommended in the Conclusions and Recommendations section of the project Geotechnical Report or in the final report of testing and observation services performed during grading.
- 8.5 We should observe the placement of subdrains, to check that the drainage devices have been placed and constructed in substantial conformance with project specifications.
- 8.6 Testing procedures shall conform to the following Standards as appropriate:

8.6.1 Soil and Soil-Rock Fills:

8.6.1.1 Field Density Test, ASTM D 1556, Density of Soil In-Place By the Sand-Cone Method.

- 8.6.1.2 Field Density Test, Nuclear Method, ASTM D 6938, Density of Soil and Soil-Aggregate In-Place by Nuclear Methods (Shallow Depth).
- 8.6.1.3 Laboratory Compaction Test, ASTM D 1557, Moisture-Density Relations of Soils and Soil-Aggregate Mixtures Using 10-Pound Hammer and 18-Inch Drop.
- 8.6.1.4. Expansion Index Test, ASTM D 4829, Expansion Index Test.

9. PROTECTION OF WORK

- 9.1 During construction, the Contractor shall properly grade all excavated surfaces to provide positive drainage and prevent ponding of water. Drainage of surface water shall be controlled to avoid damage to adjoining properties or to finished work on the site. The Contractor shall take remedial measures to prevent erosion of freshly graded areas until such time as permanent drainage and erosion control features have been installed. Areas subjected to erosion or sedimentation shall be properly prepared in accordance with the Specifications prior to placing additional fill or structures.
- 9.2 After completion of grading as observed and tested by the Consultant, no further excavation or filling shall be conducted except in conjunction with the services of the Consultant.

10. CERTIFICATIONS AND FINAL REPORTS

- 10.1 Upon completion of the work, Contractor shall furnish Owner a certification by the Civil Engineer stating that the lots and/or building pads are graded to within 0.1 foot vertically of elevations shown on the grading plan and that all tops and toes of slopes are within 0.5 foot horizontally of the positions shown on the grading plans. After installation of a section of subdrain, the project Civil Engineer should survey its location and prepare an *as-built* plan of the subdrain location. The project Civil Engineer should verify the proper outlet for the subdrains and the Contractor should ensure that the drain system is free of obstructions.
- 10.2 The Owner is responsible for furnishing a final as-graded soil and geologic report satisfactory to the appropriate governing or accepting agencies. The as-graded report should be prepared and signed by a California licensed Civil Engineer experienced in geotechnical engineering and by a California Certified Engineering Geologist, indicating that the geotechnical aspects of the grading were performed in substantial conformance with the Specifications or approved changes to the Specifications.

LIST OF REFERENCES

- 1. Kennedy, M. P., and S. S. Tan, 2008, *Geologic Map of the San Diego 30' x 60' Quadrangle, California*, USGS Regional Geologic Map Series, 1:100,000 Scale, Map No. 3;
- 2. Risk Engineering, 2016, *EZ-FRISK* (Version 7.65).
- 3. USGS computer program, U.S. Seismic Design Maps, June 2014.



GEOTECHNICAL E ENVIRONMENTAL MATERIALS



Project No. G1832-42-03 March 2, 2017

PFP Coastal Holdings, LLC 4380 La Jolla Village Drive, Suite 250 San Diego, California 92122

Attention: Mr. Matt Quinn

Subject: RESPONSE TO CITY OF SAN DIEGO REVIEW COMMENTS ECO BLOK EAST SAN DIEGO, CALIFORNIA

- References: 1. Cycle Issues, Preliminary Review, Project No. 530514, prepared by City of San Diego Development Services, LDR-Geology, Patrick Thomas, dated January 18, 2017.
 - 2. *Geotechnical Investigation, Eco Blok East, Shasta Street, San Diego, California,* prepared by Geocon Incorporated, dated December 19, 2016 (Project No. G1832-42-03).

Dear Mr. Quinn:

In accordance with your request, we have prepared this response to the geotechnical review comments presented in Reference 1. The review comments along with our responses are presented herein.

- *Issue 3:* The geotechnical consultant should consider revising their description of geologic units in accordance with the recent Geologic Map of the San Diego Quadrangle (2008).
- **Response:** Acknowledged. Based on the 2008 map, the soils at the site are classified as Old Paralic Deposits (Qop). The description provided in the *Soil and Geologic Conditions* section of our report describes them as Old Terrace Deposits (Qt). The two terms are essentially equivalent. We have modified the geologic map in Reference 2 to reflect the soil deposit as Old Paralic Deposits (Qop). The map is appended to this letter.
- *Issue 4:* The boring log for Sample B1-1 indicates a disturbed or bag sample. Clarify if the consolidation testing as depicted n Figure B-2 was performed on this sample.
- **Response:** Sample B1-1 was an undisturbed sample retrieved by a Modified California Split Spoon sampler. The boring log, Figure A-1 shows sample B1-2 as a "Drive Sample (Undistrubed)". From the same boring, a bulk sample (Sample B-1) was obtained from auger cuttings from the upper 5 feet of the boring. At a depth of approximately 2.5 feet, the drilling was stopped and a drive sample obtained.
- *Issue 5:* The geotechnical consultant must indicate if in their professional opinion the consolidation testing results are representative of the sedimentary old surficial deposits onsite.
- **Response:** It is our professional opinion that the consolidation testing results are representative of the sedimentary old surficial deposits on the project site.

- Issue 6: Based on ASTM D5333 the consolidation test results are considered to have a slight potential for hydro consolidation. Clarify if differential settlement due to hydro consolidation is considered to be a significant effect on the proposed development. *Clarify if the effect can be mitigated to an acceptable level (e.g. foundation design).*
- **Response:** ASTM D5333 test method was withdrawn in 2012 and is no longer a valid test method. The testing procedure is different than the testing produced utilized for our laboratory consolidation test (ASTM D2435). In our opinion differential settlement due to hydro consolidation could have a significant effect on structural improvements.

The hydro-collapse measured on the three consolidation tests performed for this project ranged from 0.6 percent to 2 percent. Based on these results, if a 15-foot column of soil were to become wet from infiltration, we would expect a differential settlement magnitude between 1-inch and 3 inches. It is our experience that differential settlement magnitudes in excess of ³/₄-inch across the building foundation can have significant effects on structural improvements. A structural engineer would need to determine if the effect of differential settlement can reasonably be mitigated to an acceptable level.

- Issue 7: A geotechnical condition created by the proposed development may not be considered a valid geotechnical hazard or constraint as the constraint is proposed by the project.
- **Response:** Acknowledge.
- Issue 8: Based on the responses to the review cycle issues, revise Worksheet C.4-1 as necessary.
- **Response:** Based on our responses to the review cycle issue, Worksheet C.4-1 does not need to be revised.

If there are any questions regarding this correspondence, or if we may be of further service, please contact the undersigned at your convenience.

Very truly yours,

(e-mail)

GEOCON INCORPORATED

GE 2533


RCM:GWC:dmc Addressee

Garry W. Cannon



10.2201 ERTIFIED GINEERING





Plotted:03/02/2017 12:10PM | By:RUBEN AGUILAR | File Location:Y:\PROJECTS\G1832-42-03 ECO BLOK EAST\G1832-42-03 Site Plan.dwg



GEOTECHNICAL
MATERIALS
SPECIAL INSPECTIONS

SBE SLBE SCOOP

4373 Viewridge Avenue, Ste. B San Diego, CA 92123 858.292.7575

PEP Coastal Holdings, LLC 4380 La Jolla Village Drive, Suite 250 San Diego, CA 92122 09 May 2017 NOVA Project No. 2017701

Attention: Mr. Ian Gill

Subject: Report Assessment of the Potential for Infiltration-Related Soil Collapse Eco Blök East San Diego, California

References:

<u>Geocon 2016</u>. *Geotechnical Investigation, Eco Blok East, Shasta Street, San Diego, California,* Geocon Incorporated, Project No. G1832-42-03, December 19, 2016.

San Diego 2017. Cycle Issues, Preliminary Review, Project No. 530514, City of San Diego Development Services, LDR-Geology, January 18, 2017.

<u>Geocon 2017</u>. *Response to City of San Diego Review Comments, Eco Blok East, Shasta Street, San Diego,* California, Geocon Incorporated, March 2, 2017.

Latitude 33 2017. Grading & Drainage Plans for: Eco Blok East, 1765 Fortuna Avenue, 3977 Shasta Street, 1750 Roosevelt Avenue, San Diego, California, Latitude 33, February 27, 2017.

Dear Mr. Gill:

This report provides the findings of a review of geotechnical and infiltration-related considerations for a residential development (hereafter, 'the development' or 'the site') now known as "Eco Blök East." The development located in the Pacific Beach area of the City of San Diego, California. The report is intended to supplement the above-referenced geotechnical investigation (i.e., Geocon 2016).

TERMS OF REFERENCE

The work reported herein was completed by NOVA Services, Inc. (NOVA) for PEP Coastal Holdings, LLC (PCH) in accordance with NOVA's proposal dated April 7, 2017.

OBJECTIVE, SCOPE, USE AND LIMITATIONS OF THIS WORK

Objective

The objective of the work reported herein to determine if the geotechnical-related assessment of the collapse potential of the sands provided therein is appropriate.



Scope

General

The scope and sequence of review which was undertaken by NOVA may be considered as the task-based series of activities described below

- Task 1: Project Familiarization.
- Task 2: Design Data Review and Evaluation.
- Task 3: Confirmation Sampling and Laboratory Testing.
 - Subtask 3-1, Site Reconnaissance and Permitting
 - Subtask 3-2, Engineering Borings
 - Subtask 3-3, Laboratory Testing
- Task 4: Preliminary Discussion of Findings.
- Task 5: Final Data Review and Reporting.

The following subsections abstract the scope of each of the above tasks.

Understood Use

NOVA expects that the findings and recommendations provided herein will be utilized by PEP Coastal Holdings, LLC and its Design Team in decision-making regarding development of stormwater infiltration BMPs.

Limitations

The findings of this report are limited only to an assessment of the potential for soil strain as a result of saturation by stormwater infiltration BMPs.

This report does <u>not</u> address any environmental matters; including, but not limited to assessment or investigation for the presence or absence of hazardous or toxic materials in the soil, groundwater, or surface water within or beyond the site.

SITE DESCRIPTION

Location

Eco Blök East will be developed within the limits of property now identified as 1765 Fortuna Avenue, 3977 Shasta Street, 1750 Roosevelt Avenue in San Diego. The development encompasses approximately 1.64 acres of developed land, bounded on all sides by light residential and commercial development.



PLANNED DEVELOPMENT

General

Eco Blök East will be comprised of 30 single family residential units set with 'zero lot line', fronting Shasta Street. Figure 1 provides a view of current planning for the development.





Figure 1. Conceptual Development Plan (source: Latitude 33 2017)

Stormwater BMPs

Development will disturb about 1.64 acres, adding about 1.16 acres of created impervious area over the limits of the development. Design for infiltration of stormwater will include the use of biofiltration structures that will be sited at the Shasta Street edge of each of the 30 lots. The biofiltration structures will each extend to a depth of about 4 feet below surrounding ground surface. Figure 2 depicts the plan location of the biofiltration BMPs.



(source: Latitude 33 2017)



ENGINEERING BORINGS

Engineering Borings

General

A NOVA geologist directed drilling and sampling of 3 borings, each drilled to about 12 feet below ground surface (bgs) on April 17. Subsurface conditions disclosed by the borings are the same as reported in Geocon 2016. Records of the engineering borings are provided in Attachment 1.

Figure 3 provides a plan view of the site indicating the location of the borings.




Figure 3. Boring Location Plan

Drilling and Sampling

The engineering borings (referenced herein as 'B-1' through 'B-3') were drilled by a specialty subcontractor retained by NOVA. The boring locations were determined in the field by and estimating distances from existing site features, such that the locations are approximate.

The borings were each extended to a depth of 12 feet below ground surface (bgs). Relatively undisturbed samples were recovered from the borings by use of the Modified California sampler ('ring sampler', after ASTM D 3550). The ring sampler was driven using a 140-pound hammer falling for 30 inches with a total penetration of 18 inches, recording blow counts for each six inches of penetration.

The NOVA geologist maintained a log of all sampling, as well as a depiction of the subsurface materials based on the indications of the samples and observation of the drilling itself. The recovered samples were transferred to NOVA's geotechnical laboratory for visual inspection and laboratory testing.



Closure

Each boring was backfilled upon completion, using soil cuttings to backfill the borehole to a level matching the existing surfacing.

LABORATORY TESTING

General

Soil samples recovered from the engineering borings were transferred to NOVA's geotechnical laboratory where a geotechnical engineer reviewed the soil samples and the field logs.

Representative soil samples were selected and tested in NOVA's materials laboratory to check visual classifications and to determine pertinent engineering properties. The laboratory program included visual classifications of all soil samples as well as index, expansivity and strength testing in general accordance with ASTM standards.

Records of the geotechnical laboratory testing are provided in Attachment 2.

Index Testing

'Index' testing is widely used for soil classification, as well a cost-effective means to support estimates of the mechanical characteristics (strength and compressibility) of a soil by correlation of 'index' characteristics with known characteristics of similar soil.

The visual classifications were further evaluated by performing moisture content/dry density and grain size tests. These index testing may be used to correlate samples across the site and to support estimates of a variety of soil characteristics and physical properties. Table 1 provides a summary of this testing.

Sample Ref		As Sar	Grada	ntion	Classification after	
Boring	Depth (feet)	Natural Moisture (%)	Dry Unit Weight (pcf)	Passing #200	Cu	ASTM D2488
B-1	4	7	104	-	-	SM
B-1	6	6	102	12	4	SM
B-1	8	8	105	-	-	SM
B-2	5	8	106	-	-	SM
B-2	7	8	106	16	> 10	SM
B-2	9	8	109	-	-	SM
B-3	4	6	98	-	-	SM
B-3	8	9	107	17	>10	SM

 Table 1. Abstract of the Soil Index Testing by NOVA

Notes:

1. 'Passing #200' percent by weight passing the U.S. # 200 sieve (0.074 mm), after ASTM D6913.

3. C_u' indicates Coefficient of Uniformity = D_{60} / D_{10} , using soil gradation (ASTM D6913).



Compressibility Testing

NOVA

Five (5) ring samples was tested in one dimensional consolidation after ASTM D2435. This testing was modeled to emulate conditions, saturating the soil at slightly above the existing overburden stress.

- 1. <u>Recompression</u>. The samples were loaded to at or above the existing overburden stress.
- 2. <u>Saturation</u>. The samples were saturated, recording soil compression upon saturation.
- 3. <u>Continued Loading</u>. Following stabilization after saturation, the samples were loaded to above 10,000 psf, recording continued soil compression.
- 4. <u>Rebound</u>. The samples were unloaded and the rebound recorded.

Sample Ref		As Sar	npled	Strain on	Saturation	Soil
Boring	Depth (feet)	Natural Moisture (%)	Dry Unit Weight (pcf)	Saturation Pressure (psf)	Strain on Saturation (%)	Classification
1	4	7	104	550	0.4	SM
1	6	6	102	1,000	0.6	SM
1	8	8	105	1,000	0.2	SM
2	5	8	106	1,000	0.1	SM
3	6	9	107	1,000	1.2	SM

Table 2. Abstract of the Compressibility Testing by NOVA

Geocon 2016

Geocon 2016 reports the indications of three tests of ring samples in one dimensional consolidation after ASTM D2435. This testing revealed stress-strain behavior common to sandy soils, with the exception that the sands exhibited a potential to compress ('strain' or 'settle') when first saturated.

Table 3 provides the indication of this testing. Of particular concern is Sample B1-3, which exhibited about 2% strain upon saturation.

Table 3. Abstract of the Indications of the Effects ofSaturation on Strain Reported in Geocon 2017

Saturation on Strain Reported in Geocon 2017										
Sample	Depth	Dry Unit	Strain (%) on	Soil						
Reference	(feet)	Weight (lb/ft ³)	Saturation	Classification						
B1-1	1	98	0.2	SP-SM/SM						
B1-2	3	99	0.5	SP-SM/SM						
B1-3	5	96	2.1	SP-SM/SM						



DISCUSSION

Review of Geocon 2016

Subsurface Conditions

Geocon 2016 reports that the site is underlain by thick, sandy terrace deposits. The sands within these deposits are of medium dense to dense consistency. Groundwater occurs at or near sea level, at a depth of approximately 30 to 40 feet below the existing grade.

Foundations

Structures may be developed on shallow foundations following remedial grading in the form of removal and compaction of the undocumented fill in the near surface.

Stormwater Infiltration

Geocon 2016 notes the indication of potentially excessive strain/compression that could occur when the near surface sands become saturate by releases from the stormwater infiltration BMP. As shown on Table 3, data developed by the compressibility testing indicates that saturation could cause soil movement that ranges from about 0.5 percent to 2 percent of the thickness of saturated soil.

In response to comments by the City of San Diego, Geocon 2017 utilizes the data from the compressibility testing to estimate that if a column of soil beneath a stormwater infiltration BMP were to become saturated, differential settlement on the order of 1-inch to 3-inches could be expected. Geocon 2017 notes that that differential settlement in excess of ³/₄-inch across the building foundation can have significant effects on structures.

In consideration of the foregoing, as well as the results of site-specific infiltration testing, Geocon 2017 judges that infiltration is infeasible.

Testing by NOVA

Objectives

At the outset of the work, NOVA developed a Laboratory Testing Plan intended to reproduce the testing reported in Geocon 2016 and to addresses the several factors listed below.

- 1. Compressibility Testing Data Base.
 - a. <u>Concern.</u> The three tests reported in Geocon 2016 appear to be unfairly weighted by an estimate of 2.1% hydro-collapse that is indicated by a single test (i.e., Sample B1-3 of Table 3). The results of two other tests are neither unusual, nor alarming. Design now anticipates collapse on the order of 2% over a soil column of 8-10 feet thickness, leading to high settlement estimates.
 - b. <u>Solution</u>. To address the potential that a single, anomalous test may mislead, NOVA conducted five (5) compressibility tests of the same type reported in Geocon 2016. These additional tests will improve the database for estimates of hydro-collapse.



- 2. Depth of the Testing.
 - a. <u>Concern.</u> The testing reported in Geocon 2016 is in the near surface, within the upper five feet of the soil profile. A stormwater infiltration BMP will infiltrate below the level of all but one of the tests reported on Table 3. Moreover, the remedial grading recommended in Geocon 2016 (Section 6.3.6) will remove/replace all of the tested soils, rendering the results moot.
 - b. <u>Solution</u>. The compressibility testing by NOVA expanded the considered range of depth, addressing the potential for saturation-related settlement in soils within the depth interval 4 to 8 feet bgs, the zone of soil that will be saturated by any stormwater infiltration BMP.
- 3. Soil Density.
 - a. <u>Concern</u>. As a matter of practice, soils that are potentially problematic for excessive movement upon saturation (often called 'hydro-collapse') have lower dry unit weight (γ_{DRY}) on the order of $\gamma_{DRY} = 92 \text{ lb/ft}^3$ or less (a value that is, admittedly, a 'rule of thumb' based on NOVA's experience with collapse-prone soils).
 - b. <u>Solution.</u> To cost-effectively test against this index, NOVA completed testing to determine dry density throughout the soil column. These more qualitative data may be correlated with the more rigorous compressibility testing, to add to the evidence data base 'for' or 'against' hydro-collapse.

Indications

The testing by NOVA that is reported herein addresses the several factors listed below.

- <u>Compressibility Testing Data Base</u>. Geocon 2016 and the testing reported herein provide an aggregate of eight tests (3 by Geocon and 5 by NOVA) over a soil column extending to 8 feet depth (level at which the sands become dense). Seven of the eight tests indicate no material compression (averaging about 0.3%) upon saturation. It is the judgment of NOVA that the 2.1% hydro-collapse indicated by Sample B1-3 is unrepresentative of the expected performance of the site soil.
- Depth of the Testing. The testing indicates no material potential for ground settlement upon saturation over the interval 4 feet bgs to 8 feet bgs. As noted, even if the anomalous result of Sample B1-3 (5 feet depth) is accepted, the remedial grading recommended in Geocon 2016 (Section 6.3.6) will remove/replace soil within the depth interval represented by this test, rendering the result moot.
- 3. <u>Soil Density</u>. The dry unit weight (γ_{DRY}) of the sands tested by and Geocon average NOVA γ_{DRY} > 100 lb/ft³. An extensive database of industry research identifies low dry unit weight as a qualitative identifier of collapse-prone soils. As is noted above, NOVA becomes alert for this concern when $\gamma_{DRY} < 92$ lb/ft³. The measured dry unit weights are consistent with sands that would exhibit negligible compression upon saturation. This finding is qualitative but compelling support for the judgment the sand at the site will exhibit negligible compression upon saturation.



09 May 2017 NOVA Project No. 2017701

RECOMMENDATION

In consideration of the indications of the testing reported herein, NOVA recommends that design for stormwater infiltration BMPs be undertaken with no concern for the potential that such infiltration may cause ground settlement that is potentially damaging to the planned residences.

CLOSURE

NOVA appreciates the opportunity to be of service to PEP Coastal Holdings. Should you have any questions regarding this report or other matters, please do not hesitate to call.


Sincerely, NOVA Services, Inc.

Wail Mokhtar Project Manager

John F. O'Brien, P.E, G.E. Principal Geotechnical Engineer



Attachments: Attachment 1- Engineering Borings by NOVA Attachment 2- Laboratory Testing by NOVA



SUPER SUPER SUPER ANNING & ENGINEERING HIMON STA & ENGINEERING HIMON STA & ENGINEERING HIMON STA & ENGINEERING HIMON STA & ENGINEERING					
PLATE: 1	SUBSURFACE INVESTIGATION MAP	PROJECT NO: 2017701 DATE: MAY 2017 DESIGN BY: AJS DRAWN BY: AJS CHECKED BY: WM REVIEWED BY: JDB	ECO BLOK EAST 1765 FORTUNA AVE., 3977 SHASTA ST., 1750 ROOSEVELT AVE., SAN DIEGO, CALIFORNIA	858-292-7575 858-292-7570 (FAX) WWW.USA-NOVA.COM	4373 VIEWRIDGE AVENUE, SUITE B SAN DIEGO, CALIFORNIA

Attachment 1 Engineering Borings by NOVA



	BORING LOG B-1											
DATE	EEXO	CAV	ATE	D:	API	IL 17, 2017 EQU	PMENT: B	-51				LAB TEST ABBREVIATIONS CR CORROSIVITY
EXC						COORD.: <u>N</u>					MC MAXIMUM DENSITY DS DIRECT SHEAR EI EXPANSION INDEX AL ATTERBERG LIMITS SA SIEVE ANALYSIS	
GRO		WAT	ERI	DEPTH:	GR	DUNDWATER NOT ENCOUNTERED ELEV	ATION: _4	18.0 FT				RVRESISTANCE VALUECNCONSOLIDATIONSESAND EQUIVALENT
DEPTH (FT)	GRAPHIC LOG	BULK SAMPLE	CAL/SPT SAMPLE	SOIL CLASS. (USCS)	BLOWS PER 12-INCHES	SOIL D SUMMARY OF SL (USCS; COLOR, MOISTUF		CONDITIO		ER)	LABORATORY	REMARKS
0 _				SM		GRASS AND ORGANICS VERY OLD PARALIC DEPOSITS, UNIT 6 (Qvop6): SILT	Y SAND;	LIGHT B	ROWN TO		
					12 8	REDDISH-BROWN, MOIST, LOOSE, FINE	GRAINED	, C/ UVD,			CN	6.7% 103.7pcf
-		Ì			10						CN SA	6.4% 102.0pcf
_					13 13						CN	7.7% 104.6pcf
10— — —					18	MEDIUM DENSE						
		-			21	BORING TERMINATED AT 13.5 FT. NO GI	ROUNDWATE	R ENCOU	NTEREL	. NO CAVIN	G.	
15 — — —												
 20 	-											
 25 												
_												
30			1		KE	TO SYMBOLS			ECO BLO	OK EAST		
▼ ⊠					OUNDWA			1750	ROOSE	, 3977 SHAS /ELT AVENU CALIFORNIA	E	ET,
		ę	SPT	SAMPLE	ASTM D1	586) GEOLOGIC CONT/			HP	DATE:	MAY 20 ⁻	NOVA
	С	AL. N	IOD.	SAMPLE	(ASTM D3	550) — — — SOIL TYPE CHAN	GE REVIEW	/ED BY:	AJS	PROJECT	NO.: 1017	701 APPENDIX B-1

DATE EXCAVATED: APRIL 17,2017 EQUIPMENT: 5-51 CONCREDIT EXCAVATION DESCRIPTION: #INCH DAMETER AUGER SORING GPS COORD.: NA GROUNDWATER DEPTH: GROUNDWATER MOTENCOINTERED ELEVATION: 42.0 FT Participation GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER DEPTHON Participation Participation GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER Participation GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER Participation GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER DEPTH: GROUNDWATER Participation GROUNDWATER DEPTH: GROUNDWATER DATI 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. FOR BLOK EAST 8.3% 108.0 Qpc		BORING LOG B-2									
EXCAVATION DESCRIPTION: INCL DIAMETER AUGREBORING QPS COORDJ: INA PS Difference Series GROUNDWATER DEPTH: GROUNDWATER NOT ENCONTERED ELEVATION: 42.9 fT State Series State Series GROUNDWATER DEPTH: GROUNDWATER NOT ENCONTERED ELEVATION: 42.9 fT State Series State Series USES SUBMARY OF SUBSURFACE CONSTRUCTION 40.9 ft State Series State Series USES SUBMARY OF SUBSURFACE CONSTRUCTIONS State Series State Series USES SUBMARY OF SUBSURFACE CONSTRUCTIONS State Series State Series USES COLOR SUBMARY OF SUBSURFACE CONSTRUCTIONS State Series USES COLOR SUBMARY OF SUBSURFACE SUBMARY OF SUBSURFACE CONSTRUCTIONS USES COLOR SUBMARY OF SUBSURFACE SUBMARY OF SUBSURFACE CONSTRUCTIONS USES SUBMARY SUBMARY OF SUBSURFACE SUBMARY OF	DATE EXCAVATED: APRIL 17, 2017 EQUIPMENT: B-51										
GROUNDWATER DEPTH: OPCUMUMATER NOTENCOUNTERED ELEVATION: 24 PT CN CN CONSCIDENTION SUMMARY OF SUBSURFACE CONDITIONS (USCS; COLOR, MOISTURE, DENSITY, GRAIN SIZE, OTHER) D 1 1 1 0	EXCA	VAT	ION	DES	SCRIPTI	ON: 6 II	ICH DIAMETER AUGER BORING GPS COORD.: N/A		DS DIRECT SHEAR EI EXPANSION INDEX AL ATTERBERG LIMITS		
Image: Signed biology of the second state o	GRO	JND	WAT	ERI	DEPTH:	GR	DUNDWATER NOT ENCOUNTERED ELEVATION: 42.0 FT		RV RESISTANCE VALUE CN CONSOLIDATION		
SM UNINGS AND PRAILED SEPONENTS. UNIT 6 (Qxxxp6): SILTY SAND: LIGHT BROWN TO REDDISH-BROWN, MOIST, LOOSE, FINE GRAINED 10 10 13 8.5% 106.8pcf 13 8.5% 106.8pcf 14 13 10 8.5% 106.8pcf 11 8.5% 106.8pcf 12 4.3% 109.0pcf 13 8.5% 106.8pcf 14 13 15 34 16 10 17 8.5% 106.8pcf 18 8.5% 106.0pcf 19 34 10 10 11 10 12 11 13 8.5% 106.0pcf 14 10 15 10 16 10 17 10 18 10 19 10 10 11 10 11 10 11 10 11 10 11 10 11	DEPTH (FT)	GRAPHIC LOG	BULK SAMPLE	CAL/SPT SAMPLE	SOIL CLASS. (USCS)	BLOWS PER 12-INCHES	SUMMARY OF SUBSURFACE CONDITIONS	LABORATORY	REMARKS		
Image: Second	0				SM		GRASS AND ORGANICS				
13 13 8.5% 105.6pcf 10 29 MEDIUM DENSE 8.5% 109.0pcf 34 34 34 8.5% 109.0pcf 15 34 80RING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 8.5% 109.0pcf 20 34 80RING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 8.5% 109.0pcf 20 34 80RING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 8.5% 109.0pcf 20 15 10 10 10 20 15 10 10 10 20 15 10 10 10 20 15 10 10 10 20 10 10 10 10 20 10 10 10 10 20 10 10 10 10 20 10 10 10 10 20 10 10 10 10 20 10 10 10 10 20 10 10 10 10 20	-				511	10					
A BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. BULK SAMPLE FRONEOUS BLOWCOUNT FORTUNA AVENUE, 3977 SHASTA STREET, 1750 ROOSEVELT AVENUE SAN DIEGO, CALIFORNIA	5 —					13		CN	7.8% 106.3pcf		
10 23 MEDIUM DENSE 34 34 15 34 15 34 20 8 20 8 20 8 21 8 22 8 23 8 24 8 25 8 26 8 27 8 28 8 29 8 20 8 20 8 21 8 22 8 23 8 24 8 25 8 26 8 27 8 28 8 29 8 20 8 20 8 21 8 22 8 23 8 24 9 25 8 26 8 27 8 28 8	_					13		SA			
15 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 15 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. NO CAVING. 20 BORING TERMINATED AT 13.5 FT. NO GROUNDWATER ENCOUNTERED. 20 BORING TERMINATER ENCOURS BLOWCOUNTERED. 20 BULK SAMPLE 20 BULK SAMPLE 20 BULK SAMPLE 20 BULK SAMPLE 20 SAN DIEGO, CALIFORNIA	10 — —					29	MEDIUM DENSE		6.5% 109.0pci		
15 20 20 20 20 21 25 30 KEY TO SYMBOLS SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SGROUNDWATER SAMPLE SAN DIEGO, CALIFORNIA SAN DIEGO, CALIFORNIA SAN DIEGO, CALIFORNIA	_					34	BORING TERMINATED AT 13.5 ET. NO GROUNDWATER ENCOUNTERED. NO CAVING				
25	15 — — —										
30 KEY TO SYMBOLS 30 ECO BLOK EAST SROUNDWATER # ERRONEOUS BLOWCOUNT MULK SAMPLE # ERRONEOUS BLOWCOUNT NO SAMPLE RECOVERY SAN DIEGO, CALIFORNIA	 20 										
KEY TO SYMBOLS ECO BLOK EAST GROUNDWATER # ERRONEOUS BLOWCOUNT BULK SAMPLE # ERRONEOUS BLOWCOUNT NO SAMPLE RECOVERY SAN DIEGO, CALIFORNIA	 25										
KEY TO SYMBOLS ECO BLOK EAST GROUNDWATER # ERRONEOUS BLOWCOUNT BULK SAMPLE # ERRONEOUS BLOWCOUNT NO SAMPLE RECOVERY SAN DIEGO, CALIFORNIA											
Image: Second Water # ERHONEOUS BLOWCOUNT 1750 ROOSEVELT AVENUE Image: Second Water Mosample Recovery San Diego, California	00			1		KE	Y TO SYMBOLS ECO BLOK EAST				
							1750 ROOSEVELT AVENUE	STRE	IET,		
			:	SPT				AV 00	NOVA		
CAL. MOD. SAMPLE (ASTM D3550) — — SOIL TYPE CHANGE REVIEWED BY: AJS PROJECT NO.: 1017701 APPENDIX B-2		С									

	BORING LOG B-3										
								LAB TEST ABBREVIATIONS			
DATI EXC/						IL 17, 2017 EQUIPMENT: B-51 CH DIAMETER AUGER BORING GPS COORD.: N/A		CR CORROSIVITY MC MAXIMUM DENSITY DS DIRECT SHEAR EI EXPANSION INDEX AL ATTERBERG LIMITS SA SIEVE ANALYSIS			
GRO		WAT		DEPTH:	_GR(DUNDWATER NOT ENCOUNTERED ELEVATION: 37.0 FT		RV RESISTANCE VALUE CN CONSOLIDATION SE SAND EQUIVALENT			
DEPTH (FT)	GRAPHIC LOG	BULK SAMPLE	CAL/SPT SAMPLE	SOIL CLASS. (USCS)	BLOWS PER 12-INCHES	SOIL DESCRIPTION SUMMARY OF SUBSURFACE CONDITIONS (USCS; COLOR, MOISTURE, DENSITY, GRAIN SIZE, OTHER)	LABORATORY	REMARKS			
0 _	0.0000000 00000000			SM-ML		UNDOCUMENTED FILL (Qudf): SILTY SAND-SANDY SILT; BROWN, DAMP TO DRY, LOOSE OR SOFT, FINE TO MEDIUM GRAINED					
	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			SM	13	VERY OLD PARALIC DEPOSITS, UNIT 6 (Qvop6): SILTY SAND; LIGHT BROWN TO REDDISH-BROWN, MOIST, LOOSE, FINE GRAINED		6.2% 97.9pcf			
-					17 18	MEDIUM DENSE	CN	9.4% 107.0pcf			
10 —					15	VERY DENSE GRAVEL					
						Y TO SYMBOLS ECO BLOK EAST TER # ERRONEOUS BLOWCOUNT 1765 FORTUNA AVENUE, 3977 SHASTA	STRE	ET,			
\mathbf{X}					BULK SAN	1750 ROOSEVELT AVENUE					
		:	SPT	SAMPLE	(ASTM D1	586) GEOLOGIC CONTACT LOGGED BY: HP DATE: M	AY 20	NOVA			
	CAL. MOD. SAMPLE (ASTM D3550) SOIL TYPE CHANGE					550) — – – SOIL TYPE CHANGE REVIEWED BY: AJS PROJECT NO	: 1017	7701 APPENDIX B-3			

Attachment 2 Laboratory Testing by NOVA



Laboratory tests were performed in accordance with the generally accepted American Society for Testing and Materials (ASTM) test methods or suggested procedures. Brief descriptions of the tests performed are presented below:


- CLASSIFICATION: Field classifications were verified in the laboratory by visual examination. The final soil classifications are in accordance with the Unified Soils Classification System and are presented on the exploration logs in Attachment 1.
- MAXIMUM DENSITY AND OPTIMUM MOISTURE CONTENT (ASTM D1557 METHOD A,B,C): The maximum dry density and optimum moisture content of typical soils were determined in the laboratory in accordance with ASTM Standard Test D1557, Method A, Method B, Method C.
- GRADATION ANALYSIS (ASTM C136 and/or ASTM D422): Tests were performed on selected representative soil samples in general accordance with ASTM D422. The grain size distributions of selected samples were determined in accordance with ASTM C136 and/or ASTM D422 The results of the tests are summarized on Attachment 2.3 through 2.5.
- CONSOLIDATION TESTS (ASTM D2435): Tests were performed on selected relatively undisturbed soil samples in general accordance with ASTM D2435. The samples were inundated during testing to represent adverse field conditions. The percent of consolidation for each load cycle was recorded as a ratio of the amount of vertical compression to the original height of the sample. The results of the tests are summarized on Appendix 2.6 through Appendix 2.10.

		LAB TEST SUMMARY						
		ECO BLOK EAST 1765 FORTUNA AVE., 3977 SHASTA ST., 1750 ROOSEVELT AVE.						
NOVA								
4373 VIEWRIDGE AVEN	UE, SUITE B		SAN DIEGO,	CALIFORNIA				
SAN DIEGO, CALIF PHONE: 858-292-7575	SAN DIEGO, CALIFORNIA ONE: 858-292-7575 FAX: 858-292-7570		DATE: MAY 2017	PROJECT: 2017701	ATTACHMENT: 2.1			

Sample	Sample Depth		Moisture	Dry Density
Location	(ft)	Soil Description	(%)	(pcf)
B-1	4.0'	Light Reddish Brown Silty Sand	6.7	103.7
B-1	6.0'	Light Reddish Brown Silty Sand	6.4	102.0
B-1	8.0'	Light Reddish Brown Silty Sand	7.7	104.6
B-2	5.0'	Light Reddish Brown Silty Sand	7.8	106.3
B-2	7.0'	Light Reddish Brown Silty Sand	8.5	105.6
B-2	9.0'	Light Reddish Brown Silty Sand	8.3	109.0
B-3	4.0'	Light Reddish Brown Silty Sand	6.2	97.9
B-3	8.0'	Light Reddish Brown Silty Sand	9.4	107.0


Moisture-Density (ASTM D2937)


	LAB TEST RESULTS						
NOVA 4373 VIEWRIDGE AVENUE, SUITE B	ECO BLOK EAST 1765 FORTUNA AVE., 3977 SHASTA ST., 1750 ROOSEVELT AVE. SAN DIEGO, CALIFORNIA						
SAN DIEGO, CALIFORNIA PHONE: 858-292-7575 FAX: 858-292-7570	BY: AJS	DATE: MAY 2017	PROJECT: 2017701	ATTACHMENT: 2.2			





 $\rightarrow \leftarrow$ Hydrometer Analysis \rightarrow U.S. Standard Sieve Sizes ← 200 100 16 50 30 ω 1.5 1 3/4 1/2 3/8 . Р ġ . Р ۶. ö 100 : 90 ı۱ 80 i **Percent Passing** 70 ľ 60 ١ ۱ 50 L 40 - - - -1 1 ۱ 30 ۱ ۱ 20 ľ 1 ł 10 1 I 0 100 10 0.1 0.01 0.001 1 Grain Size (mm) Gravel Sand Silt or Clay Fine Coarse Fine Medium Coarse Sample Location: B-2 Depth (ft.): 7.0' USCS Soil Type: SM Passing No. 200 (%): 16 **GRADATION ANALYSIS TEST RESULTS** ECO BLOK EAST 1765 FORTUNA AVE., 3977 SHASTA ST., 1750 ROOSEVELT AVE. N()SAN DIEGO, CALIFORNIA 4373 VIEWRIDGE AVENUE, SUITE B SAN DIEGO, CALIFORNIA BY: AJS DATE: MAY 2017 PROJECT: 2017701 ATTACHMENT: 2.4 FAX: 858-292-7570 PHONE: 858-292-7575


— Size (Inches) —> $\rightarrow \leftarrow$ — Hydrometer Analysis — < U.S. Standard Sieve Sizes \rightarrow 200 100 16 50 30 œ 1.5 1 3/4 1/2 3/8 ģ . ۷ ġ 100 90 80 **Percent Passing** 70 60 1 50 40 I 1 30 I Ŀ 1 1 20 i i 10 I 0 100 10 0.1 0.001 0.01 1 Grain Size (mm) Sand Gravel Silt or Clay Fine Coarse Fine Medium Coarse Sample Location: B-3 Depth (ft.): 8.0' USCS Soil Type: SM Passing No. 200 (%): 17 **GRADATION ANALYSIS TEST RESULTS** ECO BLOK EAST 1765 FORTUNA AVE., 3977 SHASTA ST., 1750 ROOSEVELT AVE. N()VА SAN DIEGO, CALIFORNIA 4373 VIEWRIDGE AVENUE, SUITE B SAN DIEGO, CALIFORNIA BY: AJS DATE: MAY 2017 PROJECT: 2017701 ATTACHMENT: 2.5 PHONE: 858-292-7575 FAX: 858-292-7570













GEOTECHNICAL
MATERIALS
SPECIAL INSPECTIONS

SBE SLBE SCOOP

PFP Coastal Holdings, LLC 4380 La Jolla Village Drive, Suite 250 San Diego, CA 92122

July 5, 2017 NOVA Project No. 2017701

Attention: Mr. Ian Gill

Subject: Assumption of Geotechnical Engineer-of-Record Eco Blok East Apartments 1765 Fortuna Avenue, 3977 Shasta Street, 1750 Roosevelt Avenue San Diego, California

References:

- 1. <u>Geocon 2016</u>. *Geotechnical Investigation, Eco Blok East, Shasta Street, San Diego, California*, Geocon, Project No. G1832-42-03, December 19, 2016.
- 2. <u>Geocon 2017</u>. Response to City of San Diego Review Comments, Eco Blok East, San Diego, California, Geocon Project No. G1832-42-03, March 2, 2017.
- 3. <u>Golba 2016.</u> Building Plan Set, Eco Blok Residences, 3977 Shasta Street, San Diego, California; Golba Architecture, December 13, 2016.
- 4. <u>Latitude 33 2017</u>. *Grading & Drainage Plans for: Eco Blok East, 1765 Fortuna Avenue, 3977 Shasta Street, 1750 Roosevelt Avenue, San Diego, California,* Latitude 33 Planning and Engineering, February 27, 2017.
- 5. <u>NOVA 2017</u>. *Report, Assessment of the Potential for Infiltration-Related Soil Collapse, Eco Blok East, San Diego, California,* NOVA Services, Inc., Project No. 2017701, May 9, 2017.

Dear Mr. Gill:

The intent of this letter is to document that NOVA Services, Inc. (NOVA) has been retained by PFP Coastal Holdings, LLC for the subject project. NOVA will assume the role of Geotechnical Engineer-of-Record.

NOVA has reviewed the referenced geotechnical reports and referenced plans for the Eco Blok East Development. With the exception of Potential for Infiltration-Related Collapse, NOVA agrees with the soil and geologic conditions, geologic hazard assessment, site development recommendations, infiltration test data and calculated infiltration rates presented in the referenced geotechnical reports (Geocon 2016, Geocon 2017), building plan (Golba 2016) and grading plans (Latitude 33 2017).

Geocon 2016 reports the indications of three tests of ring samples in one dimensional consolidation after ASTM D2435. This testing revealed stress-strain behavior common to sandy soils, with the exception that the sands exhibited a potential to compress ('strain' or 'settle') when first saturated. Geocon 2016 notes the indication of potentially excessive strain/compression that could occur when the near surface sands become saturated by releases from the stormwater infiltration BMP.

NOVA conducted five (5) compressibility tests of the same type reported in Geocon 2016. The findings of this work are reported in NOVA 2017. The compressibility testing NOVA expanded the considered range of depth, addressing the potential for saturation-related settlement in soils within the depth interval 4 to 8 feet



bgs, the zone of soil that will be saturated by any stormwater infiltration BMP. As is discussed in detail in NOVA 2017, the testing indicates no material potential for ground settlement upon saturation over the interval 4 feet bgs to 8 feet bgs. In consideration of the indications of the testing reported in NOVA 2017, NOVA recommends that design for stormwater infiltration BMPs be undertaken with no concern for the potential that such infiltration may cause ground settlement that is potentially damaging to the planned residences. Attached is infiltration worksheet C.4-1, Categorization of Infiltration Feasibility Conditions that was provided with NOVA 2017.

It is hoped the foregoing is clear. Should you have any questions regarding this letter or other matters, please contact the undersigned at (858) 292-7575.

Sincerely, NOVA Services, Inc.

John F. O'Brien, P.E, G.E. Principal Geotechnical Engineer



Ima Willes - Holy

Bryan Miller-Hicks, P.G., C.E.G. Senior Geologist



Worksheet C.4-1: Categorization of Infiltration Feasibility Condition

Categ	orization of Infiltration Feasibility Condition	Worksheet C.4-1	
Would in consequ Note th preclude	Full Infiltration Feasibility Screening Criteria Infiltration of the full design volume be feasible from a physical pers ences that cannot be reasonably mitigated? at it is not necessary to investigate each and every criterion in d. Instead a letter of justification from a geotechnical professional f iating any geotechnical issues will be required.	the workshee	t if infiltration is
Criteria	Screening Question	Yes	No
1	Is the estimated reliable infiltration rate below proposed facility locations greater than 0.5 inches per hour? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.2 and Appendix D.	X	
	n study conducted by Geocon (2016) was calculated to be more than 0.3 a minimum factor of safety. I-1: 7.5 in/hr (3.75 in/hr with a FOS of 2) I-2: 11.3 in/hr (5.7 in/hr with a FOS of 2) I-3: 12.0 in/hr (6.0 in/hr with a FOS of 2) I-4: 13.7 in/hr (6.9 in/hr with a FOS of 2)	5 inches per hou	ır after
	Geocon (2016)		
2	Can infiltration greater than 0.5 inches per hour be allowed without increasing risk of geotechnical hazards (slope stability, groundwater mounding, utilities, or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.2.	X	
Provide l			
C2.2 Afta exhibit n C2.3 No C2.4 BM C2.5 Sto groundw grade. C2.6 BM C2.7 Oth	eologic investigation was performed at the subject site by Geocon 2016 er the investigation performed by NOVA 2017, the findings support the ju- egligible compression upon saturation. slopes are within close proximity to the site. Ps should be at minimum of 10 feet from any utilities. rmwater infiltration can result in damaging ground water mounding dur ater elevations were estimated by Geocon to be at depths greater than 3 Ps should be at a minimum of 10 feet from retaining walls and foundation ere Factors: After evaluating the compressibility, depth of testing, and so hat the site is capable of full infiltration.	udgment that th ing wet periods 0 feet below exi ons.	e site will , however sting

	Worksheet C.4-1 Page 2 of 4				
Criteria	Screening Question	Yes	No		
3	Can infiltration greater than 0.5 inches per hour be allowed without increasing risk of groundwater contamination (shallow water table, storm water pollutants or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.3.				
Provide					
Water c	contamination was not evaluated by Geocon nor NOVA services.				
4	Can infiltration greater than 0.5 inches per hour be allowed without causing potential water balance issues such as change of seasonality of ephemeral streams or increased discharge of contaminated groundwater to surface waters? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.3.				
Provide l	basis:				
The pote	ntial for water balance was not evaluated by Geocon nor NOVA services.				
Part 1 Result*	If all answers to rows 1 - 4 are " Yes " a full infiltration design is potentially feasible. The feasibility screening category is Full Infiltration		YES		
	If any answer from row 1-4 is "No", infiltration may be possible to some	e extent but			

*To be completed using gathered site information and best professional judgment considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by County staff to substantiate findings.

1	Worksheet C.4-1 Page 3 of 4				
<u>Part 2 – P</u>	Part 2 – Partial Infiltration vs. No Infiltration Feasibility Screening Criteria				
Would infiltration of water in any appreciable amount be physically feasible without any negative consequences that cannot be reasonably mitigated?					
Criteria	Screening Question	Yes	No		
5	Do soil and geologic conditions allow for infiltration in any appreciable rate or volume? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.2 and Appendix D.	Х			
Provide ba	asis: <i>See criteria 1.</i>				
6	Can Infiltration in any appreciable quantity be allowed without increasing risk of geotechnical hazards (slope stability, groundwater mounding, utilities, or other factors) that cannot be mitigated to an acceptable level? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.2.	Х			
Provide b	asis: <i>See criteria 2</i> .				

Worksheet C.4-1 Page 4 of 4				
Criteria	Screening Question	Yes	No	
7	Can Infiltration in any appreciable quantity be allowed without posing significant risk for groundwater related concerns (shallow water table, storm water pollutants or other factors)? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.3.			
Provide <i>Water c</i>	basis: ontamination was not evaluated by Geocon nor NOVA services.			
8	Can infiltration be allowed without violating downstream water rights ? The response to this Screening Question must be based on a comprehensive evaluation of the factors presented in Appendix C.3.			
Provide basis: The potential for water balance was not evaluated by Geocon nor NOVA services.				
Part 2 Result*				

*To be completed using gathered site information and best professional judgment considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by Agency/Jurisdictions to substantiate findings

C.5 Feasibility Screening Exhibits

Table C.5-1 lists the feasibility screening exhibits that were generated using readily available GIS data sets to assist the project applicant to screen the project site for feasibility.

Figures	Layer	Intent/Rationale	Data Sources
	Hydrologic Soil Group – A, B, C, D	Hydrologic Soil Group will aid in determining areas of potential infiltration	SanGIS http://www.sangis.org/
C.1 Soils	Hydric Soils	Hydric soils will indicate layers of intermittent saturation that may function like a D soil and should be avoided for infiltration	USDA Web Soil Survey. Hydric soils, (ratings of 100) were classified as hydric. http://websoilsurvey.sc.egov.usda.gov/Ap p/HomePage.htm
	Slopes >25%	BMPs are hard to construct on slopes >25% and can potentially cause slope instability	SanGIS http://www.sangis.org/
C.2: Slopes and Geologic	Liquefaction Potential	BMPs (particularly infiltration BMPs) must	SanGIS
Hazards	Landslide Potential	not be sited in areas with high potential for liquefaction or landslides to minimize earthquake/landslide risks	http://www.sangis.org/ SanGIS Geologic Hazards layer. Subset of polygons with hazard codes related to landslides was selected. This data is limited to the City of San Diego Boundary. http://www.sangis.org/
C.3: Groundwater Table Elevations	Groundwater Depths	Infiltration BMPs will need to be sited in areas with adequate distance (>10 ft) from the groundwater table	GeoTracker. Data downloaded for San Diego county from 2014 and 2013. In cases where there were multiple measurements made at the same well, the average was taken over that year. http://geotracker.waterboards.ca.gov/data _download_by_county.asp
C.4: Contaminated Sites	Contaminated soils and/or groundwater sites	Infiltration must limited in areas of contaminated soil/groundwater	GeoTracker. Data downloaded for San Diego county and limited to active cleanup sites http://geotracker.waterboards.ca.gov/

Table C.5-1: Feasibility Screening Exhibits

This page was left intentionally blank.

