

 **NOTICE****DEVELOPMENT SERVICES DEPARTMENT**

CITY OF SAN DIEGO - 1222 FIRST AVENUE, M.S. 501, SAN DIEGO, CALIFORNIA 92101

DATE: July 5, 2017

TO: Distribution

FROM: Gregory Hopkins, Deputy Director, Development Services Department

SUBJECT: Accessible Pedestrian Push Button

Effective on August 1, 2017, applicants will be required to conform, as applicable, to the requirement of installing an Accessible Pedestrian Push Button. Should your project meet the conditions for this City facility type, this condition will be provided during the permitting review.

Specific technical details on this facility may be found as provided in the attached City Engineer notice. For your reference, the City of San Diego Supplemental Standard Specifications ("Whitebook") may be found at the following link:

<https://www.sandiego.gov/publicworks/edocref>

Permits in review which have not had a permit issued by August 1, 2017 shall comply with the requirements. All permits issued prior to August 1, 2017 shall be grandfathered into the requirements at the time of permit approval.



THE CITY OF SAN DIEGO

M E M O R A N D U M

DATE: June 27, 2017
TO: Distribution
FROM: Marnell Gibson, City Engineer
SUBJECT: New Accessible Pedestrian Signal Push Button Housing Requirement

The housing assembly for the pole-supported pedestrian signal push button or pedestrian push button shall be made of die-cast aluminum or permanent mold-cast aluminum with a color throughout that matches color no. 33538 of Federal Standard 595.

Effective August 1, 2017, design and construction of new and relocated signal poles shall comply with this new requirement and shall be installed per Section 700-5.3 Pedestrian Push Button Assemblies of the City of San Diego Standard Specifications for Public Works Construction (the "Whitebook") 2015 Edition.

Implementation:

1. **Private Projects Submitted to Development Services:**
 - a. Projects submitted on or after August 1, 2017 shall comply with the new requirement.
 - b. Projects currently in review and have not had permits issued by August 1, 2017 shall comply with the new requirement.
 - c. Projects with permits issued on or before August 1, 2017 shall be allowed to comply with the previous requirement.
2. **City Projects:**
 - a. Projects that have final design signed and stamped by the DCE, and have advertised prior to August 1, 2017 shall be allowed to comply with the previous requirements.

Please notify your Project Managers, designers, consultants, and maintenance crews of the new requirements. If you have any question or need additional information, contact Duncan Hughes at 619-533-3141 or DRHughes@sandiego.gov.



Marnell Gibson, PE C50892
City Engineer

Distribution List:

Scott Chadwick, Chief Operating Officer
Stacey LoMedico, Assistant Chief Operating Officer
Paz Gomez, Deputy Chief Operating Officer, Infrastructure/Public Works
James Nagelvoort, Director, Public Works Department
Kevin Ester, Assistant Fire Chief, San Diego Fire-Rescue
Robert Vacchi, Director, Development Services Department
Mario X. Sierra, Director, Environmental Services Department
Misty Jones, Director, Library
Herman Parker, Director, Park and Recreation Department
Halla Razak, Director, Public Utilities Department
Cybele Thompson, Director, Real Estate Assets Department
Kris McFadden, Director, Transportation & Storm Water Department
Tom Tomlinson, Assistant Director, Planning Department
Thyme Curtis, Executive Director, ADA Compliance & Accessibility
Stephen Maduli-Williams, Program Manager, Economic Development
Daniel Kay, Civic San Diego
Deputy City Engineers