REVISED DRAFT

EAST VILLAGE

COMBINED HISTORICAL SURVEYS

2005

- East Village 1988 Update Survey
 - Bayside 1989 Update Survey
 - Over 45's 2004 Survey

City of San Diego Planning Department

Betsy McCullough, Deputy Planning Director Diane Kane, Ph.D., Senior Planner, Historical Resources Section Rick Brown, Graphics

Noah Stewart, Intern, Historical Resources Section Lorraine Roley, Volunteer, Historical Resources Section

Marie Burke Lia & Associates

Scott Moomjian, Historian Wendy Tinsley, Historian

January 2005

REVISED DRAFT EAST VILLAGE HISTORICAL PROPERTY SURVEY REPORT 2005

TABLE OF CONTENTS

I. Survey Background	1
1. East Village Combined Surveys	2
A. East Village Survey Update	2
B. Bayside Survey Update	
C. Over 45s Survey	
II. East Village Historical Overview.	5
(Scott Moomjian)	
III. East Village Historical Contexts (HRB staff)	9
1. Residential Development Patterns	9
A. Residential Patterns prior to 1887	9
a) Property Type: Single Family Vernacular	9
B. Residential Patterns in 1888	
a) Property Type: Single Family Folk Victorian Cottages	11
b) Property type: Pyramidal Roof Cottage	11
c) Property Type: Second empire Houses	12
d) Property Type: Dutch Colonial Revival House	12
C. Residential Patterns in 1906	13
a) Property Type: The Foursquare	13
D. Residential Patterns, 1921-1956	14
a) Property Type: The Tenement	15
b) Property Type: Apartments by Choice	
c) Property Type: The Bungalow	19
d) Property Type: The Courtyard Apartment	
2. Industrial & Commercial Development	25
A. Taxpayer Blocks	25
B. Auto-related Properties	
a) Property Type: Automobile Showrooms	
b) Property Type: Automobile Garages	
IV. Survey Findings & Staff Recommendation	35
V. Bibliography	37

APPENDICES

- A. Historical Property Location MapsB. Thumbnail Photos of Related Property Types
- C. DPR Forms

I. SURVEY BACKGROUND

Over the past four years, five surveys have been conducted to address various historical themes in East Village. They include: 1) an update of the November 1988 Historic Site Inventory of City Centre East (East Village Survey); 2) an update of the 1989 Bayside Historic Property Inventory; 3) a new survey of properties over 45 years old that have not been previously surveyed; 4) a thematic survey of warehouses required by the Ballpark Settlement Agreement; and 5) a thematic survey of significant African American historic sites requested by the Black Historical Society of San Diego and endorsed by the Historical Resources Board (HRB).

These historical property inventories have been prepared by various consultants under the sponsorship of the Centre City Development Corporation (CCDC). Their completion is intended to coincide with the preparation of the Centre City Community Plan Update. The survey results will be used in three ways: 1) to inform land use decisions regarding long-range planning opportunities and constraints in East Village; 2) to support the Environmental Impact Report required by the California Environmental Quality Act (CEQA) for the Community Plan Update; and 3) to inform current (and future) property owners of the benefits and responsibilities associated with historical property ownership.

Comprising a total of 210 properties, the surveys have overlapping boundaries, historical themes and periods of significance. Two of the inventories (East Village and Bayside) are updates of earlier surveys. They are being brought to the HRB for review and comment because the Centre City Planned District Ordinance, Section 103.1904(e) of the City Municipal Code, requires that properties identified as potential historical sites in these surveys be reviewed by the City's HRB prior to development. Three of the surveys (Over '45s, Warehouse and African American) comply with Land Development Code Section 143.0212 that requires properties 45 years old or older to be evaluated for historical significance in conjunction with major new construction.

In preparation for the HRB hearings, HRB and CCDC staff initiated a public outreach process that included three mailings to property owners providing background information on the purpose of the historical surveys, the HRB designation process and criteria, and the benefits and responsibilities of historical property ownership. The survey findings were shared with property owners at a public information meeting held on Wednesday, November 10, 2004. The survey findings were also presented to the HRB Policy Subcommittee at its November 8, 2004, meeting.

The inventory findings were first introduced at the November 18, 2004, HRB meeting, where a broad overview of the individual survey contents, as well as their physical and thematic interrelationships was discussed. The HRB will begin reviewing the East Village, Bayside and Over 45s survey findings, included in this document, for potential adoption commencing with the January 2005 meeting. The HRB will be asked to adopt the findings of the survey in order to advise owners of the potential historical significance of their properties. The HRB will also be asked to subsequently Note and File those resources with no potential for historical significance so these parcels can be cleared for future redevelopment. Property owners may also request designation determinations to be processed upon adoption of the survey. Other than those property owner requests, the HRB will not be taking action on other potentially significant resources at this time. If and when the potentially significant properties undergo redevelopment,

a determination relative to designation will be made at that time by the HRB before permit processing.

With regard to the proposed African-American and Warehouse Thematic District surveys, the HRB will be asked to designate a thematic historic district with identified and appropriate contributors, should the HRB concur with the findings of the studies at future meetings. Complete Historical Overviews and Context Statements for the Warehouse Thematic Historic District and the African American Thematic Historic District are included in those documents, along with maps and DPR forms for district contributors.

1. East Village Combined Surveys

This document, comprised of 85 inventoried historical resources, integrates three historical surveys conducted in East Village between 2001-2004 by the office of Marie Burke Lia & Associates on behalf of the Centre City Development Corporation (Appendix A, Map 1). The survey boundaries, property types and preliminary findings are described below. Survey boundary maps and surveyed historical resources maps are located in Appendix A. Thumbnail photographs of surveyed resources, grouped by age and property type, are located in Appendix B. Major modifications to historic fabric are highlighted in red on the photographs. Consultant-prepared DPR forms for each surveyed property are located in Appendix C, along with historic photographs for some of the properties. A composite map of all surveyed properties that correlates with the numbered DPR forms is found in Appendix A, Map 3.

Readers may note occasional differences in the property architectural descriptions and age between the HRB staff-prepared photographs and spreadsheets and the consultant-prepared DPR forms. This is a reasoned difference of professional opinion, based upon differing source material, independent research and inspection of physical fabric, not an error on the part of either the staff or consultant. Differences of opinion are also evident in the consultant's findings versus the HRB staff's findings. Again, a difference of opinion between professionals is not uncommon. It is expected that the Historical Resources Board will take the best thinking of all the preservation professionals involved in the surveys and come to a reasoned conclusion of its own design.

Staff also prepared additional materials addressing HRB Criterion A for East Village residential patterns for HRB consideration. This information is located in Section III. Information on autorelated historical resources and taxpayer blocks will be mailed with the January HRB agenda packets, along with several maps currently under preparation. Additionally, as previously directed by the HRB, staff has returned one deferred property identified in the Centre City Core Historic Survey in conjunction with staff's analysis of the Taxpayer Block property type under Criterion C.

A. East Village Survey Update

This survey is an update of a 1988 survey whose slightly larger boundaries have been modified to Russ Boulevard and San Diego City College to the north; 17th Avenue and Interstate 5 to the east; J Street on the south; Sixth Avenue to the west to E Street; and the south side of the 600

through 1100 blocks of E Street and the east side of the 1000 through 1300 blocks of 12th Avenue on the west (Appendix A: Map 2).

The 1988 survey identified 109 properties. Through survey boundary adjustments, HRB designations or Note and File decisions, demolitions and relocations, the original 109 properties have dwindled to 69. Consultant Marie Lia and Associates determined that three sites appeared eligible for the National Register of Historic Places; 30 appeared eligible for local listing under HRB Criterion C (Architecture); and 21 sites appeared to merit Note and File recommendations. Fifteen properties were not evaluated pending further historical research to determine significance.

Due to the passage of time since the consultant fieldwork, two properties in the East Village survey have been designated and two have been demolished after an HRB recommendation to Note and File their designation applications, leaving 65 properties for HRB staff review. HRB staff evaluated the 15 unevaluated properties and concluded that 14 of them meet HRB Criterion C for local designation. Of the remaining 50 properties, HRB staff determined that 34 meet HRB Criterion C for architecture and 16 are recommended for Note and File. One of the individually significant properties is a contributor to the proposed African American Thematic Historic District. Although not eligible for individual designation, one of the Note and File candidates is a contributor to the proposed Warehouse Thematic Historic District. Both of these properties have been removed from the East Village 1989 Survey Update and placed in the more appropriate survey for HRB consideration at a later time.

Property types in the survey include single and multi-family residential units that range in date from the 1870s through the 1920s and encompass the popular styles of their day. Commercial properties include hotels, auto showrooms, garages and auto repair establishments, as well as miscellaneous manufacturing, vending and warehousing enterprises that require large, utilitarian spaces and inexpensive rents to prosper.

B. Bayside Survey Update

Boundaries of the 1989 Bayside Survey encompassed the area south of J Street, east of the I-5 Freeway and north of Commercial Street. The western boundaries angled northwest along Harbor Drive to 6th Avenue, concentrating on historical resources around what is now Petco Park (Appendix A, Map 2). As a result of the intense redevelopment activity in this sector of East Village, only 11 of the 27 original properties remained from the 1989 survey to update. They were re-evaluated by consultant Marie Lia and Associates and added to the East Village Survey for HRB review.

The consultant-prepared updates concluded that three of the 11 properties meet HRB Criterion C for local designation, while eight are recommended for Note and File. After a field review and additional research, HRB staff concluded that seven of the properties appear to meet HRB Criterion C for architecture and four appear to be contributors to the proposed Warehouse District. The Warehouse District contributors have been removed from the survey and will be brought back to the HRB for consideration at a later time in conjunction with that historical context. Property types are similar to those noted in the East Village Survey.

C. Over 45s Survey


In preparation for the Community Plan Update process, CCDC mounted an effort to evaluate all properties over 45 years of age in East Village that were not previously surveyed (Appendix A, Map 2). This resulted in an initial list of 152 properties that were evaluated by a committee of stakeholders including CCDC staff and consultants, HRB staff and consultants, Save Our Heritage Organization (SOHO), the Black Historical Society, the Chinese Historical Society and downtown residents and property owners. Through group consensus, the preliminary list was reduced to 61 properties that were formally evaluated by CCDC consultants, Marie Lia and Associates.

The consultant findings concluded that six of the 61 properties meet HRB Criterion C for local designation and 54 properties were recommended for clearance by HRB staff. Upon reviewing the submitted material and conducting field reviews, HRB staff determined that 14 properties appear eligible for local designation under HRB Criterion C for architecture. Of that number, eight are mid-twentieth century commercial properties and six are Victorian or Craftsman vernacular residences. An additional five properties contribute to proposed districts in East Village. Two contribute to the proposed African American Thematic District and three contribute to the proposed Warehouse District. These five properties have been removed from the survey and will be brought back to the HRB at a later time within the appropriate historical context. The remaining 42 properties had no potential for historical or architectural significance, primarily because of irreversible alterations, and were cleared by staff from further review.





Photo 2. Market at 18th & 19th looking West 1887



6th & Market looking SW c. 1885 Photo 3.




Photo 4.

10th & K looking NW

1890s

II. EAST VILLAGE HISTORICAL OVERVIEW (Scott Moomjian)

The history of the Bayside and Centre City East areas are inexorably linked to the development of downtown San Diego and its founder Alonzo Erastus Horton. Horton, who came to San Diego in 1867, purchased 960 acres of land for \$265.00 for his "New Town" San Diego development. Horton divided the acres into blocks and lots, a number of which were present in the Bayside and Centre City East areas. Thus, "Horton's Addition" was established. Later subdivisions in the area include "Sherman's Addition," and "Remondino's Subdivision of Sherman's Addition."

During the 1860s and 1870s, the Bayside area, then known as "South San Diego," relied heavily upon the wharf established at the foot of Fifth Avenue. Prior to the establishment of Horton's wharf, a few warehouse structures were located along the bay, but none remain today. These early businesses transported stored grain, honey and other products. They also received incoming shipments of lumber, iron, ore, and other necessities from other parts of the nation. In 1869, McDonald's store (later known as the San Diego Lumber Company) was erected at Sixth Avenue and L Street. Lumber, floated down the bay from Northern California and Oregon was pulled from the bay by Native Americans and stacked at the lumber company building, which was erected on redwood planks in order to protect the wood from muddy soil. In 1872, Bailey's Foundry (later known as San Diego Foundry) was constructed at the corner of 8th Avenue and M Street (now Imperial). This business provided much of the structural ironwork for businesses and commercial buildings in the Gaslamp Quarter (Lia/Brandes 1988:1; Lia/Brandes 1989:1; Lia 1999:1).

During the 1880s, New Town San Diego businesses spread north to H Street (currently Market Street), which was at the time considered the main cross road. Commercial growth was centered around Fifth Avenue and Market Street. Ultimately, San Diego expanded to D Street (currently Broadway) and beyond as merchants moved northward. With the coming of the railroad, Horton and other prominent business leaders lobbied for a railroad link which would facilitate transportation to this area. In 1885, the California Southern Railroad, a subsidiary of the Atchison, Topeka, and Sante Fe line, established tracks into San Diego from the north. This line greatly increased San Diego's population in the late 1880s. A later link with the Southern Pacific Railroad along the United State/Mexico border proved beneficial as well, particularly to the Bayside and Centre City East areas (Lia/Brandes 1988:1; Lia/Brandes 1989:1-2; Lia 1999:2) San Diegans, however, longed for an eastern railroad terminus.

With the 1885 railroad connection, an influx of newcomers to the San Diego area sparked a four-year building boom. In the Bayside and Centre City East area, simple Victorian single-family cottages were erected on 16th and 17th Avenues to accommodate laborers, porters, clerks, and other blue collar workers (Photo 1). The Rood Rental cottage, Bay View Hotel, Sheldon House and Joseph Ireland Building are examples of Victorian structures built during the boom. Standard iron works erected its manufacturing business on the corner of 7th Avenue and L Street, and the Silver Gate Warehouse, owned by local entrepreneur John Ginty, was constructed on 8th Avenue and M Street (later Imperial) (Lia/Brandes 1989:2; Lia 1999:2).

In 1886, the San Diego Gas Company enlarged its gas operations. The company, which had started from modest beginnings on 9th Avenue between M and N Streets (Imperial and

Commercial) in 1881, expanded in order to supply the needs of San Diego's growing residential and business community. The San Diego Gas Company built a new electric generating plant at 10th Avenue and M (Imperial) adjacent to the old gas plant. In 1887, the San Diego Gas and Electric Light Company was incorporated as the successor to the San Diego Gas Company and began supplying electricity for arc lights on a sundown to midnight basis in downtown San Diego (Photo 2). After the bust of 1889, the gas and electric company found it could easily service the utility needs of San Diego with existing equipment. Therefore, no new major additions were made to the plant until 1905 (Lia/Brandes 1989:2; Lia 1999: 2).

After 1900, businesses chose the Centre City East area from which to conduct operations due to the area's proximity to the railroad tracks and the wharf. San Diego's commercial center continued to expand as harbor facilities and the city's population grew. All types of commercial structures were built south of Broadway and along the water's edge (Photo 3). Warehouses, manufacturing centers, bars, restaurants, laundries, and hotels all provided services and goods for city residents and businesses. The entire area south of Broadway from the water to the east was a large commercial center for the city (Crawford 1996:6; Lia 1992:2) (Photo 4).

Businesses anticipated the creation of a much needed railroad line that would link San Diego to Arizona and then eastward across the southern part of the United States. It was believed that such a line would encourage the exchange of goods between the West and East Coasts of the United States through Yuma. In 1905, the Southern Pacific Railroad desired to break the Sante Fe Railroad's monopoly. Southern Pacific Railroad officials approached sugar magnate and San Diego businessman, John D, Spreckels to act as the "front man" for an operation that would build the railroad from San Diego to Arizona. Although the San Diego and Eastern Arizona Railroad would not be completed until 1919, railroad line and commercial advantage speculation drew local businessmen to the Centre City East area (Lia/Brandes 1988:2; Lia/Brandes 1989:3; Lia 1999:2).

By 1906, three piers had been constructed in the Centre City East area. One was located at the foot of 6th Avenue, called the San Diego Lumber pier, one at the foot of 7th Avenue called the Sheldon pier, and one at the foot of 9th Avenue called the Bailey Pier. These piers, connected to various railroad spurs, enabled warehouses and commercial enterprises in the vicinity to receive goods from other parts of the nation and world. The railroad spurs themselves extended onto the piers, and goods were unloaded from ships, put on waiting boxcars, and taken directly to businesses, or put on one of the major railroad lines out of San Diego (Lia/Brandes 1988:2; Lia/Brandes 1989:3; Lia 1999:3).

Local companies took advantage of spur line use during the first three decades of the twentieth century. In 1909, the Western Metal Supply Company, located at 215 7th Avenue was constructed. Designed as an up-to-date modern building by Chicago architect Henry Lord Gay, the company produced "everything in iron and steel from carpet tracks to structural beams." Between 1910-1911, the Schiefer & Sons Warehouse was built on 8th Avenue. In 1911, the Simon-Levi Company building was erected at 7th Avenue and J Street in order to serve the wholesale grocery business. In 1912, development reached J Street. The Julian Produce Company, the Hotel Salem (formerly identified as Loring stationers), and the Enid Apartments were all constructed in that same year. In 1913, the Nason and Company building was

constructed in order to house the commission and wholesale produce enterprise. During this same year, the impressive Simon Levi Company Building was constructed on J Street, as were the Broderick Apartments. Finally, in 1922, the San Diego Ice and Cold Storage Company took over the Silver Gate Warehouse, located at 800-822 Imperial Avenue and established "one of the finest plants in the city." The company claimed that it was "located at the heart of the industrial district," and had "excellent shipping facilities afforded by spur tracks to the San Diego and Arizona and Sante Fe railroads as well as to the waterfront" (Lia/Brandes 1988:2; Lia/Brandes 1989:3; Lia 1999:3).

During the 1920s, many San Diego businesses flourished in the Centre City East area. In 1921, the San Diego Broom Works Building was constructed on J Street. Three years later in 1924, the Showley Brothers Candy Factory was constructed at 305 8th Avenue. In 1926, the Ballinger Company warehouse was built at 944 K Street. In 1927, the Levi Wholesale Grocery Building was constructed at 330 8th Avenue, as was the Wheelworks Building on J Street. In 1928, the Qualitee Dairy commercial building was erected. Despite the fact that the Centre City East area of San Diego was affected by the Great Depression during the late 1920 and early 1930s, this area in general continued to benefit from new development. In 1930, the San Diego Gas & Electric Company constructed the San Diego Company Office Building on l0th Avenue. In some instances, however, businesses closed. Structures were left in a state of disrepair as some businesses migrated to locations north of Broadway (Lia/Brandes 1989:4; Lia 1995; Lia 1999:3).

The Second World War affected the Centre City East area as it did the entire country. A surge of activity occurred in the Centre City East area. Very few structures were constructed during the war years, and although little new construction took place during the early 1940s, many of the Centre City East buildings were drafted into service. The Schiefer & Sons factory, located at 371 8th Avenue, was used by the Standard Parachute Corporation from 1941-1945. Although no longer in existence, the Standard Parachute Corporation also used the building located at 304 11th Avenue as a supply stockroom from 1943-1948. In addition, the San Diego Machine Company, an airplane parts manufacturer, operated from 345 15th Avenue between 1934-1958. During the war years, the San Diego Gas and Electric Company had all new utility extensions put on hold, since copper wire and steel pipe were in short supply (Lia/Brandes 1988:4; Lia/Brandes 1989:4; Lia 1995; Lia 1999:4).

During and after the Second World War, as suburbs developed, many businesses relocated to newer communities where land was cheaper and buyers more plentiful. The amount of people residing in the Centre City area also declined, resulting in less local support of goods produced by the downtown businesses. From the late 1970s to the present, Centre City East has slowly become revitalized with the development of the Gaslamp Quarter, which has brought new businesses and life into the old industrial area. (Crawford 1996:6-7).

In 1999, portions of the Bayside and Centre City East areas were included in the cultural resources study prepared as part of the *Final Subsequent Environmental Impact Report to the Final Master Environmental Impact Report for the Centre City Redevelopment Project and Addressing the Centre City Community Plan and Related Documents for the proposed Ballpark and Ancillary Development Projects, and Associated Plan Amendments.* As a result of the 1999

study, one of the sites included in the original November 1988 Centre City East Survey were designated by the City of San Diego Historical Resources Board.




Photo 5.

6th & K looking East

1873




Photo 6. 9th & B looking Northeast 1870s

III. EAST VILLAGE HISTORICAL CONTEXTS

1. Residential Development Patterns

The purpose of this historic context is to recognize early residential patterns in San Diego's East Village area prior to 1930. Included in the study are single and multi-family residences in a variety of income brackets, including large, high-style Victorians, middle class Victorians and working class Victorian cottages. Modest Progressive Era duplexes and apartments, as well as high style hotels are also represented in the study, whose period of significance is roughly late 1870s to 1930. The context was developed by examining and comparing Sanborn Maps for East Village from 1887, 1888, 1906 and 1921 for residential development patterns over the 50 year period of the study. Where possible, maps were cross-referenced or augmented with historical photographs, published and archival materials noted in the bibliography.

A. Residential Patterns prior to 1887

The earliest Sanborn Map, dating to 1887 (Appendix A: Maps 4A & 4B), shows downtown commercial activity clustering along Fifth Avenue between D and I streets. The St. James Hotel at the northeast corner of Sixth Avenue and F Street is clearly the most prestigious short-term living experience in East Village. Seven smaller residential hotels, alternately described as "hotels, lodgings, or boarding" establishments, are scattered about the neighborhood, mostly within a block or two of the emerging Fifth Avenue commercial spine. The main exception is a clustering of modest lodging establishments around the intersection of 7th Avenue and K Street, presumably for people working in industries located around the harbor, like the lumber yard, gas works or grain and produce yards.

a) Property Type: Single Family Vernacular (Folk National Style)
Wooden single-family dwellings make up the majority of structures outside the Fifth Avenue commercial core and the industrial node around the Fifth Street wharf. The building footprints are boxy and of rather modest size, indicating that the buildings are utilitarian in nature with minimal architectural refinement. The buildings are widely scattered, with many platted but still undeveloped lots between them. Historic photos testify to the frontier nature of the city prior to the coming of the railroad (Photo 5). The primary building material, wood, was shipped down the coast in great lumber rafts and milled locally at San Diego lumberyards. Although mass production methods identified with the Industrial Revolution was resulting in fancy band saw Gothic Revival trim, Victorian cutwork shingles, or Eastlake-influenced lathe-turned posts in more prosperous parts of the globe, this architectural embellishment not highly evident in this first wave of San Diego building.

The most common façade treatment for commercial lodgings, characteristic of most Western frontier towns, is a flat parapet false front extending above the roofline (Photo 6). The façade extension functioned as billboard space for painted lettering to identify the business located within. A shed-roof extension supported on simple square posts shelters the front of these buildings, often covering a raised board sidewalk. None of these buildings exist today.

For single family dwellings, a simple front gable faces the street, either as a latent nod to the Greek Revival or purely a utilitarian gesture to shed rain (Photo 7). A variation on this form is the front gable with perpendicular side wing, where the wing often sports a full or partial porch covered by a shed roof. Over time and as dictated by necessity, these simple houses incrementally added single story extensions off the rear elevation for ancillary functions. Medium pitched front or side gabled roofs, or hipped roofs with shallow open eaves are characteristic of these modest one and two story dwellings, while flat roofs predominate on the commercial blocks. Vertical double-hung windows prevailed, featuring one-over-one, four-over-four or six-over six light panes.

Earlier milling favored wide boards (approximately 6 inches) with deeply grooved one-inch channels on the upper horizontal edge that locked into the board above it with a tongue and groove or rabbeted edge. When the upper part of the board had a concave curve, this treatment was known as "rustic" or "German" siding. Alternatively, board and batten siding, popular with Gothic Revival vernacular, was used. This treatment consisted of long vertical boards whose seams were covered by thin wooden strips known as battens. Horizontal shiplap siding, where the top and bottom edges were joined by a close fitting rabbeted or lapped joint, was also used.

Vernacular houses influenced by the Greek Revival feature raked molding with eave returns, corner boards and flat or pedimented cornice molding over the windows (H. T. Christian House, 1872), while Gothic Revival influenced vernacular sported cutwork vergeboards and simple spindlework porches (W. R. Norris Speculative House #3, 1872-1887). Italianate-influenced vernacular was distinguished by brackets at the eaves, windows and door trim (Edmund Wescott House, 1881; Norris House, 1880-1890). The Judson Property (c. 1900) is either a late example of the simple 1870s vernacular house, or it is mis-dated due to inadequate records.

This a-stylistic residential vernacular continued in San Diego for very simple, small workers cottages through the turn of the century, with the main differences between periods coming in siding and window treatments. Residential vernacular prior to 1887 is extremely rare in San Diego and its integrity can be expected to be fair to poor, as explained below. Prior to the railroad, the town was small with little economic activity. Although a building boomlet occurred between 1869-1873 associated with platting of New Town and Sherman's Addition, it soon fizzled and almost nothing remains from that period today. Local lumber was scarce and imported wood was valuable, so wooden buildings were moved, recycled and recombined into other buildings. Many burned or succumbed to dry rot, termites and other types of wood deterioration. Because of their humble construction and utilitarian value, wooden vernacular buildings were not considered "architecture," so a once common property type that characterized East Village's foundation vanished with little fanfare.

B. Residential Patterns in 1888

By the late 1880s, the railroad had greatly influenced the city's physical expansion and prosperity. The 1888 Sanborn (Appendix A: Maps 5A & 5B) shows development in East Village extending from 13th Street to 17th Street, with infill beginning in the westernmost lots platted as part of Sherman Heights in 1869. Out of approximately 120 blocks in the study area, only four have no development. Dwellings continue to be of modest scale and simple profile, particularly



Photo 7.

1870s Cottages




Photo 8.

1880s Victorian Cottage

below I Street, where blocks H 136 and H 149 feature a number of tiny cottages on single lots. Duplexes also begin to make an appearance. This was often an opportunity for middle class individuals to invest in real estate by living in one unit of the duplex, while renting the other.

Opportunities for boarders proliferate, especially in the four blocks adjacent to the intersection of 7th and K Streets, where a number of rooming houses were located. The city's population spurt is also reflected in the densifying commercial node along Fifth Avenue. Ten hotels now cluster within a block of this commercial spine, while rooms for rent occupy second and third floor spaces in many business blocks. Buildings identified as apartments now cluster along 7th Street, interspersed with hotels, while boarding and rooming houses continue to intermingle with single-family dwellings and the new duplexes east of the commercial area. Representative of this type of housing arrangement are The Tourist (1881) and the Joseph Ireland Building (1888), both mixed-use buildings with commercial space on the ground floor and rooming accommodations above.

a) Property Type: Single Family Folk Victorian Cottages

With prosperity, architectural styles become more elaborate. The popular Queen Anne Revival and Eastlake Victorian styles join the earlier Italianate trend, with the Gothic and Greek Revival styles waning in popularity. These High Victorian styles feature asymmetrical massing with turrets, bay windows and corner-wrapping porches, as well as elaborate cutwork shingles and spindlework porches. Two buildings in the East Village Study area, the Bay View Hotel (1889) and the Sheldon House (1886) are exemplary representatives of High Style Queen Anne Victorian.

Folk Victorian cottages retain the simple massing of the earlier vernacular houses, but add Victorian details, particularly in the gable, porch and window treatments (Photo 8). This is due to modest budgets and narrow city lots that reduced the desired picturesque massing of high style examples to the more visible street frontage. The Norris Rental (1887), for example, features asymmetrical massing, scalloped shingles in the gable end, and coupled one-over-one windows, while the Porter Long House (1894) and Rood Rental (1887) sport the characteristic three-sided bay with elongated sash windows. Spindlework porches are increasingly rare in San Diego, as many have been lost due to weathering and time. Fortunately, several properties in the study area still retain their ornate turned porch posts, if not the associated cutwork bracketing, spindlework friezes and ladder railings. These include the Morse House (1887), the Porter Long House (1894) the residence at 1321 C Street (1887) and the Olsen House (1890).

Once the predominant cultural landscape in East Village, Folk Victorian cottages are now rare due to land use conversion associated with economic development. They are significant because they represent the typical accommodations of laborers whose economic contributions to San Diego's industrial base have been historically overlooked. Their expected integrity can be anywhere from good, if recently rehabilitated to poor, if neglected by time and deferred maintenance.

b) Property Type: Pyramidal Roof Cottage

The pyramidal hipped roof vernacular house has a very long life in America. In San Diego, they appear in the earliest photos as simple wooden cubes with pyramidal roofs. By the late 1880s, the

roof hip has been truncated and accented with ornamental ironwork, while turned porch posts, cutwork brackets, scalloped shingle siding and other modest Victoriana embellish the main façade. Examples in the study area include the Padilla House (1870s), Smith House (1887), the Olsen House (1890) and the Norris Speculative House #2 (1900). In the study area, these cottages are rare due to extreme loss of a once common property type. Their expected integrity is good to fair.

c) Property Type: Second Empire Houses

Two houses in the East Village Study area are rare representatives of a residential building style not common to San Diego. The Wright House (1882) and the Thomas House (1889) sport mansard roofs characteristic of the French Second Empire Style popularized during the reign of Napoleon III (1852-70). It was used extensively in American public buildings during the administration of Ulysses S. Grant (1869-1877), and found favor among the Gilded Era Nouveau Riche once architect Richard Morris Hunt returned from his studies at the Ecole des Beaux Arts in Paris and set up a fashionable practice in New York. The Wright House is a hybrid Italianate Victorian with a mansard roof over the porch, while the Thomas House is a rather late and very modest example of the Second Empire Style that was at its height in the 1870s and early 1880s. Its appearance in 1889 testifies as to how long it took fashion to arrive from Paris to the San Diego middle class. It is rare in San Diego.

d) Property Type: Dutch Colonial Revival House

The Johnson House, constructed somewhere between 1888-1906, is another example of a rare style in San Diego, the Dutch Colonial Revival. Originating in the Dutch Colonies along the Hudson River in New York, the Dutch Colonial style represents the brief period of Dutch exploration in the New World (1614-1664) prior to the arrival of the English. Because the English permitted feudal Dutch landholders, some of whom controlled large tracts along the Hudson, to retain their property, building traditions practiced by Dutch immigrants continued in the area through the early 19th century. The distinctive gambrel roof exhibited at the Johnson House originated around 1750. The main entrance of gambrel-roofed houses was centrally located on the long wall of the house. Although brick and stone were commonly used in the Hudson Valley, timber houses with double hung sash windows were more common on western Long Island. Also characteristic of the Dutch Colonial Style is divided door, developed to keep livestock out of the house while allowing in light and air.

The Dutch Colonial Revival is part of a larger American Colonial Revival movement that began in the 1880s and has continued to the present day. The revival began in the northeastern part of the country and eventually spread nationwide through the influence of architectural pattern books, mail order catalogues and popular literature. Although an early design for what would later become known as "Dutch Colonial" was published in *MacLagan's Suburban Homes* in 1898, it was East Coast architect Aymar Embry II, who is generally credited with popularizing the Dutch Colonial Revival Style. Embry designed several Dutch inspired houses beginning around 1905 and published a book entitled *The Dutch Colonial House* in 1913. Nonetheless, gambrel roofs were cheerfully mixed in with other stylistic elements by popular/commercial designers during the 1890s because of their picturesque qualities. It was not until the 1920s and 1930s that more "correct" Dutch Colonial Revival made its way into American residential design.

The Johnson House is most probably a representative of the earlier "picturesque" phase of the Dutch colonial Revival. Although its exact date is uncertain and a rather large front extension obscures its main façade, it is a very rare example of an unusual style, particularly for the West Coast.

C. Residential Patterns in 1906

The turn-of-the-century period is characterized by homeownership expanding to the working classes. Live-in servants were becoming less prevalent (especially for the middle class) and housing styles in general were simplifying under Progressive ideals of good government through universal suffrage and political reform. During this period, it was widely thought that many urban ills brought on by industrialization and unbridled capitalism could be resolved through elevating the lower classes into the middle class through home ownership. As a result, an unprecedented attention was given to housing design, production, and financing instruments.

In San Diego, the 1906 Sanborn Map (Appendix A: Maps 6A & 6B) reflects these wider national trends, as well as local economic recovery and continued urban expansion due to railroad-related in-migration. Population growth is evident in residential patterns that clearly reflect denser living conditions more characteristic of cities than of towns or villages. Hotels and boarding establishments have a diminished presence in East Village, while apartments or rooms-to- rent are now dispersed throughout the expanded business district between Fourth and Seventh Avenues. Many of these residential arrangements are located on the second or third floors of business blocks, strengthening the trend noticed on the 1888 Sanborn Map.

While single family residential development has spread eastward to 19th Street, representing incipient development in Sherman Heights, several blocks of sparsely developed land remain between 16th and 18th Streets. Conversely, many single family residences between 8th Street and 12th Street have been converted to multi-family accommodations, indicating an interest in living quarters within walking distance to the business center of the city. Less change is obvious south of I Street, where modest cottages continue to fill in previously platted parcels. The node of boarding houses at 7th and K, however, is no longer evident, reflecting both the eastward spread of the warehouse district and the rise of modest living arrangements elsewhere in the city.

a) Property Type: The Foursquare

By the turn-of-the century, the pyramidal hipped house is once again fashionable. The simplest examples are associated with a wildly popular residential building type know as the Foursquare, which was prized for evoking "massiveness and strength." Spread nationwide by pattern books and mail order catalogues, the Foursquare is characterized by a centrally-located front door, flanked by symmetrical window arrangements on both upper and lower floors. A full or partial porch, supported on columns or square posts is attached to the first floor. In San Diego, Transitional (Late Victorian/Colonial Revival details), Craftsman and Prairie style elements embellish typical Foursquare massing during the decades flanking 1900.

Because this is a major period of growth for the city, there is a good representation of this of the housing type in neighborhoods adjacent to East Village, like Sherman Heights, Golden Hill, South Park, North Park and Uptown. Integrity in most cases is excellent to fair, depending upon

regular maintenance practices and appropriate rehabilitation techniques. Within the East Village study area, both simple one-story cottages and two-storey single-family dwellings in Transitional styles (moving from Victorian to Craftsman) are found. They feature regular massing captured within a square footprint and pyramidal roof, but retain controlled asymmetry in details like bay windows. Window styles and rhythms also shift from paired tall and narrow sashes to triplets with a large, fixed center panes flanked by narrower sashes and wide, flat window trim. Classical details like dentil moldings and columns also pay homage to the Classical Revival popularized by the 1893 Columbian Exposition in Chicago. The Hiatt House (1902), Kreiss/Wilcox House (1906), Lee House (1908), and Smythe House (1908) are good representative examples of these trends.

D. Residential Patterns, 1921-1956

By 1921, residential patterns noted in 1906 have matured and taken hold across the East Village study area (Appendix A: Maps 7A & 7B). Residential quarters have been universally eliminated from the business core, now solidly covering 4th through 7th Avenues. Five hotels accommodate short-term visitors, many now arriving in San Diego by automobile to enjoy the area's sunny climate and sandy beaches. Below Market Street, warehouse/industrial uses have expanded eastwards to 15th Street, mainly on vacant land south of L Street. Although modest worker housing remains throughout the study area, commercial and industrial buildings are beginning to encroach on the earlier residential nature of the area.

By 1956 (Appendix A: Maps 8A & 8B), residential uses have been all but eliminated by the expanding commercial and industrial sectors. This wholesale land use conversion was aided by the city's zoning regulations and the aggressive accommodation of the automobile. Auto-related businesses and infrastructure, especially parking lots, consume substantial amounts of land once occupied by dwellings. Construction of the I-5 Freeway eliminated the remaining modest cottages on 18th and 19th Streets, and severed East Village's ties to Sherman Heights. Today, only a small vestige of the area's former residential character remains along 17th Street.

During the first decades of the twentieth century, a new property type, the apartment or apartment-hotel, enters San Diego. This mode of upscale communal living had a rich history in other parts of America prior to its appearance in Southern California. In general, as cities became more crowded and land values increased, housing options other than single family residences were necessary. To investors and speculators alike, apartment construction became increasingly attractive as a real estate investment, particularly in fast-growing areas. Its appearance in mid-19th century urban America responded to the housing needs of both ends of the economic spectrum—the poor and the affluent. To find affordable housing, middle class residents moved to the suburbs where land values were substantially lower. New transportation systems like horse cars, trolleys, and later the automobile, enabled middle class mobility. The rich and the poor, however, coped with rising land values by pooling their resources and modifying their housing preferences.

Much maligned substandard housing, known as tenements, accommodated those of limited means, while apartment living became the glamorous option of choice among society's well-to-do. By the 1870s, the convenience and advanced domestic technology of apartment living fueled

their rising popularity. World War I brought on social changes that lead to the greater independence of women and increased personal mobility, while technological advances in the first part of the 20th century revolutionized domestic life. Although the American dream of home ownership remained, the stigma of apartment living waned, particularly for middle class bachelors of both sexes, who found the apartment an acceptable, and hopefully temporary, solution. As a result, and with financing available at 70-90% in the 1920s, these strains blended together to open the door to a boom in apartment living that continues today. In sum, scarcity of land, economic opportunity and social changes all contributed to shifting housing preferences. A more detailed discussion of the history of both the tenement and the apartment in America follows. Much of this material was taken directly from the National Register Nomination for the East Portland, Oregon Middle Class Apartment Building Thematic Historic District cited in the Bibliography.

a) Property Type: The Tenement

Those on the lower end of the economic scale found traditional single-family housing unaffordable. In the 1830s, to accommodate the masses in this unregulated marketplace, landlords first built "double tenements." These were buildings 3-4 stories high with two families on each floor; a second building was then squeezed into the backyard, also 3-4 stories tall but with only one family per floor. Typically, these had a living room, a kitchen and two bedrooms and offered only a minimum of space, light and ventilation. Access to each room was via the central stairwell or by passing through the other rooms of the apartment. The average tenement in New York or Boston contained 65 people.

In the 1850s, landlords improved on the profitability of "double tenements" with the "railroad tenement." These were larger and more crowded. The railroad tenement was a 90-foot long solid rectangular block that left only a narrow alley in the back of the building. Of the 12-16 rooms per floor, only those facing the street or alley received direct light or air. There were no hallways, so people had to walk through every room to cross an apartment and privacy proved difficult. The open sewers outside that were usually clogged and overflowing, a single privy at best in the backyard, garbage that went uncollected, and mud and dust in alleys and streets made these environments unpleasant and unsanitary.

Recurring outbreaks of yellow fever, cholera, smallpox, typhoid and typhus, and their association with grossly unsatisfactory living conditions, alerted concerns for public health and housing reform. Accentuating the concern was the potential for the spread of these diseases to the upper and middle classes through the handmade products manufactured in the tenements. These included cigars, garters, paper flowers, boxes and other small items. *Harper's, Atlantic, Arena, Municipal Affairs, Scribners*, building trade journals and professional architectural and social work publications, as well as newspapers, all took up the issue of tenement housing and sanitation in the 1870s. The ideal solution was the promotion of inexpensive cottages in the suburbs, accessible through trolleys. Financial realities, however, precluded single-family housing for many, and so architects and planners sought new design options for apartment living.

Several professional journals and magazines sponsored competitions for alternative tenement designs. In 1879, *New York Plumber and Sanitary Engineer* announced what would be the most significant of these competitions. The editors specified that the tenement should yield the highest

economic return, while providing fireproofing, ventilation and sanitation. James E. Ware, Jr. designed the winning entry, immediately labeled the "dumbbell" because it had two narrow airshafts within a solid rectangular block. The *New York Times, American Architect* and others all criticized the solution as unsound, unhealthy and cruel. Yet, because of its high economic return, the "dumbbell" became an immediate success among speculative buildings and the prevailing model for new tenement construction.

The typical dumbbell tenement was twenty-five feet wide and ninety feet deep. Indentations 28 inches wide and 50-60 feet long broke the solid block. Entirely closed on all four sides and rising the full height of the building, these airshafts seldom met their stated purposes of providing air and light to inside rooms. Tenants on the upper floors often threw their garbage down into the shafts, where it was left to rot. The first floor usually contained two small shops, with bedrooms behind them and another apartment in the rear. On the other floors, there were two 4-room apartments in front and two 3-room apartments in the rear. The public hallway, usually unlit, contained the stairs and one or two toilets per floor. In New York, in 1893, over 800,000 people lived in these buildings.

b) Property Type: Apartments by Choice

At the other end of the economic spectrum were those who chose to live in apartments. In the United States, this chosen alternative to single-family housing dates to the last half of the 19th century. The first building designed as an apartment house appeared in Boston in 1855, designed by Arthur Gilman. It offered permanent residences for families and bachelors. The real beginning of the movement came, however, in 1869 when Richard Morris Hunt designed the Stuyvesant on Irving Place in New York. The 5-story building offered 6-10 room suites on the lower floors for a rent of \$1200-1800 per year, while the top floor studio apartments rented for \$920 per year.

Hunt imported the concept from France. It also came as a direct response to increased land cost that resulted from population density. Building a multi-family building allowed developers to make more money. A month before Hunt completed construction, the Stuyvesant was besieged with 200 applications. The building, which cost \$150,000 to build, brought in a profit of \$23,000 in the first year. The message to investors was clear. Returns of 10-30% stimulated investors. In New York alone nearly 200 sets of "French flats" were erected between 1869 and 1876. In Chicago, following the 1871 fire, 1,142 apartment buildings went up in a single year.

The notion of apartment living was sold on the basis of efficiency and unheard-of technological advances: the entrances and public spaces were sumptuous. Marble floors and paneling, crystal chandeliers, imported carpets, and walnut or mahogany wainscoting adorned public doorways, lobbies, staircases and elevator carriages. There were central hot-water heating, central gas mains for lighting and fully equipped bathrooms for each unit. Shortly thereafter, apartment buildings featured steam elevators with uniformed operators. Bathrooms became more elaborate with hot and cold running water, hand painted china basins, and hand carved shower stall screens. Architects experimented with electric generators, later connecting the buildings to the streetcar electric service, and installed central vacuum cleaning systems with nozzles in each room connected to a large pump in the basement; individual attachments could be used as hair dryers or reversed as dust collectors. To increase light and ventilation, subsequent designs grouped

apartments around a central courtyard with central corridors. The emphasis on efficiency resulted in some apartments separating the heat and discomfort of cooking and laundry from the living quarters with public dining rooms, kitchens and laundries. Some provided servants for serving meals and cleaning clothes. The cooperative services, technological advances and attention to public spaces made the apartment seem like one of the most advanced institutions in American society.

To the vast majority of Americans, any kind of shared dwelling seemed an aberration of the model home. It was felt that close proximity and shared facilities encouraged promiscuity. Because the proximity of the bedroom to the public spaces in each apartment was particularly worrisome, several architects experimented with interior staircases for two-floor units; but, the expense made it economically wiser to keep all the rooms on one floor. Many believed the reduction of housekeeping chores brought on by the efficiency of the apartment would lead to wifely negligence of duties toward home and children. Finally, for many Americans, the imitation of decadent European living patterns did not seem fitting for good American families.

Well into the twentieth century, the middle class attacks on apartments as inadequate homes continued. *The Ladies Home Journal* issued dire warnings of Bolshevik influence over American women exerted through the increasing number of apartments. *Better Homes in America* captured the sense of alarm when it reported to the 1921 National Conference on Housing that a child's sense of individuality, moral character, and intellectual efficiency could only develop in a private, detached dwelling. The apartment was blamed for the rising divorce rate, the declining birth rate, premarital sex, and the social and economic disparities between rich and poor.

As San Diego was settled primarily in the late 19th and twentieth centuries, it did not experience rapid growth until the first decade of the twentieth century. It wasn't until preparations for the 1915 Panama Pacific Exhibition began that the city's population created a market for apartments. Both individuals coming to work on the Exposition and visitors to the Exposition needed temporary accommodations, and the local housing market responded to the increased demand. Nonetheless, most of San Diego's early apartment buildings were fairly small—few rising to over two or three stories. Simple wood-frame buildings with anywhere from six to twelve units were the norm. By the 1920s, many so-called "apartments" or "apartment-flats" were really converted single-family residences, with few special modifications to accommodate increased densities. Truly, apartment living in San Diego was a "cottage" industry, with many apartments resembling oversized single-family houses. Even the larger buildings (20-50 units) were rather unspectacular in appearance, indicating their builder/contractor origin, rather than an architectural pedigree. Within the East Village Survey Area, the Hamilton Apartments (1886, 1907), Carper Apartments (1913), Menke Family Apartments (1915) and Norris Cluster Apartments (1913) are characteristic of this local trend. Downtown San Diego was once home to hundreds of these small scale apartments, but most have either been demolished or altered, including several in the current survey. Consequently, expected integrity in remaining examples ranges from good to poor. Like the once-plentiful single-family residences in East Village, the modest scale apartment house has experienced severe attrition.

For more substantial buildings, the terms "apartment" and "apartment-hotel" are regularly interchanged throughout this period. These terms indicated a more refined living experience,

with better-appointed private living quarters and shared amenities for residents and their guests. Because of their technological complexity and the gradual adoption of stricter building codes for multi-family construction, architects or engineers were often engaged in these larger buildings. With professional involvement, these buildings more closely mirrored popular architectural trends of the day than the smaller builder/contractor versions.

A good assortment of 1920s and 1930s apartment buildings adjacent to Balboa Park reflect the Spanish/Mediterranean and Art Deco/Moderne styles of those decades. Concentrated on Sixth Avenue and on Park Avenue, many were built for visitors to the 1915 Exposition who decided to relocate to San Diego as a result of their travel experience. Because land next to the park was very desirable, the economic conditions favorable to apartment building prevailed. Another San Diego location for upscale apartment buildings was Cortez Hill, where good ocean views and proximity to downtown created optimum economic conditions for multi-family housing.

In the Centre City Core Area Survey, the recently designated Francis Apartments (1909), Carnegie Apartments (1912) and Amelia Apartments (1911) are good examples of this property type. In the East Village area, the Italianate Style St. Anthony Apartment/ Hotel (1912) demonstrates the growing luxury afforded this emerging local lifestyle. The St. Anthony featured "amusement rooms, a sun parlor, steam heart, a ballroom and 'the latest improvements and furnishings including private baths and telephones in all apartments." Even more refined versions of the property type, including the Biltmore Apartments (1925) and the Munson Apartments (1929) are constructed in East Village during the later 1920s. Expected integrity for these architect-designed properties ranges from excellent to fair.

By the 1920s, tenements and boarding houses in East Village were waning. Very few tenements ever existed in the East Village area of San Diego, and boarding houses, although plentiful in earlier days, were decidedly dwindling by the 1920s. In most other urban areas, tenements were reserved for recent immigrant populations, especially extended families. San Diego's immigration was of a different, mostly Nativist middle class, nature. Many new residents arrived as individuals, without families in tow. They were accommodated in the numerous boarding and rooming establishments where meals were provided. Many families coming to San Diego were second or third generation Americans who originally lived in the Mid-West, or were retirees looking for sunshine in their sunset years. They could afford more upscale temporary accommodations provided by apartment hotels while searching for a new suburban home.

Even working class families could reside in very modest single family cottages, often stacked five or six to an urban lot, or tucked behind a primary dwelling at the lot's rear, rather than resort to tenement living. Although San Diego's abundant supply of vacant land facilitated affordable rental housing for working class families, recent research associated with both the Asian-Pacific and African American Thematic Historic Districts suggests that people of color had more limited housing options, especially during the period of segregation (1920-1950), when many African-American establishments were clustered around Front and F Streets. Specific East Village residential hotels like the Brighton, Carter/Vine, Clermont/Coast, Grant and Latonia were reserved for these immigrant populations through discriminatory regulations. Additional information on these properties will be available in the forthcoming *Downtown San Diego*

African American Heritage Study. In the survey area, the Workman Hotel (1912) is a good representative example of the working class multi-family property type from this period.

c) Property Type: The Bungalow

By the 1900s and well into the 1920s, one option for affordable middle class housing was the bungalow, a small single-family detached house with an emphasis on austere simplicity to promote efficiency and cleanliness. The bungalow was an expression of "democratic architecture" which meant good homes available to all Americans through economy of construction and materials. As expressed by Gustav Stickley, this approach to design could remedy almost every problem facing the middle class family, from lack of servants to the increased divorce rate. By creating a healthy home environment, it also addressed larger social issues such as crime, disease and civil disorder. This perspective was echoed by the *Ladies Home Journal*, with a circulation of 2 million.

The bungalow generally referred to a relatively unpretentious small house. They were one or one and a half stories, between 600-800 sf. Bedrooms were little more than bunk spaces. The kitchen fitted like a ship's galley, accommodating one person. The family ate its meals in a large central area, a combined living/dining space. Rarely did houses have a single-purpose room, such as libraries, pantries, sewing rooms and spare bedrooms.

Condemning decoration and ornament as collectors of dust and dirt, proponents of the new style argued for austere simplicity. Eliminating unnecessary housework, uncluttered space, and smooth surfaces was preferred. Instead of cornices with crevices which had to be dusted, painted stencils began to adorn living rooms. Walls often simply received coats of smooth, white plaster. On the floor were mats, throw rags and a novel product called linoleum. Kitchen walls called for washable tiles or less expensive enameled sheet metal. Materials for walls, floors and ceilings were to be easy to clean and restful on the eyes.

Built-in conveniences abounded: Bookshelves and cabinets in the living room; fold-down tables, benches and ironing boards in the kitchen, medicine cabinets in the bathroom and more closets throughout the house. Venetian blinds replaced curtains in many houses. Rows of simple casement windows with small leaded panes eliminated the need for curtains at all.

These new and simpler bungalows did not necessarily cost less than the elaborate Victorian dwellings of a generation before. Interest in health and efficiency meant that a larger proportion of the construction costs—sometimes upwards to 25%—now went into household technology. After 1905, the bathroom was considered an essential part of the middle class house. At first, lead pipes were left partly exposed, partly from pride and partly from fear of trapped gases. By 1913, built-in bathtubs and sinks were on the market, making claw feet and visible pipes seem old-fashioned. The compact bathroom, its walls and fixtures gleaming white, became the mark of modernization.

The kitchen, too, was compact and carefully planned. It measured approximately 120 sf. One wall contained space for a Hoosier, with numerous wood drawers. New appliances stood center stage. The sink and drain board were of shiny white porcelain or enameled iron. An automatic

pump supplied hot and cold running water. A hood hung over the gas range to cut smells and cookware was intended to hang on the wall.

These changes in house architecture reflected changes in American lifestyle. The average number of children dropped to 3.5 by 1900, and many families only had one or two. Domestic production, such as quilts, home canning, and dowry linens, was disappearing. Formality was declining, with dining habits more relaxed. Family meals were less frequent and dinners had fewer courses. Entrance halls no longer served as a receiving area, while the parlor was viewed old-fashioned. With kindergarten and social groups such as Boy Scouts and Campfire Girls, the home also was no longer the center for training children.

Even with the reduced cost and size of the bungalow, for many, home ownership remained outside financial reality. In the 1920s, only 46% of all American families were homeowners. That figure was lower in metropolitan areas. An economic depression in 1921 aggravated the postwar housing shortage, limiting the number of new permits and increasing the price of housing that was being built. The average price of a new house rose from \$3,972 in 1921 to \$4,937 by 1928.

In San Diego, bungalows are very common throughout many of the communities neighboring the Centre City area. Their expected integrity varies, depending upon occupancy, use and maintenance practices. In the East Village Survey Area, several small bungalows are clustered along 16th and 17th Streets, where at one time they would have been part of Sherman Heights. Because of the transitional nature of this area, the integrity and condition of these properties varies. Only one bungalow, the J. W. and Mary Fultz House, located at 39 16th Street, has been proposed for potential designation by the HRB as a representative example of this property type in the survey area. This particular bungalow also happens to be located next to several other small Victorian cottages that have already been designated by the HRB for their contribution to the Sherman Heights cultural landscape.

d) Property Type: The Courtyard Apartment

The bungalow court and garden apartment, which appeared nationally in the 1910s, were additional efforts to provide decent, safe and sanitary housing. Developers promoted these apartment forms as modern living environments. They offered convenience, efficiency and simplicity of the bungalow to bachelors of both sexes, thereby freeing them from the constraints of domestic chores. In Southern California, working class families, retirees and artists were other demographic groups that enjoyed bungalow court living. With mortgages of 70-90% available in the 1920s, developers rushed to capture this multi-family market with an onslaught of new construction.

On the West Coast, one theory holds that courtyard housing originated in Pasadena during the first decade of the century by rather high-style architects, who designed the earliest bungalow courtyards to accommodate winter guests bored with hotel living. The grouping of "simple" free-standing cottages (complete with servants quarters!) about a common court allowed sophisticates to "rough it" in style. Built in 1909, St. Francis Court is considered the first bungalow court in the city of Pasadena. Its layout was possibly inspired by Eastern resort communities, where tourist cabins in the woods organized around a central courtyard provided a prototype. The

bungalows were furnished and equipped with "good furniture, oriental rugs, hangings, sliver, linen, kitchen utensils and such things." Rented either furnished or unfurnished, by the month, or by the year, these alternative tourist quarters included water, electricity and a gardener. Ultimately, one outcome for this mode of temporary housing was the motel. The successor to informal roadside auto camps, the motel modified the bungalow court design by converting the central common space to auto use. (Pasadena bungalow court architect Arthur S. Heineman registered the name "Mo-tel" with the Library of Congress in 1925.) The bungalow court flourished from 1910 through the 1930s, with construction virtually halting during the 1940s.

The tourist-oriented bungalow court concept rapidly spread to the common builder, who simplified, cheapened and proliferated it. The typology evolved during the first two decades of the twentieth century as a purely local response to climate, strong housing demand, an interest in indoor/outdoor living and a predilection for the free standing single family home. Originally, single-story units were informally grouped about a common open space. As the type evolved, the unique individuality of each unit became subsumed by the overall unity of the complex. Private living space and communal open space merged into a conceptual whole. As described in a 1912 article titled "New Idea in Apartments":

The "community court" idea, or plan, consists of taking two, and sometimes three or more city lots, each about 40 or 50 feet wide and from 120 to 150 feet deep, located reasonably close to the business part of the city, and constructing on the plot thus created a number of up-to-date and modernly equipped cottages, or bungalows, through the center of which runs a sort of park-way, or court. Such plots of ground will allow the building thereon of from eight to fifteen of these little individual homes.

Eventually these complexes separated space into public, semi- public and private areas in a rather predictable formula, with variations dependent upon lot size, shape and terrain. The Bungalow Court Significance Statement for the City of Pasadena identified seven typologies: A) Detached Wide Court (Enclosed) (e.g. U-shaped); B) Attached Wide Court (Enclosed) (eg. V-shaped); C) Attached Wide Court (Open); D) Detached Narrow Court (Enclosed); E) Detached Narrow Court (Open); F) Attached Narrow Court (Enclosed); and G) Half Court or "L" Shaped. As city building blocks, these urban fragments often ingeniously solved site-specific problems, such as parking and circulation, as well as more general urban design issues, such as contextualism and continuity of the streetscape.

In the sprawling, low-density metropolis of 1920's Los Angeles, the Mediterranean Revival courtyard *parti* achieved a richness particularly appropriate to Southern California. Many highly-trained architects using historically correct massing and motifs inspired by the masterpieces of Andalusia began working with the typology in earnest. Others added architectural detailing like a baker adds frosting to a cake. Tudor, French, Egyptian, Moorish, Chinese and Shingle styling interchangeably graced facades of the Los Angeles courtyard apartments. Hollywood's influence is also responsible for the more theatrical flights of fantasy present in many of these complexes. Ideally, architectural massing, exterior motifs and landscaping created an instant sense of place and history in this young city that was formed in a featureless desert at the ocean's edge. Oasis-

like in its cooling shade, peace, privacy and exotically lush landscaping, the courtyard apartment provided respite from the heat, bustle and impersonality of a growing city.

Like Los Angeles, San Diego also quickly adopted the bungalow court apartment as a preferred multi-family alternative to impersonal high-rise living. Offering a compromise between single family and multi family living arrangements, the courtyard apartment flourished in our sunny Mediterranean climate. Early suburban neighborhoods like Uptown and North Park feature many fine examples of this property type. Two courtyard apartment complexes featured within the East Village Survey Area are recommended for HRB designation. The Morse Courts from 1924 represents the Craftsman aesthetic, with several tiny bungalows regularly arranged on a lot with limited landscaping. In the Pasadena lexicon, they most closely resemble Type E, the Detached Narrow Court (Open) typology. The 1956 Sanborn Map for this property indicates that the site originally had nine units arranged in three rows of three, with the units fronting on Market Street. Although the widest spacing occurs between the two rows towards the rear of the lot, it is difficult to describe this space as a landscaped "common area" characteristic of bungalow courts. Both today and as originally configured, the property more closely resembles low cost worker cottages arranged on the lot for maximum rent return than a typical courtyard apartment, so the property's inclusion as a courtyard apartment is open to debate. Nonetheless, the property is a good example of the typical approach to low cost, free standing worker housing in East Village. The 1940 Saliba Auto Courts present a streamlined modern version that fans out around a common area. Here the layout approximates Pasadena Type B, the Attached Wide Court (Enclosed) typology. Both properties are typical modest working class examples of the courtyard apartment dwelling in East Village.

In conclusion, the wide variety of housing options exemplified in the East Village study area reflect the small city atmosphere of early San Diego, before later 20th century land use transitions and city-imposed zoning transformed the area into today's commercial and industrial core. They are left over remnants of a residential cultural landscape that reflect what the city once was and are therefore worthy of designation under HRB Criterion A. These properties are found in Table 1 and Appendix A: Map 9 (both forthcoming).

TABLE 1 GOES HERE (FORTHCOMING)

BACK SIDE OF PAGE WITH TABLE 1

2. Commercial & Industrial Development

The Industrial Revolution profoundly affected the shape of the city. Changing roles in employment created an expanded middle-class that no longer wanted to live within the confines of the city. Suburbanization followed suit. The expansion of the city was seen as a natural evolution. In 1929, Earnest Burgess compared the progression of the city to a biological organism growing by subdivision, becoming more complex and specialized. As the population grew, it was thought the natural place for development was at the periphery. Transportation systems, first railroads, horse cars and electric streetcars and later the automobile, allowed people to move further out while giving them the ability to continue their employment in the city. Rail lines stretched across the metropolitan landscape converging on the central city. They encouraged and reinforced the center's dominance over its hinterland and at the same time facilitated decentralization of certain land uses from the central city, particularly housing. They started a pattern of suburbanization that was enhanced with the advent of the automobile. While rail lines and automobile pushed into the suburbs, the central business district continued to dominate the industrial and consumer economies; however, speculators eager to cash in, realized that small stores constructed along transportation routes could serve the burgeoning residential market by selling convenience items while saving the suburbanite a trip downtown.

A. Taxpayer Blocks

The speculator's building type of choice was the one-part commercial block, or taxpayer block, as it was known in many parts of the country. Taxpayers were widespread in the early twentieth century urban landscape. Typically located along streetcar routes and later auto boulevards, they were inexpensive to construct and their flexible design allowed them to be built with little consideration for the ultimate tenant. It was assumed that more dense urban development would naturally spread from the urban core along major arterial streets, making the land much more valuable in the future. Taxpayers were seen as interim investments; owners wanting to hold a desirable piece of land, rather than leave the property vacant, built taxpayers to produce an income sufficient to pay the property taxes and sometimes to produce a small profit.

As a building type they are distinguished by their flexibility. Typically they are distinguished by a one-story row of storefronts lining the street, although a common variant includes an additional story housing offices or apartments. Designed as a shell, they are easily adapted to a wide variety of commercial uses. Their modular plan was vital to their success; essentially rectangular boxes, or bays, additional units could be appended in any number needed in order to take full advantage of a parcel. Most were built in two and three unit configurations, although they were frequently made up of six units, and in rare cases, as many as ten bays could make up a single building. As they were built on speculation and the ultimate tenants were unclear, the flexibility of design made finding tenants easier than a building designed for a specific occupant.

The system of street facing bays is essential to the form of a taxpayer block. The flexibility of the bay system allowed a single business to occupy multiple bays, or several businesses to occupy one section each. The interior could be reconfigured with little effort. On the exterior, each bay is filled with large display windows and, in most cases, a door in the center. Doors can also be situated to either side of a bay, leaving the remainder for an even larger display. In some cases,

when a business occupied multiple sections, a bay may not have a door at all. A solid kick plate is located below the windows, often covered with decorative tile. Transom windows are typically positioned above the door and display windows. On corner lots, the bay system often continues around the side of the building with a doorway located at the corner, set on a forty-five degree angle. Many times a canopy is added to shade the storefront and shelter patrons from the elements.

These utilitarian buildings were constructed of inexpensive materials, often wood-frame, brick or clay tile and sheathed in clapboards or stucco. Most have flat roofs sloping to the rear of the building. Ornamentation is infrequent and not limited to any particular architectural style. If decoration was applied, it is typically limited to tiles below display windows, or an ornamental parapet. Although attractive, parapets also function as the ideal location for a sign. In most cases, taxpayer blocks are humble; however, in certain circumstances, additional detailing may have been added. This is particularly true for those found downtown, as well as in more upscale suburban areas. In these cases, taxpayers are dressed-up with the addition of cast stone elements, ornamental ironwork, decorative window treatments such as leaded glass, patterned brick and decorative stuccowork.

Taxpayer blocks were once a common part of the San Diego commercial landscape, especially in the downtown area along streetcar lines and major arterials. Today only a handful of this property type remains. Those that do persist are expected to have had alterations within the bay systems. The series of pilasters that create the bay system, as well as the decorative elements above the bays, are the primary features of the property type and it is important that they are recognizable. The window and door system configuration within the bays are a less important feature. Seven taxpayer blocks were identified within the East Village survey areas that retain sufficient integrity and condition to be proposed for designation under HRB Criteria C as representatives of a distinctive type, period and method of construction (see Table 4). One taxpayer block (109-113 C Street, College Inn) identified in the Centre City Core survey is also included here. All eight examples retain the bay systems and their ornamentation, and some, like 801-921 F Street, still maintain most of the original window and door configuration within the bays. Others, like the MacMarr Grocery Store (705 6th Avenue), Schiller Book Bindery (760-770 11th Avenue) and College Inn (109-113 C Street) have had changes that have been found to be consistent with the Secretary of the Interior's Standards for Rehabilitation.

B. Auto-related Properties

The purpose of this historic context is to identify early commercial and industrial patterns associated with automobile in San Diego's East Village area prior to 1956. Included in the study are buildings used as auto maintenance and repair garages, storage garages, car painters, auto wreckers and car showrooms. The context was developed by examining and comparing Sanborn Maps for East Village from 1888, 1906, 1921 and 1956 for auto-related development patterns over the 70 year period of the study. Where possible, maps were cross-referenced or augmented with historical photographs, published and archival materials noted in the bibliography. Properties discussed in this section are listed in Table 2 and charted on Map 13 in Appendix A. They have been included in one or more East Village survey(s) in order to provide a robust picture of San Diego's adoption of the automobile and its impact on local commercial activities;

TABLE 2. East Village Combined Historical Surveys 2005 Criterion A: Auto-related Properties

Auto	1000 Sales (1000 S	Survey	Cleared By		Property (197		
No.				Street No.	Street Name	Property Name	Use
1	East Village	1	N	1531-1541	Broadway	J.F. McKnight Block	auto sales & service
2	East Village	14	N	1508-1544	E Street	Jerome's Furniture Store Buildings	auto sales & service
3	East Village	14	N :	934-940	16th Street	Jerome's Furniture Store Buildings	auto sales & service
4	East Village	16	N	741	F St	Maryland Hotel Garage	garage
5	East Village	46	N	660	10th Ave	Southern California Telephone Company Garage	garage
6	East Village	35	N	906-922	Market St	Federal Motor Truck Company	truck company
7	Over 45	N/A	Y	1635-1647	C St	Yates Tire Company Building	tires
8	Over 45	56	N	1015-1025	12th Avenue	Ford Apartments/ Ford Motor Building	auto sales & service
9	Over 45	N/A	Y	843	10th Ave	Tenth Street Garage	garage
10	Over 45	N/A	Y	751	7th Ave	H.J. Goodman Garage	garage
11	Over 45	N/A	Y	753	13th St	Auto Exhibit & Wrecking Company	auto wrecking company
12	Over 45	N/A	Y	731	9th Ave	United States Post Office Garage	garage
13	Over 45	N/A	Y	640	10th Ave	J.V. Caldwell Auto Repair Building	auto repair
14	Over 45	N/A	Y	410	10th Ave	Kidd & Krone Auto Painters Building	auto painting
15	Warehouse	N/A	N/A - DEMO	837	Market St	Lawton's Car Hop Restaurant	car hop restaurant
16	Warehouse	N/A	N	452	8th Ave	San Diego Auto & Carriage Works	auto & carriage co.; autopainting
17	Warehouse	N/A	N	415	14th St	San Diego Truck Company's Corral	truck company, corral, stables & garage
18	Warehouse	N/A	N	1205	J St	Auto Parts Warehouse	auto parts warehouse
19	Warehouse	N/A	N	340-344	7th Ave	Julian Warner Springs Trucking Line Depot	truck line depot
20	Warehouse	N/A	N	335	6th Ave	J.O. Hosman Garage/Marriott and Drummond Garage	garage
21	Warehouse	N/A	N/A - DEMO	301	10th Ave	Auto/Truck Paint & Metal Booth	auto repair & painting
22	Warehouse	N/A	N/A - DEMO	312	11th Ave	Desert Express, Inc Building	truck line depot
23	Warehouse	N/A	N/A - DEMO	304	11th Ave	Borderland Express/W.H. Gibson Express	Truck depot/express & garage

BACK SIDE OF TABLE 2

however, due to severely compromised integrity of this property type, only a handful of the properties mentioned in this section are actually recommended for potential designation.

The internal combustion engine automobile had a tremendous impact on American culture, the spatial organization of American cities and the shape of individual buildings. The creation of mass auto ownership required major changes in infrastructure such as road improvements, construction of bridges, and later, the development of highway networks. The car caused changes in the built environment too, both through the introduction of new building types as well as the modification of existing forms. The relationship between buildings and the street also demanded changes.

Prior to the advent of Henry Ford's Model T in 1908, the automobile was a toy of the wealthy. Only a few American manufacturers attempted to build an inexpensive car for common man; most were satisfied competing with European imports for the urban luxury market. The relatively restricted availability of gasoline, as well as its high price and the need for mechanics knowledgeable in their repair, kept cars out of reach of most Americans. Geographically, the lack of good roads outside cities limited most early autos to urban areas, particularly larger cities of the East.

During the first two decades of the twentieth century, middle class suburbanites became increasingly frustrated with the crowds, slow service and high fares of the streetcars. The automobile provided an excellent alternative. Motorist could go anywhere they wanted at any time. And they could go farther and get to their destination faster. The increased popularity was furthered through higher wages and the lower costs that came with Ford's revolutionary technological advancement: the assembly line. The efficiency of the assembly line allowed Ford to cut the cost of the Model T from \$950 in 1910 to \$290 in 1924. Before long, the automobile became the primary mode of transportation in the United States, rendering carriages and streetcars obsolete.

The first automobiles appeared in San Diego around the turn of the century. John U. Widrin, owner of a bicycle repair shop, sold the first car in San Diego. By 1903 there were enough cars in town for the City Council to adopt ordinance 1269, limiting the maximum speed of an automobile in downtown to eight miles an hour. In 1905, the secretary of state was empowered to register and license motor vehicles, which provided a uniform statewide registration system. The first vehicle license issued in San Diego was to Clyde Adair, for the operation of a Rambler. Amusingly, the 1905 *City Directory* listed his occupation as a machinist and the next year as an "automobile operator."

Due to the rarity of automobiles, especially in the West, few businesses catered specifically to the car at the turn of the century. Early on, cars were maintained and repaired either by a chauffer in a private garage, or at a blacksmith, a carriage works, or other business catering to the horse and buggy trade. Few, if any, of these structures remain. By the 1920s, independent repair garages specifically serving the automobile had replaced earlier horse-based businesses. Buildings designed with the auto in mind started replacing older building forms. Gas stations, repair shops and auto dealerships--building types that didn't exist 20 years before--became increasingly common, especially along major arterial roadways.

As would be expected for such an early date, the 1888 Sanborn Fire Insurance Company maps do not reveal automobile related land uses in the East Village area. There were however a number of uses related to the maintenance and storage of horses and horse carriages. The majority of these uses were clustered in the two blocks bounded by Sixth and Eight Streets and I and H Streets (now Island and Market respectively), a block east of the city's major commercial street. The two blocks housed five blacksmiths, two carpenters, three painters (two of which were described specifically as carriage painters), a trim shop, an upholstery shop, wagon parts storage, two buggy sheds, a carriage repository and two carriage warehouses. Interspersed throughout were liveries, corrals and feed yards. Significantly, the San Diego Electric Rapid Transit rail line ran on H Street, past the area. Additionally, the public horse auction market was located immediately south of the site. A number of lodging houses and hotels were located nearby including the American, Commercial and Garibaldi Hotels. Scattered throughout the remainder of the East Village, there were at least thirteen other businesses (either described as liveries, stables or corrals) identified as related to the care and maintenance of horses.

By 1906, the East Village district supported at least four automobile-related businesses including two automobile repair shops and two stores selling feed as well as fuel (Appendix A: Maps 10A & 10B, forthcoming). The area also supported five bicycle shops. The number of carriage and horse-related businesses within the East Village increased substantially from what was noted in 1888. The maps also depict the San Diego Truck Company and Pioneer Truck Company, the latter owned by Roscoe Hazard. Although not specifically listed as catering to the car, many of the carriage-related businesses, as well as the bicycle shops, probably offered automobile maintenance and repair in addition their normal services. As seen in 1888, horse and carriage-oriented concerns continued to cluster in the two blocks bounded by Sixth and Eighth Streets and I and H Streets; this was also the case for the bicycle and automobile businesses in 1906.

By the 1910s, the automobile was in general use throughout Southern California. For the year of 1913, the Automobile Club of Southern California listed 4,811 cars registered within the County or one automobile for every 16.5 persons. Automobile ownership only continued to increase as time progressed. Throughout the 1910s, Colonel Ed Fletcher pushed for a link between San Diego and the new national highway system, even donating the wood to build the plank-road through the sand dunes in Imperial County. A review of the 1920-1921 Sanborn Fire Insurance maps shows a significant increase in auto-related industry in the East Village (Appendix A: Maps 11A & 11B, forthcoming). The most predominant feature was the number of auto-storage buildings associated with single and multi family units. In 1906 no such building existed and by the 1920s there were at least 60, many capable of housing multiple vehicles. These outbuildings were scattered throughout the East Village in no discernable pattern and appear mostly to have been added to rear yards of existent buildings.

In terms of businesses serving motorists, garages, either for service and repair or for storage, were numerous. Easily identified by the numerous garage doors and warehouse-like massing, they were typically single story buildings constructed of inexpensive materials with limited ornamentation (much like a taxpayer block). A number of storage garages were developed in East Village many in the vicinity of luxury hotels north of Market Street. Garages such as J. McInyre's and the Elite (both holding a maximum of 50 cars) and the Maryland Hotel Garage (holding 90 cars) were all located near the Maryland Hotel. Other garages devoted to vehicle

storage were found scattered throughout East Village like White's Garage, J.W. Freidan's Garage, Boylan and Gulick, Tanley Garage as well as Broadway and American Garages. Garages dedicated to maintenance and repair were also found throughout the region.

A significant grouping of auto businesses, particularly showrooms, was located on the block bounded by 15th and 16th Streets, Broadway and E Street. Known as the McKnight Block for the original developer J. F. McKnight, the entire block was devoted to auto sales and service. Three major automobile brands were represented on the block including Cadillac, General Motors and Studebaker and White Trucks. Each of these maintained a sales floor and service department. Davis-Overland and Chevrolet were also located nearby. The surrounding blocks hosted many other businesses offering services to motorists, especially auto repair shops, auto painters, tire sales and battery sales and reconditioning. The location of these auto-oriented businesses along Broadway and 16th was not accidental. By the 1920s there had been a shift in the commercial retail and banking industries moving to Broadway from Fifth Street (now Avenue). What was originally the northern boundary of the business district was now at the heart. Broadway had developed into a major east-west corridor that connected downtown with the mesa top suburbs to the north and the east of Balboa Park. From Fifth Street east, parcels that once supported residential uses were replaced by commercial speculation. A once contiguous neighborhood was divided by commercial uses. This was also the case to the south where commercial and industrial buildings encroached on residential parcels.

As the area transitioned from residential to commercial, auto-related businesses, which needed large parcels, took advantage of the burgeoning arterial, the proximity to the central business district and lower land costs found in the East Village. As a result, a significant portion of San Diego's auto industry located in the area, particularly east of 10th Street. Other auto-related businesses devoted to more offensive uses such as junkyards, auto wrecking, trucking companies, blacksmithing and paint shops were located south of Market Street. While the automobile had become the dominant mode of individual transportation by 1920, a few businesses in East Village still catered to dwindling modes of horse-related transportation. Sanborn maps show ten horse-related businesses, all located south of Market Street, including liveries, carriage works, feed yards and hay storage areas. Even before the advent of zoning in San Diego in 1923, industry was separating itself into concentrated districts.

Throughout the 1920s, downtown retailers continued to dominate the metropolitan scene; however newer shopping districts were beginning to emerge along Fifth Avenue in Hillcrest, University and 30th in North Park and Adams Avenue in Normal Heights. These smaller districts took some of the strain off the mounting parking dilemma in the downtown; however, by 1928, traffic congestion in the central business district could no longer be ignored. In April, the City Council adopted a new traffic ordinance (Ordinance 11650), which defined the central traffic district (essentially an area surrounding the business district) and outlined specific traffic rules for the district. The most significant aspect of the ordinance was the regulation of parking within the central traffic district. Following the ordinance, parking was limited to one hour between 8:00 AM and 6:00 PM and to two hours in the area surrounding the district. The hope was to decrease congestion by encouraging parking space turnover by limiting the allowable time shoppers, who arrived predominantly by car, could park on the street.

At the same time the city's engineers were trying to figure out what to do with the cars already in the city, other agents were working to encourage more motorists to visit the Silver Gate. In April of 1928, the Automobile Club of Southern California, in coordination with the San Diego Chamber of Commerce and other organizations, sponsored a motorcade from San Diego to Memphis, Tennessee. Part of the good-roads movement, the motorcade traveled what was coined the "Broadway of America Highway," with the purpose promoting the development of a transcontinental highway system and to publicize the Pacific Coast as tourist destination accessible to the motorist. Many of San Diego's most prominent businessmen participated in the motorcade, including Colonel Fletcher, J. S. McKean (rear admiral of the 11th Naval District) and Harry C. Clark (mayor of San Diego from 1927 to 1931). Ford dealer Walter M. Casey even donated a new Tudor Ford sedan to the Chamber of Commerce for the trip.

The new ordinance regulating parking in the central traffic district had little result. Midway through 1929 the five-story Adair Garage opened at "A" and Seventh Streets, next to the Fox Theater. The 300-car capacity facility couldn't have opened at a worse time. As with the rest of the nation, the market crash of October 1929 had an enormous effect on the economy of San Diego. The rapid growth of the prior decade dropped significantly with the onset of the Depression. Business failure and unemployment was extensive. With tenants hard to find and rents dropping rapidly, property owners looked for a way to secure the maximum return with only modest improvements. The answer: scrape the existing building and replace it with a parking lot. The downturn in San Diego reached its lowest point in 1934 and by 1935, the economy started to turn around.

East Village, by 1956, had been completely transformed into a commercial and industrial landscape (Appendix A: Maps 12A & 12B, forthcoming). Only remnants remained of the area's residential past. It had also been changed into environment wholly subservient to the automobile. Maps reveal Broadway now completely lined with commercial structures. And most importantly, there was plenty of room for the auto in off-street surface parking lots. Most lots were located immediately adjacent to businesses, either to the rear or the side. This was the result of tactics used by property owners during the Depression, as well as enlarged demand brought on by increased automobile use among the expanding middle class. Parking lots were scattered throughout East Village in no apparent pattern. In most cases, whole parcels were cleared and covered with asphalt, replacing mostly housing. In total, more than ten city blocks were given over to parking by 1956. The design of buildings was also changed to accommodate the car. Buildings were pushed back from the street to leave as much room as possible between the road and the front door for parking. Large signs were added to draw customers who arrived solely by auto. Streamline forms, mimicking those of cars themselves, further added to the auto-centered landscape. Within the East Village Study Area, the E. Harris Grocery Store (1925), Todd's Market (1947) and the Davidson Furniture Store (1940) exhibit streamline design characteristics influenced by the automobile. These include long horizontal lines, window walls of plate glass protected by cantilevered horizontal canopies, and blade or fin signs oriented toward the motorist.

The node of automobile dealerships noted earlier at Broadway and 16th Street was expanded to include most parcels fronting Broadway from 16th to 12th Avenue. There were at least fourteen businesses selling cars, including Chevrolet and Ford, as well as a number of used car

dealerships. Most of the new dealers along the strip employed an updated design in dealerships; service bays, parts storage and office space were kept to the rear of the lot, leaving the frontage free for cars to be shown in a lot that lined the street.

Other patterns previously noted had changed by the 1950s. While in the 1920s maintenance and repair garages were found throughout East Village, by 1956 most were located near the Broadway auto-strip. The number of gas and service stations increased to at least 20. While Broadway had become the principal commercial thoroughfare, Market Street emerged as a major industrial arterial. With the City's industrial sector expanding south of the Market, the roadway became the boundary between the commercial area to the north and the industrial uses to the south. In 1956, the road supported a carhop restaurant, five tire shops and no less than nine gas stations. Businesses devoted to more offensive uses, such as junkyards, auto wrecking, trucking companies and paint shops, continued to locate south of Market Street.

a) Property Type: Automobile Showrooms

Early showrooms were basic affairs, often simply a corner in a hardware store. As the auto increased in popularity, changes were made in the way they were merchandised. By the 1920s, architects were being hired to create buildings specifically designed for the requirements of retail auto sales. Most buildings consisted of two or more levels housing the company's sales floor, inventory and service areas. Architectural styling and ornamentation was concentrated on the showroom portion, particularly around formal entrances. Large expanses of plate glass windows were the dominant feature of the primary façade. High ceilings, waiting rooms and decorative floors distinguished interior showroom spaces. The interiors of the services areas were characterized by bare concrete floors, exposed walls and roof trusses and skylights.

The J.F. McKnight Block is a good representative example of an early auto showroom. The building featured a showroom fronting Broadway with a service department, accessed via 16th Street, located behind the sales floor. Designed by the San Diego architect Eugene M. Hoffmann for Studebaker and White Trucks, the building featured a stucco façade with large plate glass windows along the Broadway and 16th Street. These elevations allowed passersby to view cars in the most up-to-date showroom. A cantilevered marquee highlighted the entrance. Above this, the second floor sported three bays of multi-light windows. Ornamentation was modest with a simplified geometric Mission Revival parapet and decorative tile work bands.

A few blocks west of the McKnight Block is a later Streamline Modern version of the auto showroom. Walter D. Teague, the noted industrial designer responsible for the Ford Building in Balboa Park, as well as the famous porcelain-enameled metal-clad Texaco box gas stations, is believed to have designed this building. Located on the corner of Broadway and 12th Avenue, suburbanites returning home from the central business district were offered views of the newest Ford models through the glass expanses of the corner rotunda. The building's surface was covered in smooth stucco and cool black tile. Large display windows on Broadway continued around the corner onto the 12th Street façade. The entry on 12th Avenue seemed to float within the black vitrolite glass. The ribbon windows of the second story were accentuated with flow-lines suggesting motion. The northern portion on of the 12th Avenue façade housed the service department.

b) Property Type: Automobile Garages

Early on, gasoline, routine maintenance and major repair, as well as sales, occurred in a variety of buildings. Blacksmiths, livery stables and carriage works typically provided repairs for motorists. Gas was sold through hardware stores and feed suppliers. Independent garages offering service became common in the 1920s. These buildings were very simple affairs, often little more than a shell to protect the mechanics and vehicles from the elements. Typically single story buildings, they were constructed of inexpensive materials and had limited ornamentation. They are easily identified by the numerous garage doors and warehouse-like massing. Most had unfinished interiors exemplified by concrete floors, exposed interior walls and roof trusses. Most had electric lights to supplement skylights; however they usually didn't have power or heat. Exteriors were simple: decoration was limited to little more than a parapet to hide the gable roof. Most of the garages in East Village maintained a simple Mission Revival style, which was easily accomplished through the application of a curved or stepped parapet, a coat of stucco, and decorative tiling. The J.O. Hosman/ Marriott and Drummond Garage (c. 1920), the Tenth Street Garage (c. 1925-1926), the Kidd & Krone Auto Painter Building (1925) and he H.J. Goodman Garage (c. 1925) are all good representative examples of this trend.

Within the East Village survey area, six properties related to automobile sales, service or storage are being brought before the Board; however only five are noted as potentially eligible for designation. The sixth property (Federal Motor Truck Company) has had significant alterations, compromising its integrity and is therefore recommended for Note and File. Potentially significant properties include three auto showrooms (J. F. McKnight Cadillac & Studebaker, G. M. Truck Sales & Service and the Ford Motor Building) and two garages (Maryland Hotel Garage and the Southern California Telephone Company Garage). Other properties discussed in this context statement have either been cleared by staff due to severely compromised integrity, or are part of the Warehouse Thematic District and will be brought to the HRB shortly.

In conclusion, although auto-related properties were once widespread, relatively few remain. Many have been demolished to make way for new development while others suffer from years of neglect. The two remaining showrooms demonstrate both an early example (McKnight Block) and a mature form (City Ford) of the indoor auto dealerships. This property type offers insight into the introduction of what was a new mode of transportation in the early Twentieth Century. It also serves as evidence of the important role retail automobile sales businesses played in the economic development of San Diego. Independent garages supplied the maintenance and repair needs of motorists and represent a new business type that grew out of the introduction of the automobile. Both property types are significant in revealing the increasing importance of the automobile as America's favored method of private transportation from 1900 to 1956. Those remaining auto-related buildings are the remnants of a commercial landscape reflective of the City of San Diego in the first decades of the Twentieth Century and are worthy of designation under HRB Criterion A.

IV. SURVEY FINDINGS & STAFF RECOMMENDATION

The complete survey findings are located in Table 4 at the end of this section, where the consultant recommendation is found in the column titled "Lia Rec." and the HRB Staff recommendation is found in the column titled "Staff Rec." A summary comparison of the two reviewer's recommendations is found in Table 3.

OHP Status	3S	5S1	5S2	6Z	7
Code*					
Consultant	3	29	7	32	14
Recommendation					
Staff	10	0	59	16	0
Recommendation					

Table 3. Comparison of Survey Results

- 3S Appears individually eligible for the National Register or California Register through survey evaluation.
- 5S1 Individual property that is listed or designated locally.
- Individual property that is eligible for local listing or designation.
- 6z Found ineligible for National Register, California Register or Local designation through survey evaluation.
- Not evaluated for National Register or California Register, or needs revaluation.

In Table 4, the recommended Historical Resources Board Criteria are found in the column titled "HRB Criteria." In all cases, historical resources that are recommended for designation are recommended under HRB CRITERION C (Architecture) by both the consultant and HRB Staff. In all cases, those historical resources that are recommended for local designation have received the highest state status code warranted by the property's significance. In some cases, HRB staff is also recommending additional local criteria, based upon new staff research, or upon research from earlier surveys that has been omitted (in some cases) on the updated forms on the basis that the information is already in the public record. Staff is carrying that material forward for HRB consideration to consolidate all known information in one place. Properties recommended for Note and File have either been substantially modified, are architecturally undistinguished, or lack historical significance.

The "Comments Column" in Table 4 indicates the specific HRB criteria staff is recommending, as well as any other information (such as integrity issues) relevant to potential designation or Note and File decisions. Integrity issues are also addressed in the Thumbnail Photos of sites included in the survey, found in Appendix B, where modifications are noted in red. California State Department of Parks and Recreation Primary Record Forms (DPR 523A) and Building, Structure and Object Forms (DPR 523 B) are located in Appendix C, where detailed information is found on each property included in the survey. The DPR forms are organized by lettered streets, followed by numbered streets. Each form is numbered in the upper right hand corner for quick reference. The form number corresponds to the Form Numbers in Table 1, the map numbers on Identified Sites Map #3 and the Thumbnail Photo numbers in Appendix B.

^{*}California Historical Resources Status Codes, published by the State Office of Historic Preservation (OHP), are used in this survey. OHP status code interpretation follows below:

This is a revised draft of the East Village Combined Historical Surveys, 2005. Additional Sanborn maps on auto-related resources will be available on-line and at the HRB January meeting. Please indicate on the form enclosed in the binder front pocket those properties where you disagree with the staff recommendation, or have questions you would like to discuss with HRB members during the regular public meeting on January 27, 2005. Sign the form and return it to staff by FAX or in the enclosed envelope. To facilitate survey review, only these properties will be culled for discussion. Kindly return the forms by 9:00 am, on Monday, January 24, 2005, so staff can organize the results for the HRB January 27 meeting. It is assumed that the survey findings will be modified pending HRB review and public testimony at the January meeting. After the HRB provides preliminary approval of the document findings, it will be revised, as appropriate, for formal adoption at a subsequent HRB meeting. When the survey findings are adopted, properties that do not meet HRB designation criteria will be formally Note and Filed as a separate action so they may be cleared for future development. Properties that meet HRB criteria for local designation can be formally designated at the owner's request once the survey findings have been adopted.

TABLE 4. East Village Combined Historical Surveys 2005 Staff Recommendation

Form												
No. Si	Survey		Street Name	APN	Lia Rec.	Staff Rec.	HRB Criteria	Building Name	Architectural Style	Date	Architect or Builder	Comments
		0001.101						2 4.1.4.1.9 1 14.1.10	, moninocianan etyre		, monitor of 2 amas.	
								J.F. McKnight Cadillac			Eugene Hoffman	
1 Ea	ast Village	1531-1541	Broadway	5343520400	7	5S2	A, C, D	& Studebaker	Utilitarian	1918	(Architect)	Auto-related resource; windows boarded
								St. Anthony Apartment	High Style Italian		Carter Construction	East Village residential cultural landscape;
2 E	ast Village	1640	Broadway	5342240400	5S1	5S2	A, C	Hotel	Renaissance	1912	Company (Builder)	windows replaced
												Taxpayer; conversion to restaurant meets
		100 110	0.01	5005404000	500	500			, , , , , , , , , , , , , , , , , , ,	4000		Secretary of the Interior's Standards for
3 0	Core	109-113	C Street	5335161000	582	5S2	C	College Inn	Art Deco (Taxpayer)	c. 1928	Unknown	Rehabilitation
₄ _E ,	ast Village	1317	C Street	5342050200	591	5S2	A, C	R.S. Smith Residence	Pyramidal Folk National	1887	R.S. Smith (Builder)	East Village residential cultural landscape
	ast Village			5342050200			A, C	1321 C Street	,	c. 1887	Unknown	East Village residential cultural landscape
	ast Village			5342050300			A, C	Porter Long House	Folk Victorian	1894	Unknown	East Village residential cultural landscape
	aot villago	1000	O Ciroti	001200000	001	002	71, 0	T Ofter Long Floude		c. 1887/	Cilianowii	First floor modifications on both buildings;
₇ _E ;	ast Village	1343-1345	C Street	5342051200	6Z	6Z	Note & File	S.R. Williams House		pre-1921	Unknown	1345 stuccoed
						-						East Village residential cultural landscape;
8 E	ast Village	1425 - 1431	C Street	5342040600	5S1	5S2	A, B, C	1425 C Street	Prairie	1908	C.J. Jones (Builder)	associated with William E. Smythe
									One Part Commercial			
9 Ea	ast Village	901-923	E Street	5343360100	7	5S2	С	Bidwell Block	Block (Taxpayer)	1927	Unknown	Taxpayer
											L.D. Burbeck (Architect/	
10 E	ast Village	1035	E Street	5343350900	5S1	6Z	Note & File	Custer Apartments	Italianate vernacular	1886	Builder)	Building significantly modified on three sides
l L									Italian Renasissance		L.D. Burbeck (Architect/	East Village residential cultural landscape;
11 E	ast Village	1045	E Street	5343350900	5S1		A, C	Carper Apartments	vernacular	1913	Builder)	balcony rebuilt per code
		4007.0.4000				(1327) 6Z/			Kallan Danadanan			
12	oot Villaga	1327 & 1329 -	C Ctroot	E2424E4000	7	(1329 - 1335)	۸ ۵	Menke Residence	Italian Renasissance Revival	0 101E	Unknown	Fact Village regidential cultural landscape
12 E	ast Village	1335	E Street	5343451000	/	3S	A, C		One Part Commercial	c. 1915	UNKNOWN	East Village residential cultural landscape
13 E	ast Village	1401	E Street	5343440100	67	5S2	C		Block (Taxpayer)	1923	Unknown	Taxpayer; first floor modifications
10 1.	ast village	1401	L Olicci	3343440100	02	302		reserve ricadquarters	Block (Taxpayer)	1323	OTIKIOWII	raxpayer, mat noor modifications
		1508-1544/	E Street/	5343520200/				GM Truck Sales &		1906 -		
14 O	Over 45	934-940			6Z/ 6Z	5S2/ 5S2	A, C		Spanish Eclectic	1921	Unknown	Auto-related resource; windows boarded
							,		Brick Commercial with		Hebbard & Allen	First floor modifications; building undergoing
									Italian Renaissance Revival		(Architects) W.E. Kier	rehabilitation per Secretary of the Interior's
15 Ea	ast Village	612-650	F Street	5343260300	3S	3S	C, D	The Maryland Hotel	Elements	1914	(Builder)	Standards
									One Part Commercial	1907 -	The Haverty Co. & F.O.	
16 E	ast Village	741	F Street	5351021000	7	3S	A, C	Maryland Hotel Garage		1909	Engstrum Co. (Builder)	Auto-related resource
	ant Village	004 004	C Ctroot	F0F4000400	7	500	0		One Part Commercial	4004	Linkanava	Townsyer
17 E	ast Village	801-821	F Street	5351030100	/	5S2	C	Rossi Business Block	Block (Taxpayer)	1924	Unknown	Taxpayer
									Commercial Block Lodging			Extensive alterations when converted to lofts:
									House with Spanish		Consaul Construction	does not meet Secretary of the Interior's
18 E	ast Village	1111	F Street	5351330100	67	6Z	Note & File	Hotel Yale	Eclectic influence	1927	(Builder)	Standards for Rehabilitation
	.act village		. 50,550	2301000100				1.000 100	Two Part Commercial	.027		Canadido for Hondomation
19 Ea	ast Village	1328-1344	F Street	5343451200	7	3S	С	Mission Public Market	Block (Taxpayer)	1925	Unknown	Taxpayer; first floor modified
	<u> </u>								False Front Italian	1889 -		
20 E	ast Village	1451-1453	F Street	5351710100	6Z		Note & File	1451 - 1453 F Street	vernacular	1890	Unknown	Undistinguished architecture
	ast Village			5351710900			A, C	Judson Property		c. 1900	Unknown	East Village residential cultural landscape
									Vernacular Hipped Roof			
								Kreiss/ Wilcox	Free Classic Queen Anne			
22 E	ast Village	1610-1620	F Street	5343601200	5S1	5S2	A, C	Residence	Victorian	1906	Unknown	East Village residential cultural landscape

TABLE 4. East Village Combined Historical Surveys 2005 Staff Recommendation

Form			Street									
No.	Survey	Street No.	Name	APN	Lia Rec.	Staff Rec.	HRB Criteria	Building Name	Architectural Style	Date	Architect or Builder	Comments
	- C u 1 G y	00011101	1.10					J.S.Harbison Grocery	Italianate Commercial	2 0.10	George Young/ French	Only remaining building associated with J.
23	East Village	643-655	G Street	5351061100	5S1	5S2	в, с	Building	Block	1888		S.Harbison
	ge	10.10.000					_, _	9			(= 3)	
								The Hazard, Gould,	Two Part Commercial			
24	East Village	675	G Street	5351061100	7	5S2	С	and Company Building		1909	W.J. Kirkwood (Builder)	Cornice removed; exterior stuccoed
			Island						Transitional Colonial			
25	Bayside	903-915	Avenue	5351260100	6Z	5S2	A, C	Hiatt Residence	Revival	c. 1902	Ellsworth Hiatt (Builder)	East Village residential cultural landscape
											Nelson Comstock &	
			Island						Queen Anne Spindlework		Carl Trotsche	
26	East Village	1245	Avenue	5351560900	3S	3S	A, C, D	Sheldon Residence	Victorian	1886	(Architect)	East Village residential cultural landscape
			Island									-
27	East Village	1619-1625	Avenue	5353931300	5S1	5S2	A, C	Julia Stewart House	Victorian	c. 1887	Unknown	East Village residential cultural landscape
			Island					C.E. & Ella Harney		1906 -		
28	East Village	1635	Avenue	5353931300	6Z	6Z	Note & File	House	Folk Victorian	1921	Unknown	Undistinguished architecture
									Early Twentieth-Century			
								Salem Hotel/Workman	Commercial Block Lodging			East Village residential cultural landscape; first
29	Bayside	1335	J Street	5353721500	6Z	5S2	A, C	Hotel	House	1912	H.C. Sparks (Builder)	floor slip covered; modifications reversible
30	Bayside	1479	J Street	5353960400		5S2	A, C	Joseph Ireland Building		1888	Unknown	East Village residential cultural landscape
31	Over 45	1619	J Street	5353940100	6Z	5S2	A, C	R.B. Meyers House	Craftsman	1906	Unknown	East Village residential cultural landscape
											Rohde Brothers	
32	Over 45	1615	K Street	5353830100	6Z	5S2	A, C	John Quantrell House	Craftsman	c. 1890s	(Builder)	East Village residential cultural landscape
			Market						Italianate Commercial		H.A. Perry & Moses	
33	East Village	726-732	Street	5351050700	7	5S2	С	Orford Hotel	Block	c. 1898	Frick (Architect)	First floor modifications
											Anton Reif & John B.	
									Two Part Commercial		Stannard (Architect)	
			Market						Block with Italianate		Schaniel Brothers	
34	East Village	740-744	Street	5351050800	7	6Z	Note & File	Albert Morse Block	influence	1896	(Builder)	Cornice removed; exterior stuccoed
			L					L	One Part Commercial		Frank P. Allen	Extensive modifications when converted to
			Market				l	Federal Motor Truck	Block with Art Deco		(Architect) Walter	restaurant; does not meet Secretary of the
35	East Village	906-922	Street	5351360200	6Z	6Z	Note & File	Company Building	Detailing	1931	Trepte (Builder)	Interior's Standards for Rehabilitation
			.								Frank L. Hope	
	0 45	4404	Market	505 400 40	0.7	00	0 0	E'ret Niet'r rei Deel	Lata Mada a	4054	(Architect) H. W. Grizzle	
36	Over 45	1101	Street	535-123-10	62	3S	C, D	First National Bank	Late Moderne	1954	(Builder)	
			Montret								John B. Stannard & Gustavus Clements	
27	Foot Village	1405 1404	Market	E251521400	EC1	20	C D	The Touriet	Italianata	1001		First floor modifications
37	East Village	1425-1431	Street Market	5351531400	<u>၁</u> ၁၂	3S	C, D	The Tourist Davidson Furniture	Italianate	1881	(Architect)	Original awning intact beneath later
38	Over 45	1/100	Street	5351610400	67	5S2	C		Art Modern	c. 1940	Unknown	weatherproofing; tile intact beneath paint
30	OVEI 45	1488	Market	3331010400	المحادث	JJZ		Company Bulluling	Attivioueiii	U. 194U	OHKHOWH	weatherproofing, the intact beneath paint
			Street/									
		1704-1710	17th								Pacific Building	
39	East Village	607-621	Avenue	5351900200	7	5S2	A, C	Morse Courts	Craftsman vernacular	1924	Company (Builder)	East Village residential cultural landscape
33	Last village	001-021	Market	3331300200	'	302	Α, Ο	Edmund Wescott	Oranoman vemaculai	1347	Dulluel)	Last village residential cultural landscape
40	East Village	1715	Street	5351900800	591	5S2	A, C	House	Italianate	1881	H.A. Perry (Builder)	East Village residential cultural landscape
70	Last village	17 13	Oliect	3331300000	301	302	Α, Ο	i iouse	One Part Commercial	1001	Tina. Felly (Dulluel)	Last village residential cultural landscape
			6th						Block with Modified False			Details stripped; exteror stuccoed; windows
41	East Village	505	Avenue	5351110700	67	6Z	Note & File	Walker House	Front	c. 1885	A W Delane (Architect)	replaced; first floor modified
<u> </u>	Last village	1000	Avoilue	0001110700	UL	ابر ا	14010 CE I IIC	Walker Flouse	II TOTAL	10. 1000	M.W. Dolaile (Molitect)	replaced, first floor flooringd

TABLE 4. East Village Combined Historical Surveys 2005 Staff Recommendation

Form			Street									
No.	Survey	Street No.	Name	APN	Lia Rec.	Staff Rec.	HRB Criteria	Building Name	Architectural Style	Date	Architect or Builder	Comments
												Taxpayer; attic added; conversion to restaurant
40		705	6th	5054040000	0.7	500			One Part Commercial	4000		meets Secretary of the Interior's Standards for
42	Over 45	705	Avenue	5351010300	6Z	5S2	C	MacMarr Grocery Store	Block (Taxpayer)	c. 1929	Unknown	Rehabilitation
			741-					Can Diama Haffman	On a winds Endoatin with		Louis Gill (Architect)	
42	Foot Village	704	7th	E2E1020600	EC1	3S	C D	San Diego Hoffman	Spanish Eclectic with	1000	Thomas M. Russell (Builder)	
43	East Village	701	Avenue	5351020600	551	33	C, D	Hospital and Clinic	Modern influence	1928	(bulluer)	
			8th						Two Part Commercial		George E. Cornell	
44	East Village	615		5351040300	7	5S2	C	Hotel Schneider	Block with Italian linfluence	1013	(Builder)	First floor modifications
77	Last village	010	Avenue	3331040300	'	302		rioter defineder	Block with italian influence	1313	(Dallaci)	I list noor modifications
			8th					The Revere Rooming	Two Part Commercial	1886/ 1907		
45	East Village	703-723		5351030400	6Z	6Z	Note & File	House	Block	- 1909	Unknown	Exterior modified in 1930s and 1980s
								Southern California		1000		
			10th					Telephone Company			W.E. Kier Construction	
46	East Village	660	Avenue	5351360100	5S1	5S2	A, C	Garage	Art Deco	1932	Company (Builder)	Auto-related resource
			10th					Ephraim & Mary				East Village residential cultural landscape;
47	East Village	734	Avenue	5351310500	5S1	5S2	A, B, C	Walker Morse House	Italianate	1887	Unknown	associated with Ephraim Morse
			10th									
48	East Village	743	Avenue	5351320400	6Z	5S2	A, C	H.T. Christian House	Victorian vernacular	1872	Unknown	East Village residential cultural landscape
									Vernacular Townhouse with			
			11th						Italian Renaissance			
49	East Village	650	Avenue	5351350900	6Z	6Z	Note & File	Yale Apartments	influence	1912	M.D. Goodbody	Undistinguished architecture
								Thomas J. Daley				
								•	Folk Victorian (rear			Two-story porch in 1907 building removed;
			11th					Bailey Apartment	structures) & Italianate			window & door openings modified; 1886
50	East Village	727-733 1/2		5351331500	6Z	6Z	Note & File	Buildings	(front structure)	1886/ 1907	J.D. Palmer	buildings modified both front & rear.
 			11th									
51	East Village	741		5351330300	62	6Z	Note & File	Woodford Residence	Italianate	1887	Unknown	Exterior stuccoed; windows replaced
		700 770/4005	11th						One Part Commercial		Coatt Owintin (Arabitant)	Towns you I off some origin made Connector to
E2	Foot Village	760-770/ 1025-		E2E1220700	7	5S2		Cabillar Dook Dindon	Block with Neo-Classical	1022		Taxpayer; Loft conversion meets Secretary's Standards for Rehabilitation
52	East Village	1055	Street 11th	5351320700	'	332	C	Schiller Book Bindery Hamilton Apartment	influence (Taxpayer)	1932	vvaller Treple (Bullder)	Standards for Renabilitation
53	East Village	941		5343330200	591	5S2	A, C	Building	Italianate	1886/ 1007	John Campbell (Builder)	East Village residential cultural landscape
33	Last village		12th	3343330200	331	332	Λ, Ο	The New Bay View	Italiariate	1000/ 1907		Corner towers and first floor balcony railing
54	East Village	509		5351510500	35	3S	С	Hotel	Italianate	1889	Unknown	removed
	Last village	000	12th	0001010000	00				Art Moderne (Streamline	1000	Onknown	Temoved
55	Over 45	999		5343411000	5S2	5S2	С	Store	Modernistic)	c. 1925	Unknown	
			12th						Art Moderne (Streamline			
56	Over 45	1015-1025		5342060300	5S2	5S2	A, C	Motor Building	Modernistic)	1937	Unknown	Auto-related resource; windows boarded
			12th				,	Otto and Blanche Fox	,			·
57	East Village	1154		5341930900	5S1	6Z	Note & File	Residence	Colonial Revival	1895	Unknown	Porch & window modifications
			12th									
58	East Village	1166	Avenue	5341931000	7	5S2	A, C	Biltmore Apartments	French Eclectic	1925	Unknown	East Village residential cultural landscape
								Mexican Presbyterian				
								Church/Mexican &				
								Spanish Presbyterian		1906 -		Significant for association with San Diego
59	Bayside	341-343	13th Street	5353720400	6Z	5S2	A, C	Church	Vernacular Folk Victorian	1907	Unknown	Mexican community
								Simon Padilla				
60	Bayside	353-357	13th Street	5353720300	6Z	5S2	A, C	Residence	Victorian	c. 1870s	Unknown	East Village residential cultural landscape

TABLE 4. East Village Combined Historical Surveys 2005 Staff Recommendation

		Stroot									
Survey	Street No.		APN	Lia Rec.	Staff Rec.	HRB Criteria	Building Name	Architectural Style	Date	Architect or Builder	Comments
Over 45	416	13th Street	5351560600	6Z	5S2	A, C	Residence	Folk Victorial	c. 1870s	Unknown	East Village residential cultural landscape
East Village	454	13th Street	5351560800	5S1	5S2	A, C	Wright Residence	Italianate	1882	J.S. Wright & Company	East Village residential cultural landscape
Davaida	000	4.54b. Other at	E0E0000400	500	500		Dand Dantal		- 4007	Halmann	
Bayside	360	15th Street	5353960400	552	552	A, C			C. 1887	Unknown	East Village residential cultural landscape
Over 45	648	15th Street	5351740400	5S2	5S2	С			1945	Unknown	
East Village	1037	15th Street	5342250400	5S1	5S2	A, C	B.J. Grenell House	Queen Anne Cottage	1886	E.G. Hammond	East Village residential cultural landscape
Over 45	39	16th Street	5356230400	6Z	5S2	A, C	Fultz Residence	Craftman	1923	Unknown	East Village residential cultural landscape
Over 45	255	16th Ctroot	E2E2020200	67	500	A C		Folk Vietorien	0 10700	Linknown	Fact Village regidential cultural landscape
Over 45	255	Totti Street	5353630200	02	552	A, C	Lewis Residence		C. 1670S	Unknown	East Village residential cultural landscape
East Village	701	16th Street	5351800100	7	5S2	C. D	The Snowflake Bakery		1914	John B. Stannard	
						1	,	Art Moderne (Streamline			
Over 45	716	16th Street	5351720600	6Z	5S2	С	Todd's Market	Modernistic)	c. 1947	Unknown	
East Village	815	16th Street	5343601200	5S1	5 S 2	A, C	Lee House	Colonial Revival	c. 1908	Unknown	East Village residential cultural landscape
Bayside	349-363	17th Street	5354060100	5S2	5S2	A, C	Saliba Auto Courts	Art Moderne	1940	Unknown	East Village residential cultural landscape
East Village	420/ 424	17th Street	5353930800	5S1	5S2	A, C	George Selwyn Residence	Folk National	c. 1894	Unknown	East Village residential cultural landscape
East Village	430	17th Street	5353930900	5S1	5S2	A. C	Henry & Hilda Tomas Residence	Victorian Second Empire vernacular	1889	Unknown	East Village residential cultural landscape
2.5										Jobbitt & Schaniel Bros.	3
East Village	454	17th Street	5353931100	5S1	5S2	A, C	Theodore Olson House	Folk Victorian	1890	(Builder)	East Village residential cultural landscape
East Village	470	17th Street	5353931300	5S1	5S2	A, C	Stewart House	Folk National	1904	Unknown	East Village residential cultural landscape
East Village	505	17th Street	5351901400	5S1	5S2	A, C	Norris Rental	Queen Anne Cottage	c. 1887	Unknown	East Village residential cultural landscape
East Village	508	17th Street	5351640300	6Z	6Z	Note & File	Falkenstein Residence	Folk Victorian	c. 1887	Unknown	Exterior stuccoed; windows replaced
East Village	512	17th Street	5351640300	6Z	6Z	Note & File	Rinehart Residence	Folk Victorian	c. 1900	Unknown	Exterior stuccoed; windows replaced
East Village	515	17th Street	5351901300	5S1	5S2	A, C	William Norris Spec. House #2	Folk Victorian	c. 1900	Unknown	East Village residential cultural landscape
East Village	518	17th Street	5351640300	6Z	6Z	Note & File	William E. Robinson Residence	Folk National	c. 1877	Unknown	
Ŭ							William Norris Spec.		1872 -		East Village residential cultural landscape
	1		1111001100	1	1	-, -		Same a Country of the	1880 -	2 2 (24431)	and a second control of the second control o
East Village	531	17th Street	5351904000	5S1	5S2	A, C	Norris House	Italianate	1890	Unknown	East Village residential cultural landscape
Over 45	532-534	17th Street	5351640400	6Z	5S2	A, C	Residence	Modified Dutch Colonial	1888 - 1906	Unknown	East Village residential cultural landscape
East Village	768	17th Street	5351800500	5S1	5S2	A, C	Norris Cluster Apartments	Early Prairie	c. 1913	Unknown	East Village residential cultural landscape; windows replaced
										Edward H. Depew (Architect)	East Village residential cultural landscape
	Over 45 East Village Bayside Over 45 East Village Over 45 Cover 45 East Village Over 45 East Village Bayside East Village Cover 45	Over 45 416 East Village 454 Bayside 360 Over 45 648 East Village 1037 Over 45 39 Over 45 255 East Village 701 Over 45 716 East Village 815 Bayside 349-363 East Village 420/ 424 East Village 454 East Village 470 East Village 505 East Village 508 East Village 512 East Village 515 East Village 518 East Village 525 East Village 531 Over 45 532-534 East Village 768	Over 45 416 13th Street East Village 454 13th Street Bayside 360 15th Street Over 45 648 15th Street East Village 1037 15th Street Over 45 39 16th Street Over 45 255 16th Street East Village 701 16th Street Over 45 716 16th Street East Village 815 16th Street Bayside 349-363 17th Street East Village 420/ 424 17th Street East Village 454 17th Street East Village 470 17th Street East Village 505 17th Street East Village 515 17th Street East Village 515 17th Street East Village 518 17th Street East Village 531 17th Street East Village 531 17th Street East Village 531 17th Street	Survey Street No. Name APN Over 45 416 13th Street 5351560600 East Village 454 13th Street 5351560800 Bayside 360 15th Street 5353960400 Over 45 648 15th Street 5351740400 East Village 1037 15th Street 5342250400 Over 45 39 16th Street 5356230400 Over 45 255 16th Street 5353830200 East Village 701 16th Street 5351720600 East Village 815 16th Street 53543601200 Bayside 349-363 17th Street 5353930800 East Village 420/ 424 17th Street 5353930800 East Village 454 17th Street 5353933100 East Village 470 17th Street 5351901400 East Village 508 17th Street 5351640300 East Village 515 17th Street 5351640300 East Village	Survey Street No. Name APN Lia Rec. Over 45 416 13th Street 5351560600 6Z East Village 454 13th Street 5351560800 5S1 Bayside 360 15th Street 5353960400 5S2 Over 45 648 15th Street 5351740400 5S2 East Village 1037 15th Street 5342250400 6Z Over 45 39 16th Street 5356230400 6Z East Village 701 16th Street 5353830200 6Z East Village 716 16th Street 5351720600 6Z East Village 815 16th Street 5351720600 6Z East Village 420/ 424 17th Street 5353930800 5S1 East Village 430 17th Street 5353930800 5S1 East Village 470 17th Street 5353931100 5S1 East Village 505 17th Street 5351640300 6Z	Survey Street No. Name APN Lia Rec. Staff Rec. Over 45 416 13th Street 5351560600 6Z 5S2 East Village 454 13th Street 5351560800 5S1 5S2 Bayside 360 15th Street 5353960400 5S2 5S2 Over 45 648 15th Street 5353960400 5S2 5S2 East Village 1037 15th Street 5342250400 5S1 5S2 Over 45 39 16th Street 5356230400 6Z 5S2 Over 45 255 16th Street 5353830200 6Z 5S2 East Village 701 16th Street 5351720600 6Z 5S2 East Village 815 16th Street 5354060100 7 5S2 Bayside 349-363 17th Street 5354060100 5S2 5S2 East Village 420/424 17th Street 5353930800 5S1 5S2 East Village	Survey Street No. Name APN Lia Rec. Staff Rec. HRB Criteria Over 45 416 13th Street 5351560600 6Z 5S2 A, C East Village 454 13th Street 5351560800 5S1 5S2 A, C Bayside 360 15th Street 5353960400 5S2 5S2 A, C Over 45 648 15th Street 5351740400 5S2 5S2 A, C East Village 1037 15th Street 5342250400 6S 5S2 A, C Over 45 39 16th Street 5358230400 6Z 5S2 A, C Over 45 255 16th Street 5351800100 7 5S2 C, D Over 45 716 16th Street 5351720600 6Z 5S2 A, C East Village 815 16th Street 5343601200 5S1 5S2 A, C East Village 420/ 424 17th Street 535393000 5S1 5S2	Survey	Survey Street No. Name APN Lia Rec. Staff Rec. HRB Criteria Building Ame Architectural Style	Survey Street No. Name APN La Rec. Staff Rec. HRB Criteria Bullding Name Architectural Style Date	Survey Street No. Name APN Lis Reu Staff Rec. HRBC Criteria Sulcting Name Architectural Syle Date D

V. BIBLIOGRAPHY

Apartment Hotels in Birmingham, Alabama (1900-1930), National Register of Historic Places Inventory-Nomination Form, 1984.

Ashley, Joe, *Roadside Architecture Along US 2 in Montana*, National Register of Historic Places Multiple Property Documentation Form, October 1993.

Bibb, Leland and Kathleen Flanigan, *The Role of Transportation in the Growth of the City of Oceanside*, City of Oceanside, 1997.

Bottles, Scott L., *Los Angeles and the Automobile: The Making of the Modern City*, Berkeley and Los Angeles, University of California Press, 1987.

Brandes, Ray & University of San Diego, *Historic Resources Inventory (of the) Uptown Area San Diego, California*, San Diego, June 1981.

Burgess, Ernest, "Urban Areas" in T.V. Smith and Leonard D. White, eds., *Chicago: An Experiment in Social Science Research*, Chicago, University of Chicago Press, 1929.

California Department of Parks and Recreation, Office of Historic Preservation, *California Historic Resources Inventory Survey Workbook*, Third Revision August 1986.

California Department of Parks and Recreation, Office of Historic Preservation, *Instructions for Recording Historical Resources*, Current Revision March 1997.

Ching, Francis, D.K., A Visual Dictionary of Architecture, New York, John Wiley & Sons, Inc., 1997.

Crawford, Kathleen, *Architectural and Historical Evaluation of 672 8th Avenue, San Diego, California*, January 1996.

Eig, Emily Hotaling and Laura Harris Hughes, *Apartment Buildings in Washington, D. C.* (1880-1950), National Register of Historic Places Multiple Property Documentation Form, 1993.

Fogelson Robert M., *Downtown: Its Rise and Fall, 1880-1950*, New Haven, Yale University Press, 2001.

Gowans, Alan, *The Comfortable House: North American Suburban Architecture 1890-1930*, Cambridge, MA, The MIT Press, 1986.

Grimes, Teresa, Early Auto-Related Properties in Pasadena, California, 1897-1944, National Register of Historic Places Multiple Property Documentation Form, 1996.

Heritage Architecture and Planning, *Historic Assessment Report for a Proposed Warehouse Thematic District*, San Diego, Centre City Development Corporation, 2004.

Hunter, Christine, *Ranches, Rowhouses and Railroad Flats*, New York & London, W. W. Norton & Company, 1999.

Jackson, Kenneth T., *Crabgrass Frontier: The Suburbanization of the United States*, New York, Oxford University Press, 1985.

Lettieri-McIntyre and Associates, Inc., Final Subsequent Environmental Impact Report to the Final Master Environmental Impact Report for the Centre City Redevelopment Project and Addressing the Centre City Community Plan and Related Documents for the Proposed Ballpark and Ancillary Development Projects, and Associated Plan Amendments, v. I-II, San Diego, September 13, 1999.

Lia, Marie Burke, Warehouse District Proposal for Centre City East, July 1995.

Lia & Brandes Team, *Historic Site Inventory of Bayside For Centre City Development Corporation*, San Diego, May 1989.

Lia & Brandes Team, *Historic Site Inventory of Centre City East For Centre City Development Corporation*, San Diego, November 1988.

Liebs, Chester H., From Main Street to Miracle Mile: American Roadside Architecture, Baltimore, Johns Hopkins University Press, 1995.

Longstreth, Richard & The National Trust for Historic Preservation, *The Buildings of Main Street; A Guide To American Commercial Architecture*, Washington, D.C., Preservation Press, 1987.

Longstreth, Richard, *The Drive-In, the Supermarket, and the Transformation of Commercial Space in Los Angeles, 1914-1941*, Cambridge, MA, MIT Press, 2000.

Longstreth, Richard, City Center to Regional Mall, Cambridge, MA, MIT Press, 1997.

McAlester, Virginia & Lee, A Field Guide To American Houses, New York, Alfred A. Knopf, 1986.

McShane, Clay, *Down the Asphalt Path, the Automobile and the American City*, New York, Columbia University Press, 1994.

Moomjian, Scott A., & Elizabeth Bradbury, Appendix To Cultural Resource Study For The Draft Environmental Impact Report; Ballpark and Ancillary Development Projects and Associated Plan Amendments Project, January 1999.

Painter, Susan A., San Diego's Fifth Avenue: An Interpretation of Historical Photographic Images, MA Thesis, San Diego State University, 1991.

Phillips, Steven J., *Old House Dictionary: An Illustrated Guide to American Domestic Architecture 1600-1940*, Washington, D. C., Preservation Press, 1992.

Polyzoides, Stefanos, Roger Sherwood and James Tice, *Courtyard Housing in Los Angeles*, Princeton, NJ, Princeton University Press, 1992.

Pourade, Richard F., *The Rising Tide*, San Diego, The Union-Tribune Publishing Company, 1967.

Reading, James E., *History of San Diego Highway Development*, San Diego, CA, San Diego Highway Development Association, 1977.

Sanborn Fire Insurance Maps, San Diego, New York, Sanborn Map Company, 1888, 1906, 1920, 1921, 1956.

San Diego City Directories, 1944/1945-1984.

San Diego County Assessors Office.

Sicha, Richard J., *Historic Resources of Pasadena (Partial Inventory: Bungalow Courts)*, National Register of Historic Places Inventory-Nomination Form, 1976-1981.

Starr, Raymond G., San Diego: A Pictorial History, Norfolk, The Donning Company Publishers, 1986.

Stein, Susan R., ed., *The Architecture of Richard Morris Hunt*, Chicago and London, University of Chicago Press, 1986.

Talley-Jones, Kathy and Letitia Burns O'Connor, *The Road Ahead: the Automobile Club of Southern California 1900-2000*, Los Angeles, CA, The Automobile Club of Southern California, 2000.

Tess, John M. and Robert L. Munson, *Middle Class Apartment Buildings in East Portland*, *Oregon* (1920-1945), National Register of Historic Places Multiple Property Documentation Form, 1996.

Thompson, Philip, *Transportation-related Properties of Jackson*, *Tennessee*, National Register of Historic Places Multiple Property Documentation Form, February 1992.

Tinsely, Wendy, How Cities Grow: a History of San Diego's Neighborhood Development Patterns; 1769-1955, Master's Thesis, San Diego State University, 2003.

University of San Diego, Department of History, Graduate Division, San Diego Architects, 1868-

1939, San Diego, University of San Diego, Spring 1991.

United States Department of the Interior, *How To Apply the National Register Criteria for Evaluation*, National Register Bulletin 15, Revised 1991.

Wachs, Martin, and Margaret Crawford, Eds., *The Car and the City*, Ann Arbor, MI, The University of Michigan Press, 1991.

Chris Wilson, *Auto-oriented Commercial Development in Albuquerque, New Mexico, 1915-1956*, National Register of Historic Places Multiple Property Documentation Form, September 1996.


Wright, Gwendolyn, Building the Dream: *A Social History of Housing in America*, Cambridge, MA, MIT Press, 1983.

Appendix A: Historical Property Location Maps

- 1. Location Map
- 2. Survey Areas Map
- 3. Identified Sites Map
- A. East Village Residential Development Patterns Sanborn Map, 1887
 B. East Village Residential Development Patterns Sanborn Map, 1887
- 5. A. East Village Residential Development Patterns Sanborn Map, 1888
 - B. East Village Residential Development Patterns Sanborn Map, 1888
- 6. A. East Village Residential Development Patterns Sanborn Map, 1906 B. East Village Residential Development Patterns Sanborn Map, 1906
- 7. A. East Village Residential Development Patterns Sanborn Map, 1921
 - B. East Village Residential Development Patterns Sanborn Map, 1921
- 8. A. East Village Residential Development Patterns Sanborn Map, 1956 B. East Village Residential Development Patterns Sanborn Map, 1956
- 9. East Village Residential Sites Recommended for HRB Criterion A (forthcoming)
- A. East Village Auto-Related Development Patterns Sanborn Map, 1906
 B. East Village Auto-Related Development Patterns Sanborn Map, 1906 (forthcoming)
- A. East Village Auto-Related Development Patterns Sanborn Map, 1921
 B. East Village Auto-Related Development Patterns Sanborn Map, 1921 (forthcoming)
- A. East Village Auto-Related Development Patterns Sanborn Map, 1956
 B. East Village Auto-Related Development Patterns Sanborn Map, 1956 (forthcoming)
- 13. East Village Auto-Related Sites Recommended for HRB Criterion A



Map 1
East Village Combined Historical Surveys 2005
Survey Location



Map 2 Legend East Village Combined Historical Surveys

Survey


Bayside (1989)

Core (2003)

East Village (1988 Update)

4,000 500 1,000 2,000 3,000 Feet Over 45 (2004)

Survey Areas



Bayside 1989 Updates

Core Update

East Village Combined Historical Surveys 2005

Identified Sites


0 500 1,000 2,000

Over 45s 2004

Feet










Boarding House


Single Family Dwelling

Duplex

Apartment

Hotel









Apartment

Hotel


Duplex





Hotel

Duplex







Hotel

Sanborn M a p nsurance

- Service/Repair (Auto Wrecking, Truck/Auto Repair, Fuel, Gas, Oil, Washing, Tires, Parts, Battery, Transmission) Showroom
- **Parking**

- Carriage, Repository, Blacksmith, Painting, Truck/Auto Sales Iron Works, Machine Shop



Map 10A



Fire Sanborn Insurance


Service/Repair (Auto Wrecking, Truck/Auto Repair, Fuel, Gas, Oil, Washing, Tires, Parts, Battery, Transmission) Showroom

Parking

Hotel

Carriage, Repository, Blacksmith, Painting, Truck/Auto Sales Iron Works, Machine Shop

Map 10B




Service/Repair (Auto Wrecking, Truck/Auto Repair, Fuel, Gas, Oil, Washing, Tires, Parts, Battery, Transmission) Showroom

Carriage, Repository, Blacksmith, Painting, Truck/Auto Sales Iron Works, Machine Shop

Parking

Hotel




Fire Sanborn Map Insurance

Service/Repair (Auto Wrecking, Truck/Auto Repair, Fuel, Gas, Oil, Washing, Tires, Parts, Battery, Transmission) Showroom

Carriage, Repository, Blacksmith, Painting, Truck/Auto Sales Iron Works, Machine Shop

Parking

Hotel




Carriage, Repository, Blacksmith, Painting, Truck/Auto Sales

Service/Repair (Auto Wrecking, Truck/Auto Repair, Fuel, Gas, Oil, Washing, Tires, Parts, Battery, Transmission) Showroom

Hotel

Iron Works, Machine Shop

Parking





Service/Repair (Auto Wrecking, Truck/Auto Repair, Fuel, Gas, Oil, Washing, Tires, Parts, Battery, Transmission) Showroom


Parking


Carriage, Repository, Blacksmith, Painting, Truck/Auto Sales Iron Works, Machine Shop

Early Victorian Residences*















*Modifications to original fabric noted in red

Victorian Residences*











^{*}Modifications to original fabric noted in red.


Victorian Residences*
















B-3


*Modifications to original fabric noted in red.


Victorian Residences*

















¹⁹⁰⁰

Turn of the Century Residences*















*Modifications to original fabric noted in red.


Vernacular Buildings*







21. 1455 F StreetJudson Propertyc.1900 (EV)













Courtyard Apartments






Victorian Commercial Buildings*














*Modifications to original fabric noted in red.


Apartment Buildings*














*Modifications to original fabric noted in red.


Hotel and Apartment Buildings*
















Ю


Munson Apartments


1<u>B</u>290

Commercial Buildings*
















^{*}Modifications to original fabric noted in red.

Commercial Buildings*









Auto-Related Properties*











Commercial Buildings



55. 999 12th Avenue (45)

E. Harris Grocery Store c. 1925



69. 716 16th Street (EV)
 Todd's Market c. 1947




38. 1488 Market St. (45 Davidson Furniture Store c. 1940





64. 648 15th Street (45) Davidson Furniture Warehouse 1945





Note and File*















*Modifications to original fabric noted in red.

Note and File*












^{*}Modifications to original fabric noted in red.


Note and File*














^{*}Modifications to original fabric noted in red.

and boundaries):

Primary #	
HRI # 2138-0187-0000	
Trinomial	

21 : / ((1:1:1:1:1:1:1:1:1:1:1:1:1:1:1:1:1:1:1	•				
PRIMARY RECORD		Trinomial			
0	ther Listings Update	e of November 198	8 Centre Cit	y East Survey D	ocumentation
F	Review Code	Reviewer		Date	
Page _ 1 of _ 2 *Resource P1. Other Identifier:		ed by recorder)	1531-1541	Broadway (E	ast)
*P2. Location: □ Not for Publication ■ U		a. County	San Dieg	10	
and (P2b and P2c or P2d. Attach a Location *b. USGS 7.5' Quad Point Loma			1/a of	1/4 of Sec	B.M.
c. Address <u>1531-1541</u> Broadwa	y (East)	City _	San Diego	Zip	92101
d. UTM: (Give more than one	for large or	linear resour	ces) Zone	11; r	nE/mN
e. Other Locational Data (e.g., parcel # APN: 534-352-04-00, Block			c., as appropri	ate):	
*P3a Description (Describe resource and	its major elements	Include design in	natarials cond	ition alterations	size setting

Originally constructed in 1918 for capitalist James E. Collumb, this two-story utilitarian structure has a general rectangular shaped plan and is adjoined to a smaller one-story building in the same style on the north west elevation. These buildings are collectively identified as 1531-1541 Broadway. Features include a flat roof with stepped parapets and coping, large plate glass windows on the ground floor, and multi-paned industrial style windows on the second floor. Exterior building materials consist of plastered brick and stucco for the walls, ceramic tile surrounding the lower portions of the ground floor windows, and most likely composition rolls for the roof. Clerestory windows have been in-filled, however the frame outlines are still present. Overall, the building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP6

*P4. Resources Present: • Building D
Structure □ Object a Site □ District □
Element of District □ Other (Isolates, etc.)
P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

□ Prehistoric □ Both

1918

1958 Centre City East Historic Site Inventory

*P7. Owner and Address:

Jerome Navarra Family Trust 08-31-88/
Navarra Family Trust et al. 12-16-86
1401 E Street

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev & Scott A. Moomjian, Office of Marie Burke Lia, 427 C Street.
Ste. 416, San Diego, CA 92101

*P9. Date Recorded: October 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre City East For Centre City Development Corporation</u>

Attachments: □NONE □ Location Map n Sketch Map □Continuation Sheet • Building, Structure, and Object Record □ Archaeological Record □ District Record n Linear Resource Record □ Milling Station Record n Rock Art Record n Artifact Record n Photograph Record o Other (List):

State of California — The Resources Agency	
DEPARTMENT OF PARKS AND RECREATION	ĺ

Primary	#		
HRI# _	2138-0187-0000		

BUI	LDING, STRUCTURE, AND OBJECT RECORD
Page_	2 of 2 *NRHP Status Code.7
*Reso	ource Name or # (Assigned by recorder) 1531-1541 Broadway (East), San Dieao. CA 92101
B1.	Historic Name: J.F. McKnight Block
B2.	Common Name:
B3.	Original Use: Commercial (Automobile Dealership B4. Present Use: Commercial
*B5.	Architectural Style: Utilitarian
	Construction History: (Construction date, alternations, and date of alterations) Constructed in 1918; no substantial modifications and/or alterations noted.
*B7.	Moved? No
*B8.	Related Features:
	Architect: <u>Eugene Hoffman</u> b. Builder: <u>Unknown</u> Significance: Theme Architecture Area San Diego Period of Significance 1918_

Property Type Residential Applicable Criteria C_ (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Originally constructed in 1918 and designed by architect Eugene Hoffman, the 1531-1541 Broadway buildings were previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation reveals past owners of the 1531-1541 Broadway buildings include: James E. Collumb, for whom the building was constructed (1918) and the Cycloid Engineering Corporation (1988). Past documentation reveals that the 1531-1541 Broadway buildings were "Built for the Studebaker agency of J.F. McKnight in 1918[,]...one of the many sales and services facilities mushrooming up in the city before 1920." (Lia & Brandes:1988) San Diego City Directories reveal that past proprietors of the 1531-1541 Broadway buildings (identified as 1541, no listing for 1531) include: El Cortez Pontiac Co. (1944/45 to c.1950), Kasey Pontiac (c.1955-c.1970), and American Business College (c.1975-c.1988).

Historical research has determined that the 1531-1541 Broadway buildings are not historically significant, as they have not been directly associated with any important events or individuals in terms of local, state, or national history. However, the 1531-1541 Broadway buildings do appear to be architecturally significant for embodying the distinctive characteristics of a type, period, or method of Utilitarian construction. In addition, the 1531-1541 Broadway buildings were designed by prominent architect Eugene M. Hoffman. Further research is necessary to determine whether the structure embodies the distinctive characteristics of a type, period or method of construction. Such a determination will dictate whether the resource is eligible for listing on the local register.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

Longstreth, Richard, The **Buildings** of main Street; A Guide To American Commercial **Architecture**, 1987. Rifkind, Carol, A Field Guide To American Architecture, 1980.

San Diego City Directories

San Diego County Recorders Office


B13. Remarks:

Collumb and Hoffman collaborated in later years, for the construction of the Barcelona Apartments.

*B14. Evaluator: <u>Wendy L. Tinsley, Scott A. Moomjian,</u>
Office of Marie Burke Lia

Date of Evaluation: October 2001

(This space reserved for official comments.)





C-3

Primary #	
HRI # 2138-0188-0000	
Trinomial	t .
NRHP Status Code 5S2	

PRIM	IARY RECORD	i rinomiai
		NRHP Status Code 5S2
	Other listings Updat	te of November 1988 Centre City East Survey Documentation
	75	Reviewer Date
Page _	1 of 3 *Resource Name or #: (Ass	signed by recorder) 1640 Broadway
P1.	Other Identifier:	
*P2.	Location: □ Not for Publication ■ Unrestricted *	a. County San Diego
	2b and P2c or P2d. Attach a Location Map as neces	
*b. US	GGS 7.5' Quad Point Loma Date	T; R; ¼ of Sec; B.M
c.		City San Dieao Zip 92101
d.	Other Locational Data (e.g., parcel #, directions to	or linear resources) Zone 11;mE/mM
e.	APN: 534-224-04-00, Gardner's Addit	
*P3a.		nents. Include design, materials, condition, alterations, size, setting
	and boundaries):	-
featuri The pe buildin entran	ing framed panels, and belt coursing above enthouse portion also features an extended ing is rectangular in shape and symmetrice flanked by wood molding and shaded about knee braces' that extend past the balcony	d cornice with paired brackets, a roof line balustrade between the third-floor windows and the cornice line. It cornice, paired brackets, and a raised parapet. The cal in design and features a recessed, center from the cornice by a second floor balcony that is supported by two value. (See DPR 523H, Continuation Sheet for more
		P2h Posource Attributes: // ict attributes
		P3b. Resource Attributes: (List attributes and codes) HP3 . HP5
		*P4. Resources Present: Building
		Structure Object Site District
		Element of District Other (Isolates, etc.) P5b. Description of Photo: (View, date accession #)
		*P6. Date Constructed/Age and Sources:
4		• Historic
4600		□ Prehistoric □ Both
13		1912 1988 Centre City East Historic Site Inventor
- 2	THELL	*P7. Owner and Address:
TANKS I		Daniel Furlan, C/o CSR 1640 Broadway
TA.		San Diego, CA 92101
1		*P8. Recorded by (Name, affiliation, and
5.0		address): Wendy L. Tinsley, Scott A. Moomjian, Office of Marie
		Burke Lia, Attorney at Law. 427
		C Street, Ste. 416. San Diego
*D0	Data Basardada Oatabar 2001 / Oyunar	Information and Photo Undeted June 2002
*P9. *P10.		Information and Photo Updated June 2003
		Survey: (Describe) (Describe) s, or enter "none".) Historic Site Inventory of Centre
City		ity Development Corporation
		tinuation Sheet Building, Structure, and Object Record
		urce Record n Milling Station Record □ Rock Art Record

n Artifact Record n Photograph Record a Other (List): __

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION

Primary #	
HRI# <u>2138-0188-0000</u>	

BUILDING, STRUCTURE, AND OBJECT RECORD

Page _ 2 _ of _ 3

*NRHP Status Code 5S2

*Resource Name or # (Assigned by recorder) 1640 Broadway, San Diego, CA 92101

B1. Historic Name: St. Anthony Apartment Hotel

B2. Common Name: Broadway Manor

B3. Original Use: Hotel/Apartments B4. Present Use: Residential (Multi-Family)

*B5. Architectural Style: High Style Italian Renaissance

*B6. Construction History: (Construction date, alternations, and date of alterations)

Originally constructed in 1912, original windows replaced, new exterior stucco/painting, entry doors replaced (dates unknown), this building has been recently renovated c. 1990s.

*B8. Related Features:

B9a. Architect: Unknown b. Builder: Carter Construction Company

*B10. Significance: Theme Architecture Area San Diego Period of Significance 1912_

Property Type Residential Applicable Criteria C_

(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Originally constructed in 1912, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. According to past documentation, an advertisement in the San Diego Union for the 1640 Broadway building claimed it featured amusement rooms, a sun parlor, steam heat, a ballroom, and "the latest improvements and furnishings including private baths and telephones in all apartments." (Lia/Brandes: 1988) San Diego City Directories reveal the 1640 Broadway building was known as the "St. Anthony Apartment Hotel/St. Anthony Apartments (from completion of construction in July 1912 through approximately 1944/1945) featuring approximately 24 listed units, the "Broadway Manor" (1950) featuring approximately 26 listed units, the "Broadway Manor Hotel" and "Broadway Top Hat Cocktail Lounge" with proprietor Richard S. Hoarala (1955), the "Broadway Manor Apartments" featuring approximately 25-30 listed units and the "Broadway Top Hat Tavern/Cocktail Lounge" (1960, 1965, 1970, 1975, 1980, 1984). (See DPR 523H, Continuation Sheet for an incomplete listing of the 1640 Broadway building residents)

Historical research has determined that this building is not historically significant, as it has not been associated with any significant **persons** or events, at a local, state, or national level. In addition, the identity of the architect could not be ascertained, and as such, the 1640 Broadway building does not appear to represent the work of a master architect, nor that of an important, creative individual. The 1640 Broadway building, however, is architecturally significant at the local level, as a **building** which embodies the distinctive **characteristics** of a type, period, and method of High Italian Renaissance **construction**.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)


(See DPR 523H, Continuation Sheet for more information)

B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley, Scott A. Moomijan,
Office of Marie Burke Lia

Date of Evaluation: October 2001

(This space reserved for official comments.)



DPR 523B (1/95)

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION

CONTINUATION SHEET

Primary #		
HRI #/Trinomial_	2138-0188-0000	

Continuation
 Update

Page3 of	3				
Resource Identifier:	(Assigned by recorder)	1640 Broadway,	San Diego,	CA 92101	_
Historic Name:	St. Anthony Apartm	ent Hotel			

*P3a. Description (Continued):

The entry door to the **second** floor balcony is also bordered by wood molding and features a projecting lentil with some ornamentation above. Fenestration consists of alternating double-hung and slider style windows on the north street facing elevation. An awning is visible on the west elevation of the **fourth-floor** penthouse. Overall, this building appears to be in excellent condition.

*B10. Significance (Continued):

Past residents of the 1640 Broadway building include:

1944/1945: Adolph Anderson; Mrs. Rita Baird; W.G. Barnes; C.J. Burr; R.E. Cole; Harold Collins; Larry Denton; M.J. Engles; A.V. Erickson; Beatrice Feinberg; R.D. Fifer; H.D. Gilbert; I.G. Gunnell; Bessie Hammond; Val Lane; C.B. Litchen; Mrs. E.V. Mereer; G.T. Merriwether; Mrs. Hattie Moore; Mrs. A.J. Nippell; W.E. Senger; Georgia Stone; Mrs. M.D. Taylor; and Lee Worthy.

1950: Henry Beese; Mrs. Meredith Bromfield; C.W. Brown; B.D. Carnie; Lewis Cruikshank; Max Feinberg; R.D. Fifer; A.G. Franch; J.E. Gardner; Thomas Henderson Liquors; John Hogan; John Jarrett; Carolyn Kindstrom; W.M. Lindsey; Fred Linerode; Samuel Lorchak; Felix Matte; Mrs. June Moore; Toni Moran; R.R. Padriza, Harry Reed; Margeret Selway; Louise E. Smith; R.C. Smith; Mrs. Billie Tabler; and Roger Wessell.

1960: 1) Mrs. Helen B. Flanagan; 2) John Peterson; 3) Van Seggeren; 4) Edward Grady; 5) John Lark; 6) Mrs. Ruby Lee; 7) Gerald English; 8) May Watson; 11) Mrs. Bessie Y. Dickenson; 12) Leo Armstrong; 14) Woodrow W. Herald; 15) vacant; 16) Manuel Nunes; 17) Robert A. Teague; 18) vacant; 19) Patricia K. Yung; 21) vacant; 22) James Wells; 24) vacant; 25) vacant; 26) James Elliott; 27) Robert Getty; 28) George Ten-Eyek; 29) Edward Bochefer; and 44) Jack Hardeman.

1965: Twenty-Five units listed A through Z, with the exception of unit I.

1969/1970: Twenty-Nine units listed as 1-30, with the exception of unit numbers 3, 10, 13, 20, and 23. Unit numbers 11, 24, and 26 were listed as being vacant.

1975: Twenty-Nine units listed as 1-30, with the exception of unit number 13. Five units were listed vacant.

*B12. References (Continued):

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office

DPR 523H (1/95)

PRIMARY RECORD

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary #	
PRIMARY RECORD	Trinomial	
Review Code	Reviewer Date	
Page1 of _3 *Resource Name or #(Assigned b) P1. Other Identifier:College Inn	by recorder) 109-113 West C Street	
*P2. Location: a Not for Publication Unrestricted *	a. County San Diego	
and (P2b and P2c or P2d. Attach a Location Map as necessary. *b. USGS 7.5' Quad Point Loma Date c. Address109-113 West C Street CitySan		
d. UTM: (Give more than one for large or l	inear resources) Zone;mE/mN	
e. Other Locational Data (e.g., parcel #, directions to reso Block G, Lot L, Map D Book 13, page 522		

Block G, Lot L, *P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This One-Part Commercial Block Art Deco building appears to have been constructed c.1928. Rectangular in shape, the building has a flat roof with a variety of parapets and decorative molding both along the parapets tapering, in some cases, underneath the roof line. The exterior consists of stucco. Bands of decorative molding, with in some instances, square shapes, frame much of the storefront entrance areas and upper sections. Storefronts include fixed glass, flanked by glass doors and paneled transoms and decorative tile at the base. The entire building serves a variety of different tenants. Projecting steel canopies, supported by cables, are located above the storefronts along the north and east elevations. Despite the fact that the building has been altered from its original appearance (see pages 2 and 3), the building still retains enough Art Deco character-defining features to convey significance. Overall, the building appears to be in good condition.

P3b. Resource Attributes: (List attributes and codes) HP6

*P4. Resources Prese	ent: Building
D Structure Object	Site District
Element of District Ot P5b. Description of Phaccession#)	, ,
*P6. Date Constructed/A	ge and Sources:
D Prehistoric	D Both

Sanborn Fire Insurance Maps San Diego City Directories *P7. Owner and Address: College Inn Irrevocable Trust & College Inn Partnership

5300 Marlborough Drive San Diego, CA 92116 *P8. Recorded by (Name, affiliation, and address): Office of Marie Burke

Lia, 427 C Street. Suite 416, San Diego, California 92101

*P10. Type of Survey: (Describe)

Intensive

Date Recorded: October 2003

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Resources Inventory Update Of The Core Area For Centre City Development Corporation


Attachments: □NONE □Location Map □Sketch Map ■Continuation Sheet ■Building, Structure, and Object Record □Archaeological Record □District Record □Linear Resource Record □Milling Station Record □Rock Art Record □Artifact Record □Photograph Record □ Other (List): __

State of California — The Resources Agency Primary # _ DEPARTMENT OF PARKS AND RECREATION HRI#	
BUILDING, STRUCTURE, AND OBJECT RECO	RD
Page 2 of 3 *NRHP Sta	atus Code
*Resource Name or # (Assigned by recorder) 109-113 West C S	Street
B1. Historic Name:College Inn	
B2. Common Name: Grab and Go Subs	
B3. Original Use: Commercial B4. Present Use: Commercia	
"B5. Architectural Style: One-Part Commercial Block Art*B6. Construction History: (Construction date, alternations, and date	of alterations)
Constructed c.1928. Numerous improvements since at leas and interior and exterior. Some of these changes include interior openings closed and building re-plastered (1968); installation conversion of building from copy shop to restaurant (1985); rehalf of other tenant improvements to the interior and exterior (between the conversion of	erior alterations (1957); new roof added (1963); of signage (1969); installation of window (1978); abilitation of building (1989); and an assortment
*B7. Moved? No DYes Unknown Date:	Original Location:
*B8. Related Features: None	9
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: Theme Architecture	Area <u>Centre City (Core)</u>
Period of Significance c.1928 Property Type	
(Discuss importance in terms of historical or architecti	
geographic scope. Also address integrity.)	arai comox do domica by atomo, portou, and
Historical research indicates that this building was constructed c. 1928. San story building as a restaurant and saloon with wood truss and brick. San Diego Cit by the County Assessor. Over the years, consistent with changes in building use, over the years identified between 109-113 West C Street have included the Colle College Inn Cocktails (1960); County Assessor (1929-1930); Kiltry Bonding Age Historical research indicates that this building is architecturally significant. individuals in terms of local, state, or national history. However, the building d method of commercial Art Deco construction despite the fact that the building has be does not represent the work of a master architect, builder, craftsman, or important	ry Directories first list the building in 1929 when it was occupied the structure was altered. Subsequent occupants of the buildir rige Inn (1935-1945); College Inn Cafe & Liquors (1950-1952 ency (1960); and the AAAA Bonding Agency (1960). The building was not associated with any important events or ones embody the distinctive characteristics of a type, period, and the peen modified from its original appearance. Finally, the building
any further information potential.	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list)	
City of San Diego, Building Department Permit	
Records.	(Sketch Map with north arrow required.)
City of San Diego, Water & Sewer Records.	
McAlester, Virginia & Lee, A Field Guide To	
American Houses, 2000.	100 100
Sanborn Fire Insurance Maps, 1887, 1888, 1906,	A (1) (10) L
1921, 1940, 1956.	AVE.
San Diego City and County Directories.	258
B13. Remarks: *B14. Evaluator: Office of Marie Burke Lia	(0)
Date of Evaluation: October 2003	
	0 4 (3) 1
(This space reserved for official comments.)	
	1
	1"=100'
	th .

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION

CONTINUATION SHEET	Primary # HRI #
	Trinomial
Page 3of 3_ *Resource Name or # (Assign	ed by recorder) 109-113 West C Street_
	ed by recorder) 109-113 West C Street_ke LiaDate October 2003

 $Historic \ Photograph \ (Date \ Unknown) \ \#5-608 \ "College \ Inn"; Photograph \ Courtesy \ Of \ The \ San \ Diego \ Historical \ Society \ Photographic \ Photograph \ Courtesy \ Of \ The \ San \ Diego \ Historical \ Society \ Photographic \ Photograph \ Courtesy \ Of \ The \ San \ Diego \ Historical \ Society \ Photographic \ Photograph \ Courtesy \ Of \ The \ San \ Diego \ Historical \ Society \ Photographic \ Photograph \ Courtesy \ Of \ The \ San \ Diego \ Historical \ Society \ Photographic \ Photograph \ Courtesy \ Of \ The \ San \ Diego \ Historical \ Society \ Photographic \ Photograph \ Photograph$ Collection



Primary #	
HRI #	
Trinomial	
NIDUD Ctatus Carla 552	

DEPARTMENT OF PARKS AND RECREATI	JN	пп #		
PRIMARY RECORD		Trinomial		
	Other Listings Update	e of November 1988	Centre City Eas	t Survey Documentation
	Review Code	Reviewer		Date
Page1 of2 *Resource P1. Other Identifier:	• Name or #: (Assigned	ed by recorder) 1	317 C Street	<u> </u>
*P2. Location: a Not for Publication	Unrestricted *	a. County	San Diego	
and (P2b and P2c or P2d. Attach a Location*b. USGS 7.5' Quad Point Loma			¼ of¼ of	Sec; B.M
c. Address <u>1317 C Street</u>	City	San Diego		Zip <u>92101</u>
d. UTM: (Give more than one	for large or	linear resourc	es) Zone 11;	mE/mN
e. Other Locational Data (e.g., parce APN: 534-205-02-00, Thor				
*P3a. Description (Describe resource a and boundaries):	nd its major elements	s. Include design, ma	aterials, condition,	alterations, size, setting

Originally constructed in 1887 on a steeply sloped lot, this two-story, single-family residence was designed in a Folk National architectural style, and the house itself is accessed through a short wooden bridge located between the sidewalk and the front entrance of the residence located on the second floor. It appears to have been modified through a rear addition. The residence features a symmetrical design, and a moderately pitched, hipped roof with a boxed cornice and a plain frieze. Exterior building materials consist of horizontal shiplap siding with corner boards for the exterior walls, and composition shingles for the roof. Windows appear to be single-hung or double-hung sash and feature wood surrounds. A small partial porch area is present at the front entrance and features an ornamental, centered, hipped roof supported by two wood posts. Overall, the 1317 C Street residence appears to be in good condition.



P3b. Resou	rce Attributes:	(List	attributes
and codes)	HP3		

*P4. Resources Present: • Building Structure

Object

Site

District Element of District a Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession#)

*P6. Date Constructed/Age and Sources:

- Historic
- □ Prehistoric 1887
- □ Both

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Woon H. Ping_

1305 C Street

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley,

Office of Marie Burke Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

February 2001 / Photo Updated June 2003 *P9. Date Recorded:

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre</u> <u>City East For Centre City Development Corporation</u>

Attachments: PNONE n Location Map n Sketch Map n Continuation Sheet • Building, Structure, and Object Record n Archaeological Record n District Record n Linear Resource Record n Milling Station Record □ Rock Art Record n Artifact Record n Photograph Record n Other (List):

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION Primary # HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD
Page 2 of 2 *NRHP Status Code_ 5S2
*Resource Name or # (Assigned by recorder) 1317 C Street, San Diego, CA 92101
B1. Historic Name: R.S. Smith Residence
B2. Common Name: Woon House
B3. Original Use: Residential (Single-Family) B4. Present Use: Residential (Multi-Family)
*B5. Architectural Style: Pyramidal Folk National
*B6. Construction History: (Construction date, alternations, and date of alterations) Constructed in 1887; rear addition and residence subdivided into multiple units (dates unknown).
*B7. Moved? No PYes Unknown Date: Original Location:
*B8. Related Features:
B9a. Architect: <u>Unknown</u> b. Builder: <u>R.S. Smith</u>
*B 10. Significance: Theme Architecture Area San Diego Period of Significance 1887_
Property Type Residential Applicable Criteria C_ (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)
Originally constructed in 1887, this residence was previously documented in November 1988 under
the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation reveals past
owners of the 1317 C Street residence include: carpenter R.S. Smith (1887), entrepeneur W.W. Whitney
(1893), W.W. Johnston (c.1923), and Effie Bumgarner (c.1950). San Diego City Directories reveal past
residents of 1317 C Street include: Alta A. Smith (1944/1945), owner Burns Bumgarner and E.R. Niles (1950), Mrs. Edna Vivian (unit a, 1955), Earl R. Niles (unit b, 1955 thru 1969/1970), R.D. Overton
(1317 %, 1955 thru 1965), Verda Chase (unit a, 1960), James C. Chase (1965 thru 1975), Ernest Varner
(unit b, 1975), Jose R. Daniels (1317 1/2, 1969/1970), Ernest Varner (unit b, 1975), and Victor Hooker

Historical research has determined that the 1317 C Street building is not historically significant, as the building is not associated with any important events or individuals in terms of local, state, or national history. However, the 1317 C Street residence does appear to be architecturally significant, at the local level, as a building which embodies the distinctive characteristics of a type, period, or method of Folk National construction. Constructed by R.S. Smith, the 1317 C Street residence does not represent the work of a master architect, master builder, or master craftsman, nor that of an important, creative individual.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office

B13, Remarks:


(unit c, 1975).

*B14. Evaluator: Wendy L. Tinsley,

Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION

PRIMARY RECORD

and boundaries):

Primary #	
HRI #	
Trinomial	
UDUD OLIVE OF LE FCO	

PRIMARY RECORD	I rinoi	mıaı		
	NRHP Status Code 5S2			
	Other Listings Update of No	vember 1988 Centre (City East Survey Documen	tation
	Review CodeRe	eviewer	Date	
Page1 of2 *Resource	e Name or #: (Assigned by	recorder) 1321 C	Street	
21. Other Identifier:				
P2. Location: Dot for Publication	Unrestricted * a	. County San D:	iego	
and (P2b and P2c or P2d. Attach a Location				
'b. USGS 7.5' Quad Point Loma_	TT	_; R;¼ of_		_ B.M
c. Address <u>1321 C Street</u>	City San	n Diego	Zip9210	1
d. UTM: (Give more than on	e for large or linear	r resources) Zor	ne 11; mE/ _	mN
e. Other Locational Data (e.g., parce	el #, directions to resource, el	levation, etc., as appro	opriate):	
APN: 534-205-02-00, Thomas	Resub., Block 27, Lots	3 20 thru 22		

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting,

Originally constructed in approximately 1887, this two-story, multiple-family residence was constructed on a steeply sloping lot, in a layout similar to the neighboring 1317 and 1333 C Street residences. Features of the residence include a moderately pitched, front gabled roof with a slight, enclosed eave overhang. Exterior building materials consist of composition shingles for the roof, fish scale shingles on the gabled portion of the exterior wall down from the roof line, vertical board and batten siding on the street level second floor exterior walls, and horizontal shiplap siding on the first floor exterior walls. A centered front porch is present on the second story, street level of the residence. It features a shed style roof with composition shingles, supportive spindle posts, wood railing, and remmants of brackets and stick work. Rear additions have been made to the building. Overall, the 1321 C Street building appears to be in fair condition.



P3b. Resource Attributes: (List attributes and codes) __HP3___

*P4. Resources Present: • Building a Structure a Object a Site a District □ Element of District □ Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

□ Prehistoric

a Both

c.1887

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Woon H. Ping_

1305 C Street

San Diego, CA 92101_

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev.
Office of Marie Burke Lia,

Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

#FDO	Data Dasandad.	T - 1	2001
*P9.	Date Recorded:	February	2001

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre</u>
City Fast For The Centre City Development Corporation

City East For The Centre City Development Corporation

Attachments: □NONE □ Location Map □ Sketch Map □Continuation Sheet ■ Building, Structure, and Object Record D Archaeological Record □ District Record □ Linear Resource Record □ Milling Station Record □ Rock Art Record

D Artifact Record n Photograph Record D Other (List):

BUILDING, STRUCTURE, AND OBJECT RECO Page 2 of 2 *NRHP Sta	
*Resource Name or # (Assigned by recorder) 1321 C Street,	San Diego CA 92101
B1. Historic Name:	
B2. Common Name:	
B3. Original Use: Residential (Single-Family) B4. Pre	esent Use: Residential (Multi-Family)
*B5. Architectural Style: Folk Victorian	
*B6. Construction History: (Construction date, alternations, and date of Constructed in c.1887; no substantial modifications	of alterations)
*B7. Moved? B No Gyes Gunknown Date: O	Original Location:
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	D : 1 (0: " 1007
*B 10. Significance: Theme Architecture Area San Diego Property Type Residential Applicable Cr	
(Discuss importance in terms of historical or architectural context as defined by theme, pe	
Originally constructed in c.1887, this residence was a the supervision of the Office of Marie Lia and Dr. Ray Browners of the 1321 C Street property includes original officer, R.A. Thomas (pre-1886), and San Diego-Yuma stag Diego City Directories reveal past residents of 1321 C S Earrio (1944/1945), Mrs. C.B. Bomback and Mrs. Opal Keys (A. Barris (unit b, 1955), Mattie W. Browner (unit a, 1960), Chekis (unit a, 1965), Helen Wilcome (unit b, 1965), vac. 1970), Yuen Loui (1975), Arturo Lujan (unit a, 1980 and 19 Lupe Sanchez (unit b, 1984).	previously documented in November 1988 under randes. Previous documentation reveals past First National Bank building builder, and ge line agent George H. Bower (1886). San Street include: Mrs. Violet Burton and F.A. (1950), James F. Sager (unit a, 1955), Frank), Mrs. Leila Bumgarner (unit b, 1960), John ant (unit a, 1970), Kelly Escobedo (unit b,
Historical research has determined that the 1321 significant, as the building is not associated with any illocal, state, or national history. However, the 132 architecturally significant , at the local level, as a characteristics of a type, period, or method of Folk Victarchitect could not be ascertained, the 1321 C Street is master architect or craftsman.	important events or individuals in terms of 21 C Street residence does appear to be a building which embodies the distinctive torian construction. As the identity of the
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list)	
Lia and Brandes, Historic Site Inventory of Centre	e City East, 1988.
McAlester, Virginia & Lee, A Field Guide To Americ	_
San Diego City Directories	
San Diego County Recorders Office	(Sketch Man Ath north arrow required.)
B13. Remarks:	
	, c ST.
*B14. Evaluator: Wendy I. Tinsley	DB I3 PG 522
Office of Marie Burke Lia	225
Date of Evaluation: February 2001	1 24 23 22 21 20 N N 16 17 0 10
	, D D D D B
(This space reserved for official comments.)	205
(This space reserved for official confinients.)	II 10 (5) 15
	10 14
	1 2 9 13 1 1 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7

PRIMARY RECORD

Primary #	
HRI #	
Trinomial	
NRHP Status Code 5S2	

Other Listings	Update	of November	1988	Centre	City East	Survey Documenta	tion
Review Code		Reviewer				Date	

Page __1__ of __2__ *Resource Name or #: (Assigned by recorder) 1333 C Street______

P1. Other Identifier:

*P2. Location: a Not for Publication ■ Unrestricted *

a. County San Diego_______

and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma Date T ___; R ___; ___ 4 of ___ 4 of Sec___; ____ B.M.

c. Address 1333 C Street City San Diego Zip 92101

d. UTM: (Give more than one for large or linear resources) Zone 11; ___ mE/ ___mN

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 534-205-03-00, Thomas Resub., Block 27, Lot 19

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1894, this two-story residence is located on a steeply sloped lot and is similar in layout to the neighboring 1317 and 1321 C Street residences. Designed in a Folk Victorian architectural style, the residence has a moderately pitched, cross gabled roof with no eave overhang, an angled bay window with a hipped roof and an entrance porch featuring wood railing, wood work along the porch eave and two wood posts for support. It appears that the original spindlework has been replaced with plain wood work that is present today. Exterior building materials consist of composition shingles for the roof and shiplap siding for the exterior walls. Windows appear to be double-hung sash and feature wood **surrounds**. Metal security bars cover the lower portions of the windows on the north, street facing elevation. Overall, the residence appears to be in fair condition.



P3b. Resource Attributes: (List attributes and codes) HP3_

*P4. Resources Present: • Building □
Structure a Object a Site □ District □
Element of District a Other (Isolates, etc.)
P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

n Prehistoric n Both 1894

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Woon H. Ping

1333 C Street

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley
Office of Marie Burke Lia,
Attorney at Law, 427 C Street,

Attorney at Law, 427 C Street, Ste. 416. San Diego, CA 92101

*P9. Date Recorded: February 2001 / Photo Updated June 2003

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre City East For Centre City Development Corporation</u>

Attachments: ¬NONE n Location Map n Sketch Map ¬ Continuation Sheet ■ Building, Structure, and Object Record n Archaeological Record n District Record n Linear Resource Record ¬ Milling Station Record ¬ Rock Art Record n Artifact Record n Photograph Record n Other (List):

BUILDING, STRUCTURE, AND OBJECT RECO	No. on
	ntus Code_ 5S2
*Resource Name or # (Assigned by recorder)1333 C Street,	San Diego, CA 92101
B1. Historic Name: Porter Long House	
B2. Common Name:	
B3. Original Use: Residential (Single-Family) B4. P	resent Use: Residential (Multi-Family)
*B5. Architectural Style: Folk Victorian	
*B6. Construction History: (Construction date, alternations, and date of Constructed in approximately 1894; Possible rear ad-	
*B7. Moved? No □Yes □Unknown Date:	
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
	Period of Significance 1894_
Property Type Residential Applicable C (Discuss importance in terms of historical or architectural context as defined by theme, po	
Originally constructed in 1894, this residence was the supervision of the Office of Marie Lia and Dr. Ray Bowners of the 1321 C Street building include: Porter Long and John and Mary Graham (1907 to at least 1911). San Dof 1333 C Street include: Juanita Hopkins and Mrs. Lottic Mrs. Fern Reynolds (1950), Howard McCormick (1955), Lec Frank Lima (1965), Luis Ramos-Graulau (unit a , 1970), Brannon (unit a, 1975), Joe Mendoza (unit b, 1975). Historical research has determined that the 133 significant, as the building is not associated with any local, state, or national history. However, it does appellocal level, as a building which embodies the distinctive of Folk Victorian construction. As the identity of the acceptable of the second structure of the second structure of the second structure. Additional Resource Attributes: (List attributes and codes)	randes. Previous documentation reveals past (1894), Emil and Anna Huefner (1901-1907) riego City Directories reveal past residents to Thurman (1944/1945), Mrs. A.J. Abbott and Precio Aguilar and Mrs. Rose Womack (1960) Robert D. Miller (unit b, 1970), and Ginger B. C. Street building is not historically important events or individuals in terms of the characteristics of a type, period, or method richitect could not be ascertained, the 1333
*B12. References: (partial list) Lia and Brandes, Historic Site Inventory of Centre McAlester, Virginia & Lee, A Field Guide To Americ San Diego City Directories San Diego County Recorders Office	
B13. Remarks:	(Sketch Map with north arrow required.)
	(Silver in the silver in the s
*B14. Evaluator: Wendy L. Tinsley,	
Office of Marie Burke Lia	

*B14. Evaluator: Wendy L. Tinsley,
Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)

e.

Primary #	
HRI #	
Trinomial	
NDLID Ctatus Cada C7	

PRIMARY RECORD	Т	rinomial		
2	N	RHP Status Cod	de6Z	
	Other Listings Update o	f November 198	38 Centre City East	t Survey Documentatio
	Review Code	Reviewer		Date
Page1 of4 *Resource	Name or #: (Assigned	by recorder)	1343-1345 C S	street
P1. Other Identifier:				
*P2. Location: a Not for Publication ■	Unrestricted *	a. County	San Diego	
and (P2b and P2c or P2d. Attach a Location				
*b. USGS 7.5' Quad Point Loma_	DateT_	; R;	¼ of¼ of	Sec; B.N
c. Address <u>1343-1345 C Str</u>	eet(City	San Diego	Zip92101
d. UTM: (Give more than one	for large or lin	near resour	ces) Zone 11;	mE/ml

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 534-205-12-00, Thomas Resub., Block 27, Lots 17 & 18 *P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

The two buildings shown in the photograph below are identified as 1343-1345 C Street. It is believed that these buildings were originally not associated with one another, and that they were eventually adjoined through a central staircase. The east Victorian portion was constructed in approximately 1887, and has a general rectangular shaped plan with a moderately pitched front gabled roof, and a slight enclosed eave overhang. Exterior building materials consist of composition shingles for the roof, clapboard siding for the east facade and shiplap siding for the north facade. It is a two-story, mixed-use building with residential units upstairs and commercial storefront space on the ground floor. (See DPR 523H, Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes

and codes) HP3, HP6

Resources Present: • Building a Structure a Object

Site a District Element of District P Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

Prehistoric

□ Both

c.1887/pre-1921 1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Ward. Betty D.

P.O. Box $1206\overline{63}$

San Diego. CA 92112

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, of Marie Burke Lia, Office Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

Date Recorded: February 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: P NONE P Location Map Sketch Map Continuation Sheet I Building, Structure, and Object Record n Archaeological Record P District Record P Linear Resource Record P Milling Station Record a Rock Art Record ☐ Artifact Record P Photograph Record P Other (List):

State of California — The Resources Agency Primary # DEPARTMENT OF PARKS AND RECREATION HRI#	
BUILDING, STRUCTURE, AND OBJECT RECO	
	atus Code 6Z
*Resource Name or # (Assigned by recorder) 1343 C Street,	
B1. Historic Name: S.R. Williams Home	
B2. Common Name:	
B3. Original Use: Residential B4. Present Use: Mixed-U	Jse (Commercial & Residential)
*B5. Architectural Style: Victorian portion/Enframed Wi	
*B6. Construction History: (Construction date, alternations, and date	of alterations)
Constructed in 1887; no substantial modifications	and/or alterations noted.
*B7. Moved? • No	Original Location:
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: Theme N/A Area <u>San Diego</u> F	
PropertyType _Residential/Commercial A	
(Discuss importance in terms of historical or architectural context as defined by theme, p	eriod, and geographic scope. Also address integrity.)
Originally constructed in 1887, the Victorian port previously documented in November 1988 under the supervious Brandes. Previous documentation reveals past owners of Williams (1887), Lona Johnston (1893), and various member Diego City Directories reveal that the 1343 C Street Creston" c.1944/1945 to 1950, with Mrs. D.TJ. Lord lists C Street is listed as "Creston Apartments," with Louis C 1975 1343 C Street is listed as "Creston Apartments Hote units (1-10) depending on the year. 1965 listings include and Louis C. Thielke (unit four). 1970 listings revea units five and six were not listed. 1975 listings include two), Joe O'Neal (unit three), David Stafford (unit four (unit 7a), Glenn Bradford (unit eight), Andrew Ramos (unit 7a), Glenn Bradford (unit eight), Andrew Ramos (unit 7a), state, or national history. Moreover, they do not a type, period, or method of either the Victorian architectural of construction, and do not represent the work of	sion of the Office of Marie Lia and Dr. Ray f the 1343 C Street building include: S.R. Its of the Johnston family through 1965. San building was used as a rooming house, "The ed as the proprietor. From 1955 to 1960 1343 C. Thielke as the proprietor. From 1965 thrue 1," consisting of approximately less than tene: vacant (unit one), Cavite Leet (unit two), I that units four and seven were vacant and E: Cyrus Wright (unit one), Cavite Leet (unit or), Andrew Savage (unit seven), Juan Maldano unit nine), and Larry Lauber (unit ten). S C Street buildings are neither historically relisting on the local, state, and national important events or individuals in terms of out embody the distinctive characteristics of nitectural style or the Enframed Window Hall
B1 1. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list) (See DPR 523H, Continuation Sheet for more information)	(Sketch Map with north arrow required.)
B13. Remarks:	
bio. Remarks.	, C ST.
	D8 I3 PG 522
B14. Evaluator: Wendy L. Tinsley,	, W 211
Office of Marie Burke Lia	24 23 22 21 30 10 11 21 30 10
Date of Evaluation: February 2001	
(This space reserved for official comments.)	12 206 15 16 17 17 17 17 17 17 17

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
CONTINUATION SHEET

Primary #	
HRI #/Trinomial .	

Continuation

Update

Page __3 __ of __4__

Resource Identifier: (Assigned by recorder) 1343-1345 C Street, San Diego, CA 92101_

<u>Historic Name: S.R. Williams Home</u>

P3a. Description (Continued):

Several unit entrances are located on the east **facade**, and a two-story deck and staircase is located on the rear, south elevation. The second **floor** features two angled bays on the north **elevation**, and the ground floor features a central recessed entry door between two **storefront** windows. All other windows appear to be **single-or** double-hung sash. Past documentation (**Lia/Brandes: 1988**), and a 1921 **Sanborn** Fire Insurance Map indicate that the central staircase located between the two buildings **provides** access only to the east Victorian building. Overall, this portion of the building appears to be in good condition.

The western two-story Enframed Window Wall portion, was most likely a wood structure which has been stuccoed over in recent years, and the exact construction date is unknown, however, due to a 1921 Sanborn Fire Insurance Map depicting the building, the building was constructed prior to 1921. It also has a rectangular shaped plan, and features a flat roof with a low parapet, <code>single-or-double-hung</code> sash windows around the perimeter, and two, recessed, ground floor entrances flanked by three, almost full length windows, each of which are a single glass pane. Exterior building materials consist of stucco for the exterior walls, most likely composition rolls for the roof and wood trim on north elevation <code>windows</code>.

A 1921 Sanborn Fire Insurance Map also reveals the two buildings were also identified as 1371 and 1373-1375 C Street. (See Map below)

*B12. References (Continued):

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

Longstreth, Richard, The Buildings of Main Street, A Guide To American Commercial Architecture, 1987.

San Diego City Directories
San Diego County Recorders Office



CONTINUATION SHEET

■ Continuation □ Update

4 of 4 Page

Resource Identifier: (Assigned by recorder) 1343-1345 C Street, San Diego, CA 92101 Historic Name: S.R. Williams Home

P3a. **Description** (Continued):

Western portion of the 1343-1345 C Street buildings.



Other Identifier:

Location: □ Not for Publication ■ Unrestricted *

PRIMARY RECORD

Page __1 of __3_

P1. *P2.

rces Agency RECREATION	Primary #			
	NRHP Status Co		5/96_	
Other Listings Upo	date of November 19	88 Centre City East	Survey Documentation	
Review Code	Reviewer		Date	
*Resource Name or #: (Ass	igned by recorder)	1425 C Street		
lication ■ Unrestricted * th a Location Map as necessa		San Diego		

and (P2b and P2c or P2d. Attach a Location Map as necessary T ___; R ___; ___¼ or ___¼ of Sec___; ____ B.M. *b. USGS 7.5' Quad Point Loma Date San Diego_____Zip ____ Address <u>1425-1431 C Street</u> _ City

UTM: (Give more than one for large or linear resources) Zone 11; ___mE/ ___mN d.

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 534-210-12-00, Horton's Addition, Block 179, Lots K thru L W ½ of N 40 Ft Lot J

Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1908, this symmetrical, two-story, apartment building with basement is an excellent example of the early Prairie architectural style that is sometimes referred to as the American Foursquare or the Prairie Box. It has a general rectangular shaped plan and features a low pitched, hipped roof with widely overhanging eaves, and a centered hipped dormer, also with widely overhanging eaves, and a boxed cornice with modillions. This type of hipped dormer is typical of the early vernacular Prairie style. Wide wooden steps ascend to the first floor front porch, which is partially enclosed, has a flat roof with widely overhanging eaves, and features a square pillar covered with wood on the northern corners, as well as, a single Ionic column, also at each northern porch corner. (See DPR 523H, Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes and codes) HP3

*P4. Resources Present: • Building Structure

Object n Site

District n Element of District a Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

n Prehistoric n Both August 1908

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Episcopal Community Services P.O. Box 33168

San Diego, CA 92163_

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Burke Lia. Attorney at Law, 427 C Street. Ste. 416, San Diego. CA 92101

*P9. Date Recorded: February 2001 / Photo Updated June 2003

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) __Historic Site Inventory of Centre City East For The Centre City Development Corporation

Attachments: NONE n Location Map n Sketch Map Continuation Sheet Building, Structure, and Object Record n Archaeological Record D District Record n Linear Resource Record n Milling Station Record D Rock Art Record n Artifact Record n Photograph Record n Other (List):

the same of the sa
State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD
Page 2 of 3 *NRHP Status Code 5S2 *Resource Name or # (Assigned by recorder) 1425 C Street, San Diego, CA 92101
B1. Historic Name:
B3. Original Use: Residential B4. Present Use: Residential
*B5. Architectural Style: Early Prairie
*B6. Construction History: (Construction date, alternations, and date of alterations) Constructed in August 1908; no substantial modifications and/or alterations noted
*B7. Moved? No
*B8. Related Features: B9a. Architect: Unknown b. Builder: C.J. Jones *B 10. Significance: Theme Architecture Area San Diego Period of Significance 1908 Property Type Residential Applicable Criteria C (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)
Originally constructed in 1908 by builder C.J. Jones, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation reveals past owners of the 1425 C Street property and building include: George & Sophi
Bailey (pre-1905), and W.H. Reinhardt (1905). San Diego City Directories reveal that the 1425
Street building was used as a rooming house c.1944/1945 to c.1955, with Mrs. C.D. Holcomb listed a
the proprietor in 1944/1945. Owner Mrs. Lillian Cannon is listed as the proprietor in 1950, and Clyder Bennet (1960). From 1960 thru 1975, 1425 C Street is listed as "Apartments" and "Clubhous
Apartments, consisting of approximately One to Twenty units (1-20) depending on the year. 196
listings include: vacant (units one and two), Albert P. Roach (unit three), and William Carter (unit
four), Albert DeSoto (unit five), vacant (unit six), John Keith (unit seven), Mrs. Betty Spiegel (unit
eight), Mrs. Gertrude King (unit nine), Gerald Conway (unit ten), Frank Sargatz (unit 11), Loui
Mayberry (unit 12), G.E. Arguello (unit 14), Mrs. Carol Montano (unit 15), Mrs. Helen Smith (unit 18)

(See DPR 523H, Continuation Sheet for more information)

D44 A LPC - LD Aud to a district and to a least	
B11. Additional Resource Attributes: (List attributes and codes)	

Lee Harrison (unit 19), vacant (unit 20). 1965 **listings** reveal that **five** units were vacant and units 12, 13, 16, and 17 were not listed. 1970 listings include reveal that unit four was vacant and units 2,6,9,11,13,14 were not listed. 1975 listings for the "Clubhouse Apartments" reveal that of the ten

*B12. References: (partial list)

units (1-10) listed, four units were vacant.

Lia and Brandes, *Historic Site Inventory of Centre City East*, 1988. McAlester, Virginia & Lee, *A Field Guide To American Houses*, 1986.

San Diego City Directories

San Diego County Recorders Office


B13. Remarks:

*B14. Evaluator: Wendy I . Tinsley,

Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



CONTINUATION SHEET

Primary #_____HRI #/Trinomial _____

■ Cont inuat ion
□ Update

Page3 of3_								
Resource Identifier: (Assigned by recorder) _	1425	C	Street.	San	Diego.	CA	92101	 _
Historic Name:								 _

*P3a. Description (Continued):

Elongated brackets are present under every overhanging eave portion of the building and brackets are also present on the north elevation under the two-story squared, bay windows located on either side of the front porch area. The flat roof of the first floor porch creates a small deck with a wooden balustrade on the second floor. Exterior building materials consist of horizontal clapboard, painted beige, siding for the exterior walls, wood window moldings painted a contrasting blue, most likely composition shingles for the roof. Window types include: fixed, double-hung sash, a one-story angled bay, and leaded glass windows, which are typical features of the early Prairie style. Overall, this building appears to be in excellent condition, and appears to have been maintained well over the course of its existence.

*B10. Significance (Continued):

Historical research has determined that the 1425 C Street building is not historically significant, as the building is not associated with any important events or individuals in terms of local, state, or national history. However, the building is architecturally significant as a building which embodies the distinctive characteristics of a type, period, or method of the early Prairie style, or Prairie Box construction. With features typical to the Prairie style including the symmetrical plan, hipped roof, front entry as a focal point of the building, a hipped dormer, double-hung sash windows, and squared wooden imitation piers (in place of masonry supports), this building is a good example of the early Prairie form in an urban area. Past documentation has determined that the 1425 C Street building was designed in a Neoclassical architectural style, however, the building does not possess Neoclassical features, rather the building possesses Prairie design characteristics. Many of the early Prairie buildings, such as the 1425 C Street building also feature secondary details which are derived from either Italian Renaissance or Mission architectural styles. As the identity of the architect could not be ascertained, the 1425 C Street building does not represent the work of a master architect or craftsman. In addition, constructed by C.J. Jones, the 1425 C Street building does not represent the work of a master builder, nor that of an important, creative individual. The 1425 C Street building is listed as a "6Y2" on the California State Office of Historic Preservation's Historic Property Data File for San Diego County. This listing means that the building has been determined to be ineligible for the National Register of Historic Places. However, this building is eligible for inclusion on the local register.

PRIMARY RECORD

Primary #	
HRI #	
Trinomial	
NRHP Status Code 7	

INIMAN I INECOND		THIOTHAI			
		NRHP Status	Code 7		
	Other Listings Update of	f November 19	88 Centre City E	ast Survey Documen	ntation
	Review Code	Reviewer		Date	
Page1_ of3_ *Reso	ource Name or #: (Assign	ed by recorder)	901-923 E \$	Street	
1. Other Identifier: _					
P2. Location: a Not for Publicatio	n Unrestricted *	a. Count	ty San Diego)	
ind (P2b and P2c or P2d. Attach a Lo	cation Map as necessary	·.)			
b. USGS 7.5' Quad Point Lo	maDate	_T; R	_;¼ of'/4	of Sec;	B.M.
Address <u>901-923 E S</u>	treet	_ City San	Diego Zi	p <u>92101</u>	
d. UTM: (Give more than	one for large or	linear reso	ources) Zone	11; mE/	mi
. Other Locational Data (e.g., p	arcel #, directions to reso	ource, elevation,	, etc., as appropria	te):	

APN: 534-336-01-00, Horton's Addition, Block 57, Lot A

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1927, this single-story, One-Part Commercial Block building has a general rectangular shaped plan, and features a flat roof with a parapet and corbeling up to the cornice. Exterior building materials consist of multi-colored bricks, and wood-framed glass portions for the store front windows. The brickwork features a painted geometric pattern which helps to delineate the bays from one another. There are approximately ten recessed entrances to the building's separate units. A variety of signage is present indicating the location of the different businesses within the units. Overall, this building appears to be in excellent condition.



and codes) HP6
*P4. Resources Present: I Building
Structure d Object d Site d District d
Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #) *P6. Date Constructed/Age and Sources:
I Historic
d Prehistoric d Both 1927
1988 Centre City East Historic Site Inventory
*P7. Owner and Address:
Greenberg Intervivos Trust 09-08-93 C/o Trilogy
P.O. Box 126308
San Diego. CA 92112
*P8. Recorded by (Name, affiliation, and
address): Wendy L. Tinsley, Scott
A. Moomjian, Office of Marie
Burke Lia. Attorney at Law, 427
C Street, Ste. 416, San Diego,
CA 92101

P3b. Resource Attributes: (List attributes

*P9.	Date Recorded:	October	2001

*P10. Type of Survey: (Describe)_

City East For Centre City Development Corporation

Attachments: □NONE D Location Map □ Sketch Map ■Continuation Sheet ■ Building, Structure, and Object Record □ Archaeological Record D District Record n Linear Resource Record a Milling Station Record n Rock Art Record □ Artifact Record n Photograph Record D Other (List):

N (#4)	
DEPARTMENT OF PARKS AND RECREATION HRI#	
BUILDING, STRUCTURE, AND OBJECT RECO	
Page 2 of 3 *NRHP Sta	atus Code 7
*Resource Name or # (Assigned by recorder) 901-923 E Stree	
B1. Historic Name: Bidwell Block	
B2. Common Name:	
B3. Original Use: Commercial B4. Present Use:	
*B5. Architectural Style: One Part Commercial Block styl	e
*B6. Construction History: (Construction date, alternations, and date Originally constructed in 1927; no major alteration	
*B7. Moved? No □Yes □Unknown Date:Origina	al Location:
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: Theme Architecture Area San Diego	
Property Type Commercial Applicable Commerci	
(Discuss importance in terms of historical of architectural context as defined by theme, pr	eriod, and geographic scope. Also address integrity.)
Originally constructed in 1927 by owners George and documented in November 1988 under the supervision of the Past owners of the 901-923 E Street property and building (pre-1913), and George and Mary Bidwell (1913-date un occupants of the 901 E Street unit include: clothing cl N' Save Cleaners (1955), PO Cafe Restaurant (1960), the (1980), and the Ripe Tomato Restaurant (1984). Past or Riddle Roce watch repair (1944/1945), vacant (1950, 1955), no listing (1970, 1975), Lawson's Stamp Company Street unit includes restauranteur Mrs. J.J. Carlson (1944 the Buckley Carbon Company and the Foster Company; civil no listing (1970), vacant (1975), San Diego Home Products Past occupants of the 915 E Street unit include: barber I Made Products of San Diego (1955, 1960, 1965, 1975, 1980) Past occupants of the 917 E Street unit include: ca (1944/1945), vacant (1950), and Blind Made Products of San Past occupants of the 921 E Street unit include: restaurance Gin Hoy (1955, 1960, 1965, 1975, 1980, 1984). Past occupanting (1975), New System Chinese Laundry (1955, 1960, Painting (1975), vacant (1980), and Pacific Dawn Studios	e Office of Marie Lia and Dr. Ray Brandes. include: The Odd Fellows Temple Association aknown). San Diego City Directories past eaner Hazel L. Wood (1944/1945, 1950), Sort Corner Cafe (1965, 1975), Roman's Restaurant occupants of the 905 E Street unit include:), Camera Repair Service of San Diego (1960, (1980, 1984). Past occupants of the 909 E 44/1945), vacant (1950), office supply store, engineer Harry L. Foster (1955, 1960, 1965), (1980), and the Lawson Stamp Company (1984) L.P. Bixby (1944/1945), vacant (1950), Blindard engraver F.W. Beuhler and H.A. Klinke in Diego (1955, 1960, 1965, 1975, 1980, 1984), anteur Eugene Jacobs (1950), Optometrist Hompants of the 923 E Street unit include: Lee D., 1965), no listing (1970), Duane Buart Sign
(See DPR 523H, Continuation Sheet for more information	tion)
B11. Additional Resource Attributes: (List attributes and codes) *B12. References: (partial list)	
(See DPR 523H, Continuation Sheet for more information)	(Sketch Map with north arrow required.)
B13. Remarks:	E
B13. Remarks:	F
*B14. Evaluator: Wendy L. Tinslev. Scott A. Moomijan,	T 1 4 9
Office of Marie Burke Lia	
Date of Evaluation: October 2001	2 8 KB
Date of Evaluation. October 2001	
	C U
(This space reserved for official comments.)	- 57
	CD 2 CD
1	£ # 6
	₫ , CO
	N 2 N N N N N N N N N N N N N N N N N N
	*

CONTINUATION SHEET

rimary #	 	
IRI #/Trinomial		

■ Continuation □ Update

Page __3__ of __3__

Resource Identifier: (Assigned by recorder) 901-923 E Street. San Diego, CA 92101 Historic Name: Bidwell Block

*B10. Significance (Continued):

Historical research has determined that the 901-923 E Street building is not historically significant, as it has not been associated with any important events, or individuals in terms of local, state, or national history. As the identity of the architect could not be ascertained, the 901-923 E Street building does not represent the work of a master architect, master builder, or master craftsman, nor that of an important, creative individual. While the property has been classified as a "One part commercial block," further study and/or research is necessary to determine whether structure embodies the distinct characteristics of this type, period or method of construction. Such a determination will dictate whether the resource is eligible for listing on the local register.

*B12. References (Continued):

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986. San Diego City Directories San Diego County Recorders Office

\mathbf{n}		\mathbf{D}		^^	
-	I IN/II //	\mathbf{D}			
-	IIVI	RY	Γ	\cdot	עחי

Primary #		
HRI #		
Trinomial		
NRHP Status Code	5S2	

	Other Listings Update of	November 1988	Centre City East	Survey Documentation
	Review Code	Reviewer		Date
Page1_ of2_	*Resource Name or #: (Assigne	ed by recorder)	1035 E Street	

P1. Other Identifier:

*P2. Location: a Not for Publication Unrestricted * a. County San Diego

*P2. Location: a Not for Publication ■ Unrestricted *
and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma Date T ; R ; ¼ of % of Sec ; B.M.

c. Address 1035 E Street City San Diego Zip 92101

d. UTM: (Give more than one for large or linear resources) Zone 11; mE/ __mN

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 534-335-09-00, Horton's Addition, Block 56, N 3' Lot K & All Lot L

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1886, this two-story apartment building was designed in a vernacular Italianate architectural style. It has a square shaped plan and features a moderately pitched hipped roof with wide eave overhang, a gabled dormer on the east elevation, and brackets under the eaves at the roof line, as well as below the first and second story windows. Windows appear to be double-hung sash and feature wood surrounds and sills. The recessed front entrance to the building is covered by a shed style roof and supported by two large brackets. Exterior building materials consist of clapboard siding for the exterior walls and composition shingles for the roof. Overall, this building appears to be in fair condition.



P3b. Resource Attributes: (List attributes and codes) HP3______*

*P4. Resources Present: I Building d

Structure d Object d Site d District d
Element of District d Other (Isolates, etc.)
P5b. Description of Photo: (View, date, accession#)

*P6. Date Constructed/Age and Sources:

| Historic d Prehistoric d Both 1886

1988 Centre City East Historic Site Inventory *P7. Owner and Address:

Downtown Renovations LLC______3063 Dalen Place_______San Diego, CA 92122______

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Burke Lia, Attorney at Law, 427 C Street, Ste. 416. San Diego. CA 92101

*P9. Date Recorded: February 2001 / Owner Information and Photo Updated June 2003

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre City East For Centre City Development Corporation</u>

Attachments: NONE Location Map n Sketch Map Continuation Sheet Building, Structure, and Object Record D Archaeological Record D District Record a Linear Resource Record Milling Station Record a Rock Art Record Artifact Record Photograph Record Other (List):

State of California — The Resources Agency Primary # DEPARTMENT OF PARKS AND RECREATION HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD
Page 2 of 2 *NRHP Status Code 5S2
*Resource Name or # (Assigned by recorder) 1035 E Street, San Diego, CA 92101
B2. Common Name: Courtnov Rooms
B3. Original Use: Residential (Single-Family)_ B4. Present Use: Residential (Multi-Family)
*B5. Architectural Style: Italianate vernacular
*B6. Construction History: (Construction date, alternations, and date of alterations) Originally constructed in 1886 as a single-family residence, and converted to an apartment
building in 1913. No other major alterations and/or modifications noted.
*B7. Moved? No
*B8. Related Features: B9a. Architect: L.D. Burbeck b. Builder: L.D. Burbeck *B10. Significance: Theme Architecture Area San Diego Period of Significance 1886_ Property Type Residential Applicable Criteria C_
(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)
Originally constructed in 1886, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past owners of the 1035 E Street property and building include: N.R. Hooper (February 1886), Michael & Jane Quinn (August 1886-1905), Christeine Hinsfeld Kelson & Grace Schoenfeldt (1905), and F.D. Carper (1913). Past documentation states that the 1035 E Street building was converted into the Italianate style apartments in 1913 from

Originally constructed in 1886, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past owners of the 1035 E Street property and building include: N.R. Hooper (February 1886), Michael & Jane Quinn (August 1886-1905), Christeine Hinsfeld Kelson & Grace Schoenfeldt (1905), and F.D. Carper (1913). Past documentation states that the 1035 E Street building was converted into the Italianate style apartments in 1913 from a small cottage that had been constructed in 1886 by owner F.D. Carper (Lia & Brandes:1988). Past documentation also reveals that past occupants of the 1135 E Street building include: Dr. Michael & Jane Quinn (1892-1900), and San Diego City Directories reveal the 1035 E Street building was identified as the "Custer Rooms" lodging house (1944/1945, 1950, 1955, 1960, 1965, 1969/1970, 1975), and the "Courtnoy Rooms" lodging house (1980, 1984). Past proprietors include: F.E. Ranch (1944/1945), Mrs. James Merriman (1950), and George N. Sullivan (1955).

Historical research has determined that the 1035 E Street building is not historically significant, as it has not been associated with any important events, or individuals in terms of local, **state**, or national history. The building does appear to be architecturally significant, at the local level, as a building which embodies the distinctive **characteristics** of a type, period, or method of ttalianate construction. Constructed and designed by L.D. Burbeck, the building does not represent the work of a master architect, master builder, or master craftsman.

B11. Additional Resource Attributes: (List attributes and codes)_

*B12. References: (partial list)

Growth, Paul, Living Downtown, The **History** of Residential **Hotels** in the United States, 1994. Lia and Brandes, **Historic** Site Inventory of Centre City **East**, 1988.

McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office


B13. Remarks:

*B14. Evaluator: Wendy I. Tinslev.

Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



and boundaries):

Primary #	
HRI #	
Trinomial	
NRHP Status Code 552	

PRIMARY RECORD	Trinomial
Other Listings U	pdate of November 1988 Centre City East Survey Documentation
Review Cod	deDate
Page1 of3 *Resource Name or #:	(Assigned by recorder) 1045 E Street
21. Other Identifier:	
P2. Location: a Not for Publication II Unrestricted	d* a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as no	
b. USGS 7.5' Quad Point Loma Date	
Address 1045 E Street	City <u>San Diego</u> Zip <u>92101</u>
d. UTM: (Give more than one for larg	ge or linear resources) Zone 11;mE/mN
 Other Locational Data (e.g., parcel #, directions) APN: 534-335-09-00, Horton's Add 	s to resource, elevation, etc., as appropriate): lition, Block 56, N 3' Lot K & All Lot L
P3a Description (Describe resource and its major of	elements. Include design, materials, condition, alterations, size, setting,

Originally constructed in 1913, this two-story apartment house was designed in an Italian Renaissance vernacular architectural style. It has a general square shaped plan and features a low pitched, hipped roof with wide eave overhang, and exposed rafter tails under the eave. A recessed front entrance is present at the center of the building and is shaded overhead by a second floor balcony. Supported by a bracket on each northern corner, the wood balcony features two miniature squared columns, and railing that has been extended upward. The second floor balcony features a recessed doorway similar to the first floor entrance. (See DPR 523H, Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes and codes) HP3			
*P4. Resources Present: I Building			
Structure □ Object □ Site □ District □			
Element of District Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)			
*P6. Date Constructed/Age and Sources:			
Historic			
☐ Prehistoric ☐ Both			
.1913			
1988 Centre City East Historic Site Inventory			
*P7. Owner and Address:			
Downtown Renovations LLC			
.3063 Dalen Place			
San Diego, CA 92122			
*P8. Recorded by (Name, affiliation, and			

Wendy Office of Marie Burke Lia.

Attorney at Law, 427 C Street,
Ste. 416, San Diego, CA 92101

*P9. Date Recorded: February 2001 / Owner Information and Photo Updated June 2003
*P10. Type of Survey: (Describe)
P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre
City East For Centre City Development Corporation
Attachments: NONE Location Map n Sketch Map Continuation Sheet Building, Structure, and Object Record
☐ Archaeological Record ☐ District Record n Linear Resource Record ☐ Milling Station Record n Rock Art Record
D Artifact Record Photograph Record Other (List):

State of California — The Resources Agency Primary #
DEPARTMENT OF PARKS AND RECREATION HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD
Page _ 2 _ of _ 3 _ *NRHP Status Code _ 5S2
*Resource Name or # (Assigned by recorder) 1045 E Street, San Diego, CA 92101
B1. Historic Name: Carper Apartments
B2. Common Name: Hartonia Apartments
B3. Original Use: Residential (Multi-Family) B4. Present Use: Residential (Multi-Family)
*B5. Architectural Style: Italian Renaissance vernacular
*B6. Construction History: (Construction date, alternations, and date of alterations) Originally constructed in 1913; no major alterations and/or modifications noted.
*B7. Moved? No
*B8. Related Features:
B9a. Architect: L.D. Burbeck b. Builder: L.D. Burbeck
*B 10. Significance: Theme Architecture Area San Diego Period of Significance 1913_
Property Type Residential Applicable Criteria C_
(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)
Originally constructed in 1913, this building was previously documented in November 1988 under
the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past owners of the 1045 E Street
property and building include: N.R. Hooper and Mr. Carper (1913). San Diego City Directories reveal
the 1045 E Street building was identified as the "Argonaut Apartments" building with eight units
(1944/1945, 1950, 1955, 1960, 1965, 1969/1970, 1975), and the "Hartonia Apartments" building, also
with eight units (1980, 1984) .

Historical research has determined that the 1045 E Street building is not historically significant, as **it is** not associated with any important events, or individuals in terms of local, state, or national history. The building, however, does appear to be architecturally significant, at the local level, as a building which embodies the distinctive characteristics of a type, period, or method of Italian Renaissance construction. Constructed and designed by L.D. Burbeck, the building does not represent the **work** of a master architect, master builder, or master craftsman.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Growth, Paul, Living Downtown, The History of Residential Hotels in the United States, 1994. Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories


San Diego County Recorders Office

*B14. Evaluator: Wendy L. Tinsley,

B13. Remarks:

Date of Evaluation: February 2001

(This space reserved for official comments.)



CONTINUATION SHEET

Primary #	
HRI #/Trinomial	

■ Continuation □ Update

Page 3 of 3

Resource Identifier: (Assigned by recorder) 1045 E Street, San Diego, CA 92101

Historic Name: Carper Apartments

P3a. Description (Continued):

Exterior building materials consist of composition **shingles** for the roof and clapboard siding for the exterior walls. Windows are double-hung sash and on the north, street facing **elevation**, the entrance is flanked on both sides by two, tri-partite windows featuring a fixed single pane in the center and a narrow double-hung window on either side. These windows are bordered by a single, double-hung window. Overall, this building appears to be in fair condition.

PRIMARY RECORD

Primary #	
HRI # 2138-0203-0000	
Trinomial	
NDUD Status Code 7	

	MAKIKECUKU		mnomiai		
			NRHP Status Code	⊋_7	
		Other Listings Update of	of November 1988 C	Centre City East Surve	y Documentation
		Review Code	Reviewer	Date	10
Page _	1 of4	*Resource Name or #: (Assig	ned by recorder)	1327-1335 E Street	t
21.	Other Identifier:				
[•] P2.	Location: Not for Publi	cation <pre>Unrestricted *</pre>	a. County	San Diego	
and (P2	2b and P2c or P2d. Attach	a Location Map as necessary	y.)		
b. US	GS 7.5' Quad Point	LomaDate	; R; _	¼ of¼ of Sec	; B.M
C.	Address1327	-1335 E Street	CitySan	Diego Zip	92101
d.	UTM: (Give more t	han one for large or	linear resourc	es) Zone 11;	mE/mN
e.	Other Locational Data (e	.g., parcel #, directions to reso	ource, elevation, etc.	, as appropriate):	
	APN: 534-345-10-0	00, Horton's Addition	n, Block 53, W	% of Lots K & L	
⁴P3a.	Description (Describe res	ource and its major elements.	Include design, mate	rials, condition, alteration	ons, size, setting

Originally constructed in approximately 1915, the building shown in the photograph below is identified as the "Hotel Mediterranean" located at 1329-1335 E Street. Designed in a flat roof Italian Renaissance style, this two-story building has a rectangular shaped plan and features a wide decorated cornice and frieze which extends out past the buildings edge. The street facing facade features a parapet, dentils, several levels of belt coursing (some spans around the perimeter of the building), and four triple windows, each with a large fixed window with a leaded glass transom at the center and a double-hung window flanking both sides.

(See DPR 523H, Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes and codes) HP3

*P4. Resources Present: I Building d Structure d Object d Site d District d Element of District d other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

I Historic

d Prehistoric c.1915 d Both

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Mediterranean Hotel LLC

9253 Main Street

San Diego. CA 92113

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Scott A. Moomjian, Office of Marie Burke Lia, Attorney at Law, 427 C Street. Ste. 416, San Diego, CA 92101

*P9. Date Recorded: October 2001 / Owner Information and Photo Updated June 2003_

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre City East For Centre City Development Corporation</u>

Attachments: □NONE □ Location Map □ Sketch Map • Continuation Sheet • Building, Structure, and Object Record □ Archaeological Record □ District Record □ Linear Resource Record a Milling Station Record □ Rock Art Record □ Artifact Record □ Photograph Record □ Other (List):

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	
BUILDING, STRUCTURE, AND OBJI	ECT RECORD
Page 2 of 4	
	7-1335 E Street, San Diego, CA 92101
B2. Common Name: Hotel Mediterranean	
B3. Original Use: Residential (Multi-Famil	ly) B4. Present Use: Residential (Multi-Family)_
*B5. Architectural Style: Flat Roof Italian R	
*B6. Construction History: (Construction date, alternation Constructed in 1915; No major alternation	
*B7. Moved? No □Yes □Unknown Date:	Original Location:
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: Theme Architecture Area San	
Property Type Residential (Discuss importance in terms of historical or architectural context as or	Applicable Unleria U_ defined by theme, period, and geographic scope. Also address integrity.)
	1915, this building was previously documented in November
	Marie Lia and Dr. Ray Brandes. Past documentation reveals
	J. Menke relocated to San Diego in 1888, purchased the
	nstructed the residence in 1915. Although identified as lso reveals that in 1916 four families resided in the
	ty Directories reveal past residents of the 1329 unit of
_	nnie Nichol (1980), and Francisco R. Arrieta (1984). Past
_	ck (1980, 1984). Past residents of the 1333 unit include:
no return (1980, 1984). Past residents of	the 1335 unit include: Olga Crockett (1980, 1984).

Historical research has determined that the 1329-1335 E Street building is not historically significant, as the building is not associated with any important events, or individuals in terms of local, state, or national history. In addition, the identity of the architect could not be ascertained and the building does not appear to represent the work of a master architect or craftsman. The building is, however, architecturally significant at the local level, as a building which embodies the distinctive characteristics of a type, period, and method of Flat Roof Italian Renaissance construction.


See page 3, DPR 523H, Continuation Sheet for more information
B11. Additional Resource Attributes: (List attributes and codes)
*B12. References: (partial list)
Lia and Brandes, Historic Site Inventory of Centre City East, 1988.
McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.
San Diego City Directories
San Diego County Recorders Office

*B13. Remarks:

*B14. Evaluato<u>r: Wendy L. Tinslev, Scott A. Moomijan, Office of Marie Burke Lia</u>

Date of Evaluation: October 2001

(This space reserved for official comments.)



CONTINUATION SHEET

Primary #_ HRI#/Trinomial 2138-0203-0000

Continuation

□ Update

Page 4 of __


Resource Identifier: (Assigned by recorder) 1327-1335 E Street, San Diego, CA 92101 Historic Name: Menke Residence

P3a. **Description (Continued):**

1. 1327 E Street, November 2000



2. 1921 Sanborn Fire Insurance Map depicting 1327 E Street residence & 1329-1335 E Street Building



Primary #	
HRI#/Trinomial 2138-0203-0000	

CONTINUATION SHEET

■ Continuation
□ Update

Page3 of4					
Resource Identifier: (Assigned by recorder)	1327-1335	E Street,	San Diego,	CA 92101	
Historic Name: Menke Residence					

P3a. Description (Continued):

The entrance to the building is recessed and **features** a centered, covered balcony above that features **a** wooden balustrade, two **square** pillars that connect with the cornice and roof line, and a pair of brackets underneath each front balcony corner. Exterior building materials consist of clapboard siding for the exterior walls, and wood window **surrounds**. Window types around the **building** appear vary between double-hung sash, casement, and possibly sliding. Overall, **this** building **appears** to be in excellent condition, and serves as a excellent example of the Italian Renaissance style constructed almost entirely with wood.

A single-family residence identified as 1327 E Street is located on the rear portion of the lot behind the 1329-1335 E Street building. Past documentation has incorrectly included the 1327 E Street address as if it were part of the Hotel Mediterranean building located in the front portion of the lot. The 1327 E Street residence appears to be a single-family residence and a view of the building from the street is completely obstructed by the Hotel Mediterranean. Limited field investigation activities revealed that it has a gabled roof with a slight enclosed eave overhang, and a recessed front entry with a small partial porch area that features two simple columns placed on a low extended portion of the exterior wall (rather than a separate pediment or post). Exterior building materials for the 1327 E street residence consists of clapboard siding for the exterior walls, and most likely, composition shingles for the roof. Two fixed windows with wood surrounds are present on the north elevation of the residence, both windows feature a blank lower pane, with a patterned pane above. The exact date of construction is unknown, however the 1327 E Street residence does appear on a 1921 Sanborn Fire Insurance Map. San Diego City Directories reveal past occupants of the 1327 E street residence include: S.O. Rose (1944/1945), vacant (1950), Mrs. Lupe Castillo (1955), vacant (1960, 1965), Robert R. D'Hue Jr. (1969/1970), vacant (1975), and Mrs. Bessie Gore (1980, 1984).

See page 4, DPR 523H, Continuation Sheet for photograph and historic map

*B10. Significance (Continued):

Given the limited amount of field investigation activities related to the 1327 E Street residence, it has been assigned a National Register Status Code listing of "7," which means that the building was not evaluated. Although the building does not appear to be eligible for inclusion on the National Register of Historic Places, further historical and architectural research is **necessary** in order to make a determination of whether the 1327 E Street residence is eligible for listing on the local register.

and boundaries):

Primary #	
HRI #	
Trinomial	
NDUD Ctatus Carla CD	

PRIMARY RECORD		Trinomial				
		NRHP Status C	ode 6Z			
	Other Listings Update of	November 1988	Centre City	East Survey	/ Documenta	tion
	Review Code	Reviewer_		Date		
Page1 of3 *Reso	urce Name or #: (Assigne	d by recorder)	1401 E St	reet		
P1. Other Identifier:						
*P2. Location: ☐ Not for Publication	■ Unrestricted *	a. County	San Die	TO		
and (P2b and P2c or P2d. Attach a Loc	cation Map as necessary.)					
*b. USGS 7.5' Quad Point Lon	na Date	Г; R	;¼ of	_¼ of Sec	_;	B.M.
c. Address1401	E Street	CitySa	n Diego	Zip	92101	
d. UTM: (Give more than	one for large or l	inear resou	rces) Zone	11; _	mE/	mN
e. Other Locational Data (e.g., pa	rcel #, directions to resou	rce, elevation, e	etc., as appropr	riate):		
ADN: 531-311-01-00 S	tangal Subdivision	Block 177	/ Lote 1 t	bru 6 All	AV Close	А

Originally constructed in approximately 1923, this One Part Commercial Block building was has a general rectangular shaped plan, and features a flat roof, in-filled truck entrances on the north elevation separated by sets of pilasters, a series of in-filled windows and doors along the north and west elevations, a series of decorative brick bands spanning around the north and west elevations, and raised brick ornamentation, also present on the north and west elevations. The raised brick features are tri-partite, or a modified teardrop shape, and are similar to that of brackets in appearance and placement around the building, however, remain in a rectangular brick shape. (See DPR 523H, Continuation Sheet, for more information)

Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting,



and codes) HP6; HP8_ *P4. Resources Present: | Building | Structure d Object d Site D District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #) *P6. Date Constructed/Age and Sources: Historic d Prehistoric d Both 1923 1988 Centre City East Historic Site Inventory *P7. Owner and Address: Navarra Family Trust 12-116-86 Jerome V. & Eleanor S. Navarra 3682 Kite Street San Diego, CA 92103 *P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Burke Lia.

Attorney at Law. 427 C Street,
Ste. 416. San Diego, CA 92101

P3b. Resource Attributes: (List attributes

*P9. Date Recorded: February 2001
*P10. Type of Survey: (Describe)
P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre
City East For Centre City Development Corporation
Attachments: DONE Decation Map in Sketch Map Continuation Sheet Building, Structure, and Object Record
n Archaeological Record District Record n Linear Resource Record n Milling Station Record D Rock Art Record n Artifact Record n Photograph Record a Other (List):

And the state of t
State of California — The Resources Agency Primary # •
DEPARTMENT OF PARKS AND RECREATION HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD
Page 2 of 3 *NRHP Status Code 6Z
*Resource Name or # (Assigned by recorder) 1401 E Street, San Diego, CA 92101
B1. Historic Name: United States Naval Reserve Headquarters
B2. Common Name: Jeromes Warehouse Building
B3. OriginalUse: Commercial (Office/Warehouse) B4. Present Use: Commercial (Furniture Warehouse)
*B5. Architectural Style: One Part Commercial Block with a Spanish Eclectic influence
*B6. Construction History: (Construction date, alternations, and date of alterations) Originally constructed in 1923. Interior alterations: connected with neighboring 1485 E Street building through the removal of dividing interior wall (exact date unknown, most likely c. 1975 when 1485 E street boxing arena closed down); windows, doors, and truck entrances have been stuccoed over (date(s) unknown).
*B7. Moved? B No Urknown Date: Original Location:
*B8. Related Features: B9a. Architect: Unknown b. Builder: Unknown *B10. Significance: Theme N/A Area San Diego Period of Significance 1923 Property Type Commercial: Warehouse Applicable Criteria N/A (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)
Originally constructed in approximately 1923, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past documentation reveals past owners of the 1401-1429 E Street property and building include H.F. & Charlotte Schnell (1923) Past documentation also reveals past occupants of the 1401-1429 E Street building include: the United States Naval reserve Headquarters (1923-1928), Sears, Roebuck and Company warehouse and garage (1933)

Originally constructed in approximately 1923, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past documentation reveals past owners of the 1401-1429 E Street property and building include H.F. & Charlotte Schnell (1923). Past documentation also reveals past occupants of the 1401-1429 E Street building include: the United States Naval reserve Headquarters (1923-1928), Sears, Roebuck and Company warehouse and garage (1933), Acme Past Freight Incorporated (1940), and San Diego City Directories reveal past occupants of the building include: Western Parcel Service, Western Transfer & Storage Company, Acme Fast Freight Incorporated, Atlas Freight Incorporated, and Western Freight Association (1944/1945), Western Freight Association, Western Parcel Service, Western Transfer & Storage Company (1950), Western Parcel Service, Western an & Storage, Western Carloading Company, Inc., and Western Parcel Service (1965), Western Carloading Company, Inc., Western Van & Storage, and Western Parcel Service (1960), Coast Delivery Service, Western Carloading Company, Inc., Western Van & Storage, and Western Parcel Service (1965), and Jerome's Furniture Warehouse (1969/1970, 1975, 1980, 1984, 1988). The building is still occupied and owned by Jerome's and the Navarra family.

(See DPR 523H, Continuation Sheet for more information)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

Longstreth, Richard, The Buildings of Main Street; A Guide To American Commercial Architecture, 1987.

San Diego City Directories

San Diego County Recorders Office


B13. Remarks:

*B14 Evaluator: Wendy L. Tinsley,

Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



CONTINUATION SHEET

Prima	ary #	
HRI	#/Trinomial	

Continuation

□ Update

Page __3_ of __3_

Resource Identifier: (Assigned by recorder) 1401 E Street, San Diego, CA 92101_____

Historic Name: United States Naval Reserve Headquarters

P3a. Description (Continued):

These **brick** brackets also are present on the corners of the building at the window level. "Jerome's" **signage** is present around the perimeter of the 1401-1429 building as well as the neighboring 1485 E Street building. The customer entrance to the building is on the west elevation, located on Fourteenth Street. Overall, the building appears to be in good **condition**.

*B10. Significance:

Historical research has determined that this building, identified as 1401-1429 E Street is neither historically nor architecturally significant. It is not associated with any important events, or individuals in terms of local, state, or national history, and it is not a building which embodies the distinctive characteristics of a type, period, or method of One Part Commercial block construction. As the identity of the architect could not be ascertained, the 1401-1429 E Street building does not represent the work of a master architect. The building is not eligible for listing on the local register.

_	- .			• • •	_	_	~	-	
PI	ΚI	M	Αŀ	ťΥ	R		じし)K	D

e.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION						
PRIMARY RECORD						
Other Listings						
	Reviewer Date					
Page _ 1 of _ 2 Resource Name or #: (Assigned by red	corder) 1508-1544 E Street/934-940 16 th Street					
P1. Other Identifier: <u>Jerome's Furniture Com</u>	mpany Building					
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County San Diego					
and (P2b and P2c or P2d. Attach a Location Map as necessa	ary.)					
*b. USGS 7.5' Quad Point LomaDate	T; R;% of% of Sec;B.M.					
c. Address 1508-1544 E Street/934-940 16 th St						
d. UTM: (Give more than one for large or	r linear resources) Zone;mE/mN					
e. Other Locational Data (e.g., parcel #, directions to re 1508-1544 E Street/934-940 16 th Street	esource, elevation, etc., as appropriate): -Block 4, Lots 5, 6, 7, 8, 9, Map 0143,					

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This resource consists of a Spanish Eclectic commercial building which encompasses two legal parcels on the southern half of Block 4. The building is currently used for Jerome's Furniture Company as a furniture storage/warehouse. The building originally appears to have been constructed c.1906-1921 as an automobile sales service building. The building is one-story in shape and is "C"-shaped. It extends along the southwest, south, and southeast sides of the block. The building features a flat roof with decorative parapets and pilasters. The exterior is stucco. The building features several bays and multi-paned window sections and appears to be in good condition.

P3b. Resource Attributes: (List attributes and codes)



APNs: 534-352-02 & 534-352-03

*P4. I Building **Resources Present:** 3 Structure n Object n Site a District a ilement of District n Other (Isolates, etc.) ^{5b.} Description of Photo: (View, date, accession #)

P6. Date Constructed/Age and Sources:

| Historic

☐ Prehistoric c.1906-1921

Sanborn Fire Insurance Maps

□ Both

*P7. Owner and Address:

Jerome Navarra Family Trust, Navarra Family Trust,

Ann N. Greenberg

1401 E Street

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Office of Marie Burke Lia, 427 C Street, Suite 416, San Diego, California 92101

*P9. Date Recorded: May 2004

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Resources Inventory Update Of The East Village Area For Centre City Development Corporation

Attachments: □NONE □Location Map □Sketch Map □Continuation Sheet ■Building, Structure, and Object Record □Archaeological Record □District Record □Linear Resource Record □Milling Station Record □Rock Art Record □ Artifact Record □ Photograph Record □ Other (List):

State of California — The Resources Agency Primary #	
DEPARTMENT OF PARKS AND RECREATION HRI#	
BUILDING, STRUCTURE, AND OBJECT RECORD	
Page 2 of 2 *NRHP Status Code 6Z *Resource Name or # (Assigned by recorder) 1508-1544 E Street/934-940 16 th Street	
B1. Historic Name:	
B2. Common Name: Jerome's Furniture Company Building	
B3. Original Use: Commercial B4. Present Use: Commercial	
*B5. Architectural Style: Spanish Eclectic	
Building constructed c.1906-1921. Building converted from automotive sale service use to furniture storage/warehouse (post 1956).	s and
*B7. Moved? No □Yes □Unknown Date: Original Location:	
*B8. Related Features:	
None	
B9a. Architect: Unknown b. Builder: Unknown	
*B10. Significance: ThemeN/A Area _ <u>East Village/Centre City</u>	
Period of Significance _ N/A Property Type Commercial Applicable Criteria N	
(Discuss importance in terms of historical or architectural context as defined by theme, period	d, and
geographic scope. Also address integrity.)	
This building is believed to have been constructed sometime between 1906-1921. Inspection of 1888 and 1906 Sanborn Fire Insura	
do not indicate the presence of the structure on the block between these years. However, by 1921, the entire block was fully developed buildings in existence by this year. At this time, the 1508-1544E Street/934-940 16th Street building was used as a commercial auto body	
with woodworking as well as General Motors trucks sales and service. Until at least 1956, the entire block was used for automobile sales and	
use.	
Historical research has determined that the 1508-1544E Street/934-940 16 th Street building is not historically or architecturally si The building is not associated with any important events or individuals in terms of local, state, or national history. The building does no	
the distinctive characteristics of a type, period, or method of construction, nor does it represent the work of a master architect, builder, c	
or important, creative individual.	
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list) City of San Diego, Building Department Permit Records.	
City of San Diego, Water & Sewer Records.	
Longstreth, Richard, The Buildings Of Main Street, 1987. McAlester, Virginia & Lee, A Field Guide To American Houses, (Sketch Map with north arrow required.	\
2000.	,
San Diego City and County Directories.	
B13. Remarks:	
*B14. Evaluator: Office of Marie Burke Lia Date of Evaluation: May 2004	
(D) (E) 5	
5 (2)	
(This space reserved for official comments.)	
9 7 6 2	

1508-1544 E Street/ 934-940 16th Street

ST

PRIMARY RECORD

Primary #	
HRI #	
Trinomial	
NRHP Status Code 3S	

Other Listin	gs Update o	of November	1988	Centre	City East	Survey	Documentation
Review Coo	le	Reviewer				Date	

*b. USGS 7.5' Quad Point Loma _____ Date ____ T ___; ___¼ of ___¼ of ___¼ of ____ B.M.

c. Address 612-650 F Street City San Diego Zip 92101
d. UTM: (Give more than one for large or linear resources) Zone ___; _____ mE/ __mN

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):
APN: 534-326-03-00, Block 60, Lots E thru H

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1914 and designed in a brick commercial architectural style with Italian Renaissance Revival elements the Maryland Hotel is a six-story commercial building, with basement and mezzanine. It has a general rectangular shaped plan measuring approximately 100 feet in width by 200 feet in length set on a reinforced concrete foundation. Framed by reinforced concrete and steel, features of the building include a flat roof with an ornamental cornice both above and below the sixth floor, corner quoins, and aligned double-hung windows. The ground floor features six store fronts divided by original ornamental stone pilasters with large fixed glass windows. The main entrance to the Maryland Hotel is recessed and is flanked by stepped pilasters with capitals. Overall, the building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP5, HP7

*P4. Resources Present: • Building □ Structure □ Object □ Site a District a Element of District □ Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

n Prehistoric a Both 1914

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

630 F street LLC

c/o First Commerce Corp.

550 West C Street #1000

San Diego, CA 92111_

*P8. Recorded by (Name, affiliation, and address): Wendv L. Tinsley,
Office of Marie Lia, Attorney
at Law, 427 C Street, Ste. 416,
San Diego, CA 92101

*P9. Date Recorded: March 2001 / Owner Information and Photo Updated June 2003____


*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: □NONE □ Location Map n Sketch Map □ Continuation Sheet • Building, Structure, and Object Record a Archaeological Record n District Record □Linear Resource Record □ Milling Station Record □ Rock Art Record n Artifact Record □ Photograph Record a Other (List): ______


	nary #
BUILDING, STRUCTURE, AND OBJECT	
•	RHP Status Code 3S
*Resource Name or # (Assigned by recorder)612-650_H	
B1. Historic Name: The Maryland Hotel	
B2. Common Name: The Maryland Hotel	
B3. Original Use: Commercial (Hotel) B4. Pr	
*B5. Architectural Style: Brick Commercial with	
*B6. Construction History: (Construction date, alternations, a	
Constructed in 1914; no substantial mo	
*B7. Moved? No	Original Location:
*B8. Related Features: B9a. Architect: William Sterling Hebbard with Frank	R. Allen Jr. b. Builder: W.E. Kier Construction Company
*B10. Significance: Theme Architecture Area Sal	
Property Type Commercial Hotel	
(Discuss importance in terms of historical or architectural context as defined by	/ theme, period, and geographic scope. Also address integrity.)
	g was previously documented in November 1988 under
	c. Ray Brandes. The Maryland Hotel is a six-story While the hotel is identified as 630 F Street and
	al-retail shops occupy the first floor storefronts
	Sixth Avenue and 820 Seventh Avenue. The Maryland
Hotel was designed by master architect William St	erling Hebbard, in conjunction with Frank P. Allen
	e independently from 1907-1917. Designed in a brick
	sance Revival elements, the Maryland Hotel expresses tic flares, and aptly illustrates Hebbard's design
philosophy of the period.	tic fraces, and apery fractaces nember a design
	and Hotel represented the fifth of six hotel designs
	re career from 1890-1925. It is today, the only stence. In good condition today with a tremendous
	is architecturally significant as a rare and unique
San Diego commercial hotel designed by master ar	chitect Hebbard, which represents his independent
	tel, therefore, qualifies under National Register
Criterion C:Design/Construction as the representa	tive work of a master architect.
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list)	
Lia and Brandes, Historic Site Inventory of	Centre City East, 1988.
Moomjian, Scott A., Maryland Hotel Historic	Research and Documentation, 2001
San Diego City Directories	
San Diego County Recorders Office	(Sketch Map with north arrow required.)
B13. Remarks:	
bis. Remarks.	
*B14. Evaluator: _Wendy I . Tinsley,	1 E
Office of Marie Burke Lia	
Date of Evaluation: March 2001	1 L _© ;

(This space reserved for official comments.)





612-650 FSt



Primary #	
HRI #	
Trinomial	
NRHP Status Code 7	

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI #
PRIMARY RECORD	Trinomial
	NRHP Status Code 7
Other Listings Upda	te of November 1988 Centre City East Survey Documentation
Review Code_	ReviewerDate
Page1 of2_ *Resource Name or #: (A	ssigned by recorder) 741 F Street
P1. Other Identifier:	
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as neces	ssary.)
*b. USGS 7.5' Quad Point Loma Date	
c. Address741 F Street	City <u>San Diego</u> Zip <u>92101</u>
d. UTM: (Give more than one for large	or linear resources) Zone 11:mE/mN
e. Other Locational Data (e.g., parcel #, directions to APN: 535-102-10-00, Horton's Addit	
P3a. Description (Describe resource and its major eler and boundaries):	ments. Include design, materials, condition, alterations, size, setting,
of a One Part Commercial Block building from the	this single-story building is a well preserved example early Twentieth Century. Exterior building materials

are marked on the exterior walls by brick pilasters. Each bay features a colored ornamental brick pattern above the window section. All windows around the buildings perimeter appear to be fixed, and recessed entries are present on the north and west elevation of the building. Overall, the building appears to be in excellent condition.



	Resoui odes)		ributes: HP6	(List	attril	outes
*P4.	Resc	ources	Present	: I B	uildin	ıg n
Struct	ure n	Object	☐ Site		Distri	ct 🗆
P5b.	Descri	iption o	Other of Photo			
	ssion #)		ted/Age	and S	Sour	
I His) 113ti uc	icu/Age	ana c	Jour	,63.
	ehistoric 07-19	0.9		Both		
1988	Centre Ci	ty East	Historic	Site	Inve	entory
*P7. Owner and Address:						

751 7th Avenue, # B San Diego, CA 92101 *P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev. Scott <u>A. Moomjian, Office of Marie</u> <u>Burke Lia, Attorney at Law,</u> C Street, Ste. 416. San Diego CA 92101

C/o Hughes Management

LA-BRA, LLC

*P9.	Date	Recorded:	Oatober	2001
FJ.	Date	Recorded:	Occoper	ZUUI

P11. Report Citation (Cite survey report and other sources, or enter "none",,) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: NONE n Location Map n Sketch Map Continuation Sheet I Building, Structure, and Object Record Archaeological Record a District Record n Linear Resource Record n Milling Station Record a Rock Art Record

^{*}P10. Type of Survey: (Describe)

Although previous documentation concludes that the 741 F Street building is significant for its association with the Maryland Hotel, historical research has determined that the 741 F Street building is not historically significant, as it is not associated with any important events, or individuals in terms of local, state, or national history. Constructed by the Haverty Co. and F.O. Engstrum Co. the building does not represent the work of a master builder or craftsman. While the property has been classified as "One Part Commercial Block," further study and/or research is necessary to determine whether the structure embodies the distinctive characteristics of a type, period or method of construction. Such a determination will indicate whether the resource is eligible for listing on the local register.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories


San Diego County Recorders Office

B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley, Scott A. Moomjian,
_Office of Marie Burke Lia

Date of Evaluation: October 2001

(This space reserved for official comments.)



DD	іпл Л	DV		$\boldsymbol{\Gamma}$	рη
Γ	1 IVI <i>I</i> -	ואו	RE	CU	עאי

Primary #		
HRI #		
Trinomial		
NEUE OCC.		


			NRHP Status Code	7	
		Other Listings Update o	f November 1988 Ce	entre City East Survey Documentat	cion
		Review Code	Reviewer	Date	1
Page_	3 of2	*Resource Name or #: (Assign	ned by recorder) 8	01-821 F Street	
P1.	Other Identifier	r:			
*P2.	Location: D Not for Po	ublication • Unrestricted *	a. County	San Diego	
and (F	P2b and P2c or P2d. Atta	ch a Location Map as necessary	y.)		
*b. U	JSGS 7.5' Quad Poi	nt Loma Date	T; R; _	¼ of;;	B.M.

c. Address 801-821 F Street City San Diego Zip 92101
d. UTM: (Give more than one for large or linear resources) Zone 11; mE/ __mN

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 535-103-01-00, Horton's Addition, Block 72, Lots K & L

***P3a. Description** (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This one-story One-part Commercial Block brick building was constructed in 1924. Composed of exposed brick, the building **features** eleven bays (storefront windows) with a central entrance. An undulating parapet tops the flat roof with painted white brick courses. Each bay is composed of fixed **glass** set atop a brick base below upper transom windows. Overall, the building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP6

*P4. Resources Present: | Building d Structure d Object d Site d District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

*P7. Owner and Address:

Cyrus Ben Cohen Family Trust
7-12-95. 637 South Hill Street

#D8, Los Angeles. CA 90014

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Scott A. Moomjian, Office of Marie Burke Lia, Attorney at Law, 427

C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: October 2001 / Owner Information and Photo Updated June 2003

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre City East For Centre City Development Corporation</u>

Attachments: □NONE □ Location Map n Sketch Map □Continuation Sheet ■ Building, Structure, and Object Record n Archaeological Record □ District Record □ Linear Resource Record □ Milling Station Record n Rock Art Record n Artifact Record n Photograph Record n Other (List):

State of	of California — The Resources Agency Primary #
	RTMENT OF PARKS AND RECREATION HRI#
BUI	LDING, STRUCTURE, AND OBJECT RECORD
*Reso	2 of 2 *NRHP Status Code 7 Urce Name or # (Assigned by recorder) 801-821 F Street, San Diego, CA 92101
B1.	Historic Name: Rossi Business Block
B2.	Common Name:
B3.	Original Use: CommercialB4. Present Use:Commercial
	Architectural Style: One Part Commercial Brick Block
*B6.	Construction History: (Construction date, alternations, and date of alterations) Originally constructed in 1924, dropped ceilings and paint added; no other
alte	rations/modifications known or noted.
*B7.	Moved? No
B9a. *B 10.	Related Features: Maryland Hotel Architect: Unknown b. Builder: Unknown Significance: Theme Architecture Area San Diego Period of Significance 1924 Property Type Commercial Applicable Criteria C_s importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)
inclu	The construction of 801-821 F Street commercial structure was financed by T. and Luiga Rossi in Since its initial construction, the building has been used for various commercial endeavors ding accountant, laundry, photography, and restaurant use. Among the building's earliest tenants, the San Diego Company at 803 F Street, and Mrs. A.F. Doray's confectionary at 805 F Street.

Historical research has determined that the 801-821 F Street commercial structure is not historically significant, as the building is not associated with any important events or individuals in terms of local, state, or national history. As the identity of the architect and builder could not be ascertained, the building does not represent the work of a master architect, builder, or craftsmen, nor that of an important, creative individual. While the property has been classified as "One Part Commercial Brick Block," and has been called a "splendid example of this type [of construction]," further study and/or research is necessary to determine whether the structure embodies the distinctive characteristics of a type, period or method of construction. Such a determination will dictate whether the resource is eligible for listing on the local register.

B11.Additional Resource Attributes: (List attributes and codes) _

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.
McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories


San Diego County Recorders Office

B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley, Scott A.Moomjian,
Office of Marie Burke Lia

Date of Evaluation: October 2001

(This space reserved for official comments.)



Primary #	
HRI #	
Trinomial	
NRHP Status Code 67	

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	
PRIMARY RECORD	Trinomial
	NRHP Status Code_6Z
Other Listings Update of	November 1988 Centre City East Survey Documentation
Review Code	ReviewerDate
Page1 of3 *Resource Name or #: (Assign	ed by recorder) 1111 F Street
P1. Other Identifier:	
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as necessary.	
b. USGS 7.5' Quad Point Loma Date	T; R;¼ of¼ of Sec; B.M
c. Address <u>1111 F Street</u>	City San Diego Zip92101
d. UTM: (Give more than one for large or l	linear resources) Zone 11; mE/_m
e. Other Locational Data (e.g., parcel #, directions to reson APN: 535-133-01-00, Horton's Addition	
*P3a. Description (Describe resource and its major elements and boundaries):	. Include design, materials, condition, alterations, size, setting
Commercial Block Lodging House with a Spanish Eclecand features a deck roof with two, hipped portion	ons, northwest and northeast corner quions, and
	ons, northwest and northeast corner quions, ar

additional, smaller entrances on the north elevation also feature pilasters and a marquee. Exterior building materials consist of stucco-on-lath for the exterior walls, and Mission tiles over the hipped roof sections. Fenestration consists of horizontally aligned, sliding, metal framed windows on every floor. (See DPR 523H, Continuation Sheet for more information)



and codes) <u>HP5; Hotel/Motel</u>
*P4. Resources Present: I Building
Structure Object Site District
Element of District Other (Isolates, etc.) P5b. Description of Photo: (View, date accession #)
*P6. Date Constructed/Age and Sources:
I Historic
☐ Prehistoric ☐ Both
.1927
1988 Centre City East Historic Site Inventory
*P7. Owner and Address:
*P7. Owner and Address: PamelaCotta,Stephen
*P7. Owner and Address: PamelaCotta,Stephen Reichbart, SA Lefkowitz and
*P7. Owner and Address: PamelaCotta,Stephen Reichbart, SA Lefkowitz and Jared Cotta
*P7. Owner and Address: PamelaCotta,Stephen Reichbart, SA Lefkowitz and
*P7. Owner and Address: PamelaCotta,Stephen Reichbart, SA Lefkowitz and Jared Cotta
*P7. Owner and Address: Pamela Cotta, Stephen Reichbart, SA Lefkowitz and Jared Cotta 5888 Bounty Street San Diego, CA 92120 *P8. Recorded by (Name, affiliation, and
*P7. Owner and Address: Pamela Cotta, Stephen Reichbart, SA Lefkowitz and Jared Cotta 5888 Bounty Street San Diego, CA 92120 *P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley,
*P7. Owner and Address: Pamela Cotta, Stephen Reichbart, SA Lefkowitz and Jared Cotta 5888 Bounty Street San Diego, CA 92120 *P8. Recorded by (Name, affiliation, and

Ste. 410, San Diego, CA 92101
*P9. Date Recorded: February 2001 / Owner Information and Photo Updated June 2003 *P10. Type of Survey: (Describe)
P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre City East For Centre City Development Corporation</u>
Attachments: □NONE n Location Map □ Sketch Map ■ Continuation Sheet ■ Building, Structure, and Object Record n Archaeological Record n District Record n Linear Resource Record □ Milling Station Record □ Rock Art Record a Artifact Record n Photograph Record □ Other (List):

DEPARTMENT OF PARKS AND RECREATION HRI#	
BUILDING, STRUCTURE, AND OBJECT RECO	
Page 2 of 3 *NRHP Star *Resource Name or # (Assigned by recorder) 1111 F Street,	atus Code 6Z
B1. Historic Name: Hotel Yale	
B2. Common Name: Hotel Yale	
B3. Original Use: Hotel/Motel B4. Present Use	e: Hotel/Motel
*B5. Architectural Style: Commercial Block Lodging House	
*B6. Construction History: (Construction date, alternations, and date	
Constructed in 1927; original small, double-hung sa	
second floors, and filled in with glass block on third to major modifications, and/or alterations noted.	noor (between 1988 and 2000). No other
*B7. Moved? No	L Location:
*B8. Related Features:	Location.
Bo. Related Features.	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Consaul Construction; Exteri</u>	
	Period of Significance 1927_
Property Type Hotel/Motel Applicable (Discuss importance in terms of historical or architectural context as defined by theme, per	
Originally constructed in 1927, this building was at the supervision of the Office of Marie Lia and Dr. Ray property and building include M.P. Madson (1927) and Seyn building is owned by the Seymour & Sara F. Reichbart Tr San Diego City Directories as the "Yale Hotel" in 1944/1 listed as "Hotel Yale" in 1960, 1965, 1970, 1975, and Street building as the "Hotel Yale Halfway House." Pass include: S.F. McGurk (1944/1945), the Gladys Giolitto be (1965), Mrs. Arlene A. Schleuter (1970), and Henry FRu Past documentation states that upon completion of utmost in hospitality and accommodations," including f baths featuring hot and cold water, public showers, parking was, most likely, a reference to the roof deck and numer (See DPR 523H, Continuation Sheet for more informational Resource Attributes: (List attributes and codes) *B11. Additional Resource Attributes: (List attributes and codes) *B12. References: (partial list)	Brandes. Past owners of the 1111 F Street mour & Frances Reichbart (1988). Today, the rust. The 1111 F Street building appears in 1945, 1950, and 1955. The building then is 1980. The 1984 directory lists the 1111 F st proprietors of the Yale Hotel/Hotel Yale eauty shop (1950), Mrs. Arlene S. Schleuper the 1111 f construction, the Hotel Yale "offered the ifty furnished rooms some with steam heated ng facilities, and "plenty of sunshine" which rous windows (Lia/Brandes:1988).
(See DPR 523H, Continuation Sheet for more information)	
B13. Remarks:	(Sketch Map with north arrow required.)
	* 4
*B14. Evaluator: Wendy L. Tinsley,	F STREET
Office of Marie Burke Lia	1 Dale 2
Date of Evaluation: February 2001	
	Ø # (9)
	li Oc /
	AK. 44.
(This space reserved for official comments.)	(15), (6)
	F 100.00

STREET

2

G

CONTINUATION SHEET

■ Continuation
□ Update

Page __3_ of __3_

Resource Identifier: (Assigned by recorder) 1111 F Street, San Diego, CA 92101

Historic Name: Hotel Yale

P3a. Description (Continued):

Glass block is used to in-fill the smaller, third-floor window openings, which at one time contained, double-hung sash windows. The smaller windows once present on the first and second floors have been stuccoed over. The vertical "Yale Lofts" sign is present on the northwest corner of the building. Overall, the building appears to be in good condition, and appears to have undergone renovations since it was last documented in the original 1988 Centre City East survey.

*B10. Significance (Continued):

Historical research has determined that the 1111 F Street building is neither historically nor architecturally significant. The 1111 F Street building is not associated with any important events, or individuals in terms of local, state, or national history. Moreover, it does not embody the distinctive characteristics of a type, period, or method of 1920s Commercial Block construction, and does not represent the work of a master architect or craftsman. The building is not eligible for listing at the local register.

*B12. References (Continued):

Growth, Paul, Living Downtown, The History of Residential Hotels in the United States, 1994.

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986. San Diego City Directories San Diego County Recorders Office

DPR 523H (1/95)

State of California — The Resources Agency

Primary #	
HRI #	
Trinomial	
NRHP Status Code 7	

DEPARTMENT OF PARKS AND RECREATION	ПП #
PRIMARY RECORD	Trinomial
	NRHP Status Code _ 7
Other Listings Update of	f November 1988 Centre City East Survey Documentation_
Review Code	ReviewerDate
Page1 of3_ *Resource Name or #: (Assign	ned by recorder) 1328-1344 F Street
P1. Other Identifier:	
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as necessary	.)
b. USGS 7.5' Quad Point Loma Date	_T; R;¼ of¼ of Sec; B.M.
c. Address1328-1344 F Street	City <u>San Diego</u> Zip <u>92101</u>
d. UTM: (Give more than one for large or	linear resources) Zone 11; mE/mN
e. Other Locational Data (e.g., parcel #, directions to reso	
APN: 534-345-12-00, Horton's Addition	, Block 53, Lots G & H
*P3a. Description (Describe resource and its major elements	s. Include design, materials, condition, alterations, size, setting,
and boundaries):	

Originally constructed in approximately 1925, this Two-Part Commercial Block Building has a general square shaped plan, and features a flat roof with an extended parapet that varies in heights around the facades. The parapet is covered and capped with brickwork. The exterior facade is symmetrical and is divided into distinct sections by pilasters capped with brickwork. A horizontal band of applied, sealed asphalt painted blue divides the two-floors; the first-floor consists of approximately six in-filled window and garage bays, some of which are recessed. The second floor features multi-colored brickwork in both horizontal and vertical patterns, and each bay features two industrial style windows with a multi-pane sash pattern, featuring a central, four pane casement section bordered by twelve fixed panes. Overall, this building appears to be in fair condition.



P3b. Resource Attributes: (List attributes HP3;HP8 and codes)

*P4. Resources Present: I Building Structure d Object D Site d District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)_

*P6. Date Constructed/Age and Sources:

Historic

d Prehistoric d Both 1925

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

San Diego Community College District 3375 Camino Del Rio South San Diego, CA 92116

*P8. Recorded by (Name, affiliation, and address): Wendv L. Tinslev. Scott A. Moomijan, Office of <u>Marie Burke Lia, Attorney at</u> Law, 427 C Street, Ste. 416. San Diego. CA 92101

P9. Date Recorded: October 2001 / Photo Updated June 2003

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) __Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: □NONE □ Location Map □ Sketch Map •Continuation Sheet ■ Building, Structure, and Object Record D Archaeological Record D District Record Linear Resource Record Milling Station Record Record Record Record Record Record D Rock Art Record ☐ Artifact Record ☐ Photograph Record a Other (List):

State of California — The Resources Agency Primary #	
BUILDING, STRUCTURE, AND OBJECT RECO	
Page 2 of 3 *NRHP St *Resource Name or # (Assigned by recorder) 1328-1344 F St	atus Code_7
B1. Historic Name: Standard Parachute Company Buildi	
B2. Common Name: State of California Industries F	
B3. Original Use: Commercial B4. Present Use	
*B5. Architectural Style: Two-Part Commercial Block styl	
*B6. Construction History: (Construction date, alternations, and date	of alterations)
Constructed in 1925; ground floor window and garage systems have been modified, dates unknown. No other mo	
*B7. Moved? No □Yes □Unknown Date:Origina *B8. Related Features:	ii Location.
Do. Related Features.	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: Theme Architecture Area _San Diego	
Property Type Commercial Applicable (Discuss importance in terms of historical or architectural context as defined by theme, p	
Originally constructed in 1925, this building was the supervision of the Office of Marie Lia and Dr. Ray Bra property and building include William Sweetland (1925 Sweetland used the building for rental purposes. Past the 1328-1344 P Street building include: the "Mission grocery company (1927-1930), John Lovranich operated fir physical culture company, both identified as being located sausage manufacturing business, located at 1328 F Street business, located at 1328 F Street (1940), and L.B. Marsh Allied Refrigeration Company, loca City Directories reveal past occupants of 1330 F St. (1944/1945); past occupants of 1342 F Street include: located at 1342-1344 (1950), State Center Industries For California Industries For The Blind (1965, 1969/197 Incorporated (1975), and vacant (1980, 1984). (See DPR 523H, Continuation Sheet for more information) (See DPR 523H, Continuation Sheet for more information)	andes. Past owners of the 1328-1344 F Street (), for whom the building was constructed. documentation reveals past occupants of the Public Market," occupied by H.H. Caravan's st a grocery business, and later an herb and d at 1334 F Street (1930-1942), Fred Adolphy; (1935), William Blanz; sausage manufacturing rigeration Company, located at 1342 F Street ated at 1342 F Street (1942, 1943). San Diego reet include the Standard Parachute Company vacant (1944/1945), the State Blind Shop, for The Blind (1955, 1960), San Diego Center (0), California Industries For The Blind,
(see B1R 5251), Communición Bleet for more imprimitation)	
B13. Remarks:	(Sketch Map with north arrow required.)
*B14. Evaluator: Wendy L. Tinsley, Scott A. Moomjian, Office of Marie Burke Lia Date of Evaluation: October 2001	(1) (3) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1
	(2) c v (5)
	53 4
(This space reserved for official comments.)	2 00° 1° 00
	(D) () (2)

F

ST

Primary #	
HRI #/Trinomial	

CONTINUATION SHEET

■ Continuation □ Update

Page 3 of 3

Resource Identifier: (Assigned by recorder) 1328-1344 F Street, San Diego, CA 92101

Historic Name: Standard Parachute Company Building

*B10. Significance (Continued):

Historical research has determined that the 1328 F Street building does not appear to be historically significant, as it is not associated with any important events, or individuals in terms of local, state, or national history. As the identity of the architect could not be ascertained, the 1328-1344 F Street building does not represent the work of a master architect or craftsman. While the property has been classified as a "Two Part Commercial Bank," further study and/or research is necessary to determine whether structure embodies the distinctive characteristics of this type, period or method of construction. Such a determination will dictate whether the resource is eligible for listing on the local register.

*B12. References (Continued):

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

Longstreth, Richard, The Buildings of Main Street; A Guide To American Commercial Architecture, 1987.

McAlester, Virginia & Lee, A Field Guide To American Houses, 1986. San Diego City Directories San Diego County Recorders Office

PRIMARY RECORD


and boundaries):

Primary #	
HRI # 2138-0208-0000	
Trinomial	
NRHP Status Code 67	

I IZIIA	MINI INECUIND			<u> </u>			
			NRF	IP Status Co	de_6Z		
		Other Listings	Update of Nov	rember 1988	Centre City Ea	ast Survey Doc	umentation
		Review C	ode	Reviewer		Date	
Page _	1 of 3	*Resource Name or	#: (Assigned by	recorder)	1451-1453 F	Street	
P1.	Other Identifie	r:					
*P2.	Location: n Not for Pu	ublication 📕 Unrestrict	ed *	a. County	San Diego		
	b and P2c or P2d. Atta						
*b. US	GS 7.5' Quad Po	int Loma Date	<u>}</u> T	, R	¼ of¼	of Sec; _	B.M
C.	Address 1451-	-1453 F Street		City _ <u>_Sar</u>	n Diego	.Zip	2101
d.	UTM: (Give more	than one for la	rge or line	ar resour	ces) Zone 1	.1; m	E/mN
e.		(e.g., parcel #, direction -00, Culverwell'					nd
	Horton's Additi	on, Block 176,	portion of I	Lots J thi	ru L		

Originally constructed in approximately 1889-1890, this simple, single-story, multiple-family residence was designed in a Flat Roof Italianate vernacular style. It has a rectangular shaped plan, and features a false front with a bracketed cornice and a horizontal Greek Key band. A bracketed hood is present over the front entrance on the street elevation. The only window on the north, street facing elevation is tri-partite, featuring a wide, center double-hung sash window, flanked on both sides by a narrow, double-hung sash window. (See DPR 523H, Continuation Sheet for more information)

Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting,



 $\begin{tabular}{ll} \textbf{P3b.} & \textbf{Resource Attributes:} & \textbf{(List attributes and codes)} \\ \textbf{HP2} & \end{tabular}$

*P4. Resources Present: | Building d Structure d
Object d Site d District d Element of District d
Other (Isolates, etc.)
P5b. Description of Photo: (View, date, accession #}

*P6. Date Constructed/Age and Sources:

I Historic

d Prehistoric d Both

1889-1890

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Ponce Living Trust 11-18-98

7780 Tripoli Road

San Diego. CA 92126

*P8. Recorded by (Name, affiliation, and address):

Wendy L. Tinslev,

<u>Office of Marie Burke Lia,</u>

Attorney at Law.

427 C Street. Ste. 416

San Diego, CA 92101

*P9. Date Recorded: February 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation_
Attachments: □NONE n Location Map □ Sketch Map •Continuation Sheet ■ Building, Structure, and Object Record □ Archaeological Record n District Record n Linear Resource Record n Milling Station Record n Rock Art Record □ Artifact Record n Photograph Record D Other (List):

Primary # State of California — The Resources Agency HRI# <u>138-0208-0000</u> DEPARTMENT OF PARKS AND RECREATION BUILDING, STRUCTURE, AND OBJECT RECORD *NRHP Status Code. 6Z Page 2 of 3 *Resource Name or # (Assigned by recorder) ____1451-1453 F Street, San Diego, CA 92101 B1. Historic Name: None Common Name: None B4. Present Use: Residential (Multi-Family) Original Use: Residential (Single-Family)_____ *B5. Architectural Style: Flat Roof Italianate vernacular *B6. Construction History: (Construction date, alternations, and date of alterations) Constructed in approximately 1889-1890; rear addition; date unknown. *B7. Moved? No □Yes □Unknown Date:___ Original Location: *B8. Related Features: b. Builder: Unknown B9a. Architect: Unknown *B10. Significance: Theme N/A Area San Diego Period of Significance 1889-1890_ Property Type Residential Applicable Criteria N/A_ (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Originally constructed in approximately 1889-1890, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past owners of the 1451-1453 F Street property and building include: Trinidad G. Aramburo (1950 to c.1970), and Susan & Julio Ponce (1988). Past documentation reveals past residents of the 1451-1453 F Street building include: mariner & bridge builder Amun Sevort (1890-1906), and the Flores Family (1922-1926). San Diego City Directories reveal past residents of the 1451 F Street unit include: R.D. Vadev (1944/1945), owner Trinidad G. Aramburo (1950, 1955, 1960), vacant (1965), Trinidad G. Aramburo (1970, 1975), and Julio Ponce (1980, 1984). San Diego City Directory listing also indicate that the 1453 F Street unit may first have been listed as 1451 ½ F Street, as there are both addresses appear; 1451 ½ in 1965, and 1453 in 1975, 1980, and 1984. Past residents of this unit include: no return (1965), John Ameruss (1975), and vacant (1980, 1984).

Historical research has determined that the 1451-1453 F Street building is neither historically nor architecturally significant. The 1451-1453 F Street building is not **associated** with any important events, or **individuals** in terms of local, state, or national history. Moreover, it does not embody the **distinctive** characteristics of a type, period, or method of flat roof Italianate style construction, and does not represent the work of a master architect or craftsman. The building is not eligible for listing on the local register.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, *Historic Site Inventory of Centre City East*, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office


B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley,

Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



CONTINUATION SHEET

Primary #_______ HRI #/Trinomial_2138-0208-0000

● Continuation □ Update

Page 3 of 3
Resource Identifier: (Assigned by recorder) 1451-1453 F_Street, San Diego, CA 92101
Historic Name: None

P3a. Description (Continued):

The upper sashes on all three windows are most likely fixed. Exterior building materials consist of horizontal clapboard siding for the exterior walls, a section of vertical wood siding over the foundation at the sidewalk level, and composition paper for the roof. Overall, this building appears to be in fair condition.


DPR 523H (1/95)

Primary #			
HRI #			
Trinomial			
NRHP Status Code_	6Z		
ovember 1988 Centre	F. Sitv	Doumenvat.ion	

PRIMARY RECORD	Trinomial	
	NRHP Status Code_62	Z
Othe	er ListingSupdate of November 1988 Centre	Easity Doumenvation
	Review CodeReviewer	Date
Page1 of2 *Resourc	e Name or #: (Assigned by recorder) 1455	5 F Street / 1459 F Street
P1. Other Identifier:		
*P2. Location: 🗆 Not for Publication 📗	Unrestricted * a. County Sa	n Diego
and (P2b and P2c or P2d. Attach a Location		
*b. USGS 7.5' Quad Point Lor	na Date T; R;%	4 of% of Sec; B.M
c. Address <u>1455 F Street</u>	/ 1459 F Street City San Die	eqo Zip92101
d. UTM: (Give more than on	e for large or linear resources)	Zone 11;mE/m
e. Other Locational Data (e.g., parce	el #, directions to resource, elevation, etc., as	appropriate):
APN: 535-171-09-00, Cul	Lverwell's Addition, Par 1, PM A	360

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1900, this single-family, three-story residence was designed in a Folk Victorian vernacular architectural style. It has a general rectangular shaped plan and features a moderately pitched front gabled roof with slight eave overhang, and an open, full length porch on the street facing facade. The porch features stickwork, wooden posts for support, and a shed style roof. Exterior building materials consist of shiplap siding with cornerboards for the exterior walls, and most likely composition shingles for the roof. A large tree obstructs the view of the front of the residence from the street. The poor condition of the residence and its surroundings, coupled with the presence of a major addition to the rear of the building results in the conclusion that this building has lost all architectural integrity.



P3b. Resource Attributes: (List attributes and codes) HP2; HP6

Resources Present: I Building d Structure d Object d Site d District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

I Historic

d Prehistoric d Both C.1900

1988 Centre City East Historic Site Inventory *P7. Owner and Address:

Kenneth Bourke 1455 F Street

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and

address): Wendy L. Tinsley, Marie Burke Lia, Office Attorney at Law, 427 C Street, Ste. 416. San Diego, CA 92101

*P9. **Date Recorded:** February 2001 / Owner Information and Photo Updated June 2003

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre</u> City East For Centre City Development Corporation

Attachments: UNONE Location Map n Sketch Map Continuation Sheet Building, Structure, and Object Record n Archaeological Record c District Record □ Linear Resource Record □ Milling Station Record □ Rock Art Record ☐ Artifact Record D Photograph Record n Other (List):

State of California — The Resources Agency Primary #
DEPARTMENT OF PARKS AND RECREATION HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD
Page 2 of 2 *NRHP Status Code 6Z
*Resource Name or # (Assigned by recorder)1455 F Street, San Diego, CA 92101
B1. Historic Name: <u>Judson Property</u>
B2. Common Name: Bourke Property
B3. Original Use: Residential (Single-Family) B4. Present Use: Residential/Commercial
*B5. Architectural Style: Folk Victorian vernacular
*B6. Construction History: (Construction date, alternations, and date of alterations) Constructed in approximately 19000; rear addition; date unknown.
*B7. Moved? No
*B8. Related Features:
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>
*B 10. Significance: Theme N/A Area San Diego Period of Significance <u>c.1900</u>
Property Type Residential Applicable Criteria N/A_ (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)
Originally constructed in approximately 1900, this building was previously documented in November
1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past owners of the 1455
F Street property and building include: John B. Judson (1900), John B. Ameruss (from at least 1950
to c.1970s), Melvin C. Bourke (c.1980s), and Ken & Sue Bourke and Antonio & Christine Grimalda (1988).
The building, today, is owned by Kenneth Bourke. San Diego City Directories reveal past residents
include Mrs. Emma Stumpf (1944/1945), owner John B. Ameruss (1950, 1955), vacant (1960), owner John
B. Ameruss 1965, 1970), no listing (1975), and owner Melvin C. Bourke; Bourke Real Estate Sales (1980, 1984). Past documentation states that Capitalist John B. Judson purchased this property in 1900 and
1301). Past documentation states that capitalist boili b. budson purchased this property in 1900 and

Historical research has determined that the 1455 F Street building is neither historically nor architecturally significant. The 1455 F Street building is not associated with any important events, or individuals in terms of local, state, or national history. Moreover, it does not embody the distinctive characteristics of a type, period, or method of Folk Victorian construction, and does not represent the work of a master architect or craftsman. The **building** is not eligible for listing on the local register.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.


most likely erected this residence to be used for rental purposes.

San Diego City Directories

San Diego County Recorders Office

*B14. Evaluator: Wendy L. Tinsley,
Office of Marie Burke Lia
Date of Evaluation: February 2001

(This space reserved for official comments.)



(Lia/Brandes, 1988)

Primary #	
HRI # <u>2138-0209</u>	-0000
Trinomial	
NRHP Status Code 5	52.

State of	f California — The Resources Agency	Primary #
DEPART	TMENT OF PARKS AND RECREATION	HRI #2138-0209-0000
PRIM	IARY RECORD	Trinomial
		NRHP Status Code 5S2
	Other Listings Upo	date of November 1988 Centre City East Survey Documentation
	-	Reviewer Date
Page		igned by recorder) 1610-1620 F Street
гауе <u> </u>	Other Identifier:	ighted by recorder) 1010 1020 1 Street
*P2.		a. County San Diego
	2b and P2c or P2d. Attach a Location Map as necessary	8
		; R;¼ of¼ of Sec; B.M.
c.	Address 1610-1620 F Street	City San Diego Zip 92101
d.		r linear resources) Zone 11;mE/mN
e.	Other Locational Data (e.g., parcel #, directions to re APN: 534-360-12-00, Culverwell's Add.	esource, elevation, etc., as appropriate):
*P3a.		. Include design, materials, condition, alterations, size, setting,
rsa.	and boundaries):	. Include design, materials, condition, arterations, 3126, secting,
Anne s on a v column	style, a full length porch is present and fe wood pedestal to the level of the iron por as are grouped in units of two, and three o	located on the east eave wall. Typical to the Queen eatures a boxed cornice, and classical columns raised ch railing. Typical to the Free Classic style, the on the street facing portion, and single columns are DPR 523H, Continuation Sheet for more information)
10/6/6		P3b. Resource Attributes: (List attributes and codes) HP3
/		
4		
		Structure n Object Site District
	2	Element of District Other (Isolates, etc.) P5b. Description of Photo: (View, date,
		accession #)
100		*P6. Date Constructed/Age and Sources:
		I Historic
		☐ Prehistoric ☐ Both
1	TIP	1906 1988 Centre City East Historic Site Inventory
		*P7. Owner and Address:
		Sara & Lionel Rowe
		Family Trust of 1992
		Roger Boomer. James Rone c/o Simcal Properties Inc
II		1001 B Ave 107, Coronado, CA 92118
		*P8. Recorded by (Name, affiliation, and
2		address): Wendy L. Tinsley,
		Office of Marie Burke Lia.
-	A District of the last of the	Attorney at Law, 427 C Street,
		Ste. 416, San Diego, CA 92101
*P9.	Date Recorded: February 2001 / Owner	Information and Photo Updated June 2003

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre C+tv East For Centre City Development Corporation

Attachments: DNONE n Location Map n Sketch Map Continuation Sheet Building, Structure, and Object Record n Archaeological Record n District Record n Linear Resource Record n Milling Station Record Rock Art Record a Artifact Record n Photograph Record n Other (List):_

State of California — The Resources Agency	_1
DEPARTMENT OF PARKS AND RECREATION	ŀ
BUILDING, STRUCTURE, AND 	OBJEC [*]
Page 2 of 3	4

Primary #			
HRI# <u>2138-0209-0000</u>			

Period of Significance 1906_

BUI	BUILDING, STRUCTURE, AND OBJECT RECORD													
Page .	2	of .	3			*NF	RHP S	tatus	Code	_ 5S2				
*Reso	ource Na	ame o	r# (Assigne	d by recor	der)	1610-1620	FS	treet	, San	Diego	, CA	9210	1	
B1.	Histori	c Nam	ne: Kreiss	/Wilcox	Resid	ence								
B2.	Commo	on Na	me: Kreis	ss/Wilco	x Resi	.dence								
B3.	Origina	l Use	: Reside	ntial (S:	ingle-	Family)_	В4.	Preser	nt Use	: Resid	dential	l_(Mu	lti-Fa	mily)
*B5	. Archi	tectura	al Style: v	ernacu	lar Hip	pped Roof	Free	Clas	sic C	ueen A	Anne V	ictor	rian	
*B6.	*B6. Construction History: (Construction date, alternations, and date of alterations) Constructed in 1906; no substantial modifications and/or alterations noted.													
*B7.	*B7. Moved? No □Yes □Unknown Date: Original Location:													
*B8.	Related	l Feat	ures:											
B9a.		Αı	rchitect: Unl	(nown_	b. Build	der: Unkno	wn							

Property Type Residential Applicable Criteria C_ (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Area San Diego

Originally constructed in 1906, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation reveals past owners of the 1610-1620 F Street property and building include: Jacob W. Kreiss (pre-July 1906), H.W. Wilcox (July 1906), Nasim Pares Sr. (c.1941), and Elise & Jane Fares (1988). Past documentation states that in 1941, a notice of completion was signed by N. Fares for the rehabilitation of the residence, or a conversion to a rooming house (Lia & Brandes: 1988) . This is consistent with the fact that a 1921 Samborn Fire Insurance map depicts a two-story dwelling with porch as 1620 F Street, indicating that the home had not yet been converted from a single-family to multi-family residence which included the addresses 1610 and 1612 F Street. San Diego City Directories reveal past residents of 1610 F Street include: Andrew Sobier (1944/1945), Lena Roberts (1950), William B. Valley (1955-1965), Betty L. Valley (1970), Mrs. Pauline Carpenter (1975), and Betty L. Valley (1980,1984). Past residents of 1612 F Street include: R.J. Vaughn (1944/1945), Helen Pezdek (1950), Lorenzo Sanchez & William Sanchez (1955), Robert Langland & Mary B. Strawder (1965), Larry Benjamin (1975), and Maureen Wadsworth (1970, 1980, 1984). San Diego City Directories reveal that the building contained approximately six apartment units, and was listed as the San Diego Apartments in 1944/1945, 1950, 1955, 1960, 1965, and 1970, located at 1620 F Street. From 1975 through 1984, the name San Diego Apartments does not appear in directories at that address.

(See DPR 523H, Continuation Sheet for more information)

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

*B10. Significance: Theme Architecture

(See DPR 523H, Continuation Sheet for more information)


B13. Remarks:

*B14. Evaluator:_ Wendy L. Tinsley

Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



CONTINUATION SHEET

I Continuation • Update

Page3 of3			
Resource Identifier: (Assigned by recorder)	1610-1620 F Stree	t, San Diego,	CA 92101
Historic Name: Kreiss/Wilcox Re	esidence		

*P3a. Description (Continued):

A majority of the **windows** appear to be double-hung sash, with the exception of one fixed, four pane window located in the center of the second floor bay, and a single horizontal **casement** window located on the southwest corner of the **second** floor. Exterior building materials consist of composition shingles for the **roof**, horizontal shiplap siding for the exterior walls, wood for the front **steps**, and wood lattice used to conceal the foundation. A dirt driveway is adjacent to the east side of the building, and small lawn area is located in front of the building. Overall, the exterior of the 1620 F Street building appears to be in good condition.

*B10. Significance (Continued):

Historical research has determined that the 1610-1620 F Street building is not historically significant, as the building is not associated with any important events or individuals in terms of local, state, or national history. However, the building is architecturally significant at the local level, as it embodies the distinctive characteristics of a type, period, or method of the vernacular Queen Anne Free Classic architectural style of Victorian construction. As the identity of the architect could not be ascertained, the building does not represent the work of a master architect or craftsman.

*B12. References (Continued):

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986. San Diego City Directories San Diego County Recorders Office

DPR 523H (1/95)

Primary #	
HRI # 2138-0228-0000	
Trinomial	
NRHP Status Code 5S2	

PERANTIMIENT OF PANNS AND NECKEA	ION	TITLE II E TOO OZZE			
PRIMARY RECORD		Trinomial	5S2		
	Other listings Unda	ite of November 1988		vev Document	ation
		Reviewer_			ació
Page1 of3 *Resource					
P1. Other Identifier:					
*P2. Location: □ Not for Publication	Unrestricted *	a. County	San Diego		
and (P2b and P2c or P2d. Attach a Locat *b. USGS 7.5' Quad <u>Point Loma</u>			_¼ of¼ of Sec_	_;	B.M.
c. Address <u>643-655 G Stre</u>	<u>:et</u>	City <u>San Diego</u>	Zip	92101	
d. UTM: (Give more than or	ne for large or	linear resource	es) Zone 11;	mE/	mN
Other Locational Data (e.g., parc APN: 535-106-11-00, He					_
*P3a. Description (Describeresource ar	d its major elements.	Include design, materia	ils, condition, alterat	ions, size, se	tting,

Originally constructed in 1888, this single-story, One Part Commercial Block building features an Enframed Wall Window, and was designed with an Italianate architectural influence. It has a general rectangular shaped plan, and a flat roof. The north, street facing elevation features recessed bow windows, a bracketed cornice, a protruding brick exterior wall portion which separates the recessed windows, and a central, single fixed window with a multiple pane pattern. Overall, the building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP6					
*P4. Resources Present: I Building					
Structure d Object d Site d District of					
Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date accession #)					
*P6. Date Constructed/Age and Sources:					
I Historic					
d Prehistoric d Both					
1988 Centre City East Historic Site Inventor					
*P7. Owner and Address:					
Robert & Jacqueline Sinclair Trust					
258 Kolmar Street					
La Jolla, CA 92037					
*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley. Scott					

Moomijan, Office of Marie Burke Lia. Attorney at Law, 427 C Street. Ste. 416, San Diego, CA 92101

Date Recorded: October 2001 / Owner Information and Photo Updated June 2003

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) __Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments:

NONE

Location Map

Sketch Map

Continuation Sheet I Building, Structure, and Object Record D Archaeological Record n District Record n Linear Resource Record Milling Station Record n Rock Art Record n Artifact Record n Photograph Record □ Other (List):

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI#138-0228-0000
BUILDING, STRUCTURE, AND OBJE	
Page _ 2 _ of _ 3	*NRHP Status Code_5S2_
*Resource Name or # (Assigned by recorder)643-6	
B1. Historic Name: J.S. Harbison Grocery Bu	ilding
B2. Common Name: <u>International gallery</u> B3. Original Use: Commercial (Grocery Wareh	PA Procent Use: Commercial
	Block with Enframed Wall Window & Italianate Influence_
*B6. Construction History: (Construction date, alternation	
Constructed in 1888; according to past	documentation, this building was remodeled in 1985;
	ade. No other major alterations and/or modifications
known.	
*B7. Moved? No	Original Location:
*B8. Related Features: B9a. Architect: <u>Unknown</u> b. Builder: <u>G</u>	eorge Voung/French & Rotos
*B10. Significance: Theme Person/Architecture	
Property Type Commercial	Applicable Criteria B, C_
(Discuss importance in terms of historical or architectural context as def	fined by theme, period, and geographic scope. Also address integrity.)
the supervision of the Office of Marie Lia and owners of the 643-655 6 Street property and occupants of the 643-655 G Street building in Gordon Ingle (1906), and Hazzard, Gould, Sweetwater Valley resident and noted apiarist, throughout the country, and maintained his who from 1888 through 1906. Harbison owned and le 1913. (Lia & Brandes:1988) San Diego City Dir no listing (1944/1945, 1950, 1955, 1960), Unio Vespa San Diego motorcycle sales (1975, 1980 1998/1999). Past occupants of 645 G Street (1950), Jacobson Neon Sign Studio; Silk Scr. 1969/1970, 1975), the Pannikan wholesale gift	les)
B13. Remarks:	(Sketch Map with h arrow required.)
	(Sketch Map with a now required.)
*B14. Evaluator: Wendy I. Tinsley. Scott A. Me	comii an
Office of Marie Burke Lia	GOOMYTAN, G
Date of Evaluation: October 2001	
(This space reserved for official comments.)	© 106 100 100 100 100 100 100 100 100 100
(Time appearance of the control of t	[] (D) (D) F

5

MARKET

\$

CONTINUATION SHEET

Primary #		
HRI #/Trinomial_	2138-0228-0000	

■ Continuation □ Update

Page __3__ of __3__ Resource Identifier: (Assigned by recorder) 643-655 G Street, San Diego, CA 92101

Historic Name: J.S. Harbison Grocery Building

*B10. Significance (Continued):

Historical research has determined that the 643-655 G Street building appears to be both historically significant at the local level. The building is associated with with J.S. Harbison, for whom San Diego County's Harbison Canyon is named. The building does not represent the work of a master architect or craftsman. While the property has been classified as a "One Part Commercial Block with Enframed Wall Window & Italiante Influence," further study and/or research is necessary to determine whether the structure embodies the distinctive characteristics of this type, period or method of construction.

*B12. References (Continued):

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. Longstreth, Richard, The Buildings of Main Street; A Guide To American Commercial Architecture, 1987.

McAlester, Virginia & Lee, A Field Guide To American Houses, 1986. San Diego City Directories San Diego County Recorders Office

DPR 523H (1/95)

State of California — The Resources Agency

and boundaries):

Primary #			
HRI#_2138-0228-0000			
Trinomial			

DEFAR	TIVIENT OF PARKS AND RECREATION	HKI#_4130-0248-	-0000	
PRIM	IARY RECORD	Trinomial		
	Other Listings_Update or	f November 1988 Cent:	re City East Survey Doo	rumentation
	Review Code	Reviewer	Date	
Page _	of *Resource Name or #: (Assigne	ed by recorder) 675	Q Street	
P1.	Other Identifier:			
*P2.	Location: □ Not for Publication ■ Unrestricted *	a. County S	an Diego	
and (P2	2b and P2c or P2d. Attach a Location Map as necessary.)		
b. US	GGS 7.5' Quad Point LomaDate	T; R;	1/4 of 1/4 of Sec;	B.M.
c.	Address 675 G Street C	ity <u>San Diego</u>	Zip92101	
d.	UTM: (Give more than one for large or l	inear resources)	Zone 11;m	nE/mN
e.	Other Locational Data (e.g., parcel #, directions to reso	urce, elevation, etc., as	s appropriate):	
	APN: 535-106-11-00, Horton's Addition, Block	k 86, E ¼ Lot K &	E ⅓ Lot L;	
	and Block 30 Map 456 US 6.			
*P3a.	Description (Describe resource and its major elements.	Include design, mater	rials, condition, alterations,	size, setting,

Originally constructed in 1909, this three-story brick and timber building was designed in a Two-Part Commercial Block style. It features a flat roof, a parapet, a boxed cornice on the north elevation, brick belt coursing between the third-floor window line and the cornice, and on the first and second floor window lines, and large enframed, ground floor storefront windows on the G Street and 7th Avenue facades. Fenestration consists of paired, double-hung windows on the second and third floors. The north elevation brick features painted bands between the second and third-floor windows. Overall, the building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP6; HP8 Resources Present: I Building d Structure d Object d Site

District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)_ *P6. Date Constructed/Age and Sources:

I Historic d Prehistoric d Both 1909 1988 Centre City East Historic Site Inventory

*P7. Owner and Address: Robert C. & Jacqueline Sinclair Trust 258 Kolmer Street San Diego, CA 92037

*P8. Recorded by (Name, affiliation, and address): Wendy L. <u>Tinsley, Scott</u> A. Moomjian, Office of Marie Burke Lia, Attorney at Law, 427 C Street. Ste. 416, San Diego, CA 92101

Date Recorded: October 2001

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre</u> City East For Centre City Development Corporation

Attachments: UNONE D Location Map Uncertain Sheet • Building, Structure, and Object Record D Archaeological Record D District Record Linear Resource Record Milling Station Record Record Record Record District Record D a Artifact Record Photograph Record Other (List):

State of California — The Resources Ag	ency
DEPARTMENT OF PARKS AND RECREA	ATION
DI III DINO CEDUCTURE	AND

Primary	#	
HRI# _	2138-0228-0000	

BUILDING, STRUCTURE, AND OBJECT RECORD

Page 2 of 2 *NRHP Status Code_7

*Resource Name or # (Assigned by recorder) 675 G Street, San Diego, CA 92101

B1. Historic Name: The Hazard, Gould, and Company Building

B2. Common Name: The Pannikin Building

B3. Original Use: Light Industrial/Commercial

B4. Present Use: Commercial

*B5. Architectural Style: Two-Part Commercial Block

*B6. Construction History: (Construction date, alternations, and date of alterations)

Originally constructed in 1909, original windows most likely replaced, first-floor storefront windows added on the 7th Avenue facade (dates unknown), in addition to the north elevation, according to past documentation, the cornice originally spanned along the east elevation (Lia/Brandes: 1988), it appears to have been removed (date unknown).

*B7. Moved? | No Dyes Dunknown Date: Original Location:

*B8. Related Features:

B9a. Architect: <u>Unknown</u> b. Builde *B10. Significance: Theme Architecture

b. Builder: W.J. Kirkwood

Area San Diego Perioc

Period of Significance 1909_

Property Type Commercial Applicable Criteria C_

(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Originally constructed in 1909 by J.S. Harbison, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past documentation states that the 675 G Street building was previously occupied by the Pierce Furniture Company and the Davidson Furniture Company, and that "it is one of the few remaining, nearly unaltered, turn of the century commercial structures in this part of the downtown area." (Lia/Brandes:1988).

Historical research has determined that the 675 G Street building is not historically significant, as it is not associated with any important events or individuals, in terms of local, state, or national history. As the identity of the architect could not be ascertained, the 675 G Street building does not represent the work of a master architect, nor that of an important, creative individual. In addition, the builder, H.J. Kirkwood has not been identified as a master. While the property has been classified as a "Two Part Commercial Bank," further study and/or research is necessary to determine whether the structure embodies the distinctive characteristic of this type, period or method of construction. Such a determination will dictate whether the resource is eligible for listing on the local register.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City Bast, 1988.

Longstreth, Richard, The Buildings of Main Street; A Guide To American Commercial Architecture, 1987. San Diego City Directories


San Diego County Recorders Office

B13. Remarks:


B14. Evaluator: Wendy L. Tinsley, Scott A. Moomijan.
Office of Marie Burke Lia

Date of Evaluation: October 2001

(This space reserved for official comments.)



675 G St



りらりの

	f California — The Resources Agency	Primary #				
DEPAR	TMENT OF PARKS AND RECREATION	HRI#2138-0243-0000				
PRIN	IARY RECORD	Trinomial				
		NRHP Status Code6Z				
	Other Listings					
		Reviewer Date				
Page	1 of3_ *Resource Name or #: (Assign Other Identifier:	ned by recorder) The Hiatt Residence				
*P2.		a. County San Diego				
	2b and P2c or P2d. Attach a Location Map as necessary GGS 7.5'Quad Point Loma Date	y.) T; R;¼ of¼ of Sec;B.M.				
c.	Address 903-915 Island Avenue City	San DiegoZip 92101_				
d.	UTM: (Give more than one for large or linear resources	s) Zone; mE/ mN				
e.	Other Locational Data (e.g., parcel #, directions to res					
*P3a.	Description (Describe resource and its major elemen and boundaries):	ts. Include design, materials, condition, alterations, size, setting,				
cornic reminis paired influe	es over the first floor entry doors, which are l scent of the Colonial Revival style in that it is windows treated with wood molding surrounds, an ences of the Dutch Colonial style which appears	atures a low-hipped roof flared at the eaves and boxed ocated on either side of the building. The property is features a small, one-story entry porch, fenestration of d wood shiplap siding. The flared roof suggests earlier in some revival styles. Constructed on a low concrete d to a two-family residence soon after its completion.				
*P3b.	Resource Attributes: (List attributes and codes) HP2					
*P4. R	esources Present: ■ Building □ Structure □ Object □	☐ Site ☐ District ☐ Element of District ☐ Other (Isolates, etc.)				
		P5b. Description of Photo: (View, date, accession #) Viewfacing				
		southeast, December 1998				
		*P6. Date Constructed/Age and Sources:				
_ 2x		M Historic				
		□ Prehistoric □ Both				
	F	c.1902 - Centre City Inventory				
		*P7. Owner and Address:				
		Caryl Iseman & Darryl R. Spangler 903 Island Street				
		San Diego CA 92101				
	TE BE NET	*P8. Recorded by (Name, affiliation, and				
		address): Office of Marie Burke Lia,				
		427 C Street, Suite 416,				
		San Diego, CA 92101				
		*P9. Date Recorded: _December 1998				
		. Updated April 2004				
*P10	Type of Survey: (Describe) Intensive Survey	For Potential Redevelopment				
		or enter "none".) Evaluation of Historic Resources				
	in Project Study Area For Proposed Spo					
	ments: □NONE □Location Map □Sketch Map ☑Contin					
	□Archaeological Record □District Record □Linear Resource Record □Milling Station Record □Rock Art Record					

□Artifact Record □Photograph Record □ Other (List):

State of California — The Resources Agency				
DEPARTMENT OF PARKS AND RECREATION		0243-0000		
BUILDING, STRUCTURE, AND OBJE	CT RECORD	G	7	
Page 2 of 3				
*Resource Name or # (Assigned by recorder) The				
B1. Historic Name: The Hiatt Residence B2. Common Name:			0.00	
B3. Original Use: Residential	B4. Present Use: R	esidential		
*B5. Architectural Style:Colonial Revival				
*B6. Construction History: (Construction date, alterna Altered from a single-family to a		,		
*B7. Moved? ⊠No □Yes □Unknown Date:	Original	Location:		
*B8. Related Features: Lattice fence along western perim	eter, one story	garage att	tached to r	ear of house.
B9a. Architect: <u>Unknown</u>				
*B10. Significance: Theme Architecture				
Period of Significance c.1902 Pro (Discuss importance in terms of historical or architectural con	perty Type Resid	ential period and geogra	Applicable	Criteria C
This multi-family residence has been a rental a Colonial Revival style of architecture, the h	nome appears to ha	ave undergone	e few alterat	tions to mar its
architectural integrity. The building derives it elements of that style of architecture which was	_			
during the first half of this century. These de				
shiplap siding, a low-hipped roof with boxed corn of housing which was constructed in San Diego at t				
		Jan 1 Tol Dall		jing maddie erder:
B11. Additional Resource Attributes: (List attributes and c	odes)			
2.7.7.7.00.00.00.00.00.00.00.00.00.00.00.				
*P40 - /				
*B12. References: "Lia/Brandes Team" Centre City Eas	st Survey, 1988.			
McAlester, Virginia & Lee. A Field			es.	
New York: Alfred A. Knopf,	1986.			
San Diego City Directories				
San Diego County Recorder's Office San Diego Water & Sewer Records			3 3	
can plogo water a cower records			5 E	
B13. Remarks:				ISLAND AVENUE
		5-115	535-114	ISLAND AVENUE 535-126
*B14. Evaluator:			1	2 13
		- <u>-</u>	8	
Date of Evaluation:		AVENU	2 NINTH AVENUE	S 10 ENTH AVENUE
		A A	A A A	AVEI
(This space reserved for official comments	s.) N	HIGH H	1 =	-
			\ <u>Z</u>	
	535-3	352	535-353	J STREET
	555	13	111 8	535-361
	{ }			9
	1	1 12	12	2 10
			3 7	3]

		SHE	

DELTIMINA	LITI OI	1 111111	II ID ILL		11			
CONTINUATION SHEET			Primary #					
					HRI # 21	138-024	3-0000	
					Trinomial			
0				,	•		tt Residence_ © Continuation	

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Built on a corner lot, only a few feet from the sidewalk, dense foundation vegetation offers the home some privacy from the street. The building has been restored to good condition.

*B10. Significance: (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

There are many such examples of the Colonial Revival style of architecture throughout San Diego. Furthermore, there are not enough characteristic Colonial Revival style features to make the residence a solid example of this particular style. The building has been determined to be neither historically nor architecturally significant. The building has not been associated with any significant events or individuals in San Diego, nor does it display any unique or innovative architectural characteristics.

PRIMARY RECORD

and boundaries):

Primary #	
HRI #	
Trinomial	
NRHP Status Code 3S	

Other Listings	Update of November	1988	Centre	City East	Survey	Documentation_
Other Listings	537.9-37-0071					- V

Review Code _____ Reviewer _ *Resource Name or ft: (Assigned by recorder) 1245 Island Avenue_____

Other Identifier: P1.

Location: n Not for Publication
Unrestricted * a. County San Diego and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma Date T____; R___; ____/4 of ____/4 of Sec ______ B.M. City San Diecro Zip 92101 1245 Island Avenue Address

UTM: (Give more than one for large or linear resources) Zone 11; mE/ mN d. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-156-09-00, Horton's Addition, Block 106, Lot L & N 16' Lot K Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting,

Originally constructed in 1886 at the corner of 11th Avenue and D Street (present-day Broadway) and relocated to this location in 1913, this two and one-half story residence was designed in the Queen Anne Spindlework style of Victorian architecture The building features a high hipped roof with

lower cross gables, a boxed cornice with a decorated frieze, two-story angled and square bay windows featuring pediments on top, cutaway corner windows featuring decorative corner brackets, and a wraparound entrance porch featuring turned posts, pediments, and spindlework.

(See DPR 523H, Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes and codes) HP2

*P4. Resources Present: | Building d Structure d Object d Site d District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)_

*P6. Date Constructed/Age and Sources:

I Historic

d Prehistoric d Both 1886_

1988 Centre City East Historic Site Inventory

*P7. Owner and Address: Morales Family Trust

404 S 58th Street San Diego, CA 92114

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley,
Office of Marie Burke Lia,
Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

Date Recorded: February 2001

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre

City East For Centre City Development Corporation

Attachments: PNONE a Location Map Sketch Map Continuation Sheet I Building, Structure, and Object Record □ Archaeological Record □ District Record D Linear Resource Record n Milling Station Record n Rock Art Record D Artifact Record n Photograph Record n Other (List): _

State of California — The Resources Agency Primary #
DEPARTMENT OF PARKS AND RECREATION HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD
Page 2 of 3 *NRHP Status Code 3S
*Resource Name or # (Assigned by recorder) 1245 Island Avenue, San Diego, CA 92101
B1. Historic Name: Sheldon Residence
B2. Common Name: Martinez Residence
B3. Original Use: Residential (Single-Family) B4. Present Use: Residential (Multi-Family)
*B5. Architectural Style: Oueen Anne Spindlework Victorian
*B6. Construction History: (Construction date, alternations, and date of alterations) Constructed in 1886; Relocated to current location (1913), upper portion of original tower removed (c.1940s). In 1993, the residence underwent extensive exterior and interior rehabilitation and beautification. (See 1993 NPS Part One, completed by the Office of Marie Burke Lia for more information)
*B7. Moved? No Yes Unknown Date: 1913 Original Location: Comer of 11th Avenue & D street (Broadway)
*B8. Related Features:
B9a. Architect: Nelson Comstock & Carl Trotsche b. Builder: Unknown
*B10. Significance: Theme Architecture Area San Diego Period of Significance 1886/1913_
Property Type Residential Applicable Criteria C_ (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)
(Discuss importance in terms of historical of architectural context as defined by theme, period, and geographic scope. Also address integrity.)
Originally constructed in 1886, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes, and more extensively documented in a 1993 Part One Historic Preservation Certification Application, also prepared by the Office of Marie Lia (for Centre City Development Corporation). Past owners of the 1245 Island Avenue property and building include: Dr. F.C. Sheldon (building:1886), Emma Sheldon family (1913), Carmen & John Prochaska (1938-1944), Cleto & Nora Martinez (1944-date unknown), and Juanita Morales (daughter of Nora & Cleto Martinez). Ownership of the residence, today, is maintained by the Morales Family Trust. San Diego City Directories reveal past residents of the 1245 Island Avenue residence include: Anthony Martinolich (1944/1945), owner Cleto R. Martinez (1950, 1955, 1960, 1965, 1970), Mrs. Mary T. Burgueon (1975, 1980), and Robert Martinez (1984).
(See DPR 523H, Continuation Sheet for more information)
B11. Additional Resource Attributes: (List attributes and codes)
*B12. References: (partial list)
Ching, Francis, D.K., A Visual Dictionary of Architecture, 1997. (See DPR 523H, Continuation Sheet for more information) B13. Remarks:
*B14. Evaluator: Wendy L. Tinsley,
Office of Marie Burke Lia (Sketch Map with north arrow required.)
Date of Evaluation: February 2001 : ISLAND
A (() () () () () () () () ()
(This space reserved for official comments.)

\$

CONTINUATION SHEET

Prima	ary #	
HRI	#/Trinomial	

I Continuation D Update

Page3 of3				
Resource Identifier: (Assigned by record	er) 1245 Isla	nd Avenue, Sar	n Diego, CA	92101
Historic Name: Sheldon Resid	ence			

P3a. Description (Continued):

Exterior building materials consist of contrasting wall textures including wooden plank's and patterned shingles, with composition shingles for the roof. Window types include double-hung sash, and many windows feature stained-glass portions. Overall, this residence is in excellent condition, and embodies the distinctive characteristics of the Queen Anne style.

*B10. Significance (Continued):

Historical research has determined that the 1245 Island Avenue residence is not historically significant, as the residence is not associated with any important events, or individuals, in terms of local, state, or national history. However, the 1245 Island Avenue residence is considered to be architecturally significant, as a building which embodies the distinctive characteristics of a type, period, or method of the Queen Anne Spindlework Victorian residential construction. In addition, it also represents the work of architects and master **craftsmen** Nelson Comstock & Carl Trotsche, who maintained a lucrative partnership in San Diego between 1886 and 1891. In 1993, the National Park Service made the determination that the 1245 Island Avenue residence "appears to meet the National Register Criteria for Evaluation and will likely be listed in the National Register of Historic Places if nominated by the State Historic Preservation Officer." (Part One, 1993)

*B12. References (Continued):


Lia and Brandes, Historic Site Inventory of Centre City East, v.1, 1988. Lia, Marie Burke & Dolores Mellon, Historic Preservation Certification Application, Part One-Evaluation of Significance, 1993.

McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office

DPR 523H (1/95)



C-88

Primary i		
HRI #		
Trinomial		
NIDLID OLIT	500	

PRI	IMARY RECORD	Trinomial	Code 5S2			
	Other Listings	Update of November	1988 Centre Cit	y East Survey	Documer	ntatio
	Review Code	eReviewer_		Date		
Page	of*Resource Name or if: Other Identifier:	(Assigned by recorder)	1619-1625	Island Ave	enue	
*P2.	Location: o Not for Publication • Unrestricted	* a. County	y San Died	70		
and ((P2b and P2c or P2d. Attach a Location Map as neo	cessarry/.)				
*b. (USGS 7.5' Quad Point Loma Date	;R_	;¼ of _	% of Sec	_;	B.M
c.	Address 1619-1625 Island Avenue	_ City San Diego	Zip	92101		
d.	UTM: (Give more than one for large	e or linear resou	rces) Zone_	;;	mE/	m
е.	Other Locational Data (e.g., parcel #, directions APN: 535-393-13-00, Block 21 Sher		etc., as appropr	iate):		
	Wasi of Lot 1 Wasi of Nai of	Lot 2 and E 25'	of Lot 12			

Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1887, this single-story, multiple-family residence was designed in a Victorian architectural style. It has a general rectangular shaped plan and features a hipped roof of moderate pitch with eave overhang, a boxed cornice, and two lower cross gables on the north, street facing elevation. A shallow porch with a shed style roof is present on the north elevation, and is supported by a series of wood posts. Exterior building materials consist of composition shingles for the roof, fish scale shingles for the gables, and horizontal shiplap siding with corner boards for the exterior walls. The windows appear to be double-hung, and are covered with metal bars on the street-facing elevation. Overall, this building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP3

*P4. Resources Present: I Building d Structure d Object d Site d District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

I Historic

d Prehistoric

d Both

c.1887

1938 Centre City East Historic Site Inventory

*P7. Owner and Address

Gods Extended Hand

P.O. Box 989

San Diego, CA 92112_

*P8. Recorded by (Name, affiliation, and Wendy L. Tinsley, address): Office of Marie Lia, Attorney at Law, 427 C Street. Ste. 416, San Diego, CA 92101

*P9.	Date	Recorded:	March	2001
	Date	Necolucu.	iviaicii	2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: a NONE a Location Map - Sketch Map a Continuation Sheet • Building, Structure, and Object Record n Archaeological Record a District Record Linear Resource Record Linear Resource Record Record a Rock Art Record n Artifact Record □ Photograph Record □ Other (List):

State	of Calif	ornia-	-The Re	esources Agenc	y	Primary # _	
DEP/	ARTMEN	T OF F	PARKS	AND RECREATION	ON	1 1 m 1 77	
BU	ILDIN	G, S	TRU	CTURE, AI	ND OBJEC	CT RECO	RD
	2						tus Code 5S2
*Res	ource N	ame o	r # (Ass	igned by record	ler) 1619-162	25 Island	Avenue, San Diego, CA 92101
B1.	Histori	ic Nam	e:_Jul	ia Stewart	House		
B3.	Origina	l Use	Resid	dential (Mult	i-Family) B4	Present Use	e: Residential (Multi-Family)
*B	5. Archi	itectura	Style:	Victorian_			
*B6.				: (Construction pproximately			falterations) ons and/or modifications noted.
*B7	.Moved	? N	o 🗆 🗅	′es □Unknow	n Date:		Original Location:
	Related			Unknown	b. Builder: <u>U</u>	Inknown_	
*B10), Signif	icance	: Theme	e Architecture	Area	San Diego	Period of Significance 1887

Originally constructed in approximately 1887, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation indicates past owners of the 1619-1625 Island Avenue property and building include: R.A. Thomas (pre-1886), Julia V. Stewart (1886-1903), George S. Wooley (1903-1904), C.E. and Ella Harney (1904-1922), and Joseph and Louise Giovanazzi (1922-1963). San Diego City Directories reveal that past residents of the 1619 Island Avenue unit include: no listing (1944/1945, C.H. Panning (1950), Howard Fanning (1955), William D. Brown (1960), Cesario Simental (1965), Mrs. Rae Koltner (1969/1970), vacant (1975), and no return (1980, 1984). Past residents of the 1625 Island Avenue unit include: Leopoldo J. Gomez (1944/1945, 1950, 1955), William D. McIntyre (1960), Henry John (1965), Javier Lugo (1969/1970), vacant (1975), and owner Isaac Niff (1980, 1984).

(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Applicable Criteria C

Historic research has determined that this building is not historically significant, as it is not a building which is associated with any important events, or individuals in terms of local, state, or national history. This building, however, has been determined to be architecturally significant, as a building which embodies the distinctive characteristics of a type, period, or method of Victorian multiple-family residence construction. As the identity of the architect could not be ascertained, the 1619-1625 Island Avenue building does not represent the work of a master architect or craftsman.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office

B13. Remarks:


*B14. Evaluator: _Wendy L. Tinsley

Office of Marie Burke Lia

Property Type Residential

Date of Evaluation: February 2001

(This space reserved for official comments.)




and boundaries):

Primary #	
HRI #	
Trinomial	

DEI THE IMPERT OF TARKS THE RESILE ATTOM	
PRIMARY RECORD	Trinomial
	NRHP Status Code_6Z
Other Listings Update	e of November 1988 Centre City East Survey Documentation
Review Code	ReviewerDate
Page 1 of 2 *Resource Name or #: (Ass P1. Other Identifier:	signed by recorder) 1635 Island Avenue
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as necess	
*b. USGS 7.5' Quad Point Loma Date	T; R;¼ of¼ of Sec; B.M.
	City San DiegoZip 92101
	r linear resources) Zone 11;mE/mN
e. Other Locational Data (e.g., parcel #, directions to r APN: 535-393-13-00, Sherman's Addit	
*P3a. Description (Describe resource and its major elements)	ents. Include design, materials, condition, alterations, size, setting,

Originally constructed in approximately 1888, this single-story, single-family residence was designed in a Folk Victorian architectural style. It has a general square shaped plan, and features a front gabled roof of moderate pitch with slight enclosed eave overhang. A full length porch located on the front, north elevation features bracketed wood posts for support perched upon a low wood wall which partially encloses the porch area. Exterior building materials consist of composition shingles for the roof, vertical and horizontal board-and-batten siding for the exterior walls, and the north elevation focal window appears to be double-hung with a fixed upper sash. The front entrance is off center, located on the northeast corner of the residence and concrete steps painted green ascend to the front entrance. Overall, this building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP2

Resources Present: | Building | Structure D Object d Site d District d Element of District d Other (Isolates, etc.) Description of Photo: (View, date, P5b. accession #)

*P6. Date Constructed/Age and Sources:

Historic

d Prehistoric D Both C.1888

1988 Centre City East Historic Site Inventory *P7. Owner and Address: God's Extended Hand

P.O. Box 989

San Diego, CA 92112

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley,
Office of Marie Burke Lia,
Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: February 2001

*P10. Type of Survey: (Describe)_

<u>City East For Centre City Development Corporation</u>

Attachments: UNONE Location Map Sketch Map Continuation Sheet Building, Structure, and Object Record □ Archaeological Record □ District Record □ Linear Resource Record □ Milling Station Record □ Rock Art Record ☐ Artifact Record ☐ Photograph Record ☐ Other (List):

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI#
BUILDING, STRUCTURE, AND OBJECT	CT RECORD
Page _ 2 _ of _ 2	*NRHP Status Code_6Z
*Resource Name or # (Assigned by recorder)1635	Island Avenue, San Diego, CA 92101
B1. Historic Name: Julia V. Stewart Rental_	
B2. Common Name:	
B3. Original Use: Residential	B4. Present Use: Residential
*B5. Architectural Style: Folk Victorian	
*B6. Construction History: (Construction date, alternation Constructed in approximately 1888; no material date in the construction of the construction of the construction date, alternation dat	ns, and date of alterations) ajor alterations and/or modifications noted.
*B7. Moved? No □Yes □Unknown Date:	Original Location:
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Ur</u>	
*B10. Significance: Theme. <u>Architecture</u> Area	
Property Type Residential	
(Discuss importance in terms of historical or architectural context as def	ined by theme, period, and geographic scope. Also address integrity.)
Originally constructed in approximately 18	388, this building was previously documented in November
	arie Lia and Dr. Ray Brandes. Previous documentation
	property and building include: R.A. Thomas (pre-1886),
	sey (1903-1904), C.E. & Ella Harney (1904-1922), and

1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation reveals past owners of the 1635 Island Avenue property and building include: R.A. Thomas (pre-1886), Julia V. Stewart (1886-1903), George S. Woolsey (1903-1904), C.E. & Ella Harney (1904-1922), and Joseph & Louise Giovanazzi (1922-date unknown). San Diego City Directories reveal past residents of 1635 Island Avenue include: Joseph Covina (1944/1945, 1950, 1955), Armando T. Salazar (1960), Doroteo Silva (1965), no listing (1969/1970), owner Francisco Reynoso (1975), and again, owner Doroteo Silva (1980, 1984).

Historical research has determined that the 1635 Island Avenue building is neither historically nor architecturally significant. The **building** is not associated with any important events or individuals in terms of local, state, or national history. Moreover, it does not embody the distinctive characteristics of a type, period, or method of Folk Victorian construction, and does not represent the work of a master architect or craftsman. The building is not eligible for listing on the local register.

B11. Additional Resource Attributes: (List attributes and codes)_

*B12. References: (partial list)


Ching, Francis, D.K., A Visual Dictionary of Architecture. Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley,
Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



PRIMARY RECORD

Filliary #	
HRI #_: 138-0249-0000	
Trinomial	

	NRHP Status Code	62		
Other Listings Updat	e of May 1989	Bayside	Survey Documentat	ior
Review Code	Reviewer		Date	

Page 1 of 3 *Resource Name or #: (Assigned by recorder) Workman Hotel

P1. Other Identifier:

*P2. Location: a Not for Publication • Unrestricted *

a. County San Diego

and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad __Point Loma ____Date ___T __; R __; __¼ or __¼ of Sec__; ___B.M. c. Address ____1335 J Street ____City San Diego ___Zip __92101

d. UTM: (Give more than one for large or linear resources) Zone 11; ___mE/ ___mN

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-372-15-00, Horton's Addition, Block 130, E ½ Lot L & E ½ Lot K

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1912, this three-story building identified as the Workman Hotel is a simple example of an early Twentieth Century Commercial Block lodging house with an Italian Renaissance influence. The building features a rectangular shaped plan, with a flat roof, a dentil band spanning around the building's perimeter, corbeling below the dentil band, a series of second floor masonry elements located between every second window, and belt coursing below the second floor window sills. The second floor masonry elements feature corbeling at the base, and are painted in a dark color that contrasts against the lighter, surrounding buff colored brick. Fenestration on the second and third floors consists of aligned, rectangular, double-hung sash windows in wood frames that are grouped in pairs. (See DPR 523H, Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes and codes) HP5; Hotel/Motel

*P4. Resources Present: | Building d Structure d Object d Site d District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

d Prehistoric

d Both

1989 Bayside Historic Site Inventory

*P7. Owner and Address:

Workman Hotel, LP c/o Danny Dabby 6310 Greenwich Drive #230 San Diego CA 92122

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Burke Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: February 2001 Updated April 2004

*P10. Type of Survey: (Describe)_____

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of</u> Bayside For Centre City Development Corporation

Attachments: □NONE D Location Map □ Sketch Map •Continuation Sheet ■ Building, Structure, and Object Record D Archaeological Record □ District Record □ Linear Resource Record □ Milling Station Record □ Rock Art Record □ Artifact Record □ Photograph Record □ Other (List):

State of California — The Resources Agency	
DEPARTMENT OF PARKS AND RECREATION	ĺ

Primary #		
HRI# 2138-0249-0000		

BUILDING, STRUCTURE, AND OBJECT RECORD

Property Type Hotel/Motel

DUI	LDIIA	G, 3	111	OCIC	JIL, AND	ODSEC	I KEC	UND						
Page _	2	_ of	3				*NRHP S	tatus	Code. 6	Z				
*Resc	ource N	ame o	r # (Assigned	by recorder)	Workm	an Hotel	1335	5 J Sti	reet, S	an Di	ego,	CA 9210	1
B1.	Historic	c Nam	ne:_ I	Iotel	Salem							141		
B2.	Commo	on Na	me:_	Workm	an Hotel									
B3.	Origina	l Use	: Hc	tel/M	otel_ B4.	Present Us	se: Hote	/Motel	- 5					
*B5.	Archite	ectura	l Sty	le: E	arly Twent	ieth-Cent	cury Con	nmercia	al Bloc	k Lodg	ing H	ouse_		
*B6.					onstruction da 12; Ground					unkno	wn.			
*B7.	Moved	l?	No	□Yes	□Unknown	Date:		Original	l Locatio	n:				

*B8. Related Features:

B9a. Architect: <u>Unknown</u>

b. Builder: H.C. Sparks_

*B 10. Significance: Theme N/A

Area San Diego

Period of Significance 1912_

Applicable Criteria N/A

(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Originally constructed in 1912, this building was previously documented in May 1989 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation reveals past owners of the 1335 J Street property and building include: E.W. & A.N. Loring (1912), and Floyd Hamaishi (1989). Past documentation states that E.W. and A.N. Loring signed the contract for the construction of this building with builder H.C. Sparks in 1912, and the building's construction costs totaled \$14,396.00. Loring, with family members, owned the Loring Company, a wholesale and retail stationers business. As indicated in previous documentation however, the Loring Family did not live, or operate a business out of this building. Thus this building's historic name, Loring Stationers, was inappropriately assigned. The building appears on a 1921 Sanborn Fire Insurance Map as "Hotel Salem," and appears to occupy 1335 and 1347 J Street, as well as 352, 358, and 366 14th Avenue. San Diego City Directories reveal that the 1335 J Street building was identified as the "Dewey Bachelor Hotel" (c. 1944/1945, 1950), the "Dewey Hotel For Men" (c.1955 through at least 1965), and finally the "Workman Hotel" (c.1969/1970 to the present). Past proprietors include: John Klose and Mrs. Rose P. Smith (1944/1945), Mrs. Rose P. Smith (1950, 1955), Oliver T. Guest (1965), and Thomas Frei (1969/1970).

(See DPR 523H, Continuation Sheet for more information)

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)


(See DPR 523H, Continuation Sheet for more information)

B13. Remarks:

*B14.Evaluator: Wendly. Tinsley,
Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



CONTINUATION SHEET

Primary #	
HRI #/Trinomial_2138-0249-0000	

■ Continuation

□ Update

Page __3__ of __3__

Resource Identifier: (Assigned by recorder) Workman Hotel. 1335 J Street, San Diego. CA 92101

Historic Name: Hotel Salem

*P3a. Description (Continued):

Each window features an arched brick molding that is flush with the buildings exterior walls. According to past documentation, the original street front features of the building, including bays, shop fronts, and hotel entrance, have undergone alterations. (Lia/Brandes: 1989) These alterations include replacing the original glass sections with horizontal wood paneling and creating new window spaces in the paneling. Overall, the building's exterior appears to be in good condition, however, contrary to previous documentation, the building is both historically and architecturally insignificant.

*B10. Significance (Continued):

Although the 1335 J Street building is listed as a "38" on the California State Office of Historic Preservation Historic Property Data File for San Diego County, Historical research has determined that the 1335 J Street building is neither historically nor architecturally significant. The 1335 J Street building is not associated with any important events or individuals in terms of local, state, or national history. Moreover, it does not embody the distinctive characteristics of a type, period, or method of Early Twentieth Century Commercial Block construction, and does not represent the work of a master architect or craftsman.

*B12. References (Continued):


Growth, Paul, Living Downtown, The **History** of Residential Hotels in the United **States**, 1994.

Lia and Brandes, Historic Site Inventory of Bayside, 1989.

Longstreth, Richard, The Buildings of Main Street, A Guide To American Commercial Architecture, 1997.

San Diego City Directories

San Diego County Recorders Office



DPR 523H (1/95)

9

PRIMARY RECORD

Primary #	
HRI#_2138-0251-0000	
Trinomial	

					NRHP Status Code 5S2				
					Other Listings Upd	ate of May 198	9 Baysid	le Survey Docu	mentation
					Review Code	Reviewer		Date	
Page	1	of	3	*Resourc	e Name or #: (Assigne	ed by recorder)	1479 J S	Street	
P1.	Oth	er I	dentif	ier:					
*P2.	Locati	on: 🗆	Not for F	ublication	Unrestricted *	a. County	San Di	ego	
and (F	2b and	P2c c	r P2d. <i>A</i>	ttach a Loca	tion Map as necessary	/ .)			
*h	ISGS 7	5' Our	ad E	Coint Loma	Date	т .р .	% of	1/4 of Sec	R M

C. 1479 J Street City San Diego d. UTM: (Give more than one for large or linear resources) Zone 11; __ mE/ _

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-396-04-00, Sherman Addition, Block 36, N 65' Lot 3 & N 65' Lot 4 EXC W 30' *P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1888, this two-story, Italianate building stands on the southwest corner lot of the intersection of 15th Avenue and J Street. It has a general rectangular shaped plan, and features shiplap siding, a flat roof in the Townhouse style with a bracketed cornice, double-hung windows with wooden ornamental surrounds and decorated hoods, and a second floor square bay that is angled across the cutaway corner. The cornice brackets resemble turned spindles. On the ground floor, vertical boards replace the original features in the cutaway corner, and most likely a majority of the original first floor exterior building materials have been removed and/or replaced, including the original doors and windows. The asymmetrical facade features wooden doors at both ends of the building. (See DPR 523H, Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes and codes) HP5; Hotel/Motel____

*P4. Resources Present: Building Structure D Object n Site o District n Element of District n Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

D Prehistoric

□ Both

1888

1989 Bayside Historic Site Inventory

*P7. Owner and Address:

Kenneth Cummins Revocable Trust 905 Dohaney Court Roseville CA 95661

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Burke Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101_

*P9.	Date Recorded:	February 2001	Updated April 2004					
*P10.	Type of Survey:	(Describe)						
P11	Report Citation	(Cite survey report and	other sources or	enter "none")	Historic	Site	Toventory	0

Bavside For Centre City Development Corporation_

Attachments: DNONE n Location Map n Sketch Map Continuation Sheet Building, Structure, and Object Record n Archaeological Record n District Record n Linear Resource Record o Milling Station Record n Rock Art Record n Artifact Record n Photograph Record n Other (List):__

The state of the s	Primary #
BUILDING, STRUCTURE, AND OBJECT	T RECORD
**Resource Name or # (Assigned by recorder) 1479 J B1. Historic Name: Joseph Ireland Building	Street, San Diego, CA 92101
B2. Common Name: J Street Hotel B3. Original Use: Residential *B5. Architectural Style: Italianate Townhouse	B4. Present Use: Hotel/Motel
*B6. Construction History: (Construction date, alternation Constructed in 1888; most likely has undergone ex	
*B7. Moved? I No □Yes □Unknown Date:	Original Location:
	San Diego Period of Significance 1888_ Applicable Criteria C
supervision of the Office of Marie Lia and Drowners of the 1479 J Street property and building Vernon & Florence Rood (1907-c.1936), George & I Company; Mark Madrugo & Jennie Maloy (1989). Street building include: Joseph, Elizabe Store (1913), R.O. Douglas Furnished Rooms (1918) and the J Street Hotel (c. 1955) Hotel include: Mrs. Carrie Bryant (1955), and M	ding was previously documented in May 1989 under the Ray Brandes. Previous documentation reveals passed included: Joseph Si Elizabeth Ireland (c.1888-1907) cours Corodemas (1936-1941), and the Growth Investment of an Diego City Directories reveal past occupants of the eth, and Annie Ireland (1888-1907), R.H. Root Grocery 1930), Eugene Clayton; Jess Porter (1944/1945), J.T. thru at least 1980). Past managers of the J Street are. Eva E. Taylor (c. 1965 to at least 1975). During building has been used as a single-family residence loor, and lastly as a Hotel/SRO.
(See DPR 523H, Continuation Sheet for more	e information)
B11. Additional Resource Attributes: (List attributes and codes *B12. References: (partial list))
Ching, Francis, D.K., A Visual Dictionary Lia and Brandes, Historic Site Inventory McAlester, Virginia & Lee, A Field Guide San Diego City Directories San Diego County Recorders Office	of Bayside, 1989.
B13. Remarks:	(Sketch Map with north arrow required.) J Street
*B14. Evaluator: Wendy L. Tinsley, Office of Marie Burke Lia	
Date of Evaluation: February 2001	eone (a) (b) (c) (c) (c) (c) (c) (c) (c) (c) (c) (c

396 36

396 36

396 36

(This space reserved for official comments.)

Primary #		
HRI #/Trinomial_2	138-0251-0000	

CONTINUATION SHEET

I Continuation

Update

Page3 of3		
Resource Identifier: (Assigned by recorder)	1479 J Street, San Diego, CA 92101	-
Historic Name: Joseph Ireland	Building	


P3a. Description (Continued):

At the time of **initial** survey activities in c. November 2000, renovations were being made to the building, and February 2001 **field** investigation activities revealed that the building was still under renovation. Overall, the building appears to be in fair **condition**.

*B10. Significance (Continued):

Historical research has **determined** that the 1479 J Street building is not historically significant, as the building is not associated with any important events or individuals in terms of local, state, or national history. However, with the remaining Italianate details on the second floor exterior walls, the building embodies the distinctive characteristics of a type, period, and method of Italianate Townhouse style **construction**. As the identity of the architect could not be ascertained, the 1479 J Street building does not represent the work of a master architect or craftsman. The 1479 J Street building is listed as a 4s on the California State Office of Historic Preservation Historic Property Data File for San Diego County as a property which may be eligible for inclusion on the National Register upon certain conditions being met.

DPR 523H (1/95)



PRIMARYRECORD

Primar	y #	 	
HRI#			

Trinomial_	 	 	 	

NRHP Status Code ____6Z Other Listings

Review Code _____ Pate _____ Date _____

*Resource Name or #: (Assigned by recorder) ___1619_J_Street Page 1__ of _2__

P1. Other Identifier: R.B. Meyers House Location:

Not for Publication I Unrestricted * *P2.

a. County San Diego and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma Date T ; R ; 4 of % of Sec ; B.M. Address 1619 J Street City San Diego Zip 92101 C.

d. UTM: (Give more than one for large or linear resources) Zone ; ____ mE/ ___mN

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): e. Block 34, Lot 1, Map: 856, APN: 535-394-01

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, andboundaries):

This one-story, Craftsman single-family residence is believed to have been constructed in 1906. Rectangular in shape, the building features a hipped roof with eave overhang and composition roofing. Along the northwest corner of the building, there is a partial porch formed by the roof overhang, supported by square wood columns. The exterior is composed of horizontal clapboard siding. Thicker clapboard exists along the main (north) elevation. Fenestration consists of double-hung and casement, most of which have wrought iron security grilles. Overall, the building appears to be in good condition.

P3b. Resource Attributes: (List attributes and codes) __HP2



- *P4. Resources Present: I Building ☐ Structure a Object ☐ Site ☐ District P Element of District D Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)
- *P6. Date Constructed/Age and Sources:
- Historic

Prehistoric D Both 1906

Sanborn Fire Insurance Maps Sewer Department Records

*P7. Owner and Address:

Hector M. Zamaro 1057 2nd Avenue

Ichula Vista, CA 91911__

P8. Recorded by (Name, affiliation, and address): Office of Marie Burke Lia, 427 C Street, Suite 416,

San Diego, California 92101 *P9. Date Recorded: May 2004

*P10. Type of Survey: (Describe)

Intensive

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Resources Inventory Update Of The East Village Area For Centre City Development Corporation

Attachments:

NONE
Location Map
Sketch Map
Continuation Sheet
Building, Structure, and Object Record DArchaeological Record District Record Linear Resource Record Milling Station Record Rock Art Record

□Artifact Record □Photograph Record n Other (List):__

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION		
		NPD
BUILDING, STRUCTURE, AND OF Page 2 of 2		atus Code <u>6Z</u>
B1. Historic Name: R.B. Meyers House	9	
B2 Common Name:		
B3. Original Use: Residential B4. Presi	ent use: Resider	ntiai
"B5. Architectural Style: Craftsman		
*B6. Construction History: (Construction date, alte	rnations, and date	of alterations)
Building believed constructed in	ı 1906.	
*B7. Moved? ■No □Yes □Unknown Dat *B8. Related Features:	:e:	Original Location:
None		
B9a. Architect: <u>Unknown</u> b. Builde		
The state of the s		East Village/Centre City
		Residential Applicable Criteria N/A
(Discuss importance in terms of histo geographic scope. Also address integri		ural context as defined by theme, period, and
Maps does not depict the presence of the structure during connected to the City Sewer System in November, 1906 for time. Inspection of 1921 and 1956 Sanborn Maps reveals the	these years. However r owner R.B. Meyers. he presence of the build he years included Alva	d in 1906. Inspection of 1888 and 1906 Sanborn Fire Insurance r, a Sewer Department Record indicates that the property was As such, it is believed that the residence was constructed at this ding as a one-story, dwelling with partial porch. San Diego City arez Gomez (1926), Alberto Labitoria (1930-1935), Reginald T.
associated with any important events or individuals in terr	ns of local, state, or na	historically or architecturally significant. The building is not ational history. The building does not embody the distinctive ding does not represent the work of a master architect, builder,
Data Additional December Attailed as (Ust attailed	de de en de en de e	
B11. Additional Resource Attributes: (List attr	ibutes and codes)
*B12.References: (partial list) City of San Diego, Building Department Permit	Records	
City of San Diego, Water & Sewer Records.		
McAlester, Virginia & Lee, A Field Guide To 2000.	American Houses,	(Sketch Map with north arrow required.)
Sanbom Fire Insurance Maps, 1888, 1906, 1921, San Diego City and County Directories.	1940, 1956.	J ST
		1"=100"
B13. Remarks:	a.	10-12
		® 1 337
*B14. Evaluator: Office of Marie Burl	ke Lia	<u> </u>
Date of Evaluation: May 2004	C LIA	3 10 0.69 AC
		3 10 BLK 34
(This space reserved for official comm	ents.)	34 9
		-
		5-1a. X
		3. 46 7 3 E

K ST

S D

P


е

State of California — The Resources Agency	Primary # HRI #				
DEPARTMENT OF PARKS AND RECREATION					
PRIMARY RECORD	Trinomial				
Other Listings					
Review Code	Reviewer Dat	ce			
Page 1 of 2 *Resource Name or #: (Ass					
P1. Other Identifier:John Ouantrell House					
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County San Diego				
and (P2b and P2c or P2d. Attach a Location Map as necess		3			
*b. USGS 7.5' Quad Point LomaDate	T; R;% of% of Se	<u>с;</u> В.М.			
c. Address 1615 K Street City San Dieg	io Zip92101				
d. UTM: (Give more than one for large or	· linear resources) Zone;	mE/mN			
e. Other Locational Data (e.g., parcel #, directions to Block 39, Lot 1, Map: 856, APN: 535-					

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This one-story, Craftsman single-family residence was constructed in 1921. Rectangular in shape, the building features a dual, medium pitched, side-gabled roof with modest eave overhang and composition shingles. At the rear of the building (south elevation), there is a shed roof section. The exterior consists of horizontal clapboard siding. Along the main (north) elevation, there is a partial porch area. The porch features a low-pitched, front-gabled roof with pediment, supported by four spindle columns. Windows are double-hung with metal security grilles. Overall, the building appears to be in poor condition.

P3b. Resource Attributes: (List attributes and codes)



*P4.	Res	ources	Pre	ese	nt:		Buil	ding
n Sti	ructure	n Obj	ect	а	Site		Distri	ct r
Eleme	ent of D	istrict		Oth	er (I	solat	es, e	etc.)
P5b.	Desci	ription	of	Pho	oto:	(Vie	w, d	ate
acces	sion #)							
*P6.	Date C	onstru	cte	J/Aç	ge ar	nd S	ource	es:

I Historic

n Prehistoric □ Both 1921

Sanborn Fire Insurance Maps Sewer Department Records

*P7. Owner and Address:

Joseph, Dominic, Laura Deluca Sarah D. Yielding

4615 East Talmadge Drive San Diego, CA 92116

P8. Recorded by (Name, affiliation, and address): Office of Marie Burke Lia, 427 C Street, Suite 416, San Diego, California 92101

*P9. Date Recorded: May 2004_

*P10. Type of Survey: (Describe)

Intensive

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Resources Inventory Update Of The East Village Area For Centre City Development Corporation Area_ Attachments: □NONE □Location Map □Sketch Map □Continuation Sheet Building, Structure, and Object Record □Archaeological Record □District Record □Linear Resource Record □Milling Station Record □Rock Art Record □Artifact Record □Photograph Record □ other (List):

State of California - The Resources Agency Primary # DEPARTMENT OF PARKS AND RECREATION HRI#	
BUILDING, STRUCTURE, AND OBJECT RECORD Page 2 of 2 *NRHP Status Code 6Z	
*Resource Name or # (Assigned by recorder) 1615 K Street	
B3. Original Use: Residential B4. Present Use: Residential	
Building constructed in 1921.	
B7. Moved? No DYes Unknown Date: Original Location: *B8. Related Features:	
None	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Rohde Brothers</u> *B10. Significance: Theme <u>N/A</u> Area <u>East Village/ Centre City</u> Period of Significance _ N/A Property Type Residential Applicable Criteria (Discuss importance in terms of historical or architectural context as defined by theme, period geographic scope. Also address integrity.)	N/A
This property is today identified as 1603-1615 K Street, but includes the present one-story, single-family residence, identified Street. Originally, it is believed that the building was identified as 1603 K Street and was later changed to its present address. The present was constructed in 1921. Inspection of 1888 and 1906 Sanborn Fire Insurance Maps do not reveal the presence of this structure during the However, a City of San Diego Sewer Connection Order indicates that sewer service was provided to 1603 K Street in March, 1921. The listed on the record were the Rohde Brothers. In addition, the structure is depicted on the 1921 Sanborn Map as a one-story dwelling of front porch. Review of 1940 and 1956 Sanborn Maps do not show a change in the building's configuration over these years. San Directories indicate that the first identifiable occupant of the building was John Quantrell in 1926. Subsequent occupants over the included Benjamin Packard (1930-1945), Alpheus Packard (1935), N.K. Sugioka (1950), and Henry W. Johnson (1960).	nt building these years. c contractor with partial Diego City
Historical research has determined that the 1615 K Street building is not historically or architecturally significant. The building associated with any important events or individuals in terms of local, state, or national history. The building does not embody the characteristics of a type, period, or method of construction. Moreover, the building does not represent the work of a master architectraftsman, or important, creative individual.	distinctive
B11. Additional Resource Attributes: (List attributes and codes)	
City of San Diego, Building Department Permit Records. City of San Diego, Water & Sewer Records. McAlester, Virginia & Lee, A Field Guide To American Houses, 2000. Sanborn Fire Insurance Maps, 1888, 1906, 1921, 1940, 1956. San Diego City and County Directories. (Sketch Map with north ow required for K STREE of K STRE	·
B13. Remarks:	
*B14. Evaluator: Office of Marie Burke Lia Date of Evaluation: May 2004 (This space reserved for official comments.)	į.
(This space reserved for official comments.) C	

Ţ

CLSD.

State of California — The Resources Agency

Primary #		
HRI #		
Trinomial_	2138-0270-0000	

DEPART	TMENT OF PARKS AND RECREATION	HRI #			
PRIMARY RECORD Trinomial 2138-0270-0000					
		NRHP Status Co	ode_ 7		
	Other Listings Update O	f November 1988	Centre City East Survey Documentation		
	Review Code	Reviewer	Date		
_	1 of 3 *Resource Name or #: (Assign	ned by recorder)	726-728 Market Street		
	Other Identifier: Location: Not for Publication Unrestricted *	a. County	San Diego		
	b and P2c or P2d. Attach a Location Map as necessary GS 7.5' Quad <u>Point Loma</u> Date		;		
Э.	Address 726-732 Market Street	City	San Diego Zip92101		
i.	UTM: (Give more than one for large or	linear resour	rces) Zone 11; mE/mN		
e.	Other Locational Data (e.g., parcel #, directions to rese APN: 535-105-07-00, Horton's Addition	ource, elevation, e , Block 85, W	etc., as appropriate): 1 1/2 of Lots G & H		
*P3a.	Description (Describe resource and its major elements and boundaries):	s. Include design,	materials, condition, alterations, size, setting,		

Originally constructed in approximately 1898, this building was designed in a Two-Part Commercial Block style with an Italianate architectural influence. It has a flat roof and features a bracketed boxed cornice, two large projecting rectangular bays spanning across the length of the second and third floors, and first floor shop front spaces (identified as 726 and 732 Market Street) which are separated by a central arched entry leading to the upper residential floors of the building. The first floor shop front windows are large fixed single panes of glass with a multi-pane sash pattern and clerestory windows above. Exterior building materials consist of stucco and red brick for the exterior walls, and most likely composition rolls for the roof. Overall, this building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP3:HP6 *P4. Structure Dobject Site District Element of District n Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)_ *P6. Date Constructed/Age and Sources:

Historic Prehistoric □ Both

c.1898 1988 Centre City East Historic Site Inventory *P7. Owner and Address: 8 Star Inc., C/o Susanne Starcevic 1415 28th Street

San Diego, CA 92102

*P8. Recorded by (Name, affiliation, and Wendy L. address): Tinsley, Scott Moomjian, Marie Burke Lia, Attorney at Law. 427 C Street, San Diego, CA 92101

*P9. Date Recorded: October 2001 / Owner Information and Photo Updated June 2003

*P10. Type of Survey: (Describe)

City East For Centre City Development Corporation

Attachments: DNONE a Location Map n Sketch Map Continuation Sheet Building, Structure, and Object Record a Archaeological Record n District Record Linear Resource Record D Milling Station Record n Rock Art Record ☐ Artifact Record in Photograph Record in Other (List):

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
BUILDING, STRUCTURE, AND (

Primary	#		
HRI# _	2138-0270-0000		

DUI	LDING, STRUCTURE, AND ODSECT RECORD
Page	2 of 3 *NRHP Status Code 5S2
•Resc	ource Name or # (Assigned by recorder)
B1.	Historic Name: Orford Hotel
B2.	Common Name: Hotel Arthur
B3.	Original Use: Mixed-Use Commercial/Residential B4. Present Use: Mixed-Use Commercial/Residential
*B5.	Architectural Style: Two-Part Commercial Block style with an Italianate influence
Orig	Construction History: (Construction date, alternations, and date of alterations) inally constructed in approximately 1898; Exterior stucco work (date unknown), facade bilitation efforts (between 1988-2001).
*B7.	Moved? No
	Related Features: Architect: H.A. Perry and Moses Frick b. Builder: Unknown

*B 10. Significance: Theme Architecture Area San Diego Period of Significance 1898_

> Property Type Commercial Applicable Criteria C_

(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity,)

Originally constructed in approximately 1898, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past owners of the 726-732 Market Street property and building include Mary Marston Kew and Lilla Marston Burnham and members of the Kew-Burnham families from c.1898 through 1925. See DPR 523H, Continuation Sheet for an incomplete listing of occupants of the 726-732 Market Street building.

Historical research has determined that the 726-732 Market Street building does not appear to be historically significant, as it has not been associated with any important events, or individuals in terms of local, state, or national history. The 726-732 Market Street building was previously (Lia/Brandes:1988) identified as having been designed by architects/contractors H.A. Perry and Moses Frick, who are not considered to be masters, or important, creative individuals. While the property has been classified as "Two Part Commercial Block," with an Italiante influence, further study and/or research is necessary to determine whether the structure embodies the distinctive characteristics of this type, period or method of construction. Such a determination will dictate whether the resource is eligible for listing on the local register.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City Bast, 1988.

Longstreth, Richard, The Buildings of Main Street; A Guide To American Commercial Architecture, 1987. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office

University of San Diego, San Diego Architects; 1368-1939, 1991, Department of History, Graduate Division.

B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley, Scott A. Moomjian Office of Marie Burke Lia Date of Evaluation: October 2001

(This space reserved for official comments.)

(Sketch Map with north arrow required.) G 0 0 D, 9 (1),c 2 @ R (6) E (B) MARKET STREET

CONTINUATION SHEET

Primary #	
HRI ff/Trinomial 2138-0270-0000	

Continuation a Update

Page3 of	3								
Resource Identifier:	(Assigned	by recorder)	728	Market	Street,	San	Diego,	CA	92101
Historic Name:	Orford	Hotel							

*B10. Significance (Continued):

San Diego City Directories reveal past occupants of the 726-732 Market Street building include:


726 Market Street: San Diego Amusement Company (1944/1945), L.B. Becker; Becker Book Bindery (1950, 1955, 1960), Hosier Shoe Findings (1965, 1970, 1975), and vacant (1980, 1984).

728 Market Street: The Arthur Hotel (1944/1945, 1950, 1955, 1960, 1965, 1970, 1975, 1980, 1984), with proprietor I.L. Wright (1944/1945), and with proprietor B.J. Simmons (1950), with proprietor Mrs. Mollie Black (1955).

732 Market Street: E.F. Nolan Book Binder (1944/1945), no listing (1950, 1955), Becker Book Bindery (1960), vacant (1965, 1970, 1975, 1980), and **GTM** Salvage Research & Marketing (1984).

DPR 523H (1/95)

DYGNA TOK!



C-108

PRIMARY RECORD

Primary #	
HRI #	
Trinomial	

NRHP Status Code_ 7										
	Other Listings	_Update	of N	ovember	1988	Centre	City	East	Survey	Documentation
Review Code				Review				Date		
	N.T.		1.1		1 \	740 7	4.4.3	f 1		

*P2. Location: a Not for Publication ■ Unrestricted * a. County San Diego_____ and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma Date T ___; R ___; ___ 4 of ___ 4 of Sec___; ____ B.M.

c. Address 740-744 Market Street City San Diego Zip 92101
d. UTM: (Give more than one for large or linear resources) Zone 11; mE/ mN

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-105-08-00, Horton's Addition, Block 85, E ½ of Lots G & H

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1896, this building was designed in a Two-Part Commercial Block style with an Italianate architectural influence. It has a general rectangular shaped plan and features a flat roof, rectangular double-and-single-hung windows aligned in a series of angled bays on the second floor, and first floor store fronts featuring single, large fixed panes for display and smaller vertical, rectangular shaped single-hung windows above. The first floor portion contains two shop fronts identified as 740 and 744 Market Street, with the second floor containing the residential portion identified as 742 Market Street. Rear entrances to the spaces are located on the east elevation along with additional store front windows. Exterior building materials consist of stucco over the original red brick, and most likely composition rolls for the roof. Overall, this building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP3; HP6

*P4. Resources Present: I Building
Structure
Object
Site
District
Element of District
Other (Isolates, etc.)

P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

I Historic

D Prehistoric ☐ Both 1896

1983 Centre City East Historic Site Inventory

*P7. Owner and Address: 3D Capital. LLC

5371 Wilshire Boulevard, # 21.0 Los Angeles, CA 90036

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley. Scott A. Moomiian, Office of Marie Burke Lia, Attorney at Law, 427 C Street. Ste. 416. San Diego, CA 92101

*P9. Date Recorded: October 2001 / Photo Updated June 2003

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre City East For Centre City Development Corporation</u>

Attachments: □NONE D Location Map □ Sketch Map ■Continuation Sheet I Building, Structure, and Object Record □ Archaeological Record □ District Record □ Linear Resource Record □ Milling Station Record □ Rock Art Record □ Artifact Record □ Photograph Record □ Other (List):

	NDD.
BUILDING, STRUCTURE, AND OBJECT RECO	atus Code 7
*Resource Name or # (Assigned by recorder)	
B1. Historic Name: Albert Morse Block Building	
B2. Common Name:	
B3. Original Use: Mixed-Use Commercial/Residential B4. *B5. Architectural Style: Two-Part Commercial Block style	
*B6. Construction History: (Construction date, alternations, and date Originally constructed in 1896; Original brick exterior lother modifications and/or alterations noted.	
*B7. Moved? No	Location:
*B8. Related Features:	Location.
B9a. Architect: Anton Reif and John B. Stannard b. Builder: Sch	
*B10. Significance: Theme Architecture Area San Diego Property Type Commercial Applicable C	
(Discuss importance in terms of historical or architectural context as defined by theme, pe	
Originally constructed in 1896, this building was a the supervision of the Office of Marie Lia and Dr. Ray Street property and building include the Grand Army of the Albert Morse (1892-date unknown), various members of the unknown through 1919), J.P. and Laura McClurken (1919-19523H, Continuation Sheet for an incomplete listing of	Brandes. Past owners of the 740-744 Market e Republic Veteran's Association (pre-1892) ne Morse Family including Pheobe Morse (date
be historically significant, as it has not been associated in terms of local, state, or national history. The 740 architects John B. Stannard and Anton Reif, who are consisted building does not qualify for the local registers. When Part Commercial Block with an Italianate influence, for determine whether the structure embodies the distinctive method of construction. Such a determination will dictate on the local register.	0-744 Market Street building was designed by dered to be important, creative individuals ile the property has been classified as "Tearther study and/or research is necessary to be characteristics of this type, period or
P11 Additional Passuras Attributes: (List attributes and cades)	
*B11. Additional Resource Attributes: (List attributes and codes) *B12. References: (partial list) Lia and Brandes, Historic Site Inventory of Centre City Longstreth, Richard, The Buildinga of Main Street; A Guide McAlester, Virginia & Lee, A Field Guide To American Hot San Diego City Directories San Diego County Recorders Office University of San Diego, San Diego Architects; 1868-	East, 1988. To American Commercial Architecture, 1987
1939, 1991, Department of History, Graduate	(Sketch Map with north arrow required.)
Division.	G
B13. Remarks:	CD * <
*P14 Englisher Wands I Minglas Coatt A Wandiday	CD O
*B14. Evaluator: Wendy L. Tinsley, Scott A. Moomjian, Office of Marie Burke Lia	CD .
Date of Evaluation: October 2001	, © '85' [©]
(This space reserved for official comments.)	F (5) a (2) 6
(This space reserved for official confinence.)	195
	CDt 0 a
	700 59 8

MARKET STREET

CONTINUATION SHEET

Primary #	
HRI #/Trinomial	
37-7-20-	

Continuation

Update

Page __3 of __3

Resource Identifier: (Assigned by recorder) 740-744 Market Street, San Diego, CA 92101_____ Historic Name: Albert Morse Block Building

*B10. Significance (Continued):

San $Diego\ City\ Directories$ reveal past occupants of the 740-744 Market Street building include:

740 Market Street: Roche Brothers Sheet Metal Works (1944/1945), H.C. Kuhle Barber Supply (1950), United Barber & Beauty Supply (1955, 1960, 1965, 1969/1970, 1975), and United Barber & Beauty Supply, Inc. (1980, 1984).

742 Market Street: the Baltimore Apartments with proprietor T.M. Libscomb (1944/1945), the Baltimore Apartments listed as containing approximately fifteen units (1950, 1955, 1960, 1965), and the Baltimore Apartments listed as containing approximately thirteen units (1969/1970, 1975, 1980, 1984).

744 Market Street: grocer Benjamin Halprin (1944/1945, 1950), Benjamin Halper delicatessen (1955), Bejamin O. Halpern delicatessen (1960, 1965), Ben's Delicatessen (1969/1970, 1975), Curt's Bar-B-Que Restaurant (1980), and vacant (1984).

DPR 523H (1/95)

PRIMARY RECORD

Primary #	
HRI #	
Trinomial	
NRHP Status Code 6Z	

				Other Listings	Update of November 1988	8 Centre City East	Survey Documentation
				Review Code_	Reviewer		Date
Page	1	of	3	*Resource Name or #: (Assigned by	v recorder) 906-922 M a	arket Street / 6	31-639 9 th Avenue

Page 1 of 3 *Resource Name or #: (Assigned by recorder) 906-922 Market Street / 631-639 9th Avenue P1. Other Identifier:

*P2. Location: a Not for Publication • Unrestricted *

and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma_____ Date____ T___; R___; ___% of ____¼ of Sec___; ____B.M.

c. Address 906-922 Market Street / 631-639 9th Avenue City San Diego Zip 92101

d. UTM: (Give more than one for large or linear resources) Zone___;___mE/__mN

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-136-02-00, Block 83 Horton's Addition, Lots D, E, and F.

***P3a.** Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This One-Part Commercial Block styled building with Art Deco detailing was constructed in 1931. It features a flat roof with a parapet, enframed **window** wall portions divided by pilasters, (with each pilaster featuring engraved vertical lines) and eight bay sections. Three of the bays are storefronts, while several others are boarded or in-filled. The southeastern most bays are composed of block glass, which may have been added during the 1950s or 1960s. The building is concrete with a **stucco-on-lath** exterior. Overall, the building appears to be in fair condition.



P3b. Resource Attributes: (List attributes and codes) HP6_____

*P4. Resources Present: I Building d
Structure d Object d Site d District d
Element of District d Other (Isolates, etc.)
P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

I Historic

d Prehistoric d Both

1983 Centre City East Historic Site Inventory

*P7. Owner and Address

Mitchell Investments

1827 Main Street____

San Diego, CA 92113

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev. Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416. San Diego, CA 92101

*P9. Date Recorded: October 2001 / Photo Updated June 2003

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre City East For Centre City Development Corporation</u>

Attachments: D NONE

Location Map

Sketch Map D Continuation Sheet

Building, Structure, and Object Record a Archaeological Record

District Record a Linear Resource Record D Milling Station Record

Rock Art Record n Artifact Record n Photograph Record a Other (List):

	T X
State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	
BUILDING, STRUCTURE, AND OBJE	CT RECORD
Page 2 of 3	*NRHP Status Code 7
*Resource Name or # (Assigned by recorder)922	Market Street, San Diego, CA 92101
B1. Historic Name: The Federal Motor Truck	Company Building
B2. Common Name: The Jesus Christ Netwo	ork Building
B3. Original Use: Commercial Automotive B4.	Present Use: Commercial_
*B5. Architectural Style: One-Part Commercial	Block style with Art Deco Detailing
*B6. Construction History: (Construction date, alterna Originally constructed in 1896; Original briother modifications and/or alterations noted	ck exterior has been stuccoed over (date unknown), No
*B7. Moved? No □Yes □Unknown Date:	Original Location:
*B8. Related Features: B9a. Architect: Frank P. Allen b. Builder: Walter Trep *B10. Significance: Theme Architecture Area Property Type Commercial	te_ a San Diego Period of Significance 1931_
the supervision of the Office of Marie Lia are the property on which the building is today lo	ailding was previously documented in November 1988 under ad Dr. Ray Brandes. Previous research has determined that ocated was purchased by contractor Walter Trepte in 1927

the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous research has determined that the property on which the building is today located was purchased by contractor Walter Trepte in 1927. In 1931 Trepte employed architect Frank P. Allen, Jr. to design the 906-922 Market Street building. The building was soon occupied thereafter by the Federal Motor Truck Company. Allen achieved recognition as the architect of numerous works in San Diego, Seattle, and Oregon. He served as the Director of Works for the Panama-California Exposition. During the First World War, he headed the Allen Shipbuilding. Corporation. His more notable San Diego designs include the Cabrillo Bridge and the Botanical Building and Administrative Buildings in Balboa Park, as well as the Park Manor Hotel. During the early 1940s, he was a chief draftsman in the engineering department of the California Shipbuilding Company. In 1933, Allen was awarded an A.I.A. award for his work on the Federal Motor Truck Company Building. The building was cited as a "good example of brilliant color on strong structural design in concrete." From 1937-1938, the Gill Electric Company operated a business in the building, followed by the San Diego Glass & Paint Company, which occupied the building from 1938-1988.

See DPR 523H, Continuation Sheet for more information.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

Longstreth, Richard, The Buildings of Main Street; A Guide To American Commercial Architecture, 1987. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office


University of San Diego, San Diego Architects; 1868-1939, 1991, Department of History, Graduate Division.


B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley, Scott A. Moomjian,
Office of Marie Burke Lia

Date of Evaluation: October 2001

(This space reserved for official comments.)





ath + market

PRIMARY RECORD

e.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary #		
PRIMARY RECORD	Trinomial		
Other Listings	*		
		Date	
Page1 of _3 *Resource Name or #: (Assignment) P1. Other Identifier:First National Bank	gned by recorder) 1101 M	arket Street	
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County San l	Diego	
and (P2b and P2c or P2d. Attach a Location Map as necess*b. USGS 7.5' QuadPoint Loma Date		of% of Sec; B.M.	
c. Address <u>1101 Market Street</u> City	San Diego	Zip <u>92101</u>	
d. UTM: (Give more than one for large or	r linear resources) Zo	one ; mE/ mN	

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): Lots C & J and portion of A & B, Block 102, APN: 535-123-10

This two-story, Late Moderne commercial structure was constructed as a bank in 1954. Rectangular in shape, the building is set on a reinforced concrete foundation with concrete piers and steel trusses. The building features a flat roof with little ornamentation. Along the north (main) elevation, the exterior is recessed with twelve, vertical multi-paned window sets. At the northwest corner, a flat roof projection is supported by a concrete column with the main entrance underneath. Along the west elevation, there is a horizontal row of multi-paned windows framed by concrete molding. The exterior consists of stucco over concrete. Overall, the building appears to be in good condition.

P3b. Resource Attributes: (List attributes and codes) __ HP6



*P4. Resources Present: I Building P Structure P Object D Site D District P Element of District P Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

I Historic

P Prehistoric P Both 1954 Building Permit Records

*P7. Owner and Address:

Robinson, 3703 Camino Del Rio South, #100, San Diego, CA 92108 P8. Recorded by (Name, affiliation, and address): Office of Marie Burke Lia, 427 C Street, Suite 416, San Diego, California 92101

Cal First Properties, Inc., c/o Kathv

*P9. Date Recorded: March 2004

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Resources Inventory Update Of The East Village Area For Centre City Development Corporation Attachments: PNONE Decation Map PSketch Map Continuation Sheet Building, Structure, and Object Record □Archaeological Record □District Record PLinear Resource Record PMilling Station Record PRock Art Record □Artifact Record □Photograph Record P Other (List):

State of California — The Resources Agency Primary # DEPARTMENT OF PARKS AND RECREATION HRI#	
BUILDING, STRUCTURE, AND OBJECT RECO	ORD
	atus Code6Z
*Resource Name or # (Assigned by recorder) 1101 Market Stre	
B1. Historic Name: First National Bank	
B2. Common Name: <u>Union Bank of California</u>	
B3. Original Use: Commercial B4. Present Use: Comme *B5. Architectural Style:Late Moderne	
*B6. Construction History: (Construction date, alternations, and date	
Building constructed in 1954. Improvements include nume 1972); aluminum awnings installed (1954); installation of dri room (1972); installation of automatic teller machine par construction of exterior canopy and parking improvements (19 *B7. Moved? No DYes DUnknown Date:	erous signage installed (1954, 1955, 1961, 1969, ve up teller window and teller station/conference rtitions and exterior wall remodel (1984); and 96).
*B8. Related Features:	Oliginal 2000aton.
None	
B9a. Architect: Frank L. Hope b. Builder: H.W. G	
*B10. Significance: ThemeN/A Area Period of Significance _ N/A Property Type	
(Discuss importance in terms of historical or architecture)	7.7)
geographic scope. Also address integrity.) Historical research indicates that the 1101Market Street building was cons Form indicates that the building was constructed for the First National Bank at a L. Hope served as the architect, while H.W. Grizzle served as the builder. Over the California First National Bank, the California First Bank, and currently, the Unit was subject to various improvements (see "B6. Construction History" about station/conference room were designed by architect Russell Forester.	tructed in 1954. A City of San Diego, Building Permit Application cost of approximately \$110,500. The form indicates that Frank he years, the building served the First National Bank, the Southern on Bank of California. From the 1950sthrough 1990s, the bank we). The installation of a drive up teller window and teller
The original architect of the 1101 Market Street building, Frank Lewis Hogagent for the Santa Fe Railway, moved the family to San Diego in 1913 where, sophomore year when he dropped out to work in the local Navy shipyards during at Berkeley and worked briefly for small architectural firms as a draftsman, design and Jackson and architect William Wheeler. After passing the state architectural Architects & Engineers, in 1928.	then Frank Hope Jr., attended San Diego High School until his the First World War. Hope attended the University of California mer, and project manager. In particular, Hope worked for Requa
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list)	
City of San Diego, Building Department Permit Records. City of San Diego, Water & Sewer Records.	
McAlester, Virginia & Lee, A Field Guide To American Houses, 2000.	(Sketch Map with north arrow required.)
Moomjian, Scott A., Historical Assessment Of The 693 San Elijo Street Residence, San Diego, California 92106, February 2004.	
Sanborn Fire Insurance Maps, 1887, 1888, 1906, 1921, 1940, 1956.	40 80 /> 60 8944
San Diego City and County Directories.	PAR 3
B13. Remarks:	3 PAR 1 88
*B14. Evaluator: Office of Marie Burke Lia Date of Evaluation: March 2004	AVE.
Date of Evaluation. Twater 2004	9205 to 28 (C)
(This space reserved for official comments.)	PAR 2 PAR 2 OO 0.89 AC 123
	172.04 PM18944 23
	ISLAND AVE * 1"=100"

CONTINUATION SHEET	Primary #
	Trinomial
Page 3 of 3 *Resource Name or # (Assi	igned by recorder)1101 Market Street
*Recorded by Office of Marie Burk	ce LiaDate March 2004
□ Continuation □ Update	

*B10. Significance:

During the late 1920s, work was difficult to find, and Hope worked on projects ranging from remodeling to storefront work. The turning point in Hope's career came in 1930 with the design of the Spanish styled Carmelite Monastery in Normal Heights. This project led to a number of Spanish Eclectic designs for the San Diego Catholic Diocese, including the Sacred Heart Catholic Church in Ocean Beach (1946), Our Lady of the Sacred Heart Catholic Church in City Heights (1947), the San Diego College for Women (1950), and the Immaculata on the campus of the University of San Diego (1964). A Hydrotherapy Gymnasium was designed in a Spanish Eclectic style for the Society For Crippled Children in 1934.

During the 1960s, Hope's son, Frank L. Hope, Jr. joined the firm and the company became known as The Hope Consulting Group or Hope Design Group. In 1961, Hope served as president of the California Council of the A.I.A., and in 1965, Hope was made a fellow in the A.I.A. Hope, Sr. ultimately retired in 1965. Hope's impact upon San Diego architecture was not limited to architecture. At various times, he was a director of the San Diego Chamber of Commerce, president of the San Diego Planning Commission, president of the University Club, and a director of Home Federal. He also belonged to the San Diego Rowing Club, the San Diego Rotary Club, the San Diego Navy League, and the Rancho Santa Fe Art Jury. Hope died in October 1994,

Historical research has determined that the 1101 Market Street building is not historically or architecturally significant. The building is not associated with any important events or individuals in terms of local, state, or national history. The building does not embody the distinctive characteristics of a type, period, and method of Late Moderne construction, in part due to the changes the building has sustained over the years. In addition, it does not represent the work of a master architect, builder, craftsman, or important, creative individual. While the building was designed by Frank Hope, generally recognized as a master in the field of architecture, the building was designed in a Modern style and does not represent the Spanish Eclectic style for which Hope is regarded as a master. Similarly, although Russell Forester, another figure regarded as a master architect, was responsible for changes to the building in 1972, his acclaim as a master architect was due to International style residences which he designed during the 1940s-1960s, rather than Modern commercial design modifications he produced during the 1970s.

PRIMARY RECORD

Primary #	
HRI #2138-0273-0000	
Trinomial	
NRHP Status Code 5S2	

Other Listingspdate	of November 1988	Centre	EaGity	Survey Documentation
Review Code	Reviewer			Date

Page 1 of 3 *Resource Name or #: (Assigned by recorder) 1425-1431 Market Street

P1. Other Identifier:

*P2. Location: □ Not for Publication_ • Unrestricted * a. County San Diego

and (P2b and P2c or P2d. Attach a Location Map as necessary.)
*b. USGS 7.5' Quad Point Loma Date _____ T ___; ___% of ___¼ of Sec___; ____B.M.

c. Address 1425-1431 Market Street City San Diego Zip 92101

d. UIM: (Give more than one for large or linear resources) Zone ; _____mE/ ___mN

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-153-14-00, Block 174 Horton's Addition, West Half of Lot K & L

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1888, this two-story wood framed building was designed in an Italianate architectural style. It has a general rectangular shaped plan, with an addition to the rear and features a flat roof with a parapet, a decorated cornice and frieze with brackets and a dentil band. The lower level features three shop fronts identified as 1425, 1427, and 1431 Market Street and two additional entrances presumably to the upstairs portion identified as 1427 and 1429 Market Street. Each of the three shopfront entrances feature double swinging doors surrounded on all sides by large fixed windows. The second floor features four sets of paired double-hung sash windows which have been modified to include sliders on the lower portion. Exterior building materials consist of horizontal clapboard siding with corner boards for the exterior walls, and most likely composition rolls for the roof. Overall, the building appears to be in good condition.



| P3b. Resource Attributes: (List attributes and codes) | HP5; HP6

*P4. Resources Present: I Building
Structure d Object d Site d District d
Element of District d Other (Isolates, etc.)
P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

I Historic

d Prehistoric d Both

1988 Centre City East Historic Site Inventory

*P7. Owner and Address

Home Run Properties, LLC

C/o Stephen E. Hoffman

136 Redwood Street, San Diego, 92103

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416,

San Dieqo, CA 92101___

*P9. Date Recorded: March 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre</u>
City East For Centre City Development Corporation

Attachments: a NONE □ Location Map a Sketch Map ■ Continuation Sheet • Building, Structure, and Object Record a Archaeological Record n District Record a Linear Resource Record a Milling Station Record □ Rock Art Record D Artifact Record D Photograph Record a Other (List):

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary #
BUILDING, STRUCTURE, AND OBJECT	
Page 2 of 3	*NRHP Status Code_ 5S2
*Resource Name or # (Assigned by recorder)1425-	1431 Market Street, San Diego, CA 92101
B1. Historic Name: The Tourist	
B2. Common Name: The Home Run Hotel	
	B4. Present Use: Mixed-Use Commercial
*B5. Architectural Style: Italianate	904
*B6. Construction History: (Construction date, alternation Constructed in 1888; rear addition; date	
*B7. Moved? No DYes DUnknown Date:	Original Location:
*B8. Related Features:	
	Clements b. Builder: Unknown
	San Diego Period of Significance 1888
Property Type Residential (Discuss importance in terms of historical or architectural context as de	
(2) source importance in terms of meterical of all officestal all context as as	mica sy atomo, portou, and goograpme cooper, race address integraphy
	388, this building was previously documented in Nove arie Lia and Dr. Ray Brandes. Past owners of the 1
	clude: San Diego real estate entrepreneur D.W. He
	(1988). According to past documentation this buil
was designed by San Diego architects John B.	Stannard and Gustavus Clements (Lia/Brandes:1988)
	lasted from Spring 1887 through 1889, and again
	ified as the "Tourist," the first floor of the buil

mber 425witt ding soon from ding was used as a dancing hall, salon, and store, with the second floor used as a lodging house. H. Requa, father of San Diego architect Richard Requa was the first proprietor of the Tourist as it was known until 1913. It was again known as the Tourist Hotel Past occupants of 1425 Market Street include: Ywe H. Pon laundry (1944/1945, 1950, 1955), Woo Wing laundry & Ywe H. Pon laundry (1960, 1965), Ywe H. Pon laundry (1969/1970), vacant (1975), Miguel V. Fernandez (1980), and Jose Diaz (1984). Past occupants of 1427 Market Street include: Matthew Ryan furnished rooms (1944/1945), P.H. Yee furnished rooms (1950), Tourist Room Hotel (1960, 1965, 1969/1970), The Annex Hotel (1975), The King's Rooms Hotel (1980, 1984) with Oranza B. King (1984). Past occupants of 1429 Market Street: vacant (1944/1945), Watson Sewing Machine Company (1950), vacant (1955), Mack's Radio & Elec. Shop (1960, 1965, 1969/1970, 1975), and Frederico V. Garcia (1980, 1984). Past residents of 1431 Market Street include: vacant (1944/1945), C.L. Arnold sewing machine repair/Arnold Repair Service (1955, 1960) vacant (1965, 1969/1970, 1975), and Roberto B. Garcia (1980, 1984).

quired.)

1

See DPR 523H, Continuation Sheet for more information	tion
B11. Additional Resource Attributes: (List attributes and codes) *B12. References: (partial list) See DPR 523H, Continuation Sheet for more information B13. Remarks:	(Sketch Map with north arrow re
*B14. Evaluator: Wendy L. TinsleyOffice of Marie Burke Lia Date of Evaluation: March 2001	MARKET
(This space reserved for official comments.)	(E) (F) (S) (S) (S) (S) (S) (S) (S) (S) (S) (S

4

(5)

(E)

CONTINUATION SHEET

Primary #	
HRIff/Trinomial 2138-0273-0000	

■ Continuation □ Update

Page3 of3					
Resource Identifier: (Assigned by recorder)	1425-1431	Market	Street.	San Diego,	CA 92101
Historic Name: The Tourist					

*B10. Significance (Continued):

Although the 1425-1431 Market Street building is listed as a "45" on the California State Office of Historic Preservation Historic Property Data File for San Diego County, historical research has revealed that this building is not historically significant, as it has not been directly associated with any important events, or individuals in terms of local, state, or national history. The building does however appear to be architecturally significant, at the local level, as a commercial building which embodies the distinctive characteristics of a type, period or method of Italianate construction. Past documentation has identified the architects of the 1425-1431 Market Street building as John B. Stannard and Gustavus Clements, who, although not masters, are considered to be important and creative individuals. The building, however, does not derive historical significance on this basis.

*B12.References: (Continued):

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.
McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.
San Diego City Directories
San Diego County Recorders Office
University of San Diego, San Diego Architects; 1868-1939, 1991, Department of History, Graduate Division.

DPR 523H (1/95)

	D	IN	Л	٨	R	V		0			D	
_	┍	ш	ИΖ	н	ĸ	T	ĸ		u	К		,

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION		
PRIMARY RECORD		5S2
Review Code	Reviewer	Date
Page1 of _3 *Resource Name or #: (Ass	igned by recorder) 148	8 Market Street
P1. Other Identifier:Davidson Furniture	Company Building	
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County	San Diego
and (P2b and P2c or P2d. Attach a Location Map as neces *b. USGS 7.5' Quad Point Loma Date	, ,	%of%ofSec;B.M.
c. Address <u>1488 Market Street City</u> Sa	n Diego	Zip <u>92101</u>
d. UTM: (Give more than one for large of	or linear resources	s) Zone;mE/mN
e. Other Locational Data (e.g., parcel #, directions to	resource, elevation, etc.,	as appropriate):

Block 1, Lots 7-9, Map: 856; APN: 535-161-04 **P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This one-story, Art Moderne commercial structure with mezzanine was originally constructed as a furniture company building c.1940. Square in shape, the building features a flat roof with stucco exterior. Along the lower front (east) storefront elevation, the building features a series of fixed bay windows, flanked by pilasters which appear to transition into decorative molding along the upper elevation section. The building features a prominent "U"-shaped element along the front elevation which includes the main entrance. This element begins as pilasters flanking the main entrance at the lower storefront, and rises upward as molding to form a central parapet above the roofline. The central face of this element below the roofline has been in-filled with stucco. The front elevation is divided by a projecting metal canopy which does not appear to be original. Small windows along the north elevation have been in-filled with air conditioning units. Overall, the building appears to be in good condition.


	*P4. Resources Present: Building
	□ Structure □ Object □ Site □ District □
	Element of District □ Other (Isolates, etc.) 25b. Description of Photo: (View, date accession #)
A Para	P6. Date Constructed/Age and Sources:
	☐ Prehistoric ☐ Both ☐ 1940
	Banborn Fire Insurance Maps
	an Diego City Directories
THE PERSON WAS IN	P7. Owner and Address: av Industries
	488 Market Street
And the William Control of the Contr	an Diego, CA 92101
	8. Recorded fay (Name, affiliation, and iddress): Office of Marie Burke
	ia, 427 C Street, Suite 416,
	an Diego, California 92101
*P10. Type of Survey: (Describe) Intensive	P9. Date Recorded: March 2004
P11. Report Citation (Cite survey report and other sHistoric Resources Inventory Update	sources, or enter "none".) <u>Of The East</u> Village Area For Centre CityDevelopment
Corporation	
	Continuation Sheet Building, Structure, and Object Record
□Archaeological Record □District Record □Linear	Resource Record □Milling Station Record □Rock Art Record
□Artifact Record □Photograph Record □ Other (Li	

BUILDING, STRUCTURE, AND OBJECT RECO	
	tus Code5S2
*Resource Name or # (Assigned by recorder) 1488 Market Stre	
B1. Historic Name: Davidson Furniture Company Bui	
B2. Common Name: <u>Disabled American Veterans Thr</u>	
B3. Original Use: Commercial B4. Present Use: Commercial	
»B5. Architectural Style: Art Moderne	
*B6. Construction History: (Construction date, alternations, and date	of alterations)
Building constructed $c.1940$; new stairs and fi (1979); individual air conditioning units added in	
*B7. Moved? No DYes Unknown Date:	Original Location:
*B8. Related Features: 634, 646 & 648 15 th Street	
B9a. Architect: Unknown b. Builder: Unknown	
*B10. Significance: Theme N/A Area	East Village/Centre City
Period of Significance N/A Property Type	Commercial Applicable Criteria N/A
(Discuss importance in terms of historical or architectu	ural context as defined by theme, period, and
geographic scope. Also address integrity.)	
This building was constructed as the Davidson Furniture Company building Map depicts the presence of this furniture store with a mezzanine and four rows "Davidson Furniture Company" which also included in conjunction with two furn The building was also used in conjunction with another warehouse at 648 15th Street of the building beginning in 1942 and lasting until at least 1960. The property is	of wood posts. The building was used in conjunction with the liture warehouses to the west (located at 634 and 646 15 th Street). The Davidson Furniture Company is listed as the first occupant
Historical research has determined that the 1488 Market Street building is any important events or individuals in terms of local, state, or national history. To a type, period, and method of Art Moderne construction. The building does not important, creative individual.	ne building, however, embodies the distinctive characteristics of
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list)	
City of San Diego, Building Department Permit Records.	
City of San Diego, Water & Sewer Records.	
McAlester, Virginia & Lee, A Field Guide To American Houses, 2000.	70
Sanborn Fire Insurance Maps, 1887, 1888, 1906, 1921, 1940,	(Sketch Map with north arrow required.)
1956. San Diego City and County Directories.	1
	G
B13. Remarks:	
*B14. Evaluator: Office of Marie Burke Lia	
Date of Evaluation: March 2004	æ
	F L
	3000
	4 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4
(This space reserved for official comments.)	
	2 . , ③ * ,
	120 122
	MARKET 3 1"=100"
	H
	-1

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET Prim

CONTINUATION SHEET	Primary #	34 (
	HRI #	
	Trinomial	
Page 3 of 3 *Resource Name or # ((Assigned by recorder) 1488 Market Surke LiaDate March 2004	
	Burke LiaDate March 2004	
rc Continuation Update		

Historic Photograph (C. 1940s); Sensor 5-251; "Davidson Furniture Company"; Photograph Courtesy Of



PRIMARY RECORD

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI #
PRIMARY RECORD	TrinomialNRHP Status Code_7
Other Listings Updat	e of November 1988 Centre City East Survey Documentation
Review Code	ReviewerDate
Page 1 of 3 *Resource Name or #: (Assignate) P1. Other Identifier:	ed by recorder) 1704-1710 Market Street
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as necessary. *b. USGS 7.5' Quad Point LomaDate	
c. Address 1704-1710 Market Street & 607-621 1	7 th Avenue . City San Diego Zip 92101
d. UTM: (Give more than one for large or l	inear resources) Zone; mE/mN

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): e. APN: 535-190-02-00, Sherman's Addition, Block 4, S 46' Lot 5 & ALL Lot 6 *P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1924, the six bungalows shown in the photograph below are identified as 1704-1710 Market Street and 607-621 17th Avenue. Designed in a Craftsman vernacular architectural style, the six houses are identical in design and feature a rectangular shaped plan, with a low pitched, side gabled roof with an enclosed eave overhang, and an ornamental, center gabled entrance porch supported by one square post on each front corner. Exterior building materials consist of composition shingles for the roof, and horizontal clapboard siding for the exterior walls. Window types include individually placed double-hung sash and a triple window on each building that serves as the focal point. Each triple windows features a larger fixed center sash with a multi-pane sash pattern on the upper portion, flanked on both sides by a narrow double-hung sash window. Security bars cover the windows. Overall, the buildings appear to be in good condition



ours cover the warmenty overally the culturings appear to be in	Sood Condition
	P3b. Resource Attributes: (List attributes and codes) HP3
	*P4. Resources Present: Building
A A A A	Structure D Object D Site D District D
and the state of t	Element of District Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)
	*P6. Date Constructed/Age and Sources:
	I Historic
	D Prehistoric □ Both .1924
	1988 Centre City East Historic Site Inventory
	*P7. Owner and Address Chase-Market Street Trust 03-20-00
	P.O. Box 180100
	Coronado, CA 92178
The state of the s	*P8. Recorded by (Name, affiliation, and
	address): Wendy L. Tinsley, Scott
	A. Moomijan, Office of Marie
	Lia, Attorney at Law, 427 C San Diego, CA 92178
*P9. Date Recorded: October 2001 / Owner Information and	Photo Updated June 2003
*P10. Type of Survey: (Describe)	
D44 D (0)	

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation_

Attachments: a NONE a Location Map D Sketch Map • Continuation Sheet • Building, Structure, and Object Record a Archaeological Record a District Record a Linear Resource Record a Milling Station Record

Record

Record ☐ Artifact Record a Photograph Record ☐ Other (List):


State of California — The Resources Agency Primary #
DEPARTMENT OF PARKS AND RECREATION HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD
Page 2 of 3 *NRHP Status Code 7
*Resource Name or # (Assigned by recorder) 1704-1710 Market Street, San Diego, CA 92101
B1. Historic Name: Morse Courts
B2. Common Name:
B3. Original USE: Residential B4. Flesent USE. Residential
*B5. Architectural Style: Craftsmen vernacular
*B6. Construction History: (Construction date, alternations, and date of alterations)
Constructed in 1881; according to past documentation, the front porch and balcony railings were replaced (1980s-1990s), composition shingles added to mansard roof, rear addition, dates unknown.
*B7.Moved? ☐ No Yes ☐Unknown Date: Between 1921-1940
*B8. Related Features:
B9a. Architect: Unknown b. Builder: Pacific Building Company
*B10. Significance: Theme Architecture Area San Diego Period of Significance 1924
Property Type Residential Applicable Criteria C_
(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)
Originally constructed in approximately 1924, this building was previously documented in November
1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past documentation reveals
a Notice of Completion for the north 66' of lots five and six was signed on February 27, 1924 by insurance agent Arthur J. Morse, who planned on utilizing the new buildings as rental units
insurance agent Arthur J. Morse, who prained on utilizing the new buildings as rental units

Originally constructed in approximately 1924, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past documentation reveals a Notice of Completion for the north 66' of lots five and six was signed on February 27, 1924 by insurance agent Arthur J. Morse, who planned on utilizing the new buildings as rental units. (Lia/Brandes: 1988) Past owners of the 1704-1710 Market Street/607-621 17th Avenue property and buildings include: Arthur J. Morse (1924-1948), Lee and Cornelia Kehre (1948-1949), Deta Meadwocraft (1949-1953), Marguerite Floyd (1953- date unknown), and Charles Goble, Cordelia Williams and Michelle Shaver (1988). See DPR 523H, Continuation Sheet for an incomplete listing of the residents of the 1704-1710 Market Street and 607-621 17th Avenue units.

Historical research has determined that the 1704-1710 Market Street and 607-621 17th Avenue residences are not historically significant, as the residences do not appear to be associated with any important events or individuals in terms of local, state, or national history. The buildings do not embody the distinctive characteristics of a type, period, or method of Craftsman vernacular construction. However, due to the fact that the six buildings constitute a residential "court", further study and/or research is necessary to determine whether the structures are significant due to their collective grouping. Such a determination will dictate whether the resources are eligible for listing on the local register.

*B11. Additional Resource Attributes: (List attributes and codes) *B12. References: (partial list) Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986. San Diego City Directories San Diego County Recorders Office B13. Remarks: *B14. Evaluator: Wendy L. Tinsley Office of Marie Burke Lia

(This space reserved for official comments.)



Date of Evaluation: October 2001

CONTINUATION SHEET

Primary #		 	
HRI #/Trinomial			

Continuation a Update

Page3 of3						
Resource Identifier: (Assigned by recorder)	1704-1710	Market	Street,	San Diego,	CA 92101	
Historic Name: Morse Courts	9(

P3a. Description (Continued):

Past residents of the 1704 Market Street residence include: B.W. Kern (1944/1945), vacant (1950), Billy J. Hill (1955), Cecil L. Morse (1960), Charles B. Hughes (1965), Vevia E. Stenger (1969/1970), Mary Strawder (1975), James Disham (1980), and Ruben Sanchez (1984).

Past residents of the 1710 Market Street residence include: C.E. King (1944/1945), H.E. Lescault (1950), Manuel Mendoza (1955), Carlos N. Perez (1960), Harold Hurst (1965, 1969/1970), Robert Manheim (1975), Frank B. Dolan (1980), and Unit One: Frank B. Dolan (1984), Unit Two: No Return, and Unit Three: Mario Cortez.

Past residents of the 607 17^{th} Avenue residence include: W.B. Rich (1944/1945), A.E. Trimm (1950), Antonio E. Alonzo (1955), and Edwin Roise (1960, 1965, 1969/1970, 1975, 1980, 1984).

Past residents of the 609 17th Avenue residence include: W. J. Shewbert (1944/1945, 1950), vacant (1955, 1960), Archie L. Tudor (1965), Mrs. Eva Clapp (1969/1970), Clemente Gonzales (1975), and Salvador Macias (1980, 1984).

Past residents of the 619 17^{th} Avenue residence include: Miles E. Moore (1944/1945, 1950, 1955, 1960, 1965, 1969/1970, 1975, 1980), and vacant (1984).

Past residents of the 621 17th Avenue unit include: N.H. Waddell (1944/1945), L.A. Carson (1950), Frank S. Stark (1955), Ralph O. Navarro (1960), Javier Lugo (1965), Mary Struda (1969/1970), Mrs. Rosemary Naba (1975), and Armando G. Nava (1980, 1984).

DPR 523H (1/95)


PRIMARY RECORD

and boundaries):

Primary #	
HRI #_2138-0274	-0000
Trinomial	
NRHP Status Code	5S2

	NRHP Status Code 5S2	_
	Other Listings Update of November 1988 Centre City East Survey Documentation	on
	Review CodeReviewerDate	
Page _	of3_ *Resource Name or #: (Assigned by recorder) 1715 Market Street	
P1.	ther Identifier:	_
*P2.	cation: D Not for Publication Unrestricted * a. County San Diego	_
and (P2	nd P2c or P2d. Attach a Location Map as necessary.)	
*b. U	7.5' Quad Point Loma Date T; R;¼ of ¼ of Sec;B.	٨.
c.	Idress 1715 Market Street City San Diego Zip 92101	_
d.	M: (Give more than one for large or linear resources) Zone; mE / m	N
e.	her Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):	
	PN: 535-190-08-00, Block 15 Sherman's Addition, E 50 FT of Lot 1 and All Lot 2	
*P3a.	escription (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting	g,

Originally constructed in 1881, and relocated to this lot between 1921 and 1940, this two-story apartment building was designed in an Italianate architectural style. It has a general square shaped plan and features a flat roof, with wide overhanging eaves, large curved brackets, and a full-length porch on the first floor. The porch features eight supportive wood posts, an extended mansard style roof with a flat portion out from the exterior wall which forms the foundations for the second floor balcony. Exterior building materials consist of horizontal clapboard siding for the exterior walls, wrought iron railing for the second floor balcony balustrade, composition shingles for the mansard roof, and most likely composition rolls for the flat roof. (See DPR 523H, Continuation Sheet for more information)



*P4. Resource Attributes: (List attributes and codes) HP3______
*P4. Resources Present: I Building □
Structure d Object d Site d District d Element of District d Other (Isolates, etc.)
P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

I Historic

d Prehistoric

D Both

.18B1____

1938 Centre City East Historic Site Inventory

*P7. Owner and Address

Dean C. & Theresa C. Waterman

2318 Meade Avenue

San Diego, CA 92116

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Lia. Attorney at Law, 427 C Street. Ste. 416, San Diego, CA 92101

*P9. Date Recorded: February 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre

City East For Centre City Development Corporation

Attachments: a NONE □ Location Map a Sketch Map ■ Continuation Sheet • Building, Structure, and Object Record □ Archaeological Record □ District Record □ Linear Resource Record □ Milling Station Record □ Rock Art Record □ Artifact Record □ Photograph Record □ Other (List):

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI# <u>2138-0274-0000</u>
BUILDING, STRUCTURE, AND OBJE	CT RECORD
Page 2 of 3	*NRHP Status Code 5S2
*Resource Name or # (Assigned by recorder) 1715 M	Market Street, San Diego, CA 92101
B1. Historic Name: Edmund Wescott House	
B2. Common Name:	
B3. Original Use: Residential (Single-Family)_	B4. Present Use: Residential (Multi-Family)
*B5. Architectural Style: Italianate	
	ons, and date of alterations) documentation, the front porch and balcony railings added to mansard roof, rear addition, dates unknown
*B7.Moved? No Yes Unknown Date: Bet	ween 1921-1940
Original Location: Corner of 12th Avenue and G St	reet
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: _	
	San Diego Period of Significance 1881/1921-1940
Property Type Residential (Discuss importance in terms of historical or architectural context as de	Applicable Criteria C_ fined by theme, period, and geographic scope. Also address integrity.)
	.881, this building was previously documented in Nov
	Marie Lia and Dr. Ray Brandes. Previous documen
-	et property and building include: Edmund Wescott (1 William Mossholder (1988). San <i>Diego</i> City Direc
	tet Street building include: the Edmund Wescott
	Chavex, Jose Martinez, Paul Martinez, and owner Ev
	ith nine units listed (1950), the Miller Apartment
	h nine units listed, Apartments with seven units l
and three units vacant (1969/1970), Walter Pe	etry (1975), Apartments, Mrs. Suadalupe Sanchez, and

in November cumentation t (1881-at Directories cott family ner Everett tments with its listed, z, and Mrs. Evangeline Rodriguez (1980), and no listing (1984). Past documentation states that the 1715 Market Street residence was featured in the 1883 publication titled The History of San Diego County, California, as an example of an architecturally distinct building in San Diego.

(See DPR 523H, Continuation Sheet for more information)

B11. Additional Resource Attributes: (Listattributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986. San Diego City Directories

San Diego County Recorders Office


B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley

Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



lings were unknown.

CONTINUATION SHEET

Primary #	
HRI #/Trinomial_	2138-0274-0000

■ Continuation

□ Update

Page3 of3					
Resource Identifier: (Assigned by recorder)	1715 Market	Street,	San Diego,	CA 92101	
Historic Name: Edmund Wescott H	House				

*P3a. Description (Continued):

Fenestration consists of aligned, double-hung, two-over-one windows on the north, street facing elevation. The front entry door on the first floor, and the balcony door on the second floor both feature upper transoms. Overall, this residence appear to be in good condition.

*B10. Significance (Continued):

Historical research has determined that the 1715 Market Street building is not historically **significant**, as it is not associated with any important events or individuals in terms of local, state, or national history. The building, however, is architecturally significant, at the local level, as a building which **embodies** the distinctive characteristics of a type, period, or method of the Italianate architectural style of construction. As the identity if the architect could not be ascertained, the building does not represent the work of a **master** architect or craftsman.

DPR 523H (1/95)

PRIMARY RECORD

1__ of __2

Page _

Primary #	
HRI #_2138-0367-0000	
Trinomial	
NRHP Status Code 6Z	

Other Listings	Update of November	1988	Centre	City East	Survey	Documentation
Review Code_	Reviewer				Date	
*Resource Name or #: (Assigned by recorde	er)	505 6 th	Avenue_		

P1. Other Identifier: *P2. Location: ☐ Not for Publication ■ Unrestricted* a. County San Diego_

and (P2b and P2c or P2d. Attach a Location Map as necessary.) _ T ___; R ___; ___¼ of ___¼ of Sec___; ____ *b. USGS 7.5' Quad Point Loma Date

Address 505 6th Avenue _City __San Diego __Zip __92101 UIM: (Give more than one for large or linear resources) Zone

d. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 535-111-07-00, S 1/2 Lot F, Block 97

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1885, this two-story commercial building was designed in a One-Part Commercial Block style with a modified false front on the west elevation. It has a general rectangular shaped plan and features a front-gabled roof of moderate pitch with no eave overhang, and a wall frame parapet on the west elevation. Windows are double-hung sash with a fixed upper pane, and feature wood surrounds. Exterior building materials consist of composition shingles for the roof and stucco-on-lath for the exterior walls, with some ceramic tile on the west elevation wall. The building has retained its overhanging corner entrance on the ground floor, and the overhanging portion features a transom. Green rounded awnings are present on the west and south facades and partially obscure the ground floor windows. Overall, the building appears to be in good condition partially as the result of recent renovations.



P3b. Resource Attributes: (List attributes and codes) HP6 Resources Present: Building Structure D Object D Site D District D Element of District Other (Isolates, etc.) P5b. Description of Photo: (View, date,

accession #)_ *P6. Date Constructed/Age and Sources:

Historic

D Prehistoric a Both C.1885

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Tivoli Enterprises, Inc. 620 Island Avenue,

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev, Office of Marie Lia. Attorney at Law, 427 C Street, St.e. 416, San Diego, CA 92101

Date Recorded: March 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation_

Attachments: a NONE Ducation Map Sketch Map Continuation Sheet • Building, Structure, and Object Record ☐ Archaeological Record a District Record a Linear Resource Record ☐ Milling Station Record o Rock Art Record a Artifact Record a Photograph Record Other (List): _

State of California — The Resources Agency Primary #	
DEPARTMENT OF PARKS AND RECREATION HRI#21	38-0367-0000
BUILDING, STRUCTURE, AND OBJECT RECO	ORD
	atus Code 6Z
*Resource Name or # (Assigned by recorder)505_6 th Avenue	, San Diego, CA 92101
B1. Historic Name: The Walker House	
B2. Common Name: The Tivoli	
B3. Original Use: Commercial/Residential B4. Present	Use: Commercial
*B5. Architectural Style: One-Part Commercial Block w	ith a Modified False Front
*B6. Construction History: (Construction date, alternations, and date Constructed in 1885; exterior ground floor renovations)	
*B7. Moved? ■ No □Yes □Unknown Date:	Original Location:
*B8. Related Features: B9a. Architect: A.W. Delane b. Builder: Unknown *B10. Significance: Theme N/A Area San Diego Property Type Commercial/Residential (Discuss importance in terms of historical or architectural context as defined by theme, page 1.5.	Period of Significance 1885_ Applicable Criteria N/A_
Originally constructed in 1885, this building was the supervision of the Office of Marie Lia and Dr. Ray Fowners of the 505 6 th Avenue property and building inc. family (1910-1920), Albert Depietri (1920-1943), Dominic (1988). San Diego City Directories reveal that past include: Dominic Depietri (1944/1945 to c. 1950), Don To	Brandes. Previous documentation reveals past lude: W.T. Walker (1885-1910), the Maggiora Depietri (1943), and Wilfred & Ruth A. Romero proprietors of the 505 6 th Avenue building

Cafe (c.1960 to the present).

Historical research has determined that the 505 6^{th} Avenue building is neither historically nor architecturally significant. The 505 6th Avenue building is not associated with any important events or individuals in terms of local, state, or national history. Moreover, it does not embody the distinctive characteristics of a type, period, or method of the One Part Commercial Block style of construction, and does not represent the work of a master architect or craftsman. The building is not eligible for listing on the local register.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

Longstreth, Richard, The Buildings of Main Street; A Guide To American Commercial Architecture, 1987. San Diego City Directories

San Diego County Recorders Office


B13. Remarks:

This building appears on the Gaslamp Black Historical Society's Black Cultural Sites List, as a building occupied by Black businesses including the Anna Brown Hotel (1929). This determination, however, has not been independently verified.

*B14. Evaluator: _ Wendy L. Tinsley Office of Marie Burke Lia

Date of Evaluation: March 2001

(This space reserved for official comments.)



S D

		A D	V D	^ D	
பப	I N /I	Λ \square	v D	 m	
$-\kappa$	IIVI	4 R	Y R	 l IR	.,

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary #		
PRIMARY RECORD	Trinomial		
Other Listing	s		
Page 1 of 2 *Resource Name or #: (A	ssigned by recorder)705_6 th Avenue		
	tore * a. County San Diego		
and (P2b and P2c or P2d. Attach a Location Map as nee	essary.)		
*b. USGS 7.5' Quad Point Loma Date	T; R;% of% of Sec_; B.M.		
c. Address 705 6 th Avenue City	San Diego Zip. 92101		
d. UTM: (Give more than one for large	e or linear resources) Zone; mE/mN		
e. Other Locational Data (e.g., parcel #, direction Block 71, Lot F, Map: D, Book 13,	11 1		

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This one-story, commercial building is believed to have been originally constructed c. 1929. Originally built to serve as a grocery store, the building was substantially remodeled in between 1999-2001 to reflect its current utilitarian style. Set on a reinforced concrete foundation, the building features a flat roof with decorative cornice. Along the northwest elevation, the building rises to include a parapet. The exterior consists of brick. Along the west and south elevations, there are fixed storefront windows under awnings, separated by pilasters. A one-story building, originally located on an adjacent parcel to the northeast (Assessors Parcel Number 535-101-02), was incorporated into the subject project at an unknown date. Overall, the building appears to be in good condition.

Lia, 427 C Street, Suite 416,

Resource Attributes: (List attributes and codes)

*P4. **Resources Present:** | Building 1 Structure P Object

Site

District .lement of District P Other (Isolates, etc.) 5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

Prehistoric P Both c.1929

San Diego City Directories

*P7. Owner and Address:

MH Sherman Company

c/o D.T. Daniels

P.O. Box 1715

Newport Beach, CA 92659

Recorded by (Name, affiliation, and address): Office of Marie Burke

San Diego, California 92101

*P9. Date Recorded: May 2004

*P10. Type of Survey: (Describe)


Intensive


P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Resources Inventory Update Of The East Village Area For Centre City Development Corporation_

Attachments: UNONE Uncation Map Uncation Map Uncontinuation Sheet Building, Structure, and Object Record □Archaeological Record □District Record □Linear Resource Record PMilling Station Record PRock Art Record

PArtifact Record PPhotograph Record P Other (List):_

	1 2 <u>a</u> <u>a</u> 1
BUILDING, STRUCTURE, AND OBJECT RECO	
Page 2 of 2 *NRHP St *Resource Name or # (Assigned by recorder) 705 6 th Avenue	atus Code 6Z
B1. Historic Name: <u>MacMarr Grocery Store</u>	
B2. Common Name:	
B3. Original Use: Commercial B4. Present Use: Commer	
*B5. Architectural Style: _ One-Part Commercial Block	
*B6. Construction History: (Construction date, alternations, and date	of alterations)
Building constructed c.1929; building reduced to a "shell for current restaurant use (1999-2001). Building located on 03) incorporated into subject building (date unknown).	" and remodeled to accommodate tenant improvements adjacent parcel (Assessors Parcel Number 535-101-
*B7. Moved? No □Yes □Unknown Date:	Original Location:
*B8. Related Features:	
None	
B9a. Architect: Unknown b. Builder: Unknown	
*B10. Significance: ThemeN/A Are	
	Commercial Applicable Criteria N/A
(Discuss importance in terms of historical or architec	
geographic scope. Also address integrity.)	
This building is believed to have been constructed c. 1929 as MacMarr Groccupant in 1930. The building was occupied by MacMarr until at least 1935. It Company (1940-1950), followed by the Atlas Lithograph Company in 1955. In Insurance Map first depicts the presence of the building as a "store" along the west southeast elevation (614-620 G Street). By 1956, a "sign painting shop" occupied 2001, the building was reduced to a "shell." City of San Diego Building Pe accommodate tenant improvements in conjunction with the building's restaurant	n 1940, the property was occupied by the West Coast Gas Engine 1960, the property was vacant. Inspection of a 1940 Sanborn Fire at elevation (705-709 6th Avenue) and a "machine shop" along the space at the northwest elevation (709 6th Avenue). Between 1999-rmit applications indicate that the building was remodeled to use.
Historical research has determined that the 705 6 th Avenue building is not associated with any important events or individuals in terms of local, state, or n characteristics of a type, period, or method of construction, particularly since the changes the building sustained between 1999-2001. In addition, it does not represe creative individual.	ational history. The building does not embody the distinctive original integrity of the structure has been compromised due to
B11. Additional Resource Attributes: (List attributes and code	s)
*B12. References: (partial list)	
City of San Diego, Building Department Permit Records. City of San Diego, Water & Sewer Records.	(Sketch Map with north arrow required.)
Longstreth, Richard, The Buildings Of Main Street, 1987.	F
McAlester, Virginia & Lee, A Field Guide To American Houses, 2000.	4
Sanborn Fire Insurance Maps, 1887, 1888, 1906, 1921, 1940,	- " " - "
1956. San Diego City and County Directories.	
B13. Remarks:	a 40 E
*B14. Evaluator: Office of Marie Burke Lia	
Date of Evaluation: May 2004	
(This space reserved for official comments.)	17 - 77 AVENUE
	(THO :
	. E. D.
	1-100
	g N





PRIMARY RECORD

Primary #	
HRI # 2138-0381-0000	
Trinomial	
NRHP Status Code 5S2	

Other Listings Update of November 1988 Centre City East Survey Documentation Review Code_____Reviewer____

*Resource Name or #: (Assigned by recorder) 701 7th Avenue 1 of _6 Page P1. Other Identifier:

Location:

Not for Publication • Unrestricted * a. County San Diego_ and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma Date T; R; ¼ of ¼ of Sec; B.M. c. Address 701 7th Avenue City San Diego Zip 92101

C.

d. OTM: (Give more than one for large or linear resources) Zone ___; ____ mE/ ____N

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 535-102-06-00, Lots E & F W ½ G & H, Block 72

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1928, this three-story apartment hotel was designed in a Spanish Eclectic architectural style with an early Modern influence. It has a general rectangular shaped plan and features a flat roof with a cornice spanning across all four facades, and a plain frieze dotted with patterned ventilation unit openings. Window types vary on all three floors and includes doublehung sash, single-hung sash, and single fixed sash patterns. The south facade features three arched openings indicating the location of the hallway on each floor. (See DPR 523H, Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes HP41, HP3 and codes)

*P4. Resources Present: Building n Structure D Object D Site n District n Element of District □ Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)_

*P6. Date Constructed/Age and Sources:

Historic

D Prehistoric D Both

1928

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Arlington, LLC

C/o Hughes Management

.751 7th Avenue, # B

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416.

San Diego, CA 92101

*P9 Date Recorded: March 2001 *P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: □NONE a Location Map □ Sketch Map ■ Continuation Sheet ■ Building, Structure, and Object Record a Archaeological Record o District Record DLinear Resource Record o Milling Station Record o Rock Art Record o Artifact Record a Photograph Record n Other (List):

State of California — The Resources Agency	,
DEPARTMENT OF PARKS AND RECREATION	N
BUILDING, STRUCTURE, AN	D

Primary #		
HRI#	2138-0381-0000	

OBJECT RECORD

Page	2	of	6	*NRHP	Status	Code

Historic Name: San Diego Hoffman Hospital and Clinic

B2. Common Name: The Arlington Hotel

B3. Original Use: Hospital and Clinic (1928-1936) B4. Present Use: Residential (1939-Present)

Spanish Eclectic with a Modern influence *B5. Architectural Style:

*B6. Construction History: (Construction date, alternations, and date of alterations)

Constructed in 1928; no substantial modifications and/or alterations noted.

*B7. Moved? | No □Yes □Unknown Date: Original Location:

*B8. Related Features:

b. Builder: Thomas M. Russell B9a Architect: Louis Gill

Area San Diego Period of Significance . 1928 *B 10. Significance: Theme Architecture

Applicable Criteria C_ Property Type Residential

(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Originally constructed in 1928, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation reveals past proprietors of the 701 7th Avenue property and building include: David Bancroft Hoffman (a. Late 19th Century), and Dr. D.M. Wegeforth (1928) San Diego City Directories reveal that past proprietors of the 701 7th Avenue building include: the El Tempo Hotel and Mrs. Sula McLean (c.1939-c.1944/1945), and the Arlington Apartment Hotel (c.1950-Present). Past Arlington managers listed include: F.W. Packard (1950), Releford M. Martin (1955), and Myrl Van Steenwyck (1960 thru 1970). Prior to the construction of the current 701 7th Avenue building, a previous structure had been present on the site which was the home and clinic of New Town San Diego's first medical doctor, Dr. David Bancroft Hoffman. Due to the nature of the property's prior use, as well as its centralized location, the site was chosen for the new downtown hospital in 1928, which upon completion of construction in that same year, was under the administration of Dr. H.M. Wegeforth. The hospital remained open until 1936, and the building remained vacant until 1939, when it reopened as the El Tempa Hotel under the proprietorship of Sula McLean.

(See DPR 523H, Continuation Sheet for more information)

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office

San Diego Union, February 25, 1928.

San Diego Union, April 1, 1928.


B13. Remarks:

*B14. Evaluator: Wendy L. Tinslev,

Office of Marie Burke Lia

Date of Evaluation: March 2001

(This space reserved for official comments.)



CONTINUATION SHEET

I Continuation a update

Page3 of	6		
Resource Identifier: (A	Assigned by recorder)	701 7 th Avenue, San Diego, CA 92101	
Historic Name:	San Diego Hoffman	Hospital and Clinic	

P3a. Description (Continued):

Using barrel vaulting at the front porch area, two arches are present and supported by a single squared off column with a plain capital and base, and on both sides of the corner walls, a faux pilaster is indicated by the placement of the capital and base features of a column directly on the exterior wall surface. Exterior building materials consist of plastered brick, iron railings for the porch and hallways, and most likely composition rolls for the roof. Overall, this building appears to be in excellent condition.

*B10.Significance (Continued):

Although not relevant to the current 701 7th Avenue building, past documentation provides biographical information about Hoffman that should not be excluded from the record, stating "He [Hoffman] followed Alonzo Horton to New Town and bought this corner property. Hoffman was a Vice President of the American Medical Association and a politically active member. At an 1870 State Medical Association meeting, he caused some excitement, he caused some excitement by presenting a resolution to allow all persons, of either sex, with necessary qualifications to become members. The resolution was tabled. He [Hoffman] died in 1891." (Lia/Brandes:1988)

See page 4, DPR 523H, Continuation Sheet for a complete 1960 listing of 701 $7^{\rm th}$ Avenue residents.

Historical research has determined that the 701 7th Avenue building is both historically and architecturally significant at the local level. Constructed in 1928 as New Town San Diego's first general hospital and emergency facility, the 701 7th Avenue building is considered to be historically significant at the local level. In addition, designed by prominent San Diego architect Louis Gill, FAIA, the 701 7th Avenue building is architecturally significant as an example of Gill's work, as well as a reflection of the changing axiom in architecture at the time. The 701 7th Avenue building is an example of a Spanish Eclectic style with a Modern influence, which is illustrated in the clean symmetrical surface, straight lines of the building, and a general lack of exterior ornamentation.

DPR 523H (1/95)

CONTINUATION SHEET

Primary #_______HRI #/Trinomial 2138-0381-0000_____

I Continuation

□ update

Page __4__ of __6__

Resource Identifier: (Assigned by recorder) _____701 _7th _Avenue, _San _Diego, _CA _92101

Historic Name: San Diego Hoffman Hospital and Clinic

*B10. Significance (Continued):

1960 listing of 701 7th Avenue residents:

Proprietor: Myrl VanSteenwyck

103 Ivan Mitchen	201 vacant	301 vacant
105 vacant	203 vacant	303 vacant
106 U.H. Hall	205 Chire Rezek	305 Lawrence Hansen
108 vacant	207 Alvin Voeck	307 Barton Beaudin
	208 vacant	
111 Mrs. Ethel Gibbs	209 Melvin Smith	309 Joseph L. Williams
113 John E. Hill	210 Hans Larson	310 Mrs. Dorothy White
115 Mrs. Grace Lane	211 Mrs. Emma Mangan	311 Frank Panicello
116 vacant	212 Edward Deane	312 Thomas Powers
117 vacant	213 William F. Schaeffer	313 Carl Ving
118 Charles Walter	215 vacant	314 Mrs. Villa Hornbrook
120 Edwin Garner	216 Edwin Chartier	315 vacant
121 vacant	217 vacant	316 vacant
122 Oren Hickok	218 Joseph Keller	
	219 Mrs. Charlotte Fehr	318 Horace Bell
	220 Sinnard Ross	
	222 Virginia Shubert	321 Mrs. Eva Gilbert
	223 Diego Ciulla	322 vacant
	224 Michael J. Stevens	323 vacant
	225 vacant	324 vacant
		325 vacant

CONTINUATION SHEET

Primary # HRI #/Trinomial 2138-0381-0000

Continuation

update

Page __5 of __6_


Resource Identifier: (Assigned by recorder) 701 7th Avenue, San Diego, CA 92101_____

Historic Name: San Diego Hoffman Hospital and Clinic

February 25, 1928 San Diego Union article photograph of the new hospital building.

By Creating Many-Featured Hospital

San Diego Hospital Clinic which soon will be opened at the northeast comer of Seventh and 0 streets. The building, which was designed by Louis J. Gill, local architect, offers many interesting features in hospital arrangement.



Announced as one of the best de-) the minor operating room. The ar-I operating rooms. The top floor is signed buildings for its purpose in I rangement: said to be such, to-i voted to rooms and wards for paging the first floor operating rooms. The top floor is signed buildings for its purpose in I rangement: said to be such to-i voted to rooms and wards for paging the first floor operating that serent tients. All rooms are outside rooms. Hospital_Clinic building is nearing: Cases can be cared for at one time. There will be 47 beds, each provided for floor of the such task of section on the many of seventh and 0 streets, and is as incential beds are party in October. Of difference of control on subber wheels and can which does not block the violatory early in October. Of difference on the laken with patients to and from of sunlight, is used in windows. The first floor of the many entrance to the sunlight of sunlight, is used in windows. Peatures of design which were the building. It has both steps and the design of the many entrance to the sunlight of sunlight is an incential page of the surface of the sunlight of sunlight is an incential page of the surface of the sunlight is an incential page of the surface of the sunlight is an incential page of the surface of the sunlight is a surface of the sunlight in the building restly a four-atory one, the clinic include the page of the sunlight is the sunlight of sunlight in the sunlight of sunlight is a surface of the sunlight of the surface of the sunlight in the building restly a four-atory one, the clinic include the page of the sunlight of the surface of the sunlight in the building restly a four-atory one, the clinic include the page of the sunlight in the building restly a four-atory one, the clinic include the page of the sunlight in the building restly a four-atory one, the clinic include the page of the sunlight of the sunlight in the sunlight of the

DPR 523H (1/95)

CONTINUATION SHEET

I Continuation


□ Update

Page __6__ of __6__

Resource Identifier: (Assigned by recorder) 701 7th Avenue, San Diego, CA 92101

Historic Name: San Diego Hoffman Hospital and Clinic_

April 1, 1928 San Diego Union article depicting architect Louis J. Gill's rendering of the new hospital building.



DPR 523H (1/95)

F

and boundaries):

Primary #	
HRI # 2138-0271-0000	
Trinomial	
NRHP Status Code 7	741

PRIM	MARY RECORD	Trinomial				
	N	NRHP Status Cod	de_ 7	- 4		
	Other Listings <u>Update</u>	of November 198	8 Centre Cit	y East Survey	Documer	ntation
	Review Code	Reviewer		Date		
age _	1_ of2 *Resource Name or #: (Assigned	by recorder)	615 8 th Ave	nue		
1.	Other Identifier:					
P2.	Location: □ Not for Publication ■ Unrestricted *	a. County	San Dieg			
	P2b and P2c or P2d. Attach a Location Map as necessary.)					
b. US	USGS 7.5' Quad Point Loma Date	T; R	_:% of	¼ of Se <u>c_</u>	.;	B.M
	Address 615 8 th Avenue & 804 Market Street	City S	<u>an Diego</u>	Zip _	921	01
l.	UTM: (Give more than one for large or li	near resourc	ces) Zone _		mE/	mN
	Other Locational Data (e.g., parcel #, directions to resource APN: 535-104-03-00, Horton's Addition,					
P3a.	Description (Describe resource and its major elements.	Include design.	materials, con	dition, alteration	ns. size.	settina

Originally constructed in 1913, this four-story building was designed in a Two-Part Commercial Block style. The upper portion consists of the second thru third floors, and features an overhanging boxed cornice with brackets and aligned, double-hung windows with wood sills, belt coursing between the first and second floors, and a plain frieze below the belt coursing. The first floor of the building is dedicated to commercial use, and features signage, large, fixed single panes of glass, double-entry doors for the commercial portion, and a recessed entrance with an awning for the upper residential hotel portion. Overall, the building appears to be in fair condition.



P3b. Resource Attributes: (List attributes and codes) HP5. HP6 Resources Present: • Building o Structure

Object

Site a District Element of District o Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #) *P6. Date Constructed/Age and Sources:

Historic Prehistoric a Both 1913

1988 Centre City East Historic Site Inventory


*P7. Owner and Address: Barry Hotel LLC


C/O EE LLC 615 8th Ave, San Diego, CA 92101 *P8. Recorded by (Name, affiliation, and address): _Wendy L. Tinsley, Scott Moomijan, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101


*P9. Date Recorded: October 2001 / Owner Information and Photo Updated June 2003 *P10. Type of Survey: (Describe) P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre East For Centre City Development Corporation Attachments: □NONE □ Location Map a Sketch Map o Continuation Sheet • Building, Structure, and Object Record ☐ Archaeological Record ☐ District Record a Linear Resource Record ☐ Milling Station Record c Rock Art Record Artifact Record а Photograph Record


State of California — The Resources Agency Primary #	
	38-0271-0000
BUILDING, STRUCTURE, AND OBJECT RECO	ORD
	atus Code 7
*Resource Name or # (Assigned by recorder)615 8 th Avenue,	
B1. Historic Name: The Hotel Schneider	
B2. Common Name: The Barry Hotel B3. Original Use: Mixed Use Hotel over Commercial B4. P	recent Use: Mixed Use Hotel over Commercial
*B5. Architectural Style: Two-Part Commercial Block	resent Use. Whited Use Hotel Over Commercial
*B6. Construction History: (Construction date, alternations, and date Constructed in 1913; various signage has been added entrances have been covered and changed, also according	and removed according to use, and first-floor
*B7. Moved? No	Original Location:
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: <u>George E. Corne</u> *B10. Significance: Theme Architecture Area San Diego Property Type Residential Applicable C (Discuss importance in terms of historical or architectural context as defined by theme, p	Period of Significance 1913_ Criteria C_
Originally constructed in 1913, this building was the supervision of the Office of Marie Lia and Dr. Ray Br proprietors of the 615 8 th Avenue building include: Rolan c. 1920-1934, and past owners include: Willis & Norma reveal that the Barry Hotel has been listed at 615 (c.1944/1945-present), and past owners/managers include: Starcevic (1970).	randes. Previous documentation reveals past d E. Schneider, Hotel Schneider manager from Kaufman (1988). San Diego City Directories 8 th Avenue for approximately 56-60 years
Historical research has determined that the 615 8th architecturally significant. The 615 8th Avenue building or individuals in terms of local, state, or national hascertained, the building does not represent the work of that of an important, creative individual. While the process the distinctive characteristics of this type, determination will dictate whether the resource is eligibed. Additional Resource Attributes: (List attributes and codes) *B12. References: (partial list) Lia and Brandes, Historic Site Inventory of Centre City Longstreth, Richard, The Buildings of Main Street, A Guide San Diego City Directories San Diego County Recorders Office	is not associated with any important events istory. As the identity of the could not be a master architect, master craftsman, nor property has been classified as a "Two Part ecessary to determine whether a structure period, or method of construction. Such a ble for listing on the local register. East, 1988.
B13. Remarks:	(Sketch Map with north arrow required.)
	N N
*B14. Evaluator: Wendy L. Tinsley. Scott A. Moomjian, Office of Marie Burke Lia Date of Evaluation: October 2001	G STREET
(This space reserved for official comments.)	

MARKET









C-151

PRIMARY RECORD

Primary #	
HRI #_2138-0387-0000	
Trinomial	

Other Listings <u>Update</u>	of November 1	988	Centre	City E	East	Survey Documentation
Review Code	Reviewer					Date
				d.		

NRHP Status Code 6Z

*P2. Location: a Not for Publication ■ Unrestricted * a. County San Diego and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma Date T ___; R __; __¼ of __¼ of Sec__; ___B.M.

c. Address 703-723 8th Avenue City San Diego 2ip 92101
d. UTM: (Give more than one for large or linear resources) Zone i mE/ mM

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):
APN: 535-103-04-00, Horton's Addition, Lots E & F, Block 73.

Identified as 703-723 8th Avenue in Assessors Files.

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

The building shown in the photograph below is identified **as** 703-723 **8**th Avenue, and the northernmost portion of the building was originally constructed in 1886 in a Victorian architectural style. The majority of the building is an addition constructed between 1907-1909, resulting in a **Two-**Part Commercial Block style building. It has a general rectangular shaped plan and features a flat roof with a series of recessed entrances to the various office **spaces**. The original windows have been replaced and types include: modern slider style, fixed with an upper transom, and possibly casement and double-hung. Exterior building materials consist of **stucco-on-lath** for the exterior walls, and most likely composition paper rolls for the **roof**. Overall, the exterior of the building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP6

*P4. Resources Present: ■ Building □

*P4. Resources Present: Building Structure Structure Site a District a Element of District a Other (Isolates, etc.)
P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

□ Prehistoric □ Both 1886/1907-1909

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Scarvelis Family Trust 02-02-81, 4365 Altamirano Way

San Diego, CA 92103

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: April 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: □NONE □Location Map □Sketch Map □Continuation Sheet ■ Building, Structure, and Object Record □Archaeological Record □District Record □Linear Resource Record □Milling Station Record □Rock Art Record □Artifact Record □Photograph Record □ Other (List):

Primary	/ #		
HRI#	2138-0387-0000		

BUILDING, STRUCTURE, AND OBJECT RECORD

Page 2 of 2 *NRHP Status Code 6Z

*Resource Name or # (Assigned by recorder) 701-711 8th Avenue, San Diego, CA 92101_

B1. Historic Name: The Revere Rooming House

B2. Common Name:

B3. Original Use: Hotel/Commercial B4. Present Use: Commercial

*B5. Architectural Style: Two-Part Commercial Block

*B6. Construction History: (Construction date, alternations, and date of alterations)

Originally constructed in 1886; and additions in 1907-1909.

*B7. Moved? D No • Yes □Unknown

Date: 1907-1909 additions prompted smaller original 1886 portion to be moved to the Northernmost section of Lot E.

Original Location: 1886 portion originally located on the Northeast corner of 8th Avenue and G Street._

*B8. Related Features:

B9a. Architect: Unknown

b. Builder: Unknown

*B10. Significance: Theme N/A

Area San Diego

Period of Significance 1886/1907-1909_

Property Type Residential/Commercial Applicable Criteria N/A

(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Originally constructed in 1886, with later additions in 1907-1909, this building was previously documented in November 1988 under the supervision of the Office of Marie Ha and Dr. Ray Brandes. Previous documentation reveals past owners of the 701-711 8th Avenue building include: Robert Blair (1886-1920), the Arbutus Sanitarium (c.1925-1945), and Steven Scarvelis (1988). Currently, ownership of the 701-711 8th Avenue building is maintained by the Scarvelis Family Trust. San Diego City Directories reveal that past residents/proprietors of the 701-711 8th Avenue building include: 1944/1945-711: The Oakley Rooms with Mrs. K.J. Gerold; 1950-703-707: K.W. Trowbridge Co., and 711: Lee Hotel with O.A. Madison; 1955-703: Ben Feinberg, 711: Lee Hotel with Ovid A. Madison; 1960 & 1965-703: A. Sonabent (tailors), 711: Lee Hotel; 1970-703: A. Sonabent Co., 711: Lee Hotel with Frank Soderberg and Chris C. Johnson.

Historical research has determined that the 703-723 8th Avenue building is neither historically nor architecturally significant. The 703-723 8th Avenue building is not associated with any important events or individuals in terms of local, state, or national history. Moreover, it does not embody the distinctive characteristics of a type, period, or method of Two-Part Commercial Block construction, and does not represent the work of a master architect or craftsman. The building is not eligible for listing on the local register.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

Longstreth, Richard, The Buildings of Main Street, A Guide To American Commercial Architecture, 1987. San Diego City Directories

San Diego County Recorders Office


B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley,

Office of Marie Burke Lia

Date of Evaluation: April 2001

(This space reserved for official comments.)



PRIMARY RECORD

and boundaries):

Primary #	
HRI #	
Trinomial	
NRHP Status Code_	5S2

IZIIA	IAIN I INECOND		THI IOTHIAI				
			NRHP Status Code_	5S2			
		Other Listings Updat	e of November 1988	Centre City	East Surv	ey Docume	ntation
		Review Code	Reviewer		Date		
Page _	1 of 2 *Resou	rce Name or #: (Assig	gned by recorder)	660 10 th	Avenue /	659 9 th	Avenue
P1.	Other Identifier:						
*P2.	Location: Not for Publication	■ Unrestricted *	a. County	San Diego)		
and (P2	2b and P2c or P2d. Attach a Loc	ation Map as necessary.	.)				
*b. US	GS 7.5' Quad Point Loma	Date	T; R; _	¼ of	_1/4 of Sec_	;	B.M.
С.	Address _660 10 th Avenu	ie / 659 9 th Avenue	e City San Diego	Zip	92101		
d.	UTM: (Give more than c	ne for large or l	linear resources) Zone _	_;	mE/	mN
e.	Other Locational Data (e.g., pa APN: 535-13S-01-00, Hor					L, Bloo	ck 50
⁴P3a.	Description (Describe resource	e and its major elements	s. Include design, mat	erials, condit	tion, alterati	ions, size	. settina.

Originally constructed in 1932, this single-story, One-Part Commercial Block building was designed in an Art Deco architectural style. It has a general rectangular shaped plan and features a flat roof with a series of raised parapets, protruding vertical features above the four garage doors flanked on both sides by a pilaster, a simple cornice spanning around the perimeter of the $10^{\rm th}$ Avenue portion of the building, and Chicago and industrial style windows around the facades. A smaller one-story addition was later constructed and is identified as 659 $9^{\rm th}$ Avenue. This portion also features a simple cornice, with similar **windows**. Overall, this building appears to be in good condition, and is a good example of the Art Deco style for a commercial use.



P3b. Resource Attributes: (List attributes and codes) HP6____

*P4. Resources Present: • Building D
Structure a Object □ Site □ District □
Element of District □ Other (Isolates, etc.)
P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

D Prehistoric □ Both 1932

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Chung H and Young H Lee

660 10th Avenue

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: April 2001 / Owner Information Updated June 2003


*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: o NONE □ Location Map □ Sketch Map o Continuation Sheet • Building, Structure, and Object Record D Archaeological Record D District Record n Linear Resource Record a Milling Station Record □ Rock Art Record a Artifact Record a Photograph Record n Other (List):

State of California — The Resources Agency	Primary #			
DEPARTMENT OF PARKS AND RECREATION	HRI#			
BUILDING, STRUCTURE, AND OBJE	CT RECORD			
Page 2 of 2	*NRHP Status Code_ 5S2			
	0 th Avenue, San Diego, CA 92101			
	ephone Company Garage			
	resent Use: Commercial			
B3. Original Use: Garage Space B4. P *B5. Architectural Style: Art Deco	resent ose. Commercial			
*B6. Construction History: (Construction date, alternation Constructed in 1932; the portion of	ons, and date of alterations) the building identified as 659 9 th Avenue appears			
to be a later addition.				
	Original Location:			
*B8. Related Features: B9a. Architect: Unknown b. Builder: _V	V.F. Kier Construction Company			
*B10. Significance: Theme Architecture Area	San Diego Period of Significance 1932_			
Property Type Garage Appli				
(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.) Originally constructed in 1932, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation and San Diego City Directories reveal past occupants of the 660 10 th Avenue garage include: Southern California Telephone Company (1932-c.1944/1945), and Pacific Telephone and Telegraph Company (1950, 1955, 1960, 1965, 1969/1970, 1975, 1980, and 1984). Presently, the building is occupied by the Farkas Store Fixtures Company.				
significant, as the building is not associate local, state, or national history. Howev architecturally significant , as a building who period, or method of Art Deco construction.	at the 660 10 th Avenue building is not historically ed with any important events or individuals in terms of er, the 660 10th Avenue building does appear to be ich embodies the distinctive characteristics of a type, Constructed by the W.E. Kier Construction Company, the master builder, or master craftsman, nor that of an			
B11. Additional Resource Attributes: (List attributes and cod	les)			
*B12. References: (partial list) Lia and Brandes, Historic Site Inventory McAlester, Virginia & Lee, A Field Guide San Diego City Directories San Diego County Recorders Office				
B13. Remarks:	(Sketch Map with north arrow required			
	: G			
*B14. Evaluator: Wendy L. Tinslev				
Office of Marie Burke Lia Date of Evaluation: April 2001	0.57 AC. 147 P. 305 71-2			

(This space reserved for official comments.)



PRIMARY RECORD

and boundaries):

Primary #	
HRI #_ 2138-0400-0000	
Trinomial	
NRHP Status Code 5S2	

Other Listings	Update of November	1988	Centre	City	East	Survey	Documentation
Review Code	Reviewer					Date	

Page	1 of	2	*Resource Name or #: (Assign	gned by recorder)	732-734	10 th Avenue	
P1.	Other	Identifier	:				

*P2. Location:
Not for Publication • Unrestricted *

and (P2b and P2c or P2d. Attach a Location Map as necessary.)


*b. USGS **7.5' Quad** Point Loma Date **T**; **R**; **¼** or **¼** of Sec; **B.M.** c. **Address** <u>732-734</u> <u>10th Avenue</u> City San Diego Zip <u>92101</u>

d. UTM: (Give more than one for large or linear resources) Zone ___; ____ mE/ __mN

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-131-05-00, Lot *I*, Block 74
*P3a. Description (Describe resource and its major elements. Include **design**, materials, condition, **alterations**, size, setting,

Originally constructed in 1887, this two-story apartment building has intermittently been identified as the "Tenth Street Apartments" in San Diego City Directories. Designed in an Italianate architectural style with Victorian style detailing. The building has a general square shaped plan with a low pitched, hipped roof, and features a wide eave overhang with a bracketed cornice, and vertical woodworking extending from the brackets down to the first floor porch roof, and the foundation. Exterior building materials consist of composition shingles for the roof, and horizontal clapboard siding for the exterior walls. Windows appear to be double-hung sash, and feature wood surrounds. A full length front porch is present on the east elevation of the building and features a hipped roof with an ornamental center gable, spindle style wood posts, turned columns and railings. A shallow, squared bay is present on the second floor of the east elevation, and is accentuated by the vertical stick style woodworking which borders it. Overall, the exterior of this apartment building appears to be in excellent condition.



P3b. Resource Attributes: (List attributes and codes) HP3_____

*P4. Resources Present: ■ Building D Structure n Object n Site □ District a Element of District o Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic
 Prehistoric
 1887

□ Both

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Fenwick Family Limited Partnership
c/o Terry Fenwick

2816 Columbia Street_

San Diego, CA 92103

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Lia, Attorney at Law, 427 C Street. Ste. 416,

San Diego, CA 92101____

*P9. Date Recorded: April 2001 / Owner Information and Photo Updated June 2003_

City East For Centre City Development Corporation

Attachments: n NONE n Location Map a Sketch Map □Continuation Sheet ■ Building, Structure, and Object Record a Archaeological Record □ District Record □ Linear Resource Record □ Milling Station Record n Rock Art Record a Artifact Record o Photograph Record n Other (List):

*					
State of California — The Resources Agency Primary #					
DEPARTMENT OF PARKS AND RECREATION HRI# 21					
BUILDING, STRUCTURE, AND OBJECT RECO	ORD				
	atus Code5S2				
*Resource Name or # (Assigned by recorder) 734 10 th Avenue,	San Diego, CA 92101				
B1. Historic Name: Ephraim & Mary Walker Morse Resid	ence				
B2. Common Name:					
B2. Common Name: B3. Original Use: Residential (single-family) B4. Page 1997.	resent Use: Residential (multi-family)				
*B5. Architectural Style:Italianate					
*B6. Construction History: (Construction date, alternations, and date	of alterations)				
Constructed in 1887; no substantial alteration					
*B7. Moved? No ☐ Yes ☐Unknown Date:Origi	nal Location:				
*B8. Related Features:					
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u> *B10. Significance: Theme N/A Area San Diego F	Period of Significance 1887				
Property Type Residential Applicable C					
(Discuss importance in terms of historical or architectural context as defined by theme, p	period, and geographic scope. Also address integrity.)				
Originally constructed in 1887, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past owners of the 734 10 th Avenue building known to have resided at the residence include: Ephraim & Mary Walker Morse(1887-c.1893), Norwood & Maude Tichenor (1907-1912), and Maude Tichenor (1912-c.1915). San Diego City Directories reveal the 734 10 th Avenue building was identified as the "Tenth Street Apartments" in 1944/1945 (only) and occupants included: F.J. Bay, Jack Claypool, Mrs. Lillian Edmonds, Michael Fincher, Jack Fitch, C.E. Hughes, Carl Kerner, owner F.D. Milligan, Cedric Peterson, Russell Simmons, and E.C. Stoll. Occupants in 1950 included: Mrs. A.H. Gray, H.S. Carger, W.J. Moser, and J.W. Reddock. 1955 occupants included: Mrs. Sign Sohn, and Frank Warren. Occupants in 1960 included: Paul D. Board, and Glenn O. Farley, with 2 apartments listed as vacant. Occupants in 1965 included Joseph Munsen, Mrs. Pearl Wooten, L.E. Watt, and Glenn O. Farley. Occupants in 1970 included: Mrs. Ada H. Larson, Ben Oakes, Wm. F. Norton, and Dow L. Rhoades. Occupants in 1975 included: Milda T. Harris, Jerry Schiavone, and Lois Purdorn, with one unit listed as vacant. Occupants in 1980 included: Leslie Velasquez, Clementine Lozano, Israel R. Perez, and R.E. Daniels. Lastly, Occupants in 1984 included: Pabo Alday, Clementina Lozano, Israel R. Perez, and R.E. Daniels.					
Although this building is listed as a "38" on the California State Office of Historic Preservation's Historic Property Data File for San Diego County, historical research has determined that the 734 10 th Avenue building is not historically significant, as it is not associated with any important events or individuals in terms of local, state, or national history. However, the building does appear to be architecturally significant, at the local level, as a building which embodies the distinctive characteristics of a type, period, or method of the Italianate style of construction. As the identity of the architect could not be ascertained, the building does not represent the work of a master architect or craftsman.					
B11. Additional Resource Attributes: (List attributes and codes)					
*B12. References: (partial list) Lia and Brandes, Historic Site Inventory of Centre City McAlester, Virginia & Lee, A Field Guide To American Ho San Diego City Directories					
San Diego County Recorders Office	(Sketch Map with north arrow required.)				
B13. Remarks:	8 F				
*B14. Evaluator: Wendy L. Tinslev.	9 1 2 8				
Office of Marie Burke Lia	2 - 2				
Date of Evaluation: April 2001	s s				
	E . O. 1				
(This space reserved for official comments.)	74 YEE				
	a g				

G

PRIMARY RECORD

Address

C.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary #HRI #2138-0401-0000				
PRIMARY RECORD	TrinomialNRHP Status Code _ 6Z				
	Dodatof Novembers Centre Eastty Decumentation Reviewer Date				
Page _ 1 of _ 2 *Resource Name or #: (Ass	signed by recorder) 743 10 th Avenue				
*P2. Location: □ Not for Publication ■ Unrestricted * and (P2b and P2c or P2d. Attach a Location Map as neces: *b. USGS 7.5' Quad Point LomaDate					


___ Zip_

743 10th Avenue d. UTM: (Give more than one for large or linear resources) Zone _ Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): 0 APN: 535-132-04-00, Lot C, Block 75

City <u>San Diego</u>

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1900, this two-story apartment house was designed in a Victorian vernacular architectural style for single-family use. It has a general rectangular shaped plan and features a low-pitched, hipped roof with a cross gable on the southwest roof line. Exterior building materials consist of composition shingles for the roof, horizontal shiplap siding for the exterior walls, and vertical clapboard siding for the second floor balcony enclosure. A first floor porch is present. It was most likely full length upon completion of original construction, and was partially enclosed to allow for additional living space. A full-length second floor balcony is also present, and is partially enclosed by a low wood wall approximately one foot high. West elevation window types consist of double-hung sash with a multi-pane sash pattern on the second floor, and a focal tri-partite window at the street level. Overall, the building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP3 Resources Present: Building

Structure

Object

Site

District Element of District Other (Isolates, etc.) Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic D Prehistoric c.1900

□ Both

1983 Centre City East Historic Site Inventory

*P7. Owner and Address:

Bernice M. Fenwick 1989 Trust 3707 5th Avenue, # 151_ San Diego, CA 92103

*P8. Recorded by (Name, affiliation, and Wendy L. Tinslev, address): Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

Date Recorded: April 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation_

Attachments: DNONE Location Map Sketch Map Continuation Sheet • Building, Structure, and Object Record □Archaeological Record □District Record □Linear Resource Record DMilling Station Record □Rock Art Record □Artifact Record □Photograph Record □ Other (List):

State of California — The Resources Agency	
DEPARTMENT OF PARKS AND RECREATION	1

Primary #		
HRI# 2	2138-0401-0000	

BUILDING, STRUCTURE, AND OBJECT RECORD

		-, -		,						
Page	2	of	2		*NRHP	Status	Code	6Z		_
*Res	ource N	ame or	r # (Assigned by	recorder) 743	10 th Aven	ue. San	Diego,	CA 92101		_
B1.	Histor	ic Name	: Tenth Aven	ue Apartment	cs		200			_
B2.	Comm	on Nam	ne:					_		
B3.	Origina	d Use:	Residential	(Single-fam	nily)_ B	4. Prese	nt Use:	Residential	(Multi-family)	
*R5	Archite	ectural	Stude Victoria	n vernacul	ar					

*B6. Construction History: (Construction date, alternations, and date of alterations)

Constructed in approximately 1900; first floor porch was most likely originally full length, and appears to have been partially enclosed for additional living quarters; past documentation indicates that the second floor balcony was enlarged (dates unknown).

*B8. Related Features:

B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>

*B10. Significance: Theme N/A Area San Diego Period of Significance 1900

Property Type Residential Applicable Criteria N/A

(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Originally constructed in 1900, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past owners of the 743 10th Avenue building include: M.L. Ward (1900-1902), Fred D. & Claudia Milligan (1902 until c.1949, Fred Milligan's death), and Bernice Milligan Fenwiek (1949-c.2000). A Bernice M. Fenwick Trust was established in 1989, and is currently listed as retaining ownership of the 743 10th Avenue building. San Diego City Directories reveal the 743 10th Avenue building was not listed in 1944/1945, and was identified as the "Tenth Street Apartments" in 1950, with nine tenants listed as residing in the building. The 743 10th Avenue building was identified as the "Tenth Avenue Apartments" from 1955 thru 1980, and appears to have contained approximately twelve units between those years with few vacancies listed during that time.

Historical research has determined that the $743\ 10^{th}$ Avenue building is neither historically nor architecturally significant. The $743\ 10^{th}$ Avenue **building** is not associated with any important events or individuals in terms of local, state, or national history. Moreover, it does not embody the distinctive characteristics of a type, period, or method of Victorian vernacular construction, and does not represent the work of a master architect or craftsman. The building is not eligible for listing on the local register.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, *Historic Site Inventory of Centre City East*, 1988. McAlester, Virginia & Lee, *A Field Guide To American Houses*, 1986. San Diego City Directories

San Diego County Recorders Office


B13. Remarks:


*B14. Evaluator: Wendy. Tinsley,

Office of Marie Burke Lia

Date of Evaluation: April 2001

(This space reserved for official comments.)





PRIMARYRECORD

C.

e.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary # HRI #
PRIMARYRECORD	TrinomialNRHP Status Code_6Z
Other Listings	Update of November 1988 Centre City East Survey Documentation
Review Code_	Reviewer Date
Page 1 of 3 *Resource Name or #: (A	Assigned by recorder) 650 11 th Avenue
*P2. Location: a Not for Publication • Unrestricted	a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as nec	
*b. USGS 7.5' Quad Point Loma Date	T; R;¼ or¼ of Sec;B.M.
	City San Diego Zip. 92101
d. UTM: (Give more than one for large	or linear resources) Zone;mE/mN

APN: 535-135-09-00, Portion Lot K, Block 82 *P3a. **Description** (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

Originally constructed in 1912, this three-story, multiple-family residence was designed in a vernacular townhouse style with an Italian Renaissance influence. It has a general rectangular shaped plan and features a flat roof with a cornice on the east elevation, a series of double-hung ribbon windows on the second and third floors, a projecting, skirted awning feature over the first floor, and a centered first floor front entrance flanked on both sides by two contiguous double-hung windows. The entrance features double doors with an upper transom, and the flared skirt above is ornamented with a dentil band. Exterior building materials consist of clapboard siding for the exterior walls, and most likely composition paper for the roof. A fire escape and iron balconies are present at the second and third floor levels on the east elevation, and an exterior staircase is present on the north elevation, providing entrance to rear units, Overall, the building appears to be in good condition.



*P4. Resources Present: • Building □ Structure □ Object □ Site a District □ Element of District P Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)
*P6. Date Constructed/Age and Sources: Historic
P Prehistoric a Both
1912
Historic Site Inventory
*P7. Owner and Address: 650 11 th LLC
3404 Jewell Street
San Diego, CA 92109
*P8. Recorded by (Name, affiliation, and address): Wendy L.
Tinsley, Office of Marie Lia, Attorney at Law,
427 C Street, Ste. 416, San Diego, CA 92101
*P9. Date Recorded: March 2001 / Owner
Information and Photo Updated June 2003
*P10. Type of Survey: (Describe)
P11. Report Citation (Cite survey report and other sources, or
enter "none".) Historic Site Inventory of Centre
City East For Centre City Development
Corporation
Attachments: □NONE n Location Map □ Sketch Map


• Continuation Sheet • Building, Structure, and Object Record P Archaeological Record P District Record P Linear Resource

Record P Milling Station Record P Rock Art Record P Artifact Record P Photograph Record P Other (List):

P3b. Resource Attributes: (List attributes and codes)

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI#
BUILDING, STRUCTURE, AND OBJECT	CT RECORD
Page 2 of 3	*NRHP Status Code 6Z
, , ,	Avenue, San Diego, CA 92101
B2. Common Name: B3. Original Use: Residential (multi-family)	B4. Present Use: Residential (multi-family)
	with an Italian Renaissance influence
*B6. Construction History: (Construction date, alternation	
*B7. Moved? No 🗆 Yes 🗆 Unknown Date:	Original Location:
*B8. Related Features:	2
B9a. Architect: Unknown b. Builder: M. *B 10. Significance: Theme N/\(\) Area San Die	
PropertyType Residential	Applicable Criteria N/A_
(Discuss importance in terms of historical or architectural context as defin	ned by theme, period, and geographic scope. Also address integrity.)
the supervision of the Office of Marie Lia and I owners of the Yale Apartment building includes 1944). Walter Kalben and Helen Adair (1944-195 L. Lichty (1988). A Tim & Sherry Lichty Familisted as currently retaining ownership of tinformation including San Diego City Director.	
architecturally significant. The 650 11th Avenu or individuals in terms of local, state, or distinctive characteristics of a type, period	he 650 11 th Avenue building is neither historically nor ue building is not associated with any important events national history. Moreover, it does not embody the , or method of Vernacular Townhouse construction, and itect or craftsman. The building is not eligible for
B11. Additional Resource Attributes: (List attributes and code	s)
*B12. References: (partial list)	
Lia and Brandes, Historic Site Inventory McAlester, Virginia & Lee, A Field Guide San Diego City Directories San Diego County Recorders Office	
	(Sketch Map with north arrow required.)
B13. Remarks:	
	G
*B14. Evaluator: _Wendy I . Tinslev	780 780
Office of Marie Burke Lia	
Date of Evaluation: March 2001	0°5%

(This space reserved for official comments.)



State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION

CONTINUATION SHEET

Primary #	8/
HRI #/Trinomial _	

Continuation

update

Page __3 __ of __3

Resource Identifier: (Assigned by recorder) ___650 11th Avenue, San Diego, CA 92101

<u>Historic Name: Yale Apartments</u>

*B10. Significance (Continued):

San $Diego\ City\ {\tt Directories}$ indicate past residents of the 650 $11^{\rm th}$ Avenue building include:

1944/1945: Yale Apartments, G.J. Berune, A.J. Creslo, Frank Gall, Charles Luppens, J.J. O'Brien, and J.B. Ostrowski;

1950: Yale Apartments, A.J. Creslo, J.R. Divet, Clarence Dixon, L.S. Gott lieb, Dewey Killen, H.W Lawson, A.G. Lloren, Charles Luppens, E.H. Mountjoy, Doreen Rapp, Jos. Roberti, Mrs. Isabel Robinson, Fred Ruby, Karl Schaub, Otto Stutzman;

1955: Yale Apartments, (owner) Earl H. Mountjoy;

1960: Yale Apartments, 1) Ora Ernest, 5) No Return, 6) Samuel Alexander, 7) Maria Gonzalez, 8) Jason Divit, 10) George W. Light, 11) George Graham, 14) John Jefferson, 15) Juan Flores, 17) Mrs. Helen Luppens, 18) Nell Durdick, 20) Joe Hernandez, 22) George W. Peck, 24) Roy Johns, 27) Ralph Sturgess, 28) Charley Harness, 31) William W. Dean, 33) Clyde Bryon, 34) Mrs. Olga Creslo, 36) Mrs. Doreen Rapp,, 38) Joe Mahon, 44) Al Weisman, 47) Jerry Leeman, 49) Mrs. Evangeline Rodriguez;

1965: Yale Apartments, units 1-48 listed non-consecutively;

1970: Yale Apartments, units 1-48 listed non-consecutively;

1975: Yale Apartments, twenty-five units listed as 1-48;

1980: Yale Apartments, 1) Jerry Gross, 6) R.P. Mondragon, 7) Kenneth Clark, 8) Ronald Largent, 10) Charles Hunt, 11) Roy L. Killer, 14) Sharon J. Brown, 15) C. Barker, 17) Mrs. Phyllis Lynn, 18) Verna Josin, 20) Arnold Sanchez, 22) Joseph Waseliviski, 24) Isa Kinkyleld, 27) Joseph Johnson, 28) William Griggs, 31) William Porter, 33) Mrs. Sidney Woods, 35) John Merorich, 36) Han Francisco, 38) Stanley Zuchowski, 40) Arila Rodrigues, 42) Orid Green, 44) Stine Butterman, 47) Charles C. Fountain, 48) Esther Hartman;

1984: Volunteers of America Work Furlough Program

DPR 523H (1/95)


PRIMARY RECORD

Primary #	
HRI #2138-0415-0000	
Trinomial	
NRHP Status Code 67/67	

Other Listings Update of November 1988 Centre City East Survey Documentation

	Review Code Reviewer	Date
_	1 of 3 *Resource Name or #: (Assigned by recorder) 727-733 ½ 11 th A	
*P2.	Location: a Not for Publication • Unrestricted * a. County San Diego	
	b and P2c or P2d. Attach a Location Map as necessary.) GS 7.5' Quad Point Loma Date T ; R ; ¼ or % or Map as necessary.) Address 727-733 ½ 11 th Avenue City San Diego Zip	
d.	UTM: (Give more than one for large or linear resources) Zone;	mE/mN
e.	Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 535-133-15-00, All of Lot D & WLY 3 Ft Of Lot I, Block 76	
*P3a.	Description (Describe resource and its major elements. Include design, materials , condition, alt and boundaries):	terations, size, setting,

This lot contains three structures which are collectively identified as 727-733 ½ 11th Avenue. The two rear apartment buildings, believed to be identified as 727-733 11th Avenue, were originally constructed in approximately 1886 and appear to have been designed in a Folk **Victorian architectural** style. Both of the rear two-story buildings have a general rectangular shaped plan and feature gabled roofs of moderate pitch, horizontal clapboard **siding** and single or double-hung sash **windows**. Past documentation states that the original entrance porches to these two apartment buildings were on 12th Avenue and were removed and stuccoed over in the 1940s, thus eliminating access from 12th Avenue. (See DPR 523H, Continuation Sheet for more information)



and codes) HP3 Structure Diplect District Dis Element of District

Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #) *P6. Date Constructed/Age and Sources: Historic □ Prehistoric □ Both 1886/1907 1988 Centre City East Historic Site Inventory *P7. Owner and Address: Hom Exempt Trust & Hom Non-Exempt Trust C/o John Hom, P.O. Box 611 Southeastern. PA 19399 *P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev, Scott A. Moomjian, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

P3b. Resource Attributes: (List attributes

*P9. Date Recorded: October 2001 / Photo Updated June 2003

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments:

NONE Location Map a Sketch Map • Continuation Sheet • Building, Structure, and Object Record D Archaeological Record D District Record Linear Resource Record Milling Station Record n Rock Art Record

Artifact Record a Photograph Record n Other (List):

9					
State of California — The Resources Agency	Primary #				
DEPARTMENT OF PARKS AND RECREATION	HRI# <u>213</u>	8-0415-0000			
BUILDING, STRUCTURE, AND OBJ	JECT RECO	RD			
Page2 of3		tus Code_62	3/6Z		
*Resource Name or # (Assigned by recorder) 727-73 B1. Historic Name: Thomas J. Daley Apar B2. Common Name: B3. Original Lices Possidential (M. Aleis Formation)	rtment & Jar –	nes A. Ba:	ilev Apart	ment Bui	
B3. Original Use: Residential (Multi-far *B5. Architectural Style: Folk Victorian (
*B6. Construction History: (Construction date, alternative 727-733 1 1th Avenue (Rear Structures): Originally contine 1940sthese two entrances were removed and studies 11th Avenue (Front Structure): Originally constructure unknown), two entry doors added to center of south face.	nstructed in approxuccoed over, eliminated in approximate	kimately 1887 nated access of ely 1907, a two	ff of 12 th Aven o-story balcony	nue. / has been rer	moved (date
*B7. Moved? No □	Yes □Ur	known	Date: _	Original	Location:_
*B8. Related Features: B9a. Architect: Unknown b. Builder: *B10. Significance: Theme Architecture Architecture Property Type Residential (Discuss importance in terms of historical or architectural context as	ea San Diego Applicable Cr	iteria C_			
Originally constructed in approximately previously documented in November 1988 under Brandes. Previous documentation indicates pand property include: Thomas J. Dailey (188 unknown), and Edwin Hom (1988). A Hom Exc	r the supervisions of the same	ion of the C the 727-733 ½ Bailey (1887)	office of Ma 11 th Avenue -1937), Edna	rie Lia ar apartment a Burdett	nd Dr. Ray buildings (1937-dat

Originally constructed in approximately 1886 and approximately 1907, these three buildings were previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation indicates past owners of the 727-733 ½ 11th Avenue apartment buildings and property include: Thomas J. Dailey (1886), James A. Bailey (1887-1937), Edna Burdett (1937-date unknown), and Edwin Hom (1988). A Hom Exempt & Bom Non-Exempt Trust was established in the last decade (c.1989-2000) and is listed as currently retaining ownership of the 727-733 ½ 11th Avenue buildings and property. San Diego City Directories reveal past tenants of the 727 11th Avenue unit include: Mrs. S.M. Lange (1944/1945), vacant (1950), Ernest W. White (1955), Marion Conwell (1960), Morse L. Burkhart (1965), Max L. Burkhart (1969/1970), Pedro Espina (1975), vacant (1980), and Thomas Reinhold (1984). Past residents of the 729 11th Avenue unit include: H.B. Minnick (1944/1945), vacant (1950), Steph. Clayton (1955), Samuel L. Pike (1960), Mrs. Sara L. Pike (1965 & 1969/1970), Mrs. Ana M. Terminel (1975), Jose Ramirez (1980), and Vincent Alvarez. Past residents of the 731 11th Avenue unit include: William Risso (1944/1945), G.A.L. Sohn (1950), Margeret L. Dougherty (1955), Mrs. Helen Odell (1960), Frederic R. Ashenden (1965), Thomas L. Henderson (1969/1970), and Dolores C. Rodriguez (1975 & 1980, 1984).

(See DPR 523H, Continuation Sheet for more information)

B1	1	Additional	Resource	Attributes:	(List	attributes	and	codes)	
*B12.	References:	(partial list)							
Lia a	and Brandes,	Historic Si	te Invent	ory of Centr	e Cit	y East,	1988.		
San I	Diego City	Directories							


San Diego County Recorders Office

B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley, Scott A. Moomjian
Office of Marie Burke Lia

Date of Evaluation: October 2001

(This space reserved for official comments.)



State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION

CONTINUATION SHEET

Primary #	
HRI #/Trinomial_2138-0415-0000	

■ Continuation

□ Update

Page __3 of __3

Resource Identifier: (Assigned by recorder) ____727-733 ½ 12th Avenue, San Diego, CA 92101 Historic Name: Thomas J. Daley & James A. Bailey Apartment Buildings

P3a. Description (Continued):

Overall, the exterior of these two buildings appear to be in fair condition.

Believed to be identified as 733 ½ 11th Avenue, the front apartment building shown in the photograph on page one was originally constructed in approximately 1907, and was designed in the Italianate architectural style. It features a flat roof with wide eaves and brackets, triple windows featuring outer double-hung and center fixed portions, as well as individual and paired double-hung windows. Exterior building materials consist of composition shingles for the roof, and horizontal clapboard siding for the exterior walls. A hooded dentil band is present on the west and south elevations, and the entrances to the individual apartment units are located on the south elevation. The exterior paint is in poor condition, and overall, the exterior of the building appears to be in fair condition.

*B10. Significance (Continued):

Past residents of the 733 11th Avenue unit include: E.W. White (1944/1945 & 1950), Mrs. Elena Lopez (1955), Mary Gougara (1960), Foon Tom (1965), Mrs. Thelma Tyler (1970), Mrs. Nellie H. Lopez-Montijo (1975), Diaz Alvarez (1980), John McClendin (1984). 733 ½ 11th Avenue appeared in the 1965 San *Diego City Directory*, listing resident Chom Tom as the only tenant, and then re-appeared in 1980 listing units one through nine with unit seven vacant. 1984 listings also indicate eight units for 733 ½ 11th Avenue.

Historical research has determined that the two rear 727-733 11th Avenue buildings are neither historically nor architecturally significant. The two rear 727-733 11th Avenue buildings are not associated with any important events or individuals in terms of local, state, or national history. Moreover, the two buildings do not embody the distinctive characteristics of a type, period, or method of Folk Victorian construction, and the buildings do not represent the work of a master architect, master **craftsman**, master builder, nor that of an important, creative **individual**. They are not eligible for listing on the local registers.

Historical research has determined that the 733 ½ 11th Avenue building is not historically significant, as the building is not associated with any **important** events, or individuals in terms of local, state, or national history. The 733 ½ 11th Avenue building, however, does appear to be **architecturally** significant, at the local level, as a building which embodies the distinctive characteristics of a type, period, or method of Italianate construction. As the identity of the architect could not be ascertained, the front 733 ½ 11th Avenue building does not represent the work of a master architect, **master** craftsman, master builder, nor that of an important, creative individual.

DPR 523H (1/95)

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION

Other Identifier:

PRIMARY RECORD

P1.

rces Agency RECREATION	Primary # HRI #			
	Trinomial			
	NRHP Status Co	de_6Z_		
Other Listings_	Update of November 198	38 Centre	City East	Survey Documentation
Review Code_	Reviewer			Date
*Resource Name or #: (A	ssigned by recorder)	741 11 ^t	Avenue	

Location: ☐ Not for Publication ■ Unrestricted * a. County San Diego

and (P2b and P2c or P2d. Attach a Location Map as necessary.)


*b. USGS 7.5' Quad Point Loma Date T ____; R ___; ___¼ of ___¼ of Sec __; B.M. Address 741 11th Avenue City San Diego Zip 92101

d. UTM: (Give more than one for large or linear resources) Zone ___; ____ mE/

е. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 535-133-03-00, Lot C, Block 76

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1887, this two-story, multiple-family residence was designed in an Italianate architectural style. The main portion of the building has a general square shaped plan and features a flat roof with slight eave overhang, decorative roof lien brackets, a squared bay encompassing the length of both floors south of the centrally located porch area and front entrance. Fenestration consists of long, narrow double-hung sash windows in shelved frames placed symmetrically across the facades and paired between upper and lower floors. A single-story flat roof portion extension is present on the east elevation and according to past documentation is an original feature of the building (Lia/Brandes:1988). Exterior building materials consist of stucco for the exterior walls, and most likely composition shingles or rolls for the roof. Overall, this building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP3

*P4. Structure Diplect o Site District n Element of District a Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)_

*P6. Date Constructed/Age and Sources:

Historic

a Prehistoric n Both

1887

1988 Centre City East Historic site Inventory

*P7. Owner and Address:

Dickinson/Franklin LP c/o Lyon and Lvon Inc

4440 Pacific Highway San Diego, CA 92110

*P8. Recorded by (Name, affiliation, and Wendy L. Tinslev, address): Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

Date Recorded: March 2001 / Owner Information and Photo Updated June 2003 *P9.

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments:

NONE

Location Map

Sketch Map

Continuation Sheet

Building, Structure, and Object Record o Archaeological Record District Record Linear Resource Record o Milling Station Record o Rock Art Record o Artifact Record a Photograph Record □ Other (List):

State of California — The Resources Agency Primary DEPARTMENT OF PARKS AND RECREATION HRI#	#
BUILDING, STRUCTURE, AND OBJECT RE	COPD
	Status Code 6Z
*Resource Name or # (Assigned by recorder) 741 11 th Avenu	
D4 IP 4 ' NI 35 3 D 'I	
B2. Common Name: Casa De Amigos Sobrios_	
B3. Original Use: Residential B4. Present Use: Resi	
*B5. Architectural Style: Italianate	deritial
*B6. Construction History: (Construction date, alternations, and Constructed in 1887; no substantial alternations)	
*B7. Moved? No ☐ Yes ☐Unknown Date:	
*B8. Related Features:	onginal coodion.
DO A J S of Helesons b D. Helesons	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: Theme N/A_ Area <u>San Diego</u> Property Type Residential Applica	Period of Significance_1887_ ble Criteria N/A
(Discuss importance in terms of historical or architectural context as defined by the	
Originally constructed in 1887, this building w	as previously documented in November 1988 under
the supervision of the Office of Marie Lia and Dr. Ray	
owners of the 741 11th Avenue building include: Frank	
(1912), James F. & Alma McCleary (1917-1924),	
(c.1944/1945-c.1960s), and Myron & Andrea Lyon (19 established in the last decade (c.1989-2000) and is	
741 11 th Avenue building. San Diego City Director.	
building include: owner Hugh H. McCleary (1944/1945,	
1965 through 1980 San Diego City Directories indicat	
in the 741 11th Avenue apartment building; five units	
three vacancies in 1975, and ten units with no vaca	
Sobrios" hangs over the front entrance of the reside a residential treatment center or facilities for reco	
a replacificat creatment center of facilities for reco	verifig dieolofies of mexical of hispatic descent
Historical research has determined that the 741	
architecturally significant. The 741 11th Avenue build	
or individuals in terms of local, state, or nation	
distinctive characteristics of a type, period, or met of the architect and/or builder could not be ascer	
represent the work of a master architect, master craf	
creative individual. The building is not eligible for	
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list)	
Lia and Brandes, Historic Site Inventory of Centre C	
McAlester, Virginia and Lee, A Field Guide To Americ San Diego City Directories	an Houses, 1986.
San Diego County Recorders Office	(Sketch Map with north arrow required.)
	F STREET &
B13. Remarks:	700 100
	2 01 20 2
*B14. Evaluator: Wendy L. Tinslev,	@ # × ®
Office of Marie Burke Lia	
	(3) c J
(This space reserved for official comments.)	760
	PM 3539 4000 14 PAR. A
	PAR.
	" F - (1 3 3) - 4

G STREET

PRIMARY RECORD

of 3

Other Identifier:

P1.

D RECREATION	HRI #	
	Trinomial	
	NRHP Status Code_7	
Other Listings Upo	late of November 1988 Cent	tre City East Survey Documentation
Review Code	Reviewer	Date
*Resource Name or #: (Ass	signed by recorder) 760-770	11th Avenue & 1025-1055 F street
ublication II Uprostricted	* a County S	on Diago

*P2. Location: a Not for Publication
Unrestricted * a. County San Diego_

and (P2b and P2c or P2d. Attach a Location Map as necessary.)

Drimon, #


_; ___¼ of ___¼ of Sec___; ____ B.M. *b. USGS 7.5' Quad Point Loma Date Address _760-770 11th Avenue & 1025-1055 F Street San Diego____ Zip ____92101 C. City

d. UTM: (Give more than one for large or linear resources) Zone 11; ___mE/ ___mN

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): 0. APN: 535-132-07-00, Horton's Addition, Block 75, N 1/2 Lot K & All Lot L

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, andboundaries):

Originally constructed in 1932, this single-story building was designed in a One-Part Commercial Block style with a Neo-Classical architectural influence and features a flat roof. On the east and north facades a simple entablature is present featuring a cornice above a plain frieze with ten staggered rosettes, and an architrave above a series of pilasters with plain capitals modeled after the Doric style. Exterior building materials consist of Spanish roof tiles, stucco-on-lath for the exterior walls, and modern industrial style windows located between the pilasters. Entrances to the various businesses within are located on the east and north facades, and the majority of them are located on the north elevation on F Street. The south facade of the building is plain, featuring several smaller window sections, and signage on the roof line stating "BLOKHAUS." Overall, this residence appears to be in good condition.



and codes) HP6
*P4. Resources Present: Building
Structure D Object D Site D District D
Element of District D Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)
*P6. Date Constructed/Age and Sources:
I Historic
☐ Prehistoric ☐ Both
1932
1988 Centre City East Historic Site Inventory
*P7. Owner and Address: Graham Downes
275 Island Avenue
San Diego, CA 92101
*P8. Recorded by (Name, affiliation, and
address): Wendy L. Tinsley,
Scott A. Moomijian, Office of

Burke Lia, Attorney 427 C Street, Ste. 41

San Diego, CA 92101

*P9. Date Recorded: October 2001

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) __Historic Site Inventory of Centre

City East For Centre City Development Corporation

Attachments: DNONE Decation Map December Sketch Map Continuation Sheet Building, Structure, and Object Record a Archaeological Record n District Record Linear Resource Record a Milling Station Record n Rock Art Record Artifact Record n Photograph Record n Other (List):

State of California — The Resources Agency	Primary #
	HRI#
BUILDING, STRUCTURE, AND OBJEC	TRECORD
Page2 of3	*NRHP Status Code_7
*Resource Name or # (Assigned by recorder) 760-770 11	th Avenue & 1025-1055 F street, San Diego, CA 92101
B1. Historic Name: The Schiller Book Binder	v Building_
B2. Common Name: The BlokHaus Building	
B3. Original Use:Commercial	B4. Present Use: Commercial
*B5. Architectural Style: One-Part Commercial B	lock with a Neo-Classical influence
*B6. Construction History: (Construction date, alternation Originally constructed in 1932; No major	
*B7. Moved? No □Yes □Unknown Date:	Original Location:
*B8. Related Features:	
B9a. Architect: Scott Quintin b. Builder: Walter Trepte	
*B10. Significance: Theme C Area San Die Property Type Commercial	
(Discuss importance in <i>terms</i> of historical or architectural context as defin	
Originally constructed in 1932, this buil	lding was previously documented in November 1988 under
the supervision of the Office of Marie Lia and	Dr. Ray Brandes . Designed by Los Angeles Architect
	repte Construction Company in San Diego, this building
	055 F Street. Past documentation states this buildig
was constructed for the Pacific Library Bind	ing Company of Los Angeles, and upon completion of

the supervision of the Office of Marie Lia and Dr. Ray Brandes. Designed by Los Angeles Architect Scott Quintin, and constructed by the Walter Trepte Construction Company in San Diego, this building is identified as 760-770 11th Avenue and 1025-1055 F Street. Past documentation states this building was constructed for the Pacific Library Binding Company of Los Angeles, and upon completion of construction in 1932, the Schiller Book Bindery occupied the space until 1944/1945, when the building was sold to J.A. Pellezare (Lia/Brandes: 1988). Past owners of the building include: J.A Pellezare (c.1944-1949), Laurence & Alice Castleman (1949-1966), and the Common Laborers Local Union (c.1960s-at least 1988). San Diego City Directories reveal past occupants of 670 11th Avenue include: Schiller Book Bindery (1944/1945), Pacific Surplus Wholesale Company (1950), vacant (1955), no listing (1960, 1965, 1969/1970), and Cutter Laboratories Shipping & Receiving Department (1975, 1980, 1984). The 770 11th Avenue address does not appear in San Diego City Directories in the five year increments reviewed from 1944/1945 thru 1984. Past occupants of 1025 P Street include: Commercial Press (1944/1945, 1950), vacant (1955), Hod Carriers Building and Common Laborers Local Union No. 89 AF of L-CIO (1965), Laborers International Union of North America Local 89 (1969/1970), San Diego Plasma Center Bloodbank (1975, 1980, 1984), and the Bayer Corporation Plasma Center (1998/1999). The 1055 F Street address does not appear in San Diego City Directories in the five year increments reviewed from 1944/1945 thru 1984.

(See DPR 523H, Continuation Sheet for more information)

B11. Additional Resource Attributes: (List attributes and codes) _

*B12. References: (partial list)


(See DPR 523B, Continuation Sheet for more information)

B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley. Scott A. Moomijan,
Office of Marie Burke Lia

Date of Evaluation: October 2001

(This space reserved for official comments.)



State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION

Primary #______HRI #/Trinomial _____

CONTINUATION SHEET

	Continuation	Update
200	COLLCTITUGCETOLL	 opaace

Page3 of3	
Resource Identifier: (Assigned by recorder)	
760-770 11th Avenue & 1025-1055 F Street, San Diego, CA 9210	01
Historic Name: The Schiller Book Rindery Building	

*B10. Significance (Continued):

Ristorical research has determined that this building is not historically significant, as it is not a building which has been directly associated with any important events, or individuals in local, state, or national history. The building has, however, been determined to be architecturally significant, as a building which embodies the distinctive characteristics of a type, period of method of the One-Part Commercial Block style of construction with a Neo-classical architectural influence. Designed by Scott Quintin and constructed by the Walter Trepte Construction Company, the building does not represent the work of a master architect, master builder, nor that of an important, creative individual. While the property has been classified as a "One Part Commercial Block with a Neo-Classical influence," further study and/or research is necessary to determine whether the structure embodies the distinctive characteristics of this type, period or method of construction. Such a determination will dictate whether the resource is eligible for listing on the local register.

*B12. References (Continued):

Ching, Francis D.K., A Visual Dictionary of Architecture, 1997.

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

Longstreth, Richard, The Buildings of Main Street; A Guide To American Commercial Architecture, 1987.

McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office

PRIMARYRECORD

Primary #	
HRI #_2138-0416-0000	
Trinomial	
NPHP Status Code 592	

		Other Listings Upda	te of November 1988	8 Centre City East	Survey Documentation
		Review Code	Reviewer		Date
of	3	*Resource Name or #: (Assign	ned by recorder)	941 11 th Avenue	

Page P1. Other Identifier:

*P2 Location: a Not for Publication Unrestricted * a. County San Diego and (P2b and P2c or P2d. Attach a Location Map as necessary.)

Point Loma Date *b. USGS 7.5' Quad T ; R____; ___¼ of ___¼ of Sec ___; ____B.M. Address 941 11th Avenue City San Diego Zip 92101 Ċ.

d. UTM: (Give more than one for large or linear resources) Zone ___; ____ mE/ ___mN

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): ρ. APN: 534-333-02-00, Horton's Addition, Block 50, Lot C

*P3a. **Description** (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Constructed in 1907, the building shown in the photograph below is an addition to the original 1886 building which was first constructed on the property. Designed in an Italiante architectural style, this two-story building has a general rectangular shaped plan and features a flat roof with a wide eave overhang and decorative brackets. The west elevation features the main entrance, and has solid triangular brackets supporting the flat roof. The spaces between the brackets, in contrast with the horizontal clapboarding below, is laid with boards in a pattern at forty-five degree angles to the roof. The west elevation windows are tri-partite, featuring a center fixed portion flanked on both sides by a single, narrow double-hung window, and one double-hung window over the front entrance. The front entrance features an abbreviated hipped roof with supportive brackets. Overall, the exterior of the building appears to be in poor condition.



P3b.	Resource	Attributes:	(List	attributes
and c	codes) H	23		

Resources Present: I Building Structure D Object d Site d District D Element of District Dother (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

I Historic

Prehistoric d Both 1886/1907

1988 Centre City East Historic Site Inventory

*P7. Owner and Address

Rosa Family Trustof 1993 c/o **Teresa** Villa

2 Olympic Way, Coto de 92679

*P8. Recorded by (Name, affiliation, and Wendy L. Tinslev, address): Office of Marie Lia, Attorney at Law, 427 C Street. Ste. 416,

San Diego, CA 92101_

Date Recorded: April 2001 / Owner Information and Photo Updated June 2003

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: □ NONE a Location Map □ Sketch Map • Continuation Sheet ■ Building, Structure, and Object Record a Archaeological Record District Record Linear Resource Record District Record D Artifact Record D Photograph Record n Other (List):_

State of Colifornia The Becourses Agency	
State of California — The Resources Agency Primary #	8-0416-0000
BUILDING, STRUCTURE, AND OBJECT RECO	
	atus Code 5S2
Page 2 of 3 *NRHP Star- *Resource Name or # (Assigned by recorder) 941 11 th Avenue,	
B1. Historic Name: The Hamilton Apartments Building	
B2. Common Name: The California Apartments Buildi	
B3. Original Use: Religious (1886 portion); Residential (
B4. Present Use: Residential (apartments)	
*B5. Architectural Style: Italianate	Regulations.
*B6. Construction History: (Construction date, alternations, and date Constructed in 1907 as a front addition to the origin	of alterations) nal 1886 building; no substantial alterations
and/or modifications noted.	
*B7. Moved? No ☐ Yes ☐Unknown Date:	Original Location:
*B8. Related Features: B9a. Architect: Unknown b. Builder: John Campbell *B 10. Significance: Theme Architecture Area San Diego Property Type Residential Applicable C (Discuss importance in terms of historical or architectural context as defined by theme, page 1.5.	Period of Significance 1886/1907_ Criteria C_
Originally constructed in 1907, this building was the supervision of the Office of Marie Lia and Dr. Ray B. Presbyterian Church of San Diego purchased the 941 1 construction of a parsonage on the property in 1886. Past building include Reverand H.I. Stern (1886), and Dr. W.B. of Parsons College and Western Theological Seminary, regirst six months of his service in the building, thus of the First Presbyterian Church of San Diego sold the 941 to past documentation, "passed through various non-resadditional building portion was added." (Lia/Brandes: 1981) 11th Avenue property and building in 1907, then identified on-site as proprietors through approximately 1917, when Kern. The Kern's maintained ownership of the 941 11th Avenuer the ownership of the Kern's in 1930, the 941 11th Avenuer the ownership of the Kern's in 1930, the 941 11th Avenuer the ownership of the Kern's in 1930, the 941 11th Avenuer the Ownership of the Market the Ow	randes. Past documentation reveals the First 1th Avenue property in 1885 and completed to Church Pastors who held congregation in the Noble (c.1887-1888). Noble, an 1887 graduate portedly doubled church membership within the necessitating a larger congregational space. In 1th Avenue property in 1889, and according sident owners, until 1907, when probably an 1889. Sanford & Annie Darrah purchased the 941 and as the "Hamilton Apartments," and remained the building was purchased by Adam M. & Mary enue building and property until 1934. While evenue building began to be identified as the
*B12. References: (partial list)	
Lia and Brandes, Historic Site Inventory of Centre McAlester, Virginia & Lee, A Field Guide To American Diego City Directories San Diego County Recorders Office	ican Houses, 198S.
B13. Remarks:	(Sketch Map with north arrow required.) BROADWAY «
	** ** ** **
*B14. Evaluator: Wendy L. Tinsley,	1 4 4 4
Office of Marie Burke Lia	AVENUE SOA
Date of Evaluation: April 2001	
	(D) (O)
(This space reserved for official comments.)	1
	k , a _ a

E STREET

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET

Prima	ary #		
HRI#	Trinomial 2138-0416-0	0000	
	Continuation	□ Update	

Page3 of3	
Resource Identifier: (Assigned by recorder) 941 11th	Avenue, San Diego, CA 92101
Historic Name: The Hamilton Apartments	Ruilding

*B10. Significance (Continued):

Historical **research** has determined that the 941 11^{th} Avenue apartment building is not historically significant, as it *ie* not associated with any important events or individuals in terms of **local**, **state**, or national history. The building, however, does appear to be architecturally significant, at the local level, as a building which embodies the distinctive characteristics of a type, period, or method of Italianate construction. As the identity of the architect could not be ascertained the 941 11^{th} Avenue building does not represent the work of a master architect.

DPR 523H (1/95)

State of California — The Resources Agency **DEPARTMENT OF PARKS AND RECREATION**

PRIMARY RECORD


Primary #	
HRI #	
Trinomial	
NPHP Status Code 35	

	NRHP Status Code_3S						
	Oth	er Listings <u>Upd</u>	ate of November 19	88 Centre Cit	y East Survey	Documer	ntation
	Rev	riew Code	Reviewer		Date		
Page _ 1 _ of _ 2	*Resource Nar	ne or #: (Assign	ned by recorder)	509 12 th A	venue		
P1. Other Iden	tifier: Palm H	Hotel					
*P2. Location: a Not	for Publication I Unre	estricted *	a. County	San Died	10		
and (P2b and P2c or P2	2d. Attach a Location Ma	ap as necessar	y.)				
*b. USGS 7.5' Quad	Point Loma_	Date	; R	_;¼ of	¼ of Sec	_;	B.M
c. Address	509 12 th Avenue	City	San Diego	Zip	92101		
d. UTM: (Give	more than one for	r large or	linear resour	ces) Zone	;	mE/	ml

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 535-151-11-00, Lots D thru I 0.50 AC M/L In, Block 103

*P3a. **Description** (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1889 by owner Joseph V. Collins, this three-story building was originally called the New Bay View Hotel, and is today known as the Palm Hotel. Designed in an Italianate architectural style, this large, rectangular shaped building features a flat roof, a bracketed cornice with a plain frieze spanning around the perimeter of the building, and eight rectangular, angular and octagonal bay windows. Placement of the horizontally aligned, double-hung sash windows alternates between the protruding bays and recessed, flat exterior wall portions. Exterior building materials consist of brick and wood, as well as glass for the enclosed first floor veranda. According to the 1988 Lia/Brandes Team Survey, balustrades on the second and third floors have been removed since 1926, as well as the two French Second Empire roofed towers that were once located at the north and south ends of the building. The Palm Hotel is a significant example of a 19th Century Italianate Hotel in San Diego architectural history. Located on 12th Avenue, adjacent to the eastern side of the Trolley line, the building's exterior appears to be in good condition. eastern side of the Trolley line, the building's exterior appears to be in good condition.



P3b. Resource Attributes: (List attribute and codes) HP5	es.
*P4. Resources Present: Building	D
Structure Object Site District	D
Element of District Other (Isolates, etc.	;.)
P5b. Description of Photo: (View, dat	e,
accession #)	
*DC Data Constructed/Age and Courses	

P6. Date Constructed/Age and Sources:

Historic Prehistoric D Both 1889

1988 Centre City East Historic Site Inventory

*P7. Owner and Address

Chris LaFornara 4204 Hilldale Lane San Diego, CA 92116

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, of Marie Burke Attorney at Law, 427 C Street.

Ste. 416. San Diego, CA 92101

*P9. Date Recorded: February 2001 / Owner Information and Photo Updated June 2003

*P10. Type of Survey: (Describe)

P11, Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation


Attachments: a NONE a Location Map D Sketch Map Continuation Sheet • Building, Structure, and Object Record a Archaeological Record a District Record Linear Resource Record Milling Station Record Record Record a Artifact Record a Photograph Record a Other (List):

,	2 6
	Primary #HRI#
BUILDING, STRUCTURE, AND OBJECT	
	*NRHP Status Code 3S
0	Avenue, San Diego, CA 92101
B1. Historic Name: The New Bay view Hotel_	
B2. Common Name: Palm Hotel	7.
B3. Original Use: Commercial Hotel_ B4. Prese	ent Use: Commercial Hotel
*B5. Architectural Style: Italianate	
*B6. Construction History: (Construction date, alternation	
removed (date unknown), fire escapes added (date	oor balustrades removed (after 1926), two roofed towers
	Original Location:
*B8. Related Features:	Original Location
B9a. Architect: <u>Unknown</u> b. Builder: <u>Ur</u>	nknown_
*B10. Significance: Theme Architecture Area	
Property Type Commercial Hot (Discuss importance in terms of historical or architectural context as defined to the context of	el_ Applicable Criteria C_
	lding was previously documented in November 1988 under
	or. Ray Brandes. Previous documentation indicates past ilding include: John Dillingham (pre-1887), brothers
	bert Ballantyne & Duncan McPherson IV (1988). Past
	A.B. McKee (1944/1945), Mrs. Rose Hinburg restaurant
	ximately 1960 through 1984, the directories do not list
	, instead list the following: Palms Hotel & Apartments 1984). According to previous documentation, "the San
	to be one of the most solid and carefully constructed
buildings in the city" (Lia/Brandes:1988).	
Higtorical regearch has determined that	the Palm Hotel, located at 509 12th Avenue is not
	ot associated with any important events or individuals
	story. The building, however, does appear to be
	the distinctive characteristics of a type, period, or
method of Italianate construction. As the id building does not represent the work of a mast	entity of the architect could not be ascertained, the
bulluting does not represent the work of a mast	er architect or crartsman.
B11. Additional Resource Attributes: (List attributes and code	s)
*B12. References: (partial list)	
Lia and Brandes, Historic Site Inventory of Ce.	
McAlester, Virginia and Lee, A Field Guide To San Diego City Directories	American Houses, 1986.
San Diego County Recorders Office	
	(Sketch Map with north arrow required.)
B13. Remarks:	MARKET
	I MAKKET
*B14. Evaluator: Wendy L. Tinsley,	~ [* * * *
Office of Marie Burke Lia	
Date of Evaluation: February 2001	
	(15D) · · ·
	₩ 0°' 0° L
	AVENUE STREET
(This space reserved for official comments.)	(5) 0 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1


\$

ISLAND


ŧ



Original Bay View Hotel (built 1869), 1872



Bay View Hotel, 1889



PRIMARY RECORD

d.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary #		
PRIMARY RECORD	Trinomial		
Other Listings ReviewCode	Reviewer Date		
Page1 of _2 *Resource Name or #: (Assign	ed by recorder) 999 12 th Avenue y Store		
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County San Diego		
	T; R;¼ of% of Sec; B.M.		
	Diecro Zip92101		
d. UTM: (Give more than one for large or e Other Locational Data (e.g. parcel # directions to re	linear resources) Zone;mE/mN		

Other Locational Data (e.g., parcel #, directions to Block 51, Lots A, B, K & L; Map: D Book 13, page 522; APN: 534-341-10 *P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This one-story, commercial building was designed in an Art Moderne (streamline modernistic) architectural style and appears to have been constructed in 1925. Square in shape, the building has served a restaurant use (along the northwest elevation) and market use (along the southwest elevation) since at least 1940. The building features a flat roof with stepped cornice, broken slightly along the west elevation by a small parapet and projecting tower, identifying the building as the "Popular Market." Below the roofline, there is a projecting ledge which, along the west elevation, includes "Market" signage. A single entrance to the market, flanked by in-filled bays with pilasters and transom windows, exists along the west elevation, while a single, main entrance to the restaurant and fixed storefront windows exists along the northwest elevation. Another entrance to the restaurant is located along the northeast elevation. Decorative coping detail exists along the base of the west and northwest elevations. Overall, the building appears to be in good condition.

P3b. Resource Attributes: (List attributes and codes)

	*P4. Resources Present: I Building
	n Structure □ Object D Site □ District a
	Element of District D Other (Isolates, etc.)
	P5b. Description of Photo: (View, date,
The second	accession #)

P6. Date Constructed/Age and Sources: Historic

□ Prehistoric D Both c.1925

Sanborn Fire Insurance Maps San Diego City Directories

*P7. Owner and Address: City of San Diego Redevelopment Agency

202 C Street San Diecro, CA 92101

P8. Recorded by (Name, affiliation, and address): Office of Marie Burke Lia, 427 C Street, Suite 416, San Diego, California 92101

*P9. Date Recorded: May 2004

*P10. Type of Survey: (Describe) Intensive

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Resources Inventory Update Of The East Village Area For Centre City Development Corporation Attachments: □NONE DLocation Map □Sketch Map □Continuation Sheet ■Building, Structure, and Object Record

□Archaeological Record □District Record □Linear Resource Record □Milling Station Record □Rock Art Record

□Artifact Record □Photograph Record □ Other (List):

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary #
BUILDING, STRUCTURE, AND OBJECT Page 2 of 2 *Resource Name or # (Assigned by recorder) 999 12**	T RECORD *NRHP Status Code
B1. Historic Name: Ephraim Harris Grocery	/ Store
B2. Common Name: Popular Market	
B3. Original Use: Commercial B4. Present Use	e: Commercial mline Modernistic)
*B6. Construction History: (Construction date, alternatio	
* * * * * * * * * * * * * * * * * * * *	front windows in-filled (date unknown).
*B7. Moved? ■No □Yes □Unknown Date: *B8. Related Features:	Original Location:
None	
B9a. Architect: Unknown b. Builder: Un	
	Area <u>East Village/Centre City</u>
	ty Type Commercial Applicable Criteria C
(Discuss importance in terms of historical of geographic scope. Also address integrity.)	or architectural context as defined by theme, period, and
1906, or 1921 Sanborn Fire Insurance Maps. According to San Die by Ephraim Harris. 1940 and 1956 Sanborn Maps indicate the proportion of the building and a "Rest" or restaurant at the northwe	nercial building was constructed c. 1925. The building is not depicted on 1888, ego City Directories, the building is first listed in 1926 as a grocery store operated esence of the building as a "Market" (955 12* Avenue) along the southwestern stern portion of the building (967 12th Avenue). Subsequent occupants of the 5); Oscar's Drive-In Restaurant (1950); The Coffee Shop (1955); and The Twelfth market/restaurant use.
important events or individuals in terms of local, state, or national h	e building is architecturally significant. The building is not associated with any history. However, the building embodies the distinctive characteristics of a type, 920s. The building does not represent the work of a master architect, builder,
B11. Additional Resource Attributes: (List attributes	and codes)
*B12. References: (partial list)	and codes)
City of San Diego, Building Department Permit Reco	ords. (Sketch Map with north arrow required.)
City of San Diego, Water & Sewer Records. Longstreth, Richard, The Buildings Of Main Street,	
McAlester, Virginia & Lee, A Field Guide To Americ 2000.	an Houses,
Sanborn Fire Insurance Maps, 1888, 1906, 1921, 194 San Diego City and County Directories.	0, 1956. MAL
B13. Remarks:	760-214-06 10 -52
*B14. Evaluator: Office of Marie Burke Li	
Date of Evaluation: May 2004	
	(12TH AVE)
(This space reserved for official comments.)	E 3 0.92 AC 7
	$\begin{bmatrix} 1 \\ 1 \end{bmatrix}$
	1: 100°
	i E M

PRIMARY RECORD

c. d.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary #		
PRIMARY RECORD	Trinomial		
Other Listings _			
Review Code	Reviewer Date		
	igned by recorder) 1015-1025 12 th Avenue Motor Building		
	a. County San Diego		
and (P2b and P2c or P2d. Attach a Location Map as necess			
	San Diego Zip 92101		
d. UTM: (Give more than one for large of	or linear resources) Zone ;mE/mN		


*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

Block 28, Lots D-F, Map DB13, PG 522, APN: 534-206-03

This two-story, commercial building was designed in an Art Moderne (Streamline Modernistic) architectural style and was constructed in 1937. When originally constructed, it served as an automobile sales and service building. Seton a reinforced concrete slab with concrete flooring, the building consists of a partial steel frame and a steel truss roof system. Clay tile is visible at the rear of the building. Rectangular in shape, the building features a flat roof. At the southwest corner of the building, there is a elliptical tower which rises above the roofline. This tower features bands of large and small windows on the first and second floors. The exterior of the building consists of stucco. On both the first and second floors, there are bands of fixed ribbon windows which extend across the west and south elevations. Many of the windows appear to be boarded. At the first floor, along the west and south elevations, there are entrances with circular awnings above. Overall, the building appears to be in fair condition.

P3b. Resource Attributes: (List attributes and codes)



Resources Present: I Building d Structure d Object d Site d District D Element of District Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

d Prehistoric d Both 1937

Water and Sewer Records San Diego City Directories_

*P7. Owner and Address: Salvation Army 1335 Broadway San Diego, CA 92101 P8. Recorded by (Name, affiliation, and address): Office of Marie Burke

Lia, 427 C Street, Suite 416, San Diego, California 92101

*P9. Date Recorded: November 2004

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Resources Inventory Update Of The East Village Area For Centre City Development Corporation

Attachments:

NONE | Location Map dSketch Map | Continuation Sheet | Building, Structure, and Object Record dArchaeological Record

District Record

Linear Resource Record

Milling Station Record

dRock Art Record dArtifact Record □ Photograph Record □ Other (List):

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	
B1. Historic Name: Ford Apartments/Ford	*NRHP Status Code 5S2 025 12 th Avenue Motor Building
*B5. Architectural Style: Art Moderne (Stream	B4. Present Use: Commercial mlined Modernistic)
	as and alterations include conversion of building (1966); re-roofing (1967); new entrance (1974);
*B7. Moved? No UYes Unknown Date:*B8. Related Features: None	Original Location:
B9a. Architect: <u>Unknown</u> b. Builder:	
Period of Significance 1937 (Discuss importance in terms of historical geographic scope. Also address integrity.) Historical research indicates that this building was construed in the was used as the "Ford Apartments" beginning in 1938 through 1 the building as a two-story, commercial building used for automothe second floor with automotive use on the first floor. Beginning	Property Type Commercial Applicable Criteria
was built to house City Ford and remained a Ford car dealership le constructed as a "companion" structure to the Ford Building, de	e Organisation (SOHO), which could not be independently verified, the building building until the early 1950s. In addition, it is believed that the building was esigned by architect Walter Dorwin Teague, Sr., located in Balboa Park, in 1935 was constructed (1937) in a very similar Streamline Moderne style, in very close
B11. Additional Resource Attributes: (List attributes an	nd codes)
*B12. References: (partial list) City of San Diego, Building Department Permit Re City of San Diego, Water & Sewer Records. Coons, Bruce, Electronic Mail To Diane Kane, June Longstreth, Richard, The Buildings Of Main Street McAlester, Virginia & Lee, A Field Guide To Amer 2000. Sanborn Fire Insurance Maps, 1887, 1888, 1906, 1956. San Diego City and County Directories.	e 4, 2004. et, 1987. rican Houses,
B13. Remarks: *B14. Evaluator: _ Office of Marie Burke Lia Date of Evaluation: _ November 2004	
(This space reserved for official comments.	COO H
	2 1 0 2 2

BROADWAY

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION

CONTINUATION SHEET	Primary # HRI # Trinomial
Page 3 of 3 *Resource Name or # (As	signed by recorder)1015-1025 12th Avenue
*Recorded by Office of Marie Bur	ke LiaDate November 2004
☑ Continuation D Update	

*B10. Significance:

Historical research has determined that the 1015-1025 12th Avenue building is architecturally significant. The building is not associated with any important events or individuals in terms of local, state, or national history. The building, however, embodies the distinctive characteristics of a type, period, and method of Art Moderne (Streamline Modernistic) construction. The building does not represent the work of a master architect, builder, craftsman, or important, creative individual.

State of California — The Resources Agency

Page 1 of

						9	-
DEPART	MENT	OF PA	ARKS	AND	RECI	REAT	ION
PRIM	ARY	RE	COI	RD			

RECREATION	HRI #	/ π			_
	Trinon NRHP	nial <u>.</u> Status Code	5S2		_
Other Li	stings Update of Nov	rember 1988	Centre City East	Survey Documentat	ion
Review	CodeRe	viewer		Date	
*Resource Name o	r#: (Assigned by red	order) 11	54 12 th Avenu	e	
				*P2.	lozbi

P1. Other Identifier:

□ Not for Publication • Unrestricted * a. County San Diego and (P2b and P2c or P2d. Attach a Location Map as necessary.)

___T *b. USGS 7.5' Quad Point Loma _____ Date ___ Address 1154 12th Avenue City San Dieao Zip 92101

c. UTM: (Give more than one for large or linear resources) Zone ___; ____ mE/ ___mN d.

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 534-193-09-00, Horton's addition, Block 24, Lot K

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This two-story, Colonial Revival influenced building is believed to serve as a single-family residence. Rectangular in shape, the building features a medium pitched gabled on hipped roof with boxed cornices, dormer, plain frieze, shiplap siding with cornerboards, double-hung windows with pendents over corner bay windows, and decorations over the lugsills. The house is symmetrical with a recessed center entrance and a two tier porch at the front. The upper tier features four circular wood column supports and has an overhanging pedimented gable at the top, with fishscale shingles in the gable end. Overall, the residence appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP2; possibly HP3_

Resources Present: • Building a Structure

Object

Site a District Element of District a Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

□ Prehistoric □ Both 1895

1988 Centre city East Historic Site Inventory

*P7. Owner and Address

Thomas J. Erpelding 1154 12th Avenue

San Diego, Ca 92101_

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Scott A. Moomjian, Office of Marie Burke Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: October 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: a NONE Ducation Map n Sketch Map Continuation Sheet • Building, Structure, and Object Record a Archaeological Record District Record n Linear Resource Record Milling Station Record D Rock Art Record a Artifact Record Photograph Record n Other (List):

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary #
BUILDING, STRUCTURE, AND OB	JECT RECORD
Page 2 of 2	*NRHP Status Code_ 5S2
*Resource Name or # (Assigned by recorder) 1154	12 th Avenue. San Diego, CA 92101
B1. Historic Name: Otto and Blanche Fox	Residence

*B5. Architectural Style: Colonial Revival

*B6. Construction History: (Construction date, alternations, and date of alterations) Constructed in 1895; fire escape installed at rear of building (date unknown); no substantial alterations and/or modifications noted.

B4. Present Use: Residential

*B7. Moved? No ☐ Yes ☐Unknown Date: Original Location:

*B8. Related Features:

Common Name:

B3. Original Use: Residential

B9a. Architect: Unknown b. Builder: <u>Unknown</u>

AArreaa San Diego

Period of Significance 1895 Applicable Criteria C_

*B 10. Significance: Theme Architecture Property Type Residential

(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

The property on which 1154 12th Avenue residence ia located was acquired by Otto and Blanche Fox in 1895. The couple completed construction on the residence during this year. Fox, the proprietor of the American Tea Company, and his wife, resided at this address through 1897. In 1902, Archibald Taylor, a wine and liquor merchant, and his wife, Edna Lowell Taylor, purchased the home. The property remained in the Taylor family until 1939. Various family members resided in the residence over this period. In 1949, the Musicians Club of San Diego purchased this property for their Union, local number 325. In 1966, James Britton, an architectural critic for the San Diego Union and his wife, Elizabeth, purchased the property.

Historical research has determined that the 12th Avenue residence is not historically significant, as the building is not associated with any important events or individuals in terms of local, state, or national history. The residence however, is considered architecturally significant, at the local level, as a property which embodies the distinctive characteristics of a type, period. and method of Colonial Revival construction. As the identity of the architect could not be ascertained, the building does not represent the work of a master architect or craftsman. In addition, it does not represent the work of an important, creative individual.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia and Lee, A Field Guide To American Houses, 1986.


San Diego City Directories

San Diego County Recorders Office

B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley, Scott A. Moomijan Office of Marie Burke Lia_ Date of Evaluation: October 2001

(This space reserved for official comments.)



PRIMARY RECORD

Primary #	
HRI #	
Trinomial	
NRHP Status Code 7	

Paview Code	Paviower				Date
Other Listings	Update of November	1988	Centre	City East	Survey Documentation

Page	1 o	2	*Resource Name or #: (Assigned by recorder)	1166	12 th	Avenue_	 _
P1.	Other	Identifier	:				_

*P2 a. County San Diego Location: a Not for Publication Unrestricted *

and (P2b and P2c or P2d. Attach a Location Map as necessary.) T___; R___; ¼ of __¼ of Sec __; ___B.M. *b. USGS 7.5' Quad Point Loma____Date__

Address 1166 12th Avenue City San Diego_____Zip__92101 d. UTM: (Give more than one for large or linear resources) Zone ___; ____ mE/ ___mN

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): e. APN: 534-193-10-00, Horton's Addition, Block 29, Lot L

Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1925, the design of this three-story apartment building appears to have been influenced by the French Eclectic style. Typical to the French Eclectic style, the 1166 12th Avenue building features brick wall cladding, a symmetrical facade with a centered entry, and formal facade detailing, including an elongated, arched pediment over the recessed front entrance, one set of double french doors on each floor of the east, facing elevation, large, ornamental brackets around the buildings facade, and lastly, a flat roof with a faux mansard style roof section with a boxed cornice on the west and north elevations. Windows on the east facade are three-over-one paired, double-hung sash in a wood frame with brick sills, and the front entry doors feature an upper transom. Overall, the exterior of the building appears to be in excellent condition.



P3b. Resource Attributes: (List attributes and codes) HP3

*P4. Resources Present: I Building d Structure d Object d Site d District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

1925

d Prehistoric

d Both

1988 Centre City East Historic Site Inventory

*P7. Owner and Address Gustav & Elizabeth Onlig

2802 Hartford Court San Diego, CA 92117

*P8, Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Scott A. Moomiian, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA

92101

Date Recorded: October 2001

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: a NONE - Location Map D Sketch Map - Continuation Sheet Building, Structure, and Object Record D Archaeological Record D Linear Resource Record a Milling Station Record n Rock Art Record n Artifact Record D Photograph Record D Other (List):_


State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI#
BUILDING, STRUCTURE, AND OBJE	CT RECORD
Page 2 of 2	*NRHP Status Code_7
	2 th Avenue, San Diego, CA 92101
	Building
B2. Common Name:	
B3. Original Use: Residential (apartments)	B4. Present Use: Residential (apartments)
*B5. Architectural Style: French Eclectic	
	ons, and date of alterations) and third-floor balconies were fire escape ladders were no other alterations/modifications known or noted.
*B7. Moved? No D Yes DUnknown Date:	Original Location:
*B8. Related Features:	
Property Type Residential	San Diego Period of Significance 1925 Applicable Criteria C fined by theme, period, and geographic scope. Also address integrity.)
1988 under the supervision of the Office of indicates past owners of the 1166 12 th Aven (1925), Ella B. & Horace Humphreys (1925-1	1925, this building was previously documented in November Marie Lia and Dr. Ray Brandes. Previous documentation we property and building include: Alexander Schreibner 1948, Arthur L. Herzog (1948-1961). The building is who have maintained ownership of the building from at re City East survey.
significant, as the building is not associated local, state, or national history. As the is building does not represent the work of a master the property has been classified as a *Frence determine whether the structure embodies the	at the 1166 12 th Avenue building is not historically ed with any important events or individuals in terms of dentity of the architect could not be ascertained, the er, nor that of an important, creative individual. While ch Eclectic, further study or research is necessary to e distinctive characteristics of this type, period or ill dictate whether the resource is eligible for listing
B11. Additional Resource Attributes: (List attributes and coo	des)
*B12. References: (partial list)	
Lia and Brandes, Historic Site Inventory	y of Centre City East , 1988.
McAlester, Virginia & Lee, A Field Guide	
San Diego City Directories	

B13. Remarks:

San Diego County Recorders Office

*B14. Evaluator: Wendy L. Tinsley, Scott A. Moomjian, Office of Marie Burke Lia Date of Evaluation: October 2001

(This space reserved for official comments.)



DD	IMA	DV	DE	$\boldsymbol{\cap}$	
FK	IIVIA	RI	RE	Lυ	עאי

and boundaries):

State of California — The Resources Agency	Primary #			
DEPARTMENT OF PARKS AND RECREATION	HRI #2138-0423-0000			
PRIMARY RECORD Trinomial				
	NRHP Status Code_6Z			
Other Listings U	odate of May 1989 Bayside Survey Documentation			
Review Code	Reviewer Date			
P1. Other Identifier:				
*P2. Location: ☐ Not for Publication ■ Unrestricted *	a. County San Diego			
and (P2b and P2c or P2d. Attach a Location Map as necessary	• · · · · · · · · · · · · · · · · · · ·			
*b. USGS 7.5' Quad Point LomaDate	T; R;¼ of¼ of Sec; B.M.			
c. Address 341-343 13 th Avenue	City <u>San Diego</u> Zip <u>92101</u>			
d. UTM: (Give more than one for large or	r linear resources) Zone 11;mE/mN			
e. Other Locational Data (e.g., parcel #, directions to re APN: 535-372-04-00, Horton's Addition				
*P3a. Description (Describe resource and its major eleme	nts. Include design, materials, condition, alterations, size, setting,			

Originally constructed in approximately 1906-1907, this building is identified as 341-343 13th Avenue. Designed in a vernacular Polk Victorian architectural style, this residence consists of onestory of livable space with a basement built below the street level on the rear portion of the building. It has a general rectangular shaped plan, and features a moderately pitched, front gabled roof with an unenclosed eave overhang, exposed rafter tails, and supportive knee braces. Exterior building materials consist of clapboard siding for the exterior walls, and most likely, composition shingles for the roof.

(See DPR 523H, Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes HP3 and codes)

Resources Present: Building a *P4. Structure Diplect a Site a District a Element of District a Other (Isolates, etc.) Description of Photo: (View, date, accession #)_

*P6. Date Constructed/Age and Sources:

Historic

n Prehistoric

n Both

c.1906-1907

1939 Bayside Historic Site Inventory

*P7. Owner and Address:

Stonecreek Homes, Inc. 3555 Rosecrans #211

San Diego CA 92110

*P8. Recorded by (Name, affiliation, and Wendy L. Tinsley, address): Office of Marie Burke Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

AC10 1025			The state of the s	
*P9.	Date Recorded	February	2001	Updated April 200-

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Bavside For Centre City Development Corporation

Attachments: □NONE D Location Map D Sketch Map ■Continuation Sheet ■ Building, Structure, and Object Record D Archaeological Record D District Record n Linear Resource Record n Milling Station Record n Rock Art Record a Artifact Record n Photograph Record n Other (List):_

State of California — The Resources	Agency
DEPARTMENT OF PARKS AND REC	REATION

Primary :	#	
HRI#	2138-0249-0000	

BIIII DING	STRUCTURE.		OR IFCT	RECORD
JUILDING.	SINUCIUNE.	AIND	ODJECI	NEGOND

Page 2 of 3 *NRHP Status Code 6Z	
*Resource Name or # (Assigned by recorder) 341-343 13 th Avenue, San Diego, CA 92101	
B1. Historic Name: Mexican Presbyterian Church/Mexican & Spanish Presbyterian Church	
B2. Common Name: 341-343.13 th Avenue	
B3. Original Use: Religious B4. Present Use: Residential (Multiple-Family)	
*B5. Architectural Style: vernacular Folk Victorian	
*B6. Construction History: (Construction date, alternations, and date of alterations) Constructed in c.1906-1907; signaled by the installation of two front entry doors on street elevation, the building was divided into two residential units, c.1940.	facing
*B7. Moved? No	
*B8. Related Features: B9a. Architect: Unknown b. Builder: Unknown *B10. Significance: Theme N/A Arrea San Diego Period of Significance 1906-1907_ Property Type Religious/Residential Applicable Criteria N/A_ (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)	
Originally constructed in c.1906-1907, this building was previously documented in May 1989	

Originally constructed in c.1906-1907, this building was previously documented in May 1989 under the supervision of the Office of Marie Ha and Dr. Ray Brandes. Previous documentation reveals past owners of the 341-343 13th Avenue property and building include: Mary D. Howard (pre-1906), First Presbyterian Church (1906), owner/occupant the Mexican Presbyterian Church (1907-1926), owner/occupant the Mexican Presbyterian Church Spanish Presbyterian Church; Rev. Jose Rodriguez (1927-1939). After the Presbyterian Church sold the property in 1939, the building was split into two units for residential rental purposes. San Diego City Directories reveal past occupants of the 341 13th Avenue unit include: Felix Gonzales (1950), Mrs. Lillian Cooley (1955), Mrs. Anita Gonzales (1960), Vacant (1965), Juslova Vertiz Jr. (1969/1970), Mrs. Natividad Cardenas (1975), and Pedro Meraz (1980). Past occupants of the 343 13th Avenue unit include: Reyes Chavez (1950), no listing (1955), Mrs. Dolores G. Mora (1960), Mrs. Carmen C. Vertiz (1965, 1969/1970), and Ruben Ortega (1975, 1980). The 341-343 13th Street units did not appear in 1944/1945 San Diego City Directories. A 1921 Sanborn Fire Insurance Map indicates that, at that time, the building was most likely identified as 349 13th Avenue, due to the fact that the 349 13th Avenue building appears as the "Mexican Presbyterian Church" on the map (see below).

(See DPR 523H, Continuation Sheet for more information)

B11. Additional Resource Attributes: (List attributes and codes)_____

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Bayside, 1989. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories


San Diego County Recorders Office

B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley,
Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



CONTINUATION SHEET

Primary #	
HRI #/Trinomial 2138-0249-0000	

Continuation

Update

Page __3__ of __3__

Resource Identifier: (Assigned by recorder) 341-343 13th Avenue, San Diego, CA 92101_


Historic Name: Mexican Presbyterian Church/Mexican & Spanish Presbyterian Church

P3a. Description (Continued):

The two west elevation windows are double-hung sash, and feature gothic inspired arched, window frames. A similarly shaped air vent is located beneath the front gable end of the roof line. A front porch area is present on the street facing elevation, and features an ornamental, center gabled roof of moderate pitch, also with an unenclosed eave and exposed rafter tails. The porch roof <code>is</code> supported by post and lintel construction. Two front doors are present on the street facing elevation; one for each unit. Overall, the <code>building's</code> exterior is in poor condition.

*B10. Significance (Continued):

Although the 341-343 13th Avenue building is listed as a 3S on the California State Office of Historic Preservation Historic Property Data File for San Diego County, Historical research has determined that the 341-343 13th Avenue building is neither historically nor architecturally significant. The 341-343 13th Avenue building is not associated with any important events or individuals in terms of local, state, or national history. Moreover, it does not embody the distinctive characteristics of a type, period, or method of Folk Victorian construction, and does not represent the work of a master architect or craftsman.



DPR 523H (1/95)

St DI


P

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary # HRI #
PRIMARY RECORD	Trinomial
Other Listings	
	Reviewer Date
Page1 of3 *Resource Name or #:	(Assigned by recorder) Simon Padilla Residence
P1. Other Identifier:	-
*P2. Location: a Not for Publication Unrestricted	* a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as nec *b. USGS 7.5' Quad <u>Point Loma</u> Date	essary.) T•R;% of¼ or Sec;B.M.
	City <u>San Diego</u> Zip <u>92101</u>
	ources) Zone; mE/ mN
e. Other Locational Data (e.g., parcel #, directions Horton's Addition, Block 130	

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This two-story residence is designed in a Victorian style. It has a low-pitched hipped with composition tiles, and a slight eave overhang without brackets. a porch with upper decorative spindle ornamentation and brackets between slender wood columns. The porch front appears modified with a quasi-chinese wood Chippendale. Windows are double hung and sliding is horizontal clapboard. This residence may been converted into a duplex sometime during the mid-1940s, as a door located at the southwest corner of the residence appears to have been added. The residence is in poor condition.

*P3b. Resource Attributes: (List attributes and codes) Resources Present:



d District d Element of District B Other

P5b. Description of Photo: (View, date,

*P6. Date Constructed/Age and Sources:

d Both

San Diego City Directories

*P8. Recorded by (Name, affiliation, and

Office of Marie Burke Lia 427 C Street, Suite 416____

*P9.	Date Recorded:	June	1998	Updated	April 2004

Intensive Survey For Potential Area Redevelopment *P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Evaluation of Historical Resources Within Project Study Area For Proposed Sports Entertainment District_

Attachments: dNONE Location Map dSketch Map Continuation Sheet Building, Structure, and Object Record □Archaeological Record □District Record dLinear Resource Record □Milling Station Record □Rock Art Record □ Artifact Record dphotograph Record d Other (List):

State of California — The Resources Agency Primary #
DEPARTMENT OF PARKS AND RECREATION HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD Page 2 of 3 *NRHP Status Code 6Z
*Resource Name or # (Assigned by recorder) Simon Padilla Residence
B1. Historic Name: Simon Padilla Residence
B2. Common Name: Residence
B3. Original Use: Residential B4. Present Use: Residential
•B5. Architectural Style:Victorian
*B6. Construction History: (Construction date, alternations, and date of alterations)
Duplex Conversion, Entrance Added (Date Unknown), Porch alteration (Date Unknown)
*B7. Moved? fefNo Yes Unknown Date: Original Location:
*B8. Related Features:
Metal Fence
B9a. Architect:Unknown b. Builder:Unknown
*B10. Significance: Theme <u>Architecture</u> Area <u>San Diego</u>
Period of Significance <u>c.1918</u> Property Type <u>Residential</u> Applicable Criteria <u>C</u> (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)
The earliest tenant determined to have been associated with this building was Simo
C. Padilla and his wife Isabella who resided here from 1919-1926. The residence wa
listed at 355 13 th Avenue. Simon Padilla was employed by the Benson Lumber Company. I
1927 Mrs. Pola Castro resided at the home. One year later, J.J. Castro lived there
After 1931, the residence accommodated a number of different tenants: Manuel Blanco (1931
1932), Mrs. B.E. Wismer (1933), Salvador Mangusing (1937), Emelio Gomez (1938), Francisc
Igno (1939), Richard Vanos (1940), Mrs. Catalina Monteyo (1941), and H.M. McClaren (1942)
After 1947, the San Diego City Directory lists two addresses for the same building indicating the likely conversion of the residence into a duplex. The residence, after
1947, still had a rather high turnover rate among tenants : Claud Optiz (353 13 th) and Davi
Gonzales (355 13^{th}) in 1947-1948, Fred Chavez (353 13^{th}) and Adelina Cameron (355 13^{th}) i
B11. Additional Resource Attributes: (List attributes and codes)
*B12. References:
McAlester, Virginia & Lee. A Field Guide To American Houses.
New York: Alfred A. Knopf, 1986.
Sanborn Fire Insurance Maps, 1888-1956.
San Diego City Directories
San Diego Union Index 535-371 535-372 E
B13. Remarks:
2 9 4 16
3 8 5
*B14. Evaluator: 9 6 7 8 9 10
Date of Evaluation: K 5T-
E3E 278 E2E 278
(This space reserved for official comments.)
1 1 1 1 1 1 1 1 1 1

*Recorded by Office of Marie Burke Lia

DEPARTM	ENTOFPARKSANDRECREATION	ON
CONTINU	ATION SHEET	Primary #
		HRI #
		Trinomial
Page 3 of	f 3 *Resource Name or # (Assigned by re	ecorder) Simon Padilla Residence

Date June 1998

■ Continuation

□ Update

*B10. Significance: (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

1950 and 1950-1954 **respectively**, Minnie and Blanche Millan (353 $13^{\rm th}$) in 1952 and 1953-1954 respectively, Blanche Millan (353 $13^{\rm th}$) and **Mrs. Eutemia Carmelo** (355 $13^{\rm th}$) from 1955-1957 respectively, and Mrs. Blanche T. **Millan** (355 $13^{\rm th}$) from 1958-1960, and Lorenza **Vidal** (353 $13^{\rm th}$) from 1959-1960.


The building has been determined to be neither historically nor architecturally significant. The building has not been associated with any significant events or individuals in San Diego, nor does it display any unique or innovative architectural characteristics.

	of California — The Resources Aç RTMENT OF PARKS AND RECRE					
PRIMARY RECORD		Trinomial				
		Other Listings Review Code	Reviewer	Dat	te	
Page	1 of _2 *Resour	ce Name or #: (Assig	ned by recorder) 416	13 th Street		
P1.	Other Identifier: Carme	en Savalez Reside	ence			
*P2.	Location: Not for Publication	n 📕 Unrestricted *	a. County S	San Diego	0 = 1001	
*b. U	2b and P2c or P2d. Attach a Lo SGS 7.5' Quad Point Lom	Date				
C.	Address 416 13th Stree					
d.	UTM: (Give more than o	one for large or	linear resources	s) Zone;	mE/	_mN
e.	Other Locational Data (e.g., pa				-156-06	

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This one and one-half story, rectangular-shaped single-family residence was designed in a Folk Victorian architectural style and was constructed sometime c. 1888-1906. When originally built, the residence featured a full-length porch across its east elevation. Sometime between 1921-1940, this porch was extended across the length of the south elevation. The building features a high-pitched, front-gabled roof with slight eave overhang and composition shingle roofing material. The exterior consists of horizontal clapobard. The porch features a deck roof with eave overhang along the south elevation. It is supported by slender wood columns with a picket balustrade. It is in poor condition. Fenestration includes double-hung with dormers along the south elevation. Overall, the building appears to be in poor condition.

P3b. Resource Attributes: (List attributes and codes)



*P4. **Resources Present:** I Building P Structure O Object P Site P District Element of District O Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

n Prehistoric P Both c.1888-1906

Sanborn Fire Insurance Maps

*P7. Owner and Address:

Jesus M. Villa & Mary Croce_ Croce Family Trust 2/2/02 416 13th Street_

San Diego, CA 92101_

*P8. Recorded by (Name, affiliation, and address): Office of Marie Burke, Lia, 427 C Street, Suite 416, San Diego, California 92101_ *P9. Date Recorded: May 2004_

*P10. Type of Survey: (Describe)

BUILDING, STRUCTURE, AND OBJECT RECO	ORD
Tage _2 or 2 // Assigned by secondary 43.5 42th Care of	atus Code 6Z
*Resource Name or # (Assigned by recorder) 416 13 th Street_	
B1. Historic Name: Carmen Savalez Residence	
B2. Common Name:	
B3. Original Use: Residential B4. Present Use: Residential	
*B6. Construction History: (Construction date, alternations, and date Building constructed c.1888-1906. Building r	
*B7. Moved? No DYes Unknown Date:	Original Location:
*B8. Related Features:	
None	
B9a. Architect: Unknown b. Builder: Unknown	
*B10. Significance: Theme _N/A Area _	Bast Village/Centre City
Period of Significance N/A Property Type Resi	
(Discuss importance in terms of historical or architect	
geographic scope. Also address integrity.)	tara context as domina by thome, period, and
This single-family residence was constructed c. 1888-1906. Review of an ofthe building during this year. However, by 1906, the building is shown as a one along the northeast elevation adjoining a one and one-half story "shed." A full-len Map shows that by this year, the front porch had been lengthened or extended removed. The one-story addition along the northwest elevation, however, remained occupant of the residence was Mrs. Carmen Savalez in 1926. A City of San Diego provided to the property in August, 1946 for Mrs. A.W. Laval. Other occupants a included Lillian Davis (1935); Embers Soniga (1940); Haywood Davis (1950-19) Historical research has determined that the 416–13* Street building is not associated with any important events or individuals in terms of local, state, or characteristics of a type, period, or method of construction. In addition, the building in important, creative individual.	and one-halfstory "dwelling" with an attached one-story addition agth porch was located along the east elevation. A 1940 Sanborn across the south elevation and the rear shed structure had been d. San Diego City Directories indicate that the earliest identifiable Water Department Service Order indicates that water service was ssociated with the building over the course of its existence have (55) and Lola Perkins (1950). ot historically or architecturally significant. The building is not national history. The building does not embody the distinctive
B11. Additional Resource Attributes: (List attributes and codes	
*B12. References: (partial list)	")
biz. Releiences. (partial list)	(Sketch Map with north arrow required.)
City of San Diego, Building Department Permit Records. City of San Diego, Water & Sewer Records. McAlester, Virginia & Lee, A Field Guide To American Houses, 2000.	: ISLAND
Sanborn Fire Insurance Maps, 1888, 1906, 1921, 1940, 195S. San Diego City and County Directories.	A 4 9
B13. Remarks:	Box K 100 22 (701)
*B14. Evaluator: Office of Marie Burke Lia	
Date of Evaluation: May 2004	0.56 AC 100 31(00)
	BLK 106
(This areas areas to a stiring a surrounts)	BLK 106
(This space reserved for official comments.)	156)
	3 E . " 5
	2 244 (3 (4 (4 (4 (4 (4 (4 (4 (4 (4 (4 (4 (4 (4
	(U F 6 5 4)
	60 100 100
	, J 1,,=100,

PRIMARY RECORD

Primary #	
HRI #	
Trinomial	

Other Listings	Update of November	1988	Centre	City East	Survey Documentation
Review Code	Reviewer				Date

NRHP Status Code 5S2

Page 1 of 3_ *Resource Name or #: (Assigned by recorder) 454 13th Avenue_____

P1. Other Identifier:

*P2. Location: a Not for Publication • Unrestricted *

a. County San Diego______
and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma Date T; R; R; 4 of 4 of Sec_; B.N

c. Address 454 13th Avenue City San Diego Zip 92101
d. UIM: (Give more than one for large or linear resources) Zone ___; ____ mE/ ___mN

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-156-08-00, Horton's Addition, Block 106, N 8' Lot J & S 34' Lot K

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1882, this single-story, **single-family** residence was designed in an Italianate architectural style. It has a general square shaped plan and features a flat roof with a boxed cornice and scrolled brackets. Two flat roofed, angled bays are present on the east, street facing **elevation**, each featuring a center section devoid of a window, and flanked on both **sides** by a narrow double-hung window. The bays also feature a bracketed entablature, and a dentil band **spanning** across the roof line. A small porch area is present at the northeast corner of the residence and features a mansard roof with fishscale shingles, additional dentiled entablature, and a supportive column. At the time **of** field investigation activities, this house was undergoing maintenance and general **rehabilitation**. Overall, this house appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP2_____

*P4. Resources Present: ■ Building a Structure a Object a Site □ District a Element of District □ Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

n Prehistoric

Both

1882_

1988 Centre City East Historic Site Inventory

*P7. Owner and Address

Jefferv D. Ratliff

454 13th Street

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev

Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: March 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: □NONE a Location Map a Sketch Map • Continuation Sheet ■ Building, Structure, and Object Record D Archaeological Record □ District Record a Linear Resource Record □ Milling Station Record a Rock Art Record a Artifact Record □ Photograph Record □ Other (List):

DEPARTMENT OF PARKS AND RECREATION HRI#	
BUILDING, STRUCTURE, AND OBJECT REC	
	Status Code5S2
*Resource Name or # (Assigned by recorder) 454 13th Avenue,	
B1. Historic Name: Wright Residence	
B2. Common Name:	
B3. Original Use: Residential (Single-Family)_ B4.	Present Use: Residential (Single-Family)
*B5. Architectural Style: Italianate	
*B6. Construction History: (Construction date, alternations, and da Constructed in 1882; according to past documenta residence (Lia/Brandes:1988). No other apparent substitution	ation, rooms have been added to the rear of the
	Original Location:
*B8. Related Features: B9a. Architect: Unknown b. Builder: J.S. Wright:	and Company
*B10. Significance: Theme Architecture Area San Dieg	
Property Type Residential Applicable	
(Discuss importance in terms of historical or architectural context as defined by theme	
Originally constructed in 1882, this building was the supervision of the Office of Marie Lia and Dr. Ray Rowners of the 454 13th Avenue property and building in Diego Architect John B. Stannard & his wife Mary (15c.1960s). Past documentation states that J.S. & Harri 1874 and erected a four room house and a cistern in 18 field investigation activities for the 1988 Centre furniture maker by trade, had built the Czerwinski resit the C.S. Hannah residence on 3rd and Laurel, in the Eatharriet Wright maintained ownership of the 454 13th Ave John B. & Mary Stannard. Stannard arrived in San residential and commercial structures for nearly three occupied the residence until 1910, the Stannard family (Lia/Brandes:1988). San Diego City Directories reveal N.M. Chavez (1944/1945, 1950, 1955, 1960), Rafael Moren (1975), Mrs. Zoraida D. Durazo (1980), and Christina E (See DPR 523H, Continuation Sheet for more informational Resource Attributes: (List attributes and codes)	Grandes. Previous documentation indicates past clude: J.S. & Harriet Wright (1874-1902), San 302-c.1941), and Nicholas M. Chavez (c.1940s-et Wright purchased the 454 13 th Avenue lot in 382, the cistern was still in existence during City Bast survey. "Wright, a carpenter and idence on 6 th near Broadway in 1875, and in 1887 astlake style." J.S. Wright died in 1889 and enue residence until 1902, when it was sold to Diego in 1887, and "designed many notable et decades." Although John & Mary Stannard only maintained ownership of the property until 1941 past residents 454 13 TH Avenue include: owner to (1965), vacant (1969/1970), Mrs. Marie Duran Hara (1984).
*B12. References: (partial list)	
(See DPR 523H, Continuation Sheet for more information	1)
B13. Remarks:	(Sketch Map with north arrow required.)
*P44 Feeleston Wander to m' 3	: ISLAND
*B14. Evaluator: Wendy L. Tinsley	
Office of Marie Burke Lia	-
(This space reserved for official comments.)	(I) Sold AC. 12 N 29 3 1 (24) 2 5 5 6 AC. 12 N 29 7 28 70 1 N 2 5 6 AC. 12 N 29 7 28 7 28 7 28 7 28 7 28 7 28 7 28 7
	166

\$

CONTINUATION SHEET

Primary #	
HRI #/Trinomial	

I Continuation

□ Update

Page __3 of __3

Resource Identifier: (Assigned by recorder) 454 13th Avenue, San Diego, CA 92101

Historic Name: Wright Residence

*B10. Significance (Continued):

Historical research has determined that the 454 13th Avenue residence is not historically **significant**, as it is not associated with any important **events** or **individuals** in terms of local, state, or national history. **However**, it does appear to be architecturally significant, as a building which embodies the distinctive **characteristics** of a type, period, or method of Italianate construction. In addition, past documentation **states** that this **residence** is **"one** of the oldest in this part of the city" (**Lia/Brandes:1988**). As the identity of the architect could not be ascertained, the 454 13th Avenue residence does not represent the work of a master architect or craftsman. The builder, J.S. Wright (and **Company**), does not rise to the level of a master builder.

*B12. References (Continued):

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office

DPR 523H (1/95)

PRIMARY RECORD

А

Primary #	
HRI #_2138-0431-0000	
Trinomial	

PRIMARI RECORD		minomiai		
		NRHP Status Code	5S2	
	Other Listings_U	pdate of May 1989	Bayside Survey I	Documentation
	Review Code	Reviewer	Date	
Page 1 of 3 *Resource	Name or #: (Assi	gned by recorder) 36	0 15 th Avenue	
P1. Other Identifier:				
*P2. Location: n Not for Publication	Unrestricted *	a. County	San Diego	
and (P2b and P2c or P2d. Attach a Location	on Map as necessa	ary.)		
*b. USGS 7.5' Quad Point Loma_	Date	; R; _	¼ of¼ of Sec	_; B.M
c. Address 360 15 th Av	enue	City <u>San Die</u>	<u>go</u>	2101

UTM: (Give more than one for large or linear resources) Zone 11; _____ mE/ Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): Believed to be part of APN: 535-396-04-00, Sherman's Addition, Block 36, W 30' of N 65' of Lot 3

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1887, this single-story, single-family residence was designed in a vernacular Queen Anne style of Victorian architecture. It has a rectangular shaped plan and features a hipped roof with a single, lower cross gable on the eastern elevation at the front entrance of the residence. Exterior building materials consist of horizontal shiplap siding for the exterior walls, and composition shingles for the roof. Only one double-hung sash window is present on the south elevation of the residence, and a direct view of the north side of the residence is partially obstructed by the neighboring two-story rooming house (the J Street Hotel) . (See DPR 523H Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes and codes) ___HP2 Resources Present: Building D *P4. Structure n Object n Site n District n

Element of District n Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)_

*P6. Date Constructed/Age and Sources:

I Historic

n Prehistoric c.1887

Both

1989 Bayside Historic Site Inventory

*P7. Owner and Address:

Kenneth Cummins Revocable Trust 905 Dohaney Court Roseville CA 95661

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Burke Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

Updated April 2004 *P9. Date Recorded: February 2001

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Bayside For Centre City Development Corporation

Attachments: □NONE □ Location Map n Sketch Map ■Continuation Sheet I Building, Structure, and Object Record n Archaeological Record a District Record n Linear Resource Record n Milling Station Record D Rock Art Record ☐ Artifact Record n Photograph Record D Other (List):

State of California — The Resources Agency Primary #	
DEPARTMENT OF PARKS AND RECREATION HRI#2138-0431-0000	_
BUILDING, STRUCTURE, AND OBJECT RECORD	
Page 2 of 3 *NRHP Status Code 5S1	
*Resource Name or # (Assigned by recorder) Rood Rental, 360 15th Avenue. San Diego, CA 92101	_
B1. Historic Name: Rood Rental	_
B2. Common Name:	_
B3. Original Use: Residential (Single-Family) B4. Present Use: Residential (Single-Family)	_
*B5. Architectural Style: vernacular Oueen Anne Victorian	_
*B6. Construction History: (Construction date, alternations, and date of alterations) Constructed in approximately 1887; no major alterations or modifications noted.	
*B7. Moved? ☐ No ☐Yes ☐Unknown Date:Original Location:	_
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: Theme Architecture Area San Diego Period of Significance c.1887_	
Property Type Residential Applicable Criteria C_	
(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)	
Originally constructed in approximately 1887, this building was previously documented in May 19	
under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentati indicates that this residence was most likely relocated to this location prior to 1921. The origin	
location, however, was not identified. Previous documentation reveals past owners of the 360 1	
Avenue property and building include: Vernon & Florence Rood (1907-c.1936), and Lawrence Piria	no
(1989). Past documentation states that the 360 15th Avenue residence has been consistently used	as
a rental property over the course of its existence at this location.	
Historical research has determined that the 360 15th Avenue residence is not historical	ly
Historical research has determined that the 360 15^{th} Avenue residence is not historical significant, as it is not associated with any important events or individuals in terms of loca	1,
Historical research has determined that the 360 15th Avenue residence is not historical significant, as it is not associated with any important events or individuals in terms of loca state, or national history. However, the residence appears to be architecturally significant, as	1, a
Historical research has determined that the 360 15th Avenue residence is not historical significant, as it is not associated with any important events or individuals in terms of loca state, or national history. However, the residence appears to be architecturally significant, as residence which embodies the distinctive characteristics of a type, period, or method of Queen An	a ne
Historical research has determined that the 360 15th Avenue residence is not historical significant, as it is not associated with any important events or individuals in terms of loca state, or national history. However, the residence appears to be architecturally significant, as	a ne ce
Historical research has determined that the 360 15 th Avenue residence is not historical significant, as it is not associated with any important events or individuals in terms of loca state, or national history. However, the residence appears to be architecturally significant, as residence which embodies the distinctive characteristics of a type, period, or method of Queen An vernacular construction. The exterior of the residence, however, is in poor condition. The residence is the last remaining example of its type on this block, and there are few examples located in the surrounding blocks. As the identity of the architect could not be ascertained, the 360 15 th Aven	a ne ce he
Historical research has determined that the 360 15 th Avenue residence is not historical significant, as it is not associated with any important events or individuals in terms of loca state, or national history. However, the residence appears to be architecturally significant, as residence which embodies the distinctive characteristics of a type, period, or method of Queen An vernacular construction. The exterior of the residence, however, is in poor condition. The residence is the last remaining example of its type on this block, and there are few examples located in the surrounding blocks. As the identity of the architect could not be ascertained, the 360 15 th Aven residence does not represent the work of a master architect or craftsman. The 360 15 th Aven	a ne ce he ue
Historical research has determined that the 360 15 th Avenue residence is not historical significant, as it is not associated with any important events or individuals in terms of loca state, or national history. However, the residence appears to be architecturally significant, as residence which embodies the distinctive characteristics of a type, period, or method of Queen An vernacular construction. The exterior of the residence, however, is in poor condition. The residence is the last remaining example of its type on this block, and there are few examples located in the surrounding blocks. As the identity of the architect could not be ascertained, the 360 15 th Aven residence does not represent the work of a master architect or craftsman. The 360 15 th Aven residence is listed on the California State Office of Historic Preservation Historic Property Da	a ne ce he ue ta
Historical research has determined that the 360 15 th Avenue residence is not historical significant, as it is not associated with any important events or individuals in terms of loca state, or national history. However, the residence appears to be architecturally significant, as residence which embodies the distinctive characteristics of a type, period, or method of Queen An vernacular construction. The exterior of the residence, however, is in poor condition. The residence is the last remaining example of its type on this block, and there are few examples located in the surrounding blocks. As the identity of the architect could not be ascertained, the 360 15 th Aven residence does not represent the work of a master architect or craftsman. The 360 15 th Aven residence is listed on the California State Office of Historic Preservation Historic Property Da File for San Diego County as a property which may be eligible for inclusion on the National Regist	a ne ce he ue
Historical research has determined that the 360 15 th Avenue residence is not historical significant, as it is not associated with any important events or individuals in terms of loca state, or national history. However, the residence appears to be architecturally significant, as residence which embodies the distinctive characteristics of a type, period, or method of Queen An vernacular construction. The exterior of the residence, however, is in poor condition. The residence is the last remaining example of its type on this block, and there are few examples located in the surrounding blocks. As the identity of the architect could not be ascertained, the 360 15 th Aven residence does not represent the work of a master architect or craftsman. The 360 15 th Aven residence is listed on the California State Office of Historic Preservation Historic Property Da	a ne ce he ue

*B12. References: (partial list)

McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

Lia and Brandes, Historic Site Inventory of Bayside, 1989.

San Diego City Directories

San Diego County Recorders Office


B13. Remarks:

*B14. Evaluator: Wendy L. Tinslev,

Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



CONTINUATION SHEET

Primary #	
HRI #/Trinomial_2138-0431-0000	

I Continuation

Update

Page3_ of	3								
Resource Identifie	er: (Assigned by recorder)	360_	15 th	Avenue.	San	Diego,	CA	92101	
Historic Name	e: Rood Rental								

P3a. Description (Continued):

A set of wooden stairs lead to the front entrance of the residence, where a partial porch area is present and is shaded by a separate, shed-style roof, and supported by three wood posts. The primary feature of the residence is a single bay window located on the front, street-facing elevation. The bay features a separate, shed-style, hipped roof with three double-hung sash windows. The windows feature decorative mullions fashioned after pilasters, and a dentil band spans across the three sections of the angled roof line. The dentil sections are marked by decorative brackets, which feature scroll and spindlework similar to that found in the window mullions.

At the time of initial survey activities in c. November 2000, renovations were being made to the residence, and February 2001 field activities revealed that the residence was still under renovation. Overall, the exterior of the residence appears to be in poor condition, as the exterior walls require painting, and the missing roof shingles signal that the roof is in need of repair and/or replacement.

DPR 523H (1/95)

PRIMARY RECORD

535-174-04

C. d.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary # HRI #
PRIMARY RECORD	Trinomial
Other Listings	
	Reviewer Date
Page1 of _3 *Resource Name or #: (Assign	ned by recorder) 648 15 th Street
P1. Other Identifier: Davidson Furniture C	
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County San Diecro
and (P2b and P2c or P2d. Attach a Location Map as necess *b. USGS 7.5' Quad <u>Point Loma</u> Date	ary.) T; R;½ of% of Se <u>c;</u> B.M.
c. Address 648 15th Street City San	<u>Diecro</u> <u>Zip</u> <u>92101</u>
d. UTM: (Give more than one for large or	r linear resources) Zone; mE/mN
e. Other Locational Data (e.g., parcel #, directions to r Block 16, Lots 1-3 par 3 doc 108411 re	esource, elevation, etc., as appropriate): ec 66 in un-numbered lot & alley; Map 143, APN:

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

This two-story, with mezzanine, commercial building, is believed to have been constructed for the Davidson Furniture Company as a warehouse in 1945. The building has not substantially changed in appearance since its construction. Designed in a Streamline Moderne/International style, the building is square in shape and set on a reinforced concrete foundation with concrete walls and brick. The building features a flat roof and stucco exterior. Along the main (east) elevation, the building is divided by coping which bisects the ground floor from the mezzanine and second floor. Along the ground floor, the building features broad horizontal grooves with two bay areas and "roll"up style metal doors. The horizontal grooves and coping dictate a strong Streamline Moderne/International style influence. Two entrances are separated by small double-hung windows. Along the mezzanine and second floor, there are a two ribbon sets which contain multi-paned awning windows. Overall, the building appears to be in good condition.

P3b. Resource Attributes: (List attributes and codes) HP6

* P4. Resources Present: Building Structure
Object
Site
District ement of District Other (Isolates, etc.) b. Description of Photo: (View, date, cession #)

P6. Date Constructed/Age and Sources: Historic

Prehistoric ☐ Both 945

Diecro Water Sewer Connection Records

*P7. Owner and Address:

Robert Mayberry Family Limited Partnership 2123 El Cajon Boulevard San Diecro, CA 92104_

P8. Recorded by (Name, affiliation, and address): Office of Marie Burke Lia, 427 C Street, Suite 416, San Diecro, California 92101

Date Recorded: March 2004

*P10. Type of Survey: (Describe)

Intensive

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Resources Inventory Update Of The East Village Area For Centre City Development Corporation Attachments:

NONE | Location Map | Sketch Map | Continuation Sheet | Building, Structure, and Object Record □Archaeological Record □District Record □Linear Resource Record □Milling Station Record □Rock Art Record □Artifact Record □Photograph Record n Other (List): _

e de la companya della companya della companya de la companya della companya dell	
State of California — The Resources Agency Primary # DEPARTMENT OF PARKS AND RECREATION HRI#	
BUILDING, STRUCTURE, AND OBJECT RECO	ORD atus Code5S2
*Resource Name or # (Assigned by recorder) 648 15th Street_	
B1. Historic Name: Davidson Furniture Company Ware	
B2. Common Name: Mayberry Auto & Mini-Storage	
B3. Original Use: Commercial B4. Present Use: Commer	
*B5. Architectural Style:Streamline Moderne/Interna	
*B6. Construction History: (Construction date, alternations, and date	of alterations)
Building constructed in 1945. Tenant improstairs, walls, and elevator, 1999).	vements (installation of fire doors at
*B7. Moved? No Date:	Original Location:
*B8. Related Features:	
20. Related Federals	
1488 Market Street	
DOS Auskitast. Unknown h Duildon Unknown	
B9a. Architect: Unknown b. Builder: Unknown	
*B10. Significance: Theme <u>Architecture</u> A	성요하다 그리지 않는데 나를 하는데 하면 하는데 하는데 그리고 하는데
Period of Significance 1945Property Type	
(Discuss importance in terms of historical or architect	tural context as defined by theme, period, and
geographic scope. Also address integrity.)	
This building is believed to have been constructed for the Davidson Furnand sewer connection records indicate that service was provided to the property in Company. While the building is depicted on the 1940 Sanborn Fire Insurance Davidson Furniture Company (which also had two other buildings located next d 1945. In any event, the building was associated with the Davidson Furniture Company (which also had two other buildings located next d 1945.	October, 1945 for "A.T. Davidson" and the Davidson Furniture Map as a "furniture warehouse" at 646 15 th Street for use by the oor), it is believed that the building was built a few years later in mpany until at least 1956.
Historical research has determined that the 648 15 th Street building is arcl important events or individuals in terms of local, state, or national history. The building period, and method of commercial Art Moderne construction. It does not represent creative individual.	lding, however, embodies the distinctive characteristics of a type,
B11. Additional Resource Attributes: (List attributes and codes	s)
*B12. References: (partial list)	
City of San Diego, Building Department Permit Records. City of San Diego, Water & Sewer Records. Longstreth, Richard, The Buildings Of Main Street, 1987. McAlester, Virginia & Lee, A Field Guide To American Houses,	(Sketch Map with north arrow required.)
2000.	*
Sanborn Fire Insurance Maps, 1887, 1888, 1906, 1921, 1940, 1956.	§ G & ST
San Diego City and County Directories.	
B13. Remarks:	T. C.
*B14. Evaluator: Office of Marie Burke Lia	(D) (B) (D)
	4 1 7 7
Date of Evaluation: March 2004	1 0 H D
(This space reserved for official comments.)	Total entry County 19
	MARKET 1-100

CONTINUATION SHEET	Primary #
	HRI #
	Trinomial
Page 3 of 3 *Resource Name or #	(Assigned by recorder) 648 15 th Street
*Recorded by Office of Marie	Burke Lia Date March 2004
☑ Continuation P Update	

Historic Photograph (1950); Sensor 5-602; "Davidson Furniture Company"; Photograph Courtesy Of The San Diego Historical Society



PRIMARY RECORD

Primary #		
HRI# 2138-0432	-0000	
Trinomial	- 27	
NRHP Status Code	5S2	

			NRHP Status C	ode_552			
		Other Listings U	odate of November 19	88 Centre Ci	ty East Surve	y Docum	entation
		Review Code	Reviewer_		Date_		
Page _	_1_ of _2_ *Resourc	e Name or #: (Ass	signed by recorder)	1037 15 th	Avenue		
P1.	Other Identifier:						
*P2.	Location: Dot for Publication	Unrestricted *	a. County	San Die	go		
and (P2	2b and P2c or P2d. Attach a Locat	ion Map as necess	ary.)				
*b. US	GGS 7.5' Quad Point Loma_	Date	; R	_;'/4 of _	% of Sec	;	B.M.
C.	Address 1037 15 th Avenue	City	San Diego	Zip_	92101		
d.	UTM: (Give more than one	e for large o	linear resour	ces) Zone	;	_ mE/	mN
e.	Other Locational Data (e.g., parce APN: 535-225-04-00, S ½						
*P3a	Description (Describeresource and	dits major elements	Include design ma	terials condi	tion alteration	ns size :	setting

*P3a. Description (Describeresource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1886, this single-story, single-family residence was designed in a Queen Anne cottage style of Victorian architecture. It has a general rectangular shaped plan, and features a hipped roof with a cross gabled portion featuring a boxed cornice and diamond shaped wood shingles on the west elevation. Other features include: a rectangular bay window on the west elevation with a hipped roof portion overhead, and four double-hung sash windows; a corner porch entrance supported by turned posts and featuring ornamental brackets, and an upper transom window above the front door. Exterior building materials consist of composition shingles for the roof, horizontal dropped, simple wood siding, and wood shingles for the exterior walls. Overall, the residence appears to be in fair condition.



- **P3b.** Resource Attributes: (List attributes and codes) HP2
- *P4. Resources Present: Building D
 Structure a Object □ Site □ District a
 Element of District □ Other (Isolates, etc.)
 P5b. Description of Photo: (View, date, accession #)
- *P6. Date Constructed/Age and Sources:
- Historic
- a Prehistoric
- □ Both
- 1886
- 1988 Centre City East Historic Site Inventory

*P7. Owner and Address

Valderrama, Raul; Lucero, Rachel; and Rebecca Jones

1037 15" Street

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: March 2001

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: a NONE a Location Map a Sketch Map a Continuation Sheet ■ Building, Structure, and Object Record D Archaeological Record a District Record a Linear Resource Record □ Milling Station Record □ Rock Art Record □ Artifact Record □ Photograph Record □ Other (List):

Primary	#		
HRI#	2138-0432-0000		

BUILDING, STRUCTURE, AND OBJECT RECORD

*NRHP Status Code 5S2 Page 2 of 2 *Resource Name or # (Assigned by recorder) 1037 15th Avenue, San Diego, CA 92101 B1. Historic Name: B.J. Grenell House Common Name: Valderrama Rental B2. B3. Original Use: Residential (single-family) B4. Present Use: Residential (single-family) *B5. Architectural Style: Oueen Anne Cottage *B6. Construction History: (Construction date, alternations, and date of alterations) Constructed in approximately 1886; no substantial alterations and/or modifications noted *B7. Moved? No ☐ Yes ☐Unknown Date:___ Original Location: *B8. Related Features: R₉a Architect: Unknown_ b. Builder: E.G. Hammond_ *B 10. Significance: Theme Architecture Area San Diego Period of Significance 1886_

Property Type Residential Applicable Criteria <u>C</u>
(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Originally constructed in approximately 1886, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation indicates past owners of the 1037 15th Street property and building include: carpenter E.G. Hammond (1886-c.1898), Samual & Ella Garwood (1898-1912), and Ralph L. & Ildica Conklin (1912-1936), and Octavio Valderrama (c.1955-c.1988). Partial ownership of the residence is currently maintained by Raul Valderrama. San Diego City Directories reveal that past residents of the 1037 15th Street residence include: Frank Bosco, Marcus Mercado, and owner Stanley Norris (1944/1945), and owner Octavio Valderramma (1950-1975). There no tenants listed as occupying the residence in 1980 and 1984.

Historical research has determined that the 1037 15th Street residence is not **historically significant**, as it is not associated with any important events or individuals in terms of local, state, or national history. However, the residence does appear to be architecturally significant, at the local level, as a building which embodies the distinctive characteristics of a type, period, or method of Queen Anne Cottage **construction**. As the identity of the architect could not be ascertained, the residence does not represent the work of a master architect or craftsman.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To Amercian Houses, 1986. San Diego City Directories

San Diego County Recorders Office


B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley

Office of Marie Burke Lia

Date of Evaluation: March 2001

(This space reserved for official comments.)



PRIMARY RECORD

e.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary #		
PRIMARY RECORD	Trinomial		
Other Listings_			
	Reviewer Date		
	signed by recorder) 39 16 th Street		
*P2. Location: □ Not for Publication ■ Unrestricted	* a. County San Diecro		
	T; R; _% of _% of Sec; B.M.		
c. Address 39 16th Street City Sa	an Diecro Zip 92101		
d. UTM: (Give more than one for large of	or linear resources) Zone ; mE/mN		

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Block 57, South 38 feet of Lot 3, Map 856, APN: 535-623-04

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

This one-story, single-family residence was designed in a Craftsman architectural style and was constructed in 1923. Irregular in shape, the residence features a front-gabled roof of moderate pitch, with eave overhang and exposed rafters. Triangular knee braces have been added underneath the central roofline. Along the southwest elevation, the building has a re-built, partial porch which is front-gabled of moderate pitch with eave overhang and exposed rafters. The porch pediment is vented with projecting braces. Porch piers are square and sheathed in horizontal clapboard. The piers have tapered porch columns. Concrete steps with metal railing lead to the porch area. The exterior of the residence consists of horizontal clapboard. Fenestration consists of paired, double-hung windows with metal security grilles. Overall, the residence appears to be in good condition.

P3b. Resource Attributes: (List attributes and codes) HP2



*P4. Resources Present: I Building ☐ Structure ☐ Object D Site ☐ District D Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

d Prehistoric 1923

Sanborn Fire Insurance Maps San Diego City Directories

☐ Both

*P7. Owner and Address: SVDP Management Inc

3350 E Street

San Diego, CA 92102_

*P8. Recorded by (Name, affiliation, and address): Office of Marie Burke Lia, 427 C Street, Suite 416_ San Diecro, California 92101

*P9. Date Recorded: March 2004

*P10. Type of Survey: (Describe)

Intensive

Historic Resources Inventory P11. Report Citation (Cite survey report and other sources, or enter "none".) Update Of The East Village Area For Cente City Development Corporation Attachments: DNONE DLocation Map DSketch Map DContinuation Sheet Building, Structure, and Object Record □Archaeological Record □District Record □Linear Resource Record □Milling Station Record dRock Art Record □Artifact Record □Photograph Record □ Other (List):__

State of California — The Resources Agency Primary # _ DEPARTMENT OF PARKS AND RECREATION HRI#	0
	DD
BUILDING, STRUCTURE, AND OBJECT RECO	
Page 2 of 2 *NRHP Star *Resource Name or # (Assigned by recorder) 39 16 th Street_	tus Code 62
B1. Historic Name: J. Wesley and Mary Fultz Reside	
B2. Common Name:	
B3. Original Use: Residential B4. Present Use: Residential	al
*B5. Architectural Style: _ Craftsman	
*B6. Construction History: (Construction date, alternations, and date	
Building constructed in 1923. New composite remodeled, including "beam" added and bathroom and	
*B7. Moved? No DYes Unknown Date:	Original Location:
*B8. Related Features:	Ongman 200anom
201 11024004 204042021	
None	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: ThemeN/A Area	East Village/ Centre City
Period of Significance N/A Property Type F	Residential Applicable Criteria N/A
(Discuss importance in terms of historical or architectus geographic scope. Also address integrity.)	ral context as defined by theme, period, and
This single-family residence was designed in a Craftsman architectural style Insurance Map indicates the presence of another dwelling on the property during the presence of the 39 16th Street residence by this time. San Diego City Directorie Fultz in 1923. The Fultzs lived in the home until at least 1926. Subsequent occup (1930); Mable Chander (1935); I.H. Lipscomb (1940-1950); Julius R. Torres (1950); Historical research has determined that the 39 16th Street building is not associated with any important events or individuals in terms of local, state, or na characteristics of a type, period, or method of Craftsman construction, particularly signs over the years. In addition, it does not represent the work of a master architect, building is not associated with any important events or individuals in terms of local, state, or na characteristics of a type, period, or method of Craftsman construction, particularly signs over the years. In addition, it does not represent the work of a master architect, building in the property during t	his year. However, a 1940 Sanborn Fire Insurance Map shows is list the first occupants of the residence as J. Wesley and Mary pants over the years have included J.T. Tolk (1926); C.F. Clark 5); and Manuel D. Gauna (1960). historically or architecturally significant. The building is not tional history. The building does not embody the distinctive nce the building appears to have been remodeled and/or re-built
	560
B11. Additional Resource Attributes: (List attributes and codes)	
*P40 = 0	
*B12. References: (partial list) City of San Diego, Building Department Permit Records.	
City of San Diego, Water & Sewer Records.	(Sketch Map with north arrow required.)
McAlester, Virginia & Lee, A Field Guide To American Houses, 2000.	
Sanborn Fire Insurance Maps, 1887, 1888, 1906, 1921, 1940,	IMPERIAL *
1956.	
San Diego City and County Directories. B13. Remarks:	
DIS. Reliaiks.	2 1 (5), 3
*B14. Evaluator: Office of Marie Burke Lia	D 1 411 2
Date of Evaluation: March 2004	t. 6230° L
(This space reserved for official comments.)	BLK 57
	6 6 7
29	
	* * * * * * * * * * * * * * * * * * *
]	COMMERCIAL 1'=100'
1 11	· · · · · · · · · · · · · · · · · · ·


State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI #
PRIMARY RECORD	Trinomial
	NRHP Status Code 6Z
Other Listing	S
Review Code	e Reviewer Date
Page 1 of 2 *Resource Name or #:	(Assigned by recorder) 255 16 th Street
P1. Other Identifier: William and Mamie	Lewis Residence
P2. Location: c Not for Publication Unrestricted	* a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as ne	cessary.)
*b. USGS 7.5' Quad Point Loma Date	T; R;% of% of Sec; B.M.
c. Address 255 16 th Street City	San Diego Zip 92101

Block 39, Lot 2, Map: 853; APN: 535-383-02 *P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting,

UTM: (Give more than one for large or linear resources) Zone

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

This one-story, single-family residence appears to have been designed in a Folk Victorian architectural style and constructed c. 1888. The building is almost rectangular in shape and features a multi-gabled roof. Along the main (west) elevation, the building features a medium pitched, front-gable roof with slight eave overhang and composition shingles. A partial porch is located along the northwest elevation. Along the north elevation, the building has two side-gables, both of medium pitch and moderate eave overhang. The west elevation features thick clapboard siding. Siding along the north elevation is board-and-batten. A focal window along the west elevation is a paired, double-hung variety. Overall, the building appears in poor condition.



Element of District n Other (Isolates, etc.) P5b. Description of Photo: (View, date, *P6. Date Constructed/Age and Sources: □ Both Sanborn Fire Insurance Maps Joseph, Dominic, Laura Deluca, Drive 92116 P8. Recorded by (Name, affiliation, and address): Office of Marie Burke 427 C Street, Suite 416, San Diego, California 92101 Date Recorded: May 2004

Building

Intensive P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Resources Inventory Update Of The East Village Area For Centre City Development Corporation_ Attachments: NONE Location Map Sketch Map Continuation Sheet Building, Structure, and Object Record □Archaeological Record □District Record □Linear Resource Record □Milling Station Record □Rock Art Record □Artifact Record □Photograph Record □ Other (List):_

d.

and boundaries):

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI#
BUILDING, STRUCTURE, AND OBJECT	
Page 2 of 2	*NRHP Status Code 6Z
	Street
	vis Residence
	D. M. L. L.
	: Residential
*B6. Construction History: (Construction date, alternati	ons, and date of alterations)
Building constructed c.1888; Exterior 1888-1906); Building altered again to re	or remodeled along front and rear elevations (c.eflect current appearance (c.1906-1921).
*B7. Moved? ■No □Yes □Unknown Date: *B8. Related Features:	Original Location:
bo. Related reatures.	
None	8
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
	Area East Village/ Centre City
-	erty Type Residential Applicable Criteria N/A
(Discuss importance in terms of historical geographic scope. Also address integrity.)	or architectural context as defined by theme, period, and
the presence of this building as a one-story, dwelling during this yet a slightly larger partial porch area along the northwest elevation an were removed and it appears by this date that the building may have arliest identifiable occupants of the property were William T. Lewi least 1926 followed by A.A. Clark (1930), Mary Ramirez (1940), Barry	een constructed c. 1888. Inspection of a 1888 Sanborn Fire Insurance Map depict ar identified as 255 17 th Street. By 1906, the building had been altered to include d additions at the rear (east) elevation. By 1921, however, these improvement we reflected its current appearance. San Diego City Directories indicate that the s, a cook, and his wife, Mamie, in 1924. The couple lived in the home until a pruschi (1945), Anita Ynzunza (1950), Samuel Parker (1955), and Joe Andrews (1960).
associated with any important events or individuals in terms of l	building is not historically or architecturally significant. The building is no ocal, state, or national history. The building does not embody the distinctive eover, the building does not represent the work of a master architect, builden
B11. Additional Resource Attributes: (List attribute	s and codes)
*B12. References: (partial list) City of San Diego, Building Department Permit Recording of San Diego, Water & Sewer Records. McAlester, Virginia & Lee, A Field Guide To America 2000. Sanborn Fire Insurance Maps, 1888, 1906, 1921, 194	can Houses,
San Diego City and County Directories.	1956. 12 O
B13. Remarks:	
*B14. Evaluator: Office of Marie Burke Li	
Date of Evaluation: May 2004	
(This space reserved for official comments.)	STREET STREET

PRIMARY RECORD

RECREATION		HRI #				
84. A		Trinomial				
		NRHP Status Code_ 7				
Other L	istings Upda	te of November 1988	Centre	EaGity	D Scument ation	
Review	v Code	Reviewer_			Date	
*Resource Name	or #: (Assig	ned by recorder)	701	16 th Avenue	<u> </u>	

P1. Other Identifier: *P2. Location: D Not for Publication • Unrestricted * a. County San Diego_

Driman, #

and (P2b and P2c or P2d. Attach a Location Map as necessary.) T___;R___; __¼ of __¼ of Sec__; ___B.M. *b. USGS 7.5' Quad Point Loma Date

Address 701 16th Avenue City San Diego______ "Zip _____92101 C. UTM: (Give more than one for large or linear resources) Zone ___; ____ mE/ d.

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): e. APN: 535-180-01-00, Culverwell's Addition, Block 13, Lots 4 thru 12

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1914, this two-story brick, One Part Commercial Block style building has a rectangular shaped plan and features a flat roof, brick corbeling near the roof line, and brick belt coursing between the first and second floors. The first floor windows appear to be industrial style with a multi-pane sash pattern. The second floor window types vary between a fixed single-panes and sliding windows with an upper fixed portion. Overall, the building appears to be in good condition. Overall, the residence appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP8; HP6_

Resources Present: • Building n Structure

Object

Site a District Element of District

Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

n Prehistoric 1914

n Both

1988 Centre City Eaet Historic Site Inventory

*P7. Owner and Address

James S. Brown Revocable Trust Donald R. & Judith R. Clark Trust 591 Camino De La Reina San Diego, CA 92108

*P8. Recorded by (Name, affiliation, and address): <u>Wendy L. Tinsley, Scott</u> A. Moomjian, Office of Marie Lia, Attorney at Law. 427 C Street, Ste. 416, San Dieao. CA 92101

*P9. Date Recorded: October 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments:
NONE n Location Map n Sketch Map D Continuation Sheet Building, Structure, and Object Record D Archaeological Record a District Record D Linear Resource Record a Milling Station Record n Rock Art Record D Artifact Record a Photograph Record a Other (List):_

State of California — The Resources Agency Primary DEPARTMENT OF PARKS AND RECREATION HRI#	· #
BUILDING, STRUCTURE, AND OBJECT RE	
	Status Code 7
*Resource Name or # (Assigned by recorder) 701 16 th Aven	
B1. Historic Name: The Snowflake Bakery Building B2. Common Name: The Surva Automotive Building	
B3. Original Use: <u>Light Industrial (Bakery Warehouse)</u>	
*B5. Architectural Style: One Part Commercial Block_	and the state of t
*B6. Construction History: (Construction date, alternations, and originally constructed in 1914; original windows	
single-story addition to the east side of the building	
*B7. Moved? B No □ Yes □Unknown Date:	Original Location:
*B8. Related Features:	laka ayya
B9a. Architect: <u>John B. Stannard</u> b. Builder: <u>L</u> *B10. Significance: Theme Architecture Area San Diego	
Property Type Light Industrial/Comme	ercial Applicable Criteria C_
(Discuss importance in terms of historical or architectural context as defined by then	
Originally constructed in 1914, this building was the supervision of the Office of Marie Lia and Dr. R	
Snowflake Bakery Company occupied two other building	gs prior to its tenancy in this building. "An
announcement as early as June 1908 foretold of the accepte then had a small brick building on it. By October 1:	
Stannard to build a new plant appeared in the San Dia	
reflected a full history of the [Snowflake] bakery and	
City Directories reveal past occupants of the 701 16 Company, Incorporated (1944/1945, 1950, 1955, 19	
Incorporated (1980), and the Vons San Diego Bakery	
Historical research has determined that this bui	ilding is not historically significant, as it is
not directly associated with any important events or is	ndividuals in terms of local, state, or national
history. The 701 16 th Avenue building, however, is ar as a building which embodies the distinctive characte	
Commercial Block construction. Although the build:	ing does not qualify at the local level on this
basis, it also represents the work of architect J important, creative individual at the local level.	ohn B. Stannard, who is considered to be an
important, creative individual at the local level.	
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list) Lia and Brandes, Historic Site Inventory of Ce	ntre City East 1988
McAlester, Virginia & Lee, A Field Guide	- · · · · · · · · · · · · · · · · · · ·
Amercian Houses, 1986.	(Sketch Map with north arrow required.)
San Diego City Directories San Diego County Recorders Office	
ball blego county recorders office	
B13. Remarks:	9 1
	5 4 2
*B14. Evaluator: Wendy L. Tinsley	_
Office of Marie Burke Lia	— , , , [6]
Date of Evaluation: March 2001	

(This space reserved for official comments.)

4

	95
State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI #
PRIMARY RECORD	Trinomial
TRIMART RESORD	NRHP Status Code6Z
Other Listing	s
Review Code	eReviewer Date
	Assigned by recorder)716_16 th Street
*P2. Location: □ Not for Publication ■ Unrestricted	* a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as new	cessary.)
	T; R;% of _¼ of Sec_; B.M.
	DiegoZip92101
	e or linear resources) Zone;mE/mN
e. Other Locational Data (e.g., parcel #, directions Block 14, Lots 5 & 6, Map 143, AP	
*P3a. Description (Describe resource and its major eleand boundaries):	ements. Include design, materials, condition, alterations, size, setting
Additional newer signage is located along the south and east eleva is stucco. Flanking the main entrance, there is a fixed storefront w	above the rounded corner entrance, there is a vertical tower element for signage ations, identifying the building as "GTM's Discount General Store." The exterior window to the west and a series of fixed storefront windows along the east elevation the south elevation. Overall, the building appears to be in good condition. HP6
Tob. Procedure / Minbales. (Elst ambales and cedes)	*P4. Resources Present: Building
	D Structure D Object D Site District F
	Element of District P Other (Isolates, etc.) P5b. Description of Photo: (View, date
	accession #)
	*P6. Date Constructed/Age and Sources:
DISCOUNT	Historic
GTM's DISCOUNT GENERAL STORE	P Prehistoric D Both
	c.1947
	Record Record
	San Diego City Directories
	*P7. Owner and Address:
	Navarra Family Trust
	Ann N. Greenberg Trust
	1401 E Street
	San Diego, CA 92101 *P8. Recorded by (Name, affiliation, and
	address): Office of Marie Burke
- SERVICE - CONTRACTOR - CONTRA	Lia, 427 C Street, Suite 416,
	San Diego, California 92101_

*P9. Date Recorded: March 2004

*P10. Type of Survey: (Describe)

Intensive

P11. Report Citation (Cite survey report and other sources, or enter "none".)

Historic Resources Inventory

Update Of the East Village Area For Centre City Development Corporation

Attachments:

NONE

Location Map

Sketch Map

Continuation Sheet •Building, Structure, and Object Record

Archaeological Record

District Record

Linear Resource Record

Milling Station Record

DRock Art Record

□Artifact Record □Photograph Record n Other (List):_


	6 E
BUILDING, STRUCTURE, AND OBJECT RECOR	
	us Code 6Z
*Resource Name or # (Assigned by recorder) 716 16 th Street	us code
B1. Historic Name: Todd' s Market	
B2. Common Name: GTM's Discount General Store	
B3. Original Use: Commercial B4. Present Use: Commercia	
*B5. Architectural Style: _ Art Moderne (streamline mode	rnistic)
*B6. Construction History: (Construction date, alternations, and date of	alterations)
Building constructed c.1947. Building re-roofe	ed (1975).
*B7. Moved? ■No □Yes □Unknown Date:	Original Location:
*B8. Related Features:	Oliginal Education.
None	
2. A. 21. 1.00. 1.	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: Theme <u>N/A</u> Area _	
Period of Significance _ N/A Property Type Col	
(Discuss importance in terms of historical or architectura	al context as defined by theme, period, and
geographic scope. Also address integrity.)	
This commercial building is believed to have been constructed c.1947. Although the 1940 Sanborn Fire Insurance Map, a City of San Diego Sewer Connection On in September, 1947 for owner Homer McClure. Further, the property is listed as "T in 1950. The property address is not listed in San Diego City Directories between 19 Markets (1955); San Diego Motor Parts (1960), and as a paint store during the mid-	order indicates that water service was provided to the property Fodd's Market" with "H.W. Wilkinson, meats" at the property 940-1949 Over the years, the building has served as Mayfair
Historical research indicates that the 716 16 th Street building is not historically with any important events or individuals in terms of local, state, or national history • of a type, period, or method of Art Moderne construction. In addition, it does not reimportant, creative individual.	• The building does not embody the distinctive characteristics
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list)	
City of San Diego, Building Department Permit Records.	
City of San Diego, Water & Sewer Records. Longstreth, Richard, The Buildings Of Main Street, 1987. McAlester, Virginia & Lee, A Field Guide To American Houses,	(Sketch Map with north arrow required.)
2000. Sanborn Fire Insurance Maps, 1887, 1888, 1906, 1921, 1940,	F ST
1956.	# 199 (C) (C) 199 (H)
San Diego City and County Directories.	
B13. Remarks:	11 2
*P14 Evaluation Office of Monie Punks Lie	tg (3) ©
*B14. Evaluator: Office of Marie Burke Lia Date of Evaluation: March 2004	to (10) (2)
Date of Evaluation: March 2004	1 (4) 9 (1724)
(This space reserved for official comments.)	9 1723
	0 5
	, 0
	7 6
	G ST 8 NU
	- IN

Primary #	
HRI #	
Trinomial	
NRHP Status Code .	5S2

PRIMARY RECORD		Trinomial	ode_ , 5S2	
	ther Listings_Update	of November 1988	Centre City East Survey	Documentation
	Review Code	<u>Reviewer</u>	Date	
Page1 of3 *Resou P1. Other Identifier: *P2. Location: a Not for Publication			815 16 th Avenue	
and (P2b and P2c or P2d. Attach a Loc				
*b. USGS 7.5' Quad <u>Point Lom</u> c. Address <u>815 16th</u>				
d. UTM: (Give more than of Other Locational Data (e.g., part Believed to be part of Al	rcel #, directions to re	esource, elevation, e	etc., as appropriate):	


*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1908, this two-story multiple-family residence was designed originally for single-family use in a Colonial Revival architectural style. It has a general rectangular shaped plan, and features a moderately pitched, hipped roof, with a hipped dormer, two red brick chimneys, and a widely overhanging eave on the west, street facing elevation. Exposed beams are present under the eave and appear to be more ornamental than functional. A full length front porch is present on the west elevation, and features five Doric columns, and one rounded pilaster where the porch meets the exterior wall. (See DPR 523H, Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes and codes) HP3
*P4. Resources Present: I Building
Structure \square Object \square Site \square District \square
Element of District Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)
*P6. Date Constructed/Age and Sources:
I Historic
☐ Prehistoric ☐ Both
.1908
1988 Centre City East Historic Site Inventory
*P7. Owner and Address: Nasim Fares Jr.
637 Lippizan Way
El Cajon, CA 92019
*P8. Recorded by (Name, affiliation, and
address): Wendy L. Tinsley,
Office of Marie Burke Lia,

State of California — The Resources Agency Primary #			
BUILDING, STRUCTURE, AND OBJECT RECORD			
Page 2 of 3 *NRHP Status Code 5S2			
*Resource Name or # (Assigned by recorder) 815 16 th Avenue, San Diego, CA 92101			
B1. Historic Name: The Lee House			
B2. Common Name: The Sixteenth Avenue Apartments Building			
B3. Original Use: Residential (Single-Family) B4. Present Use: Residential (Multi-Family)			
*B5. Architectural Style: Colonial Revival			
*B6. Construction History: (Construction date, alternations, and date of alterations) Originally constructed in approximately 1908; no major alterations and/or modifications noted.			
*B7. Moved? No			
*B8. Related Features:			
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>			
*B 10. Significance: Theme Architecture Area San Diego Period of Significance 1908_			
Property Type Residential Applicable Criteria C_ (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)			
Originally constructed in approximately 1908, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past owners of the 815 16 th Avenue property and building include: D.C. Place (pre-1907), and John M. & Julia Lee (1907-c.1913 when John Lee died). San Diego City Directories reveal past residents of the 815 16 th Avenue building include: the widowed Julia Lee (1914), William Labb (1944/1945), and Mrs. Nellie Brest (1950). San Diego City Directories also reveal the 815 16 th Avenue building was identified as the "Sixteenth Street Apartments" building in 1955 and contained approximately five units. Past residents of these units include: 1. Mrs. Nellie Brest, 2. Mrs. Geneva Baker, 3. Mrs. Camille I. Bailey, 4. Mrs. Alice Christianson, and 5. William Eldridge (1955); 1. Mrs. Nellie Brest, 2. Frank Kettleman, 3. Mrs. Camille Bailey, and 4. Michael Endine (1960); 1. Vacant, 2. Mrs. Maria J. Barrios, and 3 5. Vacant (1965); 1. Mrs. Juana A. Avelino, 2. Henry Andel, 3. Henry U. Coronado, and 4. Flores Santiago (1975); 1. Mrs. Juana A. Avelino, 2. Guadalupe Sanchez, 3. Severiano V. Golindo, 4. Thomas Rivas, and 5. Juan M. Munoz (1980); and 1. Mrs. Juan Avelino, 2. Josefina Mores, 3. Peter Hidalgo, 4. No listing, and 5. Lorenso Chacon (1984).			
Historical research has determined that the 815 16 th Avenue building is not historically significant, as it is not directly associated with any important events, or individuals in terms of local, state, or national history. The 815 16 th Avenue building, however, is considered to be architecturally significant at a local level, as a building which embodies the distinctive characteristics of a type, period, or method of the Colonial Revival style of construction. As the identities of the architect or builder could not be ascertained, the building does not represent the work of a master architect, master builder, or master craftsman.			
B11. Additional Resource Attributes: (List attributes and codes)			
*B12. References: (partial list)			
(See DPR 523H, Continuation Sheet for more information) (Sketch Map with north arrow required.)			
B13. Remarks:			
100 100			
*B14. Evaluator: Wendy L. Tinsley,			



State of California — The Resources Agency

DEPARTMENT OF PARKS AND RECREATION **CONTINUATION SHEET**

Primary #	
HRI #/Trinomial	
Continuation	□ Update

Page3 of3					
Resource Identifier: (Assigned by recorder)	815	16 th Avenue.	San Diego,	CA	92101
Historic Name: The Lee House					

P3a. Description (Continued):

Above the boxed cornice of the first-floor porch, a bay window is present with an adjacent door which allows for accessability onto the porch roof. A railing or balustrade around the second floor porch was most likely present at the time of original construction. A first floor bay window is also present, and all other windows appear to be double-hung sash. Exterior building materials consist of composition shingles for the roof, and shiplap siding. Wooden steps ascend to, and iron railing encloses the front porch area. Overall, the building appears to be in good condition.

*B12. References (Continued):

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986. San Diego City Directories San Diego County Recorders Office

PRIMARY RECORD

y	Primary #
ON	HRI#
	Trinomial
	NRHP Status Code_5S2
Other Listings	Update of May 1989 Survey Documentation

Review Code Reviewer Date

Page 1 of 2 *Resource Name or #: (Assigned by recorder) 349-363 17th Avenue

Page 1 Of 2 *Resource Name or #: (Assigned by recorder) 349-363 17 Avenue Pl. Other Identifier:

P1. Other Identifier:

*P2. Location: a Not for Publication • Unrestricted *

a. County San Diego

*P2. Location: a Not for Publication • Unrestricted * a. County San Diego and (P2b and P2c or P2d. Attach a Location Map as necessary.)


*b. USGS 7.5' Quad Point Loma Date T ; R ; ¼ of ¼ of Sec ; c. Address 349-363 17th Avenue City San Diego Zip 92101

d. UTM: (Give more than one for large or linear resources) Zone __; ____ mE/ __mN

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):
APN: 535-406-01-00, Remondinos Sub, Sherman's Addition, Block 33, Lots M-P

***P3a. Description** (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1940, this eight-unit apartment complex known as the Auto Courts, was designed in an Art Moderne or Streamline Modernistic architectural style. Located immediately west of Interstate 5, the apartments are arranged in two sets of four units, with each set facing in towards one another. Each unit is aligned off-center from another unit, thereby achieving an overall stepped "C-shaped" courtyard effect. Each of the eight units display common architectural features indicative of the Art Moderne style including: flat roofline, smooth stucco exterior wall surface, asymmetrical facade, horizontal grooves/lines in the sides of exterior walls, curved wall corners, and small circular (port-hole) windows. Each of these units also display larger square windowswith decorative security grilles, and a small concrete porch covering. (See DPR 523H, Continuation Sheet for more information)



P3b. Resource Attributes: (List attributes and codes) HP3_____

*P4. Resources Present: • Building □ Structure a Object □ Site □ District □ Element of District n Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

□ Prehistoric n Both 1940

1989 Bayside Historic Site Inventory_

*P7. Owner and Address

San Diego, CA 92102

*P8. Recorded by (Name, affiliation, and address) :Wendy Tinsley/Scott Moomjian, Office of Marie Lia,

Attorney at Law, 427 C Street,
Ste. 416, San Diego, CA 92101

*P9. Date Recorded: February 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Bayside For Centre City Development Corporation

Attachments:

NONE a Location Map a Sketch Map
Continuation Sheet • Building, Structure, and Object Record
Archaeological Record a District Record n Linear Resource Record n Milling Station Record a Rock Art Record
Artifact Record Photograph Record D Other (List):

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI#
BUILDING, STRUCTURE, AND OBJEC	CT RECORD
Page 2 of 2	*NRHP Status Code_5S1
*Resource Name or # (Assigned by recorder) 349-363	17 th Avenue, San Diego, CA 92101
B1. Historic Name: Saliba Auto Courts	(9)
B2. Common Name: Auto Courts	
B3. Original Use: Residential (Multi-Family)	B4. Present Use: Residential (Multi-Family)
*B5. Architectural Style:ftrt Moderne	Some Person
*B6. Construction History: (Construction date, alternation Originally constructed in 1940; no major	
*B7. Moved? No 🗆 Yes 🗆 Unknown Date:	
*B8. Related Features: B9a. Architect: <u>Unknown</u> b. Builder: <u>L</u>	
*B 10. Significance: Theme Architecture Area	LIPS AND THE PROPERTY OF THE P
Property Type Residential	
Discuss importance in terms of historical or architectural context as def	ined by theme, period, and geographic scope. Also address integrity.)
under the supervision of the Office of Marie	partment complex was previously documented in May 1989 Lia and Dr. Ray Brandes, and again in November 1998 by Treals the Auto Courts were constructed by grocers Gabrie
	apartments were rented to various tenants including
aircraft workers, auto wreckers, and radio tech	hnicians. Original tenants of the complex include: J.B

Historical research has determined that the 349-363 $17^{\rm th}$ Avenue apartment complex is not historically significant, as the complex is not associated with any important events or individuals in terms of local, state, or national history. However, the complex does appear to be architecturally significant at the local level, for its buildings which embody the distinctive characteristics of a type, period, or method of the Art Moderne architectural style of construction. As the identity of the architect could not be ascertained, the complex does not appear to represent the work of a master architect or craftsman.

Testman (# 349), Lester Loeser (# 351), E.H. Torson (# 353), R.H. Jones (# 355), J.P. Hewitt (# 357),

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Bayside, 1989.

McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office

A.A. LaCarra (# 359), Joseph Parga (# 361), and C.M. Fisher (# 363).


B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley

Office of Marie Burke Lia

Date of Evaluation: February 2001

(This space reserved for official comments.)



PRIMARY RECORD

Primary #	
HRI #	
Trinomial	
NDUD Status Code 592	

Other Listings Upd	date of November	1988 Centre	City East Surve	y Documentation
Review Code	Revie	wer	Date	9

Page 1 of 2 *Resource Name or #: (Assigned by recorder) 420 17th Avenue /424 17th Avenue P1. Other Identifier:

*P2. Location: □ Not for Publication ■ Unrestricted * a. County San Diego_______
and (P2b and P2c or P2d. Attach a Location Map as necessary.)
*b. USGS 7.5' Quad Point Loma______Date_____T ____; R ____; ___¼ of ____¼ of Sec___; _____B.N


*b. USGS 7.5' Quad <u>Point Loma</u> <u>Date</u> <u>T</u>; <u>R</u>; <u>¼ of ¼ of Sec</u>; <u>B.I</u> c. Address _____420 17th Avenue / 424 17th Avenue City San Diego _ Zip 92101_

d. UTM: (Give more than one for large or linear resources) Zone 11; _____ mE/ ___mN
 e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-393-08-00, Sherman's Addition, Block 21, All Lot & EXC S 30 Page 1986.

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1894, this single-story, single-family residence was designed in a Folk National architectural style. It has a general square shaped plan, and features a moderately pitched, pyramidal hipped roof, with a boxed cornice and plain frieze. The northeast corner of the residence features a recessed, open porch with a low, partial wall portion and a wood poet for support. Windows appear to be single-or-double-hung sash and are covered with iron security bars. A large, focal window is present on the east, street facing elevation, and it features three window sections, most likely a center fixed portion, flanked by a single-or-double hung window on either side. Exterior building materials consist of composition shingles for the roof and horizontal clapboard siding for the exterior walls. Overall, the residence appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP2

*P4. Resources Present: I Building ☐ Structure ☐ Object d Site d District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

D Prehistoric d Both

C.1894

1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

Abel Arreola 1345 Grove

_San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Burke Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: March 2001 / Owner Information and Photo Updated June 2003

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre

City East For Centre City Development Corporation_

Attachments: UNONE Uncation Map n Sketch Map Uncontinuation Sheet Uncontinuation Sheet Uncord Building, Structure, and Object Record n Archaeological Record n District Record Uncord Linear Resource Record D Milling Station Record n Rock Art Record

☐ Artifact Record a Photograph Record n Other (List):

State of California — The Resources Agency Primary # DEPARTMENT OF PARKS AND RECREATION HRI#	
BUILDING, STRUCTURE, AND OBJECT RECO	RD
	itus Code 5S2
*Resource Name or # (Assigned by recorder)420_17 th Avenue.	
B1. Historic Name: The George Selwyn Residence	
B2. Common Name: The Catalino P. Bernardo Residence	
B3. Original Use: Residential (Single-Family)_ B4. Pr	esent Use: Residential (Single-Family)
*B5. Architectural Style: Folk National	
*B6. Construction History: (Construction date, alternations, and date of Originally constructed in approximately 1894; no major a	alterations and/or modifications noted.
*B7. Moved? ■ No □Yes □Unknown Date:Original	I Location:
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u> *B10. Significance: Theme Architecture Area San Diego	Period of Significance 1894
Property Type Residential Applicable C	
(Discuss importance in terms of historical or architectural context as defined by theme, pe	
Originally constructed in 1894, this building was p	
the supervision of the Office of Marie Lia and Dr. Ray I property and building include: George M. & Ada Selwyn	
(1923-date unknown), and Catalino P. Bernardo (c.1955 to	
17 th Avenue residence include: George & Ada Selwyn (1894-	-1923), Antonio & Josephine Malavenda (1923-
1924), J.E. Harvey (1944/1945), owner Catalino P. Bernardo	
Catalino P. Bernardo (1960, 1965, 1969/1970, 1975, 1980 George Selwyn was butcher and branch manager for the C.S	
operated both a furniture business and grocery business	
repairman.	
significant, as it is not directly associated with any in local, state, or national history. The 420 17th Aven architecturally significant, at the local level, as characteristics of a type, period, or method of the Pyra As the identities of the architect or builder could represent the work of a master architect, master builder	aue building, however, is considered to be a building which embodies the distinctive amidal Family of Folk National construction. not be ascertained, the building does not
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list)	+ 1000
Lia & Brandes, Historic Site Inventory of Centre City Eas McAlester, Virginia & Lee, A Field Guide To American Hou	
San Diego City Directories	2027 1700.
San Diego County Recorders Office	
B13. Remarks:	(Sketch Map with north arrow required.)
*	ISLAND (
*B14. Evaluator: Wendy L. Tinslev,	
Office of Marie Burke Lia	, (3) 1 12 "
Date of Evaluation: March 2001	
	, 2, 10 m
	+ + + + + + + + + + + + + + + +
This area was a few Wilders and N	
(This space reserved for official comments.)	BLK, 51
	393
	A CO
	H. C.

PRIMARY RECORD

Primary #		
HRI #_2138-0442	-0000	
Trinomial		
NRHP Status Code	5S2	

Other Listings	Update of November 1	988 Centre City East	Survey Documentation
Review Code	Reviewer		Date

Review Code Reviewer Date

Page 1 of 2 *Resource Name or #: (Assigned by recorder) 430 17th Avenue

P1. Other Identifier:

*P2. Location:
Not for Publication • Unrestricted *

a. County San Diego_
and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma _____ Date ____ T ___; ___¼ of ___¼ of Sec__; _____B.M.

c. Address 430 17th Avenue City San Diego Zip 92101

d. UTM: (Give more than one for large or linear resources) Zone ___; ____ mE/ __m

e. Other Locational Data (e.g., parcel # directions to resource elevation etc. as appropriate):

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 535-393-09-00, Lot 9, Block 21

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1889, this one-and-one-half story, single-family residence was designed in a Victorian Second Empire vernacular architectural style. It features a mansard style roof, a boxed cornice with a dentil band, two inset dormers with gabled pediments on the east elevation roof, a center front entry door with an upper transom above, and a centered second floor balcony supported by posts and brackets which form a small partial porch area at the front entrance. Windows types vary between double-hung sash with iron security bars on the first floor, and double-hung sash with a multi-pane sash pattern on the second story dormers. An interior end chimney is present on the south elevation, and an entry door to the second floor balcony with a gabled pediment is also present. -Exterior building materials consist of composition shingles for the roof, and stucco-on-lath for the exterior walls. Overall, this residence appears to be in fair condition.



P3b. Resource Attributes: (List attributes and codes) HP2_____

*P4. Resources Present: ■ Building □ Structure D Object a Site □ District a Element of District □ Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

D Prehistoric D Both 1889

1988 Centra City East Historic Site Inventory

*P7. Owner and Address

Ned and Nigel Roundtree

430 17th Street

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101_____.

*P9. Date Recorded: March 2001

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none". Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: a NONE a Location Map a Sketch Map □ Continuation Sheet ■ Building, Structure, and Object Record D Archaeological Record □ District Record a Linear Resource Record a Milling Station Record □ Rock Art Record a Artifact Record a Photograph Record a Other (List):

Otato of California The Decourse Assessed Britana #	e
State of California — The Resources Agency Primary #	8-0442-0000
BUILDING, STRUCTURE, AND OBJECT RECO	
Page 2 of 2 *NRHP Status	Costs2
*Resource Name or # (Assigned by recorder) 430 17 th A	
B1. Historic Name: Henry & Hilda	Thomas Residence
B2. Common Name:	
B3. Original Use: Residential (Single-family) B4. P	resent Use: Residential (Single-family)
	oire vernacular
*B6. Construction History: (Construction date, alternations, and date	of alterations)
Constructed in 1889; first floor partial porch area and s	
awnings over second floor windows and door present in 1988 phot exterior stucco work (date unknown).	ograph have been removed (date unknown), recent
*B7. Moved? No □ Yes □Unknown	Date: Original Location:
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	8
*B 10. Significance: Theme Architecture Area San Diego	
Property Type Residential Applicable C (Discuss importance in terms of historical or architectural context as defined by theme, p	
(Discuss importance in terms of historical of architectural context as defined by theme, p	eriou, and geographic scope. Also address integrity.)
Originally constructed in 1889, this building was per the supervision of the Office of Marie Lia and Dr. Ray Bracowners of the 430 17 th Avenue property and building incl (1889-1891), J.H. & Alice McNeil (1891-1901), teacher Luc Re (1907-dateunknown), and Christine Hendricks (1988). was a brick mason, and J.H. McNeil, a noted capitalist Southern Railroad in 1884. Prior to purchasing the 430 Ceanside, where he owned land and a store. San Diego of the 430 17 TH Avenue building include: owner Mrs. F.R. (1950-1980), with J.C. Omega (1950), Joe Franciso (1965). Historical research has determined that the 430 significant, as it is not associated with any important state, or national history. However, the residence does the local level as a building which or hading the diegonal level.	ndes. Previous documentation indicates past rude: German Immigrants Henry & Hilda Thomas cia P. Woods (1901-1907), grocer Charles del Past documentation states that Henry Thomas t, had been a conductor for the California 30 17 th Avenue residence, McNeil resided in City Directories reveal that past residents. Padillo (1944/1945), owner Alberto Llanes), and Norman Ramirez (1969/1970).
at the local level, as a building which embodies the dis or method of the Victorian Second Empire vernacular ar identity of the architect could not be ascertained, the the work of a master architect or craftsman.	chitectural style of construction. As the
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list)	
Lia and Brandes, Historic Site Inventory of Centre City	East, 1988.
McAlester, Virginia & Lee, A Field Guide To American Hot	uses, 1986.
San Diego City Directories San Diego County Regarders Office	
San Diego County Recorders Office B13. Remarks:	
bio. Remarks.	
*B14. Evaluator: Wendy L. Tinsley,	(Sketch Map with north arrow required.)
Office of Marie Burke Lia	ISLAND
Date of Evaluation: March 2001	
	, (3) 1 12 .
	2) 2 3 11
(This space reserved for official comments.)	BLK' 21

3

5 5 5

\$

PRIMARY RECORD

Primary #		
HRI #		
Trinomial		
NRHP Status Code_	5S2	

Other Listings	Update of November	1988	Centre	City East	Survey Documentation
Review Code	Reviewer_				Date

Page ____ of ___ *Resource Name or #: (Assigned by recorder) 454 17th Avenue____

P1. Other Identifier:

*P2. Location: a Not for Publication Unrestricted * a. County San Diego

and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad <u>Point Loma</u> <u>Date</u> T ; R ; <u>¼ of _ ¼ of Sec_ ; B.M.</u> c. Address <u>454 17th Avenue City San Diego</u> Zip <u>92101</u>

d. UTM: (Give more than one for large or linear resources) Zone __; ____ mE/ __ml

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 535-393-11-00, Sherman's Addition, Block 21, Lot 11

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1890, this single-story, single-family residence was designed in a Folk Victorian architectural style. It has a general square shaped plan and features a moderately pitched, truncated and pyramidal hipped roof, with a slight enclosed eave overhang, and an ornamental center gabled dormer. An enclosed, nearly full-length front porch is present, and features a flat roof, a fishscale-shingles frieze, turned wooden spindle posts for support, and a low wall which partially encloses the porch area. Metal security bars fill in the space between the porch wall and porch roof line, and metal bars also appear to be present on all windows around the residence. Exterior building materials consist of composition shingles for the roof, and horizontal clapboard siding for the exterior walls. Windows appear to be double-hung sash. Overall, the exterior of the residence appears to be in fair condition.



P3b. Resource Attributes: (List attributes and codes) HP2

*P4. Resources Present: • Building c

Structure Object Site D District c Element of District D Other (Isolates, etc.)

P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

- Historic
- □ Prehistoric

a Both

1890

1988 Centra City East Historic Site Inventor

*P7. Owner and Address

Simon and Associates LLP

3063 Dalen Place

San Diego, CA 92122

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley_Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101_

*P9. Date Recorded: March 2001 / Owner Information and Photo Updated June 2003

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: □NONE D Location Map a Sketch Map n Continuation Sheet ■ Building, Structure, and Object Record n Archaeological Record D District Record n Linear Resource Record a Milling Station Record n Rock Art Record □ Artifact Record n Photograph Record □ Other (List):

State of California — The Resources Agency Primary # DEPARTMENT OF PARKS AND RECREATION HRI#	N. C.
BUILDING, STRUCTURE, AND OBJECT RECO	ORD
Page 2 of 2	*NRHP Status Code
*Resource Name or # (Assigned by recorder) 454 17 th Avenue,	
B1. Historic Name: Theodore	Olsen House
B2. Common Name: Zenobia Watley Residence	
B3. Original Use: Residential (Single-Family) B4. P	resent Use: Residential (Single-Family)
*B5. Architectural Style: Folk Vic	torian
*B6. Construction History: (Construction date, alternations, and date Constructed in 1890; no substantial alterati	
*B7. Moved? No ☐ Yes ☐ Unknown Date: Original	inalLocation:
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Jobbitt & Scha</u> *B10. Significance: Theme Architecture Area <u>San Diego</u>	
Property Type Residential Applicable C	
(Discuss importance in terms of historical or architectural context as defined by theme, p	period, and geographic scope. Also address integrity.)
Originally constructed in 1890, this building was	
the supervision of the Office of Marie Lia and Dr. Ray Bra past owners of the 454 17 th Street property and building i	
& Ada Olsen (1895-1932), James F. & Adele Lamond (1932	
Zenobia Watley (c.1955-present) . San Diego City Direct	tories reveal that past residents of the 454
17^{TE} Street building include: Henry Dietrich and Benjamin	
owner Mrs. Zenobia Watley (1955), Eddie Nicholson (1960)	, and again owner Zenobia Watley (1965-1984).
Historical research has determined that the 454	17 th Street building is not historically
significant, as it is not associated with any importar	
state, or national history. However, it does appear to be	be architecturally significant, as a building
which embodies the distinctive characteristics of a	
construction. As the identity of the architect could not	
does not represent the work of a master architect or construction. Brothers, does not rise to the level of a master builde	
Districts, does not rise to the rever of a master surface	
B11. Additional Resource Attributes: (List attributes and codes)	•
*B12. References: (partial list)	
Lia and Brandes, Historic Site Inventory of Centr	
McAlester, Virginia & Lee, A Field Guide To Ameri	can Houses, 1986.
San Diego City Directories	
San Diego County Recorders Office	
B13. Remarks:	
bio. Remarks.	(Sketch Map with north arrow required.)
	(Oketeri wap with horiti arrow required.)
*B14. Evaluator: Wendy L. Tinslev	ISLAND
Office of Marie Burke Lia	
Date of Evaluation: March 2001	(C) 12"
	(1) (1)
(This space reserved for official comments.)	BLK, 51
	5 333
	a
1	

		_	
IN/I	RY		١

Primary #	
HRI #	
Trinomial	
NPUP Status Codo 592	

Other Listings Upd	ate of	November	1988	Centre	City	East	Survey	Documentation
Daviou Codo		Daviou					Doto	

P1. Other Identifier:

*P2. Location: a Not for Publication ■ Unrestricted * a. County San Diego______

and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma Date T ; R ; M of M of Sec ; B.M.

c. Address 470 17th Avenue City San Diecro Zip 92101
d. UTM: (Give more than one for large or linear resources) Zone 11; mE/ __mN

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-393-13-00, Sherman's Addition, Block 21, All of Lot 1, N 3' of Lot 2, and All of Lot 12

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1904, this single-story, single-family residence was designed in a Folk National architectural style. It has a general square shaped plan, and features a moderately pitched, hipped roof, with flaired eaves, a boxed cornice and plain frieze. A partial porch area is present on the east elevation, and features a low, partial wall portion with wood posts for support. Windows appear to be single or double-hung, some with an upper multi-pane sash pattern. An angled bay on the east elevation serves as the focal point for the residence. Exterior building materials consist of composition shingles for the roof and horizontal clapboard siding for the exterior walls. Overall, with the exception of the roof, the residence appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP2

*P4. Resources Present: I Building d Structure d Object d Site d District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

d Prehistoric d Both 1904

1983 Centra City East Historic Site Inventory

*P7. Owner and Address:

God's Extended Hand

P.O. Box 989

San Diecro, CA 92112

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Burke Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: March 2001

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) __Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: "NONE n Location Map Sketch Map Continuation Sheet Building, Structure, and Object Record n Archaeological Record District Record n Linear Resource Record District Record n Rock Art Record a Artifact Record n Photograph Record District Clist):

DIMIDING OFFICE AND AD THAT THE	ODD
BUILDING, STRUCTURE, AND OBJECT REC	7.70
Page 2 of 2 *NRHP S *Resource Name or # (Assigned by recorder) 470 17 th Avenu	tatus Code. 5S2
B1. Historic Name: The Stewart House	
B2. Common Name:	Dresent Heat Desidential (Cincle Benilly)
B3. Original Use: Residential (Single-Family) B4. *B5. Architectural Style: Folk National	Present Use: Residential (Single-Family)
*B6. Construction History: (Construction date, alternations, and dat	e of alterations)
Originally constructed in approximately 1904; ang	
*B7. Moved? No Yes Unknown Date:Origin	
*B8. Related Features:	100000000000000000000000000000000000000
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: Theme Architecture_ Area San Diego	o Period of Significance 1904_
Property Type Residential Applicable	
Discuss importance in terms of historical or architectural context as defined by theme,	periou, and geographic scope. Also address integrity.)
Originally constructed in approximately 1904, this 1988 under the supervision of the Office of Marie Lia 17th Street property and building include: Julia V. Stew (1907-at least 1910), and Isiah & Ethel Soloman (c.19 residence include: Mrs. C.H. Verdugo (1944/1945), Virg. Paul A. Valencia (1960), William Q. Cano (1965), and Je According to past documentation, Julia Stewart, who al throughout San Diego County, was well known for her laws Joseph Sefton. The suit alleged that Sefton had remove property for the purpose of constructing the flume	and Dr. Ray Brandes. Past owners of the 47 art (c.1904-1907), James S. & Martha Thompso 220s). Past residents of the 470 17 th Street 1 Phillips (1950), Orlando R. Carter (1955 esus J. Molina (1969/1970, 1975, 1980, 1984) ong with this property, owned other properties wit against San Diego Flume Company President 2 lemon trees from Stewart's Spring Vallethrough that area. Past documentation also
indicates that Stewart did not ever reside at 470 17 th Sits early days" (Lia/Brandes:1988).	
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or nodoes, however, appear to be architecturally significate embodies the distinctive characteristics of a type, perconstruction. As the identities of the architect or but the significant of the	17 th Street building is not historicall be been directly associated with any important ational history. The 470 17 th Avenue building that, at the local level, as a building which with a could not be ascertained, the building which is the could not be ascertained.
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or nodoes, however, appear to be architecturally significate embodies the distinctive characteristics of a type, per construction. As the identities of the architect or but does not represent the work of a master architect, mass	17 th Street building is not historicall be been directly associated with any important ational history. The 470 17 th Avenue building int, at the local level, as a building which with a the local field. The folk National style outlider could not be ascertained, the building
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or n does, however, appear to be architecturally significal embodies the distinctive characteristics of a type, pe construction. As the identities of the architect or but does not represent the work of a master architect, mass	17 th Street building is not historicall be been directly associated with any important ational history. The 470 17 th Avenue building that, at the local level, as a building which with a three three priority or method of the Folk National style outlider could not be ascertained, the building
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or n does, however, appear to be architecturally significal embodies the distinctive characteristics of a type, per construction. As the identities of the architect or building not represent the work of a master architect, mass B11. Additional Resource Attributes: (List attributes and codes)	17 th Street building is not historicall be been directly associated with any important ational history. The 470 17 th Avenue building int, at the local level, as a building which wriod, or method of the Folk National style of a builder could not be ascertained, the building ter builder, or master craftsman.
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or nodoes, however, appear to be architecturally significate embodies the distinctive characteristics of a type, per construction. As the identities of the architect or but does not represent the work of a master architect, mass	17 th Street building is not historicall be been directly associated with any important ational history. The 470 17 th Avenue building the nt, at the local level, as a building which with the notation of the Folk National style of the could not be ascertained, the building ter builder, or master craftsman. Bast, 1988.
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or nodoes, however, appear to be architecturally significate embodies the distinctive characteristics of a type, personstruction. As the identities of the architect or buildoes not represent the work of a master architect, massistant and codes. B11. Additional Resource Attributes: (List attributes and codes) *B12. References: (partial list) Lia & Brandes, Historic Site Inventory of Centre City of McAlester, Virginia & Lee, A Field Guide To American Education Diego City Directories	17 th Street building is not historically been directly associated with any important ational history. The 470 17 th Avenue building ont, at the local level, as a building which ariod, or method of the Folk National style chailder could not be ascertained, the building ter builder, or master craftsman. Bast, 1988. Bouses, 1986.
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or nodoes, however, appear to be architecturally significate embodies the distinctive characteristics of a type, per construction. As the identities of the architect or buildoes not represent the work of a master architect, mass and codes are perfectly as a Brandes, Historic Site Inventory of Centre City of McAlester, Virginia & Lee, A Field Guide To American Estan Diego City Directories	o 17th Street building is not historically been directly associated with any important ational history. The 470 17th Avenue building the nt, at the local level, as a building which wilder could not be ascertained, the building ter builder, or master craftsman. Bast, 1988.
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or nodoes, however, appear to be architecturally significate embodies the distinctive characteristics of a type, per construction. As the identities of the architect or buildoes not represent the work of a master architect, mass and codes. B11. Additional Resource Attributes: (List attributes and codes) *B12. References: (partial list) Lia & Brandes, *Historic* Site* Inventory of Centre City* McAlester, Virginia & Lee, A Field Guide To American Estan Diego City Directories San Diego County Recorders Office	17th Street building is not historicall be been directly associated with any important ational history. The 470 17th Avenue building that the local level, as a building which wriod, or method of the Folk National style of ailder could not be ascertained, the building ther builder, or master craftsman. Bast, 1988. Touses, 1986. (Sketch Map with north arrow required.)
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or nodoes, however, appear to be architecturally significate embodies the distinctive characteristics of a type, per construction. As the identities of the architect or buildoes not represent the work of a master architect, mass and allowed the first of the architect of the construction. As the identities of the architect or buildoes not represent the work of a master architect, mass and allowed the construction of the architect of the construction of the architect of the architect of the architect of the construction of the architect of the construction of the architect of the construction of the architect of the architect of the construction of the architect of the architect of the construction of the architect	17 th Street building is not historically been directly associated with any important ational history. The 470 17 th Avenue building ont, at the local level, as a building which ariod, or method of the Folk National style chailder could not be ascertained, the building ter builder, or master craftsman. Bast, 1988. Bouses, 1986.
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or nodoes, however, appear to be architecturally significate embodies the distinctive characteristics of a type, per construction. As the identities of the architect or buildoes not represent the work of a master architect, mass and solves. B11. Additional Resource Attributes: (List attributes and codes) *B12. References: (partial list) Lia & Brandes, *Historic* Site* Inventory of Centre City* McAlester, Virginia & Lee, A Field Guide To American Estan Diego City Directories San Diego County Recorders Office	2) 17 th Street building is not historically been directly associated with any important ational history. The 470 17 th Avenue building int, at the local level, as a building which ariod, or method of the Folk National style of a uilder could not be ascertained, the building ter builder, or master craftsman. Bast, 1988. Houses, 1986. (Sketch Map with north arrow required.)
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or notices, however, appear to be architecturally significated embodies the distinctive characteristics of a type, per construction. As the identities of the architect or buildies not represent the work of a master architect, mass and all a	2) 17th Street building is not historically been directly associated with any important ational history. The 470 17th Avenue building the nt, at the local level, as a building which wrick, or method of the Folk National style chailder could not be ascertained, the building ter builder, or master craftsman. Bast, 1988. Bast, 1988. Bouses, 1986. (Sketch Map with north arrow required.)
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or not does, however, appear to be architecturally significated embodies the distinctive characteristics of a type, per construction. As the identities of the architect or buildies not represent the work of a master architect, mass and a state and codes. B11. Additional Resource Attributes: (List attributes and codes) B12. References: (partial list) Lia & Brandes, Historic Site Inventory of Centre City of Calester, Virginia & Lee, A Field Guide To American House San Diego City Directories San Diego County Recorders Office B13. Remarks: B14. Evaluator: Wendy L. Tinsley, Office of Marie Burke Lia	been directly associated with any important ational history. The 470 17 th Avenue building int, at the local level, as a building which ariod, or method of the Folk National style chailder could not be ascertained, the building ter builder, or master craftsman. Bast, 1988. Houses, 1986. (Sketch Map with north arrow required.) ISLAND
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or notices, however, appear to be architecturally significated embodies the distinctive characteristics of a type, personstruction. As the identities of the architect or buildies not represent the work of a master architect, mass and a series of the architect of the does not represent the work of a master architect, mass and a series of the architect of the does not represent the work of a master architect, mass and a series of the architect of the does not represent the work of a master architect, mass and a series of the architect of the does not represent the work of a master architect, mass and a series of the architect of the does not represent the work of a master architect, mass and a series of the architect of the architect of the does not represent the work of a master architect of the does not represent the work of a master architect of the does not represent the work of a master architect of the does not represent the work of a master architect of the does not represent the work of a master architect of the does not represent the work of a master architect of the does not represent the work of a master architect of the does not represent the work of a master architect of the does not represent the work of a master architect of the does not represent the work of a master architect of the does not represent the work of a type, person the does not represent the work of a type, person the does not represent the work of a type, person the does not represent the work of a type, person the does not represent the work of a type, person the does not represent the work of a type, person the does not represent the work of a type, person the does not represent the work of a type, person the does not represent the work of a type, person the does not represent the work of a type, person the does not represent the work of a type, person the does not represent the wore	D 17th Street building is not historically been directly associated with any important ational history. The 470 17th Avenue building that, at the local level, as a building which ariod, or method of the Folk National style childer could not be ascertained, the building ter builder, or master craftsman. Bast, 1988. Houses, 1986. (Sketch Map with north arrow required.) ISLAND
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or not does, however, appear to be architecturally significated embodies the distinctive characteristics of a type, per construction. As the identities of the architect or building not represent the work of a master architect, mass and a state and codes. B11. Additional Resource Attributes: (List attributes and codes) FB12. References: (partial list) Lia & Brandes, Historic Site Inventory of Centre City of Callester, Virginia & Lee, A Field Guide To American House and Diego City Directories San Diego County Recorders Office B13. Remarks: FB14. Evaluator: Wendy L. Tinsley, Office of Marie Burke Lia	been directly associated with any important ational history. The 470 17 th Avenue building int, at the local level, as a building which ariod, or method of the Folk National style childer could not be ascertained, the building ter builder, or master craftsman. Bast, 1988. Souses, 1986. (Sketch Map with north arrow required.)
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or nodoes, however, appear to be architecturally significate embodies the distinctive characteristics of a type, per construction. As the identities of the architect or buildoes not represent the work of a master architect, mass and solves. B11. Additional Resource Attributes: (List attributes and codes) *B12. References: (partial list) Lia & Brandes, Historic Site Inventory of Centre City McAlester, Virginia & Lee, A Field Guide To American House San Diego County Recorders Office B13. Remarks: *B14. Evaluator: Wendy L. Tinsley,	2) 17th Street building is not historically been directly associated with any important ational history. The 470 17th Avenue building that, at the local level, as a building which ariod, or method of the Folk National style coulder could not be ascertained, the building ter builder, or master craftsman. Bast, 1988. (Sketch Map with north arrow required.) ISLAND ISLAND
Historical research has determined that the 470 significant, as the building does not appear to have events, or individuals in terms of local, state, or no does, however, appear to be architecturally significate embodies the distinctive characteristics of a type, per construction. As the identities of the architect or buildoes not represent the work of a master architect, mass as a self-self-self-self-self-self-self-self-	been directly associated with any important ational history. The 470 17 th Avenue building int, at the local level, as a building which ariod, or method of the Folk National style childer could not be ascertained, the building ter builder, or master craftsman. Bast, 1988. Souses, 1986. (Sketch Map with north arrow required.)

PRIMARY RECORD

Primary #	
HRI #	
Trinomial	

	NRHP Status (Code	5S2_			
har Listings	IIndate	of November	1000	Centre	City Fact	Current Dogumentation

Other Listings Update of November 1988 Centre City East Survey Documentation

Review Code _____ Reviewer ____ Date _____

Page 1 of 2 *Resource Name or #: (Assigned by recorder) 505 17th Avenue

P1. Other Identifier:

*P2. Location: □ Not for Publication ■ Unrestricted *

a. County San Diego_______

and (P2b and P2c or P2d. Attach a Location Map as necessary.)

*b. USGS 7.5' Quad Point Loma Date T; R; ¼ of ¼ of Sec; B.M.
c. Address 505 17th Avenue City San Diego Zip 92101

d. UTM: (Give more than one for large or linear resources) Zone __; ____ mE/ __mN

e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 535-190-14-00, S 32 Ft of W ½ Lot 6, Block 15

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1887, this single-story, **single-family** cottage was designed in the Queen Anne architectural style. It has a general rectangular shaped plan and features a moderately pitched, truncated, hipped roof with a slight, enclosed eave overhang, and an offset cross gable on the north facing portion of the roof line. An open entry porch is present and features a hipped roof, supportive wooden posts with **brackets**, and iron railing. Exterior building materials consist of composition shingles for the **roof**, fish scale shingles for the gabled portion siding, and shiplap siding with corner boards for the exterior walls. Windows are double-hung sash and feature wood **surrounds**. A low iron fence borders the property, and matches the front porch railing as **well** as the metal roof cresting. Overall, the exterior of this building appears to be in excellent condition.



P3b. Resource Attributes: (List attributes and codes) HP2

~ *P4. Resources Present: • Building D Structure □ Object a Site a District a Element of District □ Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

□ Prehistoric c.1887

□ Both

1988 Centre city East Historic Site Inventory

*P7. Owner and Address

Michael D. Highfill

505 17th Avenue_

San Diego, CA 92101_

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: April 2001

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments:

NONE c Location Map D Sketch Map a Continuation Sheet • Building, Structure, and Object Record D Archaeological Record a District Record a Linear Resource Record

Milling Station Record Rock Art Record Artifact Record a Photograph Record D Other (List):

State of California—	TheResou	rces Agency
DEPARTMENT OF P	ARKS AND	RECREATION

Primary #	
HRI#	

BUILDING, STRUCTURE, AND OBJECT RECORD

Page 2 of 2

*NRHP Status Code 5S2

*Resource Name or # (Assigned by recorder) 505 17th Avenue, San Diego, CA 92101

B1. Historic Name: Norris Rental

B2. Common Name: William B. Norris Spec. House #1

B3. Original Use: Residential B4. Present Use: Residential

*B5. Architectural Style: Oueen Anne Cottage

*B6. Construction History: (Construction date, alternations, and date of alterations)

Constructed in approximately 1887; no substantial alterations and/or modifications noted.

*B7. Moved? □ No B Yes □Unknown Date: Between approximately 1921-1940 Original Location: Unknown_

*B8. Related Features:

B9a. Architect: Unknown b. Builder: Unknown

*B10. Significance: Theme N/A Area San Diego Period of Significance 1887_

Property Type Residential Applicable Criteria C

(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

Originally constructed in approximately 1887 and moved to the current site between 1921 and 1940, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Previous documentation indicates past owners of the 505 17th Avenue property and building include: William B. Frisbee (pre-1872), William B. Norris and various members of the Norris Family (1872-1940). According to past documentation William B. Norris worked as a carpenter, and had relocated several other residences to this area on 17th Avenue (Lia/Brandes:1988). Past residents of 505 17^{TE} Avenue include: E.L. Winkler (1950), Morris Wroclawski (1955), owner Joseph Koffler (1960), Joe Chavez (1965), Mrs. Socorro Flores (1969/1970), vacant (1975), and Pilar Hernan lez (1980, 1984).

Historical research has determined that the 505 17th Avenue building is not historically **significant**, as the building is not associated with any important events or individuals in terms of local, state, or national history. However, the residence does appear to be architecturally significant, as a building which embodies the distinctive characteristics of a type, period, or method of the Queen Anne architectural style of **construction**. As the identity of the architect could not be ascertained, the 505 17th Avenue residence does not represent the work of a master architect or **craftsman**.

B11. Additional Resource Attributes: (List attributes and codes)

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office


B13. Remarks:

*B14. Evaluator: Wendy L. Tinslev,

Office of Marie Burke Lia

Date of Evaluation: April 2001

(This space reserved for official comments.)



PRIMARY RECORD

Primary #	
HRI #	
Trinomial	
NRHP Status Code 67	


			NRHP Status Cod	e_6Z		
		Other Listings Update of	November 1988 C	entre City East	Survey Document:	ation
		Review Code	Reviewer		Date	
Page	1 of2	*Resource Name or #: (Assigne	d by recorder)	508 17 th Avenue	e	
P1.	Other Identifie	er:				
*P2	Location: o Not for P	ublication <pre>Unrestricted *</pre>	a. County	San Diego		
and	(P2b and P2c or P2d. Att	ach a Location Map as necessary.)			
*b.	USGS 7.5' Quad Po		T; R;_	% of% of	Sec;	B.W
C.	Address	508 17 th Avenue	CitySan	Diego	Zip 92101	

UTM: (Give more than one for large or linear resources) Zone 11; _____ mE/ d. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-164-03-00, Sherman's Addition, Block 16, S 2/3 of Lot 7

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, andboundaries):

Originally constructed in approximately 1887, this single-story, single-family residence was designed in a Folk Victorian architectural style, and ia identical to the neighboring 512 17th Street residence. It has a general rectangular shaped plan, and features a moderately pitched, front gabled roof, with a full length front porch. The porch features a separate shed style, hipped roof with a plain frieze, turned spindle posts with ornamental brackets, and thin wood balusters. building materials consist of composition shingles for the roof, and stucco-on-lath for the exterior walls. Windows appear to be double-hung sash, and there are two east elevation windows which serve as a focal point for the residence. Metal security bars cover these windows, and an attic vent is present on the front gable of the residence. Overall, this residence appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP2

*P4. Resources Present: | Building D Structure D Object O Site D District D Element of District Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

D Prehistoric c.1887

□ Both

1988 Centre City East Historic Site Inventory *P7. Owner and Address:

<u> Virginia Hueso Trust 07-17-97</u>

1228 Edgemont Street

San Diego, CA 92102

*P8. Recorded by (Name, affiliation, and Wendy L. Tinsley, address): Burke Lia, Office of Marie Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

Date Recorded: March 2001 / Photo Updated June 2003

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) <u>Historic Site Inventory of Centre</u> City East For Centre City Development Corporation

Attachments: NONE Location Map Sketch Map Continuation Sheet Building, Structure, and Object Record ☐ Archaeological Record ☐ District Record n Linear Resource Record ☐ Milling Station Record D Rock Art Record n Artifact Record n Photograph Record n Other (List):

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION Primary #
BUILDING, STRUCTURE, AND OBJECT RECORD
Page 2 of 2 *NRHP Status Code 6Z *Resource Name or # (Assigned by recorder) 508 17 th Avenue, San Diego, CA 92101
B1. Historic Name: Falkenstein Residence
B2. Common Name:
B3. Original Use: Residential (Single-Family) B4. Present Use: Residential (Single-Family)
*B5. Architectural Style: Folk Victorian
*B6. Construction History: (Construction date, alternations, and date of alterations) Originally constructed in approximately 1887; metal bars added over windows, original wood siding stuccoed over (dates unknown). No other major alterations and/or modifications noted.
*B7. Moved? No
*B8. Related Features: neighboring 512 17 th Avenue residence.
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u> *B10. Significance: Theme N/A Area San Diego Period of Significance 1887_
Property Type Residential Applicable Criteria N/A_
(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)
Originally constructed in approximately 1887, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past documentation reveals little information about the history of this residence or its past owners and occupants. There is no indication as to how the historic name of the 508 17 th Avenue residence, the "Falkenstein Residence," was ascertained by past historians, as past documentation states only "This house was included on the 1940 Sanborn Fire Insurance Map, and was probably moved to this lot. It is very similar to the one at 512 17 th Avenue." San Diego City Directories reveal past residents of 508 17 th Avenue include Mrs. E.M. Cox (1944/1945), J.P. Klespitz (1950), Hector R. Garcia (1955), Juan Hurtavo (1960, 1965), Mrs. Regina Sanchez (1969/1970), Miguel Sosa (1975), Evalia Sosa (1980), and Maria E. Ruiz (1984).
Historical research has determined that the 508 17 th Avenue building is neither historically nor architecturally significant. It is not a building which has been directly associated with any important events, or individuals in terms of local, state, or national history, and it is not a building which embodies the distinctive characteristics of a type, period, or method of Folk Victorian construction. As the identities of the architect or builder could not be ascertained, the building does not represent the work of a master architect, master builder, or master craftsman. This building is not eligible for listing with the local register.
B1 1. Additional Resource Attributes: (List attributes and codes) *B12. References: (partial list) Lia and Brandes, Historic Site Inventory of Centre city East, 1988. McAlester, Virginia and Lee, A Field guide To American Houses, 1986.
San Diego City Directories San Diego County Recorders Office (Sketch Map with north arrow required.)


Lia and Brandes, Historic Site Inventory of Centre city McAlester, Virginia and Lee, A Field guide To American San Diego City Directories
San Diego County Recorders Office

B13. Remarks:

*B14. Evaluator: Wendy L. Tinsley,
Office of Marie Burke Lia

Date of Evaluation: March 2001

(This space reserved for official comments.)



PRIMARY RECORD

Primary #	
HRI #	
Trinomial	
NRHP Status Code 6Z	

Ot	her Listings	Update	of	November	1988	Centre	City	East	Survey	Documentation
	Review Co			Revie					Date	

*Resource Name or #: (Assigned by recorder) 512 17th Avenue Page Other Identifier: P1.

San Diego a. County Location: D Not for Publication Unrestricted *

and (P2b and P2c or P2d. Attach a Location Map as necessary.) _; R ____; __% of ___% of Sec ___; _ Point Loma Date T_ *b. USGS 7.5' Quad

512 17th Avenue Address City San Diego Zip 92101 d.

UTM: (Give more than one for large or linear resources) Zone 11; mE/ Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

APN: 535-164-03-00, Sherman's Addition, Block 16, N 1/3 of lot 7 & S 1/3 of Lot 8 Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting,

and boundaries):

Originally constructed in approximately 1900, this single-story, single-family residence was designed in a Folk Victorian architectural style, and is identical to the neighboring 508 17^{th} Street residence. It has a general rectangular shaped plan, and features a moderately pitched, front gabled roof, with a full length front porch. The porch features a separate shed style, hipped roof with a plain frieze, turned spindle posts with ornamental brackets, and thin wood balusters. Exterior building materials consist of composition shingles for the roof, and stucco-on-lath for the exterior walls. Windows appear to be double-hung sash, and there are two east elevation windows which serve as a focal point for the residence. Metal security bars cover these windows, and an attic vent is present on the front gable of the residence. Overall, this residence appears to be in good condition.



P3b. Resource Attributes: (List attributes land codes) HP2

*P4. Resources Present: | Building d Structure d Object d Site d District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

d Prehistoric d Both c.1900

1388 Centre City East Historic Site Inventory

*P7. Owner and Address:

<u>Virginia Hueso Trust</u>

1228 Edgemont Street

San Diego, CA 92102

*P8. Recorded by (Name, affiliation, and <u>Wendy L. Tinsley,</u> <u>Marie Burke Lia,</u> address): Office

Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

Date Recorded: March 2001 / Photo Updated June 2003

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) __Historic Site Inventory of Centre City East For Centre City Development Corporation_

Attachments: PNONE a Location Map a Sketch Map Continuation Sheet Building, Structure, and Object Record n Archaeological Record n District Record D Linear Resource Record n Milling Station Record D Rock Art Record D Artifact Record n Photograph Record n Other (List):

DEPARTMENT OF PARKS AND RECREATION HRI#					
BUILDING, STRUCTURE, AND OBJECT RECO					
	tatus Code. 6Z				
*Resource Name or # (Assigned by recorder) 512 17 th Avenue					
B1. Historic Name: Rinehart Residence B2. Common Name:					
B3. Original Use: Residential (Single-Family) B4. Pr *B5. Architectural Style: Folk Victorian	Present Use: Residential (Single-Family)_				
*B6. Construction History: (Construction date, alternations, and date	e of alterations)				
Originally constructed in approximately 1900; metal					
siding stuccoed over (dates unknown). No other major al	alterations and/or modifications noted.				
*B7. Moved? No					
*B8. Related Features: neighboring 508 17 th Avenue resid	idence.				
	Period of Significance 1900_				
	Criteria N/A_				
(Discuss importance in terms of historical or architectural context as defined by theme, p	period, and geographic scope. Also address integrity.)				
Originally constructed in approximately 1900, this building was previously documented in November 1988 under the supervision of the Office of Marie Lia and Dr. Ray Brandes. Past documentation states "On March 5, 1878, Matthew Sherman sold the [512 17th Avenue] property to John Mumford; after several sales, on December 10, 1925, Charles E. Rhinehart signed a notice of completion for construction of a residence. Whether that notice of completion applied to this particular house or not, is uncertain, as this house appears to be of an earlier period. This house is an example of a modest Folk Victorian cottage. It is similar to the house next door at 508 17th Avenue" (Lia/Brandes:1988). Past documentation reveals little information about the history of the 508 17th Avenue residence or its past owners and occupants. Regarding the neighboring 508 17th Avenue residence, past documentation states only "This house was included on the 1940 Sanborn Fire Insurance Map, and was probably moved to this lot. It is very similar to the one at 512 17th Avenue." Given the relocation period between 1921 and 1940, it is possible that the 512 17th Avenue residence was the residence that Charles Rhinehart signed a notice of completion for in 1925, and most likely, both this residence and the neighboring residence were relocated to this location in 1925. San Diego City Directories reveal past residents of 512 17th Avenue include: Lillian F. Hansen (1944/1945), F.M. Gallindo (1950), Jose C. Chavez (1955), Joe Chavez (1960), Ricardo Adame (1965), Mrs. Refugio Godoy (1969/1970), Mrs. Regina A. Sanchez (1975, 1980), and Jose Maldonado (1984).					
B11. Additional Resource Attributes: (List attributes and codes	;S)				
*B12. References: (partial list) (See DPR 523H, Continuation Sheet for more information)					
	(Sketch Map with north arrow required.)				
B13. Remarks:	MARKET				
	WANTE				
	. 00 88				
*B14. Evaluator: Wendy L. Tinsley,	1 120				
Office of Marie Burke Lia					
Date of Evaluation: March 2001					
	BLK 16 日				
(This space reserved for official comments.)	BLK 16 E				
1	5 t				
1					
	3 6 7				

ISLAND

1

Primary #	
HRI #/Trinomial_	

CONTINUATION SHEET

■ Continuation
□ Update

Page __3 _ of __3

Resource Identifier: (Assigned by recorder) 512 17th Avenue, San Diego, CA 92101

Historic Name: Rhinehart Residence

*B10. Significance (Continued):

Historical research has determined that the 512 17th Avenue building is neither historically nor architecturally significant. It is not a building which has been directly associated with any important events, or individuals in terms of local, state, or national history, and it is not a building which embodies the distinctive characteristics of a type, period, or method of Folk Victorian construction. As the identities of the architect or builder could not be ascertained, the building does not represent the work of a master architect, master builder, or master craftsman. The building is not eligible for listing on the local register.

*B12. References (Continued):

Lia and Brandes, Historic Site Inventory of Centre City East, 1988.

McAlester, Virginia and Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office

				RF	^		
LJL	<i>_</i> , , , ,	/ /	\mathbf{L}		, 1	_	
	T 111	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	T	\mathbf{r}			

otate of Gamorina The Resources Agency	i ililially #				
DEPARTMENT OF PARKS AND RECREATION	HRI #				
PRIMARY RECORD	Trinomial	Trinomial			
	NRHP Statu	is Code 5S2			
Other L	istings <u>Update</u> of November	r 1988 Centre City East	Survey Documentation		
Review	CodeReview	er	Date		
Page 1 of 2 *Resource Name of	r #: (Assigned by recorde	r) 515 17 th Avenue			
P1. Other Identifier:					
P2. Location: D Not for Publication II Unrest	ricted a. Cou	unty San Diego			
and (P2b and P2c or P2d. Attach a Location Map	as necessary.)				

;R ; % of % of Sec ; B.M. *b. USGS 7.5' Quad Point Loma Date Address 515 17th Avenue City San Diego ____ Zip _____92101

Primary #

UTM: (Give more than one for large or linear resources) Zone d.

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): e. APN: 535-190-13-00, W 50' of S 17' of Lot 5 & W 50'/Exc S Lot 6, Block 15

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1900, this single-story, single-family residence was designed in a Folk Victorian architectural style. It has a general square shaped plan and features a moderately pitched, truncated and pyramidal hipped roof with metal roof cresting, a boxed cornice, and a plain frieze. Exterior building materials consist of composition shingles for the roof, shiplap siding for the west elevation exterior wall, and board and batten siding for the north and south elevation exterior walls. A front entry porch is present and features supportive wooden posts with ornamental brackets made of iron, and matching iron railing which partially encloses the porch area. Windows are double-hung sash with a vertical, multi-pane sash pattern. Overall, the exterior of this residence appears to be in excellent condition.



P3b. Resource Attributes: (List attributes and codes) HP2

Resources Present: • Building a Structure a Object

Site

District a Element of District a Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

Prehistoric □ Both

C.1900

1988 Centre City East Historic Site Inventory

*P7. Owner and Address

Fran S. Brooks 515 17th Street

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinslev, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: April 2001

*P10. Type of Survey: (Describe)_

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: D NONE D Location Map a Sketch Map a Continuation Sheet • Building, Structure, and Object Record D Archaeological Record a District Record a Linear Resource Record Milling Station Record a Rock Art Record □ Artifact Record n Photograph Record a Other (List):

State of California — The Resources Agency Prim	ary #
DEPARTMENT OF PARKS AND RECREATION HRIE	
BUILDING, STRUCTURE, AND OBJECT I	RECORD
Page 2 of 2 *NR	HP Status Code 5S2
*Resource Name or # (Assigned by recorder) 515 17 th Av	enue, San Diego, CA 92101
B1. Historic Name: William Norris House	
B2. Common Name: William B. Norris Spec. Ho	use #2
B3. Original Use: Residential (single-family)	B4. Present Use: Residential (single-family)
*B5. Architectural Style: Folk Victorian	- Marian III and a second and a
*B6. Construction History: (Construction date, alternations, all Constructed in approximately 1900; no subst	
*B7. Moved? ☐ No ☐ Yes ☐ Unknown Date: after c.1	921 Original Location:
*B8. Related Features:	
B9a. Architect: Unknown b. Builder: Unkno	
*B 10. Significance: Theme Architecture Area <u>Sar</u>	
Property Type Residential Appl	
(Discuss importance in terms of historical or architectural context as defined by	theme, period, and geographic scope. Also address integrity.)
	and moved to the current site after approximately
1921, this building was previously documented in of Marie Lia and Dr. Ray Brandes. Previous document	
property and building include: William R. Frisbie	
From the result of the result	F

of Marie Lia and Dr. Ray Brandes. Previous documentation indicates past owners of the 515 17th Avenue property and building include: William R. Frisbie pre-1872), William B. Norris and various members of the Norris Family (1872-1940). Past residents of the 515 17th Avenue building include: Mrs. L.R. Collins and Harold Goldschneider (1950), owner Joseph Koffler (1955), Augustin W. Albarran (1960), Mrs. Anna E. Mendez (1965), Epifanio S. Romo (1969/1970 & 1975), and Emerio Soto (1980, 1984).

Historical research has determined that the 515 17th Avenue building is not historically

Historical research has determined that the 515 17th Avenue building is not historically significant, as it is not associated with any important events or individuals in terms of local, state, or **national** history. However, the **building** does appear to be architecturally significant, as a building which embodies the **distinctive** characteristics of a type, period, or method of Folk Victorian construction. As the identity of the architect could not be ascertained, the 515 17th Avenue residence does not represent the work of a master architect or craftsman.


B11. Additional Resource Attributes: (List attributes and codes)_

*B12. References: (partial list)

Lia and Brandes, Historic Site Inventory of Centre City East, 1988. McAlester, Virginia & Lee, A Field Guide To American Houses, 1986.

San Diego City Directories

San Diego County Recorders Office



PRIMARY RECORD

1 of 2

Page

RECREATION	HRI #			
	Trinomial			
	NRHP Status Co	de_6Z		
Other Listings Update	of November 1988	Centre Ci	ty East	Survey Documentation
Review Code	Reviewer			Date
*Resource Name or #: (Assign	ned by recorder)	518 17 th	Avenue	9
: — <u>— — — — — — — — — — — — — — — — — —</u>	C 4			

P1. Other Identifier: Location: a Not for Publication Unrestricted * a. County San Diego_

and (P2b and P2c or P2d. Attach a Location Map as necessary.)

__; ___¼ of ___¼ of Sec___; ____ B.M. *b. USGS 7.5' Quad Point Loma_____Date___ Address 518 17th Avenue City San Diego Zip 92101


Primary #

d. UTM: (Give more than one for large or linear resources) Zone 11: ______mE/

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): e.

APN: 535-164-03-00, Sherman's Addition, Block 16, N 2/3 of Lot 8 Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1877, this two-story residence was designed in a gabled front Folk National architectural style. It has a general "L"-shaped plan, and features a moderately pitched, front gabled roof, with slight eave overhang. The first-floor section of the residence appears to have been added at a later date. Exterior building materials consist of composition shingles for the roof, stucco-on-lath for the first-floor addition's exterior walls, and horizontal shiplap siding with corner boards for the original two-story portion's exterior walls. The windows have been replaced and all appear to be modern sliders. Overall, the exterior of this residence appears to be in poor condition.



P3b. Resource Attributes: (List attributes and codes) HP2; possibly HP3

*P4. Resources Present: | Building d Structure d Object d Site d District d Element of District d Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

I Historic

d Prehistoric d Both

C.1877 1988 Centre City East Historic Site Inventory

*P7. Owner and Address:

<u>Virginia Hueso Trust 07-17-97</u> 1228 Edgemont Street

San Diego, CA 92102

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Burke Lia, Attorney at Law, 427 C Street,

Ste. 416, San Diego, CA 92101

March	2001	/ Pł	noto U	Jpdated	June	2003
	March	March 2001	<u>March 2001 / Pl</u>	March 2001 / Photo U	March 2001 / Photo Updated	March 2001 / Photo Updated June

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: PNONE n Location Map n Sketch Map Continuation Sheet Building, Structure, and Object Record ☐ Archaeological Record n District Record n Linear Resource Record n Milling Station Record ☐ Rock Art Record n Artifact Record n Photograph Record n Other (List):

BUILDING, STRUCTURE, AND OBJECT RECO	4
Page 2 of 2 *NRHP Sta *Resource Name or # (Assigned by recorder) 518 17 th Avenue	Son Diago CA 02101
B1. Historic Name: William E. Robinson Residence	
B2. Common Name:	
B3. Original Use: Residential (Single-Family) B4. Pr	resent Use: Residential (Single-Family)
*B5. Architectural Style: Folk National	
*B6. Construction History: (Construction date, alternations, and date	of alterations)
Originally constructed in approximately 1877; relocated floor addition, date unknown.	to current location between 1901-1921, first
*B7. Moved? ☐ No Yes ☐Unknown Date: pre-1921 Origin	nal Location: 1640 Island Avenue
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: Theme N/A Area San Diego Personal Area San Diego Personal Applicable C	
(Discuss importance in terms of historical or architectural context as defined by theme, pe	
Originally constructed in approximately 1877, and lo	ogated at 1640 Taland Avenue, this building
was previously documented in November 1988 under the sur	
Ray Brandes. Past owners of the 518 17th Avenue propert	ty and residence include: Ellen J. & Thomas
Sherman (pre-1877), William E. Robinson (1877), daughter	
Dunham, Augusta B. Dunham (1877-1879), William Rupech (1 H.K. & Daisy Pollock.	8/9-1686), 1.W. & Hattle Rutter (1666-1923),
Historical research has determined that this buildin	
significant. It is not a building which is directly individuals in local, state, or national history. Mor	
characteristics of a type, period, or method of Folk Nat	
architect, and/or builder could not be ascertained, the	
master architect, master builder, nor that of an important eliquible for listing on the local register.	nt, creative individual. The building is not
erigible for fiscing on the local register.	
B11. Additional Resource Attributes: (List attributes and codes)
*B12. References: (partial list)	
Lia and Brandes, Historic Site Inventory of Centry	
McAlester, Virginia & Lee, A Field Guide To Ameri	can Houses, 1986.
San Diego City Directories San Diego County Recorders Office	
San Diego County Recorders Office	
B13. Remarks:	
Past documentation states that the 518 17th Avenue residence is (Lia/Brandes: 1988), however, the integrity of the building ha	s an example of an early Prefabricated structure
state of its disrepair.	s been lost due to modifications and the general
	(Sketch Map with north arrow required.)
*B14. Evaluator: Wendy L. Tinsley, Office of Marie Burke Lia	MARKET
Date of Evaluation: March 2001	. 30 80
Date of Transport March 2001	127
	HD
	3 10
(This space reserved for official comments.)	된 <u>BLK</u> 16 된 9 ® ₄ 9
	9 04 8
	5
	° · - ·
	1 6 7 1

ISLAND

\$

PRIMARY RECORD


and boundaries):

rimary #		
HRI #_ 2138-0444	1-0000	
rinomial		
RHP Status Code	6Z	
	6Z	

	NRHP Status Code _6:	Z
Ot Re	ther Listings <u>Up</u> date of November 1988 Cen eview Code Reviewer	tre City East Survey Documentation
Page <u>1</u> of <u>3</u> *Resource Na P1. Other Identifier:	ame or #: (Assigned by recorder) 525	Date 17 th Avenue
*P2. Location: n Not for Publication • Ur and (P2b and P2c or P2d. Attach a Location N	Map as necessary.)	
*b. USGS 7.5' Quad Point Loma c. Address 525 17 th Avenue City	Date T; R;	¼ of ¼ of Sec;B.M.
	or large or linear resources) 2	

Other Locational Data (e.g., parcel #, directions to resource, elevation etc as appropriate): APN: 535-190-41-00, Lot 5 except S 17 Ft, Block 15 Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, *P3a.

Originally constructed between approximately 1872-1887 this residence was designed in a Folk Victorian architectural style It features a cross gabled roof of moderate pitch with a slight eave overhang, a molded cornice with a plain frieze, and gothic ____val vergeboards under the south elevation eave. Exterior building materials consist of composition shingles for the roof, and shiplap siding with corner boards for the exterior walls of the roof line helps to create an open entrance porch which features simp1 The west elevation features two windows; one modern slid r style located _____ area, and the other off-center located on the gable wall, featuring three vertical panes with a single horizontal pane above, and surrounded by a bracketed hood and bracketed slipsill. See DPR 523H, Continuation Sheet for more information.



P3b. Resource Attributes: (List attributes and codes) HP3 codes) HP3

*P4. Resources Present: Building n Structure n Object

Site D District Element of District other (Isolates, etc.) P5b. Description of Photo: (View, date accession

*P6. Date Constructed/Age and Sources:

Historic D Prehistoric

D Both

C.1872-1887

1988 Centre City East Historic Site Inventory *P7. Owner and Address

Francisco J. and Pilar Robles

1256 Raven Avenue

Chula Vista, CA 91911

*P8. Recorded by (Name, affiliation, and Wendy L. Tinsley, address): Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

P9- Date Record	led: Apr	il 2001							
*P10. Type	of S	Survey:	(Describe)	_	_	di-			
P11. Report Citation	Centre	CILLY	EVETODIIIETT	COLDORA	LION				
Attachments: DNON	JIU - DISTIII	CL NECUIU	- Linear nesourc	ntinuation ce Record	Sheet Millir	■ Building,S ng Station Re	tructure ^{al} cord □ Ro	Object Record	rd

State of California — The Resources Agency Primary #	
DEPARTMENT OF PARKS AND RECREATION HRI# _21	38-0444-0000
BUILDING, STRUCTURE, AND OBJECT REC	ORD
	atus Code 6z
*Resource Name or # (Assigned by recorder) 525 17 th Avenue,	San Diego, CA 92101
B1. Historic Name: W. R. Norris House	
B2. Common Name: William B. Norris Spec. House #3	
B3. Original Use: Residential (Single-family) B4.	Present Use: Residential (Multi-family)
*B5. Architectural Style: Modified Folk Victorian	of alternation of
*B6. Construction History: (Construction date, alternations, and date Constructed between approximately 1872-1887; north wall expressions are supported by the construction of the constru	
*B7. Moved? No Yes Unknown Date: between c. 192	
*B8. Related Features:	original Essation.
B9a. Architect: <u>Unknown</u> b. Builder: <u>Norris & Sons</u>	_
	Period of Significance 1872-1887_
Property Type Residential Applicable (Discuss importance in terms of historical or architectural context as defined by theme,	
Originally constructed between approximately 1872-	1887 and moved to the gurrent 525 17th Avenue
location between approximately 1921 and 1940, this build under the supervision of the Office of Marie Lia an indicates past owners of the 525 17th Street property and 1872), William B. Norris and various members of the Norri reveals William B. Norris worked as a carpenter with Albert, worked as a painter. Together, the four men work houses such as this one (Lia/Brandes:1988). Past resi (1944/1945), David Lerma (1950), owner Francisco Martine and Eugene DeVoe at 525 ½ (1965), Isabel Rodriguez (525 Alex P. Lopez (1975), Alex P. Lopez (525a), R. Estell lastly, no return (525a), R. Estella (525b), and Arture	ing was previously documented in November 1988 d Dr. Ray Brandes. Previous documentation d building include: William R. Frisbie (pre- ris Family (1872-c.1940). Past documentation his sons Erwin and Frank, and his third son rised as Norris & Sons, apparently constructing dents of 525 17 TH Avenue include: no listing to 1955), vacant (1960), Fred Whitehead (525) and Mrs. Evalia Sosa at 525 ½ (1969/1970), a (525b), and no return at 525c (1980), and
Although this buildings is listed as a "48" or Preservation's Historic Property Data File for San Dieg that the 525 17 th Avenue building is neither historical 17 th Avenue building is not associated with any important state, or national history. Moreover, it does not embor period, or method of Folk Victorian construction, and architect, builder or craftsman.	o County, historical research has determined ly nor architecturally significant. The 525 at events or individuals in terms of local, dy the distinctive characteristics of a type,
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list) Lia and Brandes, Historic Site Inventory of Centre City McAlester, Virginia and Lee, A Field Guide To American San Diego City Directories San Diego County Recorders Office	
	(Sketch Map with north arrow required.)
B13. Remarks:	* MARKET
*B14. Evaluator: Wendy L. Tinsley, Office of Marie Burke Lia Date of Evaluation: April 2001	
(This appear and to a titrical and the	TD 3
(This space reserved for official comments.)	BLK 15 a state 5

· (4)

8 ISLAND

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET

Primary #			
HRI #/Trinomial	2138-0444-0000	•	

• Continuation

Update

Page3 of3_					
Resource Identifier: (Assigned by recorder)	525	17 th Avenue,	San Diego,	CA 92101_	
Historic Name: W.R. Norris House					

*P3a. Description (Continued):

A **four-point**, star-shaped attic vent is centered above the gable wall window. The north wall of the residence **appears** to have been extended out, as a close examination reveals the connection between the old wood siding and the newer wood siding. Overall, the exterior of the residence **appears** to be in good condition. The building is not eligible for listing on the local register.

DPR 523H (1/95)

PRIMARY RECORD

Primary #		
HRI #		
Trinomial		
NRHP Status Code	5S2	

Other Listings	Update of Novem	ber 1988 (Centre City Ea	st Survey Documentat	ior
Review Code	Revie	wer		Date	

				11011011							
Page	1.	of	2	*Resource Name of	or #: (Assigned I	by recorder)	531	17 th	Avenue_		
P1.	Oth	er :	Identifie	er:							

*P2. Location:

Not for Publication • Unrestricted *

a. County San Diego

and (P2b and P2c or P2d. Attach a Location Map as necessary.)


*b. USGS 7.5' Quad Point Loma Date T ; R ; M of Sec ; B.M.

c. Address 531 17th Avenue City San Diego Zip 92101

d. UTM: (Give more than one for large or linear resources) Zone ___; ____ mE/ ___mN
 e. Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):
 APN: 535-190-40-00, Lot 4, Block 15

*P3a. **Description** (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed between approximately 1880-1890, this single-story, single-family residence was designed in an Italianate architectural style. It has a general rectangular shaped plan and features a flat roof with a wide bracketed cornice, a plain frieze, and a full length front porch. The porch features a hipped roof, eight supportive posts with decorative brackets below a plain frieze. The front entry door is recessed in the porch area, and is flanked on each side by two, individually placed, double-hung windows. Exterior building materials consist of shiplap siding for the exterior walls and most likely composition paper rolls for the roof. Overall, the exterior of this residence appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) __HP2_

***P4. Resources Present:** • Building a Structure a Object □ Site □ District a Element of District □ Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

☐ Prehistoric ☐ Both

c.1880-1890

1988 Centre City East Historic Site Inventory

*P7. Owner and Address

Ramirez Family Trust 02-23-96

531 17th Street

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. Date Recorded: April 2001

*P10. Type of Survey: (Describe)_


P11. Report Citation (Cite survey report and other sources, or enter "none".)Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments: □ NONE a Location Map D Sketch Map a Continuation Sheet ■ Building, Structure, and Object Record a Archaeological Record D District Record D Linear Resource Record a Milling Station Record a Rock Art Record □ Artifact Record a Photograph Record □ Other (List): _____

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary #
BUILDING, STRUCTURE, AND OBJECT	CT RECORD
	*NRHP Status Code 5S2
	Avenue, San Diego, CA 92101
B2. Common Name: William B. Norris Spec.	
	7) B4. Present Use: Residential (Multi-family)
*B5. Architectural Style: Italianate	
*B6. Construction History: (Construction date, alternation Constructed in between approximately 1880-1890; *B7. Moved? ☐ No • Yes ☐ Unknown Date: between Date: D	no substantial alterations and/or modifications noted
*B8. Related Features: B9a. Architect: Unknown b. Builder: U *B10. Significance: Theme Architecture Area Property Type Residential (Discuss importance in terms of historical or architectural context as defined.)	nknown_ San Diego Period of Significance 1880-1890_ Applicable Criteria C_
site between approximately 1921-1940, this buithe supervision of the Office of Marie Lia and building and property include: William R. F	ately 1880-1890 and moved to the current 531 17 th Avenue lding was previously documented in November 1988 under d Dr. Ray Brandes. Past owners of the 531 17th Avenue Frisbie (pre-1872) and William B. Norris (1872-dat e prior to 1940, Norris moved this frame dwelling upor
the property for use as a rental" (Lia/Bran	des. 1988) San Diego City Directories reveal pas

Historical research has determined that the 531 17th Avenue building is not historically significant, as it is not associated with any important events or individuals in terms of local, state, or national history. However, the residence does appear to be architecturally significant, as a building which embodies the distinctive **characteristics** of a type, period, or method of construction. Moreover, past documentation has also determined that this residence is "significant for its single-story Italianate architecture" (Lia/Brandes:1988). As the identity of the architect could not be ascertained, the 531 17th Avenue residence does not represent the work of a master architect or craftsman

residents of 531 17™ Street include: no listing (1944/1945), M.J. French (1950), Louis Gonzales (1955), Mateo V. Contrero, and Mrs. Ana Saucedo (1965), Luis Burgoin, and owner Jose Ramirez (1969/1970), owner Jose Ramirez (1975), owner Jose M. Ramirez (531a) and Richard E. Patterson at 531b



(1980, 1984).

PRIN	ИДК	YΚ	+CC)KI)

d. ė.

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI #
PRIMARY RECORD	Trinomial
Other Listings	TWO II Otatus Oodo <u>OZ</u>
Review Code	Reviewer Date
Page1 _ of _2 *Resource Name or #: (Assign	ned by recorder)532-534_17 th Street
P1. Other Identifier: <u>Jason L. Johnson Res</u>	idence
*P2. Location: □ Not for Publication ■ Unrestricted *	a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as necessar	
*b. USGS 7.5' Quad Point Loma Date	
	an Diego Zip <u>92101</u>
d. UTM: (Give more than one for large or	linear resources) Zone; mE/mN

Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate):

This one and two-story, former single-family residence was constructed sometime between 1888-1906. The building consists of a rear, two-story portion, which was originally a single-family residence, but now serves multi-family use. This portion appears to have been originally designed in either a Queen Anne or Folk Victorian architectural style. However, modifications to the structure make this unclear. This portion features a gambrel roof with composition shingles and limited decorative detail in the gabled pediments. The exterior consists of horizontal clapboard. A dormer with diamond-paned transom is located along the east elevation. Other windows are generally double-hung. A one-story projection is located along the northwest elevation. Along the southeast elevation, a one-story addition was constructed sometime between 1921-1940. This addition features a side-gabled roof with what appears to be an attached deck and composition shingles. Siding is fishscale and vertical clapboard. Windows are sliding casement with metal security grilles. Overall, the building appears to be in fair condition.

P3b. Resource Attributes: (List attributes and codes) HP3

Block 16, Lot 9, Map: 856; APN: 535-164-04



*P4. Resources Present: | Building ☐ Structure ☐ Object ☐ Site a District ☐ Element of District D Other (Isolates, etc.) Description of Photo: (View, date, accession #) *P6. Date Constructed/Age and Sources:

Historic

O Prehistoric c.1888-1906

Sanborn Fire Insurance Maps___ *P7. Owner and Address:

n Both

Francisca S. Preciado 534 17th Street_

San Diego, CA 92101

P8. Recorded by (Name, affiliation, and address): Office of Marie Burke Lia, 427 C Street, Suite 416, San Diego, California 92101___ *P9. Date Recorded: May 2004

*P10. Type of Survey: (Describe) Intensive

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Resources Inventory Update Of The East Village Area For Centre City Development Corporation_ _Attachments: □NONE □Location Map □Sketch Map □Continuation Sheet ■Building, Structure, and Object Record □Archaeological Record □District Record □Linear Resource Record □Milling Station Record □Rock Art Record □Artifact Record □Photograph Record □ Other (List):

State of California — The Resources Agency Primary # DEPARTMENT OF PARKS AND RECREATION HRI#	
and the second s	
BUILDING, STRUCTURE, AND OBJECT RECO	
*Resource Name or # (Assigned by recorder) 532-534 17 th Str	atus Code 6Z
B1. Historic Name: Jason L. Johnson Residence	
B2. Common Name:	
B3. Original Use: Residential B4. Present Use: Resident	
*B5. Architectural Style: Modified Victorian	
*B6. Construction History: (Construction date, alternations, and date	of alterations)
Building constructed c.1888-1906. The structure original between 1921-1940, the building was converted into apartment constructed along the front (east) elevation. Interior improve	t use with three units and a one story addition
*B7. Moved? No □Yes □Unknown Date:	Original Location:
*B8. Related Features:	
None	
B9a. Architect: <u>Unknown</u> b. Builder: <u>Unknown</u>	
*B10. Significance: ThemeN/A Area _E	East Village/Centre City
Period of Significance N/A Property Type R	esidential Applicable Criteria N/A
(Discuss importance in terms of historical or architect geographic scope. Also address integrity.)	tural context as defined by theme, period, and
This property essentially consists of a two-story, former single-family reside serves a multi-family use. Inspection of Sanborn Fire Insurance Maps indicates that was constructed c. 1888-1906. The building is not listed on the 1888 Sanborn M 1940, the one-story addition was built along the southeast elevation and the e (apartments). The earliest identifiable occupant of the 534 17th Street residence, pri Johnson occupied the property until 1926. Subsequent occupants of the 532-534 Stromquist, Ingnacio Peralta, A. W. Watkins, Alberto M. Morlett, Victor M. Verd Ferro, Sergio Barreto and Jose L. Ponce.	the original single-family residence, identified as 534 17 th Street, (ap, but is listed on the 1906 map as a two-story "dwelling." By entire structure was converted to multi-family use as "3 Apts" or to its multi-family conversion, was Jason L. Johnson in 1923 17 th Street building between 1930-1960 have included Mrs. S.L.
Historical research has determined that the 532-534 17th Street building is n associated with any important events or individuals in terms of local, state, or r characteristics of a type, period, or method of construction, particularly in light sustained over the years. In addition, it does not represent the work of a master at	national history. The building does not embody the distinctive of the substantial alterations and modifications the building has
B11. Additional Resource Attributes: (List attributes and codes)
*B12. References: (partial list)	
City of San Diego, Building Department Permit Records. City of San Diego, Water & Sewer Records. McAlester, Virginia & Lee, A Field Guide To American Houses, 2000.	(Sketch Map with north arrow required.) MARKET
Sanborn Fire Insurance Maps, 1888, 1906, 1921, 1940, 1956. San Diego City and County Directories.	1130
B13. Remarks:	
*B14. Evaluator: Office of Marie Burke Lia	E BLK 16
(This space reserved for official comments.)	BLK 16 F
1	6 7 4
	ISLAND 17-100'
1	**

PRIMARY RECORD

c.

d.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary # HRI #_ 2138-0446-0000
PRIMARY RECORD	Trinomial
	NRHP Status Code 5S2
Other Listings Updat	te of Novembers Centre EasttSurvey Documentation
Review Code	Reviewer Date
Page1 of3 *Resource Name or #: (Assignment) P1. Other Identifier:	gned by recorder) 768 17 th Avenue
*P2. Location: □ Not for Publication • Unrestricted *	a. County San Diego
and (P2b and P2c or P2d. Attach a Location Map as necessary	ary.)
*b. USGS 7.5' Quad Point Loma Date	T; R;¼ Of¼ of Sec;B.M.
c. Address _768 17 th Avenue City San Die	
d. UTM: (Give more than one for large or	· linear resources) Zone; mE/mN

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): APN: 535-180-05-00, E 50 Ft Lot 1 & portion Lot 2, Block 13 Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in approximately 1913, this two-story apartment house was designed in the Early Prairie architectural style. It has a general square shaped, symmetrical plan and features a nearly flat roof with wide eave overhang, and a boxed and bracketed cornice. A centered portico is present on the west elevation of the residence and features two oversized wooden pillars, and a balcony with wooden railing above. A centered, hipped dormer is present, and windows are double hung sash type. The first floor windows are tri-partite, featuring a center fixed portion with an upper multi-pane sash pattern, flanked on both sides by a narrow double-hung window. Iron security bars cover all the first floor windows. Exterior building materials consist of composition shingles for the roof, and clapboard siding for the exterior walls. Overall, this building appears to be in good condition.



Resource Attributes: (List attributes P3h and codes) HP3 *P4. Structure

Object

Site a District

Element of District n Other (Isolates, etc.) Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

 Historic D Prehistoric

n Both

1913

1988 Centre City East Historic Site Inventory

*P7. Owner and Address

Mark Frederick

768 17th Street #4

San Diego, CA 92101

*P8. Recorded by (Name, affiliation, and address): Wendy L. Tinsley, Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

*P9. March 2001 / Owner Information and Photo Updated June 2003 Date Recorded:

*P10. Type of Survey: (Describe)

P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic gite Inventory of Centre

City East For Centre City Development Corporation_

Attachments:
NONE n Location Map a Sketch Map • Continuation Sheet Building, Structure, and Object Record D Archaeological Record a District Record Linear Resource Record Milling Station Record a Rock Art Record ☐ Artifact Record ☐ Photograph Record D Other (List): __

State of California — The Resources Agency	Primary #
DEPARTMENT OF PARKS AND RECREATION	HRI# 2138-0446-0000
BUILDING, STRUCTURE, AND OBJECT	CT RECORD
Page 2 of 3	*NRHP Status Code 5S2
*Resource Name or # (Assigned by recorder) 768 17	th Avenue, San Diego, CA 92101
B1. Historic Name: Norris Cluster Apartments	8
B2. Common Name:	
	B4. Present Use: Residential (Multi-family)
	Box, American Foursquare)
*B6. Construction History: (Construction date, alternation Constructed in approximately 1913; no s	ubstantial alterations and/or modifications noted
*B7. Moved? ■ No □ Yes □Unknown Date:	
*B8. Related Features:	
B9a. Architect: <u>Unknown</u> b. Builder: <u>U</u>	
	San Diego Period of Significance 1913_
Property Type Residential [Discuss importance in terms of historical or architectural context as defined by the context of the	Applicable Criteria C_ ned by theme, period, and geographic scope. Also address integrity.)
	913, this building was previously documented in November rie Lia and Or. Ray Brandes . Past documentation reveals
	ment or rooming houses built in this part of the city
	an influx of tourists for the 1915 Exposition in Balboa
	the 768 17^{th} Avenue property and building include E.V.
	otel proprietor, J.E. Norris (1912-date unknown). Past
proprietors include Floyd Halsapple (1918).	(See DPR 523H, Continuation Sheet for more information)
Historical research has determined that the	ne 768 17th Avenue apartment building is not historically
	y important events or individuals in terms of local,
	lding does appear to be architecturally significant, at
	the distinctive characteristics of a type, period, or dentity of the architect could not be ascertained, the
building does not represent the work of a mast	
	W.
B1 1. Additional Resource Attributes: (List attributes and code	s)
*B12. References: (partial list) Lia and Brandes, Historic Site Inventory	of Centre City Fast 1988
McAlester, Virginia & Lee, A Field Guide	
San Diego City Directories	To finelical floubes, 1900.
San Diego County Recorders Office	
B13. Remarks:	
	(Sketch Map with north arrow required.)
*B14. Evaluator: Wendy L. Tinsley,	
Office of Marie Burke Lia	
Date of Evaluation: March 2001	00 100 4473 11 41
	ę · /z / (\$) ;ę
	- " CD" - E
	된 % 13' · E
(This space reserved for official comments.)	
T C C C C C C C C C C C C C C C C C C C	
· ·	

G

CONTINUATIONSHEET

Primary #		
HRI #/Trinomial	2138-0446-0000	(50)

I Continuation update

Page3 Of3			
Resource Identifier: (Assigned by recorder)	768 17 th Avenue,	5an Diego, C	A 92101
Historic Name: Norris Cluster A	partments	9	

*B10. Significance (Continued):

According to previous documentation, J.E. Norris was a partner in Norris and Moore, a property management/real estate office, who are cited as having been proprietors of the Golden West Hotel in 1914 (Lia/Brandes:1988).

San Diego City **Directories** reveal past residents of the 768 $17^{\rm th}$ Avenue apartment building include:

1944/1945: Mrs. M.M. Connors, W.A. Hanson, Ernesto Romero, K.W. Snodenly, T.V. Vogel, and R.E. Weakley;

1950: B.W. Barnes, F.M. Coleman, H.W. Comstock, C.O. Davis, F.W. Jones, and R.V. Neff;

1955: 1) Cyrus E. Stearns, 2) Mrs. Robbie Workman, 3) vacant, 4) H.J. Clapper, 5) Henry Bennett, and 6) Charles W. Abies;

1960: 1) Mrs. Mildred Bredeson, 2) Henry J. Wolff, 3) Leroy Layman, 4) D.C. Dickerman, 5} vacant, and 6) Jay Impson;

1965: Apartments, 1) Jason R. Wallis, 2) vacant, 3) vacant, 4) Edmondo Comez, 5) vacant, and 6) vacant;

1969/1970: six units listed as 1-6, and unit # 3 ie listed as vacant.

1975: Apartments, 1) Daniel Flores, 2) Mrs. Juana Munoz, 3) Margeret Witham, 4) Mrs. Herlinda Rosas, 5) Jerome Kneeland, and 6) Jesus Diaz;

1980: 1) Benny Juarez, 2) **Mrs.** Lena Vegas, 3) vacant, 4) Antonio Solario, 5) Jerome Kneeland, and 6) Mrs. Anna M. Luna;

1984: Apartments, 1) Carlos F. Solorio, 2) Luna Villegas, 3) vacant, 4) Margarita Gonzales, 5) Jerome Kneeland, and 6) no return.

DPR 523H (1/95)

PRIMARY RECORD

у	Primary #				
ON	HRI #				
	Trinomial				
	NRHP Status Cod	e 5S2			
Other Listings	Update of November 1988	3 Centre	City East	Survey	Documentation
Raview Code	Reviewer			Date	

		Review Code	Reviewer	Date	
Page_	1 of3	*Resource Name or #: (Assign	ed by recorder)	914 17 th Avenue	
D1	Other Identifi	ier.			

Location: n Not for Publication • Unrestricted * San Diego *P2 a. County and (P2b and P2c or P2d. Attach a Location Map as necessary.)


T ____; R ____; ___¼ of ___¼ of Sec __; ____ B.M. *b. USGS 7.5' Quad Point Loma Date Address 914 17th Avenue City San Diego ___ Zip ____92101

d. UTM: (Give more than one for large or linear resources) Zone ___; ____ mE/ ___mN

Other Locational Data (e.g., parcel #, directions to resource, elevation, etc., as appropriate): ρ APN: 534-360-07-00, Culverwell's Addition, Lots 5 & 6, Block 3

*P3a. Description (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries):

Originally constructed in 1929, this four-story apartment building with basement was designed in a Spanish Eclectic architectural style. Located on a sloping lot adjacent to Interstate 5, the building has a general rectangular shaped plan and features a moderately pitched, hipped roof with wide eave overhang and exposed beams, a centered roof tower, a recessed entry on the east elevation with an arched opening and decorative tiled walls, and a fire escape on the south elevation extending down the four floors. Exterior building materials consist of Spanish tiles for the roof and stuccoon-lath for the exterior walls. Window types vary between paired casements and single-hung sash, both in wood sills. The entrance to the building is on the east elevation, and an undeveloped lot is adjacent to the west elevation of the building. Overall, the exterior of this building appears to be in good condition.



P3b. Resource Attributes: (List attributes and codes) HP3

Resources Present: • Building D Structure
Object
Site
District Element of District a Other (Isolates, etc.) P5b. Description of Photo: (View, date, accession #)

*P6. Date Constructed/Age and Sources:

Historic

n Prehistoric □ Both 1929

1988 Centre City East Historic Site Inventory

*P7. Owner and Address

John B. Purdin

3171 Adams Ave #E

San Diego, CA 92116

*P8. Recorded by (Name, affiliation, and Wendy L. Tinslev, address): Office of Marie Lia, Attorney at Law, 427 C Street, Ste. 416, San Diego, CA 92101

#P9. April 2001 / Owner Information and Photo Updated June 2003 Date Recorded:

*P10. Type of Survey: (Describe)


P11. Report Citation (Cite survey report and other sources, or enter "none".) Historic Site Inventory of Centre City East For Centre City Development Corporation

Attachments:

NONE Location Map n Sketch Map • Continuation Sheet • Building, Structure, and Object Record a Archaeological Record a District Record n Linear Resource Record n Milling Station Record Record Record a Artifact Record n Photograph Record D Other (List):

	a a
BUILDING, STRUCTURE, AND OBJECT RECO)BD
·	atus Code_ 5S2
*Resource Name or # (Assigned by recorder) 914 17 th Avenue,	
B1. Historic Name: Munson Apartments	
B2. Common Name: Alcazar Apartments	
B3. Original Use: Residential (apartments) *B5. Architectural Style: Spanish Eclectic	N O
*B6. Construction History: (Construction date, alternations, and date Constructed in 1929; no substantial alterations)	
*B7. Moved? ■ No □ Yes □Unknown Date:	Original Location:
*B8. Related Features:	
B9a. Architect: Edward H. Depew b. Builder: Unknown	
*B10. Significance: Theme Architecture Area San Diego Property Type Residential Applicable (
(Discuss importance in terms of historical or architectural context as defined by theme,	period, and geographic scope. Also address integrity.)
Originally constructed in 1929, this four-story approximately sunder the supervision of the Office of Marthe 914 17th Avenue property and building include: S.S. Chester Munson (1929), and James M. & Janet A. Dort(198 incomplete listing of tenants of the 914 17th Avenue Directories from 1944/1945 thru 1984.	rie Lia and Dr. Ray Brandes. Past owners of Culverwell (pre-1871), Delia Schaefer (1871) 8). See DPR 523H, Continuation Sheet for an
Historical research has determined that the 914 17 th to be historically significant , as the 914 17 th Avenue appears any important events or individuals in terms of local, suppear to be architecturally significant, at the local distinctive characteristics of a type, period, and method by architect Edward H. Depew, who began his career in 19 apartment building does not represent the work of a mast an important, creative individual .	artment building has not been associated with state, or national history. However, it does l level, as a building which embodies the od of Spanish Eclectic construction. Designed 227 and ended it in 1930, the 914 17th Avenue
B11. Additional Resource Attributes: (List attributes and codes)	
*B12. References: (partial list) Lia and Brandes, Historic Site Inventory of Centre McAlester, Virginia & Lee, A Field Guide To Amer. San Diego City Directories San Diego County Recorders Office	
B13. Remarks:	(Sketch Map with north arrow required.)
	BROADWAY
*B14. Evaluator: Wendy L. Tinsley,	
Office of Marie Burke Lia	60 12 1 @ c
Date of Evaluation: April 2001	// I
	i

(This space reserved for official comments.)



CONTINUATION SHEET

Primary #	
HRI #/Trinomial	

I Continuation D Update

Page3 of	3							
Resource Identifier:	(Assigned by recorder)	914	17 th	Avenue,	San	Diego,	CA	92101
Historic Name:	Munson Apartments							

*B10. Significance (Continued):

San ${\it Diego~City~Directories}$ reveal past tenants of the 914 $17^{\rm th}$ Avenue apartment building include:

1944/1945: Alcazar Apartments; J.L. Beeson, Harriet Binford, Roy Boggs, G.C. Bontyard, H.P. Bowman, Mrs. M.E. Bean, Bennie Ennis, Albert Guyot, K.S. Hall, E.H. Holbert, Mrs. Cecil Howard, Van Kelly, Mrs. O.H. Kinney, Harriet E. Munson, Mrs. Kathryn Reamey, Mrs. Bertha Riseling, Mrs. F.S. Rudrauff, Lloyd Thompson, E.J. Tyron, and George Wargo.

1950: Alcazar Apartments; R.E. Begley, Harriet Binford, Donald Boalich, George Fiehler, C.W. Cierd, T.M. Greene, James Hayden, T.L. Henderson, Helene O'Kinney, O.L. Larson, Nancy Leonard, O.F. Miller, Viola Minnick, Harriet E. Munson, Daisye Oldham, Mrs. Bertha Riseling, G.M. Rockwell, Anthony Spacensky, Lois Starck, A.N. Starrett, E.P. Staub, Evelyn A. Thompson, and G.E. Wargo.

1955: Alcazar Apartments; Robert Schrader, Louis Spadacino, George Griffith, Derrell D. Pitts, R.D. Warden, Mack Harten, H.D. Williams, John Schustek, Robert G. Parsons, Leo Banks, James C. Smith, E.S. Purcell, George Wargo, Rex Gorham, V. Olson, Harriet E. Munson, Evelyn A. Thompson, Mrs. Bertha Riseling, Jos. W. Lowder, Helene O. Kinney, Herman Ohler, Mrs. Ann L. Starrett, and Clara Prevost.

1960: Alcazar Apartments; Adrian De La Torre, Ralph N. Sunday, Martha Parker, Darrell D. Pitts, Mrs. Bertha Riseling, Mack Harten, Mrs. R.C. Troy, C.W. Goodson, James W. Ledford, Jack Seymour, George Wargo, Gleen Donvey, Morris Hill, Gil Postmus, Harriet Munson, John Quinn, C.M. Wood, John McCorkle, Herbert Sayher, Sam Garriffo, and Mrs. Karen Anderson.

1965: Alcazar Apartments; twenty-four units listed as one thru twenty-five, with eight vacancies.

1969/1970: Alcazar Apartments; twenty-four units listed as one thru twenty-five, with one vacancy.

1975: Alcazar Apartments; Aaron Parazych, Mrs. Opal Hipp, Renato A. Gaza, Louis Sumrall, Joe Barnhill, Mrs. Cleone Ryser, Carl Worthy, Lawrence R. Larson, Robert Ogden, Harold Gaylord, John Maguire, Albert Smith, V. Roy Saint Clair, Mrs. Filomena M. Garcia, Harry E. Durgen Jr., Harold Summer, Harriet E. Munson, Howard L. Evans, William Collazo, Walter C. Peterson, Robert E. Muffley, Hugo McGee, Mrs. Hazel Fender, and Mrs. Lucille Morgan.

1980: Alcazar Apartments, twenty-four units listed as one thru twenty-five, with no vacancies.

1984: twenty-four units listed as one thru twenty-five, with two vacancies.

DPR 523H (1/95)

