


WATER PURIFICATION DEMONSTRATION PROJECT RESULTS

HOOMAN PARTOW, PE MEHDI KHALILI, PE

OCTOBER 22, 2013







WATER SUPPLY CHALLENGES

- Limited local supplies
- Increasing cost of imported water
- Pumping restrictions
- Recurring drought conditions
- Population growth
- Natural disasters







WHAT IS BEING DONE...

Regional:

Desalination



Local:


- Water Conservation
- Groundwater Development
- Recycled Water
- Water Purification





Water Purification Process

Multi-Barrier Water Purification Steps



Water Purification Process

Microfiltration & Ultrafiltration



Reverse Osmosis



Ultraviolet Light / Hydrogen Peroxide





WATER PURIFICATION DEMONSTRATION PROJECT

COMPONENTS

- Advanced Water
 Purification (AWP) Facility
- Independent Advisory Panel (IAP)
- San Vicente Reservoir Study
- Regulatory requirements
- Energy and cost analysis
- Education and outreach program





AWP FACILITY TESTING & MONITORING PLAN

- Testing period August 1, 2011 to July 31, 2012
- Measured for 342 constituents and parameters in recycled water, purified water, and imported water
- Conducted 9,000 individual water quality laboratory tests
- Implemented continuous and daily monitoring before and after each treatment step to verify integrity of each treatment process
- Visit <u>www.purewatersd.org</u> for more information



SAN VICENTE RESERVOIR STUDY RESULTS

- Reservoir provides an environmental barrier that satisfies anticipated regulatory requirements
- Purified water will be diluted at least 200:1 under all anticipated reservoir operations

Water quality in San Vicente will not be affected by adding

purified water







REGULATORY FRAMEWORK

- Regulatory agencies, CDPH,
 Regional Water Board, and County
 Dept of Environmental Health,
 attended IAP meetings
- Regulators commented on:
 - AWP Facility equipment
 - Testing & Monitoring Plan
 - San Vicente Reservoir Study





ENERGY & COST ANALYSIS

Energy:

- Energy consumption and greenhouse gas emissions of purified water delivered to San Vicente comparable to that of imported water
- Energy consumption and greenhouse gas emissions of purified water lower than ocean desalination



Cost:

 \$2,000 per acre-foot to produce and convey 15 mgd of purified water to San Vicente Reservoir

































ENVIRONMENTAL

















- **BIOCOM**
- Building Industry Association of San Diego

EQUINOX CENTER

- Building Owners and Managers Association, San Diego Chapter
- Citizens Coordinate for Century 3
- Coastal Environmental Rights Foundation
- Empower San Diego
- **Endangered Habitats League**
- **Environmental Health Coalition**
- **Equinox Center**
- Friends of Infrastructure
- Industrial Environmental Association
- National Association of Industrial and Office Properties

- San Diego and Imperial Counties Labor Council
- San Diego Audubon Society
- San Diego Regional Economic Development Corporation
- San Diego Coastkeeper
- San Diego County Apartment Association
- San Diego County Taxpayers Association
- San Diego Business Leadership Alliance
- San Diego Regional Chamber of Commerce
- San Diego River Park Foundation
- Surfrider Foundation, San Diego Chapter
- Sustainability Alliance of Southern California
- **Utility Consumers' Action Network**



SUMMARY

ADVANCED WATER PURIFICATION FACILITY

Operated 12 months; produced water that met all state and federal standards

SAN VICENTE RESERVOIR STUDY

Satisfied all anticipated regulatory requirements

REGULATORY FRAMEWORK

Received conceptual approval for a full-scale project from CDPH & Regional Water Board

ENERGY & COST ANALYSIS

Determined energy use is comparable to imported water and costs \$2,000 per AF

EDUCATION & OUTREACH

Increased understanding and approval of water purification

PROJECT REPORT

Adopted by City Council in April 2013

AND NOW WE'RE ...

- Responding to directives set forth by City Council
- Continuing tours, presentations and events





INFORMATION

Visit: www.purewatersd.org

Email: purewatersd@sandiego.gov

Call: (619) 533-7572

Reports: purewatersd.org/projectreports








BACK-UP SLIDES






Membrane-filtration: Step One




- Hollow fiber with holes in the sides
- Used to make baby food, purify medicines, fruit juices and more
- Excellent pre-filter before reverse osmosis






Reverse Osmosis: Step Two



- Same technology used by bottled water companies
- Forces water under high pressure through sheets of plastic membrane
- Demineralizes and purifies water




Ultraviolet Light plus H₂O₂: Step Three



- High-intensity light and hydrogen peroxide
- Creates advanced oxidation reaction, essentially destroys anything in the water







SAN VICENTE RESERVOIR STUDY

RESERVOIR ENLARGEMENT

- San Vicente Dam and Reservoir constructed in 1944
- Reservoir enlarged from 90,000 acre feet to 247,000 acre feet
- Water Authority is constructing facilities
- City will operate reservoir, dam, and outlet works
- Refilling will take three to five years

1944 to 2012



2013






PURIFIED WATER DISTRIBUTION AREAS

Under normal operations, purified water is delivered to the Alvarado WTP and to the area in green.


In an extraordinary event, such as extended drought, purified water could go to six WTPs and to the crosshatched area.





PIPELINE ALIGNMENT STUDY

- 22 mile, 36-inch pipeline to convey water from the AWP Facility to San Vicente Reservoir
- Two potential alignments identified:
 - State Route 52 alignment
 - Mission Gorge alignment
- Additional analysis is needed to refine alignment






REGULATED CONSTITUENTS

Regulations/Guidelines	Number of Constituents		
California Department of Public Health Goals			
Primary Drinking Water Maximum Contaminant Levels (MCLs)	90		
Secondary Drinking Water MCLs	18		
Microbial	4		
Notification Levels	30		
Groundwater Replenishment Criteria	142		
San Diego Water Board (projected)			
San Vicente Reservoir Limits	143		
Total	231		



COMPARING THE COST OF THE WATER



Projected cost of purified water (solid line) of a full-scale reservoir augmentation project at San Vicente Reservoir compared to actual and projected costs of untreated imported water (dashed lines).



DEMONSTRATION PROJECT SAN VICENTE IPR/RA COST ESTIMATE

	Capital	Annual Operating and Maintenance
AWP Facility	\$144,700,000	\$8,145,000
Pipeline & Pump station	\$224,500,000	\$3,385,000
Increased North City Tertiary Treatment	\$0	\$3,965,000
Total	\$369,200,000	\$15,495,000

Result - \$2,000 per acre-foot to produce and convey
 15 mgd of purified water to San Vicente Reservoir



AVOIDED WASTEWATER COSTS

	Capital	Annual Operating and Maintenance
Point Loma Wet Weather Storage Facility	\$123,000,000	\$6,150,000
Reduced Treatment at Point Loma	\$0	\$2,210,000
Reduced Pumping at Pump Station No. 2	\$0	\$450,000
Total	\$123,000,000	\$8,810,000
Total (per-acre-foot basis)	\$1,000	

Net cost: \$1,000 per acre-foot to produce and convey
 15 mgd of purified water to San Vicente Reservoir



PUBLIC OUTREACH & EDUCATION







LOCAL NEWS

San Diego studies making drinking water from waste water



Final Report Says Recycling

Water Is Not So Expensive

Turning wastewater into drinking water could provide a large, reliable source of water for San Diego. But water recycling has been politically controversial because some people think reusing wastewater is

It's also been seen as expensive; about twice the cost of importing water from outside the region.

But the final report on San Diego's Water Purification Demonstration Project now claims the future cost of recycled and imported water would be about the same, around \$1,000 per acre foot.

The report indicates recycling water does: money by reducing the need for imported by cutting the volume of water the city mu



Tide turns for water purification plan

By Deborah Sullivan Brennan 64 M APRIL 27 2013





The New Hork Times

SundayReview | The Opinion Pages

'Taking the Waste Out of Wastewater'






Purification system that makes toilet water clean enough to drink is closer to coming to San Diego



Public Outreach & Education Program RESEARCH RESULTS

Use Advanced Treated Recycled Water as an Addition to Drinking Water Supply





Public Outreach & Education Program RESEARCH RESULTS

ACCEPTING OF RECYCLED WATER TO SUPPLEMENT DRINKING WATER IF RESPONDENT LEARNED CERTAIN FACTS

