

City of San Diego

CONTRACTOR'S NAME: Superior Ready Mix Concrete, L.P. dba SRM Contracting & Paving

ADDRESS: 1508 W. Mission Road, Escondido, CA 92025

TELEPHONE NO.: 619-265-0955

FAX NO.: 619-583-3147

CITY CONTACT: Eleida Felix Yackel Contract Specialist, Email: EFelixYackel@sandiego.gov

Phone No. (619) 533-3449, Fax No. (619) 533-3633

DZhang/RWBustamante/egz

CONTRACT DOCUMENTS

FOR

ORIGINAL



UUP SHERMAN HEIGHTS STREET RESURFACING

VOLUME 1 OF 2

BID NO.: K-15-1361-DBB-3

SAP NO. (WBS/IO/CC): B-00829 / B-00714 / B-00851 / B-00705

CLIENT DEPARTMENT: 2116

COUNCIL DISTRICT: 8

PROJECT TYPE: ID / IJ

THIS CONTRACT IS SUBJECT TO THE FOLLOWING:

- THE CITY'S SUBCONTRACTING PARTICIPATION REQUIREMENTS FOR SLBE PROGRAM.
- PREVAILING WAGE RATES: STATE FEDERAL
- APPRENTICESHIP

BID DUE DATE:

2:00 PM

MAY 12, 2015

CITY OF SAN DIEGO


PUBLIC WORKS CONTRACTS

1010 SECOND AVENUE, 14th FLOOR, MS 614C

SAN DIEGO, CA 92101

ENGINEER OF WORK

The engineering Specifications and Special Provisions contained herein have been prepared by or under the direction of the following Registered Engineer:



For City Engineer

4/2/15

Date

Seal



TABLE OF CONTENTS

DESCRIPTION	PAGE NUMBER
1. NOTICE INVITING BIDS	4
2. CONTRACT FORMS AGREEMENT:	
1. Contract Forms	17
3. CONTRACT FORMS ATTACHMENTS:	
1. Performance Bond and Labor and Materialmen’s Bond	20
2. Drug-Free Workplace.....	22
3. American with Disabilities Act (ADA) Compliance Certification	23
4. Contractor Standards - Pledge of Compliance Certificate	24
5. Affidavit of Disposal Certificate	25
4. ATTACHMENTS:	
A. SCOPE OF WORK	28
B. INTENTIONALLY LEFT BLANK.....	29
C. EQUAL OPPORTUNITY CONTRACTING PROGRAM	31
D. INTENTIONALLY LEFT BLANK.....	34
E. SUPPLEMENTARY SPECIAL PROVISIONS	35
SUPPLEMENTARY SPECIAL PROVISIONS APPENDICES	47
1. Appendix A - Fire Hydrant Meter Program	48
2. Appendix B - Materials Typically Accepted by Certificate of Compliance	62
3. Appendix C - Sample City Invoice	64
4. Appendix D - Resurfacing Location Maps.....	66
5. Appendix E - Resurfacing Location List.....	73
6. Appendix F - Curb Ramp Location and Type List.....	76
7. Appendix G - SSP to Caltrans Standard Specifications 2010 Edition	90
8. Appendix H – Continental Crosswalk Markings Layout and Notes	96
F. INTENTIONALLY LEFT BLANK.....	100

CITY OF SAN DIEGO, CALIFORNIA

NOTICE INVITING BIDS

1. **RECEIPT AND OPENING OF BIDS:** Bids will be received at the Public Works Contracts at the location, time, and date shown on the cover of these specifications for performing work on **UUP Sherman Heights Street Resurfacing** (Project).
2. **SUMMARY OF WORK:** The Work involves furnishing all labor, materials, equipment, services, and other incidental works and appurtenances for the construction of the Project as described in ATTACHMENT A.
3. **BIDS ARE PUBLIC RECORDS:** Upon receipt by the City, Bids shall become public records subject to public disclosure. It is the responsibility of the respondent to clearly identify any confidential, proprietary, trade secret or otherwise legally privileged information contained within the Bid. General references to sections of the California Public Records Act (PRA) will not suffice. If the Contractor does not provide applicable case law that clearly establishes that the requested information is exempt from the disclosure requirements of the PRA, the City shall be free to release the information when required in accordance with the PRA, pursuant to any other applicable law, or by order of any court or government agency, and the Contractor will hold the City harmless for release of this information.
4. **SUBCONTRACTING PARTICIPATION PERCENTAGES:**
 - 4.1. The City has incorporated **mandatory** SLBE-ELBE subcontractor participation percentages to enhance competition and maximize subcontracting opportunities. For the purpose of achieving the mandatory subcontractor participation percentages, a recommended breakdown of the SLBE and ELBE subcontractor participation percentages based upon certified SLBE and ELBE firms has also been provided to achieve the mandatory subcontractor participation percentages:

1. SLBE participation	5.1%
2. ELBE participation	10.0%
3. Total mandatory participation	15.1%
 - 4.2. The Bidders are strongly encouraged to attend the Pre-Bid Meeting to better understand the Good Faith Effort requirements of this contract. See the City's document titled "SLBE Program, Instructions For Bidders Completing The Good Faith Effort Submittal" available at: <http://www.sandiego.gov/eoc/>
 - 4.3. The Bid will be declared **non-responsive** if the Bidder fails the following mandatory conditions:
 - 4.3.1. Bidder's inclusion of SLBE-ELBE certified subcontractors at the overall mandatory participation percentage identified in this document; OR.
 - 4.3.2. Bidder's submission of Good Faith Effort documentation, saved in searchable Portable Document Format (PDF) and stored on Compact Disc (CD) or Digital Video Disc (DVD), demonstrating the Bidder made a good

faith effort to outreach to and include SLBE-ELBE Subcontractors required in this document within **3 Working Days** of the Bid opening if the overall mandatory participation percentage is not met.

4.4. For additional Equal Opportunity Contracting Program requirements, see Attachment C.

5. PRE-BID MEETING:

5.1. There will be a Pre-Bid Meeting to discuss the scope of the Project, bidding requirements, pre-qualification process, and Equal Opportunity Contracting Program requirements and reporting procedures in the Public Works Contracts Conference Room, at 1010 Second Avenue 14th Floor, San Diego, CA 92101 at **10:00 AM, on April 22, 2015.**

5.2. All potential bidders are encouraged to attend.

5.3. To request a copy of the agenda on an alternative format, or to request a sign language or oral interpreter for this meeting, call the Public Works Contracts at (619) 533-3450 at least 5 Working Days prior to the Pre-Bid Meeting to ensure availability.

6. CONTRACTOR REGISTRATION AND ELECTRONIC REPORTING SYSTEM:

6.1. Prior to the Award of the Contract or each Task Order, you and your Subcontractors and Suppliers must register with the City's web-based vendor registration and bid management system, BidsOnline™ hosted by PlanetBids System. For additional information go to:

<http://www.sandiego.gov/purchasing/bids-contracts/vendorreg.shtml>.

6.2. The City may not award the contract until registration of all subcontractors and suppliers is complete. In the event this requirement is not met within the time frame specified in the Notice of Intent to Award letter, the City reserves the right to rescind the Notice of Award / Intent to Award and to make the award to the next responsive and responsible bidder / proposer.

7. **JOINT VENTURE CONTRACTORS:** Provide a copy of the Joint Venture agreement and the Joint Venture license to the City within 10 Working Days after receiving the Contract forms. See 2-1.1.2, "Joint Venture Contractors" in The WHITEBOOK for details.

8. **PREVAILING WAGE RATES:** Pursuant to San Diego Municipal Code section 22.3019, construction, alteration, demolition, repair and maintenance work performed under this Contract is subject to State prevailing wage laws. For construction work performed under this Contract cumulatively exceeding \$25,000 and for alteration, demolition, repair and maintenance work performed under this Contract cumulatively exceeding \$15,000, the Contractor and its subcontractors shall comply with State prevailing wage laws including, but not limited to, the requirements listed below.

8.1. **Compliance with Prevailing Wage Requirements.** Pursuant to sections 1720 through 1861 of the California Labor Code, the Contractor and its subcontractors shall ensure that all workers who perform work under this Contract are paid not less

than the prevailing rate of per diem wages as determined by the Director of the California Department of Industrial Relations (DIR). This includes work performed during the design and preconstruction phases of construction including, but not limited to, inspection and land surveying work.

8.1.1. Copies of such prevailing rate of per diem wages are on file at the City and are available for inspection to any interested party on request. Copies of the prevailing rate of per diem wages also may be found at <http://www.dir.ca.gov/OPRL/DPreWageDetermination.htm>. Contractor and its subcontractors shall post a copy of the prevailing rate of per diem wages determination at each job site and shall make them available to any interested party upon request.

8.1.2. The wage rates determined by the DIR refer to expiration dates. If the published wage rate does not refer to a predetermined wage rate to be paid after the expiration date, then the published rate of wage shall be in effect for the life of this Contract. If the published wage rate refers to a predetermined wage rate to become effective upon expiration of the published wage rate and the predetermined wage rate is on file with the DIR, such predetermined wage rate shall become effective on the date following the expiration date and shall apply to this Contract in the same manner as if it had been published in said publication. If the predetermined wage rate refers to one or more additional expiration dates with additional predetermined wage rates, which expiration dates occur during the life of this Contract, each successive predetermined wage rate shall apply to this Contract on the date following the expiration date of the previous wage rate. If the last of such predetermined wage rates expires during the life of this Contract, such wage rate shall apply to the balance of the Contract.

8.2. Penalties for Violations. Contractor and its subcontractors shall comply with California Labor Code section 1775 in the event a worker is paid less than the prevailing wage rate for the work or craft in which the worker is employed.

8.3. Payroll Records. Contractor and its subcontractors shall comply with California Labor Code section 1776, which generally requires keeping accurate payroll records, verifying and certifying payroll records, and making them available for inspection. Contractor shall require its subcontractors to also comply with section 1776. Contractor and its subcontractors shall submit weekly certified payroll records online via the City's web-based Labor Compliance Program. Contractor is responsible for ensuring its subcontractors submit certified payroll records to the City.

8.3.1. For contracts entered into on or after April 1, 2015, Contractor and their subcontractors shall furnish records specified in Labor Code section 1776 directly to the Labor Commissioner in the manner required by Labor Code section 1771.4.

8.4. Apprentices. Contractor and its subcontractors shall comply with California Labor Code sections 1777.5, 1777.6 and 1777.7 concerning the employment and wages of apprentices. Contractor is held responsible for the compliance of their subcontractors with sections 1777.5, 1777.6 and 1777.7.

- 8.5. Working Hours.** Contractor and their subcontractors shall comply with California Labor Code sections 1810 through 1815, including but not limited to: (i) restrict working hours on public works contracts to eight hours a day and forty hours a week, unless all hours worked in excess of 8 hours per day are compensated at not less than 1½ times the basic rate of pay; and (ii) specify penalties to be imposed on design professionals and subcontractors of \$25 per worker per day for each day the worker works more than 8 hours per day and 40 hours per week in violation of California Labor Code sections 1810 through 1815.
- 8.6. Required Provisions for Subcontracts.** Contractor shall include at a minimum a copy of the following provisions in any contract they enter into with a subcontractor: California Labor Code sections 1771, 1771.1, 1775, 1776, 1777.5, 1810, 1813, 1815, 1860 and 1861.
- 8.7. Labor Code Section 1861 Certification.** Contractor in accordance with California Labor Code section 3700 is required to secure the payment of compensation of its employees and by signing this Contract, Contractor certifies that “I am aware of the provisions of Section 3700 of the California Labor Code which require every employer to be insured against liability for workers’ compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the work of this Contract.”
- 8.8. Labor Compliance Program.** The City has its own Labor Compliance Program authorized in August 2011 by the DIR. The City will withhold contract payments when payroll records are delinquent or deemed inadequate by the City or other governmental entity, or it has been established after an investigation by the City or other governmental entity that underpayment(s) have occurred. For questions or assistance, please contact the City of San Diego’s Equal Opportunity Contracting Department at 619-236-6000.
- 8.9. Contractor and Subcontractor Registration Requirements.** This project is subject to compliance monitoring and enforcement by the DIR. As of March 1, 2015, no contractor or subcontractor may be listed on a bid or proposal for a public works project unless registered with the DIR pursuant to Labor Code section 1725.5. As of April 1, 2015, a contractor or subcontractor shall not be qualified to bid on, be listed in a bid proposal, or enter into any contract for public work, unless currently registered and qualified to perform public work pursuant to Labor Code section 1725.5. By submitting a bid or proposal to the City, Contractor is certifying that he or she has verified that all subcontractors used on this public work project are registered with the DIR in compliance with Labor Code sections 1771.1 and 1725.5, and Contractor shall provide proof of registration to the City upon request.
- 8.9.1.** A Contractor’s inadvertent error in listing a subcontractor who is not registered pursuant to Labor Code section 1725.5 in response to a solicitation shall not be grounds for filing a bid protest or grounds for considering the bid non-responsive provided that any of the following apply: (1) the subcontractor is registered prior to bid opening; (2) within twenty-four hours after the bid opening, the subcontractor is registered and has paid the penalty registration fee specified in Labor Code section 1725.5; or (3) the subcontractor is replaced by another registered subcontractor pursuant to Public Contract Code section 4107.

9. INSURANCE REQUIREMENTS:

- 9.1. All certificates of insurance and endorsements required by the contract are to be provided upon issuance of the City’s Notice of Intent to Award letter.
- 9.2. Refer to sections 7-3, “LIABILITY INSURANCE”, and 7-4, “WORKERS’ COMPENSATION INSURANCE” of the Supplementary Special Provisions (SSP) for the insurance requirements which must be met.

10. PREQUALIFICATION OF CONTRACTORS:

- 10.1. Contractors submitting Bid must be pre-qualified for the total amount proposed, inclusive of all alternate items prior to the date of submittal. Bids from contractors who have not been pre-qualified as applicable and Bids that exceed the maximum dollar amount at which contractors are pre-qualified will be deemed **non-responsive** and ineligible for award. Complete information and links to the online prequalification application are available at:

<http://www.sandiego.gov/cip/bidopps/prequalification.shtml>

- 10.2. The completed application must be submitted online to the Public Works Contracts, Prequalification Program no later than 2 weeks prior to the bid opening. For additional information or the answer to questions about the prequalification program, contact David Stucky at 619-533-3474 or dstucky@sandiego.gov.

11. REFERENCE STANDARDS: Except as otherwise noted or specified, the Work shall be completed in accordance with the following standards:

Title	Edition	Document Number
Standard Specifications for Public Works Construction (“The GREENBOOK”)	2012	PITS070112-01
City of San Diego Standard Specifications for Public Works Construction (“The WHITEBOOK”)*	2012	PITS070112-02
City of San Diego Standard Drawings*	2012	PITS070112-03
Caltrans Standard Specifications	2010	PITS070112-04
Caltrans Standard Plans	2010	PITS070112-05
California MUTCD	2012	PITS070112-06
City Standard Drawings - Updates Approved For Use (when specified)*	Varies	Varies
Standard Federal Equal Employment Opportunity Construction Contract Specifications and the Equal Opportunity Clause Dated 09-11-84	1984	769023
NOTE: *Available online under Engineering Documents and References at: http://www.sandiego.gov/publicworks/edocref/index.shtml		

12. **CITY'S RESPONSES AND ADDENDA:** The City at its option, may respond to any or all questions submitted in writing, via letter, or FAX in the form of an addendum. No oral comment shall be of any force or effect with respect to this solicitation. The changes to the Contract Documents through addendum are made effective as though originally issued with the Bid. The Bidders shall acknowledge the receipt of Addenda on the form provided for this purpose in the Bid.
13. **CITY'S RIGHTS RESERVED:** The City reserves the right to cancel the Notice Inviting Bids at any time, and further reserves the right to reject submitted Bids, without giving any reason for such action, at its sole discretion and without liability. Costs incurred by the Bidder(s) as a result of preparing Bids under the Notice Inviting Bids shall be the sole responsibility of each bidder. The Notice Inviting Bids creates or imposes no obligation upon the City to enter a contract.
14. **CONTRACT PRICING FORMAT:** This solicitation is for a Lump Sum contract with Unit Price provisions as set forth in the Bid Proposal Form(s), Volume 2.
15. **SUBMITTAL OF "OR EQUAL" ITEMS:** See Section 4-1.6, "Trade Names or Equals" in The WHITEBOOK and as amended in the SSP.
16. **AWARD PROCESS:**
 - 16.1. The Award of this contract is contingent upon the Contractor's compliance with all conditions precedent to Award.
 - 16.2. Upon acceptance of a Bid, the City will prepare contract documents for execution within approximately 21 days of the date of the Bid opening and award the Contract approximately within 7 days of receipt of properly executed Contract, bonds, and insurance documents.
 - 16.3. This contract will be deemed executed, and effective, only upon the signing of the Contract by the Mayor or designee of the City.
17. **SUBCONTRACT LIMITATIONS:** The Bidder's attention is directed to Standard Specifications for Public Works Construction, Section 2-3, "SUBCONTRACTS" in The GREENBOOK and as amended in the SSP which requires the Contractor to self-perform not less than the specified amount. Failure to comply with this requirement shall render the bid **non-responsive** and ineligible for award.
18. **AVAILABILITY OF PLANS AND SPECIFICATIONS:** Contract Documents may be obtained by visiting the City's website: <http://www.sandiego.gov/cip/>. Plans and Specifications for this contract are also available for review in the office of the City Clerk or Public Works Contracts.
19. **SUBMISSION OF QUESTIONS:**
 - 19.1. The Director (or designee), of the Public Works Department is the officer responsible for opening, examining, and evaluating the competitive Bids submitted to the City for the acquisition, construction and completion of any public improvement except when otherwise set forth in these documents. All questions related to this solicitation shall be submitted to:

Public Works Contracts
1010 Second Avenue, 14th Floor
San Diego, California, 92101
Attention: [Contract Specialist listed on the front cover hereof]

OR:

Email address of the Contract Specialist listed on the front cover hereof.

- 19.2. Questions received less than 14 days prior to the date for opening of Bids may not be considered.
 - 19.3. Clarifications deemed by the City to be material shall be issued by Addenda and uploaded to the City's online bidding service.
 - 19.4. Only questions answered by formal written addenda will be binding. Oral and other interpretations or clarifications will be without legal effect. It is the Bidder's responsibility to become informed of any Addenda that have been issued and to include all such information in its Bid.
20. **ELIGIBLE BIDDERS:** No person, firm, or corporation shall be allowed to make, file, or be interested in more than one (1) Bid for the same work unless alternate Bids are called for. A person, firm or corporation who has submitted a sub-proposal to a Bidder, or who has quoted prices on materials to a Bidder, is not hereby disqualified from submitting a sub-proposal or quoting prices to other Bidders or from submitting a Bid in its own behalf. Any Bidder who submits more than one bid will result in the rejection of all bids submitted.
 21. **SAN DIEGO BUSINESS TAX CERTIFICATE:** The Contractor and Subcontractors, not already having a City of San Diego Business Tax Certificate for the work contemplated shall secure the appropriate certificate from the City Treasurer, Civic Center Plaza, first floor and submit to the Contract Specialist upon request or as specified in the Contract Documents. Tax Identification numbers for both the Bidder and the listed Subcontractors must be submitted on the City provided forms with the Notice Inviting Bids and Contract forms.
 22. **PROPOSAL FORMS:** Bid shall be made only upon the Bidding Documents i.e., Proposal form attached to and forming a part of the specifications. The signature of each person signing shall be in longhand.
 - 22.1. Bidder shall complete and submit all pages in the "Bidding Document" Section (see Volume 2) as their Bid per the schedule given under "Required Documents Schedule," (see Volume 1). Bidder is requested to retain for their reference other portions of the Contract Documents that are not required to be submitted with the Bid. The entire specifications for the bid package do not need to be submitted with the bid.
 - 22.2. The City may require any Bidder to furnish a statement of experience, financial responsibility, technical ability, equipment, and references.
 - 22.3. Bids and certain other forms and documents as specified in the Volume 2 of 2 of the Contract Documents shall be enclosed in a sealed envelope and shall bear the title of the work and name of the Bidder and the appropriate State Contractors License designation which the Bidder holds.

22.4. Bids may be withdrawn by the Bidder prior to, but not after, the time fixed for opening of Bids.

23. BIDDER'S GUARANTEE OF GOOD FAITH (BID SECURITY):

23.1. Bidders shall submit Bid Security at bid time. Bid Security shall be in one of the following forms: a cashier's check, or a properly certified check upon some responsible bank; or an approved corporate surety bond payable to the City of San Diego for an amount of not less than 10% of the total bid amount.

23.2. This check or bond, and the monies represented thereby, will be held by the City as a guarantee that the Bidder, if awarded the contract, will in good faith enter into the contract and furnish the required final performance and payment bonds.

23.3. The Bidder agrees that in the event of the Bidder's failure to execute this contract and provide the required final bonds, the money represented by the cashier's or certified check will remain the property of the City; and the Surety agrees that it will pay to the City the damages, not exceeding the sum of 10% of the amount of the Bid, that the City may suffer as a result of such failure.

23.4. A Bid received without the specified bid security may be rejected as **non-responsive**.

24. AWARD OF CONTRACT OR REJECTION OF BIDS:

24.1. This contract may be awarded to the lowest responsible and reliable Bidder.

24.2. Bidders shall complete the entire Bid schedule (also referred to as "schedule of prices" or Proposal form). Incomplete price schedules will be rejected as being non-responsive.

24.3. The City reserves the right to reject any or all Bids, and to waive any informality or technicality in Bids received and any requirements of these specifications as to bidding procedure.

24.4. Bidders will not be released on account of their errors of judgment. Bidders may be released only upon receipt by the City from the Bidder within 3 Working Days, excluding Saturdays, Sundays, and state holidays, after the opening of Bids, of written notice which includes proof of honest, credible, clerical error of material nature, free from fraud or fraudulent intent, and of evidence that reasonable care was observed in the preparation of the Bid.

24.5. A non-selected Bidder may protest award of the Contract to the selected Bidder by submitting a written "Notice of Intent to Protest" including supporting documentation which shall be received by Public Works Contracts no later than 10 days after the City's announcement of the selected Bidder or no later than 10 days from the date that the City issues notice of designation of a Bidder as non-responsive in accordance with San Diego Municipal Code Chapter 2, § 22.3029, "Protests of Contract Award."

- 24.6. The City of San Diego will not discriminate with regard to race, religious creed, color, national origin, ancestry, physical handicap, marital status, sex or age, in the award of contracts.
- 24.7. Each Bid package properly executed as required by these specifications shall constitute a firm offer, which may be accepted by the City within the time specified in the Proposal.
- 24.8. The City reserves the right to evaluate all Bids and determine the lowest Bidder on the basis of any proposed alternates, additive items or options, at its discretion that will be disclosed in the Volume 2 of 2.

25. BID RESULTS:

- 25.1. The Bid opening by the City shall constitute the public announcement of the Apparent Low Bidder. In the event that the Apparent Low Bidder is subsequently deemed non-responsive or non-responsible, a public announcement will be posted in the City's web page <http://www.sandiego.gov/cip/index.shtml>, with the name of the newly designated Apparent Low Bidder.
- 25.2. To obtain Bid results, either attend Bid opening, review the results on the City's web site, or provide a self-addressed, stamped envelope, referencing Bid number, and Bid tabulation will be mailed to you upon verification of extensions. Bid results cannot be given over the telephone.

26. THE CONTRACT:

- 26.1. The Bidder to whom award is made shall execute a written contract with the City of San Diego and furnish good and approved bonds and insurance certificates specified by the City within 14 days after receipt by Bidder of a form of contract for execution unless an extension of time is granted to the Bidder in writing.
- 26.2. If the Bidder takes longer than 14 days to fulfill these requirements, then the additional time taken shall be added to the Bid guarantee. The Contract shall be made in the form adopted by the City, which includes the provision that no claim or suit whatsoever shall be made or brought by Contractor against any officer, agent, or employee of the City for or on account of anything done or omitted to be done in connection with this contract, nor shall any such officer, agent, or employee be liable hereunder.
- 26.3. If the Bidder to whom the award is made fails to enter into the contract as herein provided, the award may be annulled and the Bidder's Guarantee of Good Faith will be subject to forfeiture. An award may be made to the next lowest responsible and reliable Bidder who shall fulfill every stipulation embraced herein as if it were the party to whom the first award was made.
- 26.4. Pursuant to the San Diego City Charter section 94, the City may only award a public works contract to the lowest responsible and reliable Bidder. The City will require the Apparent Low Bidder to (i) submit information to determine the Bidder's responsibility and reliability, (ii) execute the Contract in form provided by the City, and (iii) furnish good and approved bonds and insurance certificates specified by the

City within 14 Days, unless otherwise approved by the City, in writing after the Bidder receives notification from the City, designating the Bidder as the Apparent Low Bidder and formally requesting the above mentioned items.

- 26.5.** The award of the Contract is contingent upon the satisfactory completion of the above mentioned items and becomes effective upon the signing of the Contract by the Mayor or designee. If the Apparent Low Bidder does not execute the Contract or submit required documents and information, the City may award the Contract to the next lowest responsible and reliable Bidder who shall fulfill every condition precedent to award. A corporation designated as the Apparent Low Bidder shall furnish evidence of its corporate existence and evidence that the officer signing the Contract and bond for the corporation is duly authorized to do so.
- 27. EXAMINATION OF PLANS, SPECIFICATIONS, AND SITE OF WORK:** The Bidder shall examine carefully the Project Site, the Plans and Specifications, other materials as described in the Special Provisions, Section 2-7, and the proposal forms (e.g., Bidding Documents). The submission of a Bid shall be conclusive evidence that the Bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and scope of Work, the quantities of materials to be furnished, and as to the requirements of the Bidding Documents Proposal, Plans, and Specifications.
- 28. CITY STANDARD PROVISIONS:** This contract is subject to the following standard provisions. See The WHITEBOOK for details.
- 28.1.** The City of San Diego Resolution No. R-277952 adopted on May 20, 1991 for a Drug-Free Workplace.
- 28.2.** The City of San Diego Resolution No. R-282153 adopted on June 14, 1993 related to the Americans with Disabilities Act.
- 28.3.** The City of San Diego Municipal Code §22.3004 for Pledge of Compliance.
- 28.4.** The City of San Diego's Labor Compliance Program and the State of California Labor Code §§1771.5(b) and 1776.
- 28.5.** Sections 1777.5, 1777.6, and 1777.7 of the State of California Labor Code concerning the employment of apprentices by contractors and subcontractors performing public works contracts.
- 28.6.** The City's Equal Benefits Ordinance (EBO), Chapter 2, Article 2, Division 43 of The San Diego Municipal Code (SDMC).
- 28.7.** The City's Information Security Policy (ISP) as defined in the City's Administrative Regulation 90.63.
- 29. PRE-AWARD ACTIVITIES:**
- 29.1.** The selected contractor by the City to execute a contract for this Work shall provide the information required within the time specified in "Required Documents," of this bid package. Failure to provide the information within the time specified may result in the Bid being rejected as **non-responsive**.

29.2. If the Bid is rejected as non-responsive, the selected contractor by the City to execute a contract for this Work shall forfeit the required Bid. The decision that the selected contractor by the City to execute a contract for this Work is non-responsive for failure to provide the information required within the time specified shall be at the sole discretion of the City.

30. REQUIRED DOCUMENT SCHEDULE:

30.1. The Bidder's attention is directed to the City's Municipal Code §22.0807(e), (3)-(5) for important information regarding grounds for debarment for failure to submit required documentation.

30.2. The specified Equal Opportunity Contracting Program (EOCP) forms are available for download from the City's web site at:

<http://www.sandiego.gov/eoc/forms/index.shtml>

ITEM	WHEN DUE	FROM	DOCUMENT TO BE SUBMITTED
1.	BID SUBMITTAL DATE/TIME	ALL BIDDERS	Bid
2.	BID SUBMITTAL DATE/TIME	ALL BIDDERS	Bid Bond
3.	BID SUBMITTAL DATE/TIME	ALL BIDDERS	Non-collusion Affidavit to be Executed By Bidder and Submitted with Bid under 23 USC 112 and PCC 7106
4.	BID SUBMITTAL DATE/TIME	ALL BIDDERS	Contractors Certification of Pending Actions
5.	BID SUBMITTAL DATE/TIME	ALL BIDDERS	Equal Benefits Ordinance Certification of Compliance
6.	BID SUBMITTAL DATE/TIME	ALL BIDDERS	Form AA35 - List of Subcontractors
7.	BID SUBMITTAL DATE/TIME	ALL BIDDERS	Form AA40 - Named Equipment/Material Supplier List
8.	WITHIN 3 WORKING DAYS OF BID OPENING	ALL BIDDERS	SLBE Good Faith Efforts Documentation
9.	WITHIN 3 WORKING DAYS OF BID OPENING WITH GOOD FAITH EFFORT DOCUMENTATION	ALL BIDDERS	Form AA60 – List of Work Made Available
10.	WITHIN 3 WORKING DAYS OF BID OPENING WITH GOOD FAITH EFFORT DOCUMENTATION	ALL BIDDERS	Proof of Valid DBE-MBE-WBE-DVBE Certification Status e.g., Certs.

ITEM	WHEN DUE	FROM	DOCUMENT TO BE SUBMITTED
11.	WITHIN 10 WORKING DAYS AFTER RECEIPT BY BIDDER OF CONTRACT FORMS	APPARENT LOW BIDDER	Names of the principal individual owners of the Apparent Low Bidder
12.	WITHIN 10 WORKING DAYS AFTER RECEIPT BY BIDDER OF CONTRACT FORMS	APPARENT LOW BIDDER	If the Contractor is a Joint Venture: <ul style="list-style-type: none"> • Joint Venture Agreement • Joint Venture License
13.	WITHIN 10 WORKING DAYS AFTER RECEIPT BY BIDDER OF CONTRACT FORMS	APPARENT LOW BIDDER	Form BB05 - Work Force Report
14.	WITHIN 10 WORKING DAYS AFTER RECEIPT BY BIDDER OF CONTRACT FORMS	APPARENT LOW BIDDER	Contract Forms - Agreement
15.	WITHIN 10 WORKING DAYS AFTER RECEIPT BY BIDDER OF CONTRACT FORMS	APPARENT LOW BIDDER	Contract Forms - Payment and Performance Bond
16.	WITHIN 10 WORKING DAYS AFTER RECEIPT BY BIDDER OF CONTRACT FORMS	APPARENT LOW BIDDER	Certificates of Insurance and Endorsements
17.	WITHIN 10 WORKING DAYS AFTER RECEIPT BY BIDDER OF CONTRACT FORMS	APPARENT LOW BIDDER	Contractor Certification - Drug-Free Workplace
18.	WITHIN 10 WORKING DAYS AFTER RECEIPT BY BIDDER OF CONTRACT FORMS	APPARENT LOW BIDDER	Contractor Certification - American with Disabilities Act
19.	WITHIN 10 WORKING DAYS AFTER RECEIPT BY BIDDER OF CONTRACT FORMS	APPARENT LOW BIDDER	Contractors Standards - Pledge of Compliance

CONTRACT FORMS
AGREEMENT

CONTRACT FORMS

CONSTRUCTION CONTRACT

This contract is made and entered into between THE CITY OF SAN DIEGO, a municipal corporation, herein called "City", and SUPERIOR READY MIX CONCRETE, L.P DBA SRM CONTRACTING & PAVING, herein called "Contractor" for construction of **UUP Sherman Heights Street Resurfacing**, Bid No **K-15-1361-DBB-3**, in the amount of ONE MILLION SEVEN HUNDRED SEVENTY-THREE THOUSAND TWO HUNDRED DOLLARS (\$1,773,200.00), which is comprised of the Base Bid alone.

IN CONSIDERATION of the payments to be made hereunder and the mutual undertakings of the parties hereto, City and Contractor agree as follows:

1. The following are incorporated into this contract as though fully set forth herein:
 - (a) The attached Faithful Performance and Payment Bonds.
 - (b) The attached Proposal included in the Bid documents by the Contractor.
 - (c) Reference Standards listed in the Notice Inviting Bids and the Supplementary Special Provisions (SSP).
 - (d) That certain documents entitled **UUP Sherman Heights Street Resurfacing**, on file in the office of the Public Works Department as Document No. **B-00829, B-00714, B-00851, B-00705**, as well as all matters referenced therein.
2. The Contractor shall perform and be bound by all the terms and conditions of this contract and in strict conformity therewith shall perform and complete in a good and workmanlike manner **UUP Sherman Heights Street Resurfacing**; Bid Number **K-15-1361-DBB-3**, San Diego, California.
3. For such performances, the City shall pay to Contractor the amounts set forth at the times and in the manner and with such additions or deductions as are provided for in this contract, and the Contractor shall accept such payment in full satisfaction of all claims incident to such performances.
4. No claim or suit whatsoever shall be made or brought by Contractor against any officer, agent, or employee of the City for or on account of anything done or omitted to be done in connection with this contract, nor shall any such officer, agent, or employee be liable hereunder.
5. This contract is effective as of the date that the Mayor or designee signs the agreement.


CONTRACT FORMS (continued)


IN WITNESS WHEREOF, this Agreement is signed by the City of San Diego, acting by and through its Mayor or designee, pursuant to Municipal Code §22.3102 authorizing such execution.

THE CITY OF SAN DIEGO

APPROVED AS TO FORM

Jan I. Goldsmith, City Attorney

By: 
Stephen Samara
Principal Contract Specialist
Public Works Contracting Group

By: 
Print Name: RYAN P. GERRITY
Deputy City Attorney

Date: 8-31-15

Date: 9/3/15

CONTRACTOR

By: 

Print Name: Arnold Veldkamp

Title: Secretary

Date: _____

City of San Diego License No.: B1982002304

State Contractor's License No.: 626277

CONTRACT FORMS
ATTACHMENTS

**CONTRACT FORMS ATTACHMENTS
PERFORMANCE BOND AND LABOR AND MATERIALMEN'S BOND**

FAITHFUL PERFORMANCE BOND AND LABOR AND MATERIALMEN'S BOND:

SUPERIOR READY MIX CONCRETE, L.P DBA SRM CONTRACTING & PAVING, a corporation, as principal, and Nationwide Mutual Insurance Company, a corporation authorized to do business in the State of California, as Surety, hereby obligate themselves, their successors and assigns, jointly and severally, to The City of San Diego a municipal corporation in the sum of ONE MILLION SEVEN HUNDRED SEVENTY-THREE THOUSAND TWO HUNDRED DOLLARS (\$1,773,200.00) for the faithful performance of the annexed contract, and in the sum of ONE MILLION SEVEN HUNDRED SEVENTY-THREE THOUSAND TWO HUNDRED DOLLARS (\$1,773,200.00) for the benefit of laborers and materialmen designated below.

Conditions:

If the Principal shall faithfully perform the annexed contract **UUP Sherman Heights Street Resurfacing**, Bid Number **K-15-1361-DBB-3**, San Diego, California then the obligation herein with respect to a faithful performance shall be void; otherwise it shall remain in full force.

If the Principal shall promptly pay all persons, firms and corporations furnishing materials for or performing labor in the execution of this contract, and shall pay all amounts due under the California Unemployment Insurance Act then the obligation herein with respect to laborers and materialmen shall be void; otherwise it shall remain in full force.

The obligation herein with respect to laborers and materialmen shall inure to the benefit of all persons, firms and corporations entitled to file claims under the provisions of Chapter 3 of Division 5 of Title I of the Government Code of the State of California or under the provisions of Section 3082 et seq. of the Civil Code of the State of California.

Changes in the terms of the annexed contract or specifications accompanying same or referred to therein shall not affect the Surety's obligation on this bond, and the Surety hereby waives notice of same.

CONTRACT FORMS ATTACHMENTS (continued)
PERFORMANCE BOND AND LABOR AND MATERIALMEN'S BOND

The Surety shall pay reasonable attorney's fees should suit be brought to enforce the provisions of this bond.

Dated July 7, 2015

Approved as to Form


Superior Ready Mix Concrete, L.P. dba SRM Contracting & Paving

Principal

By 


Arnold Veldkamp
Printed Name of Person Signing for Principal

Jan I. Goldsmith, City Attorney

By 
Deputy City Attorney

Nationwide Mutual Insurance Company

Surety

By 
Attorney-in-fact

Approved:

By: 
Stephen Samara
Principal Contract Specialist
Public Works Contracting Group

PO Box 1820

Local Address of Surety

La Mesa, CA 91944

Local Address (City, State) of Surety

619-668-6543

Local Telephone No. of Surety

Premium \$ 7,979.00

Bond No. Bd 740775

ACKNOWLEDGMENT


A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

State of California
County of San Diego

On July 7, 2015 before me, Michele M. Stubbs, Notary Public, personally appeared Arnold Veldkamp, who proved to me on the basis of satisfactory evidence to be the person whose name is subscribed to the within instrument and acknowledged to me that he executed the same in his authorized capacity, and that by his signature on the instrument the person, or the entity upon behalf of which the person acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.



Michele M. Stubbs

Power of Attorney

KNOW ALL MEN BY THESE PRESENTS THAT:

Nationwide Mutual Insurance Company, an Ohio corporation
Farmland Mutual Insurance Company, an Iowa corporation
Nationwide Agribusiness Insurance Company, an Iowa corporation

AMCO Insurance Company, an Iowa corporation
Allied Property and Casualty Insurance Company, an Iowa corporation
Depositors Insurance Company, an Iowa corporation

hereinafter referred to severally as the "Company" and collectively as the "Companies," each does hereby make, constitute and appoint:

Keith E. Clements La Mesa, CA

each in their individual capacity, its true and lawful attorney-in-fact, with full power and authority to sign, seal, and execute on its behalf any and all bonds and undertakings, and other obligatory instruments of similar nature, in penalties not exceeding the sum of

Five Million and no/100

\$5,000,000.00

and to bind the Company thereby, as fully and to the same extent as if such instruments were signed by the duly authorized officers of the Company; and all acts of said Attorney pursuant to the authority given are hereby ratified and confirmed.

This power of attorney is made and executed pursuant to and by authority of the following resolution duly adopted by the board of directors of the Company:

"RESOLVED, that the president, or any vice president be, and each hereby is, authorized and empowered to appoint attorneys-in-fact of the Company, and to authorize them to execute and deliver on behalf of the Company any and all bonds, forms, applications, memorandums, undertakings, recognizances, transfers, contracts of indemnity, policies, contracts guaranteeing the fidelity of persons holding positions of public or private trust, and other writings obligatory in nature that the business of the Company may require; and to modify or revoke, with or without cause, any such appointment or authority; provided, however, that the authority granted hereby shall in no way limit the authority of other duly authorized agents to sign and countersign any of said documents on behalf of the Company."

"RESOLVED FURTHER, that such attorneys-in-fact shall have full power and authority to execute and deliver any and all such documents and to bind the Company subject to the terms and limitations of the power of attorney issued to them, and to affix the seal of the Company thereto; provided, however, that said seal shall not be necessary for the validity of any such documents."

This power of attorney is signed and sealed under and by the following bylaws duly adopted by the board of directors of the Company.

Execution of Instruments. Any vice president, any assistant secretary or any assistant treasurer shall have the power and authority to sign or attest all approved documents, instruments, contracts, or other papers in connection with the operation of the business of the company in addition to the chairman of the board, the chief executive officer, president, treasurer or secretary; provided, however, the signature of any of them may be printed, engraved, or stamped on any approved document, contract, instrument, or other papers of the Company.

IN WITNESS WHEREOF, the Company has caused this instrument to be sealed and duly attested by the signature of its officer the 13th day of February, 2014.

Terrance Williams, President and Chief Operating Officer of Nationwide Agribusiness Insurance Company and Farmland Mutual Insurance Company; and **Vice President** of Nationwide Mutual Insurance Company, AMCO Insurance Company, Allied Property and Casualty Insurance Company, and Depositors Insurance Company

ACKNOWLEDGMENT

STATE OF IOWA, COUNTY OF POLK: ss

On this 13th day of February, 2014, before me came the above-named officer for the Companies aforesaid, to me personally known to be the officer described in and who executed the preceding instrument, and he acknowledged the execution of the same, and being by me duly sworn, deposes and says, that he is the officer of the Companies aforesaid, that the seals affixed hereto are the corporate seals of said Companies, and the said corporate seals and his signature were duly affixed and subscribed to said instrument by the authority and direction of said Companies.

Sandy Alitz
Notarial Seal - Iowa
Commission Number 152785
My Commission Expires March, 24, 2017

Notary Public
My Commission Expires
March 24, 2017

CERTIFICATE

I, Robert W Horner III, Assistant Secretary of the Companies, do hereby certify that the foregoing is a full, true and correct copy of the original power of attorney issued by the Company; that the resolution included therein is a true and correct transcript from the minutes of the meetings of the boards of directors and the same has not been revoked or amended in any manner; that said Terrance Williams was on the date of the execution of the foregoing power of attorney the duly elected officer of the Companies, and the corporate seals and his signature as officer were duly affixed and subscribed to the said instrument by the authority of said board of directors; and the foregoing power of attorney is still in full force and effect.

IN WITNESS WHEREOF, I have hereunto subscribed my name as Assistant Secretary, and affixed the corporate seals of said Companies this 7th day of July, 20 15.

Assistant Secretary

This Power of Attorney Expires March 24, 2017

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.


ACKNOWLEDGMENT

State of California
County of San Diego

On July 7, 2015 before me, Diana Kelly, Notary Public, personally appeared Keith E. Clements who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/~~she~~/they executed the same in his/~~her~~/~~their~~ authorized capacity(ies), and that by his/~~her~~/~~their~~ signature(s) on the instrument the person(s) or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.



Diana Kelly

CONTRACTOR CERTIFICATION


DRUG-FREE WORKPLACE

PROJECT TITLE: UUP Sherman Heights Street Resurfacing

I hereby certify that I am familiar with the requirements of San Diego City Council Policy No. 100-17 regarding Drug-Free Workplace as outlined in the WHITEBOOK, Section 7-13.3, "Drug-Free Workplace", of the project specifications, and that;

SEM Contracting : PAVING
(Name under which business is conducted)

has in place a drug-free workplace program that complies with said policy. I further certify that each subcontract agreement for this project contains language which indicates the subcontractor's agreement to abide by the provisions of subdivisions a) through c) of the policy as outlined.

Signed 

Printed Name ARNOLD VELD KAMP

Title SECRETARY

CONTRACTOR CERTIFICATION

AMERICAN WITH DISABILITIES ACT (ADA) COMPLIANCE CERTIFICATION

PROJECT TITLE: UUP Sherman Heights Street Resurfacing


I hereby certify that I am familiar with the requirements of San Diego City Council Policy No. 100-4 regarding the American With Disabilities Act (ADA) outlined in the WHITEBOOK, Section 7-13.2, "American With Disabilities Act", of the project specifications, and that;

SRM Contracting, Paving

(Name under which business is conducted)

has in place a workplace program that complies with said policy. I further certify that each subcontract agreement for this project contains language which indicates the subcontractor's agreement to abide by the provisions of the policy as outlined.

Signed



Printed Name

Arnold Veldkamp

Title

Secretary

CONTRACTOR CERTIFICATION

CONTRACTOR STANDARDS – PLEDGE OF COMPLIANCE

PROJECT TITLE: UUP Sherman Heights Street Resurfacing

I declare under penalty of perjury that I am authorized to make this certification on behalf of SEM Contracting, PAVING, as Contractor, that I am familiar with the requirements of City of San Diego Municipal Code § 22.3224 regarding Contractor Standards as outlined in the WHITEBOOK, Section 7-13.4, ("Contractor Standards"), of the project specifications, and that Contractor has complied with those requirements.

I further certify that each of the Contractor's subcontractors whose subcontracts are greater than \$50,000 in value has completed a Pledge of Compliance attesting under penalty of perjury of having complied with City of San Diego Municipal Code § 22.3224.

Dated this 10th Day of July, 2015.

Signed 

Printed Name Arnold Veldkamp

Title Secretary

AFFIDAVIT OF DISPOSAL

WHEREAS, on the _____ DAY OF _____, 2_____ the undersigned entered into and executed a contract with the City of San Diego, a municipal corporation, for:

UUP Sherman Heights Street Resurfacing

(Name of Project)

as particularly described in said contract and identified as Bid No. **K-15-1361-DBB-3**; SAP No. (WBS/IO/CC) **B-00829, B-00714, B-00851, B-00705**; and **WHEREAS**, the specification of said contract requires the Contractor to affirm that "all brush, trash, debris, and surplus materials resulting from this project have been disposed of in a legal manner"; and **WHEREAS**, said contract has been completed and all surplus materials disposed of:

NOW, THEREFORE, in consideration of the final payment by the City of San Diego to said Contractor under the terms of said contract, the undersigned Contractor, does hereby affirm that all surplus materials as described in said contract have been disposed of at the following location(s)

and that they have been disposed of according to all applicable laws and regulations.

Dated this _____ DAY OF _____, _____.

by _____ Contractor

ATTEST:

State of _____
County of _____

On this _____ DAY OF _____, 2_____, before the undersigned, a Notary Public in and for said County and State, duly commissioned and sworn, personally appeared _____ known to me to be the _____ Contractor named in the foregoing Release, and whose name is subscribed thereto, and acknowledged to me that said Contractor executed the said Release.

Notary Public in and for said County and State

ATTACHMENTS

ATTACHMENT A
SCOPE OF WORK

SCOPE OF WORK

1. **SCOPE OF WORK:** Asphalt overlay / slurry seal and curb ramp installations for Utilities Underground Program Sherman Heights (8G, 8F, K Street Phase I & II and Island Ave Phase I & II) in Council District 8, including all labor, materials, equipments, services, and other associated minor repair and incidental works and appurtenances. Details of work are described in Appendix D, E and F.

The asphalt overlay work includes placement of asphalt concrete, adjustment of city manhole and gate valve covers, cold milling, pavement base repair, street and sidewalk sweeping, tree trimming, replace traffic striping and markings/legends, traffic control drawings& permits, storm drain inlet protection and the replacement of inlet markers, sediment control and all other incidental works.

The slurry seal work includes weed abatement, crack sealing, milling, pavement base repair, application of Rubber Polymer Modified Slurry (RPMS) Type II, replacing traffic striping/markings, traffic control drawings and permits, storm drain inlet protection, sweeping and all other incidental works.

All existing crosswalks shall be replaced with continental crosswalks per City Standard Drawing in Appendix H.

- 1.1. The Work shall be performed in accordance with:

- 1.1.1. The Notice Inviting Bids, inclusive.

2. **CONSTRUCTION COST:** The City’s estimated construction cost for this contract is **\$2,210,000.**
3. **LOCATION OF WORK:** Utilities Underground Program District Sherman Heights (8F, 8G, Island Ave Phase I & II and K Street Phase I & II), in Council District 8.
4. **CONTRACT TIME:** The Contract Time for completion of the Work shall be **120 Working Days.**
5. **CONTRACTOR'S LICENSE CLASSIFICATION:** In accordance with the provisions of California Law, the Contractor shall possess valid appropriate licenses at the time that the Bid is submitted. Failure to possess the specified licenses shall render the Bid as **non-responsive** and shall act as a bar to award of the Contract to any Bidder not possessing required licenses at the time of Bid.

- 5.1. The City has determined the following licensing classifications for this contract:

Option	Classifications
1	CLASS A
2	CLASS C12

- 5.2. The Bidder shall satisfy the licensing requirement by meeting **at least** one of the listed options.

ATTACHMENT B
INTENTIONALLY LEFT BLANK

ATTACHMENT C
EQUAL OPPORTUNITY CONTRACTING PROGRAM

EQUAL OPPORTUNITY CONTRACTING PROGRAM REQUIREMENTS

1. To The WHITEBOOK, Chapter 10, Sections D and E, DELETE each in its entirety, and SUBSTITUTE with the following:

D. CITY'S EQUAL OPPORTUNITY COMMITMENT.

1. Nondiscrimination in Contracting Ordinance.

1. The Contractor, Subcontractors and Suppliers shall comply with requirements of the City's Nondiscrimination in Contracting Ordinance, San Diego Municipal Code §§22.3501 through 22.3517.

The Contractor shall not discriminate on the basis of race, gender, religion, national origin, ethnicity, sexual orientation, age, or disability in the solicitation, selection, hiring, or treatment of subcontractors, vendors, or suppliers. The Contractor shall provide equal opportunity for subcontractors to participate in subcontracting opportunities. The Contractor understands and agrees that violation of this clause shall be considered a material breach of the contract and may result in contract termination, debarment, or other sanctions.

The Contractor shall include the foregoing clause in all contracts between the Contractor and Subcontractors and Suppliers.

2. Disclosure of Discrimination Complaints. As part of its Bid or Proposal, the Bidder shall provide to the City a list of all instances within the past 10 years where a complaint was filed or pending against Bidder in a legal or administrative proceeding alleging that Bidder discriminated against its employees, subcontractors, vendors, or suppliers, and a description of the status or resolution of that complaint, including any remedial action taken.
3. Upon the City's request, the Contractor agrees to provide to the City, within 60 days, a truthful and complete list of the names of all Subcontractors and Suppliers that the Contractor has used in the past 5 years on any of its contracts that were undertaken within San Diego County, including the total dollar amount paid by the Contractor for each subcontract or supply contract.
4. The Contractor further agrees to fully cooperate in any investigation conducted by the City pursuant to the City's Nondiscrimination in Contracting Ordinance, Municipal Code §§22.3501 through 22.3517. The Contractor understands and agrees that violation of this clause shall be considered a material breach of the Contract and may result in remedies being ordered against the Contractor up to and including contract termination, debarment and other sanctions for violation of the provisions of the Nondiscrimination in Contracting Ordinance. The Contractor further understands and agrees that the procedures,

remedies and sanctions provided for in the Nondiscrimination in Contracting Ordinance apply only to violations of the Ordinance.

E. EQUAL EMPLOYMENT OPPORTUNITY OUTREACH PROGRAM.

1. The Contractor, Subcontractors and Suppliers shall comply with the City's Equal Employment Opportunity Outreach Program, San Diego Municipal Code §§22.2701 through 22.2707.

The Contractor shall not discriminate against any employee or applicant for employment on any basis prohibited by law. Contractor shall provide equal opportunity in all employment practices. Prime Contractor shall ensure their subcontractors comply with this program. Nothing in this section shall be interpreted to hold a prime contractor liable for any discriminatory practice of its subcontractors.

The Contractor shall include the foregoing clause in all contracts between the Contractor and Subcontractors and Suppliers.

2. If the Contract is competitively solicited, the selected Bidder shall submit a Work Force Report (Form BB05), within 10 Working Days after receipt by the Bidder of Contract forms to the City for approval as specified in the Notice of Intent to Award letter from the City.
3. If a Work Force Report is submitted, and the City determines there are under-representations when compared to County Labor Force Availability data, the selected Bidder shall submit an Equal Employment Opportunity Plan.
4. If the selected Bidder submits an Equal Employment Opportunity Plan, it shall include the following assurances:
 1. The Contractor shall maintain a working environment free of discrimination, harassment, intimidation and coercion at all sites and in all facilities at which the Contractor's employees are assigned to work.
 2. The Contractor reviews its EEO Policy, at least annually, with all on-site supervisors involved in employment decisions.
 3. The Contractor disseminates and reviews its EEO Policy with all employees at least once a year, posts the policy statement and EEO posters on all company bulletin boards and job sites, and documents every dissemination, review and posting with a written record to identify the time, place, employees present, subject matter, and disposition of meetings.
 4. The Contractor reviews, at least annually, all supervisors' adherence to and performance under the EEO Policy and maintains written documentation of these reviews.

5. The Contractor discusses its EEO Policy Statement with subcontractors with whom it anticipates doing business, includes the EEO Policy Statement in its subcontracts, and provides such documentation to the City upon request.
6. The Contractor documents and maintains a record of all bid solicitations and outreach efforts to and from subcontractors, contractor associations and other business associations.
7. The Contractor disseminates its EEO Policy externally through various media, including the media of people of color and women, in advertisements to recruit, maintains files documenting these efforts, and provides copies of these advertisements to the City upon request.
8. The Contractor disseminates its EEO Policy to union and community organizations.
9. The Contractor provides immediate written notification to the City when any union referral process has impeded the Contractor's efforts to maintain its EEO Policy.
10. The Contractor maintains a current list of recruitment sources, including those outreaching to people of color and women, and provides written notification of employment opportunities to these recruitment sources with a record of the organizations' responses.
11. The Contractor maintains a current file of names, addresses and phone numbers of each walk-in applicant, including people of color and women, and referrals from unions, recruitment sources, or community organizations with a description of the employment action taken.
12. The Contractor encourages all present employees, including people of color and women employees, to recruit others.
13. The Contractor maintains all employment selection process information with records of all tests and other selection criteria.
14. The Contractor develops and maintains documentation for on-the-job training opportunities, participates in training programs, or both for all of its employees, including people of color and women, and establishes apprenticeship, trainee, and upgrade programs relevant to the Contractor's employment needs.
15. The Contractor conducts, at least annually, an inventory and evaluation of all employees for promotional opportunities and encourages all employees to seek and prepare appropriately for such opportunities.
16. The Contractor ensures the company's working environment and activities are non-segregated except for providing separate or single-user toilets and necessary changing facilities to assure privacy between the sexes.

ATTACHMENT D
INTENTIONALLY LEFT BLANK

ATTACHMENT E
SUPPLEMENTARY SPECIAL PROVISIONS

SUPPLEMENTARY SPECIAL PROVISIONS

The following Supplementary Special Provisions (SSP) modifies the following documents:

- 1) Standard Specifications for Public Works Construction (The GREENBOOK) currently in effect.
 - 2) The City of San Diego Standard Specifications for Public Works Construction (The WHITEBOOK).
-

SECTION 1 – TERMS, DEFINITIONS, ABBREVIATIONS, UNITS OF MEASURE, AND SYMBOLS

1-2 TERMS AND DEFINITIONS.

Normal Working Hours. To the City Supplement, ADD the following:

The Normal Working Hours are 8:30 AM to 3:30 PM.

SECTION 2 - SCOPE AND CONTROL OF WORK

2-3.2 Self Performance. DELETE in its entirety and SUBSTITUTE with the following:

1. You must perform, with your own organization, Contract work amounting to at least 50% of the base bid alone or base bid and any additive or deductive alternate(s) that together when added or deducted form the basis of award.
2. The self performance percentage requirement will be waived for contracts when a “B” License is required or allowed.

2-5.3.1 General. To the City Supplement, ADD the following

7. For products for which an AML is available, products listed in the AML shall be used. A submittal review will be conducted for products not identified on an AML on a case-by-case basis when:
 - a) The product type or category is not in the AML.
 - b) The AML does not list at least two available manufacturers of the product.
 - c) The material or manufacturer listed in the AML is no longer available. Documentation to substantiate the product is no longer available or in production is required as part of the submittal.

In the case of conducting a submittal review when required by the Plans or Special Provisions, or when requested by the Engineer, all submittals shall be accompanied by the City’s submittal form.

The Product Submittal Form is available for download at:

<http://www.sandiego.gov/publicworks/edocref/index.shtml>

2-6 WORK TO BE DONE. To the City Supplement, ADD the following:

4. Contractor shall notify the Resident Engineer two weeks before resurfacing operations begins. Resident Engineer will forward the resurfacing schedule to Design Engineer for final paving conflict check before any resurfacing is allowed.

SECTION 3 – CHANGE IN WORK

3-2.2.1 General. To the City Supplement, ADD the following:

Unit Bid prices for painted traffic stripes, thermoplastic traffic stripes, thermoplastic pavement markings, and pavement marker must not be subject to adjustment regardless of quantity used or if none is used.

SECTION 4 - CONTROL OF MATERIALS

4-1.3.6 Preapproved Materials. To the City Supplement, ADD the following:

3. You shall submit in writing a list of all products to be incorporated in the Work that are on the AML.

4-1.6 Trade Names or Equals. ADD the following:

You must submit your list of proposed substitutions for “an equal” (“or equal”) item(s) **no later than 5 Working Days after the determination of the Apparent Low Bidder** and on the City’s Product Submittal Form available at:

<http://www.sandiego.gov/publicworks/edocref/index.shtml>

SECTION 7 - RESPONSIBILITIES OF THE CONTRACTOR

7-3 LIABILITY INSURANCE. DELETE in its entirety and SUBSTITUTE with the following:

The insurance provisions herein must not be construed to limit your indemnity obligations contained in the Contract.

7-3.1 Policies and Procedures.

1. You must procure the insurance described below, at its sole cost and expense, to provide coverage against claims for loss including injuries to persons or damage to property, which may arise out of or in connection with the performance of the Work by you, your agents, representatives, officers, employees or Subcontractors.

2. Insurance coverage for property damage resulting from your operations is on a replacement cost valuation. The market value will not be accepted.
3. You must maintain this insurance for the duration of this contract and at all times thereafter when you are correcting, removing, or replacing Work in accordance with this contract. Your liabilities under the Contract, e.g., your indemnity obligations, is not deemed limited to the insurance coverage required by this contract.
4. Payment for insurance is included in the various items of Work as bid by you, and except as specifically agreed to by the City in writing, you are not entitled to any additional payment. Do not begin any work under this contract until you have provided and the City has approved all required insurance.
5. Policies of insurance must provide that the City is entitled to 30 days (10 days for cancellation due to non-payment of premium) prior written notice of cancellation or non-renewal of the policy. Maintenance of specified insurance coverage is a material element of the Contract. Your failure to maintain or renew coverage or to provide evidence of renewal during the term of the Contract may be treated by the City as a material breach of the Contract.

7-3.2 Types of Insurance.

7-3.2.1 Commercial General Liability Insurance.

1. Commercial General Liability Insurance must be written on the current version of the ISO Occurrence form CG 00 01 07 98 or an equivalent form providing coverage at least as broad.
2. The policy must cover liability arising from premises and operations, XCU (explosions, underground, and collapse), independent contractors, products/completed operations, personal injury and advertising injury, bodily injury, property damage, and liability assumed under an insured's contract (including the tort liability of another assumed in a business contract).
3. There must be no endorsement or modification limiting the scope of coverage for either "insured vs. insured" claims or contractual liability. You must maintain the same or equivalent insurance for at least 10 years following completion of the Work.
4. All costs of defense must be outside the policy limits. Policy coverage must be in liability limits of not less than the following:

<u>General Annual Aggregate Limit</u>	<u>Limits of Liability</u>
Other than Products/Completed Operations	\$2,000,000
Products/Completed Operations Aggregate Limit	\$2,000,000
Personal Injury Limit	\$1,000,000
Each Occurrence	\$1,000,000

7-3.2.2 Commercial Automobile Liability Insurance.

1. You must provide a policy or policies of Commercial Automobile Liability Insurance written on the current version of the ISO form CA 00 01 12 90 or later version or equivalent form providing coverage at least as broad in the amount of \$1,000,000 combined single limit per accident, covering bodily injury and property damage for owned, non-owned, and hired automobiles (“Any Auto”).
2. All costs of defense must be outside the limits of the policy.

7-3.3 Rating Requirements. Except for the State Compensation Insurance Fund, all insurance required by this contract as described herein must be carried only by responsible insurance companies with a rating of, or equivalent to, at least “A-, VI” by A.M. Best Company, that are authorized by the California Insurance Commissioner to do business in the State, and that have been approved by the City.

7-3.3.1 Non-Admitted Carriers. The City will accept insurance provided by non-admitted, “surplus lines” carriers only if the carrier is authorized to do business in the State and is included on the List of Approved Surplus Lines Insurers (LASLI list).

All policies of insurance carried by non-admitted carriers must be subject to all of the requirements for policies of insurance provided by admitted carriers described herein.

7-3.4 Evidence of Insurance. Furnish to the City documents e.g., certificates of insurance and endorsements evidencing the insurance required herein, and furnish renewal documentation prior to expiration of this insurance. Each required document must be signed by the insurer or a person authorized by the insurer to bind coverage on its behalf. We reserve the right to require complete, certified copies of all insurance policies required herein.

7-3.5 Policy Endorsements.

7-3.5.1 Commercial General Liability Insurance.

7-3.5.1.1 Additional Insured.

- a) You must provide at your expense policy endorsement written on the current version of the ISO Occurrence form CG 20 10 11 85 or an equivalent form providing coverage at least as broad.
- b) To the fullest extent allowed by law e.g., California Insurance Code §11580.04, the policy must be endorsed to include the City and its respective elected officials, officers, employees, agents, and representatives as additional insured.
- c) The additional insured coverage for projects for which the Engineer’s Estimate is \$1,000,000 or more must include liability arising out of: (a) Ongoing operations performed by you or on your behalf, (b) your products, (c) your work, e.g., your completed operations performed by you or on your behalf, or (d) premises owned, leased, controlled, or used by you.

- d) The additional insured coverage for projects for which the Engineer's Estimate is less than \$1,000,000 must include liability arising out of: (a) Ongoing operations performed by you or on your behalf, (b) your products, or (c) premises owned, leased, controlled, or used by you.

7-3.5.1.2 Primary and Non-Contributory Coverage. The policy must be endorsed to provide that the coverage with respect to operations, including the completed operations, if appropriate, of the Named Insured is primary to any insurance or self-insurance of the City and its elected officials, officers, employees, agents and representatives. Further, it must provide that any insurance maintained by the City and its elected officials, officers, employees, agents and representatives must be in excess of your insurance and must not contribute to it.

7-3.5.1.3 Project General Aggregate Limit. The policy or policies must be endorsed to provide a Designated Construction Project General Aggregate Limit that will apply only to the Work. Only claims payments which arise from the Work must reduce the Designated Construction Project General Aggregate Limit. The Designated Construction Project General Aggregate Limit must be in addition to the aggregate limit provided for the products-completed operations hazard.

7-3.5.2 Commercial Automobile Liability Insurance.

7-3.5.2.1 Additional Insured. Unless the policy or policies of Commercial Auto Liability Insurance are written on an ISO form CA 00 01 12 90 or a later version of this form or equivalent form providing coverage at least as broad, the policy must be endorsed to include the City and its respective elected officials, officers, employees, agents, and representatives as additional insured, with respect to liability arising out of automobiles owned, leased, hired or borrowed by you or on your behalf. This endorsement is limited to the obligations permitted by California Insurance Code §11580.04.

7-3.6 Deductibles and Self-Insured Retentions. You must pay for all deductibles and self-insured retentions. You must disclose deductibles and self-insured retentions to the City at the time the evidence of insurance is provided.

7-3.7 Reservation of Rights. The City reserves the right, from time to time, to review your insurance coverage, limits, deductibles and self-insured retentions to determine if they are acceptable to the City. The City will reimburse you, without overhead, profit, or any other markup, for the cost of additional premium for any coverage requested by the Engineer but not required by this contract.

7-3.8 Notice of Changes to Insurance. You must notify the City 30 days prior to any material change to the policies of insurance provided under this contract.

7-3.9 Excess Insurance. Policies providing excess coverage must follow the form of the primary policy or policies e.g., all endorsements.

7-4 WORKERS' COMPENSATION INSURANCE. DELETE in its entirety and SUBSTITUTE with the following:

7-4.1 Workers' Compensation Insurance and Employers Liability Insurance.

1. In accordance with the provisions of §3700 of the California Labor Code, you must provide at your expense Workers' Compensation Insurance and Employers Liability Insurance to protect you against all claims under applicable state workers compensation laws. The City, its elected officials, and employees will not be responsible for any claims in law or equity occasioned by your failure to comply with the requirements of this section.
2. Limits for this insurance must be not less than the following:

<u>Workers' Compensation</u>	<u>Statutory Employers Liability</u>
Bodily Injury by Accident	\$1,000,000 each accident
Bodily Injury by Disease	\$1,000,000 each employee
Bodily Injury by Disease	\$1,000,000 policy limit

3. By signing and returning the Contract you certify that you are aware of the provisions of §3700 of the Labor Code which require every employer to be insured against liability for worker's compensation or to undertake self-insurance in accordance with the provisions of that code and you must comply with such provisions before commencing the Work as required by §1861 of the California Labor Code.

7-4.1.1 Waiver of Subrogation. The policy or policies must be endorsed to provide that the insurer will waive all rights of subrogation against the City, and its respective elected officials, officers, employees, agents, and representatives for losses paid under the terms of the policy or policies and which arise from work performed by the Named Insured for the City.

7-8.6 Water Pollution Control. ADD the following:

1. Based on a preliminary assessment by the City, the Contract is subject to WPCP.

7-10.5.3 Steel Plate Covers. Table 7-10.5.3(A), REVISE the plate thickness for 5'-3" trench width to read 1 3/4".

7-15 INDEMNIFICATION AND HOLD HARMLESS AGREEMENT. To the City Supplement, fourth paragraph, last sentence, DELETE in its entirety and SUBSTITUTE with the following:

Your duty to indemnify and hold harmless does not include any claims or liability arising from the established active or sole negligence, or willful misconduct of the City, its officers, or employees.

7-20 ELECTRONIC COMMUNICATION. ADD the following:

Virtual Project Manager will be used on this contract.

SECTION 9 - MEASUREMENT AND PAYMENT

9-3.2.5 Withholding of Payment. To the City Supplement, item i), DELETE in its entirety and SUBSTITUTE with the following:

- i) Your failure to comply with 7-2.3, "PAYROLL RECORDS" and 2-16, "CONTRACTOR REGISTRATION AND ELECTRONIC REPORTING SYSTEM."

ADD:

9-3.7 Compensation Adjustments for Price Index Fluctuations. This Contract is subject to the provisions of The WHITEBOOK for Compensation Adjustments for Price Index Fluctuations for the paving asphalt.

SECTION 203 – BITUMINOUS MATERIALS

203-15 RUBBER POLYMER MODIFIED SLURRY (RPMS). To the City Supplement, CORRECT section numbering as follows:

OLD SECTION NUMBER	TITLE	NEW SECTION NUMBER
203-15	RUBBER POLYMER MODIFIED SLURRY (RPMS)	203-16
203-15.1	General	203-16.1
203-15.2	Materials	203-16.2
203-15.3	Composition and Grading	203-16.3
203-15.4	Mix Design	203-16.4

ADD the following:

RPMS shall be used on this contract.

SECTION 302 – ROADWAY SURFACING

302-1.12 Payment. To the City Supplement, ADD following:

No additional payment shall be made for milling, grinding or saw-cutting PCC or other materials.

302-3 PREPARATORY REPAIR WORK. To the City Supplement, DELETE in its entirety and SUBSTITUTE with the following:

PREPARATORY REPAIR WORK.

1. Prior to roadway resurfacing or the application of slurry, the Contractor shall complete all necessary preparation and repair work to the road segment e.g., tree trimming, weed spray, weed abatement, crack sealing, asphalt repair, hump removal, miscellaneous asphalt patching, removal of raised pavement markers, removal of pavement markings, etc. and as specified in the Special Provisions.
2. Preparatory work shall include, but not be limited to, tree trimming, weed spray, weed abatement, crack sealing, asphalt repair i.e., mill and pave, hump removal, miscellaneous asphalt patching, removal of raised pavement markers, removal of pavement markings, etc.
3. The Contractor shall repair areas of distressed asphalt concrete pavement by milling or removing damaged areas of pavement to a minimum depth of 2” for Residential streets, and a minimum depth of 3” for all others to expose firm and unyielding pavement. The Contractor shall prepare subgrade as needed and install a minimum of 2” for residential streets, and a minimum of 3” for all others, of compacted asphalt concrete pavement over compacted native material as directed by the Engineer.
4. If, in order to achieve the minimum specified depth, the base material is exposed, the material shall be compacted to 95% relative compaction to a depth 10” below the finished grade (dig out). Compaction tests shall be made to ensure compliance with the specifications. The Engineer will determine when and where the test will occur. The City will pay for the soils testing required by the Engineer, which meets the required compaction. The Contractor shall reimburse the City for the cost of retesting failing compaction tests. If additional base material is required, the Contractor shall use Class 2 Aggregate Base in accordance with 200-2.2, “Crushed Aggregate Base.”
5. Recycled base material shall conform to Crushed Miscellaneous Base Material in accordance with 200-2.4, “Crushed Miscellaneous Aggregate Base.”
6. Prior to replacing asphalt, the area shall be cleaned by removing all loose and damaged material, moisture, dirt, and other foreign matter and shall be tack coated in accordance with 302-5.4 “Tack Coat.”
7. The Contractor shall install new asphalt within the repair area or for patches in accordance with 302-5, “ASPHALT CONCRETE PAVEMENT.” Asphalt concrete shall be C2-PG 64-10 in compliance with 400-4, “ASPHALT CONCRETE.”
8. No preparatory asphalt work shall be done when the atmospheric temperature is below 50 °F or during unsuitable weather.
9. Following the asphalt placement, the Contractor shall roll the entire area of new asphalt in both directions at least twice. The finished patch shall be level and smooth in compliance with 302-5.6.2 “Density and Smoothness.” After placement and compaction of the asphalt patch, the Contractor shall seal all finished edges with a 4” wide continuous band of SS-1H.

10. The minimum dimension for each individual repair shall be 4' x 4' and shall be subject to the following conditions:
 - a) If the base material is exposed to achieve the required minimum removal thickness, the base material shall be prepared conforming to 301-1, "SUBGRADE PREPARATION."
 - b) When additional base material is required, then the contractor shall use Class 2 Aggregate Base in accordance with 200-2.2, "Crushed Aggregate Base." Recycled base material shall conform to Crushed Miscellaneous Base Material in accordance with 200-2.4, "Crushed Miscellaneous Base."
 - c) The Contractor may use grinding as a method for removal of deteriorated pavement when the areas indicated for removal are large enough (a minimum of the machine drum width) and when approved by the Engineer.
 - d) For both scheduled and unscheduled base repairs, failed areas may be removed by milling or by excavation provided that the edges are cut cleanly with a saw. The areas shall be cleaned and tack coated in accordance with 302-5.4, "Tack Coat" before replacing the asphalt. The areas for scheduled repairs have been marked on the street.
11. Base Repairs:
 - a) Base Repairs with RAC. Areas where failed paving is removed either by cold milling or by excavation shall be restored to existing pavement grade with ¾" RAC at 8" depth unless otherwise directed by the Engineer. The asphalt concrete shall be B3-PG 64-10 as specified in Section 400-4, "Asphalt Concrete". Base repairs shall not exceed 20% RAP in content.
 - b) If paving operations cause damage outside of the contractor's control and require additional base repair, the areas shall be removed either by cold milling or by excavation and shall be restored to existing pavement grade with ¾" RAC at 8" depth unless otherwise directed by the Engineer. The asphalt concrete shall be B3-PG 64-10 as specified in Section 400- 4, "Asphalt Concrete".
12. When approved by the Engineer, quantities identified in the Contract may need to be increased during construction.

302-3.1

Asphalt Patching.

1. Asphalt patching shall consist of patching potholes, gutter-line erosion, and other low spots in the pavement that are deeper than ½" per 302-5.6.2, "Density and Smoothness." These areas are generally smaller and more isolated than those areas in need of mill and pave.
2. The areas requiring patching have been identified in the Contract Documents, marked on the streets, or as directed by the Engineer. The Contractor shall identify any new areas that may require patching prior to slurry work to ensure the smoothness and quality of the finished product.
3. The Contractor shall identify and repair any areas that may require patching, prior to the placement of slurry seal for smooth finished product.

4. Asphalt overlay shall not be applied over deteriorated pavement. Preparatory asphalt work shall be completed and approved by the Engineer before proceeding with asphalt overlay.
5. The Contractor shall remove distressed asphalt pavement either by saw cutting or milling, to expose firm and unyielding pavement; prepare subgrade (as needed); and install compacted asphalt concrete pavement over compacted native material as directed by the Engineer.
6. Prior to replacing asphalt, the area shall be cleaned and tack coated per 302-5.4, "Tack Coat".
7. Following the asphalt placement, the Contractor shall roll the entire patch in both directions covering the patch at least twice.
8. After placement and compaction of the asphalt patch, the Contractor shall seal all finished edges with a 4" wide continuous band of SS-1H.
9. Base repairs shall not exceed 20% RAP in content.

302-3.2

Payment.

1. Payment for replacement of existing pavement when required shall be included in the unit bid price for Asphalt Pavement repair for the total area replaced and no additional payment shall be made regardless of the number of replacements completed. No payment shall be made for areas of over excavation or outside trench areas in utility works unless previously approved by the Engineer. No payment for pavement replacement will be made when the damage is due to the Contractor's failure to protect existing improvements. The Contractor shall reimburse the City for the cost of retesting all failing compaction tests.
2. The areas and quantities shown on the road segments and in appendices are given only for the Contractor's aid in planning the Work and preparing Bids. The Engineer will designate the limits to be removed and these designated areas shall be considered to take precedent over the area shown in an Appendix to the Contract Documents. The quantities shown in the appendices are based on a street assessment survey and may vary.
3. At the end of each day, the Contractor shall submit to the Engineer an itemized list of the asphalt pavement repair work completed. The list shall include the location of the work and the exact square footage of the repair.
4. Preparatory repair work and tack coating will be paid at the Contract unit price per ton for Asphalt Pavement Repair. No payment shall be made for areas of over excavation unless previously approved by the Engineer.
5. Milling shall be included in the Bid item for Asphalt Pavement Repair unless separate Bid item has been provided.

6. Payment for miscellaneous asphalt patching shall be included in the Contract unit price for slurry and no additional payment shall be made therefore.

302-5.1.1 Damaged AC Pavement Replacement. To the City Supplement, DELETE in its entirety.

302-5.1.2 Measurement and Payment. To the City Supplement, DELETE in its entirety.

302-5.2.1 Measurement and Payment. To the City Supplement, item c), ADD the following:
Imported Subgrade material shall be paid per bid item "Imported Backfill".

SECTION 701 – WATER POLLUTION CONTROL

701-11 POST-CONSTRUCTION REQUIREMENTS. To the City Supplement, second paragraph, ADD the following:

Comply with the following post-construction requirements:

Additional sweeping shall be done after the construction, including gutter and sidewalk area.

SECTION 705 – WATER DISCHARGES

705-2.6.1 General. Paragraph (3), CORRECT reference to Section 803 to read "Section 703."

705-2.6.3 Community Health and Safety Plan. To the City Supplement, DELETE in its entirety and SUBSTITUTE with the following:

705-2.6.3 Community Health and Safety Plan. See 703-2, "Community Health and Safety Plan."

END OF SUPPLEMENTARY SPECIAL PROVISIONS (SSP)

SUPPLEMENTARY SPECIAL PROVISIONS

APPENDICES

APPENDIX A
FIRE HYDRANT METER PROGRAM

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 1 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

1. **PURPOSE**

1.1 To establish a Departmental policy and procedure for issuance, proper usage and charges for fire hydrant meters.

2. **AUTHORITY**

2.1 All authorities and references shall be current versions and revisions.

2.2 San Diego Municipal Code (NC) Chapter VI, Article 7, Sections 67.14 and 67.15

2.3 Code of Federal Regulations, Safe Drinking Water Act of 1986

2.4 California Code of Regulations, Titles 17 and 22

2.5 California State Penal Code, Section 498B.0

2.6 State of California Water Code, Section 110, 500-6, and 520-23

2.7 Water Department Director

Reference

2.8 State of California Guidance Manual for Cross Connection Programs

2.9 American Water Works Association Manual M-14, Recommended Practice for Backflow Prevention

2.10 American Water Works Association Standards for Water Meters

2.11 U.S.C. Foundation for Cross Connection Control and Hydraulic Research Manual

3. **DEFINITIONS**

3.1 **Fire Hydrant Meter:** A portable water meter which is connected to a fire hydrant for the purpose of temporary use. (These meters are sometimes referred to as Construction Meters.)

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 2 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

- 3.2 **Temporary Water Use:** Water provided to the customer for no longer than twelve (12) months.
- 3.3 **Backflow Preventor:** A Reduced Pressure Principal Assembly connected to the outlet side of a Fire Hydrant Meter.

4. **POLICY**

- 4.1 The Water Department shall collect a deposit from every customer requiring a fire hydrant meter and appurtenances prior to providing the meter and appurtenances (see Section 7.1 regarding the Fees and Deposit Schedule). The deposit is refundable upon the termination of use and return of equipment and appurtenances in good working condition.
- 4.2 Fire hydrant meters will have a 2 ½" swivel connection between the meter and fire hydrant. The meter shall not be connected to the 4" port on the hydrant. All Fire Hydrant Meters issued shall have a Reduced Pressure Principle Assembly (RP) as part of the installation. Spanner wrenches are the only tool allowed to turn on water at the fire hydrant.
- 4.3 The use of private hydrant meters on City hydrants is prohibited, with exceptions as noted below. All private fire hydrant meters are to be phased out of the City of San Diego. All customers who wish to continue to use their own fire hydrant meters must adhere to the following conditions:
 - a. Meters shall meet all City specifications and American Water Works Association (AWWA) standards.
 - b. Customers currently using private fire hydrant meters in the City of San Diego water system will be allowed to continue using the meter under the following conditions:
 - 1. The customer must submit a current certificate of accuracy and calibration results for private meters and private backflows annually to the City of San Diego, Water Department, Meter Shop.

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 3 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

2. The meter must be properly identifiable with a clearly labeled serial number on the body of the fire hydrant meter. The serial number shall be plainly stamped on the register lid and the main casing. Serial numbers shall be visible from the top of the meter casing and the numbers shall be stamped on the top of the inlet casing flange.
3. All meters shall be locked to the fire hydrant by the Water Department, Meter Section (see Section 4.7).
4. All meters shall be read by the Water Department, Meter Section (see Section 4.7).
5. All meters shall be relocated by the Water Department, Meter Section (see Section 4.7).
6. These meters shall be tested on the anniversary of the original test date and proof of testing will be submitted to the Water Department, Meter Shop, on a yearly basis. If not tested, the meter will not be allowed for use in the City of San Diego.
7. All private fire hydrant meters shall have backflow devices attached when installed.
8. The customer must maintain and repair their own private meters and private backflows.
9. The customer must provide current test and calibration results to the Water Department, Meter Shop after any repairs.
10. When private meters are damaged beyond repair, these private meters will be replaced by City owned fire hydrant meters.

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 4 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

11. When a private meter malfunctions, the customer will be notified and the meter will be removed by the City and returned to the customer for repairs. Testing and calibration results shall be given to the City prior to any re-installation.
 12. The register shall be hermetically sealed straight reading and shall be readable from the inlet side. Registration shall be in hundred cubic feet.
 13. The outlet shall have a 2 ½ "National Standards Tested (NST) fire hydrant male coupling.
 14. Private fire hydrant meters shall not be transferable from one contracting company to another (i.e. if a company goes out of business or is bought out by another company).
- 4.4 All fire hydrant meters and appurtenances shall be installed, relocated and removed by the City of San Diego, Water Department. All City owned fire hydrant meters and appurtenances shall be maintained by the City of San Diego, Water Department, Meter Services.
- 4.5 If any fire hydrant meter is used in violation of this Department Instruction, the violation will be reported to the Code Compliance Section for investigation and appropriate action. Any customer using a fire hydrant meter in violation of the requirements set forth above is subject to fines or penalties pursuant to the Municipal Code, Section 67.15 and Section 67.37.
- 4.6 **Conditions and Processes for Issuance of a Fire Hydrant Meter**
- Process for Issuance
- a. Fire hydrant meters shall only be used for the following purposes:
 1. Temporary irrigation purposes not to exceed one year.

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 5 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

2. Construction and maintenance related activities (see Tab 2).
 - b. No customer inside or outside the boundaries of the City of San Diego Water Department shall resell any portion of the water delivered through a fire hydrant by the City of San Diego Water Department.
 - c. The City of San Diego allows for the issuance of a temporary fire hydrant meter for a period not to exceed 12 months (365 days). An extension can only be granted in writing from the Water Department Director for up to 90 additional days. A written request for an extension by the consumer must be submitted at least 30 days prior to the 12 month period ending. No extension shall be granted to any customer with a delinquent account with the Water Department. No further extensions shall be granted.
 - d. Any customer requesting the issuance of a fire hydrant meter shall file an application with the Meter Section. The customer must complete a "Fire Hydrant Meter Application" (Tab 1) which includes the name of the company, the party responsible for payment, Social Security number and/or California ID, requested location of the meter (a detailed map signifying an exact location), local contact person, local phone number, a contractor's license (or a business license), description of specific water use, duration of use at the site and full name and address of the person responsible for payment.
 - e. At the time of the application the customer will pay their fees according to the schedule set forth in the Rate Book of Fees and Charges, located in the City Clerk's Office. All fees must be paid by check, money order or cashiers check, made payable to the City Treasurer. Cash will not be accepted.
 - f. No fire hydrant meters shall be furnished or relocated for any customer with a delinquent account with the Water Department.
 - g. After the fees have been paid and an account has been created, the

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 6 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

meter shall be installed within 48 hours (by the second business day). For an additional fee, at overtime rates, meters can be installed within 24 hours (within one business day).

4.7 Relocation of Existing Fire Hydrant Meters

- a. The customer shall call the Fire Hydrant Meter Hotline (herein referred to as "Hotline"), a minimum of 24 hours in advance, to request the relocation of a meter. A fee will be charged to the existing account, which must be current before a work order is generated for the meter's relocation.
- b. The customer will supply in writing the address where the meter is to be relocated (map page, cross street, etc). The customer must update the original Fire Hydrant Meter Application with any changes as it applies to the new location.
- c. Fire hydrant meters shall be read on a monthly basis. While fire hydrant meters and backflow devices are in service, commodity, base fee and damage charges, if applicable, will be billed to the customer on a monthly basis. If the account becomes delinquent, the meter will be removed.

4.8 Disconnection of Fire Hydrant Meter

- a. After ten (10) months a "Notice of Discontinuation of Service" (Tab 3) will be issued to the site and the address of record to notify the customer of the date of discontinuance of service. An extension can only be granted in writing from the Water Department Director for up to 90 additional days (as stated in Section 4.6C) and a copy of the extension shall be forwarded to the Meter Shop Supervisor. If an extension has not been approved, the meter will be removed after twelve (12) months of use.
- b. Upon completion of the project the customer will notify the Meter Services office via the Hotline to request the removal of the fire hydrant meter and appurtenances. A work order will be generated

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 7 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

for removal of the meter.

- c. Meter Section staff will remove the meter and backflow prevention assembly and return it to the Meter Shop. Once returned to the Meter Shop the meter and backflow will be tested for accuracy and functionality.
- d. Meter Section Staff will contact and notify Customer Services of the final read and any charges resulting from damages to the meter and backflow or its appurtenance. These charges will be added on the customer's final bill and will be sent to the address of record. Any customer who has an outstanding balance will not receive additional meters.
- e. Outstanding balances due may be deducted from deposits and any balances refunded to the customer. Any outstanding balances will be turned over to the City Treasurer for collection. Outstanding balances may also be transferred to any other existing accounts.

5. EXCEPTIONS

- 5.1 Any request for exceptions to this policy shall be presented, in writing, to the Customer Support Deputy Director, or his/her designee for consideration.

6. MOBILE METER

- 6.1 Mobile meters will be allowed on a case by case basis. All mobile meters will be protected by an approved backflow assembly and the minimum requirement will be a Reduced Pressure Principal Assembly. The two types of Mobile Meters are vehicle mounted and floating meters. Each style of meters has separate guidelines that shall be followed for the customer to retain service and are described below:
 - a) **Vehicle Mounted Meters:** Customer applies for and receives a City owned Fire Hydrant Meter from the Meter Shop. The customer mounts the meter on the vehicle and brings it to the Meter Shop for

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 8 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

inspection. After installation is approved by the Meter Shop the vehicle and meter shall be brought to the Meter Shop on a monthly basis for meter reading and on a quarterly basis for testing of the backflow assembly. Meters mounted at the owner's expense shall have the one year contract expiration waived and shall have meter or backflow changed if either fails.

b) **Floating Meters:** Floating Meters are meters that are not mounted to a vehicle. **(Note: All floating meters shall have an approved backflow assembly attached.)** The customer shall submit an application and a letter explaining the need for a floating meter to the Meter Shop. The Fire Hydrant Meter Administrator, after a thorough review of the needs of the customer, (i.e. number of jobsites per day, City contract work, lack of mounting area on work vehicle, etc.), may issue a floating meter. At the time of issue, it will be necessary for the customer to complete and sign the "Floating Fire Hydrant Meter Agreement" which states the following:

- 1) The meter will be brought to the Meter Shop at 2797 Caminito Chollas, San Diego on the third week of each month for the monthly read by Meter Shop personnel.
- 2) Every other month the meter will be read and the backflow will be tested. This date will be determined by the start date of the agreement.

If any of the conditions stated above are not met the Meter Shop has the right to cancel the contract for floating meter use and close the account associated with the meter. The Meter Shop will also exercise the right to refuse the issuance of another floating meter to the company in question.

Any Fire Hydrant Meter using reclaimed water shall not be allowed use again with any potable water supply. The customer shall incur the cost of replacing the meter and backflow device in this instance.

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 9 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

7. **FEE AND DEPOSIT SCHEDULES**

- 7.1 **Fees and Deposit Schedules:** The fees and deposits, as listed in the Rate Book of Fees and Charges, on file with the Office of the City Clerk, are based on actual reimbursement of costs of services performed, equipment and materials. These deposits and fees will be amended, as needed, based on actual costs. Deposits, will be refunded at the end of the use of the fire hydrant meter, upon return of equipment in good working condition and all outstanding balances on account are paid. Deposits can also be used to cover outstanding balances.

All fees for equipment, installation, testing, relocation and other costs related to this program are subject to change without prior notification. The Mayor and Council will be notified of any future changes.

8. **UNAUTHORIZED USE OF WATER FROM A HYDRANT**

- 8.1 Use of water from any fire hydrant without a properly issued and installed fire hydrant meter is theft of City property. Customers who use water for unauthorized purposes or without a City of San Diego issued meter will be prosecuted.
- 8.2 If any unauthorized connection, disconnection or relocation of a fire hydrant meter, or other connection device is made by anyone other than authorized Water Department personnel, the person making the connection will be prosecuted for a violation of San Diego Municipal Code, Section 67.15. In the case of a second offense, the customer's fire hydrant meter shall be confiscated and/or the deposit will be forfeited.
- 8.3 Unauthorized water use shall be billed to the responsible party. Water use charges shall be based on meter readings, or estimates when meter readings are not available.
- 8.4 In case of unauthorized water use, the customer shall be billed for all applicable charges as if proper authorization for the water use had been obtained, including but not limited to bi-monthly service charges, installation charges and removal charges.

CITY OF SAN DIEGO CALIFORNIA DEPARTMENT INSTRUCTIONS	NUMBER DI 55.27	DEPARTMENT Water Department
SUBJECT FIRE HYDRANT METER PROGRAM (FORMERLY: CONSTRUCTION METER PROGRAM)	PAGE 10 OF 10	EFFECTIVE DATE October 15, 2002
	SUPERSEDES DI 55.27	DATED April 21, 2000

- 8.5 If damage occurs to Water Department property (i.e. fire hydrant meter, backflow, various appurtenances), the cost of repairs or replacements will be charged to the customer of record (applicant).

**Larry Gardner
Water Department Director**

- Tabs: 1. Fire Hydrant Meter Application
2. Construction & Maintenance Related Activities With No Return To Sewer
3. Notice of Discontinuation of Service

APPENDIX

Administering Division: Customer Support Division

Subject Index: Construction Meters
Fire Hydrant
Fire Hydrant Meter Program
Meters, Floating or Vehicle Mounted
Mobile Meter
Program, Fire Hydrant Meter

Distribution: DI Manual Holders



Application for Fire Hydrant Meter (EXHIBIT A)

(For Office Use Only)

NS REQ	FAC#
DATE	BY

METER SHOP (619) 527-7449

Meter Information

Application Date	Requested Install Date:
------------------	-------------------------

Fire Hydrant Location: (Attach Detailed Map//Thomas Bros. Map Location or Construction drawing.) Zip:	T.B.	G.B. (CITY USE)
Specific Use of Water:		
Any Return to Sewer or Storm Drain, If so, explain:		
Estimated Duration of Meter Use:	<input type="checkbox"/>	<input type="checkbox"/> Check Box if Reclaimed Water

Company Information

Company Name:			
Mailing Address:			
City:	State:	Zip:	Phone: ()
*Business license#		*Contractor license#	
A Copy of the Contractor's license OR Business License is required at the time of meter issuance.			
Name and Title of Billing Agent: (PERSON IN ACCOUNTS PAYABLE)			Phone: ()
Site Contact Name and Title:			Phone: ()
Responsible Party Name:			Title:
Cal ID#			Phone: ()
Signature:		Date:	
Guarantees Payment of all Charges Resulting from the use of this Meter. Insures that employees of this Organization understand the proper use of Fire Hydrant Meter			

Fire Hydrant Meter Removal Request	Requested Removal Date:
Provide Current Meter Location if Different from Above:	
Signature:	Title: Date:
Phone: ()	Pager: ()

City Meter	Private Meter
Contract Acct #:	Deposit Amount: \$ 936.00 Fees Amount: \$ 62.00
Meter Serial #	Meter Size: 05 Meter Make and Style: 6-7
Backflow #	Backflow Size: Backflow Make and Style:
Name: UUP Sherman Heights Street Resurfacing Appendix A - Fire Hydrant Meter Program	Signature: Date: 59 Page

WATER USES WITHOUT ANTICIPATED CHARGES FOR RETURN TO SEWER

Auto Detailing
Backfilling
Combination Cleaners (Vactors)
Compaction
Concrete Cutters
Construction Trailers
Cross Connection Testing
Dust Control
Flushing Water Mains
Hydro Blasting
Hydro Seeing
Irrigation (for establishing irrigation only; not continuing irrigation)
Mixing Concrete
Mobile Car Washing
Special Events
Street Sweeping
Water Tanks
Water Trucks
Window Washing

Note:

1. If there is any return to sewer or storm drain, then sewer and/or storm drain fees will be charges.

Date

Name of Responsible Party
Company Name and Address
Account Number: _____

Subject: Discontinuation of Fire Hydrant Meter Service

Dear Water Department Customer:

The authorization for use of Fire Hydrant Meter # _____, located at *(Meter Location Address)* ends in 60 days and will be removed on or after *(Date Authorization Expires)*. Extension requests for an additional 90 days must be submitted in writing for consideration 30 days prior to the discontinuation date. If you require an extension, please contact the Water Department, or mail your request for an extension to:

City of San Diego
Water Department
Attention: Meter Services
2797 Caminito Chollas
San Diego, CA 92105-5097

Should you have any questions regarding this matter, please call the Fire Hydrant Hotline at (619) _____ - _____.

Sincerely,

Water Department

APPENDIX B

MATERIALS TYPICALLY ACCEPTED BY CERTIFICATE OF COMPLIANCE

Materials Typically Accepted by Certificate of Compliance

1. Soil amendment
2. Fiber mulch
3. PVC or PE pipe up to 16 inch diameter
4. Stabilizing emulsion
5. Lime
6. Preformed elastomeric joint seal
7. Plain and fabric reinforced elastomeric bearing pads
8. Steel reinforced elastomeric bearing pads
9. Waterstops (Special Condition)
10. Epoxy coated bar reinforcement
11. Plain and reinforcing steel
12. Structural steel
13. Structural timber and lumber
14. Treated timber and lumber
15. Lumber and timber
16. Aluminum pipe and aluminum pipe arch
17. Corrugated steel pipe and corrugated steel pipe arch
18. Structural metal plate pipe arches and pipe arches
19. Perforated steel pipe
20. Aluminum underdrain pipe
21. Aluminum or steel entrance tapers, pipe downdrains, reducers, coupling bands and slip joints
22. Metal target plates
23. Paint (traffic striping)
24. Conductors
25. Painting of electrical equipment
26. Electrical components
27. Engineering fabric
28. Portland Cement
29. PCC admixtures
30. Minor concrete, asphalt
31. Asphalt (oil)
32. Liquid asphalt emulsion
33. Epoxy

APPENDIX C
SAMPLE CITY INVOICE

City of San Diego, Field Engineering Div., 9485 Aero Drive, SD CA 92123						Contractor's Name:					
Project Name:						Contractor's Address:					
SAP No. (WBS/IO/CC):											
City Purchase Order No. :						Contractor's Phone #:			Invoice No.		
Resident Engineer (RE):						Contractor's Fax #:			Invoice Date:		
RE Phone#:			RE Fax#:			Contact Name:			Billing Period:		
Item #	Item Description	Contract Authorization				Previous Estimate		This Estimate		Totals to Date	
		Unit	Qty	Price	Extension	%/QTY	Amount	% / QTY	Amount	% / QTY	Amount
1	2 Parallel 4" PVC C900	LF	1,380	\$34.00	\$46,920.00						
2	48" Primary Steel Casing	LF	500	\$1,000.00	\$500,000.00						
3	2 Parallel 12" Secondary Steel	LF	1,120	\$53.00	\$59,360.00						
4	Construction and Rehab of PS 49	LS	1	\$150,000.00	\$150,000.00						
5	Demo	LS	1	\$14,000.00	\$14,000.00						
6	Install 6' High Chain Link Fence	LS	1	\$5,600.00	\$5,600.00						
7	General Site Restoration	LS	1	\$3,700.00	\$3,700.00						
8	10" Gravity Sewer	LF	10	\$292.00	\$2,920.00						
9	4" Blow Off Valves	EA	2	\$9,800.00	\$19,600.00						
10	Bonds	LS	1	\$16,000.00	\$16,000.00						
11	Field Orders	AL	1	80,000	\$80,000.00						
11.1	Field Order 1	LS	5,500	\$1.00	\$5,500.00						
11.2	Field Order 2	LS	7,500	\$1.00	\$7,500.00						
11.3	Field Order 3	LS	10,000	\$1.00	\$10,000.00						
11.4	Field Order 4	LS	6,500	\$1.00	\$6,500.00						
12	Certified Payroll	LS	1	\$1,400.00	\$1,400.00						
CHANGE ORDERS											
Change Order 1			4,890								
Items 1-4					\$11,250.00						
Item 5-Deduct Bid Item 3		LF	120	-\$53.00	(\$6,360.00)						
Change Order 2			160,480								
Items 1-3					\$95,000.00						
Item 4 Deduct Bid Item 1		LF	380	-\$340.00	(\$12,920.00)						
Item 5-Increase bid Item 9		LF	8	\$9,800.00	\$78,400.00						
Change Order 3 (Close Out)			-121,500								
Item 1 Deduct Bid Item 3			53	-500.00	(\$26,500.00)						
Item 2 Deduct Bid Item 4		LS	-1	45,000.00	(\$45,000.00)						
Items 3-9			1	-50,500.00	(\$50,500.00)						
SUMMARY							Total This	\$ -	Total Billed		\$0.00
A. Original Contract Amount						Retention and/or Escrow Payment Schedule					
B. Approved Change Order 1 Thru 3						Total Retention Required as of this billing					
C. Total Authorized Amount (A+B)						Previous Retention Withheld in PO or in Escrow					
D. Total Billed to Date						Add'l Amt to Withhold in PO/Transfer in Escrow:					
E. Less Total Retention (5% of D)						Amt to Release to Contractor from PO/Escrow:					
F. Less Total Previous Payments											
G. Payment Due Less Retention						Contractor Signature and Date:					
H. Remaining Authorized Amount											



APPENDIX D
RESURFACING LOCATION MAPS

RESIDENTIAL PROJECT 8-G Sherman Heights 2



SENIOR ENGINEER LABIB QASEM 619-533-6670
 PROJECT MANAGER DAYUE ZHANG 619-533-7409
 CONSTRUCTION PROJECT INFORMATION LINE 619-533-4207
 STUDENT ENGINEER JAIME RAMOS 619-533-4662
 P.T.E.A. ARIA NOORAZAR 619-533-5314

RIGHT- OF- WAY DIVISION



Legend

Street Maintenance

-  Full Width Overlay
-  Slurry Seal
-  Residential Project Block 8G



COMMUNITY NAME:
 SHERMAN HEIGHTS
 UUP Sherman Heights Street Resurfacing
 Date: April 02, 2014

COUNCIL DISTRICT: 8

SAP ID: B-00829.3

THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESS OR IMPLIED, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OR MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Note: This product may contain information reproduced with permission granted by RAND MCNALLY & COMPANY to SanGIS. This map is copyrighted by RAND MCNALLY & COMPANY. It is unlawful to copy or reproduce all or any part thereof, whether for personal use or resale, without the prior, written permission of RAND MCNALLY & COMPANY.

RESIDENTIAL PROJECT BLOCK 8-F (Sherman Heights 1)

SENIOR ENGINEER
LABIB QASEM
619-533-6670

STUDENT ENGINEER
JAIME RAMOS
619-533-4662



PROJECT MANAGER
DAYUE ZHANG
619-533-7409

P.T.E.A.
ARIA NOORAZAR
619-533-6670

CONSTRUCTION PROJECT
INFORMATION LINE
619-533-4207



RIGHT- OF- WAY DIVISION



Legend

- Edge Overlay
- Full Width Overlay
- Slurry Seal
- Residential Project Block 8F




THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESS OR IMPLIED, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OR MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Note: This product may contain information reproduced with permission granted by RAND MCNALLY & COMPANY to SanGIS. This map is copyrighted by RAND MCNALLY & COMPANY. It is unlawful to copy or reproduce all or any part thereof, whether for personal use or resale, without the prior, written permission of RAND MCNALLY & COMPANY.




ISLAND AVENUE PHASE I (16th St to 24 St)



SENIOR ENGINEER LABIB QASEM 619-533-6670	PROJECT MANAGER DAYUE ZHANG 619-533-7409	CONSTRUCTION PROJECT INFORMATION LINE 619-533-4207
STUDENT ENGINEER JAIME RAMOS 619-533-4662	PROJECT ENGINEER ARIA NOORAZAR 619-533-5314	



RIGHT- OF- WAY DIVISION



Legend

-  Slurry Seal
-  Island Avenue (Phase I)



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESS OR IMPLIED, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OR MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Note: This product may contain information from the SANDAG Regional Information System which cannot be reproduced without the written permission of SANDAG. This product may contain information reproduced with permission granted by RAND McNALLY & COMPANY to SANDAG. This map is copyrighted by RAND McNALLY & COMPANY. It is unlawful to copy or reproduce all or any part thereof, whether for personal use or resale, without the prior, written permission of RAND McNALLY & COMPANY.



ISLAND AVENUE PHASE II (26th St to 30th St)



SENIOR ENGINEER LABIB GASEM 619-533-6670
 PROJECT MANAGER DAYUE ZHANG 619-533-7409
 CONSTRUCTION PROJECT INFORMATION LINE 619-533-4207

STUDENT ENGINEER P.T.E.A. JAIME RAMOS 619-533-4662
 ARIA NOORAZAR 619-533-5314

RIGHT- OF- WAY DIVISION



Legend

Street Maintenance

-  Full Width Overlay
-  Slurry Seal
-  Island Avenue (Phase II)



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESS OR IMPLIED, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OR MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Note: This product may contain information reproduced with permission granted by RAND McNALLY & COMPANY to SanGIS. This map is copyrighted by RAND McNALLY & COMPANY. It is unlawful to copy or reproduce all or any part thereof, whether for personal use or resale, without the prior, written permission of RAND McNALLY & COMPANY.

K STREET PHASE I (19th St to 24th St)



SENIOR ENGINEER
LABIB QASEM
619-533-6670



PROJECT MANAGER
DAYUE ZHANG
619-533-7409

CONSTRUCTION PROJECT
INFORMATION LINE
619-533-4207


STUDENT ENGINEER
JAIME RAMOS
619-533-4662

P.T.E.A.
ARIA NOORAZAR
619-533-5314

RIGHT- OF- WAY DIVISION



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OR MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Note: This product may contain information reproduced with permission granted by RAND McNALLY & COMPANY to SanGIS. This map is copyrighted by RAND McNALLY & COMPANY. It is unlawful to copy or reproduce all or any part thereof, whether for personal use or resale, without the prior, written permission of RAND McNALLY & COMPANY.



K STREET PHASE II (26th St to 31st St)



SENIOR ENGINEER
LABIB QASEM
619-533-6670

PROJECT MANAGER
DAYUE ZHANG
619-533-7409

CONSTRUCTION PROJECT
INFORMATION LINE
619-533-4207

STUDENT ENGINEER P.T.E.A.
JAIME RAMOS
619-533-4662

ARIA NOORAZAR
619-533-5314

RIGHT- OF- WAY DIVISION



Legend

-  Slurry Seal
-  K Street (Phase II)



No Scale

COMMUNITY NAME:
SHERMAN HEIGHTS
UUP Sherman Heights Street Resurfacing

COUNCIL DISTRICT: 8

SAP ID: B-00851.3




THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESS OR IMPLIED, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OR MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Note: This product may contain information from the SANDAG Regional Information System which cannot be reproduced without the written permission of SANDAG. This product may contain information reproduced with permission granted by RAND MCNALLY & COMPANY® to SanGIS. This map is copyrighted by RAND MCNALLY & COMPANY®. It is unlawful to copy or reproduce all or any part thereof, whether for personal use or resale, without the prior, written permission of RAND MCNALLY & COMPANY .

APPENDIX E
RESURFACING LOCATION LIST

Project Area	Street Name	Cross Street 1	Cross Street 2	Treatment Type
8F	26th Street	Market St	Island Ave	Fullwidth Overlay
8F	26th Street	Market St	26th Street	Slurry Seal
8F	26th Street	Island Ave	J Street	Slurry Seal
8F	26th Street	J Street	K Street	Slurry Seal
8F	26th Street	K Street	L Street	Slurry Seal
8F	26th Street	L Street	Imperial Ave	Edge Overlay
8F	26th Street	Imperial Ave	Commercial Ave	Fullwidth Overlay
8F	27th Street	Imperial Ave	Commercial Street	Fullwidth Overlay
8F	25th Street	Island Ave	J Street	Slurry Seal
8F	25th Street	J Street	K Street	Slurry Seal
8F	25th Street	K Street	L Street	Slurry Seal
8F	25th Street	L Street	Imperial Ave	Slurry Seal
8F	25th Street	Imperial Ave	Commercial Street	Slurry Seal
8F	22nd Street	Imperial Ave	Commercial Street	Edge Overlay
8F	J Street	26th Street	27th Street	Fullwidth Overlay
8F	K Street	24th Street	25th Street	Fullwidth Overlay
8F	K Street	25th Street	26th Street	Fullwidth Overlay
8F	K Street	26th Street	27th Street	Fullwidth Overlay
8F	L Street	24th Street	25th Street	Fullwidth Overlay
8F	L Street	25th Street	26th Street	Fullwidth Overlay
8F	L Street	26th Street	27th Street	Fullwidth Overlay
8F	Imperial Ave	21th Street	22nd Street	Fullwidth Overlay
8F	Imperial Ave	22nd Street	24th Street	Fullwidth Overlay
8F	Imperial Ave	24th Street	25th Street	Fullwidth Overlay
8F	Imperial Ave	27th	Intersection Imperial	Fullwidth Overlay
8F	Commercial St	22nd Street	24th Street	Slurry Seal
8G	19th Street	G Street	Market St	Slurry Seal
8G	19th Street	Market St	Island Ave	Fullwidth Overlay
8G	19th Street	Island Ave	J Street	Fullwidth Overlay
8G	19th Street	J Street	K Street	Fullwidth Overlay
8G	19th Street	K Street	L Street	Fullwidth Overlay
8G	19th Street	L Street	Imperial Ave	Fullwidth Overlay
8G	19th Street	Imperial Ave	Commercial Street	Fullwidth Overlay
8G	20th Street	G Street	Market St	Fullwidth Overlay
8G	20th Street	Market St	Island Ave	Slurry Seal
8G	21th Street	G Street	Market St	Fullwidth Overlay
8G	22nd Street	G Street	Market St	Fullwidth Overlay
8G	22nd Street	Market St	Island Ave	Fullwidth Overlay
8G	22nd Street	Island Ave	J Street	Slurry Seal
8G	22nd Street	J Street	K Street	Slurry Seal
8G	22nd Street	K Street	L Street	Fullwidth Overlay
8G	22nd Street	L Street	Imperial Ave	Fullwidth Overlay
8G	G Street	19th Street	20th Street	Slurry Seal
8G	G Street	20th Street	21th Street	Slurry Seal
8G	G Street	21th Street	22nd Street	Slurry Seal
8G	G Street	22nd Street	24th Street	Slurry Seal
8G	G Street	24th Street	East Terminus Boundary	Slurry Seal
8G	Market St	21th Street	20th Street	Fullwidth Overlay
8G	Market St	20th Street	19th Street	Fullwidth Overlay
8G	Market St	19th Street	Edge of Bridge Concrete	Fullwidth Overlay
8G	Market St	22nd Street	24th Street	Fullwidth Overlay
8G	Island Ave	19th Street	20th Street	Slurry Seal
8G	Island Ave	24th Street	East Terminus Boundary	Fullwidth Overlay
8G	J Street	90' West of 19th St	19th Street	Fullwidth Overlay
8G	J Street	19th Street	20th Street	Slurry Seal
8G	J Street	20th Street	21th Street	Slurry Seal
8G	J Street	21th Street	22nd Street	Slurry Seal

8G	L Street	19th Street	20th Street	Fullwidth Overlay
8G	L Street	20th Street	21th Street	Fullwidth Overlay
8G	L Street	21th Street	22nd Street	Fullwidth Overlay
8G	L Street	22nd Street	24th Street	Fullwidth Overlay
Project Area	Street Name	Cross Street 1	Cross Street 2	Treatment Type
Island Ave PH 1	Island Ave	15th Street	16th Street	Slurry Seal
Island Ave PH 1	Island Ave	16th Street	17th Street	Slurry Seal
Island Ave PH 1	Island Ave	17th Street	19th Street	Slurry Seal
Island Ave PH 1	Island Ave	16th & Island	Intersection	Full Width Overlay
Island Ave PH 2	Island Ave	28th Street	29th Street	Slurry Seal
Island Ave PH 2	Island Ave	29th Street	Dodson Street	Slurry Seal
Island Ave PH 2	Island Ave	Dodson Street	30th Street	Slurry Seal
Island Ave PH 2	Island Ave	30th Street	East Terminus Boundary, 210	Fullwidth Overlay
Island Ave PH 2	28th Street	Island Ave	South Terminus Boundary, 50	Slurry Seal
Island Ave PH 2	Hoitt St	Island Ave	South Terminus Boundary, 50	Slurry Seal
K Street PH 1	K Street	19th Street	20th Street	Slurry Seal
K Street PH 1	K Street	20th Street	21th Street	Fullwidth Overlay
K Street PH 1	K Street	21th Street	22nd Street	Fullwidth Overlay
K Street PH 1	K Street	22nd Street	24th Street	Fullwidth Overlay
K Street PH 2	K Street	27th Street	Langley Street	Slurry Seal
K Street PH 2	K Street	Langley Street	28th Street	Slurry Seal
K Street PH 2	K Street	28th Street	Hoitt Street	Slurry Seal
K Street PH 2	K Street	Hoitt Street	Dodson Street	Slurry Seal
K Street PH 2	K Street	Dodson Street	30th Street	Slurry Seal

APPENDIX F
CURB RAMP LOCATION AND TYPE LIST



STANDARD DRAWING

GENERAL CURB RAMP NOTES & SUPPLEMENTAL DETAILS
 TYPE A & B SDG-130
 TYPE C SDG-132
 TYPE D SDG-134
 TYPE E SDG-135
 TYPE F SDG-136
 EX STAMP/IMPRESSION PLACEMENT SDG-16

LEGEND


- (B) CURB RAMP NO's
- + EX UTILITY POLE
- EX FIRE HYDRANT
- EX STREET LIGHT
- T EX TREE
- EX STREET SIGN
- EX CURB RAMP

NOTE




1. PROTECT EXISTING WATER METER/UTILITY AND ELECTRICAL BOX AND ADJUST TO GRADE.
2. HISTORIC STAMPS TO BE SAVED AND REINSTALLED PER SDG's.
3. MODIFIED CURB RAMP CAN BE EXTENDED UP TO MAXIMUM OF 15 LINEAR FEET TO CATCH THE REQUIRED SLOPE OR REPLACE THE DAMAGED SIDEWALK.
4. THE DETECTABLE WARNING TILES SHALL BE STAINLESS STEEL PER THE CITY'S APPROVED MATERIALS LIST.
5. CONTRACTOR TO MOVE THE LIMIT LINE BEFORE EACH CURB RAMP.
6. USE 12"-WIDE WHITE THERMOPLASTIC FINISH

CURB RAMP NOTES TABLE

LOCATION NO	CURB RAMP		REPLACEMENT	NEW	HISTORIC STAMPS	TRUNCATED CORNER MATERIAL		SURVEY MARKER	MISC SIGN	COMMENTS / MODIFICATIONS
	TYPE	CASE				STAINLESS STEEL	OTHER			
1	A		X		X	X	X	X		
2	A		X		X	X	X	X		
3	D		X		X	X	X			
4	D		X		X	X	X	X		ATT BOX
5	D		X		X	X	X			
6	D		X		X	X	X			
7	A		X		X	X	X	X		INSTALLED BY DIFFERENT CONTRACT
8	A		X		X	X	X	X		INSTALLED BY DIFFERENT CONTRACT
9	D		X		X	X	X			INSTALLED BY DIFFERENT CONTRACT
10	D		X		X	X	X			INSTALLED BY DIFFERENT CONTRACT
11	A		X		X	X	X			INSTALLED BY DIFFERENT CONTRACT
12	A		X		X	X	X			INSTALLED BY DIFFERENT CONTRACT
13	D		X		X	X	X			INSTALLED BY DIFFERENT CONTRACT
14	D		X		X	X	X			INSTALLED BY DIFFERENT CONTRACT
15	D		X		X	X	X			
16	D		X		X	X	X			PHONE BOX
17	A		X		X	X	X			PROTECT EXISTING STREET LIGHT
18	A		X		X	X	X			RAISE CURB NO MORE THAN 5% PROVIDE AFLUSH CONDITION WITH PAVEMENT SURFACE
19	D		X		X	X	X			
20	D		X		X	X	X			
21	A		X		X	X	X			
22	A		X		X	X	X			TRASH CAN; BUS SIGN; TRAFFIC VAULT PROTECT EXISTING STREET LIGHT
23	D		X		X	X	X			
24	D		X		X	X	X			
25	D		X		X	X	X			
26	D		X		X	X	X			COX VAULT
27	D		X		X	X	X			BROKEN WATER METER BOX (NEEDS TO BE REPLACED).
28	A		X		X	X	X			TRAFFIC LIGHT; TRASH CAN; BUS SIGN
29	D		X		X	X	X			
30	D		X		X	X	X			



DETAIL "C"
No Scale



CURB RAMP NOTES TABLE										
LOCATION	CURB RAMP TYPE	CASE	REPLACEMENT	NEW	HISTORIC STAMPS	TRUNCATED POLE MATERIAL	OTHER	SURVEY MARKER	MISC. SIGN	COMMENTS / MODIFICATIONS
31	A		X			X				TRASH CAN
32	A	X				X				TRASH CAN ADVERTISEMENT FLAG
33	D		X			X				ELECTRICAL SUPPORT POLE
34	D			X		X				STREET LIGHT VAULT; PROTECTION POLES; S&E TRANSFORMER VAULT
35	A		X			X				TRASHCAN & STREET LIGHT VAULT; REMOVE RAILROAD TRACKS
36	A	X				X				TRASHCAN; TROLLEY SUPPORT POLE; STREET LIGHT VAULT
37	C2	X				X				MODIFIED, REINSTALL BAILERS AS NEEDED
38	C2	X				X				PROTECT EXISTING FENCING
39	D			X		X				TRASHCAN; BUS SIGN
40	D			X		X				STREET LIGHT VAULT
41	D	X				X				
42	C1	X				X				INSTALL PEDESTRIAN BARRICADE PER SDE-103 ON STREET LIGHT VAULT
43	B	X				X				DIRECTIONAL SEE DETAIL THIS SHEET, PROTECT EXISTING FENCING
44	A	X				X				TRAFFIC LIGHT; ELECTRICAL VAULT; TRAFFIC BOX
45	D	X				X				RAMP TO HAVE FLARES ON BOTH SIDES
46	D	X				X				TELEPHONE BOOTH; CABLE BOX; TELEPHONE BOX; CURB RAMP TO HAVE FLARES ON BOTH SIDES
48	B		X			X				
49	A	X				X		X		INSTALL PEDESTRIAN BARRICADE AT CORNER PER SDE-103; DIRECTIONAL CURB RAMP
50	A	X				X				
51	A	X				X	X			
53	A	X				X				INSTALL PEDESTRIAN BARRICADE PER SDE - 103 SEE DETAIL
54	B	X				X	X			INSTALL MODIFIED B ON SOUTH
55	B		X			X	X			INSTALL MODIFIED B FACING NORTH

NOTE


- PROTECT EXISTING WATER METER/UTILITY AND ELECTRICAL BOX AND ADJUST TO GRADE.
- HISTORIC STAMPS TO BE SAVED AND REINSTALLED PER SDGS.
- MODIFIED CURB RAMP CAN BE EXTENDED UP TO MAXIMUM OF 15 LINEAR FEET TO CATCH THE REQUIRED SLOPE OR REPLACE THE DAMAGED SIDEWALK.
- THE DETECTABLE WARNING TILES SHALL BE STAINLESS STEEL PER THE CITY'S APPROVED MATERIALS LIST.
- CONTRACTOR TO MOVE THE LIMIT LINE BEFORE EACH CURB RAMP. USE 12"-WIDE WHITE THERMOPLASTIC FINISH


LEGEND

- (B) CURB RAMP NO'S
- EX UTILITY POLE
- EX FIRE HYDRANT
- EX STREET LIGHT
- EX TREE
- EX STREET SIGN
- EX CURB RAMP
- (C) UNDER CONSTRUCTION

STANDARD DRAWING

GENERAL CURB RAMP NOTES & SUPPLEMENTAL DETAILS
 TYPE A & B SDC-132
 TYPE C1 SDC-134
 TYPE C2 SDC-135
 TYPE D SDC-136
 EX STAMP/IMPRESSION PLACEMENT SDC-137
 PEDESTRIAN BARRICADE SDE-103





CURB RAMP NOTES TABLE									
LOCATION NO	CURB RAMP		REPLACEMENT	NEW	HISTORIC STAMPS	TRUNCATED FOR MATERIAL	SURVEY MARKER	MISC SIGN	COMMENTS / MODIFICATIONS
	TYPE	CASE							
56	D			X		X			
57	A	A		X	X	X			
58	A		X		X	X	X		
59	A		X		X	X			
60	D		X		X	X			
61	D		X		X	X			
62	B		X						ON WEST SIDE CORNER
63	D		X						
64	D		X			X			
65	A		X			X			
66	D		X			X			
67	A		X			X			
68	D		X			X			
69	D		X			X			
70	D		X			X			
71	A	X				X			

STANDARD DRAWING

GENERAL CURB RAMP NOTES & SUPPLEMENTAL DETAILS
 TYPE A & B
 TYPE C
 TYPE D
 EX STAMP/IMPRESSION PLACEMENT

SDG-130
 SDG-132
 SDG-134
 SDG-135
 SDG-136
 SDG-137

LEGEND


(B) CURB RAMP NO'S
 + EX UTILITY POLE
 * EX FIRE HYDRANT
 ○ EX STREET LIGHT
 T EX TREE
 + EX STREET SIGN
 □ EX CURB RAMP





NO SCALE

NOTE

1. PROTECT EXISTING WATER METER/UTILITY AND ELECTRICAL BOX AND ADJUST TO GRADE.
2. HISTORIC STAMPS TO BE SAVED AND REINSTALLED PER SDGHS.
3. MODIFIED CURB RAMP CAN BE EXTENDED UP TO MAXIMUM OF 15 LINEAR FEET TO CATCH THE REQUIRED SLOPE OR REPLACE THE DAMAGED SIDEWALK.
4. THE DETECTABLE WARNING TILES SHALL BE STAINLESS STEEL PER THE CITY'S APPROVED MATERIALS LIST.
5. CONTRACTOR TO MOVE THE LIMIT LINE BEFORE EACH CURB RAMP. USE 12"-WIDE WHITE THERMOPLASTIC FINISH




LOCATION NO	CURB RAMP TYPE	CASE	REPLACEMENT	NEW	HISTORIC STAMPS	TRUNCATED CONC. STEEL	STAINLESS STEEL	OTHER	SURVEY MARKER	MISC. SIGN	COMMENTS / MODIFICATIONS
1	C1			X		X					NO EXISTING CURB RAMP, RELOCATE SIGNS IF NEEDED TO PROVIDE THE CLEARANCE REQUIRED FOR THE ACCESSIBLE PATH PER MUTCD. RELOCATE COX COMMUNICATION VAULT. ADD ADDITIONAL 5' X 10' SIDEWALK, W OF G ST, MOVE STOP LIMIT LINE 5' N OF 22ND ST. SEE DETAIL "A"
2	A			X		X					NO EXISTING CURB RAMP, RELOCATE SIGNS IF NEEDED TO PROVIDE THE CLEARANCE REQUIRED FOR THE ACCESSIBLE PATH PER MUTCD. SEE DETAIL "B".
3	C2	X				X					
4	A	X				X					
5	C2		X		X	X					RELOCATE STREET LIGHT VAULT, RELOCATE PPB'S AS NECESSARY TO COMPLY WITH MUTCD. CONTRACTOR TO PROTECT THE BUILDING CORNER AND FENCE.
6	A	X			X	X					RELOCATE PPB'S AS NECESSARY TO COMPLY WITH MUTCD. RELOCATE STREET LIGHT VAULT.





NOTE:

1. PROTECT EXISTING WATER METER/UTILITY AND ELECTRICAL BOX AND ADJUST TO GRADE.
2. HISTORIC STAMPS TO BE SAVED AND REINSTALLED PER SDGHS.
3. MODIFIED CURB RAMP CAN BE EXTENDED UP TO MAXIMUM OF 15 LINEAR FEET TO CATCH THE REQUIRED SLOPE OR REPLACE THE DAMAGED SIDEWALK.
4. THE DETECTABLE WARNING TILES SHALL BE STAINLESS STEEL PER THE CITY'S APPROVED MATERIALS LIST.
5. CONTRACTOR TO MOVE THE LIMIT LINE BEFORE EACH CURB RAMP. USE 12"-WIDE WHITE THERMOPLASTIC FINISH



(B)	CURB RAMP NO'S	□	STORM DRAIN INLET
+	EX UTILITY POLE	T	EX TREE
□	EX FIRE HYDRANT	+	EX STREET SIGN
o	EX STREET LIGHT	PPB	PEDESTRIAN PUSHBUTTONS
□	EX CURB RAMP	MUTCD	MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES
□	CURB RAMP - TYPE A		
□	CURB RAMP - TYPE B		
□	CURB RAMP - TYPE C1		
□	CURB RAMP - TYPE C2		
□	CURB RAMP - TYPE D		
□	DETECTABLE WARNING TILES		
□	GENERAL CURB RAMP NOTES & SUPPLEMENTAL DETAILS		
□	EX STAMP/IMPRESSION PLACEMENT		
□	ISLAND REFUGE/PASSAGEWAY DETAILS		

CITY OF SAN DIEGO, CALIFORNIA PUBLIC WORKS - ENGINEERING AND CAPITAL PROJECTS SHEET 1 OF 3 SHEETS				ISS. # B-00829
FOR CITY ENGINEER	DATE	PROJECT MANAGER	DATE	
DESCRIPTION	BY	APPROVED	DATE	FILED
ORIGINAL				
PROJECT ENGINEER				
198-1719				
COST COORDINATOR				
6280407-1834444				
COST COORDINATOR				
CONTRACTOR	DATE STARTED			
INSPECTOR	DATE COMPLETED			



CURB RAMP NOTES TABLE

LOCATION NO	CURB RAMP		REPLACEMENT	NEW	HISTORIC STAMPS	TRUNCATED CORNER MATERIAL STEELED OTHER	SURVEY MARKER	MISC SIGN	COMMENTS / MODIFICATIONS
	TYPE	CASE							
7	A		X		X	X			INSTALLED BY DIFFERENT CONTRACT
8	A			X	X	X			INSTALLED BY DIFFERENT CONTRACT
9	A			X	X	X			INSTALLED BY DIFFERENT CONTRACT
10	A			X	X	X			INSTALLED BY DIFFERENT CONTRACT
11	A			X	X	X			INSTALLED BY DIFFERENT CONTRACT
12	A		X			X			INSTALLED BY DIFFERENT CONTRACT
13	A		X			X			INSTALLED BY DIFFERENT CONTRACT
14	A			X	X	X			INSTALLED BY DIFFERENT CONTRACT
15	D				X	X	X		NO EXISTING CURB RAMP, HISTORICAL STAMP
16	D				X	X	X		NO EXISTING CURB RAMP, HISTORICAL STAMP




FIGURE 406.6
DIAGONAL OR CORNER TYPE CURB RAMPS

NOTE:

1. PROTECT EXISTING WATER METER/UTILITY AND ELECTRICAL BOX AND ADJUST TO GRADE.
2. HISTORIC STAMPS TO BE SAVED AND REINSTALLED PER SDGHS.
3. MODIFIED CURB RAMP CAN BE EXTENDED UP TO MAXIMUM OF 15 LINEAR FEET TO CATCH THE REQUIRED SLOPE OR REPLACE THE DAMAGED SIDEWALK.
4. THE DETECTABLE WARNING TILES SHALL BE STAINLESS STEEL PER THE CITY'S APPROVED MATERIALS LIST.
5. CONTRACTOR TO MOVE THE LIMIT LINE BEFORE EACH CURB RAMP. USE 12"-WIDE WHITE THERMOPLASTIC FINISH.


LEGEND:

ⓑ	CURB RAMP NO'S	☐	STORM DRAIN INLET
+	EX UTILITY POLE	T	EX TREE
☐	EX FIRE HYDRANT	+	EX STREET SIGN
•	EX STREET LIGHT	PPB	PEDESTRIAN PUSHBUTTONS
☐	EX CURB RAMP	EX	EXISTING
	UP TO STANDARD		

PROPOSED CURB RAMPS PER STANDARD DRAWINGS:
 CURB RAMP - TYPE A & B SDG-132
 CURB RAMP - TYPE C1 SDG-134
 CURB RAMP - TYPE C2 SDG-135
 CURB RAMP - TYPE D SDG-136
 CURB RAMP - TYPE D SDG-130
 DETECTABLE WARNING TILES SDG-130
 GENERAL CURB RAMP NOTES & SUPPLEMENTAL DETAILS SDG-130
 EX STAMP/IMPRESSION PLACEMENT SDG-135
 ISLAND REFUGE/PASSAGEWAY DETAILS SDG-130


2013 UUP CURB RAMPS
RESIDENTIAL PROJECT BLOCK 8-G
SHERMAN HEIGHTS 2

CITY OF SAN DIEGO, CALIFORNIA		WBS #	B-00829
PUBLIC WORKS - ENGINEERING AND CAPITAL PROJECTS		SEWER	
SHEET 2 OF 3 SHEETS		WATER	
DATE:		PROJECT MANAGER:	
FOR CITY ENGINEER:	DATE:	DATE:	
DESCRIPTION:	BY:	APPROVED:	DATE:
ORIGINAL:			
			PROJECT ENGINEER
			198-1719
			DESIGN COORDINATOR
			62886407-1834444
			CURB COORDINATOR
CONTRACTOR:	DATE STARTED:		
INSPECTOR:	DATE COMPLETED:		



CURB RAMP NOTES TABLE

LOCATION (20)	CURB RAMP		REPLACEMENT	NEW	HISTORIC STAMPS	TRUNCATED OR MATERIAL	SURVEY MARKER	MISC SIGN	COMMENTS / MODIFICATIONS
	TYPE	CASE							
17	D			X					
18	D			X	X	X			NO EXISTING CURB RAMP. HISTORICAL STAMP INSTALLED BY DIFFERENT CONTRACT
19	A			X	X	X			INSTALLED BY DIFFERENT CONTRACT
20	A		X			X			INSTALLED BY DIFFERENT CONTRACT
21	A		X			X			INSTALLED BY DIFFERENT CONTRACT
22	A			X	X	X			INSTALLED BY DIFFERENT CONTRACT
23	A			X	X	X			INSTALLED BY DIFFERENT CONTRACT
24	A			X	X	X			INSTALLED BY DIFFERENT CONTRACT
25	A			X	X	X			INSTALLED BY DIFFERENT CONTRACT
25	E	X		X	X	X			RELOCATE TRAFFIC SIGNAL VAULT, RELOCATE PPB'S AS NECESSARY TO COMPLY WITH MUTCD. HISTORICAL STAMP.
26	A		X			X			RELOCATE PPB'S AS NECESSARY TO COMPLY WITH MUTCD.
27	C2		X			X			INSTALLED BY DIFFERENT CONTRACT
28	A		X			X			INSTALLED BY DIFFERENT CONTRACT
29	C1		X			X			INSTALLED BY DIFFERENT CONTRACT
30	C2		X			X			INSTALLED BY DIFFERENT CONTRACT



NOTE:

- PROTECT EXISTING WATER METER/UTILITY AND ELECTRICAL BOX AND ADJUST TO GRADE.
- HISTORIC STAMPS TO BE SAVED AND REINSTALLED PER SDGIS.
- MODIFIED CURB RAMP CAN BE EXTENDED UP TO MAXIMUM OF 15 LINEAR FEET TO CATCH THE REQUIRED SLOPE OR REPLACE THE DAMAGED SIDEWALK.
- THE DETECTABLE WARNING TILES SHALL BE STAINLESS STEEL PER THE CITY'S APPROVED MATERIALS LIST.
- CONTRACTOR TO MOVE THE LIMIT LINE BEFORE EACH CURB RAMP. USE 12"-WIDE WHITE THERMOPLASTIC FINISH.


LEGEND:	
(B)	CURB RAMP NO'S
+	EX UTILITY POLE
□	EX FIRE HYDRANT
○	EX STREET LIGHT
□	EX CURB RAMP UP TO STANDARD
□	STORM DRAIN INLET
○	STORM DRAIN MANHOLE
T	EX TREE
+	EX STREET SIGN
PPB	PEDESTRIAN PUSHBUTTONS
EX	EXISTING

PROPOSED CURB RAMPS PER STANDARD DRAWINGS:
 CURB RAMP - TYPE A & B SDG-132
 CURB RAMP - TYPE C1 SDG-134
 CURB RAMP - TYPE C2 SDG-135
 CURB RAMP - TYPE D SDG-136
 DETECTABLE WARNING TILES SDG-130
 GENERAL CURB RAMP NOTES & SUPPLEMENTAL DETAILS SDG-130
 EX STAMP/IMPRESSION PLACEMENT SDG-135
 ISLAND REFUGE/PASSAGEWAY DETAILS SDG-130

2013 UUP CURB RAMPS			
RESIDENTIAL PROJECT BLOCK 8-G SHERMAN HEIGHTS 2			
CITY OF SAN DIEGO, CALIFORNIA		PWS # B-00829	
PUBLIC WORKS - ENGINEERING AND CAPITAL PROJECTS		SHEET 2 OF 2 SHEETS	
FOR CITY ENGINEER		DATE	
DESCRIPTION	BY	APPROVED	DATE
ORIGINAL			
PROJECT NUMBER		P98-1719	
CITY COORDINATOR		6286407-1834444	
CONTRACTOR		DATE STARTED	
INSPECTOR		DATE COMPLETED	

CURB RAMP NOTES TABLE

LOCATION	CURB RAMP		REPLACEMENT	NEW	HISTORIC STAMPS	SURVEY MARKER	ST. SIGN	COMMENTS / MODIFICATIONS
	TYPE	CASE						
1	A		X					
2	A		X				X	
3	A		X				X	ADJUST TO ACCOMMODATE LIGHT AND ELECTRICAL BOX
4	A		X				X	ADJUST TO ACCOMMODATE LIGHT AND ELECTRICAL BOX
5	A		X				X	RAISE SIDEWALK AND ADJUST TO ACCOMMODATE LIGHT POST ELECTRIC BOX AND POLE
6	A		X				X	
7	A		X				X	
8	A		X				X	



NOTES

1. PROTECT EXISTING WATER METER/UTILITY AND ELECTRICAL BOX AND ADJUST TO GRADE.
2. HISTORIC STAMPS TO BE SAVED AND REINSTALLED PER SDG-115.
3. MODIFIED CURB RAMPS CAN BE EXTENDED UP TO MAXIMUM OF 15 LINEAR FEET TO CATCH THE REQUIRED SLOPE OR REPLACE THE DAMAGED SIDEWALK.
4. THE DETECTABLE WARNING TILES SHALL BE STAINLESS STEEL PER THE CITY'S APPROVED MATERIALS LIST.
5. CONTRACTOR TO NOTIFY THE SURVEY DIVISION 7 DAYS PRIOR TO REMOVAL OF SIDEWALK FOR CURB RAMP CONSTRUCTION TO RELOCATE ANY SURVEY MARKERS.

LEGEND


- Ⓢ CURB RAMP NO's
- EX UTILITY POLE
- ⊠ EX FIRE HYDRANT
- EX STREET LIGHT
- T EX TREE
- ↑ EX STREET SIGN
- EX CURB RAMP
- ⊞ EX ELEC STRUCT
- ⊞ CATV STRUCT
- ⊞ TELEPHONE STRUCT
- WATER METER

STANDARD DRAWING


GENERAL CURB RAMP NOTES & SUPPLEMENTAL DETAILS	SDC-130
TYPE A & B	SDC-132
TYPE C	SDC-134
TYPE C2	SDC-135
TYPE D	SDC-136
EX STAMP/IMPRESSION PLACEMENT	SDC-115



SHEET #



LOCATION (B)	CURB RAMP		REPLACEMENT	NEW	HISTORIC STAMPS	STAINLESS STEEL TILES	SURVEY MARKER	MSC SIGN	COMMENTS / MODIFICATIONS
	TYPE	CASE							
1	A			X		X	X		NO EXISTING CURB RAMP, SEE DETAIL "A". REPLACE DRIVEWAY. REPLACE THE BROKEN CONCRETE PORTION OF SIDEWALK AND GUTTER.
2	A		X			X	X		NO EXISTING CURB RAMP, SEE DETAIL "A". STEEP TRANSITION ON THE LEFT SIDE OF THE CURB, USE 6" MONOLITHIC CURB, RELOCATE STREET NAME SIGNAL AND THE STOP LIMIT LINE.
3	A		X			X	X		NO EXISTING CURB RAMP, SEE DETAIL "A" CONTRACTOR TO PROTECT THE EXISTING CONCRETE WALL BEHIND THE SIDEWALK, USE 6" MONOLITHIC CURB, RELOCATE STOP LIMIT LINE.
4	C2			X	X	X	X		NO EXISTING CURB RAMP, (D) HISTORICAL STAMP, SEE DETAIL "A". RELOCATE STREET NAME SIGNAL AND STOP LIMIT LINE.
5	B		X			X			NO EXISTING CURB RAMP, SEE DETAIL "B". CONTRACTOR TO RELOCATE ALL UTILITY VAULTS ALONG SIDEWALK AS NECESSARY TO ACCOMMODATE CURB RAMP CONSTRUCTION.
6	C2		X			X	X		SEE DETAIL "B". CONTRACTOR TO PROTECT THE EXISTING CONCRETE WALL BEHIND THE SIDEWALK.
7	C2			X	X	X			NO EXISTING CURB RAMP, (D) HISTORICAL STAMP, SEE DETAIL "B". USE 6" MONOLITHIC CURB, INSTALL PEDESTRIAN BARRICADE SDE-103.
B	A		X			X			STORM DRAIN INLET
B	A		X			X			STORM DRAIN INLET



NOTE:

- PROTECT EXISTING WATER METER/UTILITY AND ELECTRICAL BOX AND ADJUST TO GRADE.
- HISTORIC STAMPS TO BE SAVED AND REINSTALLED PER SDG15.
- MODIFIED CURB RAMP CAN BE EXTENDED UP TO MAXIMUM OF 15 LINEAR FEET TO CATCH THE REQUIRED SLOPE OR REPLACE THE DAMAGED SIDEWALK.
- THE DETECTABLE WARNING TILES SHALL BE STAINLESS STEEL PER THE CITY'S APPROVED MATERIALS LIST.
- CONTRACTOR TO MOVE THE LIMIT LINE BEFORE EACH CURB RAMP. USE 12"-WIDE WHITE THERMOPLASTIC FINISH.


(B)	CURB RAMP No's	-x-x-	PEDESTRIAN BARRICADE
+	EX UTILITY POLE	+	EX STREET SIGN
□	EX FIRE HYDRANT	□	EX CURB RAMP UP TO STANDARD
○	EX STREET LIGHT		
T	EX TREE		

PROPOSED CURB RAMPS PER STANDARD DRAWINGS:


CURB RAMP - TYPE A & B	SDC-132
CURB RAMP - TYPE C1	SDC-134
CURB RAMP - TYPE C2	SDC-135
CURB RAMP - TYPE D	SDC-136
DETECTABLE WARNING TILES	SDC-137
SUPPLEMENTAL DETAILS	SDC-138
EX STAMP/IMPRESSON PLACEMENT	SDC-139
ISLAND REFUGE/PASSAGEWAY DETAILS	SDC-140
PEDESTRIAN BARRICADE	SDC-103




CITY OF SAN DIEGO, CALIFORNIA		ISS #	B-00705
PUBLIC WORKS - ENGINEERING AND CAPITAL PROJECTS		SEER	
SHEET 1 OF 2		DESIGNED BY	
FOR CITY ENGINEER	DATE	PROJECT MANAGER	
DESCRIPTION	BY	APPROVED	DATE
ORIGINAL			
CONTRACTOR	DATE STARTED	CURB COORDINATOR	
INSPECTOR	DATE COMPLETED		




DETAIL "A"




DETAIL "B"



PLAN - TYPE A



SECTION A-A



PLAN - TYPE C2


LEGEND	
(B)	CURB RAMP NO'S
+	EX UTILITY POLE
□	EX FIRE HYDRANT
○	EX STREET LIGHT
T	EX TREE
-x-x-	PEDESTRIAN BARRICADE
+	EX STREET SIGN
□	EX CURB RAMP UP TO STANDARD

PROPOSED CURB RAMPS PER STANDARD DRAWINGS:	
CURB RAMP - TYPE A & B	SDG-122
CURB RAMP - TYPE C1	SDG-124
CURB RAMP - TYPE C2	SDG-135
CURB RAMP - TYPE D	SDG-136
DETECTABLE WARNING TILES	SDG-130
GENERAL CURB RAMP NOTES & SUPPLEMENTAL DETAILS	SDG-130
ISLAND REFUGE/PASSAGEWAY DETAILS	SDG-135
PEDESTRIAN BARRICADE	SDE-103

2013 UUP CURB RAMPS			
ISLAND AVE PHASE II (26TH TO 30TH)			
CITY OF SAN DIEGO, CALIFORNIA PUBLIC WORKS - ENGINEERING AND CAPITAL PROJECTS SHEET 2 OF 2 SHEETS		PWS # B-00705 SEWER # PROJECT NUMBER 198-1725 CDDP CODE/OWNER 6286407-1838444 CDDP CONTRACTOR	
FOR CITY ENGINEER	DATE	PROJECT MANAGER	DATE
DESCRIPTION	BY	APPROVED	DATE
ORIGINAL		FILED	
CONTRACTOR		DATE STARTED	
INSPECTOR		DATE COMPLETED	


NOTES

1. PROTECT EXISTING WATER METER/UTILITY AND ELECTRICAL BOX AND ADJUST TO GRADE.
2. HISTORIC STAMPS TO BE SAVED AND REINSTALLED PER SDG-115.
3. MODIFIED CURB RAMP CAN BE EXTENDED UP TO MAXIMUM OF 15 LINEAR FEET TO CATCH THE REQUIRED SLOPE OR REPLACE THE DAMAGED SIDEWALK.
4. THE DETECTABLE WARNING TILES SHALL BE STAINLESS STEEL REPLACEABLE PER THE CITY'S APPROVED MATERIALS LIST.
5. CONTRACTOR TO NOTIFY THE SURVEY DIVISION 7 DAYS PRIOR TO REMOVAL OF SIDEWALK FOR CURB RAMP CONSTRUCTION TO RELOCATE ANY SURVEY MARKERS.



CURB RAMP NOTES TABLE

LOCATION	CURB RAMP		REPLACEMENT	NEW	HISTORIC STAMPS	SURVEY MARKER	ST. SIGN	COMMENTS / MODIFICATIONS
	TYPE	CASE						
1	A		X					FIX THE BOTTOM LANDING 5' FROM FL
2	A		X			X		FIX THE BOTTOM LANDING 5' FROM FL. MOVE THE STOP LIMIT LINE PER DETAIL B FROM SDG 133 SHEET 4/5
3	A			X	X			RE-INSTALL THE STREET SIGN. THE BOTOM OF THE SIGN SHALL BE 80" MIN. FROM FF
4	D		X					
5	D		X					
6	D		X					
7	D		X					



DETAIL B
TYPICAL ONE-RAMP
CORNER INSTALLATION
SDG-130
NO SCALE

STANDARD DRAWING

GENERAL CURB RAMP NOTES & SUPPLEMENTAL DETAILS
 TYPE A & B
 TYPE C1
 TYPE C2
 TYPE D
 EX STAMP/IMPRESSION PLACEMENT

SDG-130
 SDG-132
 SDG-134
 SDG-135
 SDG-136
 SDG-15


LEGEND

- Ⓟ CURB RAMP NO's
- + EX UTILITY POLE
- ⊠ EX FIRE HYDRANT
- ⊙ EX STREET LIGHT
- T EX TREE
- ⌋ EX STREET SIGN
- ⊞ EX CURB RAMP
- ⊞ EX ELECTRIC PB-RISER-TRANS



NO SCALE

SHEET #




CURB RAMP NOTES TABLE

LOCATION	CURB RAMP TYPE	CASE	REPLACEMENT	NEW	HISTORIC STAMPS	TRUNCATED CONE DOWNS		SURVEY MARKER	MISC SIGN	COMMENTS / MODIFICATIONS
						STAINLESS STEEL	OTHER			
1	A	X			X					N/A
2	A	X			X					N/A
3	B	X			X					N/A
4	D	X			X					N/A
5	D	X			X					N/A
6	B	X			X					SEE DETAIL "A" AND RELOCATE PPB'S TO COMPLY WITH MUTCD.
7	B	X			X					SEE DETAIL "A" INSTALL PEDESTRIAN PUSHBUTTON NW OF 28TH AND K ST. RELOCATE LIMIT LINE BEFORE THE CURB RAMP.
8	B	X			X					SEE DETAIL "A" AND RELOCATE PPB'S TO COMPLY WITH MUTCD.
9	B	X			X					SEE DETAIL "A" RELOCATE PPB'S TO COMPLY WITH MUTCD AND RELOCATE LIMIT LINE BEFORE THE CURB RAMP.
10	B	X			X			X		SEE DETAIL "A" RELOCATE FIRE HYDRANT, RT. RELOCATE PPB'S AS NECESSARY TO COMPLY WITH MUTCD.
11	B	X			X			X		SEE DETAIL "A" RELOCATE PPB'S TO COMPLY WITH MUTCD AND RELOCATE LIMIT LINE BEFORE THE CURB RAMP.
12	B	X			X			X		SEE DETAIL "A".
13	B	X			X			X		SEE DETAIL "A" RELOCATE EXISTING ABOVE GROUND UTILITY BOX AND RELOCATE LIMIT LINE BEFORE THE CURB RAMP.
14	A	X			X					SEE DETAIL "B"
15	A	X			X			X		SEE DETAIL "B"
16	B	X			X					SEE DETAIL "B"
17	B	X			X					NO EXISTING CURB RAMP, NEW DESIGN 29 FEET OFFSET, SEE DETAIL B
18	B	X			X					NO EXISTING CURB RAMP, NEW DESIGN 29 FEET OFFSET, SEE DETAIL B
19	D	X			X					N/A
20	D	X			X					N/A
21	B	X			X					N/A
22	B	X			X					N/A
23	A	X			X	X		X		(1) HISTORIC STAMP
24	A	X			X	X		X		(3) HISTORIC STAMPS
25	B	X			X					N/A
26	A	X			X					N/A
27	A	X			X					N/A
28	A	X			X					N/A
29	A	X			X					N/A

NOTE:



1. PROTECT EXISTING WATER METER/UTILITY AND ELECTRICAL BOX AND ADJUST TO GRADE.
2. HISTORIC STAMPS TO BE SAVED AND REINSTALLED PER SDGHS.
3. MODIFIED CURB RAMP CAN BE EXTENDED UP TO MAXIMUM OF 15 LINEAR FEET TO CATCH THE REQUIRED SLOPE OR REPLACE THE DAMAGED SIDEWALK.
4. THE DETECTABLE WARNING TILES SHALL BE STAINLESS STEEL PER THE CITY'S APPROVED MATERIALS LIST.
5. CONTRACTOR TO MOVE THE LIMIT LINE BEFORE EACH CURB RAMP. USE 12"-WIDE WHITE THERMOPLASTIC FINISH







LEGEND	
(B) - CURB RAMP NO'S	PPB - PEDESTRIAN PUSHBUTTONS
— EX UTILITY POLE	MUTCD - MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES
□ - EX FIRE HYDRANT	N/A - NOT AVAILABLE
○ - EX STREET LIGHT	EX - EXISTING
T - EX TREE	
— EX STREET SIGN	
□ - EX CURB RAMP UP TO STANDARD	

PROPOSED CURB RAMPS PER STANDARD DRAWINGS:	
CURB RAMP - TYPE A & B	SDG-132
CURB RAMP - TYPE C1	SDG-134
CURB RAMP - TYPE C2	SDG-135
CURB RAMP - TYPE D	SDG-136
DETECTABLE WARNING TILES	SDG-130
GENERAL CURB RAMP NOTES & SUPPLEMENTAL DETAILS	SDG-130
EX STAMP/IMPRESSION PLACEMENT	SDG-130
ISLAND REFUGE/PASSAGEWAY DETAILS	SDG-130

2013 UUP CURB RAMPS			
K STREET PHASE II (26TH TO 30TH)			
CITY OF SAN DIEGO, CALIFORNIA			
PUBLIC WORKS - ENGINEERING AND CAPITAL PROJECTS			
SHEET 1 OF 2			
PROJECT NO.	ISSUE NO.	DATE	PROJECT MANAGER
FOR CITY ENGINEER	DATE	PROJECT ENGINEER	
DESCRIPTION	BY	APPROVED	DATE
ORIGINAL			
CONTRACTOR	DATE STARTED		
SUPERVISOR	DATE COMPLETED		



TWO-CURB RAMP CORNER INSTALLATION DETAILS



LEGEND

- (B) - CURB RAMP NO'S
- - EX UTILITY POLE
- ⊗ - EX FIRE HYDRANT
- ⊕ - EX STREET LIGHT
- T - EX TREE
- † - EX STREET SIGN
- - EX CURB RAMP
- - LIMIT LINE
- - STORM DRAIN INLET
- - TRAFFIC SIGNAL LOOP
- - PEDESTRIAN BARRICADE
- - PEDESTRIAN PUSHBUTTON

PROPOSED CURB RAMPS PER STANDARD DRAWINGS:

CURB RAMP - TYPE A & B	SDG-132
CURB RAMP - TYPE C1	SDG-134
CURB RAMP - TYPE C2	SDG-134
CURB RAMP - TYPE D	SDG-135
DETECTABLE WARNING TILES	SDG-130
GENERAL CURB RAMP NOTES & SUPPLEMENTAL DETAILS	SDG-130
EX STAMP/IMPRESSION PLACEMENT	SDG-136
ISLAND REFUGE/PASSAGEWAY DETAILS	SDP-130
PEDESTRIAN BARRICADE	SDE-103

2013 UUP CURB RAMPS

K STREET PHASE II
 (26TH TO 31TH)

CITY OF SAN DIEGO, CALIFORNIA
 PUBLIC WORKS - ENGINEERING AND CAPITAL PROJECTS
 SHEET 2 OF 2 SHEETS

ISSUED BY: B-00551
 DATE: 12/8-17/13
 SHEET COORDINATE: 6280407-1834444
 CROSS COORDINATE: 6280407-1834444

FOR CITY ENGINEER	DATE	PROJECT MANAGER

CONTRACTOR: _____ DATE STARTED: _____
 INSPECTOR: _____ DATE COMPLETED: _____

APPENDIX G

SSP TO CALTRANS STANDARD SPECIFICATIONS 2010 EDITION

APPENDIX G

SUPPLEMENTARY SPECIAL PROVISIONS TO THE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS

2010 Edition

SECTION 84: TRAFFIC STRIPES AND PAVEMENT MARKINGS

84-1.03A General ADD the following:

Prior to eradication of existing striping and pavement markings, the contractor shall be responsible for developing and recording control points to re-establish the existing traffic striping and pavement markings. The Contractor shall prepare and submit, for the Engineer's approval, a video recording of all existing improvements, including striping and pavement markings, with sufficient detail to re-establish the existing traffic striping and pavement markings in accordance with City Supplement Section 7-9.1. The Contractor shall provide striping and pavement marking plans to the Resident Engineer a minimum two weeks prior to the start of the AC overlay. The Contractor shall be responsible for verifying the striping and pavement marking quantities.

84-1.03C TOLERANCES AND APPEARANCE ADD the following:

Striping of lane lines and centerlines shall conform to the California MUTCD for the lowest speed of the right-of-way regardless of the speed for the road segment being striped.

84-2.02 MATERIALS ADD the following:

All Pavement markings shall be installed with yellow or white preformed thermoplastic, extruded thermoplastic, or spray thermoplastic. Extrude thermoplastic shall be PTH02ALKYD or equivalent and subject to approval by the Engineer. Products used must be on the State of California, Department of Transportation (Caltrans) Prequalified and Tested Signing and Delineation Materials list. The stencils or preformed pavement markings shall conform to drawings A24 A-F of the Standard Plans of the State of California Department of Transportation, 2010 Edition. Stencils shall be approved by the Engineer prior to use on the contract. Thermoplastic products must be installed in accordance with manufacturer's specifications.

For this contract, the glass beads shall conform to State Specification No. 8010-21C-22 (Type II).

84-1.03D Surface Preparation ADD the following:

Existing thermoplastic markings located within the limits of the area to receive slurry seal shall be removed a maximum of 10 calendar days prior to the application of slurry by wet sandblasting or other approved methods. Dry sandblasting may be used in selected areas only with the permission of the Engineer and with approval of the air pollution control authority having jurisdiction over the area in which the work will be performed. Temporary pavement markers shall be installed at all limit lines, crosswalks, and lane lines to ensure safe traffic operations.

84-1.03E Application of Stripes and Markings ADD the following:

All crosswalk lines, limit lines, and pavement legends (except within a bike lane) shall be thermoplastic in accordance with these Specifications. At no time shall thermoplastic pavement markings be located within designated bike lanes.

The Contractor shall install all required thermoplastic pavement markings, including limit lines, within five (5) calendar days after the day on which the slurry seal is applied on a road segment. Pavement markings shall be applied after a minimum of one coat of traffic striping has been applied to ensure proper placement.

84-2.04 PAYMENT. ADD the following:

All work, materials, labor, costs, and time associated with removing and applying thermoplastic pavement markings shall be included in the lump sum bid item for "Thermoplastic Pavement Markings".

84-3.02A General ADD the following:

For this contract, paint for traffic stripes shall be State of California Department of Transportation Specification PTWB-01 for Paint, Waterborne Traffic Line, White, Yellow, and Black. Samples of paint will be collected randomly in the field for testing by the Engineer. If the paint is found to contain lead or any lead compound, the Contractor shall, at its own expense, neatly and thoroughly remove any and all lead or lead compound bearing markings (both stripes and/or pavement markings) from the road surface. Any waste material generated as a result of the aforesaid removal operation shall be considered as Hazardous Material and shall be disposed of, at the Contractor's expense, in conformance to all applicable State and Federal laws. Certification of said disposal shall be provided to the Engineer.

In the event air pollution control requirements change, the Contractor shall use a lead-free paint product that conforms to the most current State Specifications that satisfy the requirements.

The State Specification No. for glass beads is amended to read "8010-21C-22 (Type II)".

84-3.03 CONSTRUCTION ADD the following:

The first coat of paint for traffic striping shall be applied within five calendar days after the day on which slurry seal is placed on each road segment. The second coat of paint for traffic striping may be applied the same day as the first coat, if the first coat of paint is dry. If the first coat of paint is not dry, the second coat of paint shall be applied no later than five calendar days after the day on which the slurry seal is placed.

In the event traffic striping or pavement marking is not applied within the time restraints specified in this contract, the City may suspend or cease resurfacing operations until such time all required traffic striping and pavement marking has been properly applied, to the satisfaction of the Engineer. For each road segment, all traffic striping shall be completed prior to the installation of raised pavement markers.

The Contractor shall be responsible for maintaining safe traffic operation through the work area.

84-3.04 PAYMENT ADD the following:

All work, materials, labor, costs, and time associated with replacing traffic striping shall be included in the lump sum bid item for "Painted Traffic Striping".

SECTION 85: PAVEMENT MARKERS

85-1.02A General ADD the following:

All references herein to the term "reflective" pavement markers shall refer to the term "retroreflective" pavement markers as the term is used in the Standard Specifications. For the purposes of this project, the two terms are considered interchangeable.

The Resident Engineer shall not be precluded from sampling and testing products appearing on the State of California, Department of Transportation Pre-qualified Products Lists (PQL), including products on the Prequalified and Tested Signing and Delineation Materials list. For each type of product supplied from the PQL, the manufacturer shall furnish, to the Resident Engineer, a Certificate of Compliance in conformance with the provisions in Section 6-3.05E, "Certificates of Compliance", of the CalTrans Standard Specifications.

Products not included in the PQL may be used in the work provided the products conform to the requirement of the CalTrans Standard Specifications and Special Provisions.

Materials and products may be added to the PQL if the manufacturer submits an inquiry to the New Product Coordinator at the Transportation Laboratory, Department of Transportation. Approval of materials or products will depend upon compliance with the California Department of Transportation New Product Evaluation Guidelines dated July 2009.

85-1.02A General ADD the following:

TYPE OF MARKERS:

TYPE A – Non-reflective White Markers

TYPE AY – Non-Reflective Yellow Markers

TYPE C – Red-Clear Retroreflective Markers

TYPE D – 2-Way Yellow Retroreflective Markers

TYPE G – One-Way Clear Retroreflective Markers

TYPE H – One-Way Yellow Retroreflective Markers

TYPE I – 2-Way Blue Retroreflective Markers

TEMPORARY MARKERS

Temporary pavement markers shall be Bunzl Extrusion Model T.O.M., or an approved equal. Reflective temporary pavement markers shall be two-way amber or one-way white to match existing delineation of the traffic stripe and pavement marking. Non-reflective temporary pavement markers shall be one-way white. Payment for all work, materials, labor, costs, and time associated with

placing temporary markers shall be included in the unit Bid item for slurry seal (EAS, REAS, RPMS, etc.) or overlay.

85-1.02C RETROREFLECTIVE PAVEMENT MARKERS ADD the following:

Pavement marker height shall be 0.70" maximum. "Low profile" type markers will not be accepted.

85-1.03A General ADD the following:

Pressure sensitive adhesive pad types shall not be used.

The control lines for placing markers shall be the existing traffic stripes, a theoretical extension thereof, or as directed by the Engineer. With the exception of Two-Way Blue Retroreflective Markers located adjacent to all fire hydrants within the project limits, the Contractor will not be required to place pavement markers on roads that are not striped.

Prior to the application of slurry seal or AC overlay, the Contractor shall remove all existing raised Pavement Markers within the project area.

Upon completion of the application of slurry seal or AC overlay, the Contractor shall install new Pavement Markers in accordance with California Department of Transportation Standard Plans A20 A-D and this Contract. The Contractor shall install Two-Way Blue Retroreflective markers at each fire hydrant, within the project limits, in accordance with the City of San Diego Standard Drawing number SDW-104 or as directed by the Engineer. These standards may require the installation of additional markers that were not pre-existing.

Markers shall not be placed in the following locations, unless otherwise directed by the Engineer:

1. On raised medians.
2. Adjacent to raised medians, which are not supplemented by left-edge striping.
3. Adjacent to right-edge striping.

Placement of all required pavement markers shall be completed within 15 calendar days after application of slurry seal or AC overlay on each road segment. In the event pavement markers are not applied within the time restraints specified in this contract, the City may suspend or cease sealing operations until such time all required pavement markers have been placed to the satisfaction of the Resident Engineer.

PLACEMENT OF TEMPORARY MARKERS

Upon completion of the application of the slurry or AC overlay, the Contractor shall establish the alignment and installation of temporary pavement markers. The placement of the temporary markers shall be an accurate representation of the striping and markings that existed prior to the application of slurry seal or AC overlay.

The temporary pavement markers shall be in place prior to allowing vehicles to resume the use of the travel way.

Temporary pavement markers shall be used for traffic stripes (traffic lines), edge lanes as defined herein, on the striped edge of the lanes at gore areas that separate traffic at exit and entrance ramps, and on pavement markings.

Traffic stripes (traffic lines) are defined as longitudinal centerlines and lane lines which separate traffic lanes in the same or opposing direction of travel. Reflective temporary pavement markers shall be used on traffic stripes. Non-reflective temporary pavement markers shall be used on longitudinal edge lines that mark the edge of the traveled way.

Pavement markings are defined as transverse markings which include, but are not limited to, word and symbol markings, limit lines (stop lines), crosswalk lines, shoulder markings, parking stall markings, railroad crossing markings, speed bump and lump markings, and bike lane symbols.

The markers shall be installed in accordance with the manufacturer's installation procedure instructions. Temporary pavement markers shall be maintained in place and clearly visible from both directions of traffic, until final traffic striping and pavement marking has been completed on each road segment. Upon completion of striping and marking of each road segment, any remaining temporary markers, located outside of a painted area or pavement marking, shall be removed by the Contractor without damage to the slurry seal or AC overlay.

Nothing in these specifications shall be construed as reducing the minimum standards specified in Part 6, "Temporary Traffic Control" of the "California Manual on Uniform Traffic Control Devices" 2012 Edition, or as relieving the Contractor of responsibility as provided in Section 7-1.04, "Public Safety", of the CalTrans Standard Specifications.




85-1.04 PAYMENT ADD the following:

All work, materials, labor, costs, and time associated with removal and replacement of pavement markers shall be included in the lump sum bid item for "Pavement Markers (retroreflective and non-retroreflective)".

All work, materials, labor, costs, and time associated with installation and removal of temporary pavement markers shall be included in the lump sum bid item for "Pavement Markers (retroreflective and non-retroreflective)".

APPENDIX H
CONTINENTAL CROSSWALK MARKINGS LAYOUT AND NOTES

TYPICAL CONTINENTAL CROSSWALK MARKINGS



- LEGEND**
- CONSTRUCTION LINE
 - CURB & GUTTER
 - █ CROSSWALK BAR (24" WIDE)

GENERAL NOTES:



1. ALL MARKED CROSSWALKS SHALL HAVE CONTINENTAL MARKINGS UNLESS APPROVED OTHERWISE.
2. MARKED CROSSWALK LOCATIONS CONSISTING OF BRICK PAVERS OR OTHER DECORATIVE PAVING SHALL BE PROVIDED WITH A LIMIT LINE ONLY.
3. SIGNALIZED INTERSECTIONS SHALL BE PROVIDED WITH A MARKED CROSSWALK ACROSS EACH LEG WHERE PEDESTRIANS ARE PERMITTED TO CROSS.
4. CONTINENTAL CROSSWALK MARKINGS SHALL BE ALIGNED PARALLEL TO THE DIRECTION OF VEHICULAR TRAVEL.
5. LIMIT LINES SHALL BE INSTALLED A MINIMUM OF 4 FEET IN ADVANCE OF MARKED CROSSWALKS FOR THE APPROACH LANES AT ALL CONTROLLED CROSSINGS.
6. MARKED CROSSWALKS SHOULD BE A MINIMUM OF 10 FEET IN WIDTH. PLACEMENT OF CONTINENTAL CROSSWALKS SHALL COMPLY WITH ACCESSIBILITY REGULATIONS PER THE MOST RECENT VERSION OF AMERICANS WITH DISABILITIES ACT (ADA) STANDARDS.
7. THE CROSSWALK BETWEEN A DUAL RAMP CORNER AND A SINGLE RAMP CORNER SHALL BE AT LEAST 10 FEET WIDE AND SATISFY THE MINIMUM OF 2 FEET BEYOND THE FLARE REQUIREMENT FOR THE SINGLE RAMP.
8. CONTINENTAL CROSSWALK BARS SHALL BE UNIFORM WITHIN THE SAME CROSSING. NO PARTIAL BARS SHALL BE INSTALLED.
9. A CROSSWALK BAR SHALL BE CENTERED IN THE CENTER OF THE CROSSING.
10. CROSSWALK MARKINGS SHALL BE CALIFORNIA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (CA-MUTCD) RETROREFLECTIVITY COMPLIANT AND SKID RESISTANT.

SHEET 1 OF 3

REVISION	BY	APPROVED	DATE	CITY OF SAN DIEGO - STANDARD DRAWING	RECOMMENDED BY THE CITY OF SAN DIEGO STANDARDS COMMITTEE
ORIGINAL	JF	L. NAGELVOORT	02/15		<i>CRF</i> COORDINATOR
				CONTINENTAL CROSSWALK MARKINGS LAYOUT AND NOTES	DRAWING NUMBER
					SDM-116



CASE 1 – SINGLE RAMP ORTHOGONAL

CASE 2 – SINGLE RAMP SKEWED



CASE 3 – DUAL RAMP ORTHOGONAL

CASE 4 – DUAL RAMP SKEWED



LEGEND

- CONSTRUCTION LINE
- ===== CURB & GUTTER
- ▬▬▬▬▬ CROSSWALK BAR (24" WIDE)

SHEET 2 OF 3

REVISION	BY	APPROVED	DATE
ORIGINAL	JF	J. NAGELVOORT	02/15

CITY OF SAN DIEGO – STANDARD DRAWING


RECOMMENDED BY THE CITY OF SAN DIEGO
STANDARDS COMMITTEE

C. P. D'Angelo 2/5/2015
COORDINATOR C.E. BE923 DATE


**CONTINENTAL CROSSWALK
MARKINGS LAYOUT AND NOTES**

DRAWING NUMBER **SDM-116**

CASE 5 – DUAL AND SINGLE RAMP ORTHOGONAL



CASE 6 – DUAL AND SINGLE RAMP SKEWED



- LEGEND**
- CONSTRUCTION LINE
 - CURB & GUTTER
 - █ CROSSWALK BAR (24" WIDE)

SHEET 3 OF 3

REVISION	BY	APPROVED	DATE
ORIGINAL	JF	J. NAGELVOORT	02/15

CITY OF SAN DIEGO – STANDARD DRAWING

CONTINENTAL CROSSWALK MARKINGS LAYOUT AND NOTES

RECOMMENDED BY THE CITY OF SAN DIEGO STANDARDS COMMITTEE

C. Aringia 2/5/2015
COORDINATOR FILE: 56823 DATE

DRAWING NUMBER **SDM-116**

ATTACHMENT F
INTENTIONALLY LEFT BLANK

City of San Diego

CITY CONTACT Eleida Felix Yackel Contract Specialist, Email: EFelixYackel@sandiego.gov
Phone No. (619) 533-3449, Fax No. (619) 533-3633

ADDENDUM "A"

FOR

UUP SHERMAN HEIGHTS STREET RESURFACING

BID NO.: K-15-1361-DBB-3
SAP NO. (WBS/IO/CC): B-00829 / B-00714 / B-00851 / B-00705
CLIENT DEPARTMENT: 2116
COUNCIL DISTRICT: 8
PROJECT TYPE: ID / IJ

BID DUE DATE:

**2:00 PM
MAY 12, 2015
CITY OF SAN DIEGO
PUBLIC WORKS CONTRACTS
1010 SECOND AVENUE, 14th FLOOR, MS 614C
SAN DIEGO, CA 92101**

ENGINEER OF WORK

The engineering Specifications and Special Provisions contained herein have been prepared by or under the direction of the following Registered Engineer:



For City Engineer

5/5/15

Date

Seal:



A. CHANGES TO CONTRACT DOCUMENTS

The following changes to the Contract Documents are hereby made effective as though originally issued with the bid package. Bidders are reminded that all previous requirements to this solicitation remain in full force and effect.

B. VOLUME 1

1. To Supplementary Special Provisions Appendices, ADD Appendix I – Sherman Heights Resurfacing Field Data Table, with pages 4 through 6 of this Addendum.

James Nagelvoort, Director
Public Works Department

Dated: *May 5, 2015*
San Diego, California

JN/RWB/Lad

APPENDIX I

SHERMAN HEIGHTS RESURFACING FIELD DATA TABLE

Project Area	Street Name	Cross Street 1	Cross Street 2	Thomas Bro. Sheet No.	Treatment	Street Section Length (FT)	Street Section Width (FT)	Slurry Seal (SQ FT)	Full Width Grind (SQ FT)	6 FT Edge Milling (Linear FT)	AC Overlay (SQ FT)
8F	26th Street	Market St	Island Ave	1289-D3	Fullwidth Overlay	325	40	0	13,000	0	13,000
8F	26th Street	Market St	26th Street	1289-D3	Slurry Seal	60	70	4,200			
8F	26th Street	Island Ave	J Street	1289-D4	Slurry Seal	330	40	13,200	0	0	0
8F	26th Street	J Street	K Street	1289-D4	Slurry Seal	340	40	13,600	0	0	0
8F	26th Street	K Street	L Street	1289-D4	Slurry Seal	330	40	13,200	0	0	0
8F	26th Street	L Street	Imperial Ave	1289-D4	Edge Overlay	330	40	0	0	820	13,200
8F	26th Street	Imperial Ave	Commercial Ave	1289-D4	Fullwidth Overlay	335	40	0	13,400	0	13,400
8F	27th Street	Imperial Ave	Commercial Street	1289-D4	Fullwidth Overlay	330	25	0	8,250	0	8,250
8F	25th Street	Island Ave	J Street	1289-D4	Slurry Seal	380	60	22,800	0	0	0
8F	25th Street	J Street	K Street	1289-D4	Slurry Seal	385	60	23,100	0	0	0
8F	25th Street	K Street	L Street	1289-D4	Slurry Seal	385	60	23,100	0	0	0
8F	25th Street	L Street	Imperial Ave	1289-D4	Slurry Seal	325	60	19,500	0	0	0
8F	25th Street	Imperial Ave	Commercial Street	1289-D4	Slurry Seal	325	70	22,750	0	0	0
8F	22nd Street	Imperial Ave	Commercial Street	1289-C4	Edge Overlay	315	50	0	0	830	15,750
8F	J Street	26th Street	27th Street	1289-D4	Fullwidth Overlay	750	36		27,000		27,000
8F	K Street	24th Street	25th Street	1289-D4	Fullwidth Overlay	625	55	0	34,375	0	34,375
8F	K Street	25th Street	26th Street	1289-D4	Fullwidth Overlay	640	50	0	32,000	0	32,000
8F	K Street	26th Street	27th Street	1289-D4	Fullwidth Overlay	650	50	0	32,500	0	32,500
8F	L Street	24th Street	25th Street	1289-D4	Fullwidth Overlay	630	50	0	31,500	0	31,500
8F	L Street	25th Street	26th Street	1289-D4	Fullwidth Overlay	635	50	0	31,750	0	31,750
8F	L Street	26th Street	27th Street	1289-D4	Fullwidth Overlay	660	50	0	33,000	0	33,000
8F	Imperial Ave	21th Street	22nd Street	1289-C4	Fullwidth Overlay	280	52	0	14,560	0	14,560
8F	Imperial Ave	22nd Street	24th Street	1289-C4	Fullwidth Overlay	477	52	0	24,804	0	24,804
8F	Imperial Ave	24th Street	25th Street	1289-D4	Fullwidth Overlay	680	52	0	35,360	0	35,360
8F	Imperial Ave	27th Street	Intersection Imperial	1289-D4	Fullwidth Overlay	30	57		1,710		1,710
8F	Commercial St	22nd Street	24th Street	1289-C4	Slurry Seal	610	25	15,250	0	0	0
8G	19th Street	G Street	Market St	1289-C3	Slurry Seal	330	30	9,900	0	0	0
8G	19th Street	Market St	Island Ave	1289-C3	Fullwidth Overlay	320	50	0	16,000	0	16,000
8G	19th Street	Island Ave	J Street	1289-C4	Fullwidth Overlay	325	50	0	16,250	0	16,250
8G	19th Street	J Street	K Street	1289-C4	Fullwidth Overlay	400	55	0	22,000	0	22,000
8G	19th Street	K Street	L Street	1289-C4	Fullwidth Overlay	375	50	0	18,750	0	18,750
8G	19th Street	L Street	Imperial Ave	1289-C4	Fullwidth Overlay	330	50	0	16,500	0	16,500
8G	19th Street	Imperial Ave	Commercial Street	1289-C4	Fullwidth Overlay	310	50	0	15,500	0	15,500
8G	20th Street	G Street	Market St	1289-C3	Fullwidth Overlay	340	55	0	18,700	0	18,700
8G	20th Street	Market St	Island Ave	1289-C3	Slurry Seal	325	55	17,875	0	0	0
8G	21th Street	G Street	Market St	1289-C3	Fullwidth Overlay	350	50	0	17,500	0	17,500
8G	22nd Street	G Street	Market St	1289-C3	Fullwidth Overlay	350	50	0	17,500	0	17,500
8G	22nd Street	Market St	Island Ave	1289-C3	Fullwidth Overlay	335	50	0	16,750	0	16,750
8G	22nd Street	Island Ave	J Street	1289-C4	Slurry Seal	380	50	19,000	0	0	0
8G	22nd Street	J Street	K Street	1289-C4	Slurry Seal	330	50	16,500	0	0	0
8G	22nd Street	K Street	L Street	1289-C4	Fullwidth Overlay	325	50	0	16,250	0	16,250
8G	22nd Street	L Street	Imperial Ave	1289-C4	Fullwidth Overlay	325	50	0	16,250	0	16,250
8G	G Street	19th Street	20th Street	1289-C3	Slurry Seal	300	45	13,500	0	0	0
8G	G Street	20th Street	21th Street	1289-C3	Slurry Seal	300	45	13,500	0	0	0
8G	G Street	21th Street	22nd Street	1289-C3	Slurry Seal	300	45	13,500	0	0	0
8G	G Street	22nd Street	24th Street	1289-C3	Slurry Seal	470	50	23,500	0	0	0
8G	G Street	24th Street	East Terminus Boundary	1289-C3	Slurry Seal	110	50	5,500	0	0	0
8G	Market St	21th Street	20th Street	1289-C3	Fullwidth Overlay	290	70	0	20,300	0	20,300
8G	Market St	20th Street	19th Street	1289-C3	Fullwidth Overlay	290	70	0	20,300	0	20,300
8G	Market St	19th Street	Bridge Concrete	1289-C3	Fullwidth Overlay	147	70		10,290	0	10,290

8G	Market St	22nd Street	24th Street	1289-C3	Fullwidth Overlay	450	70		31,500	0	31,500
8G	Island Ave	19th Street	20th Street	1289-C4	Slurry Seal	290	50	14,500	0	0	0
8G	Island Ave	24th Street	East Terminus Boundary	1289-D4	Fullwidth Overlay	70	50	0	3,500	0	3,500
8G	J Street	90' West of 19th St	19th Street	1289-C4	Fullwidth Overlay	160	50	0	8,000	0	8,000
8G	J Street	19th Street	20th Street	1289-C4	Slurry Seal	285	50	14,250	0	0	0
8G	J Street	20th Street	21th Street	1289-C4	Slurry Seal	280	50	14,000	0	0	0
8G	J Street	21th Street	22nd Street	1289-C4	Slurry Seal	230	50	11,500	0	0	0
8G	L Street	19th Street	20th Street	1289-C4	Fullwidth Overlay	225	50	0	11,250	0	11,250
8G	L Street	20th Street	21th Street	1289-C4	Fullwidth Overlay	230	50	0	11,500	0	11,500
8G	L Street	21th Street	22nd Street	1289-C4	Fullwidth Overlay	230	50	0	11,500	0	11,500
8G	L Street	22nd Street	24th Street	1289-C4	Fullwidth Overlay	485	50	0	24,250	0	24,250
Island Ave PH 1	Island Ave	15th Street	16th Street	1289-C4	Slurry Seal	285	50	14,250	0	0	0
Island Ave PH 1	Island Ave	16th Street	17th Street	1289-C4	Slurry Seal	285	50	14,250	0	0	0
Island Ave PH 1	Island Ave	17th Street	19th Street	1289-C4/C3	Slurry Seal	300	50	15,000	0	0	0
Island Ave PH 1	Island Ave	16th & Island	Intersection	1289-C4	Full Width Overlay	55	55		3,025		3,025
Island Ave PH 2	Island Ave	28th Street	29th Street	1289-E3	Slurry Seal	600	40	20,500	0	0	0
Island Ave PH 2	Island Ave	29th Street	Dodson Street	1289-E3	Slurry Seal	295	40	11,800	0	0	0
Island Ave PH 2	Island Ave	Dodson Street	30th Street	1289-E3	Slurry Seal	285	40	11,400	0	0	0
Island Ave PH 2	Island Ave	30th Street	East Terminus Boundary, 210 ft	1289-E3	Fullwidth Overlay	210	40	0	8,400	0	8,400
Island Ave PH 2	28th Street	Island Ave	South Terminus Boundary, 50 ft	1289-E4	Slurry Seal	65	50	3,250	0	0	0
Island Ave PH 2	Hoitt St	Island Ave	South Terminus Boundary, 50 ft	1289-E4	Slurry Seal	65	40	2,600	0	0	0
K Street PH 1	K Street	19th Street	20th Street	1289-C4	Slurry Seal	280	50	14,000	0	0	0
K Street PH 1	K Street	20th Street	21th Street	1289-C4	Fullwidth Overlay	280	50	0	14,000	0	14,000
K Street PH 1	K Street	21th Street	22nd Street	1289-C4	Fullwidth Overlay	285	50	0	14,250	0	14,250
K Street PH 1	K Street	22nd Street	24th Street	1289-C4	Fullwidth Overlay	435	50	0	21,750	0	21,750
K Street PH 2	K Street	27th Street	Langley Street	1289-D4	Slurry Seal	380	50	19,000	0	0	0
K Street PH 2	K Street	Langley Street	28th Street	1289-D4	Slurry Seal	325	50	16,250	0	0	0
K Street PH 2	K Street	28th Street	Hoitt Street	1289-E4	Slurry Seal	275	50	13,750	0	0	0
K Street PH 2	K Street	Hoitt Street	Dodson Street	1289-E4	Slurry Seal	565	50	28,250	0	0	0
K Street PH 2	K Street	Dodson Street	30th Street	1289-E4	Slurry Seal	455	50	22,750	0	0	0

DIR ✓
License # ✓
MC

City of San Diego

CONTRACTOR'S NAME: SPM Contracting & Paving
ADDRESS: 7192 Mission Gorge Road, San Diego, CA 92120
TELEPHONE NO.: (619) 215-0955 FAX NO.: (619) 583-3147
CITY CONTACT: Eleida Felix Yackel Contract Specialist, Email: EFelixYackel@sandiego.gov
Phone No. (619) 533-3449, Fax No. (619) 533-3633
DZhang/RWBustamante/egz

CONTRACT DOCUMENTS



FOR

UUP SHERMAN HEIGHTS STREET RESURFACING

VOLUME 2 OF 2

BID NO.: K-15-1361-DBB-3
SAP NO. (WBS/IO/CC): B-00829 / B-00714 / B-00851 / B-00705
CLIENT DEPARTMENT: 2116
COUNCIL DISTRICT: 8
PROJECT TYPE: ID / IJ

THIS CONTRACT IS SUBJECT TO THE FOLLOWING:

- THE CITY'S SUBCONTRACTING PARTICIPATION REQUIREMENTS FOR SLBE PROGRAM.
- PREVAILING WAGE RATES: STATE FEDERAL
- APPRENTICESHIP

**THIS BIDDING DOCUMENT TO BE SUBMITTED IN ITS ENTIRETY
REFER TO VOLUME 1 COVER PAGE FOR TIME, DATE, AND LOCATION**

TABLE OF CONTENTS

DESCRIPTION

PAGE NUMBER

Volume 2 - Bidding Documents

The following forms must be completed in their entirety and submitted with the Bid. Include the form(s) even if the information does not apply. Where the information does not apply write in N/A. Failure to include any of the forms may cause the Bid to be deemed **non-responsive**. If you are uncertain or have any questions about any required information, contact the City no later than 14 days prior to Bid due date.

1. Bid/Proposal.....	3
2. Bid Bond.....	6
3. Non-Collusion Affidavit to be executed by Bidder and Submitted with Bid under 23 USC 112 and PCC 7106	7
4. Contractors Certification of Pending Actions.....	8
5. Equal Benefits Ordinance Certification of Compliance.....	9
6. Proposal (Bid).....	10
7. Form AA35 - List of Subcontractors	14
8. Form AA40 - Named Equipment/Material Supplier List	15

BIDDING DOCUMENTS

PROPOSAL

Bidder's General Information

To the City of San Diego:

Pursuant to "Notice Inviting Bids", specifications, and requirements on file with the City Clerk, and subject to all provisions of the Charter and Ordinances of the City of San Diego and applicable laws and regulations of the United States and the State of California, the undersigned hereby proposes to furnish to the City of San Diego, complete at the prices stated herein, the items or services hereinafter mentioned. The undersigned further warrants that this bid is not made in the interest of, or on behalf of, any undisclosed person, partnership, company, association, organization, or corporation; that the bid is genuine and not collusive or sham; that the bidder has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid, and has not directly or indirectly colluded, conspired, connived, or agreed with any bidder or anyone else to put in a sham bid, or that anyone shall refrain from bidding; that the bidder has not in any manner, directly or indirectly, sought by agreement, communication, or conference with anyone to fix the bid price of the bidder or any other bidder, or to fix any overhead, profit, or cost element of the bid price, or of that of any other bidder, or to secure any advantage against the public body awarding the contract of anyone interested in the proposed contract; that all statements contained in the bid are true; and, further, that the bidder has not, directly or indirectly, submitted his or her bid price or any breakdown thereof, or the contents thereof, or divulged information or data relative thereto, or paid, and will not pay, any fee to any corporation, partnership, company, association, organization, bid depository, or to any member or agent thereof to effectuate a collusive or sham bid.

The undersigned bidder(s) further warrants that bidder(s) has thoroughly examined and understands the entire Contract Documents (plans and specifications) and the Bidding Documents therefore, and that by submitting said Bidding Documents as its bid proposal, bidder(s) acknowledges and is bound by the entire Contract Documents, including any addenda issued thereto, as such Contract Documents incorporated by reference in the Bidding Documents.

IF A SOLE OWNER OR SOLE CONTRACTOR SIGN HERE:

- (1) Name under which business is conducted _____
- (2) Signature (Given and surname) of proprietor _____
- (3) Place of Business (Street & Number) _____
- (4) City and State _____ Zip Code _____
- (5) Telephone No. _____ Facsimile No. _____
- (6) Email Address _____

IF A PARTNERSHIP, SIGN HERE:

- (1) Name under which business is conducted Superior Ready mix Concrete, LP, dba
SEM Contracting & Paving


BIDDING DOCUMENTS

(2) Name of each member of partnership, indicate character of each partner, general or special (limited): *see attached sheet

J. Brower Investments, Inc - General Partner

JBCHC Limited Partnership - Limited Partner

(3) Signature (Note: Signature must be made by a general partner)



Full Name and Character of partner

Arnold Veldkamp

Secretary

(4) Place of Business (Street & Number) 7192 Mission Gorge Road

(5) City and State San Diego, CA Zip Code 92120

(6) Telephone No. (619) 265-0955 Facsimile No. (619) 583-3147

(7) Email Address bautler@semcp.com

IF A CORPORATION, SIGN HERE:

(1) Name under which business is conducted _____

(2) Signature, with official title of officer authorized to sign for the corporation:

(Signature)

(Printed Name)

(Title of Officer)

(Impress Corporate Seal Here)

(3) Incorporated under the laws of the State of _____

(4) Place of Business (Street & Number) _____

(5) City and State _____ Zip Code _____

(6) Telephone No. _____ Facsimile No. _____

(7) Email Address _____

SUPERIOR READY MIX CONCRETE, L. P.
DBA ~ SRM CONTRACTING & PAVING
A California Limited Partnership
1508 W. Mission Road
Escondido, CA 92029

General Partner:

J. BROUWER INVESTMENTS, INC., A California Corporation
Jacob Brouwer, President
Garret Brouwer, Vice President
Arnold Veldkamp, Secretary
Brent Cooper, V. P.
Address: 1508 W. Mission Road, Escondido, CA 92029

Limited Partner:

JBCHC LIMITED PARTNERSHIP, A California Limited Partnership
Jacob Brouwer, General Partner
Address: 1508 W. Mission Road, Escondido, CA 92029

BIDDING DOCUMENTS

THE FOLLOWING SECTIONS MUST BE FILLED IN BY ALL PROPOSERS:

In accordance with the "NOTICE INVITING BIDS", the bidder holds a California State Contractor's license for the following classification(s) to perform the work described in these specifications:

LICENSE CLASSIFICATION A

LICENSE NO. 626277 EXPIRES August 31, 2015

DEPARTMENT OF INDUSTRIAL RELATIONS (DIR) REGISTRATION NUMBER 1000003711

This license classification must also be shown on the front of the bid envelope. Failure to show license classification on the bid envelope may cause return of the bid unopened.

TAX IDENTIFICATION NUMBER (TIN): [REDACTED]

Email Address: bbutler@srmcp.com

THIS PROPOSAL MUST BE NOTARIZED BELOW:

I certify, under penalty of perjury, that the representations made herein regarding my State Contractor's license number, classification and expiration date are true and correct.

Signature *Arnold Velakamp* Title Secretary
Arnold Velakamp

SUBSCRIBED AND SWORN TO BEFORE ME, THIS 7th DAY OF May, 2015.

Notary Public in and for the County of San Diego, State of California

Michelle M. Stubbs

(NOTARIAL SEAL)



BIDDING DOCUMENTS

BID BOND

KNOW ALL MEN BY THESE PRESENTS,

That Superior Ready Mix Concrete L.P. dba SRM Contracting & Paving as Principal, and Nationwide Mutual Insurance Company as Surety, are held and firmly bound unto The City of San Diego hereinafter called "OWNER," in the sum of **10% OF THE TOTAL BID AMOUNT** for the payment of which sum, well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors, and assigns, jointly and severally, firmly by these presents.

WHEREAS, said Principal has submitted a Bid to said OWNER to perform the WORK required under the bidding schedule(s) of the OWNER's Contract Documents entitled

UPP Sherman Heights Street Resurfacing - Bid K-15-1361-DBB-3

NOW THEREFORE, if said Principal is awarded a contract by said OWNER and, within the time and in the manner required in the "Notice Inviting Bids" enters into a written Agreement on the form of agreement bound with said Contract Documents, furnishes the required certificates of insurance, and furnishes the required Performance Bond and Payment Bond, then this obligation shall be null and void, otherwise it shall remain in full force and effect. In the event suit is brought upon this bond by said OWNER and OWNER prevails, said Surety shall pay all costs incurred by said OWNER in such suit, including a reasonable attorney's fee to be fixed by the court.

SIGNED AND SEALED, this 21st day of April, 2015

Superior Ready Mix Concrete L.P. dba SRM Contracting & Paving (SEAL)
(Principal)

Nationwide Mutual Insurance Company (SEAL)
(Surety)

By: [Signature]
(Signature)

By: [Signature]
(Signature)
Keith E. Clements, Attorney-In-Fact

(SEAL AND NOTARIAL ACKNOWLEDGEMENT OF SURETY)

ACKNOWLEDGMENT


A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

State of California
County of San Diego

On April 21, 2015 before me, Michele M. Stubbs, Notary Public, personally appeared Arnold Veldkamp, who proved to me on the basis of satisfactory evidence to be the person whose name is subscribed to the within instrument and acknowledged to me that he executed the same in his authorized capacity, and that by his signature on the instrument the person, or the entity upon behalf of which the person acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.



Michele M. Stubbs

Power of Attorney

KNOW ALL MEN BY THESE PRESENTS THAT:

Nationwide Mutual Insurance Company, an Ohio corporation
Farmland Mutual Insurance Company, an Iowa corporation
Nationwide Agribusiness Insurance Company, an Iowa corporation

AMCO Insurance Company, an Iowa corporation
Allied Property and Casualty Insurance Company, an Iowa corporation
Depositors Insurance Company, an Iowa corporation

hereinafter referred to severally as the "Company" and collectively as the "Companies," each does hereby make, constitute and appoint:

Keith E. Clements, La Mesa, CA

each in their individual capacity, its true and lawful attorney-in-fact, with full power and authority to sign, seal, and execute on its behalf any and all bonds and undertakings, and other obligatory instruments of similar nature, in penalties not exceeding the sum of

Four Million Dollars and NO/100

\$4,000,000.00

and to bind the Company thereby, as fully and to the same extent as if such instruments were signed by the duly authorized officers of the Company; and all acts of said Attorney pursuant to the authority given are hereby ratified and confirmed.

This power of attorney is made and executed pursuant to and by authority of the following resolution duly adopted by the board of directors of the Company:

"RESOLVED, that the president, or any vice president be, and each hereby is, authorized and empowered to appoint attorneys-in-fact of the Company, and to authorize them to execute and deliver on behalf of the Company any and all bonds, forms, applications, memorandums, undertakings, recognizances, transfers, contracts of indemnity, policies, contracts guaranteeing the fidelity of persons holding positions of public or private trust, and other writings obligatory in nature that the business of the Company may require; and to modify or revoke, with or without cause, any such appointment or authority; provided, however, that the authority granted hereby shall in no way limit the authority of other duly authorized agents to sign and countersign any of said documents on behalf of the Company."

"RESOLVED FURTHER, that such attorneys-in-fact shall have full power and authority to execute and deliver any and all such documents and to bind the Company subject to the terms and limitations of the power of attorney issued to them, and to affix the seal of the Company thereto; provided, however, that said seal shall not be necessary for the validity of any such documents."

This power of attorney is signed and sealed under and by the following bylaws duly adopted by the board of directors of the Company.

Execution of Instruments. Any vice president, any assistant secretary or any assistant treasurer shall have the power and authority to sign or attest all approved documents, instruments, contracts, or other papers in connection with the operation of the business of the company in addition to the chairman of the board, the chief executive officer, president, treasurer or secretary; provided, however, the signature of any of them may be printed, engraved, or stamped on any approved document, contract, instrument, or other papers of the Company.

IN WITNESS WHEREOF, the Company has caused this instrument to be sealed and duly attested by the signature of its officer the 13th day of February, 2014.



Terrance Williams, President and Chief Operating Officer of Nationwide Agribusiness Insurance Company and Farmland Mutual Insurance Company; and **Vice President** of Nationwide Mutual Insurance Company, AMCO Insurance Company, Allied Property and Casualty Insurance Company, and Depositors Insurance Company

ACKNOWLEDGMENT

STATE OF IOWA, COUNTY OF POLK: ss

On this 13th day of February, 2014, before me came the above-named officer for the Companies aforesaid, to me personally known to be the officer described in and who executed the preceding instrument, and he acknowledged the execution of the same, and being by me duly sworn, deposes and says, that he is the officer of the Companies aforesaid, that the seals affixed hereto are the corporate seals of said Companies, and the said corporate seals and his signature were duly affixed and subscribed to said instrument by the authority and direction of said Companies.

Sandy Alitz
Notarial Seal - Iowa
Commission Number 152785
My Commission Expires March, 24, 2017

Notary Public
My Commission Expires
March 24, 2017

CERTIFICATE

I, Robert W Horner III, Secretary of the Companies, do hereby certify that the foregoing is a full, true and correct copy of the original power of attorney issued by the Company; that the resolution included therein is a true and correct transcript from the minutes of the meetings of the boards of directors and the same has not been revoked or amended in any manner; that said Terrance Williams was on the date of the execution of the foregoing power of attorney the duly elected officer of the Companies, and the corporate seals and his signature as officer were duly affixed and subscribed to the said instrument by the authority of said board of directors; and the foregoing power of attorney is still in full force and effect.

IN WITNESS WHEREOF, I have hereunto subscribed my name as Secretary, and affixed the corporate seals of said Companies this 21st day of April, 2015.

Secretary

This Power of Attorney Expires March 24, 2017


A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

ACKNOWLEDGMENT

State of California
County of San Diego

On April 21, 2015 before me, Diana Kelly, Notary Public, personally appeared Keith E. Clements who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s) or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.



WITNESS my hand and official seal.

Diana Kelly

BIDDING DOCUMENTS

CONTRACTORS CERTIFICATION OF PENDING ACTIONS

As part of its bid or proposal (Non-Price Proposal in the case of Design-Build contracts), the Bidder shall provide to the City a list of all instances within the past 10 years where a complaint was filed or pending against the Bidder in a legal or administrative proceeding alleging that Bidder discriminated against its employees, subcontractors, vendors or suppliers, and a description of the status or resolution of that complaint, including any remedial action taken.

CHECK ONE BOX ONLY.

- The undersigned certifies that within the past 10 years the Bidder has NOT been the subject of a complaint or pending action in a legal administrative proceeding alleging that Bidder discriminated against its employees, subcontractors, vendors or suppliers.

- The undersigned certifies that within the past 10 years the Bidder has been the subject of a complaint or pending action in a legal administrative proceeding alleging that Bidder discriminated against its employees, subcontractors, vendors or suppliers. A description of the status or resolution of that complaint, including any remedial action taken and the applicable dates is as follows:

DATE OF CLAIM	LOCATION	DESCRIPTION OF CLAIM	LITIGATION (Y/N)	STATUS	RESOLUTION/REMEDIAL ACTION TAKEN

Contractor Name: SJM Contracting & Paving

Certified By Arnold Veldkamp Title Secretary
Name

 Date 5/7/15
Signature

USE ADDITIONAL FORMS AS NECESSARY

BIDDING DOCUMENTS

**EQUAL BENEFITS ORDINANCE
CERTIFICATION OF COMPLIANCE**



For additional information, contact:
CITY OF SAN DIEGO
EQUAL BENEFITS PROGRAM
 202 C Street, MS 9A, San Diego, CA 92101
 Phone (619) 533-3948 Fax (619) 533-3220

COMPANY INFORMATION

Company Name: <u>Sem Contracting Paving</u>	Contact Name: <u>Bill Butler</u>
Company Address: <u>7192 Mission Gorge Road</u>	Contact Phone: <u>(619) 265-0955</u>
<u>San Diego, CA 92120</u>	Contact Email: <u>bbutler@semcp.com</u>

CONTRACT INFORMATION

Contract Title: <u>UUP Sherman Height Street Resurfacing</u>	Start Date:
Contract Number (if no number, state location): <u>K-15-13661-DBB-3</u>	End Date:

SUMMARY OF EQUAL BENEFITS ORDINANCE REQUIREMENTS

The Equal Benefits Ordinance [EBO] requires the City to enter into contracts only with contractors who certify they will provide and maintain equal benefits as defined in SDMC §22.4302 for the duration of the contract. To comply:

- Contractor shall offer equal benefits to employees with spouses and employees with domestic partners.
 - Benefits include health, dental, vision insurance; pension/401(k) plans; bereavement, family, parental leave; discounts, child care; travel/relocation expenses; employee assistance programs; credit union membership; or any other benefit.
 - Any benefit not offer an employee with a spouse, is not required to be offered to an employee with a domestic partner.
- Contractor shall post notice of firm's equal benefits policy in the workplace and notify employees at time of hire and during open enrollment periods.
- Contractor shall allow City access to records, when requested, to confirm compliance with EBO requirements.
- Contractor shall submit *EBO Certification of Compliance*, signed under penalty of perjury, prior to award of contract.

NOTE: This summary is provided for convenience. Full text of the EBO and Rules Implementing the EBO are available at www.sandiego.gov/administration.

CONTRACTOR EQUAL BENEFITS ORDINANCE CERTIFICATION

Please indicate your firm's compliance status with the EBO. The City may request supporting documentation.

- I affirm **compliance** with the EBO because my firm (*contractor must select one reason*):
- Provides equal benefits to spouses and domestic partners.
 - Provides no benefits to spouses or domestic partners.
 - Has no employees.
 - Has collective bargaining agreement(s) in place prior to January 1, 2011, that has not been renewed or expired.
- I request the City's approval to pay affected employees a cash equivalent in lieu of equal benefits and verify my firm made a reasonable effort but is not able to provide equal benefits upon contract award. I agree to notify employees of the availability of a cash equivalent for benefits available to spouses but not domestic partners and to continue to make every reasonable effort to extend all available benefits to domestic partners.

It is unlawful for any contractor to knowingly submit any false information to the City regarding equal benefits or cash equivalent associated with the execution, award, amendment, or administration of any contract. [San Diego Municipal Code §22.4307(a)]

Under penalty of perjury under laws of the State of California, I certify the above information is true and correct. I further certify that my firm understands the requirements of the Equal Benefits Ordinance and will provide and maintain equal benefits for the duration of the contract or pay a cash equivalent if authorized by the City.

<u>Arnold Veldkamp / Secretary</u>	<u>[Signature]</u>	<u>5/7/15</u>
Name/Title of Signatory	Signature	Date

FOR OFFICIAL CITY USE ONLY

Receipt Date:	EBO Analyst:	<input type="checkbox"/> Approved <input type="checkbox"/> Not Approved – Reason:
---------------	--------------	---

(Rev 02/15/2011)

BIDDING DOCUMENTS

PROPOSAL (BID)

The Bidder agrees to the construction of **UUP Sherman Heights Street Resurfacing** for the City of San Diego, in accordance with these contract documents for the prices listed below. The Bidder guarantees the Contract Price for a period of 120 days (90 days for federally funded contracts and contracts valued at \$500,000 or less) from the date of Bid opening to Award of the Contract. The duration of the Contract Price guarantee shall be extended by the number of days required for the City to obtain all items necessary to fulfill all conditions precedent e.g., bond and insurance.

Item	Quantity	Unit	NAICS	Payment Reference	Description	Unit Price	Extension
BASE BID							
1	1	LS	524126	2-4.1	Bonds (Payment and Performance)	 	\$ 15,100. ⁰⁰
2	1	LS	237310	7-10.2.6	Traffic Control	 	\$ 21,447. ⁰⁰
3	1	AL		9-3.5	Field Orders - Type II	 	\$150,000.00
4	82	EA	237310	301-1.7	Adjusting Existing Gate Valve Cover to Grade	\$ 60.00	\$ 4,920. ⁰⁰
5	9	EA	237310	301-1.7	Adjusting Water Meter Box to Grade	\$ 144.00	\$ 1,296. ⁰⁰
6	4	EA	237310	301-1.7	Adjusting Electrical/Utility Box to Grade	\$ 144.00	\$ 576. ⁰⁰
7	30	EA	237310	301-1.7	Adjusting Existing Manhole Frame & Cover to Grade	\$ 172.00	\$ 5,160. ⁰⁰
8	1,650	LF	237310	302-1.12	Cold Milling - 6' Edge	\$ 1.85	\$ 3,052. ⁵⁰
9	751,949	SF	237310	302-1.12	Full Width Grinding - 1.5" Cold Milling	\$ 0.24	\$ 180,467. ⁷⁶
10	564,775	SF	237310	302-4.12.4	Rubber Polymer Modified Slurry Type II	\$ 0.21	\$ 118,602. ⁷⁵
11	35	EA	238210	302-1.12	Replace Type E Traffic Signal Loops	\$ 403.00	\$ 14,105. ⁰⁰
12	16	EA	238210	302-1.12	Replace Type E Modified or Q Traffic Signal Loops	\$ 403.00	\$ 6,448. ⁰⁰
13	6	EA	238210	302-1.12	Replace Traffic Loop Conduit Stub	\$ 477.00	\$ 2,862. ⁰⁰
14	400	TONS	237310	302-3.2	Base Repair	\$ 138.00	\$ 55,200. ⁰⁰
15	1,000	TONS	237310	302-3.2	Asphalt Pavement Repair (Mill & Pave)	\$ 138.00	\$ 138,000. ⁰⁰
16	6,986	TONS	237310	302-5.9	1.5 Inch Asphalt Concrete Overlay	\$ 69.85	\$ 487,972. ¹⁰

BIDDING DOCUMENTS

Item	Quantity	Unit	NAICS	Payment Reference	Description	Unit Price	Extension
17	3,611	SY	237310	302-7.4	Non-Woven Fiberglass/Polyester Interlayer Paving Mat	\$ 2.60	\$ 9,388. ⁶⁰
18	49	EA	237310	303-5.9	Contractor Date Stamp and Impressions	\$ 185.50	\$ 9,089. ⁵⁰
19	930	LF	237310	303-5.9	Type G Curb & Gutter Replacement	\$ 37.10	\$ 34,503. ¹⁰
20	500	SF	237310	303-5.9	Cross Gutter Replacement	\$ 15.40	\$ 7,700. ⁰⁰
21	5,130	SF	237310	303-5.9	Remove and Replace Existing Sidewalk	\$ 9.00	\$ 46,170. ⁰⁰
22	400	SF	237310	303-5.9	Remove and Replace Alley Apron	\$ 15.37	\$ 6,148. ⁰⁰
23	42	EA	237310	303-5.10.2	Curb Ramp Type A with Stainless Steel Detectable Warning Tiles	\$ 2,544. ⁰⁰	\$ 106,848. ⁰⁰
24	14	EA	237310	303-5.10.2	Curb Ramp Type B with Stainless Steel Detectable Warning Tiles	\$ 2,544. ⁰⁰	\$ 35,616. ⁰⁰
25	3	EA	237310	303-5.10.2	Curb Ramp Type C1 with Stainless Steel Detectable Warning Tiles	\$ 2,544. ⁰⁰	\$ 7,632. ⁰⁰
26	8	EA	237310	303-5.10.2	Curb Ramp Type C2 with Stainless Steel Detectable Warning Tiles	\$ 2,544. ⁰⁰	\$ 20,352. ⁰⁰
27	58	EA	237310	303-5.10.2	Curb Ramp Type D with Stainless Steel Detectable Warning Tiles	\$ 2,279. ⁰⁰	\$ 132,182. ⁰⁰
28	17	EA	237310	303-5.10.2	Curb Ramp Case B with Stainless Steel Detectable Warning Tiles	\$ 2,544. ⁰⁰	\$ 43,248. ⁰⁰
29	11,296	LB	237310	302-14.5	Crack Seal	\$ 2.61	\$ 29,482. ⁵⁶
30	8	EA	238210	307-2	Furnish & Install Pedestrian Push Button Pole and Foundation	\$ 1,166. ⁰⁰	\$ 9,328. ⁰⁰
31	8	EA	238210	307-2	ADA Pedestrian Push Button Assembly Type B with Push Button Sign	\$ 265. ⁰⁰	\$ 2,120. ⁰⁰
32	8	EA	238210	307-2	Pull Box	\$ 371. ⁰⁰	\$ 2,968. ⁰⁰
33	200	LF	238210	307-2	2" PVC Conduit	\$ 17.00	\$ 3,400. ⁰⁰
34	1	EA	237310	307-2	Pedestrian Barricade	\$ 371.00	\$ 371. ⁰⁰
35	1	EA	237310	307-2	Remove and Install Sign	\$ 212.00	\$ 212. ⁰⁰
36	19	EA	541370	309-4	Survey Monuments	\$ 90.00	\$ 1,710. ⁰⁰
37	1	LS	237310	84-3.04 (APP. G)	Painted Traffic Striping	X	\$ 7,431. ⁰⁰

BIDDING DOCUMENTS

Item	Quantity	Unit	NAICS	Payment Reference	Description	Unit Price	Extension
38	1	LS	237310	84-2.04 (APP. G)	Thermoplastic Pavement Markings	XXXXXX	\$ 46,174. ⁰⁰
39	1	LS	237310	85-1.04 (APP. G)	Pavement Markers (Retroreflective and Non-retroreflective)	XXXXXX	\$ 2,698. ²³
40	1	LS	541330	701-13.9.5	Water Pollution Control Program Development	XXXXXX	\$ 514. ⁰⁰
41	1	LS	237310	701-13.9.5	Water Pollution Control Program Implementation	XXXXXX	\$ 2,705. ⁰⁰
ESTIMATED TOTAL BASE BID:							\$ 1,773,200. ⁰⁰

MC

TOTAL BID PRICE FOR BID (Items 1 through 41, inclusive) amount written in words: one million, seven hundred, seventy three thousand and two hundred dollars

The Bid shall contain an acknowledgment of receipt of all addenda, the numbers of which shall be filled in on the Bid form. If an addendum or addenda has been issued by the City and not noted as being received by the Bidder, this proposal shall be rejected as being **non-responsive**. The following addenda have been received and are acknowledged in this bid: A,


The names of all persons interested in the foregoing proposal as principals are as follows:

J. Brower Investments, Inc.
JBCE Limited Partnership

IMPORTANT NOTICE: If Bidder or other interested person is a corporation, state secretary, treasurer, and manager thereof; if a co-partnership, state true name of firm, also names of all individual co-partners composing firm; if Bidder or other interested person is an individual, state first and last names in full.

Bidder: Superior Ready mix Concrete, LP, dba SKM Contracting & Paving
 Title: Secretary

BIDDING DOCUMENTS

Business Address: 7192 mission Gorge Road. San Diego CA. 92120
Place of Business: 7192 mission Gorge Road. San Diego CA. 92120
Place of Residence: _____
Signature: 

NOTES:

- A. The City shall determine the low Bid based on the Base Bid alone.
- B. Prices and notations shall be in ink or typewritten. All corrections (which have been initiated by the Bidder using erasures, strike out, line out, or "white-out") shall be typed or written in with ink adjacent thereto, and shall be initialed in ink by the person signing the bid proposal.
- C. Failure to initial all corrections made in the bidding documents may cause the Bid to be rejected as **non-responsive** and ineligible for further consideration.
- D. Blank spaces must be filled in, using figures. Bidder's failure to submit a price for any Bid item that requires the Bidder to submit a price shall render the Bid **non-responsive** and shall be cause for its rejection.
- E. Unit prices shall be entered for all unit price items. Unit prices shall not exceed two (2) decimal places. If the Unit prices entered exceed two (2) decimal places, the City will only use the first two digits after the decimal points without rounding up or down.
- F. All extensions of the unit prices bid will be subject to verification by the City. In the case of inconsistency or conflict between the product of the Quantity x Unit Price and the Extension, the product shall govern.
- G. In the case of inconsistency or conflict, between the sums of the Extensions with the estimated total Bid, the sum of the Extensions shall govern.
- H. Bids shall not contain any recapitulation of the Work. Conditional Bids will be rejected as being **non-responsive**. Alternative proposals will not be considered unless called for.
- I. Subcontractors' License Number must be filled in. Failure to provide the information specified may deem the bidder **non-responsive**.

SUPERIOR READY MIX CONCRETE, L. P.
DBA ~ SRM CONTRACTING & PAVING
A California Limited Partnership
1508 W. Mission Road
Escondido, CA 92029

General Partner:

J. BROUWER INVESTMENTS, INC., A California Corporation
Jacob Brouwer, President
Garret Brouwer, Vice President
Arnold Veldkamp, Secretary
Brent Cooper, V. P.
Address: 1508 W. Mission Road, Escondido, CA 92029

Limited Partner:

JBCHC LIMITED PARTNERSHIP, A California Limited Partnership
Jacob Brouwer, General Partner
Address: 1508 W. Mission Road, Escondido, CA 92029

BIDDING DOCUMENTS

LIST OF SUBCONTRACTORS

In accordance with the requirements provided in the "Subletting and Subcontracting Fair Practices Act", Division 2, Part 1, Chapter 4 of the Public Contract Code, the Bidder shall list below the name and address of each Subcontractor who will perform work, labor, render services or specially fabricates and installs a portion [type] of the work or improvement, in an amount in excess of 0.5% of the Contractor's total Bid. The Bidder shall also list below the portion of the work which will be done by each subcontractor under this Contract. The Contractor shall list only one Subcontractor for each portion of the Work. The **DOLLAR VALUE** of the total Bid to be performed shall be stated for all subcontractors listed. Failure to comply with this requirement shall result in the Bid being rejected as **non-responsive** and ineligible for award. The Bidder's attention is directed to the Special Provisions - General; Paragraph 2-3 Subcontracts, which stipulates the percent of the Work to be performed with the Bidders' own forces. The Bidder shall list all SLBE, ELBE, DBE, DVBE, MBE, WBE, OBE, SDB, WoSB, HUBZone, and SDVOSB Subcontractors that Bidders are seeking recognition towards achieving any mandatory, voluntary, or both subcontracting participation percentages.

Subcontractors' License Number must be filled in. Failure to provide the information specified may deem the bidder **non-responsive**.

NAME, ADDRESS AND TELEPHONE NUMBER OF SUBCONTRACTOR	CONSTRUCTOR OR DESIGNER	SUBCONTRACTOR LICENSE NUMBER	TYPE OF WORK	DOLLAR VALUE OF SUBCONTRACT (MUST BE FILLED OUT)	MBE, WBE, DBE, DVBE, OBE, ELBE, SLBE, SDB, WoSB, HUBZone, OR SDVOSB	WHERE CERTIFIED	CHECK IF JOINT VENTURE PARTNERSHIP
Name: <u>YBS Concrete Inc</u> Address: <u>821 Kuhn Drive</u> City: <u>Chula Vista</u> State: <u>CA</u> Zip: <u>91941</u> Phone: <u>(619) 271-6122</u> Email:	Constructor	#885270	Concrete Improvements	\$403,930 ⁰⁰	ELBE #11YB319	City of San Diego	
Name: <u>Dyco Specialties Inc</u> Address: <u>128 W. Second Ave</u> City: <u>Chula Vista</u> State: <u>CA</u> Zip: <u>91910</u> Phone: <u>(619) 422-9204</u> Email:	Constructor	#298637	Striping markers Signs @ Pedestrian barricades	\$53,670 ⁰⁰	SLBE #PS110238	City of San Diego	

① As appropriate, Bidder shall identify Subcontractor as one of the following and shall include a valid proof of certification (except for OBE, SLBE and ELBE):

Certified Minority Business Enterprise	MBE	Certified Woman Business Enterprise	WBE
Certified Disadvantaged Business Enterprise	DBE	Certified Disabled Veteran Business Enterprise	DVBE
Other Business Enterprise	OBE	Certified Emerging Local Business Enterprise	ELBE
Certified Small Local Business Enterprise	SLBE	Small Disadvantaged Business	SDB
Woman-Owned Small Business	WoSB	HUBZone Business	HUBZone
Service-Disabled Veteran Owned Small Business	SDVOSB		

② As appropriate, Bidder shall indicate if Subcontractor is certified by:

City of San Diego	CITY	State of California Department of Transportation	CALTRANS
California Public Utilities Commission	CPUC	San Diego Regional Minority Supplier Diversity Council	SRMSDC
State of California's Department of General Services	CADoGS	City of Los Angeles	LA
State of California	CA	U.S. Small Business Administration	SBA

The Bidder will not receive any subcontracting participation percentages if the Bidder fails to submit the required proof of certification.

BIDDING DOCUMENTS

LIST OF SUBCONTRACTORS

In accordance with the requirements provided in the "Subletting and Subcontracting Fair Practices Act", Division 2, Part 1, Chapter 4 of the Public Contract Code, the Bidder shall list below the name and address of each Subcontractor who will perform work, labor, render services or specially fabricates and installs a portion [type] of the work or improvement, in an amount in excess of 0.5% of the Contractor's total Bid. The Bidder shall also list below the portion of the work which will be done by each subcontractor under this Contract. The Contractor shall list only one Subcontractor for each portion of the Work. The **DOLLAR VALUE** of the total Bid to be performed shall be stated for all subcontractors listed. Failure to comply with this requirement shall result in the Bid being rejected as **non-responsive** and ineligible for award. The Bidder's attention is directed to the Special Provisions - General; Paragraph 2-3 Subcontracts, which stipulates the percent of the Work to be performed with the Bidders' own forces. The Bidder shall list all SLBE, ELBE, DBE, DVBE, MBE, WBE, OBE, SDB, WoSB, HUBZone, and SDVOSB Subcontractors that Bidders are seeking recognition towards achieving any mandatory, voluntary, or both subcontracting participation percentages.

Subcontractors' License Number must be filled in. Failure to provide the information specified may deem the bidder **non-responsive**.

NAME, ADDRESS AND TELEPHONE NUMBER OF SUBCONTRACTOR	CONSTRUCTOR OR DESIGNER	SUBCONTRACTOR LICENSE NUMBER	TYPE OF WORK	DOLLAR VALUE OF SUBCONTRACT (MUST BE FILLED OUT)	MBE, WBE, DBE, DVBE, OBE, ELBE, SLBE, SDB, WoSB, HUBZone, OR SDVOSB	WHERE CERTIFIED	CHECK IF JOINT VENTURE PARTNERSHIP
Name: <u>Perry Electric</u> Address: <u>P.O. Box 710130</u> City: <u>San Lee</u> State: <u>CA</u> Zip: <u>92072</u> Phone: <u>(619) 449-0511</u> Email:	Constructor	#747931	Electrical	\$38,880 ⁰⁰	SUBC #117M0131	City of San Diego	
Name: <u>Continental Western transportation</u> Address: <u>P.O. Box 216636</u> City: <u>San Diego</u> State: <u>CA</u> Zip: <u>92106</u> Phone: <u>(619) 218-1151</u> Email:	Constructor	#532967	non-Woven Fiberglass Polyester Reinforced mat	\$8,738 ⁶²	DBE	N/A	

① As appropriate, Bidder shall identify Subcontractor as one of the following and shall include a valid proof of certification (except for OBE, SLBE and ELBE):

Certified Minority Business Enterprise	MBE	Certified Woman Business Enterprise	WBE
Certified Disadvantaged Business Enterprise	DBE	Certified Disabled Veteran Business Enterprise	DVBE
Other Business Enterprise	OBE	Certified Emerging Local Business Enterprise	ELBE
Certified Small Local Business Enterprise	SLBE	Small Disadvantaged Business	SDB
Woman-Owned Small Business	WoSB	HUBZone Business	HUBZone
Service-Disabled Veteran Owned Small Business	SDVOSB		

② As appropriate, Bidder shall indicate if Subcontractor is certified by:

City of San Diego	CITY	State of California Department of Transportation	CALTRANS
California Public Utilities Commission	CPUC	San Diego Regional Minority Supplier Diversity Council	SRMSDC
State of California's Department of General Services	CADoGS	City of Los Angeles	LA
State of California	CA	U.S. Small Business Administration	SBA

The Bidder will not receive any subcontracting participation percentages if the Bidder fails to submit the required proof of certification.

BIDDING DOCUMENTS

LIST OF SUBCONTRACTORS

In accordance with the requirements provided in the "Subletting and Subcontracting Fair Practices Act", Division 2, Part 1, Chapter 4 of the Public Contract Code, the Bidder shall list below the name and address of each Subcontractor who will perform work, labor, render services or specially fabricates and installs a portion [type] of the work or improvement, in an amount in excess of 0.5% of the Contractor's total Bid. The Bidder shall also list below the portion of the work which will be done by each subcontractor under this Contract. The Contractor shall list only one Subcontractor for each portion of the Work. The **DOLLAR VALUE** of the total Bid to be performed shall be stated for all subcontractors listed. Failure to comply with this requirement shall result in the Bid being rejected as **non-responsive** and ineligible for award. The Bidder's attention is directed to the Special Provisions - General; Paragraph 2-3 Subcontracts, which stipulates the percent of the Work to be performed with the Bidders' own forces. The Bidder shall list all SLBE, ELBE, DBE, DVBE, MBE, WBE, OBE, SDB, WoSB, HUBZone, and SDVOSB Subcontractors that Bidders are seeking recognition towards achieving any mandatory, voluntary, or both subcontracting participation percentages.

Subcontractors' License Number must be filled in. Failure to provide the information specified may deem the bidder **non-responsive**.

NAME, ADDRESS AND TELEPHONE NUMBER OF SUBCONTRACTOR	CONSTRUCTOR OR DESIGNER	SUBCONTRACTOR LICENSE NUMBER	TYPE OF WORK	DOLLAR VALUE OF SUBCONTRACT (MUST BE FILLED OUT)	MBE, WBE, DBE, DVBE, OBE, ELBE, SLBE, SDB, WoSB, HUBZone, OR SDVOSB	WHERE CERTIFIED	CHECK IF JOINT VENTURE PARTNERSHIP
Name: <u>American Asphalt South Inc</u> Address: <u>P.O. Box 310036</u> City: <u>Fontana</u> State: <u>CA</u> Zip: <u>92331</u> Phone: <u>(909) 427-8276</u> Email:	Constructor	#784969	Slurry Seal Crack Seal	\$137,999 ²⁹	OBE	N/A	
Name: <u>McGrath Consulting</u> Address: <u>P.O. Box 2488</u> City: <u>El Cajon</u> State: <u>CA</u> Zip: <u>92021</u> Phone: <u>(619) 443-3811</u> Email:	Designer	N/A	Water Pollution Control Plan	\$485 ⁰⁰	ELBE #11MH0280	City of San Diego	

① As appropriate, Bidder shall identify Subcontractor as one of the following and shall include a valid proof of certification (except for OBE, SLBE and ELBE):

- | | | | |
|---|--------|--|---------|
| Certified Minority Business Enterprise | MBE | Certified Woman Business Enterprise | WBE |
| Certified Disadvantaged Business Enterprise | DBE | Certified Disabled Veteran Business Enterprise | DVBE |
| Other Business Enterprise | OBE | Certified Emerging Local Business Enterprise | ELBE |
| Certified Small Local Business Enterprise | SLBE | Small Disadvantaged Business | SDB |
| Woman-Owned Small Business | WoSB | HUBZone Business | HUBZone |
| Service-Disabled Veteran Owned Small Business | SDVOSB | | |

0.3657
MC

② As appropriate, Bidder shall indicate if Subcontractor is certified by:

- | | | | |
|--|--------|--|----------|
| City of San Diego | CITY | State of California Department of Transportation | CALTRANS |
| California Public Utilities Commission | CPUC | San Diego Regional Minority Supplier Diversity Council | SRMSDC |
| State of California's Department of General Services | CADoGS | City of Los Angeles | LA |
| State of California | CA | U.S. Small Business Administration | SBA |

The Bidder will not receive any subcontracting participation percentages if the Bidder fails to submit the required proof of certification.

BIDDING DOCUMENTS

LIST OF SUBCONTRACTORS

In accordance with the requirements provided in the "Subletting and Subcontracting Fair Practices Act", Division 2, Part 1, Chapter 4 of the Public Contract Code, the Bidder shall list below the name and address of each Subcontractor who will perform work, labor, render services or specially fabricates and installs a portion [type] of the work or improvement, in an amount in excess of 0.5% of the Contractor's total Bid. The Bidder shall also list below the portion of the work which will be done by each subcontractor under this Contract. The Contractor shall list only one Subcontractor for each portion of the Work. The **DOLLAR VALUE** of the total Bid to be performed shall be stated for all subcontractors listed. Failure to comply with this requirement shall result in the Bid being rejected as **non-responsive** and ineligible for award. The Bidder's attention is directed to the Special Provisions - General; Paragraph 2-3 Subcontracts, which stipulates the percent of the Work to be performed with the Bidders' own forces. The Bidder shall list all SLBE, ELBE, DBE, DVBE, MBE, WBE, OBE, SDB, WoSB, HUBZone, and SDVOSB Subcontractors that Bidders are seeking recognition towards achieving any mandatory, voluntary, or both subcontracting participation percentages.

Subcontractors' License Number must be filled in. Failure to provide the information specified may deem the bidder **non-responsive**.

NAME, ADDRESS AND TELEPHONE NUMBER OF SUBCONTRACTOR	CONSTRUCTOR OR DESIGNER	SUBCONTRACTOR LICENSE NUMBER	TYPE OF WORK	DOLLAR VALUE OF SUBCONTRACT (MUST BE FILLED OUT)	MBE, WBE, DBE, DVBE, OBE, ELBE, SLBE, SDB, WoSB, HUBZone, OR SDVOSB	WHERE CERTIFIED	CHECK IF JOINT VENTURE PARTNERSHIP
Name: _____ Address: _____ City: _____ State: _____ Zip: _____ Phone: _____ Email: _____							
Name: _____ Address: _____ City: _____ State: _____ Zip: _____ Phone: _____ Email: _____							

Ⓢ As appropriate, Bidder shall identify Subcontractor as one of the following and shall include a valid proof of certification (except for OBE, SLBE and ELBE):

Certified Minority Business Enterprise	MBE	Certified Woman Business Enterprise	WBE
Certified Disadvantaged Business Enterprise	DBE	Certified Disabled Veteran Business Enterprise	DVBE
Other Business Enterprise	OBE	Certified Emerging Local Business Enterprise	ELBE
Certified Small Local Business Enterprise	SLBE	Small Disadvantaged Business	SDB
Woman-Owned Small Business	WoSB	HUBZone Business	HUBZone
Service-Disabled Veteran Owned Small Business	SDVOSB		

Ⓣ As appropriate, Bidder shall indicate if Subcontractor is certified by:

City of San Diego	CITY	State of California Department of Transportation	CALTRANS
California Public Utilities Commission	CPUC	San Diego Regional Minority Supplier Diversity Council	SRMSDC
State of California's Department of General Services	CADoGS	City of Los Angeles	LA
State of California	CA	U.S. Small Business Administration	SBA

The Bidder will not receive any subcontracting participation percentages if the Bidder fails to submit the required proof of certification.

BIDDING DOCUMENTS

NAMED EQUIPMENT/MATERIAL SUPPLIER LIST

The Bidder seeking the recognition of equipment, materials, or supplies obtained from Suppliers towards achieving any mandatory, voluntary, or both subcontracting participation percentages shall list the Supplier(s) on the Named Equipment/Material Supplier List. The Named Equipment/Material Supplier List, at a minimum, shall have the name, locations (City) and the DOLLAR VALUE of the Suppliers. The Bidder will be credited up to 60% of the amount to be paid to the Suppliers for such materials and supplies unless vendor manufactures or substantially alters materials and supplies in which case 100% will be credited. The Bidder is to indicate (Yes/No) whether listed firm is a supplier or manufacturer. In calculating the subcontractor participation percentages, vendors/suppliers will receive 60% credit of the listed DOLLAR VALUE, whereas manufacturers will receive 100% credit. If no indication provided, listed firm will be credited at 60% of the listed dollar value for purposes of calculating the Subcontractor Participation Percentage, Suppliers will receive 60% credit of the listed DOLLAR VALUE, whereas manufacturers will receive 100% credit. If no indication provided, listed firm will be credited at 60% of the listed DOLLAR VALUE for purposes of calculating the subcontractor participation percentages.

NAME, ADDRESS AND TELEPHONE NUMBER OF VENDOR/SUPPLIER	MATERIALS OR SUPPLIES	DOLLAR VALUE OF MATERIAL OR SUPPLIES (MUST BE FILLED OUT)	SUPPLIER (Yes/No)	MANUFACTURER (Yes/No)	MBE, WBE, DBE, DVBE, OBE, ELBE, SLBE, SDB, WoSB, HUBZone, OR SDVOSB®	WHERE CERTIFIED®
Name: _____ Address: _____ City: _____ State: _____ Zip: _____ Phone: _____ Email: _____						
Name: _____ Address: _____ City: _____ State: _____ Zip: _____ Phone: _____ Email: _____						

Ⓜ As appropriate, Bidder shall identify Vendor/Supplier as one of the following and shall include a valid proof of certification (except for OBE, SLBE and ELBE):

Certified Minority Business Enterprise	MBE	Certified Woman Business Enterprise	WBE
Certified Disadvantaged Business Enterprise	DBE	Certified Disabled Veteran Business Enterprise	DVBE
Other Business Enterprise	OBE	Certified Emerging Local Business Enterprise	ELBE
Certified Small Local Business Enterprise	SLBE	Small Disadvantaged Business	SDB
Woman-Owned Small Business	WoSB	HUBZone Business	HUBZone
Service-Disabled Veteran Owned Small Business	SDVOSB		

Ⓢ As appropriate, Bidder shall indicate if Vendor/Supplier is certified by:

City of San Diego	CITY	State of California Department of Transportation	CALTRANS
California Public Utilities Commission	CPUC	San Diego Regional Minority Supplier Diversity Council	SRMSDC
State of California's Department of General Services	CADoGS	City of Los Angeles	LA
State of California	CA	U.S. Small Business Administration	SBA

The Bidder will not receive any subcontracting participation percentages if the Bidder fails to submit the required proof of certification.