SECTION 03310 - CAST-IN-PLACE SITEWORK CONCRETE

City of San Diego, CWP Guidelines

PART 1 -- GENERAL

1.1 WORK OF THIS SECTION

- A. The WORK of this Section includes providing finished cast-in-place lean concrete, sitework concrete, minor non-hydraulic concrete structures, air placed concrete, including formwork, steel reinforcement, mixing, placing curing, and repairing, all in conformance with SSPWC.
- B. Sitework concrete includes curbs, gutters, catch basins, sidewalks, pavements, fence and guard post embedment, underground duct bank encasement, and all concrete WORK indicated to be sitework concrete.

1.2 RELATED SECTIONS

- A. The WORK of the following Sections applies to the WORK of this Section. Other Sections of the Specifications, not referenced below, shall also apply to the extent required for proper performance of this WORK.
 - 1. Section 03280 Joints in Sitework Concrete

1.3 STANDARD SPECIFICATIONS

A. Except as otherwise indicated in this Section of the Specifications, the CONTRACTOR shall comply with the Standard Specifications for Public Works Construction (SSPWC), as specified in Section 01090 - REFERENCE STANDARDS.

1.4 SHOP DRAWINGS AND SAMPLES

A. Submittals shall be made in compliance with Section 01300 and in accordance with the requirements of SSPWC, Section 201.

1.5 TESTS

A. Tests on component materials, for the compressive strength of concrete, and for construction tolerances shall be performed in accordance with the requirements of SSPWC, Section 201.

PART 2 -- PRODUCTS

2.1 CONCRETE MATERIALS

A. Concrete component materials, including curing materials and joint materials shall be in accordance with SSPWC, Subsections 201-1, 201-4, and 201-5.

2.2 FORMWORK

A. Concrete formwork shall comply with SSPWC Subsection 204-1.

2.3 STEEL REINFORCEMENT

A. Reinforcing steel shall conform to SSPWC Subsection 201-2.

PART 3 -- EXECUTION

3.1 GENERAL

A. Proportioning and mixing, preparation of surfaces for concreting, handling, transporting and placing concrete, finishing and curing concrete surfaces and related procedures shall be performed in accordance with SSPWC, Subsections 303-1 and 303-5.

3.2 AIR-PLACED CONCRETE

A. Air-placed concrete construction (Gunite and Shotcrete) shall be in accordance with SSPWC, Subsection 303-2 and the applicable provisions of Subsection 303-1.

** END OF SECTION **