



NOTES:

1. CEMENT SLURRY BACKFILL SHALL BE THOROUGHLY CONSOLIDATED, HAVE A MAXIMUM SLUMP OF 4 INCHES, AND MAY CONTAIN 30% MAXIMUM 3/8" ROCK.
2. CONCRETE SHALL BE PLACED AND FINISHED IN ACCORDANCE WITH 306-6. CONCRETE MAY BE PLACED IMMEDIATELY FOLLOWING SLURRY BACKFILL.
3. CONCRETE TRENCH COVER SHALL BE A MINIMUM OF 5 1/2" THICK IN ALLEY OR LOCAL RESIDENTIAL STREETS AND 7" THICK IN ALL OTHER STREETS. SEE NOTE #5 IN SDG-108 FOR CONCRETE CLASS OPTIONS AND CURING REQUIREMENTS.
4. EXISTING PORTLAND CEMENT CONCRETE PAVEMENT WILL REQUIRE SAWCUTTING.
5. FOR ELECTRICAL SUPPLY CABLES, SEE CALIFORNIA PUBLIC UTILITY COMMISSION GENERAL ORDER NO. 128, RULE 33.4 CLEARANCES AND DEPTHS.

REVISION	BY	APPROVED	DATE
ORIGINAL		BAHMANIAN	04/86
TITLE BLOCK		A. OSKOUI	12/06
UPDATED	KA	J. NAGELVOORT	01/12
UPDATED	KA	J. NAGELVOORT	08/13
UPDATED	KA	J. NAGELVOORT	01/14

CITY OF SAN DIEGO – STANDARD DRAWING

**NARROW TRENCH RESURFACING
FOR PCC SURFACED STREETS**

RECOMMENDED BY THE CITY OF SAN DIEGO
STANDARDS COMMITTEE

CA Branga 1/30/14
COORDINATOR R.C.E. 56523 DATE

DRAWING NUMBER **SDG-118**