



THE CITY OF SAN DIEGO

MEMORANDUM

DATE: July 15, 2015

TO: Helene Deisher, Development Project Manager II, Development Services Department

FROM: Stephanie Bracci, Senior Planner, Transportation & Storm Water Department

SUBJECT: Substantial Conformance Review for Individual Maintenance Plan (IMP) and Individual Technical Assessments for Tijuana River Pilot Channel and Smuggler's Gulch, City of San Diego Site Development Permit No. 1134892, Master Storm Water System Maintenance Program

Dear Ms. Deisher:

The Transportation & Storm Water Department (T&SWD) formally requests your Department's expedited review and written approval to conduct channel maintenance activities in the Tijuana River Pilot Channel and Smuggler's Gulch (MMP Maps 138 a-c, & 139). In conformance with the City of San Diego (City) modified Master Storm Water System Maintenance Program's (Master Maintenance Program or MMP) amended Site Development Permit (SDP) No. 1134892 and Program Environmental Impact Report (PEIR) Project No. 42891/SCH No. 2004101032, the attached Individual Maintenance Plan (IMP) package is submitted for Substantial Conformance Review (SCR). The City is currently planning for project implementation in fall 2015.

The channel maintenance plans and methodologies are substantially similar to previously approved plans with minor updates as indicated below. The impacts associated with ongoing channel maintenance activities are fully mitigated through implementation of habitat and water quality mitigation measures either in progress or already complete. The City is currently planning for project implementation in fall 2015.

PROJECT LOCATION

The project is located in the Tijuana River Valley Community Planning Area. The Pilot Channel and Smugglers Gulch Channel are generally bordered by Hollister Street to the east and Monument Road to the south. Maintenance will include use of two existing staging areas, Staging Area B and Staging Area D as identified on the IMP. Staging Area B is just east of the southern end of Smuggler's Gulch Channel. Staging Area D is located to the east end of the project, near the South Bay International Wastewater Treatment Plant. The channel maintenance areas, access routes, and Staging Area B lie within the City of San Diego Multi-Habitat Planning Area (MHPA). Staging Area D is outside and to the east of the MHPA. The channels are located in the Coastal Zone. The project site is located within the U.S. Geological Survey 7.5 minute Imperial Beach quadrangle.

BACKGROUND AND EXISTING PERMITS

A previous Tijuana River Pilot Channel and Smuggler's Gulch Channel maintenance project IMP and Individual Assessment (IA) package received SCR approval in February 2013. Maintenance activities in the Pilot Channel and Smuggler's Gulch Channel were conducted between September 23, 2013 and March 14, 2014. Appropriate environmental permits were also issued by the California Department of Fish and Wildlife (CDFW), Regional Water Quality Control Board (RWQCB), United States Fish and Wildlife Service (USFWS), Army Corps of Engineers (ACOE), and the California Coastal Commission (CCC) in 2012 and 2013 based on the project scope, impacts, and mitigation. Appropriate construction-related Best Management Practices and concurrent wetland compensatory mitigation have been implemented as part of the comprehensive channel maintenance project.

Current planned channel maintenance activities are authorized under the permits and provisions listed in Table 1 below.

Table 1. Summary of Permit Authorization for Maintenance of the Tijuana River Pilot Channel and Smuggler's Gulch

Permit Authorizations	Permit Date	Impact Area
City of San Diego Site Development Permit No. 1134892	2013	4.31 acres
California Coastal Commission Coastal Development Permit No. A-6-NOC-11-086	2012	4.31 acres
RWQCB Amendment to Water Quality Certification (File No. 09C-077)	2013	4.31 acres
CDFG Streambed Alteration Agreement No. 1600-2011-0271-R5	2013	4.31 acres
ACOE Individual Permit (File No. SPL-2009-00719-RRS)	2010	4.31 acres
U.S. Fish and Wildlife Service Biological Opinion (FWS-SDG-08BO600-10F001)	2012	4.31 acres

PROJECT DESCRIPTION

The proposed maintenance of the Tijuana River Pilot and Smuggler's Gulch Channels includes the mechanized removal of sediment, vegetation and trash and debris from the channels. In addition, pre-maintenance work is planned for the eastern portion of the Pilot Channel to pump accumulated stagnant ponded water from winter and spring rains downstream in order to sufficiently dry out the channel and allow for mechanized excavation. The pre-maintenance pumping work is a deviation from the previously approved project. Details regarding biological, noise and water quality aspects related to this project component are detailed in the appropriate IA cover letter contained herein.

The periodic maintenance of both channels is needed to restore the channels' flood conveyance capacity to their original design condition and to protect the Tijuana River National Estuarine Research Reserve from impacts due to downstream transport of accumulated sediment and trash and debris from the project area. The project incorporates removal of approximately 10,000–30,000 cubic yards of material, occupying a total of 4.31 acres.

INDIVIDUAL MAINTENANCE PLAN AND MAINTENANCE METHODOLOGY

Consistent with the PEIR for the MMP, the City submits an IMP and related Individual Technical Assessments for review and approval. The IMP identifies the scope of work, maintenance methodology and procedures, equipment, and duration for maintenance activities planned in the two channels. To provide more proactive guidance for the maintenance activities being conducted, the IMP also includes a comprehensive list of Best Management Practices (BMPs), maintenance protocols and mitigation measures derived from the applicable permits and regulations that are being implemented to avoid, minimize, and/or mitigate potential environmental effects to sensitive resources.

Specifically, the IMP includes the following components:

- Narrative description of the specific aspects of planned maintenance activities, including: impact area (length and width of facility to be maintained), maintenance methods, equipment types, access routes/points, staging and stockpiling areas, pre- and potential during-maintenance pumping activities and maintenance duration/schedule.
- Master list of BMPs, maintenance protocols and mitigation measures applicable to the maintenance activities being performed, derived from the following source documents and permits:
 - City of San Diego Transportation & Storm Water Department Master Storm Water System Maintenance Program (MMP)
 - MMP Programmatic Environmental Impact Report (PEIR)
 - Site Development Permit No. 1134892 for Master Maintenance Program Project No. 320787

- California Coastal Commission Coastal Development Permit (CDP) NO. A-6-NOC-11-086
 - Regional Water Quality Control Board (RWQCB) 401 Water Quality Certification (401) No. 09C-077
 - California Department of Fish and Wildlife (CDFW) 1600 Streambed Alteration Agreement (1600) No. 1600-2011-0271-R5
 - Army Corps of Engineers (ACOE) 404 Individual Permit (File No. SPL-2009-00719-RRS)
 - U.S. Fish and Wildlife Service (USFWS) Tijuana River Valley Biological Opinion (BO) (FWS-SDG-08BO600-10F001)
- Construction plan set for maintenance activities.
 - Individual Technical Assessments conducted to inform the specific maintenance activities and mitigation measures required for the project, including:
 - Individual Hydrology and Hydraulic Assessment (IHHA);
 - Individual Biological Assessment (IBA);
 - Individual Historical Assessment (IHA);
 - Individual Water Quality Assessment (IWQA); and
 - Individual Noise Assessment (INA).

Since channel maintenance work ended in 2014, natural and anthropogenic processes in the upstream watershed have resulted in additional sediment, trash and debris accumulation in the channel maintenance areas. Site conditions have generally returned to the pre-maintenance conditions evaluated as part of the 2013 SCR package. In addition, ponded water from winter and spring rains has again accumulated in the eastern portion of the Pilot Channel. The City has prepared an updated IBA based on current biological conditions in the Tijuana River Pilot and Smuggler's Gulch Channels. Details regarding the water quality and noise aspects related to this project component are detailed in the appropriate IA cover letters.

The planned maintenance activities for 2015 include pumping of accumulated stagnant ponded water in the eastern portion of the Pilot Channel to downstream areas. The pumping activity is needed in order to sufficiently dry out the channel to allow for mechanized excavation prior to the beginning of maintenance activities and as-needed during maintenance. The City has prepared a diversion plan to manage the water pumping activities planned to occur between August 1 and September 15 and as-needed for the duration of the project. The diversion plan includes focused biological surveys and a protected species plan to mitigate potential noise impacts to protected species from the pumping activity. Other maintenance methods remain unchanged from the previous maintenance event and include: mobilization and demobilization of equipment, excavation and clearing of accumulated sediment, trash and debris from the channel areas,

maintenance of culverts in the Smugglers Gulch Channel and maintenance of existing equipment turnaround areas.

The City's technical environmental consultants conducted a review of the previous SCR IHHA, IHA, IWQA, and INA and prepared a new IBA based on current conditions. Since conditions and the project scope are generally the same as those for the 2013-2014 maintenance event, the technical environmental consultants determined that these studies are generally applicable to the work anticipated in fall 2015. Cover letters for the IHHA, IHA, IWQA and INA have been prepared to document any minor changes in conditions or methodology that may impact mitigation measure implementation.

CONCLUSION

The PEIR for the MMP outlines a SCR process where annual plans for priority channels requiring maintenance activities are reviewed by the City's Development Services Department (DSD) and the state and federal resource agencies for consistency with the MMP permits and PEIR. The IMP and attachments have been reviewed internally and evaluated against the SCR checklist (Attachment 3) contained in the MMP. The SCR Checklist concludes that the proposed maintenance is consistent with the requirements of the MMP and PEIR.

Should you have any questions or need additional information, please contact Stephanie Bracci, Senior Planner, by e-mail at sbracci@sanidiego.gov or phone at (619) 527-3445.

Sincerely,



Stephanie Bracci
Senior Planner

Attachments:

1. Individual Maintenance Plan (IMP) for Tijuana River Pilot and Smuggler's Gulch Channels
 - a. Construction Plans
 - b. Master List of Best Management Practices (BMPs), Maintenance Protocols and Mitigation Measures
 - c. Water Pollution Control Plan (WPCP)
 - d. Maintenance Methodology
2. Regulatory Permits
3. Substantial Conformance Review Checklist

Page 6
Ms. Deisher
July 15, 2015

Appendices:

- A. Individual Hydrology and Hydraulic Assessment (IHHA)
- B. Individual Biological Assessment (IBA)
- C. Individual Historical Assessment (IHA)
- D. Individual Water Quality Assessment (IWQA)
- E. Individual Noise Assessment (INA)

cc: Lisa Honma, California Regional Water Quality Control Board
Kelly Fisher, California Department of Fish and Game
Patrick Gower, US Fish and Wildlife Service
Alex Llerandi, California Coastal Commission
Robert Smith, US Army Corps of Engineers