

LAND DEVELOPMENT MANUAL
APPENDIX P

GENERAL GRADING GUIDELINES FOR
PALEONTOLOGICAL RESOURCES

Paleontological resources (i.e., fossils) are the buried remains and/or traces of prehistoric organisms (i.e., animals, plants, and microbes). Body fossils such as bones or teeth, shells, leaves, and wood, as well as trace fossils such as tracks, trails, burrows, and footprints, are found in the geologic deposits (formations) within which they were originally buried. Fossil remains are considered important if they are: 1) well preserved; 2) taxonomically identifiable; 3) type/topotypic specimens; 4) age diagnostic; 5) useful in environmental reconstruction; or 6) represent new, rare, and/or endemic taxa.

Fossils are typically found buried in geologic deposits of sedimentary rock layers. They are exposed by natural weathering as well as by manmade earthmoving operations. Paleontological resources may be encountered during grading/excavation activities associated with project construction (e.g., residential subdivision projects, new roadway projects, urban redevelopment projects, or utility installation/improvement projects) where such work would be performed in previously undisturbed geologic deposits/formations/rock units (i.e., not in artificial fill materials).

The mapping of geologic deposits/formations/rock units can be located in the published geologic maps by Kennedy and Tan, 2008 all areas of the City of San Diego except Otay Mesa; and Todd, 2004 for the Otay Mesa area. The maps use colors to indicate the geographic distribution of individual geologic deposits/formations/rock units, with a map legend for reference of the geologic deposits/formations/rock units that are present in the project area. The geologic maps are available through the California Geological Survey and United State Geological Survey. Online digital versions of 1:100,000 scale maps are available at the following websites: <https://ngmdb.usgs.gov/mapview/>; http://www.conservation.ca.gov/cgs/rghm/rgm/Pages/preliminary_geologic_maps.aspx; and <https://pubs.usgs.gov/of/2004/1361/>.

These General Grading Guidelines for Paleontological Resources do not replace the Significance Determination Thresholds set forth in Land Development Manual Appendix A for Paleontological Resources.

The following is the standard monitoring requirement that shall be placed on grading plans and implemented when required pursuant to LDC section 142.0151:

I. Prior to Permit Issuance

Entitlements Plan Check

Prior to issuance of any construction permits, including but not limited to, the first Grading Permit, Demolition Plans/Permits and Building Plans/Permits or a Notice to Proceed for Subdivisions, but prior to the first preconstruction meeting, whichever is applicable, the City Engineer (CE) and/or Building Inspector (BI) shall verify that the requirements for Paleontological Monitoring have been noted on the appropriate construction documents.

1. The applicant shall submit a letter of verification to Resident Engineer (RE) and/or Building Inspector (BI) identifying the qualified Principal Investigator (PI) for the project and the names of all persons involved in the paleontological monitoring program. A qualified PI is defined as a person with a Ph.D. or M.S. or equivalent in paleontology or closely related field (e.g., sedimentary or stratigraphic geology, evolutionary biology, etc.) with demonstrated knowledge of southern California paleontology and geology, and documented experience in professional paleontological procedures and techniques.

2. II. Prior to Start of Construction

A. Verification of Records Search

1. The PI shall provide verification to RE and/or BI that a site specific records search has been completed. Verification includes, but is not limited to a copy of a confirmation letter from the San Diego Natural History Museum, or another relevant institution that maintains paleontological collections recovered from sites within the City of San Diego.
2. The letter shall introduce any pertinent information concerning expectations and probabilities of discovery during trenching and/or grading activities.

B. PI Shall Attend Preconstruction Meetings

1. Prior to beginning any work that requires monitoring, the Applicant shall arrange a Preconstruction Meeting that shall include the PI, Construction Manager (CM) and/or Grading Contractor, RE, and BI, as appropriate. The qualified paleontologist (PI) shall attend any grading/excavation related Preconstruction Meetings to make comments and/or suggestions concerning the Paleontological Monitoring program with the Construction Manager and/or Grading Contractor.

- a. If the PI is unable to attend the Preconstruction Meeting, the Applicant shall schedule a focused Preconstruction Meeting with the PI, RE, CM or BI, if appropriate, prior to the start of any work that requires monitoring.
2. Identify Areas to be Monitored

Prior to the start of any work that requires monitoring, the PI shall submit a Paleontological Monitoring Exhibit (PME) based on the appropriate construction documents (reduced to 11x17) to RE and/or BI identifying the areas to be monitored including the delineation of grading/excavation limits. The PME shall be based on the results of a site specific records search as well as information regarding existing known geologic conditions (e.g., geologic deposits as listed in the Paleontological Monitoring Determination Matrix below).
3. When Monitoring Will Occur
 - a. Prior to the start of any work, the PI shall also submit a construction schedule to the RE and/or BI indicating when and where monitoring will occur.
 - b. The PI may submit a detailed letter to RE and/or BI prior to the start of work or during construction requesting a modification to the monitoring program. This request shall be based on relevant information such as review of final construction documents and geotechnical reports which indicate conditions such as depth of excavation and/or thickness of artificial fill overlying bedrock, presence or absence of fossils , etc., which may reduce or increase the potential for resources to be present.

III. During Construction

- A. Monitor Shall be Present During Grading/Excavation/Trenching
 1. The paleontological monitor shall be present full-time during grading/excavation/trenching activities as identified on the PME that could result in impacts to formations with high and moderate resource sensitivity. **The Construction Manager is responsible for notifying the PI, RE and/or BI of changes to any construction activities such as in the case of a potential safety concern within the area being monitored. In certain circumstances OSHA safety requirements may necessitate modification of the PME.**
 2. The PI may submit a detailed letter to RE and/or BI during construction requesting a modification to the monitoring program when a field condition such as trenching activities that do not encounter previously undisturbed and paleontologically sensitive geologic deposits as previously assumed, and/or when unique/unusual fossils are encountered, which may reduce or increase the potential for paleontological resources to be present.

3. The paleontological monitor shall document field activity via the Consultant Site Visit Record (CSV). The CSV's shall be emailed by the CM to the RE and/or BI the first day of monitoring, the last day of monitoring, monthly (**Notification of Monitoring Completion**), and in the case of ANY discoveries.

B. Discovery Notification Process

1. In the event of a discovery, the paleontological monitor shall direct the contractor to temporarily divert trenching activities in the area of discovery and notify the RE and/or BI. The contractor shall also process a construction change for administrative purposes to formalize the documentation and recovery program, including modification to Mitigation Monitoring and Compliance (MMC).
2. The paleontological monitor shall notify the PI (unless paleontological monitor is the PI) of the discovery.
3. The PI shall notify MMC of the discovery, and shall submit documentation to MMC within 24 hours by email with photos of the resource in context.

C. Recovery of Fossils

If a paleontological resource is encountered:

1. The paleontological monitor shall salvage unearthed fossil remains, including simple excavation of exposed specimens or, if necessary as determined by the PI, plaster-jacketing of large and/or fragile specimens or more elaborate quarry excavations of richly fossiliferous deposits.
2. The paleontological monitor shall record stratigraphic and geologic data to provide a context for the recovered fossil remains, including a detailed description of all paleontological localities within the project site, as well as the lithology of fossil-bearing strata within the measured stratigraphic section, and photographic documentation of the geologic setting.

V. Post Construction

A. Preparation and Submittal of Draft Paleontological Monitoring Report

1. The PI shall submit two copies of the Draft Paleontological Monitoring Report (even if negative), prepared to the satisfaction of the Development Services Department. The Draft Paleontological Monitoring Report shall describe the methods, results, and conclusions of all phases of the Paleontological Monitoring Program (with appropriate graphics) to MMC for review and approval within 90 days following the completion of monitoring,

- a. For significant or potentially significant paleontological resources encountered during monitoring, as identified by the PI, the Paleontological Recovery Program shall be included in the Draft Monitoring Report.
 - b. The PI shall be responsible for recording (on the appropriate forms) any significant or potentially significant fossil resources encountered during the Paleontological Monitoring Program in accordance with the City's Paleontological Guidelines (revised November 2017), and submittal of such forms to the San Diego Natural History Museum and MMC with the Draft Paleontological Monitoring Report.
 2. MMC shall return the Draft Paleontological Monitoring Report to the PI for revision or, for preparation of the Final Report.
 3. The PI shall submit revised Draft Paleontological Monitoring Report to MMC for approval.
 4. MMC shall provide written verification to the PI of the approved Draft Paleontological Monitoring Report.
 5. MMC shall notify the RE and/or BI, of receipt of all Draft Paleontological Monitoring Report submittals and approvals.
- B. Handling of Recovered Fossils
1. The PI shall ensure that all fossils collected are cleaned to the point of curation (e.g., removal of extraneous sediment, repair of broken specimens, and consolidation of fragile/brittle specimens) and catalogued as part of the Paleontological Monitoring Program.
 2. The PI shall ensure that all fossils are analyzed to identify stratigraphic provenance, geochronology, and taphonomic context of the source geologic deposit; that faunal material is taxonomically identified; and that curation has been completed, as appropriate.
- C. Curation of Fossil Remains: Deed of Gift and Acceptance Verification
1. The PI shall be responsible for ensuring that all fossils associated with the paleontological monitoring program for this project are permanently curated with an accredited institution that maintains paleontological collections (such as the San Diego Natural History Museum).
 2. The PI shall include an acceptance verification from the curation institution in the Final Paleontological Monitoring Report submitted to the RE and/or BI, and MMC.

D. Final Paleontological Monitoring Report(s)

1. The PI shall submit two copies of the Final Paleontological Monitoring Report to MMC (even if negative), within 90 days after notification from MMC that the Final Paleontological Monitoring Report has been approved.
2. The RE and/or BI shall, in no case, issue the Notice of Completion until receiving a copy of the approved Final Paleontological Monitoring Report from MMC, which includes the Acceptance Verification from the curation institution.

Paleontological Monitoring Determination Matrix

Geological Deposit/Formation/Rock Unit	Potential Fossil Localities	Sensitivity Rating
Alluvium (Qsw, Qal, or Qls)	All communities where this unit occurs	Low
Ardath Shale (Ta)	All communities where this unit occurs	High
Bay Point/Marine Terrace (Qbp) ¹	All communities where unit occurs	High
Cabrillo Formation (Kcs)	All communities where unit occurs	Moderate
Delmar Formation (Td)	All communities where unit occurs	High
Friars Formation (Tf)	All communities where unit occurs	High
Granite/Plutonic (Kg)	All communities where unit occurs	Zero
Lindavista Formation (Qln, Qlb) ²	A. Mira Mesa/Tierrasanta B. All other areas	A. High B. Moderate
Lusardi Formation (Kl)	Black Mountain Ranch/Lusardi Canyon Poway/Rancho Santa Fe B. All other areas	A. High B. Moderate
Mission Valley Formation (Tmv)	All communities where unit occurs	High
Mt. Soledad Formation (Tm, Tmss, Tmsc)	A. Rose Canyon B. All other areas where this unit occurs	A. High B. Moderate
Otay Formation (To)	All communities where unit occurs	High
Point Loma Formation (Kp)	All communities where unit occurs	High
Pomerado Conglomerate (Tp)	A. Scripps Ranch/Tierrasanta B. All other areas	High
River /Stream Terrace Deposits (Qt)	A. South Eastern/Chollas Valley/Fairbanks Ranch/Skyline/Paradise Hills/Otay Mesa, Nestor/San Ysidro B. All other areas	A. Moderate B. Low
San Diego Formation (Qsd)	All communities where this unit occurs.	High
Santiago Peak Volcanics (Jsp) A. Metasedimentary B. Metavolcanic	A. Black Mountain Ranch/La Jolla Valley, Fairbanks Ranch/Mira Mesa/Peñasquitos B. All other areas	A. Moderate B. Zero
Scripps Formation (Tsd)	All communities where this unit occurs	High
Stadium Conglomerate (Tst)	All communities where this unit occurs	High
Sweetwater Formation	All communities where this unit occurs	High
Torrey Sandstone (Tf)	A. Black Mountain Ranch/Carmel Valley B. All other areas	A. High B. Low